

Authorized GOGGLES	Unit of Issue	Manufacturer's Part Number	NSN
Smith Optics Outside the Wire Goggle Kit, Foliage Green	1 each	OTW01FG-FSB	4240-01-583-4955
Smith Optics Outside the Wire Goggle Kit, Black	1 each	OTW01BK-FSB	4240-01-583-4907
Smith Optics Outside the Wire Goggle Kit, Desert Tan	1 each	OTW01TN-FSB	4240-01-583-4954
Replacement Frame, Foliage Green, Smith Optics Outside the Wire	1 each	OTWFRM-FG	4240-01-587-9282
Replacement Frame, Black, Smith Optics Outside the Wire	1 each	OTWFRM-BK	4240-01-587-9280
Replacement Lens, Clear, Smith Optics Outside the Wire	1 each	OTW01C	4240-01-583-5160
Replacement Lens, Gray, Smith Optics Outside the Wire	1 each	OTW01Y	4240-01-583-5163
Replacement Lenses, Clear, Smith Optics Outside the Wire	Package of 50	OTW01C-50	4240-01-583-5162
Replacement Lenses, Gray, Smith Optics Outside the Wire	Package of 50	OTW01Y-50	4240-01-583-5167
Replacement Case, Smith Optics Outside the Wire	1 each	OTWGLBAG-BK	4240-01-583-5225
Retention Strap, Foliage Green, Smith Optics Outside the Wire	1 each	OTWSTRAP-FG	4240-01-583-5185
Retention Strap, Black, Smith Optics Outside the Wire	1 each	OTWSTRAP-BK	4240-01-583-5168
Retention Strap, Desert Tan, Smith Optics Outside the Wire	1 each	OTWSTRAP-TN	4240-01-583-5181
Replacement Sleeve, Foliage Green, Smith Optics Outside the Wire	1 each	EGARSLV-FG	4240-01-583-5198
Replacement Sleeve, Black, Smith Optics Outside the Wire	1 each	EGARSLV-BK	4240-01-583-5187
Replacement Sleeve, Desert Tan, Smith Optics Outside the Wire	1 each	EGARSLV-TN	4240-01-583-5194
Anti-Fog Cloth, Smith Optics Outside the Wire	Package of 20	FOG98	4240-01-583-5248
Cleaning Cloth, Smith Optics Outside the Wire	Package of 36	SMBST36PK-EL	4240-01-583-5267
Prescription Lens Carrier with goggle connector (fits the Smith Optics Aegis Spectacle and the Smith Optics Outside the Wire Goggle, when used with goggle connector)	1 each	ELRXKIT	6540-01-584-3885
Prescription Lens Carriers with goggle connector (fits the Smith Optics Aegis spectacle and the Smith Optics Outside the Wire Goggle, when used with goggle connector)	Package of 25	ELRXKIT-25	6540-01-584-3916



The Smith Optics Outside the Wire goggle consists of an injection molded rubber frame (one size) with interchangeable polycarbonate lenses. The frame is lined with a foam for improved comfort where it contacts the face. Foam covered venting around the periphery provides ventilation while keeping sand/dust out. All lenses have been treated with a hard-coat on the exterior surface to reduce scratching and an anti-fog coating on the interior surface to reduce fogging. The anti-reflective sleeve reduces glint when the goggle is not in use. The goggle weighs 4.9 ounces, provides ballistic-fragmentation protection, and meets ANSI Z87.1-2003 optical and safety requirements. The lens material blocks 99.9% of all UVA and UVB light. An optional prescription lens carrier is available for those who require corrective lenses.

WARNING: Use of prescription lens configurations not listed on the Authorized Protective Eyewear List (APEL) for a specific APEL spectacle or goggle may result in serious injury. We strongly recommend that Soldiers use Army optometry clinics to obtain prescription (Rx) correction for APEL products approved for this purpose. Rx correction is available through garrison and deployed optometry clinics at no cost to the Soldier. All APEL approved Rx configurations have been subjected to ballistic fragmentation testing for safety. Offers by vendors for unapproved Rx products via vendor website and/or through conferences should be avoided, as these items may not be safe or operationally suitable for use in a field environment.