Authorized GOGGLES	Unit of Issue	Manufacturer's Part Number	NSN
Wiley-X SPEAR Goggle Kit, Black Frame (OS7V7)	1 each	SP29B	4240-01-600-1785
Wiley-X SPEAR Goggle Kit, Foliage Green Frame (OS7V7)	1 each	SP29G	4240-01-600-1791
Replacement parts (for all colors):			
Wiley-X SPEAR Goggle replacement clear lens (Ea)	1 each	SP29C	4240-01-600-1736
Wiley-X SPEAR Goggle replacement smoke lens (Ea)	1 each	SP29S	4240-01-600-1737
Wiley-X SPEAR Goggle replacement clear lens (Pg/10)	Package of 10	SP29C10	4240-01-600-1733
Wiley-X SPEAR Goggle replacement smoke lens (Pg/10)	Package of 10	SP29S10	4240-01-600-1734
Wiley-X SPEAR goggle replacement facial cavity seal (Ea)	1 each	SP29FCS	4240-01-600-1741
Wiley-X SPEAR goggle replacement facial cavity seal (Pg/10)	Package of 10	SP29FCS10	4240-01-600-1739
Replacement parts (Foliage Green):			
Wiley-X SPEAR Goggle Frame, Foliage Green	1 each	SP29GF	4240-01-600-1761
Wiley-X SPEAR goggle replacement elastic strap. Color FOLIAGE GREEN	1 each	SP29EG	4240-01-600-1775
Replacement parts (Black):			
Wiley-X SPEAR Goggle Frame, Black	1 each	SP29BF	4240-01-600-1751
Wiley-X SPEAR goggle replacement elastic strap. Color BLACK	1 each	SP29EB	4240-01-600-1771
Additional Components:			
Prescription Lens Carrier, compatible with Wiley X Talon spectacle and Spear Goggle	1 each	СНХ	6540-01-584-0073
Prescription Lens Carrier, compatible with Wiley X Talon spectacle and Spear Goggle	Package of 25	CHX25	6540-01-585-7160



The Wiley-X Spear protective goggle consists of an injection molded rubber frame (one size) with Interchangeable polycarbonate lenses. The frame comes with a removable foam gasket which allows the user to choose between a foam or rubber face seal. Foam covered venting around the periphery provides ventilation while keeping sand/dust out. All lenses have been treated with a hard-coat on the exterior surface to reduce scratching and an anti-fog coating on the interior surface to reduce fogging. The anti-reflective sleeve reduces glint when the goggle is not in use. The Wiley-X Spear Goggle weighs 4.8 ounces. The Wiley-X Spear provides ballistic-fragmentation protection, and meets ANSI Z87.1-2003 optical and safety requirements. The lens material blocks 99.9% of all UVA and UVB light. An optional prescription lens carrier is available for those who require corrective lenses.

WARNING: Use of prescription lens configurations not listed on the Authorized Protective Eyewear List (APEL) for a specific APEL spectacle or goggle may result in serious injury. We strongly recommend that Soldiers use Army optometry clinics to obtain prescription (Rx) correction for APEL products approved for this purpose. Rx correction is available through garrison and deployed optometry clinics at no cost to the Soldier. All APEL approved Rx configurations have been subjected to ballistic fragmentation testing for safety. Offers by vendors for unapproved Rx products via vendor website and/or through conferences should be avoided, as these items may not be safe or operationally suitable for use in a field environment.