



STATISTICAL BRIEF # 104

January 2011

Medicaid Hospitalizations, 2008

Elizabeth Stranges, MS, Katheryn Ryan, MPH, Anne Elixhauser, PhD

Introduction

In 2008, approximately 19 percent of the U.S. population received medical insurance through Medicaid, a joint federal-state health insurance program for eligible low-income individuals and families. Eligibility requirements vary by state and are based on factors including household income, disability, age, and pregnancy. With changes to eligibility requirements recently enacted through healthcare reform, the Medicaid program will expand to cover more of the nation's uninsured. 3

This Statistical Brief presents descriptive data from the Healthcare Cost and Utilization Project (HCUP) Nationwide Inpatient Sample (NIS) and provides an overview of hospitalizations for patients whose primary payer was Medicaid in 2008.⁴ This Statistical Brief also compares the differences between stays billed to Medicaid and those with an expected primary payer of private insurance or uninsured. All differences between estimates provided in the text are statistically significant at the 0.05 level or better.

Highlights

- Medicaid was the primary payer for 18.4 percent of the 39.9 million community hospital stays in 2008— 7.4 million hospitalizations.
- Hospital stays covered by Medicaid increased by 30 percent from 1997-2008, compared to a 5 percent increase in privately insured stays and a 27 percent increase in uninsured stays.
- All Medicaid hospitalizations cost \$51.1 billion in 2008, accounting for 14.0 percent of the total cost of inpatient care.
- Compared to the cost of privately insured stays (\$8,400), Medicaid stays cost less (\$6,900). There was no difference in costs for Medicaid compared to the uninsured.
- Between 2000 and 2008, the average inflation-adjusted cost of a Medicaid hospital stay increased by 11 percent compared to 34 percent for privately insured stays and 26 percent for the uninsured.
- About half of all stays covered by Medicaid were for pregnancy, childbirth, and newborn infants.
- Two mental health conditions ranked among the top ten most frequent reasons for Medicaid hospitalizations—mood disorders (210,000 stays) and schizophrenia and other psychotic disorders (112,000 stays).
- About 42 percent of Medicaidcovered patients were from the poorest communities compared with only 19 percent of privately insured stays.

¹ The Kaiser Family Foundation. Statehealthfacts.org retrieved from: http://www.statehealthfacts.org/ (accessed January 4, 2011).

² Center for Medicare and Medicaid Services. Medicaid Program-General Information retrieved from: http://www.cms.gov/MedicaidGenInfo (accessed January 4, 2011)

³ Kaiser Commission on Medicaid and the Uninsured. Medicaid Coverage and Spending under Health Reform: National and State-by-State Results for Adults at or Below 133% FPL.

Retrieved from: http://www.kff.org/healthreform/upload/Medicaid-Coverage-and-Spending-in-Health-Reform-National-and-State-By-State-Results-for-Adults-at-or-Below-133-FPL-Executive-Summary.pdf (accessed January 4, 2011)

⁴ Patients covered by both Medicare and Medicaid will tend to have the primary payer listed as "Medicare" and thus are less likely to be included in this report.

Findings

In 2008, Medicaid was the primary expected payer for 7.4 million hospitalizations, accounting for 18.4 percent of all U.S. community hospital stays (table 1).

Table 1. Characteristics of hospital inpatients covered by Medicaid, private Insurance, and the uninsured, 2008

	Medicaid	Private insurance	Uninsured
Number of discharges (millions)	7.4	14.1	2.1
(share of all discharges)	(18.4%)	(35.4%)	(5.3%)
Age, mean (in years)	24.6 ^{a,b}	37.1 ^a	36.2 ^b
Percentage distribution by:			
Age groups		_	
<1	27.5 ^{a,b}	16.8 ^a	12.1 ^b
1–17	9.8 ^{a,b}	5.2 ^a	2.8 ^b
18–44	41.4 ^{a,b}	34.6 ^a	47.1 ^b
45–64	18.6 ^{a,b}	34.6 ^a	34.1 ^b
65+	2.7 ^{a,b}	8.8 ^a	3.9 ^b
Gender			
Male	35.4 ^{a,b}	40.0 ^a	51.9 ^b
Female	64.6 ^{a,b}	60.0 ^a	48.1 ^b
Median income of patient's ZIP Code			
Low income (under \$39,000)	42.1 ^{a,b}	19.3 ^a	36.2 ^b
Not low income (\$39,000 and above)	57.9 ^{a,b}	80.7 ^a	63.8 ^b
Patient residence			
Large central metro area	37.1 ^b	32.0 ^a	34.0
Large fringe metro area (suburban)	16.6 ^{a,b}	27.2 ^a	21.9 ^b
Medium and small metro area	27.5	25.3	26.1
Non-metropolitan area (rural)	18.7 ^b	15.4 ^a	18.0

^a Medicaid stays are significantly different from privately insured stays at p< 0.05.


Source: AHRQ, Center for Delivery, Organization, and Markets, Healthcare Cost and Utilization Project, Nationwide Inpatient Sample, 2008

Almost twice as many (14.1 million) hospital stays were paid by private insurance. The uninsured accounted for 2.1 million discharges or about 5 percent of all discharges in 2008. During the 11-year period between 1997 and 2008, the number of hospitalizations covered by Medicaid increased by 30 percent (from 5,644,000 in 1997 to 7,355,000 in 2008), the number covered by private insurance increased by 5 percent (from 13,388,000 in 1997 to 14,108,000 in 2008), and the number of uninsured stays increased by 27 percent (from 1,676,000 in 1997 to 2,126,000 in 2008) (figure 1). Overall, the U.S. population increased 12 percent during this same time period⁵ and Medicaid enrollment increased 40 percent. §

^b Medicaid stays are significantly different from uninsured stays at p< 0.05.

⁵ Calculated using population from the U.S. Bureau of the Census. Retrieved from: http://www.census.gov/popest/national/asrh/2008-nat-res.html (January 4, 2011)

⁶ Ellis ER, Roberts D, Rousseau DM, Schwartz T. Medicaid Enrollment in 50 States: June 2008 Data Update. The Kaiser Commission on Medicaid and the Uninsured. September 2009. http://www.kff.org/medicaid/upload/7606-04.pdf



Characteristics of hospitalized Medicaid patients compared to privately insured and uninsured patients, 2008 As shown in table 1, the average Medicaid hospital patient in 2008 was younger than privately insured and uninsured patients (24.6 years versus 37.1 years and 36.2 years). Over a quarter of all Medicaid hospitalizations were for newborns (27.5 percent) and almost 10 percent were for children ages 1–17. Thus, 37.3 percent of all Medicaid hospital stays were for patients under 18 years. In contrast, patients under 18 accounted for 22.0 percent of privately insured hospital stays and 14.9 percent of uninsured patients.

Adults 18–44 years old accounted for the greatest share of Medicaid hospitalizations (41.4 percent) while 45–64 year olds accounted for only 18.6 percent of Medicaid stays. Among the privately insured, 34.6 percent of patients were 18–44 years old and 34.6 percent were 45–64 years old. Among the uninsured, 18–44 year olds made up the largest share of patients (47.1 percent).

Hospital stays covered by Medicaid were more typically for females (64.6 percent) than males, as were privately insured stays (60.0 percent female). In contrast, stays for the uninsured were divided more equally between males (51.9 percent) and females (48.1 percent).

Patients from the poorest communities accounted for 42.1 percent of Medicaid stays and 36.2 percent of uninsured stays, but just 19.3 percent of privately insured stays.

Hospitalized Medicaid patients were less likely to reside in a suburban location (16.6 percent of Medicaid stays) than privately insured or uninsured patients (27.2 percent and 21.9 percent, respectively).

Characteristics of Medicaid hospitalizations compared to privately insured and uninsured, 2008 Altogether, Medicaid hospitalizations cost \$51.1 billion in 2008 (table 2)—14.0 percent of the total cost of hospitalizations in the U.S (\$364.9 billion). The aggregate cost of privately insured hospital stays (\$117.1 billion) was more than twice that of Medicaid stays. In 2008, the total cost for uninsured hospital stays was \$15.5 billion or about 4.2 percent of the total cost of hospitalizations in the U.S.

Table 2. Characteristics of hospital stays covered by Medicaid, private insurance and the uninsured, 2008

	Medicaid	Private insurance	Uninsured
Number of discharges (in millions)	7.4	14.1	2.1
Aggregate costs (in billions)	\$51.1 ^{a,b}	\$117.1 ^a	\$15.5 ^b
Cost per stay, mean	\$6,900 ^a	\$8,400 ^a	\$7,300
Length of stay, mean (in days)	4.3 ^{a,b}	3.8 ^a	3.8 ^b
In-hospital deaths (percentage)	0.9 ^{a,b}	1.1 ^a	1.4 ^b
Percentage distribution by:			
Discharge status			
Routine (percentage)	86.9 ^a	85.1 ^a	87.1
Another short-term hospital (percentage)	1.8	1.8	1.9
Another institution (percentage)	4.1 ^b	4.3	3.4 ^b
Home health care (percentage)	4.9 ^{a,b}	7.2 ^a	2.7 ^b
Against medical advice (percentage)	1.5 ^{a,b}	0.5 ^a	3.4 ^b

^a Medicaid stays are significantly different from privately insured stays at p< 0.05.

Source: AHRQ, Center for Delivery, Organization, and Markets, Healthcare Cost and Utilization Project, Nationwide Inpatient Sample, 2008


Compared to privately insured hospitalizations, Medicaid hospitalizations typically cost less (average cost per stay of \$6,900 versus \$8,400), despite having a slightly longer average length of stay (4.3 days versus 3.8 days). There was no significant difference between the costs for Medicaid hospitalizations and uninsured hospital stays; however, Medicaid stays were longer on average than uninsured stays (4.3 days compared to 3.8 days).

As shown in table 2, discharges against medical advice occurred for 1.5 percent of Medicaid stays, 0.5 percent of privately insured stays, and 3.4 percent of uninsured stays.

Figure 2 shows that between 2000 and 2008, the average inflation-adjusted cost of a Medicaid hospital stay increased by 11 percent—from \$6,200 to \$6,900—less than the increase for privately insured or uninsured

 $^{^{\}rm b}$ Medicaid stays are significantly different from uninsured stays at p< 0.05.

costs. During the same period, the average cost of a privately insured stay increased by 34 percent—from \$6,300 to \$8,400, while hospital costs for the uninsured increased by nearly 26 percent—from \$5,800 to \$7,300.




Most common reasons for Medicaid hospitalizations, 2008

Figure 3 illustrates the most common reasons for hospital stays by body system. Half of all stays with Medicaid as the expected primary payer were for maternal or neonatal conditions. In comparison, these conditions accounted for 33 percent of privately insured hospitalizations and 20 percent of uninsured hospitalizations.

Table 3 shows that five of the top ten most common specific diagnoses for Medicaid hospitalizations were related to pregnancy, childbirth, or newborns. These five principal diagnoses accounted for 34 percent of Medicaid hospitalizations. For privately insured patients, these conditions accounted for 22 percent of all hospitalizations and for the uninsured, they accounted for 15 percent of all stays and many ranked very low. For example, prolonged pregnancy ranked as the 7th most common condition among Medicaid-covered inpatients, but ranked 23rd for the privately insured and 47th among the uninsured.

Two mental health conditions—mood disorders (210,000 Medicaid stays) and schizophrenia and other psychotic disorders (112,000 Medicaid stays)—ranked among the top ten most frequent reasons for Medicaid hospitalizations. While mood disorders was also a common reason for privately insured and uninsured stays (291,000 privately insured stays and 79,000 uninsured stays), schizophrenia was not (51,000 stays, ranked 62nd for privately insured and 20,000 stays, ranked 26th for uninsured). Alcohol and substance use conditions

were common diagnoses for the uninsured (ranked 5th and 8th), but were the 31st and 21st most common reasons for hospital stays billed to Medicaid.



Pneumonia was the 5th most common reason for a Medicaid-covered stay and was also a top ten condition among the privately insured (ranked 9th) and the uninsured (ranked 7th). Asthma was a top ten condition for Medicaid-covered stays (ranked 8th) but stays for this condition were less common for the privately insured (ranked 24th) and the uninsured (ranked 14th).

Skin and subcutaneous tissue infection was a top ten diagnosis for Medicaid (106,000 discharges, ranked 10th) and uninsured stays (67,000 stays, ranked 4th); it ranked 12th among privately insured stays (195,000 stays).

Most common procedures performed during Medicaid hospitalizations, 2008 In 2008, seven of the ten most common procedures performed during Medicaid hospitalizations were related to pregnancy, childbirth, or newborns (table 4: C-section, repair of current obstetric laceration, circumcision, artificial rupture of membranes to assist delivery, fetal monitoring, treatment and ligation of fallopian tubes, and episiotomy). The first five of these were also among the ten most common procedures performed during privately insured hospitalizations. Three of the seven—C-section, repair of current obstetric laceration, and circumcision—were also among the top ten procedures for the uninsured.

Blood transfusions, respiratory intubation, and upper gastrointestinal (UGI) endoscopy were also among the top ten most frequently performed procedures for Medicaid, privately insured, and uninsured hospital stays.

Table 3. Number of discharges, percentage distribution, and rank of the top ten most frequent principal diagnoses for inpatient hospital stays covered by Medicaid, private insurance, and the uninsured, 2008

	NUMBER OF DISCHARGES IN THOUSANDS Percentage of discharges by payer			RANK			
PRINCIPAL CCS DIAGNOSIS	Medicaid	Private insurance	Uninsured	Medicaid	Private insurance	Uninsured	
All discharges	7,355	14,108	2,126				
	100%	100%	100%				
Liveborn	1,722	2,169	240	1	1	1	
	23%	15%	11%	·	•		
Trauma to perineum and	2070	7370	7.770				
vulva	288	476	28	2	2	17	
	4%	3%	1%				
Previous C-section	214	282	19	3	7	28	
	3%	2%	1%				
Mood disorders	210	291	79	4	6	2	
	3%	2%	4%				
Pneumonia	157	257	47	5	9	7	
	2%	2%	2%				
Normal pregnancy and/or	138	119	13	6	27	42	
delivery	2%	1%	1%				
Prolonged pregnancy	116	127	11	7	23	47	
	2%	1%	1%				
Asthma	115	126	32	8	24	14	
	2%	1%	1%				
Schizophrenia and other	112	51	20	9	62	26	
psychotic disorders	2%	0%	1%				
Skin and subcutaneous	106	195	67	10	12	4	
tissue infections	1%	1%	3%				
Osteoarthritis	23	358	6	53	3	77	
	0%	3%	0%				
Spondylosis, intervertebral	36	305	15	40	4	35	
disc disorders, other back problems	0%	2%	1%				
Coronary atherosclerosis	58	302	36	27	5	12	
-	1%	2%	2%				
Nonspecific chest pain	86	257	68	16	8	3	
	1%	2%	3%			:	
Cardiac dysrhythmias	34	208	23	43	10	22	
	0%	1%	1%				
Alcohol-related disorders	54	86	61	31	41	5	
	1%	1%	3%				
Diabetes mellitus with	95	132	52	12	20	6	
complications	1%	1%	2%	_			
Substance-related disorders	70	60	43	21	55	8	
	10						

Table 3. Number of discharges, percentage distribution, and rank of the top ten most frequent principal diagnoses for inpatient hospital stays covered by Medicaid, private insurance, and the uninsured, 2008—continued

	NUMBER OF DISCHARGES IN THOUSANDS Percentage of discharges by payer				RANK	
PRINCIPAL CCS DIAGNOSIS	Medicaid	Private insurance	Uninsured	Medicaid	Private insurance	Uninsured
Biliary tract disease	57	195	42	28	13	9
	1%	1%	2%			
Acute myocardial infarction	35	187	40	41	16	10
	0%	1%	2%			

Source: AHRQ, Center for Delivery, Organization, and Markets, Healthcare Cost and Utilization Project, Nationwide Inpatient Sample, 2008

Table 4. Number of discharges, percent distribution, and rank of the top ten most frequent all-listed procedures for inpatient hospital stays covered by Medicaid, private insurance, and the uninsured, 2008

	NUMBER OF DISCHARGES IN THOUSANDS Percentage of discharges by payer			RANK			
PRINCIPAL CCS PROCEDURES	Medicaid	Private insurance	Uninsured	Medicaid	Private insurance	Uninsured	
All discharges	7,355	14,108	2,126				
	100%	100%	100%				
Cesarean section	527	762	42	1	2	8	
	7%	5%	2%				
Repair of current obstetric	770	070	270				
laceration	481	794	48	2	1	7	
	7%	6%	2%				
Circumcision	400	738	49	3	3	6	
	5%	5%	2%				
Artificial rupture of membranes	386	543	33	4	5	13	
to assist delivery	5%	4%	2%				
Fetal monitoring	385	506	32	5	7	15	
	5%	4%	1%				
Blood transfusion	286	666	97	6	4	1	
	4%	5%	5%				
Respiratory intubation and	241	366	75	7	8	4	
mechanical ventilation	3%	3%	4%				
Ligation of fallopian tubes	147	140	*	8	27	38	
	2%	1%	*				
Upper gastrointestinal	126	336	68	9	10	5	
endoscopy, biopsy	2%	2%	3%				
Episiotomy	120	207	12	10	18	35	
	2%	1%	1%				
Diagnostic cardiac catheterization, coronary	106	518	85	13	6	2	
arteriography	1%	4%	4%				
Hysterectomy, abdominal and							
vaginal	46	365	17	26	9	23	
	1%	3%	1%				
Alcohol and drug	97	121	76	14	32	3	
rehabilitation/detoxification	1%	1%	4%				
Appendectomy	54	227	40	21	16	9	
	1%	2%	2%				
Percutaneous coronary	42	274	40	31	11	10	
angioplasty (PTCA)	1%	2%	2%				

Source: AHRQ, Center for Delivery, Organization, and Markets, Healthcare Cost and Utilization Project, Nationwide Inpatient Sample, 2008

Data Source

The estimates in this Statistical Brief are based upon data from the HCUP Nationwide Inpatient Sample, 1997–2008.

Definitions

Payer

Payer is the expected primary payer for the hospital stay. To make coding uniform across all HCUP data sources, payer combines detailed categories into more general groups:

- Medicare includes fee-for-service and managed care Medicare patients.
- Medicaid includes fee-for-service and managed care Medicaid patients. Patients covered by the State Children's Health Insurance Program (SCHIP) may be included here. Because most state data do not identify SCHIP patients specifically, it is not possible to present this information separately.
- Private insurance includes Blue Cross, commercial carriers, and private HMOs and PPOs.
- Other includes Worker's Compensation, TRICARE/CHAMPUS, CHAMPVA, Title V, and other government programs.
- Uninsured includes an insurance status of "self-pay" and "no charge."

When more than one payer is listed for a hospital discharge, the first-listed payer is used. Patients covered by both Medicare and Medicaid will tend to have the primary payer listed as "Medicare" and thus are less likely to be included in this report.

Diagnoses, Procedures, ICD-9-CM, and Clinical Classifications Software (CCS)

The principal diagnosis is that condition established after study to be chiefly responsible for the patient's admission to the hospital. Secondary diagnoses are concomitant conditions that coexist at the time of admission or that develop during the stay. The principal procedure is the procedure that was performed for definitive treatment rather than one performed for diagnostic or exploratory purposes (i.e., the procedure that was necessary to take care of a complication). If two procedures appear to meet this definition, the procedure most related to the principal diagnosis was selected as the principal procedure. All-listed procedures include all procedures performed during the hospital stay.

ICD-9-CM is the International Classification of Diseases, Ninth Revision, Clinical Modification, which assigns numeric codes to diagnoses. There are about 12,000 ICD-9-CM diagnosis codes.

Clinical Classification Software (CCS) is a tool that categorizes ICD-9-CM diagnoses and procedures into clinically meaningful categories.⁵ This "clinical grouper" makes it easier to quickly understand patterns of diagnoses and procedures.

Major Diagnosis Categories (MDCs) are broad groups of DRGs (Diagnosis Related Groups) that relate to an organ or a system (digestive system, for example) and not to an etiology. For example, MDC 01 - Diseases and Disorders of the Nervous System, MDC 02 - Diseases and Disorders of the Eye, MDC 03 - Diseases and Disorders of the Ear, Nose, Mouth and Throat. Each hospital stay has one DRG and one MDC assigned to it.

Types of hospitals included in HCUP

HCUP is based on data from community hospitals, defined as short-term, non-Federal, general and other hospitals, excluding hospital units of other institutions (e.g., prisons). HCUP data include OB-GYN, ENT, orthopedic, cancer, pediatric, public, and academic medical hospitals. They exclude long-term care, rehabilitation, psychiatric, and alcoholism and chemical dependency hospitals, but these types of discharges are included if they are from community hospitals.

⁵ HCUP CCS. Healthcare Cost and Utilization Project (HCUP). May 2008. U.S. Agency for Healthcare Research and Quality, Rockville, MD. www.hcup-us.ahrq.gov/toolssoftware/ccs/ccs.jsp

Unit of analysis

The unit of analysis is the hospital discharge (i.e., the hospital stay), not a person or patient. This means that a person who is admitted to the hospital multiple times in one year will be counted each time as a separate "discharge" from the hospital.

Costs and charges

Total hospital charges were converted to costs using HCUP Cost-to-Charge Ratios based on hospital accounting reports from the Centers for Medicare and Medicaid Services (CMS). Costs will tend to reflect the actual costs of production, while charges represent what the hospital billed for the case. For each hospital, a hospital-wide cost-to-charge ratio is used because detailed charges are not available across all HCUP States. Hospital charges reflect the amount the hospital charged for the entire hospital stay and does not include professional (physician) fees. For the purposes of this Statistical Brief, costs are reported to the nearest hundreds.

Median income of the patient's ZIP Code

Median community-level income is the median household income of the patient's ZIP Code of residence. The cut-offs for the quartile designation are determined using ZIP Code demographic data obtained from Claritas. The income quartile value is missing for homeless and foreign patients. In 2008, the lowest income quartile ranged from \$1–\$38,999, while the highest income quartile was defined as \$64,000 or above. Patients in the lowest quartile were classified as living in the poorest communities; all others were classified as living in "relatively wealthier" or "other communities."

Discharge status

Discharge status indicates the disposition of the patient at discharge from the hospital, and includes the following six categories: routine (to home), transfer to another short-term hospital, other transfers (including skilled nursing facility, intermediate care, and another type of facility such as a nursing home), home health care, against medical advice (AMA), or died in the hospital.

Location of patient's residence

Based on an urban-rural designation of the patient's county of residence. The categorization is a simplified adaptation of the 2006 version of a system developed by the National Center for Health Statistics (NCHS) especially for use in health care research:

- "Large central" refers to counties of metro areas of 1 million or more population, and can be considered cores of large cities.
- "Large fringe" refers to counties of metro areas of 1 million or more population and can be considered suburbs of large cities.
- "Medium and small metro" refers to counties in metro areas with less than 1 million population but with at least 50,000.
- "Non-metropolitan" refers to rural counties with less than 50,000 population.

About HCUP

HCUP is a family of powerful health care databases, software tools, and products for advancing research. Sponsored by the Agency for Healthcare Research and Quality (AHRQ), HCUP includes the largest all-payer encounter-level collection of longitudinal health care data (inpatient, ambulatory surgery, and emergency department) in the United States, beginning in 1988. HCUP is a Federal-State-Industry Partnership that brings together the data collection efforts of many organizations—such as State data organizations, hospital associations, private data organizations, and the Federal government—to create a national information resource.

HCUP would not be possible without the contributions of the following data collection Partners from across the United States:

⁶ HCUP Cost-to-Charge Ratio Files (CCR). Healthcare Cost and Utilization Project (HCUP). 2001–2007. U.S. Agency for Healthcare Research and Quality, Rockville, MD. www.hcup-us.ahrq.gov/db/state/costtocharge.jsp.

Arizona Department of Health Services

Arkansas Department of Health

California Office of Statewide Health Planning and Development

Colorado Hospital Association

Connecticut Hospital Association

Florida Agency for Health Care Administration

Georgia Hospital Association

Hawaii Health Information Corporation

Illinois Department of Public Health

Indiana Hospital Association

Iowa Hospital Association

Kansas Hospital Association

Kentucky Cabinet for Health and Family Services

Louisiana Department of Health and Hospitals

Maine Health Data Organization

Maryland Health Services Cost Review Commission

Massachusetts Division of Health Care Finance and Policy

Michigan Health & Hospital Association

Minnesota Hospital Association

Missouri Hospital Industry Data Institute

Montana MHA - An Association of Montana Health Care Providers

Nebraska Hospital Association

Nevada Department of Health and Human Services

New Hampshire Department of Health & Human Services

New Jersey Department of Health and Senior Services

New Mexico Health Policy Commission

New York State Department of Health

North Carolina Department of Health and Human Services

Ohio Hospital Association

Oklahoma State Department of Health

Oregon Association of Hospitals and Health Systems

Pennsylvania Health Care Cost Containment Council

Rhode Island Department of Health

South Carolina State Budget & Control Board

South Dakota Association of Healthcare Organizations

Tennessee Hospital Association

Texas Department of State Health Services

Utah Department of Health

Vermont Association of Hospitals and Health Systems

Virginia Health Information

Washington State Department of Health

West Virginia Health Care Authority

Wisconsin Department of Health Services

Wyoming Hospital Association

About the NIS

The HCUP Nationwide Inpatient Sample (NIS) is a nationwide database of hospital inpatient stays. The NIS is nationally representative of all community hospitals (i.e., short-term, non-Federal, non-rehabilitation hospitals). The NIS is a sample of hospitals and includes all patients from each hospital, regardless of payer. It is drawn from a sampling frame that contains hospitals comprising about 95 percent of all discharges in the United States. The vast size of the NIS allows the study of topics at both the national and regional levels for specific subgroups of patients. In addition, NIS data are standardized across years to facilitate ease of use.

For More Information

For more information about HCUP, visit www.hcup-us.ahrq.gov.

For additional HCUP statistics, visit HCUPnet, our interactive query system, at www.hcup.ahrq.gov.

For information on other hospitalizations in the U.S., download *HCUP Facts and Figures: Statistics on Hospital-based Care in the United States in 2008*, located at http://www.hcup-us.ahrq.gov/reports.jsp.

For a detailed description of HCUP, more information on the design of the NIS, and methods to calculate estimates, please refer to the following publications:

Steiner, C., Elixhauser, A., Schnaier, J. The Healthcare Cost and Utilization Project: An Overview. *Effective Clinical Practice* 5(3):143–51, 2002.

Introduction to the HCUP Nationwide Inpatient Sample, 2008. Online. May 2010. U.S. Agency for Healthcare Research and Quality. http://www.hcup-us.ahrq.gov/db/nation/nis/NIS 2008 INTRODUCTION.pdf.

Houchens, R., Elixhauser, A. *Final Report on Calculating Nationwide Inpatient Sample (NIS) Variances*, 2001. HCUP Methods Series Report #2003-2. Online. June 2005 (revised June 6, 2005). U.S. Agency for Healthcare Research and Quality. http://www.hcup-us.ahrq.gov/reports/CalculatingNISVariances200106092005.pdf

Suggested Citation

Stranges, E. (Thomson Reuters), Ryan, K. (Thomson Reuters), and Elixhauser, A. (AHRQ). *Medicaid Hospitalizations, 2008.* HCUP Statistical Brief #104. January 2011. Agency for Healthcare Research and Quality, Rockville, MD. http://www.hcup-us.ahrq.gov/reports/statbriefs/sb104.pdf

* * *

AHRQ welcomes questions and comments from readers of this publication who are interested in obtaining more information about access, cost, use, financing, and quality of health care in the United States. We also invite you to tell us how you are using this Statistical Brief and other HCUP data and tools, and to share suggestions on how HCUP products might be enhanced to further meet your needs. Please e-mail us at hcup@ahrq.gov or send a letter to the address below:

Irene Fraser, Ph.D., Director Center for Delivery, Organization, and Markets Agency for Healthcare Research and Quality 540 Gaither Road Rockville, MD 20850