



STATISTICAL BRIEF #106

February 2011

Overview of Hospitalizations among Patients with COPD, 2008

Lauren M. Wier, M.P.H., Anne Elixhauser Ph.D., Anne Pfuntner B.U.E.P., David H. Au, M.D., M.S.

Introduction

Chronic obstructive pulmonary disease (COPD) is a heterogeneous group of respiratory conditions made up predominantly of chronic bronchitis and emphysema and is defined by airflow limitation that is not completely reversible. In the United States, current estimates suggest about 12 million people have been diagnosed with COPD, but there are likely many more who unknowingly have the disease. COPD recently became the third leading cause of death in the United States, and about half of those who have COPD die within 10 years of diagnosis. COPD is incurable; however, lifestyle changes, primarily quitting smoking, can moderate the rate of lung loss for many patients with COPD.

COPD typically presents after prolonged exposure to smoking tobacco or other noxious inhaled substances. At the time of diagnosis, many patients have moderate to severe disease. As a result, COPD is primarily diagnosed in middle-aged and older adults.³ Because COPD is predominantly caused by smoking cigarettes, patients with COPD often have many coexisting conditions that are also associated with tobacco use including cardiovascular disease and diabetes. One of the hallmarks of COPD is exacerbation which marks an acute deterioration in symptoms. COPD exacerbations occur up to 2 to 3 times per year. The cause of these exacerbations is often unknown, though frequently patients have viral or bacterial infections.

This Statistical Brief presents data from the Healthcare Cost and Utilization Project (HCUP) comparing patient characteristics and hospital utilization among patients 40 years and older for all COPD stays, including stays for an

Highlights

- In 2008, there were about 822,500 hospital stays for chronic obstructive pulmonary disease (COPD) among adults age 40 years and older. In addition, another 3.8 million hospital stays included COPD as a secondary, or complicating, condition during an admission for some other problem. Thus, nearly 1 out of every 5 patients 40 years or older in U.S. hospitals has a diagnosis of COPD.
- Aggregate costs for hospital stays with COPD as a principal diagnosis were \$6.1 billion with a 4.8 day mean length of hospitalization and an average cost per stay of \$7,500. COPD stays with acute exacerbation accounted for 514,000 (62.5 percent) of all COPD stays and had comparable resource use to other COPD hospitalizations.
- Hospitalization rates for acute exacerbation of COPD were highest among patients 75–84 years (1,075 stays per 100,000 population), but dropped for patients 85 years and older (913 stays per 100,000).
- Hospitalization rates for COPD with acute exacerbation were highest in the Midwest (436 stays per 100,000) and the South (438 stays per 100,000) and lowest in the West (218 stays per 100,000), mirroring regional smoking rates.
- Hospitalization rates were also highest in the poorest communities (533 versus 312 stays per 100,000) and in rural areas (563 stays versus 305 stays per 100,000 in large metropolitan areas), where smoking rates tend to be higher.
- For patients with a secondary diagnosis of acute exacerbation of COPD, pneumonia was the primary reason for hospitalization for 22.3 percent of admissions and respiratory failure was the reason for 21.4 percent of admissions. In addition, over 20 percent of hospital stays with acute exacerbation of COPD as the main reason for admission also had a diagnosis of pneumonia; 20 percent had respiratory failure.

¹ Chabner D-E. The Language of Medicine. 5th Edition. Philadelphia: W.B. Saunders Company, 1996. 409. ² "What is COPD?" National Heart Lung and Blood Institute: Diseases and

² "What is COPD?" National Heart Lung and Blood Institute: Diseases and Conditions Index. June 2010.

http://www.nhlbi.nih.gov/health/dci/Diseases/Copd/Copd_WhatIs.html (accessed February 14, 2011)

3 Porter R.S. (Ed.). "Chronic Obstructive Pulmonary Disease." In The Merck

Orter R.S. (Ed.). "Chronic Obstructive Pulmonary Disease." In The Merck Manual Online. January 2010.

http://www.merckmanuals.com/professional/sec05/ch049/ch049a.html# (accessed February 14, 2011)

acute exacerbation of COPD and stays without an acute exacerbation (i.e., all other COPD stays). In addition, this report examines the secondary diagnoses commonly associated with a principal diagnosis of COPD, the principal diagnoses of patients who have COPD as a secondary diagnosis, and the procedures that are frequently performed during stays for COPD. All differences between estimates noted in the text are statistically significant at the 0.05 level or better.

Findings

In 2008, there were about 822,500 hospital stays for chronic obstructive pulmonary disease (COPD) among adults age 40 years and older. As shown in table 1, COPD stays that explicitly coded an acute exacerbation accounted for 514,000 (62.5 percent) of all COPD stays. The remaining COPD stays discharged with a principal diagnosis of COPD, but without explicitly noting "acute exacerbation," accounted for 308,500 (37.5 percent) of COPD hospitalizations. Thus, nearly 1 out of every 5 patients 40 years or older in U.S. hospitals has a diagnosis of COPD. The mean length of hospitalizations (about 4.7 days) and average cost per stay (\$7,500) were similar for acute exacerbation and other COPD hospitalizations.

Characteristics of COPD hospital stays

While the vast majority of COPD stays were discharged to home, routine discharge was less common among acute exacerbation stays (65.0 percent) than among other COPD stays (71.5 percent). Conversely, the percentage of stays discharged to long term care (e.g., nursing homes and rehab) was greater among stays for acute exacerbation of COPD relative to other COPD (14.6 versus 10.9 percent).

Table 1. Characteristics of hospital stays for patients admitted to U.S. hospitals for COPD, principal diagnosis, 2008

principal diagnosis, 2000	AII COPD	Principal COPD diagnosis of acute exacerbation	Principal COPD diagnosis without acute exacerbation
Number of discharges	822,500	514,000	308,500
Mean length of stay (days)	4.8	4.7	4.8‡
Mean hospital costs	\$7,500	\$7,500	\$7,500‡
Aggregate national costs	\$6.1 billion	\$3.8 billion	\$2.3 billion
Percentage routine discharge to home	67.4	65.0	71.5
Percentage transferred to another facility (skilled nursing facility, intermediate care, and another type of facility such as a nursing home)	13.2	14.6	10.9
Percentage died in hospital	1.6	1.8	1.3
Primary expected payer (percentage)			
Medicare	68.7	71.6	64.0
Medicaid	9.8	8.8	11.5
Privately insured	15.5	14.1	17.8
Uninsured	3.4	3.1	4.1
Mean age (years)	68.7	69.7	67.2


[‡] Non-acute exacerbation COPD discharges are <u>not</u> statistically different from acute exacerbation COPD discharges at p<0.05. Source: AHRQ, Center for Delivery, Organization, and Markets, Healthcare Cost and Utilization Project, Nationwide Inpatient Sample (NIS), 2008

2


⁴ See Definitions for the case definition of COPD and acute exacerbation.

Medicare was the most common expected payer for hospital stays for patients with acute exacerbation and other COPD (71.6; 64.0 percent), followed by private insurance (14.1; 17.8 percent) and Medicaid (8.8; 11.5 percent).

Patients with acute exacerbation were, on average, 2.5 years older than patients with other COPD (69.7 versus 67.2 years older, respectively). As shown in figure 1, hospitalization rates for acute exacerbation increased with age up to 75–84 years (1,075 stays per 100,000 population), but dropped for patients 85 years and older (913 stays per 100,000). The rate of hospitalization was slightly higher among females than males for all COPD stays, for stays with acute exacerbation and without.



As shown in figure 2, hospitalization rates for acute exacerbation were highest in the Midwest and the South. These regions also had the highest smoking prevalence (about 19.5 percent, relative to 14.6 and 17.5 percent in the Northeast and West, respectively). Hospitalization rates for acute exacerbation were highest in the poorest communities and in rural areas. Although the definitions may not be identical, research indicates that smoking rates are higher among individuals with incomes below the poverty level (31.5 percent relative to 19.6 percent among those at or above poverty level) and among adults living in rural areas (22.2 percent versus 17.3 percent in suburban and 18.1 percent in urban areas).



⁵ Regional smoking prevalence rates calculated from the following sources: Centers for Disease Control and Prevention (CDC). State-specific prevalence of cigarette smoking and smokeless tobacco use among adults—United States, 2009. MMWR Morb Mortal Wkly Rep. 2010 Nov 5;59(43):1400-6. http://www.cdc.gov/mmwr/preview/mmwrhtml/mm5943a2.htm?s_cid=mm5943a2_w.
See Table 1. State-specific prevalence of cigarette smoking and smokeless tobacco use among adults—United States, 2009.
U.S. Census Bureau, "Cumulative Estimates of Resident Population Change for the United States, Regions, States and Puerto Rico and Region and State Rankings: April 1, 2000 to July 1, 2009 (NST-EST2009-02)"; published 22 December 2009; http://www.census.gov/popest/states/NST-pop-chg.html. See Table 12, Statistical Abstract of the United States, 2010.

[§] Data on smoking prevalence by income from: Vander Weg M.W., Cunningham C.L., Howren M.B., Cai X. (2011). Tobacco use and exposure in rural areas: Findings from the Behavioral Risk Factor Surveillance System. Addictive Behaviors; 36(3):231-236.

⁷ Data on smoking prevalence by residence from: Centers for Disease Control and Prevention (CDC). State-specific prevalence of cigarette smoking and smokeless tobacco use among adults—United States, 2009. MMWR Morb Mortal Wkly Rep. 2010 Nov 5;59(43):1400-6.

Most common comorbidities associated with COPD

Table 2 shows the ten most common comorbidities for hospitalized patients with COPD in 2008. Comorbidities are complicating conditions that effect the management of the main reason for hospitalization (or the principal diagnosis, in this case, COPD). Hypertension was the most common comorbidity, present among about half of hospital stays for patients with acute and other COPD.

Other common comorbidities included current or past tobacco-related diagnoses (44–48 percent), coronary atherosclerosis (hardening of the arteries; 28–31 percent), and lipid disorders (28 percent). Diabetes without complication and congestive heart failure (CHF) each occurred in about one-quarter of acute exacerbation and other COPD stays.

Patients with acute exacerbation experienced respiratory failure and pneumonia comorbidities more frequently than patients with other COPD. Over 20 percent of COPD patients with acute exacerbation had respiratory failure and/or pneumonia, compared to 13–15 percent for other COPD patients.

Table 2. Most common secondary diagnoses associated with a principal diagnosis of COPD, 2008

	All COPD		Acute exacerbation		Without acute exacerbation	
Secondary diagnoses	Number (%)	Rank	Number (%)	Rank	Number (%)	Rank
Essential hypertension	415,800 (50.6%)	1	257,500 (50.1%)	1	158,300 (51.3%)	1
Current and/or past use/abuse of tobacco	379,700 (46.2%)	2	244,400 (47.5%)	2	135,300 (43.9%)	2
Coronary atherosclerosis and other heart disease	245,600 (29.9%)	3	159,100 (31.0%)	3	86,500 (28.0%)	4
Disorders of lipid metabolism	228,400 (27.8%)	4	141,100 (27.5%)	4	87,300 (28.3%)	3
Diabetes mellitus without complication	207,600 (25.2%)	5	126,800 (24.7%)	6	80,800 (26.2%)	5
Congestive heart failure	196,900 (23.9%)	6	130,000 (25.3%)	5	66,900 (21.7%)	6
Fluid and electrolyte disorders	178,700 (21.7%)	7	113,500 (22.1%)	7	65,300 (21.2%)	8
Cardiac dysrhythmias	170,600 (20.7%)	8	111,100 (21.6%)	8	59,500 (19.3%)	9
Esophageal disorders	166,500 (20.2%)	9	100,000 (19.5%)	11	66,500 (21.6%)	7
Respiratory failure	153,300 (18.6%)	10	105,800 (20.6%)	10	47,500 (15.4%)	11
Pneumonia	147,000 (17.9%)	11	106,000 (20.6%)	9	41,000 (13.3%)	13
Mood disorders (depressive and bipolar disorders)	141,500 (17.2%)	12	87,100 (16.9%)	12	54,400 (17.6%)	10

Note: More than one secondary diagnosis may be recorded during a hospital stay.

Note: The distribution of other COPD discharges is statistically different from the distribution of acute exacerbation discharges at p<0.05.

Source: AHRQ, Center for Delivery, Organization, and Markets, Healthcare Cost and Utilization Project, Nationwide Inpatient Sample (NIS), 2008

Most common reasons for hospitalization of patients with a secondary diagnosis of COPD COPD is listed commonly as a secondary diagnosis during hospitalization, that is, a complicating condition that effects the management of a patient who is admitted for some other reason. COPD was a secondary diagnosis for 3.8 million hospital stays in 2008.

Table 3 shows that pneumonia was the most common principal reason for hospitalization among patients with a secondary diagnosis of acute exacerbation COPD (22.3 percent). Respiratory failure was the principal diagnosis for 21.4 percent of patients with acute exacerbation COPD. Circulatory disorders represented 5 of the top 10 reasons for hospital admissions with a secondary diagnosis of COPD: CHF, coronary atherosclerosis, cardiac dysrhythmias, acute myocardial infarction (heart attack), and nonspecific chest pain.

Nearly two-thirds (63 percent) of stays with a secondary diagnosis of acute exacerbation of COPD had a principal diagnosis of pneumonia, CHF, respiratory failure, or septicemia. These same principal diagnoses accounted for a much smaller share of stays without an acute exacerbation of COPD (21.3 percent).

Table 3. Most common principal diagnoses for patients with COPD as a secondary diagnosis, 2008

·	All COPD*		Acute exacerbation*		Without acute exacerbation*	
Total stays with COPD as secondary diagnosis	3,827,100		619,200		3,207,900	
Principal Diagnosis	Number (%)	Rank	Number (%)	Rank	Number (%)	Rank
Pneumonia	370,800 (9.7%)	1	138,000 (22.3%)	1	232,800 (7.3%)	1
Congestive heart failure	310,200 (8.1%)	2	80,300 (13.0%)	3	229,900 (7.2%)	2
Respiratory failure	245,100 (6.4%)	3	132,600 (21.4%)	2	112,500 (3.5%)	4
Septicemia	145,300 (3.8%)	4	39,200 (6.3%)	4	106,100 (3.3%)	5
Coronary atherosclerosis	128,100 (3.3%)	5	7,300 (1.2%)	10	120,800 (3.8%)	3
Cardiac dysrhythmias	115,100 (3.0%)	6	11,600 (1.9%)	7	103,500 (3.2%)	6
Acute myocardial infarction	107,000 (2.8%)	7	18,600 (3.0%)	5	88,400 (2.8%)	7
Nonspecific chest pain	85,400 (2.2%)	8	4,300 (0.7%)	15	81,100 (2.5%)	8
Cancer of bronchus; lung	72,700 (1.9%)	9	11,400 (1.8%)	8	61,300 (1.9%)‡	10
Complication of device; implant or graft	70,500 (1.8%)	10	3,400 (0.5%)	23	67,100 (2.1%)	9
Aspiration pneumonia; food/emesis	68,600 (1.8%)	18	16,900 (2.7%)	6	39,700 (1.2%)	23
Acute renal failure	61,900 (1.6%)	11	10,100 (1.6%)	9	58,500 (1.8%)	12

^{*}Based on secondary diagnoses.

[‡] The distribution of other COPD discharges is *not* statistically different from the distribution of acute exacerbation discharges at p<0.05.

Source: AHRQ, Center for Delivery, Organization, and Markets, Healthcare Cost and Utilization Project, Nationwide Inpatient Sample (NIS), 2008

Procedures associated with hospitalizations related to COPD

Table 4 shows that invasive intubation/ventilation and noninvasive ventilation were the most frequently performed procedures during stays for acute exacerbation and other COPD. Both types of intubation were used slightly more frequently among patients with acute exacerbation—4.3 percent acute exacerbation patients received invasive ventilation and 3.7 percent received noninvasive ventilation, compared with 3.0 percent for both types of ventilation for patients without acute exacerbation. Blood transfusion was more commonly performed during stays for acute exacerbation (2.8 percent of stays) than during other COPD stays (2.2 percent of stays).

Five of the top ten procedures were diagnostic—bronchoscopy and biopsy of bronchus, echocardiogram, upper gastrointestinal endoscopy, computer tomography (CT) scan of chest, and cardiac catheterization.

Table 4. All-listed procedures for patients admitted to U.S. hospitals with a principal diagnosis of COPD, 2008

OCI D, 2000	All COPD		Acute exacerbation		Without acute exacerbation	
All-listed procedures	Number (%)	Rank	Number (%)	Rank	Number (%)	Rank
Invasive intubation and ventilation	31,200 (3.8%)	1	22,000 (4.3%)	1	9,200 (3.0%)	2
Noninvasive ventilation	28,600 (3.5%)	2	19,200 (3.7%)	2	9,400 (3.0%)	1
Blood transfusion	21,200 (2.6%)	3	14,200 (2.8%)	3	6,900 (2.2%)	4
Diagnostic bronchoscopy and biopsy of bronchus	15,800 (1.9%)	4	8,300 (1.6%)	6	7,400 (2.4%)	3
Diagnostic ultrasound of heart (echocardiogram)	15,700 (1.9%)	5	9,700 (1.9%)	4	6,000 (1.9%)‡	5
Upper gastrointestinal endoscopy; biopsy	13,500 (1.6%)	6	8,500 (1.7%)	5	5,000 (1.6%)‡	6
CT scan chest	8,100 (1.0%)	7	5,100 (1.0%)	7	3,000 (1.0%)‡	8
Diagnostic cardiac catheterization; coronary arteriography	8,100 (1.0%)	8	4,800 (0.9%)	8	3,300 (1.1%)	7
Hemodialysis	6,900 (0.8%)	9	4,300 (0.8%)	9	2,600 (0.8%)‡	9
Prophylactic vaccinations and inoculations	6,100 (0.7%)	10	3,600 (0.7%)	10	2,600 (0.8%)	10

[‡] The distribution of other COPD discharges is *not* statistically different from the distribution of acute exacerbation discharges at p<0.05.

Data Source

The estimates in this Statistical Brief are based upon data from the 2008 HCUP Nationwide Inpatient Sample (NIS) Supplemental source included data on regional population estimates from "Table 1: Annual Estimates of the Resident Population for the United States, Regions, States, and Puerto Rico: April 1, 2000 to July 1, 2009 (NST-EST2009-01)", Population Division, U.S. Census Bureau, Release date: December 2009 (http://www.census.gov/popest/states/NST-ann-est.html).

Source: AHRQ, Center for Delivery, Organization, and Markets, Healthcare Cost and Utilization Project, Nationwide Inpatient Sample (NIS), 2008

Definitions

Diagnoses and Procedures, ICD-9-CM, and Clinical Classifications Software (CCS)

The principal diagnosis is that condition established after study to be chiefly responsible for the patient's admission to the hospital. Secondary diagnoses are concomitant conditions that coexist at the time of admission or that develop during the stay.

The principal procedure is the procedure that was performed for definitive treatment rather than performed for diagnostic or exploratory purposes (i.e., the procedure that was necessary to take care of a complication). If two procedures appear to meet this definition, the procedure most related to the principal diagnosis was selected as the principal procedure.

ICD-9-CM is the International Classification of Diseases, Ninth Revision, Clinical Modification, which assigns numeric codes to diagnoses and procedures. There are about 14,000 ICD-9-CM diagnosis codes and 3,900 ICD-9-CM procedure codes. CCS categorizes ICD-9-CM diagnosis and procedure codes into a manageable number of clinically meaningful categories. This "clinical grouper" makes it easier to quickly understand patterns of diagnoses and procedures.

CCS categories were used for most analyses that examined other diagnoses and procedures on the discharge record. ICD-9-CM diagnosis codes 305.1-305.13 and V158.2 were employed to assess tobacco use as a secondary diagnosis among patients with COPD.

Case definition

For this report, stays for acute exacerbation of COPD were identified as having principal ICD-9-CM diagnosis code 491.21. The ICD-9-CM codes defining non-acute exacerbation of COPD were: 491.xx, 492.xx, 493.2, or 496.xx.

Types of hospitals included in HCUP

HCUP is based on data from community hospitals, defined as short-term, non-Federal, general and other hospitals, excluding hospital units of other institutions (e.g., prisons). HCUP data include OB-GYN, ENT, orthopedic, cancer, pediatric, public, and academic medical hospitals. Excluded are long-term care, rehabilitation, psychiatric, and alcoholism and chemical dependency hospitals. Please note, a discharge of this nature will be included in the NIS if it occurred in a community hospital.

Unit of analysis

The unit of analysis is the hospital discharge (i.e., the hospital stay), not a person or patient. This means that a person who is admitted to the hospital multiple times in one year will be counted each time as a separate "discharge" from the hospital.

Costs and charges

Total hospital charges were converted to costs using HCUP Cost-to-Charge Ratios based on hospital accounting reports from the Centers for Medicare and Medicaid Services (CMS). Costs will tend to reflect the actual costs of production, while charges represent what the hospital billed for the case. For each hospital, a hospital-wide cost-to-charge ratio is used because detailed charges are not available across all HCUP States. Hospital charges reflect the amount the hospital charged for the entire hospital stay and does not include professional (physician) fees. For the purposes of this Statistical Brief, costs are reported to the nearest hundred.

Urban-rural location

Urban-rural location is one of six categories as defined by the National Center for Health Statistics:

- Large Central Metropolitan: Central counties of metropolitan areas with a population of 1 million or greater
- Large Fringe Metropolitan: Fringe counties of counties of metropolitan areas with a population of 1 million or greater

⁸ HCUP CCS. Healthcare Cost and Utilization Project (HCUP). December 2009. U.S. Agency for Healthcare Research and Quality, Rockville, MD. www.hcup-us.ahrq.gov/toolssoftware/ccs/ccs.jsp

⁹ HCUP Cost-to-Charge Ratio Files (CCR). Healthcare Cost and Utilization Project (HCUP). 2001–2008. U.S. Agency for Healthcare Research and Quality, Rockville, MD. www.hcup-us.ahrg.gov/db/state/costtocharge.jsp.

- Medium Metropolitan: Counties in metro area of 250,000–999,999 population
- Small Metropolitan: Counties in metro areas of 50,000–249,999 population
- Micropolitan: Micropolitan counties, i.e. a non-metropolitan county with an area of 10,000 or more population
- Non-core: Non-metropolitan and non-micropolitan counties

Median community-level income

Median community-level income is the median household income of the patient's ZIP Code of residence. The cut-offs for the quartile designation are determined using ZIP Code demographic data obtained from Claritas. The income quartile is missing for homeless and foreign patients.

Payer

Payer is the expected primary payer for the hospital stay. To make coding uniform across all HCUP data sources, payer combines detailed categories into more general groups:

- Medicare includes fee-for-service and managed care Medicare patients.
- Medicaid includes fee-for-service and managed care Medicaid patients. Patients covered by the State Children's Health Insurance Program (SCHIP) may be included here. Because most state data do not identify SCHIP patients specifically, it is not possible to present this information separately.
- Private insurance includes Blue Cross, commercial carriers, and private HMOs and PPOs.
- Other includes Worker's Compensation, TRICARE/CHAMPUS, CHAMPVA, Title V, and other government programs.
- Uninsured includes an insurance status of "self-pay" and "no charge."

When more than one payer is listed for a hospital discharge, the first-listed payer is used.

Region

Region is one of the four regions defined by the U.S. Census Bureau:

- Northeast: Maine, New Hampshire, Vermont, Massachusetts, Rhode Island, Connecticut, New York, New Jersey, and Pennsylvania
- Midwest: Ohio, Indiana, Illinois, Michigan, Wisconsin, Minnesota, Iowa, Missouri, North Dakota,
 South Dakota, Nebraska, and Kansas
- South: Delaware, Maryland, District of Columbia, Virginia, West Virginia, North Carolina, South Carolina, Georgia, Florida, Kentucky, Tennessee, Alabama, Mississippi, Arkansas, Louisiana, Oklahoma, and Texas
- West: Montana, Idaho, Wyoming, Colorado, New Mexico, Arizona, Utah, Nevada, Washington,
 Oregon, California, Alaska, and Hawaii

Discharge status

Discharge status indicates the disposition of the patient at discharge from the hospital, and includes the following six categories: routine (to home), transfer to another short-term hospital, other transfers (including skilled nursing facility, intermediate care, and another type of facility such as a nursing home), home health care, against medical advice (AMA), or died in the hospital.

About HCUP

HCUP is a family of powerful health care databases, software tools, and products for advancing research. Sponsored by the Agency for Healthcare Research and Quality (AHRQ), HCUP includes the largest all-payer encounter-level collection of longitudinal health care data (inpatient, ambulatory surgery, and emergency department) in the United States, beginning in 1988. HCUP is a Federal-State-Industry Partnership that brings together the data collection efforts of many organizations—such as State data organizations, hospital associations, private data organizations, and the Federal government—to create a national information resource.

HCUP would not be possible without the contributions of the following data collection Partners from across the United States:

Arizona Department of Health Services

Arkansas Department of Health

California Office of Statewide Health Planning and Development

Colorado Hospital Association

Connecticut Hospital Association

Florida Agency for Health Care Administration

Georgia Hospital Association

Hawaii Health Information Corporation

Illinois Department of Public Health

Indiana Hospital Association

Iowa Hospital Association

Kansas Hospital Association

Kentucky Cabinet for Health and Family Services

Louisiana Department of Health and Hospitals

Maine Health Data Organization

Maryland Health Services Cost Review Commission

Massachusetts Division of Health Care Finance and Policy

Michigan Health & Hospital Association

Minnesota Hospital Association

Missouri Hospital Industry Data Institute

Montana MHA - An Association of Montana Health Care Providers

Nebraska Hospital Association

Nevada Department of Health and Human Services

New Hampshire Department of Health & Human Services

New Jersey Department of Health and Senior Services

New Mexico Health Policy Commission

New York State Department of Health

North Carolina Department of Health and Human Services

Ohio Hospital Association

Oklahoma State Department of Health

Oregon Association of Hospitals and Health Systems

Pennsylvania Health Care Cost Containment Council

Rhode Island Department of Health

South Carolina State Budget & Control Board

South Dakota Association of Healthcare Organizations

Tennessee Hospital Association

Texas Department of State Health Services

Utah Department of Health

Vermont Association of Hospitals and Health Systems

Virginia Health Information

Washington State Department of Health

West Virginia Health Care Authority

Wisconsin Department of Health Services

Wyoming Hospital Association

About the NIS

The HCUP Nationwide Inpatient Sample (NIS) is a nationwide database of hospital inpatient stays. The NIS is nationally representative of all community hospitals (i.e., short-term, non-Federal, non-rehabilitation hospitals). The NIS is a sample of hospitals and includes all patients from each hospital, regardless of payer. It is drawn from a sampling frame that contains hospitals comprising about 95 percent of all discharges in the United States. The vast size of the NIS allows the study of topics at both the national and regional levels for specific subgroups of patients. In addition, NIS data are standardized across years to facilitate ease of use.

For more information

For more information about HCUP, visit www.hcup-us.ahrq.gov.

For additional HCUP statistics, visit HCUPnet, our interactive guery system, at www.hcup.ahrq.gov.

For information on other hospitalizations in the U.S., download *HCUP Facts and Figures: Statistics on Hospital-based Care in the United States in 2008*, located at http://www.hcup-us.ahrq.gov/reports.jsp.

For a detailed description of HCUP, more information on the design of the NIS, and methods to calculate estimates, please refer to the following publications:

Steiner, C., Elixhauser, A., Schnaier, J. The Healthcare Cost and Utilization Project: An Overview. *Effective Clinical Practice* 5(3):143–51, 2002.

Introduction to the HCUP Nationwide Inpatient Sample, 2008. Online. May 2010. U.S. Agency for Healthcare Research and Quality. http://hcup-us.ahrg.gov/db/nation/nis/NIS 2008 INTRODUCTION.pdf

Houchens, R., Elixhauser, A. *Final Report on Calculating Nationwide Inpatient Sample (NIS) Variances, 2001.* HCUP Methods Series Report #2003-2. Online. June 2005 (revised June 6, 2005). U.S. Agency for Healthcare Research and Quality.

http://www.hcup-us.ahrq.gov/reports/CalculatingNISVariances200106092005.pdf

Suggested Citations

Wier, L.M. (Thomson Reuters), Elixhauser, A. (AHRQ), Pfuntner, A. (Thomson Reuters), Au, D.H. (Department of Veterans Affairs). *Overview of Hospitalizations among Patients with COPD, 2008.* HCUP Statistical Brief #106. February 2011. Agency for Healthcare Research and Quality, Rockville, MD. http://www.hcup-us.ahrq.gov/reports/statbriefs/sb106.pdf

Acknowledgments

The authors would like to acknowledge Mika Nagamine (Thomson Reuters) and Minya Sheng (Thomson Reuters) for programming assistance.

Funding

Dr. Au was supported through the Department of Veterans Affairs, VA Puget Sound Health Care System and Health Services Research and Development

Disclaimer

The views expressed represent those of the authors and do not necessarily represent the views of the Department of Veterans Affairs.

* * *

AHRQ welcomes questions and comments from readers of this publication who are interested in obtaining more information about access, cost, use, financing, and quality of health care in the United States. We also invite you to tell us how you are using this Statistical Brief and other HCUP data and tools, and to share suggestions on how HCUP products might be enhanced to further meet your needs. Please e-mail us at hcup@ahrq.gov or send a letter to the address below:

Irene Fraser, Ph.D., Director Center for Delivery, Organization, and Markets Agency for Healthcare Research and Quality 540 Gaither Road Rockville, MD 20850