



Understanding How They Attack Your Weaknesses: CAPEC



Sean Barnum MITRE





The Long-established Principal of "Know Your Enemy"

"One who knows the enemy and knows himself will not be endangered in a hundred engagements. One who does not know the enemy but knows himself will sometimes be victorious. Sometimes meet with defeat. One who knows neither the enemy nor himself will invariably be defeated in every engagement."



■ The Art of War, Sun Tzu



The Importance of Knowing Your Enemy



An appropriate defense can only be established if you know how it will be attacked

Remember!

- Software Assurance must assume motivated attackers and not simply passive quality issues
- Attackers are very creative and have powerful tools at their disposal
- Exploring the attacker's perspective helps to identify and qualify the risk profile of the software



What are Attack Patterns?



- Blueprint for creating a specific type of attack
- Abstracted common attack approaches from the set of known exploits
- Capture the attacker's perspective to aid software developers, acquirers and operators in improving the assurance profile of their software





Leveraging Attack Patterns Throughout the Software Lifecycle

- Guide definition of appropriate policies
- Guide creation of appropriate security requirements (positive and negative)
- Provide context for architectural risk analysis
- Guide risk-driven secure code review
- Provide context for appropriate security testing
- Provide a bridge between secure development and secure operations



Common Attack Pattern Enumeration and Classification (CAPEC)



Community effort targeted at:

- Standardizing the capture and description of attack patterns
- Collecting known attack patterns into an integrated enumeration that can be consistently and effectively leveraged by the community
- Gives you an attacker's perspective you may not have on your own

Excellent resource for many key activities

- Abuse Case development
- Architecture attack resistance analysis
- Risk-based security/Red team penetration testing
- Whitebox and Blackbox testing correlation
- Operational observation and correlation

Where is CAPEC today?

- http://capec.mitre.org
- Currently 311 patterns, stubs, named attacks









Development Institute

What do Attack Patterns Look Like?



Primary Schema Elements

- Identifying Information
 - Attack Pattern ID
 - Attack Pattern Name
- Describing Information
 - Description
 - Related Weaknesses
 - Related Vulnerabilities
 - Method of Attack
 - Examples-Instances
 - References
- Prescribing Information
 - Solutions and Mitigations
- Scoping and Delimiting Information
 - Typical Severity
 - Typical Likelihood of Exploit
 - Attack Prerequisites
 - Attacker Skill or Knowledge Required
 - Resources Required
 - Attack Motivation-Consequences
 - Context Description

Supporting Schema Elements

- Describing Information
 - Injection Vector
 - Payload
 - Activation Zone
 - Payload Activation Impact
- Diagnosing Information
 - Probing Techniques
 - Indicators-Warnings of Attack
 - Obfuscation Techniques
- Enhancing Information
 - Related Attack Patterns
 - Relevant Security Requirements
 - Relevant Design Patterns
 - Relevant Security Patterns



Attack Pattern Description Schema Formalization



Description

- **Summary**
- **Attack Execution Flow**
 - Attack_Phase^{1..3} (Name(Explore, Experiment, Exploit))
 - Attack Step^{1..*}
 - Attack Step Title
 - Attack Step Description
 - Attack_Step_Technique ^{0..*}
 - Attack Step Technique Description
 - Leveraged Attack Patterns
 - Relevant Attack Surface Elements
 - Observables^{0..*}
 - Environments
 - Indicator^{0..*} (ID, Type(Positive, Failure, Inconclusive))
 - Indicator Description
 - Relevant_Attack_Surface_Elements
 - Environments
 - Outcome^{0..*} (ID, Type(Success, Failure, Inconclusive))
 - Outcome Description
 - Relevant_Attack_Surface_Elements
 - Observables^{0..*}
 - Environments
 - Security Control^{0..*} (ID, Type(Detective, Corrective, Preventative))
 - Security Control Description
 - Relevant_Attack_Surface_Elements
 - Observables^{0..*}

Individual CAPEC Dictionary Definition (Release 1.2) Blind SQL Injection Attack Pattern 7 ID Typical High Severity Description Summary Blind SQL Injection results from an insufficient mitigation for SQL Injection alone error messages are considered best practice, the suppression alone Injection. Blind SQL Injection is a form of SQL Injection that overcome

Blind SQL Injection results from an insufficient mitigation for SQL Injection. Although suppressing database error messages are considered best practice, the suppression alone is not sufficient to prevent SQL Injection. Blind SQL Injection is a form of SQL Injection that overcomes the lack of error messages. Without the error messages that facilitate SQL Injection, the attacker constructs input strings that probe the target through simple Boolean SQL expressions. The attacker can determine if the syntax and structure of the injection was successful based on whether the query was executed or not. Applied iteratively, the attacker determines how and where the target is vulnerable to SQL Injection.

In order to achieve this using Blind SQL Injection, an attacker:

Pattern Abstraction: Detailed

the result is the same as when the attacker entered "username" in the field, then the attacker knows that the application is vulnerable to SQL Injection. The attacker can then ask yes/no questions from the database server to extract information from it. For example, the attacker can extract table names from a database using the following types of queries:

"username' AND ascii(lower(substring((SELECT TOP 1 name FROM sysobjects WHERE xtype='U'), 1, 1))) > 108".


For example, an attacker may try entering something like "username' AND 1=1; -- "in an input field. If


If the above query executes properly, then the attacker knows that the first character in a table name in the database is a letter between m and z. If it doesn't, then the attacker knows that the character must be between a and I (assuming of course that table names only contain alphabetic characters). By performing a binary search on all character positions, the attacker can determine all table names in the


database. Subsequently, the attacker may execute an actual attack and send something like:
"username'; DROP TABLE trades; --

Complete CAPEC Entry Information











A Few Key Use Cases for CAPEC in Support of SwA

- Help developers understand weaknesses in their real-world context (how they will be attacked)
- Objectively identify specific attacks under which software must demonstrate resistance, tolerance and resilience for a given level of assurance
- Indirectly scope which weaknesses are relevant for a given threat environment
- Identify relevant mitigations that should be applied as part of policy, requirements, A&D, implementation, test, deployment and operations
- Identify and characterize patterns of attacks for security test case generation
- Identify and characterize threat TTPs for red teaming
- Identify relevant issues for automated tool selection
- Identify and characterize issues for automated tool results analysis



HS SED Homeland Security Systems Engineering and Development Institute

CAPEC and Security Measurement


CAPEC current non-automation value

- Measuring stick for evaluating and comparing penetration testing tools and application defense tools
 - Similar to CWE value to secure code analysis tools and CVE value to vulnerability scanners
- Measuring stick for attack resistance claims of assurance cases
 - It comes down to the proxies for measuring security (vulnerabilities, weaknesses and attack resistance)

CAPEC developing automation value

- Characterizing the nature of software attack
 - Formalization of attack patterns to enable:
 - Recognition and mapping of attack instances from the operations realm
 - Refined ability to measure attack resistance in terms of resistance to individual sub-elements of attack with observables
 - Automated generation of penetration attack cases
 - Defining & mapping attack simulations in penetration testing tools
 - Alignment with malware characterization (MAEC)





CAPEC Status



Where is CAPEC today?

- •V1.4
 - Massive schema changes
 - Some new content
 - Added initial set of network attack patterns
- •V1.5
 - Added ~25 new network attack patterns
 - Added enhanced material to ~35 patterns
 - New View added for WASC Threat Taxonomy 2.0
 - Added ~65 mappings to CWE and several within CAPEC

Currently 311 patterns, stubs, named attacks; 67 categories and 6 views



CAPEC Current Content (12 Major Categories)



- 1000 Mechanism of Attack
- Data Leakage Attacks (118)
- Resource Depletion (119)
- •Injection (Injecting Control Plane content through the Data Plane) (152)
- **•**Spoofing (156)
- Time and State Attacks (172)
- Abuse of Functionality (210)
- Exploitation of Authentication (225)
- Probabilistic Techniques (223)
- Exploitation of Privilege/Trust (232)
- Data Structure Attacks (255)
- Resource Manipulation (262)
- Network Reconnaissance (286)



CAPEC Current Content (Which Expand to...)



Exploitation of Authentication - (225) 1000 - Mechanism of Attack Data Leakage Attacks - (118) Exploitation of Session Variables, Resource IDs and other Trusted Data Excavation Attacks - (116) Credentials - (21) Data Interception Attacks - (117) Authentication Abuse - (114) Resource Depletion - (119) Authentication Bypass - (115) Violating Implicit Assumptions Regarding XML Content (aka XML Denial Exploitation of Privilege/Trust - (232) of Service (XDoS)) - (82) Privilege Escalation - (233) Resource Depletion through Flooding - (125) Exploiting Trust in Client (aka Make the Client Invisible) - (22) Resource Depletion through Allocation - (130) Hijacking a Privileged Thread of Execution - (30) Resource Depletion through Leak - (131) Subvert Code-signing Facilities - (68) Denial of Service through Resource Depletion - (227) Target Programs with Elevated Privileges - (69) Injection (Injecting Control Plane content through the Data Plane) - (152) Exploitation of Authorization - (122) Remote Code Inclusion - (253) Hijacking a privileged process - (234) Analog In-band Switching Signals (aka Blue Boxing) - (5) Data Structure Attacks - (255) SQL Injection - (66) Accessing/Intercepting/Modifying HTTP Cookies - (31) Email Injection - (134) Buffer Attacks - (123) Attack through Shared Data - (124) Format String Injection - (135) LDAP Injection - (136) Integer Attacks - (128) Pointer Attack - (129) Parameter Injection - (137) Reflection Injection - (138) Resource Manipulation - (262) Code Inclusion - (175) Accessing/Intercepting/Modifying HTTP Cookies - (31) Resource Injection - (240) Input Data Manipulation - (153) Script Injection - (242) Resource Location Attacks - (154) Command Injection - (248) Infrastructure Manipulation - (161) Character Injection - (249) File Manipulation - (165) XML Injection - (250) Variable Manipulation - (171) DTD Injection in a SOAP Message - (254) Configuration/Environment manipulation - (176) Spoofing - (156) Abuse of transaction data strutcture - (257) Content Spoofing - (148) Registry Manipulation - (269) Identity Spoofing (Impersonation) - (151) Schema Poisoning - (271) Action Spoofing - (173) Protocol Manipulation - (272) Time and State Attacks - (172) Network Reconnaissance - (286) Forced Deadlock - (25) ICMP Echo Reguest Ping - (285) Leveraging Race Conditions - (26) TCP SYN Scan - (287) Leveraging Time-of-Check and Time-of-Use (TOCTOU) Race Conditions -ICMP Echo Request Ping - (288) Infrastructure-based footprinting - (289) Manipulating User State - (74) Enumerate Mail Exchange (MX) Records - (290) Abuse of Functionality - (210) DNS Zone Transfers - (291) Functionality Misuse - (212) Host Discovery - (292) Abuse of Communication Channels - (216) Traceroute Route Enumeration - (293) Forceful Browsing - (87) ICMP Address Mask Request - (294) ICMP Timestamp Request - (295) Passing Local Filenames to Functions That Expect a URL - (48) Probing an Application Through Targeting its Error Reporting - (54) ICMP Information Request - (296) WSDL Scanning - (95) TCP ACK Ping - (297) API Abuse/Misuse - (113) UDP Ping - (298) Try All Common Application Switches and Options - (133) TCP SYN Ping - (299) Cache Poisoning - (141) Port Scanning - (300) TCP Connect Scan - (301) Software Integrity Attacks - (184) Directory Traversal - (213) TCP FIN scan - (302) Analytic Attacks - (281) TCP Xmas Scan - (303) Probabilistic Techniques - (223) TCP Null Scan - (304) TCP ACK Scan - (305) Fuzzing - (28) TCP Window Scan - (306) TCP RPC Scan - (307) UDP Scan - [368] S SEDI FFRDC is managed and operated by The MITRE Corporation for DHS.

CAPEC Current Content (311 Attacks...)





Current Maturation Paths



- Extend coverage of CAPEC
- Improve quality of CAPEC
- Expand the scope of CAPEC
- Bridge secure development with secure operations
- Improve integration with other standards (MAEC, CEE, etc.)
- Expand use of CAPEC



Expanding the Scope of CAPEC




- Originally focused solely on attacks against software systems
- CAPEC has begun to expand its scope to encompass the capture and characterization of attack patterns in domains outside of but relevant to software system attacks
- CAPEC v1.4
 - Network attack patterns
- CAPEC v1.6
 - Social Engineering attack patterns
 - Supply chain attack patterns





Attack Patterns Bridge Secure Development and Secure Operations







Attack Patterns Help Answer Foundational Questions Regarding Secure Operations

Question	Role of Attack Patterns
Are we being attacked? (Were we attacked?)	Attack patterns offer structured descriptions of common attacker behaviors to help interpret observed operational data and determine its innocent or malicious intent.
How are we being attacked?	Attack patterns offer detailed structured descriptions of common attacker behavior to help interpret observed operational data and determine exactly what sort of attack is occurring.
What is the objective of the attack?	Elements of attack patterns outlining attacker motivation and potential attack effects can be leveraged to help map observed attack behaviors to potential attacker intent.
What is our exposure?	The structure detail and weakness mapping of attack patterns can provide guidance in where to look and what to look for when certain attack pattern behaviors are observed.
Who is attacking us?	Attack pattern threat characterization and detailed attack execution flow can provide a framework for organizing real-world attack data to assist in attribution.
What should we do to prevent against attacks in the future?	Attack patterns offer prescriptive guidance on solutions and mitigation approaches that can be effective in improving the resistance tolerance and/or resilience to instances of a given pattern of attack.



"Observables" are the Key Enabler for Bridging Secure Development and Secure Operations



- The Observables construct is intended to capture and characterize events or properties that are observable in the operational domain.
- These observable events or properties can be used to adorn the appropriate portions of the attack patterns in order to tie the logical pattern constructs to real-world evidence of their occurrence or presence.
- It enables the alignment of the low-level aggregate mapping of observables that occurs in the operations domain to the higher-level abstractions of attacker methodology, motivation, and capability that exist in the development domain.

Observables Intent



- By capturing them in a structured fashion, the intent is to enable future potential for detailed automatable mapping and analysis heuristics.
- The current Observables draft schema adorns the Attack_Step, Attack_Step_Technique, Attack_Step Outcome, and Attack_Step Security_Control elements of the attack pattern schema. It focuses on characterizing specific observable measures, their value, their sensor context, and how accurate or easy to obfuscate they are.
- Future schema revisions should flesh out the construct to cover other relevant dimensions.

Observables Structure



The imminent revision of the Observables schema will:

- Capture more complete descriptive information for the measure source
- Support for both Static "Stateful Measures" and Dynamic "Events"
- Enable Measure composition, chaining and logical combination through multiplicities and relationships
- Leverage flexible structures for Actions, Objects & Attributes to support description of both current and future "observables"
- Provide extensive relevant content for enumeration constraints on source, event, action, object & attribute types



A Few Use Cases for "Observables" in Bridging Secure Development (SD) and Secure Operations (SO)



- •SO: Correlate observed events (realtime or from incident management) to detect that attack is occurring
- •SO: Correlate observed events (realtime or from incident management) to identify what type of attack is occurring
- •SO: Utilize info in relevant CAPEC patterns to focus where else to look for other indicators of attack
- •SO: Utilize info in relevant CAPEC patterns to focus where else to look to determine severity of breach
- SO: Utilize info in relevant CAPEC patterns to characterize the attacker (including maybe someday supporting attribution)
- •SD: Utilize real-world operations events to identify new attack patterns
- •SD: Utilize real-world operations events to prioritize relevant attack patterns based on reality of what is being used
- •SD: Utilize real-world operations events to determine if mitigations are effective







- The Observables schema is a shared need and solution among CAPEC, the Malware Attribute Enumeration and Characterization (MAEC) & the Common Event Expression (CEE)
- Continuing to refine bidirectional linkages and integrations between CAPEC & MAEC

Manually review code after security education

Manual code review, especially review of high-risk code, such as code that faces the Internet or parses data from the Internet, is critical, but only if the people performing the code review know what to look for and how to fix any code vulnerabilities they find. The best way to help understand classes of security bugs and remedies is education, which should minimally include the following areas:

- . C and C++ vulnerabilities and remedies, most notably buffer overrums and
- . Web-specific vulnerabilities and remedies, such as cross-site scripting (XSS).
- . Database-specific vulnerabilities and remedies, such as SQL injection.
- . Cummon cryptographic errors and remedies.

Many vulnerabilities are programming language (C, C++ etc) or domain-specific (web, database) and others can be categorized by vulnerability type, such as injection (XSS and SQL Injection) or cryptographic (poor random number generation and weak secret storage) so specific training in these areas is advised.

Resources

- . A Process for Performing Security Code Reviews, Michael Howard, IEEE Security & Privacy July/August 2006.
- . NET Framework Security -- Code Review,
- . Common Weakness Enumeration, MITRE: http://cwe.mitre.org/
- Max //www.codesecurely.org/Wist/view.aspe/Security. Code. Reviews
- Security Code Review Use Visual Studio Bookmarks To Capture Security Findings; http://blags.mads.com/alls/Jarchave/2008/01/24/securityvisual studio-bookmarks to capture escurity findings angx
- conty Cade Review Guidelines, Adom Shortack;
- I//www.verbecom/mark/cs/security/code-review.html . DO SASP Top Ten; 1979; //www.owasp.org/index.ohp/DWASP Top Ten Project



CWE **CAPEC**

Industry Uptake

മമമ ooo. 10001

Testing

Testing activities validate the secure implementation of a product, which rethe likelihood of security bugs being released and discovered by customers a malicious users. The majority of SAFECode members have adopted the folio software security testing practices in their software development lifecycle. The is not to "test in security," but rather to validate the redustness and secur the software products prior to making the product available to customers. testing methods do find security bugs, especially for products that may not undergone critical secure development process changes.

Fuzz testing

Fuzz testing is a reliability and security testing technique that relies on bu intentionally malformed data and then having the software under test consume the mathermed data to see how it responds. The science of fuzz testing is somewhat. new but it is maturing rapidly. There is a small market for fuzz testing tools today, but in many cases software developers must build bespoke fuzz testers to suit specialized file and network data formats. Fuzz testing is an effective testing technique because it uncovers weaknesses in data handling code.

- . Fudz Testing of Application Reliability, University of Wisconsin; http://pages.rs.wisc.edu/~bart/fuzz/fuzz.html
- · Automated Whitebox Fuzz Testing, Michael Levin, Patrick Godefrold and Dave Moinar, Microsoft Research htp://mp.research.microsoft.com/pub/tr/TR-2007-58.pdf
- . IAWest letter Spring 2007 "Look out! It's the fuzz!" Matt Warnock; http://tax.attic.mit/wtac/download/viv10_No1.pdf
- . Fuzzing: Brute Force Vulnerability Discovery. Sutton, Greene & Amini,
- + Common Attack Pattern Enumeration and Classification, MCTRE; http://eaowc.mitre.org/



Fundamental Practices for Secure Software Development

A Guide to the Most Effective Secure **Development Practices in Use Today**

OCTOBER 8, 2008

LEAD WRITER Michael Howard, Microsoft Corp.

CONTRIBUTORS Gunter Bits, SAP AC lerry Cactivan, Microsoft Carp. Matt Coles, EWC Corporation Danny Dhillon, EWC Corporation Chris Rasian, Microsoft Colo. Cassio Goldschmidt, Symantoc Corp. ... Janne Usalletto, Nobia Wesley Higalic Symunion Corp.

Steve Liames Microsoft Corp. Brief Minn's, Juniper Networks, Inc. Hardik Parekti, EMC Corporation Date Rendely, EMC Corporation Alcoundt Selectyon, North Asserv Sondhi, EWC Composition Acts Vine Spile, Notice





Linkage with Fundamental Changes in Enterprise Security Initiatives DI

Twenty Critical Controls for Effective Cyber Def Guidelines

What the 20 CSC Critics say...

20 Critical Security Controls - Version 2.0

- 20 Critical Security Controls Introduction (Version 2.0)
- Critical Control 1: Inventory of Authorized and Unauthorized
- Critical Control 2: Inventory of Authorized and Unauthorized
- Critical Control 3: Secure Configurations for Hardware and So Servers
- Critical Control 4: Secure Configurations for Network Devices
- Critical Control 5: Boundary Defense
- Critical Control 6: Maintenance, Monitoring, and Analysis of
- Critical Control 7: Application Software Security
- Critical Control 8: Controlled Use of Administrative Privilege
- Critical Control 9: Controlled Access Based on Need to Know
- Critical Contro
- Critical Control
- Critical Contr
- Critical Contr
- Critical Control
- Critical Control
- Critical Contro
- Critical Contr
- Critical Contr
- Critical Control
- Critical Control
- Critical Control

Procedures and tools for implementing the

CAG: Critical Control 7: Application Software Security

<< previous control

Consensus Audit Guidelines

next control >>

How do attackers exploit the lack of this control?

Attacks against vulnerabilities in web-based and other application software have been a top priority for criminal organizations in recent years. Application software that does not properly check the size of user input, fails to sanitize user input by filtering out unneeded but potentially malicious character sequences, or does not initialize and clear variables properly could be vulnerable to remote compromise. Attackers can inject specific exploits, including buffer overflows, SQL injection attacks, and cross-site scripting code to gain control over vulnerable machines. In one attack in 2008, more than 1 million web servers were exploited and turned into infection engines for visitors to those sites using SQL injection. During that attack, trusted websites from state governments and other organizations compromised by attackers were used to infect hundreds of thousands of

CWE and CAPEC included in Control 7 of the "Twenty Critical Controls for Effective Cyber Defense: Consensus Audit Guidelines"

Source code testing tools, web application security scanning tools, and object code testing tools have proven useful in securing application software, along with manual application security penetration testing by testers who have extensive programming knowledge as well as application penetration testing expertise. The Common Weakness Enumeration (CWE) initiative is utilized by many such tools to identify the weaknesses that they find. Organizations can also use CWE to determine which types of weaknesses they are most interested in addressing and removing. A broad community effort to identify the "Top 25 Most Dangerous Programming Errors" is also available as a minimum set of important issues to investigate and address during the application development process. When evaluating the effectiveness of testing for these weaknesses, the Common Attack Pattern Enumeration and Classification

(CAPEC) can be used to organize and record the breadth of the testing for the CWEs as well as a

way for testers to think like attackers in their development of test cases.











ISO/IEC JTC 1/SC 27 NXXXX

ISO/IEC JTC 1/SC 27/WG x NXXXXX

ISO/IEC JTC 1/SC 27 Information technology - Security techniques

Secretariat DIN, Germany

DOC TYPE NB NWI Proposal for a technical report (TR)

National Body New Work Item Proposal on "Secure software development and evaluation under ISO/IEC 15408 and ISO/IEC 18405" INCITRICS1. National Body of (US)

2009-09-30 DATE:

PROJECT 15488 and 18605

STATUS This document is circulated for consideration at the forthcoming meeting of SC 27/WG 3 to be held in Redmond (WA, USA) on 2rd – 6th November 2009.

ACTION ID

DUE DATE:

SOURCE

DISTRIBUTION P-, O- and L-Members

W. Furny, SC 27 Chairman M. De Soete, SC 27 Vice-Chair

E. J. Humphrevs, K. Naemura, M. Ballón, M.-C. Kano, K. Rannesbero, W.G.

NO. OF PAGES:

Common Criteria v4 CCDB

SC27

WG3

- TOE to leverage CAPEC & CWE
- Also investigating how to leverage ISO/IEC 15026

NIAP Evaluation Scheme

- Above plus
- Also investigating how to **leverage SCAP**

New Work Item Proposal

PROPOSAL FOR A NEW WORK ITEM

Date of presentation of proposal: YYYY-MM-DD	Proposer: ISO/IEC JTC 1 SC27
Secretariat:	ISOMECUTC 1 N XXXX
National Body	ISOMECUTC 1/SC 27 N

A proposal for a new work item shall be submitted to the secretarist of the ISO(IDC joint technical committee concerned with a copy to the ISO Central Secretariat.

Presentation of the proposal

Title Secure software development and evaluation under ISO/IEC 15408 and ISO/IEC 18405

In the case where a target of evaluation (TOE) being evaluated, under ISO/IEC 15408 and ISO/IEC 15405, includes specific software portions, the TOE developer may optionally present the developer's actinical nationals for mitigating software common attack patterns and nelated weaknesses as described in the latest revision of the Common Attack Pattern Enumeration and Classification (CAPEC) available from http://saper.mitre.org/. The developer's technical rationale is expected to include a range mitigation techniques, from architectural properties to design features, coding techniques, use of tools of

This Technical Report (TR) provides guidance for the developer and the evaluator on how to use the CAPEC as a technical reference point during the TOE development life cycle, and in an evaluation of the OE secure software under ISO/IEC 15408 and 18045, by addressing:

- a) A refinement of the IS 15408 Attack Potential calculation table for software, taking into account the entries contained in the CAPEC and their characterization.
- b) How the information for mitigating software common attack patierns and related weaknesses is used in an IS 15406 evaluation, in particular providing guidance on how to determine which attack patterns and weaknesses are applicable to the TOE, taking into consideration of
 - 1. the TOE technology
 - 2. the TOE security problem definition:
 - 3. the interfaces the TOE exports that can be used by potential attackers;
 - 4. the Affack Polantial that the TDE needs to provide resistance for
- c) How the technical rationale provided by the developer for mitigating software common attack patterns and related weaknesses is used in the evaluation of the TOE design and the development of test cases.
- the evaluator, who needs to consider all the applicable attack patterns and be able to exploit specific related software weaknesses while performing the subsequent valnerability analysis (AVA_VAN) activities on the TOE.
- e) How incomplete entries from the CAPEC are resolved during an IS 15408 evaluation.
- How the evaluator's attack and weakness analysis of the TOE incorporates other attacks and weaknesses not yet discurrented in the CAPEC.

The TR also investigates specific elements from the ISO AEC 19825 (and its revision) are applicable to the guidelines being developed in the TR within the context of IS 19486 and 18485.

ISO/IEC JTC 1/SC 27/WG 3, NWP "Secure software development and evaluation under its 150/IEC 15408 and ISO/IEC 18045"







- The way how the CAPEC and related CWE taxonomies are to be used by the developer, which needs to consider and provide sufficient and effective mitigation to all applicable attacks and weaknesses.
- The way how the CAPEC and related CWE taxonomies are to be used by the evaluator, which needs to consider all the applicable attack patterns and be able to exploit all the related software weaknesses while performing the subsequent AVA VAN activities.
- How incomplete entries from the CAPEC are to be addressed during an evaluation.
- How to incorporate to the evaluation attacks and weaknesses not included in the CAPEC.



CAPEC Future Plans



- V1.6 (imminent)
 - •Will flesh out 15 stub patterns to full patterns
 - •Will add ~10 new patterns around application framework attacks
 - •Will add 5-10 new social engineering attack pattern stubs
 - •Will add 5-10 new supply chain attack pattern stubs
 - •Will incorporate extensively refined Observables schema
- •Strategic focus for the near to mid-term will be on utilizing CAPEC as a bridge between secure development and secure operations
- Continue expanding and refining content
- Continue expanding outreach and supporting CAPEC use
- Establish initial compatibility program



Questions?

sbarnum@mitre.org



Know Their Attacks

