



# **Status Update**

Jon Baker September 28, 2010



HS SEDI is a trademark of the U.S. Department of Homeland Security (DHS). The HS SEDI FFRDC is managed and operated by The MITRE Corporation for DHS.

# **OVAL Overview**

An international, information security, community standard to promote open and publicly available security content, and to standardize the transfer of this information across the entire spectrum of security tools and services.

### Open Vulnerability and Assessment Language

- A community-developed open standard
- Began in December 2002

### OVAL Language

- XML-based framework for making logical assertions about a system
  - Vulnerable, Compliant, Installed application, Patched
- OVAL Interpreter
  - An open source reference implementation

### OVAL Repository

collection of community contributed OVAL Definitions

### OVAL Adoption

both educate vendors and receive constructive technical feedback





# **MITRE's Role in OVAL**



#### MITRE is a not-for-profit corporation, chartered to work solely in the public interest. \*\*\*

- MITRE operates Federally Funded Research and Development Centers (FFRDCs).
- Non-compete charter fosters "trusted moderator" status.
- Work in the public interest.
- Government sponsored.

#### OVAL Moderator

- Help drive consensus between government customers and greater community with technical solutions and changes.
- Promote the growth and adoption of OVAL.
- **Listen** to the community and guide the development of OVAL.
- Facilitate the OVAL Board.
- **Moderate** the OVAL Repository.
- Balance different perspectives to arrive at the consensus solution that is best for OVAL and the public interest.



# **OVAL Releases**

Minor releases add tests, minor capabilities, and critical fixes.

Releases occur as needed by the community (2-3 per year).

All releases are approved by the OVAL Board.

#### Version 5.0

- Release Date: June 16, 2006
- Version 5.1
  - Release Date: November 6, 2006
- Version 5.2
  - Release Date: January 31, 2007

#### Version 5.3

- Release Date: June 27, 2007

#### Version 5.4

- Release Date: April 10, 2008

#### Version 5.5

- Release Date: October 1, 2008

SCAP 1.0

#### Version 5.6

- Release Date: September 11, 2009
- Version 5.7
  - Release Date: May 12, 2010
- Version 5.8
  - Release Date: September 15, 2010
- Version 5.9
  - Planning Started: September 15, 2010
- Version 6.0
  - Planning: TBD







3

# SCAP's Use of OVAL



#### OVAL provides the low level system assessment capability.



#### OVAL's Use Cases

- 1. Security Advisory Distribution Defining the conditions under which the issue exists.
- 2. Vulnerability Assessment Detecting the presence of the issue.
- 3. Patch Management Determining if the patch can be installed.
- 4. Configuration Management Defining the desired configuration and monitoring systems.
- 5. Auditing and Centralized Audit Validation Representing detail system assessment results over time.
- 6. Security Information Management Systems (SIMS) Standardized assessment result format for consumption and fusion with other sensor inputs.
- 7. System Inventory Describing how to detect an installed application.
- 8. Malware and Threat Indicator Sharing Describing the possible locations of malware or threat artifacts and indicators.



# What's new for OVAL 5.5?

#### Corrected documentation and Schematron errors.

- Search scope limited to SACL/DACL when checking permissions in Windows.
- Data types are based on XML Schema data types.
- Clarified 'version' datatype format.
- Require @var\_check when a @var\_ref is used.

#### Added several new functions.

- arithmetic, regex\_capture, time\_difference

#### Added Cisco PIX OS component schema.

#### Added and corrected several tests.

- win-def:wuaupdatesearcher\_test
- win-def: user\_sid55\_test
- ios-def:version55\_test
- catos-def:version55\_test
- catos-def:line\_test





5

# What's new for OVAL 5.6?

- Allow pattern matches on elements that are restricted to an enumeration.
- Allow a test to reference multiple states for more sophisticated state comparisons.
- Introduced a choice structure inside of objects to allow files to be defined by either a path and filename or simply a complete file path.
- Changed the required <u>regular expression syntax</u> to Perl 5's regular expression specification.
- Deprecated the resolve\_group behavior on all tests in the Windows component schema except for the sid\_sid\_test and the sid\_test.
  - helps to avoid overly resource-intensive searches for Windows trustees.
- New Tests and Component Schemas Added in Version 5.6
  - Added the win-def:serviceeffectiverights\_test to support checking the rights of services on Windows.
  - Added the ind-def:ldap\_test to support checking settings via LDAP queries to a directory server.
  - Added the aix-def:interim\_fix\_test to support checking interim or emergency fixes on IBM AIX.
  - Added the SharePoint component schema.
  - Added a new patch test to the VMware ESX component schema.







# **Tests Reference Multiple States**





### A single item can be tested against multiple states.

- Allows for the expression of ranges of acceptable values.
- Specify multiple acceptable values.
- Simplifies content authoring.

### What Changed?

- Introduced a new @state\_operation on the oval-def:TestType.
- Changed the multiplicity of states in the oval-def:TestType.

### Example: Minimum password length is between 8 and 16

- Items must satisfy state 1:

<min\_passwd\_len datatype="int" operation="greater than or equal">8</min\_passwd\_len>

– AND state 2:

<min\_passwd\_len datatype="int" operation="less than or equal">16</min\_passwd\_len>



# What's new for OVAL 5.7?





- Added support for n-tuples.
- Numerous Schematron rule refinements and performance focused improvements.
  - Introduced Schematron phases.
- Significant documentation improvements were made throughout the OVAL Language.

### Removed deprecated items.

ind-def:filemd5\_test and apache-def:version\_test

### Added new tests.

- Added the win-def:dnscache\_test and unix-def:dnscache\_test
- Added new tests in order to leverage n-tuple support.



# **N-Tuples**







- A record comprised of any number of related fields can be represented and tested in OVAL.
  - Example Pair: {Name, ScreenSaverTimeOut}
  - Improves support for WMI, XML, SQL, and other complex data stores.

### What Changed?

- Introduced a new structure to represent a record.
- Updated WMI, SQL, XML, Active Directory related tests to leverage the new record structure.

#### Example:

#### WQL - SELECT Name, ScreenSaverTimeOut FROM Win32\_Desktop;

<wmi\_state id="oval:sample:ste:2" operator="AND" version="1" xmlns="...">
<result datatype="record" operation="equals" >
<field name= "Name" datatype="string" operation="equals">user2</field>
<field name= "ScreenSaverTimeOut" datatype="int" operation="less than">600</field>
</result>
</wmi\_state>



# What's new for OVAL 5.8?



- Refactored datatype constraints on all entities.
- Added support for unbounded filter elements in objects.
- Added an explicit mapping of tests, objects, states, and items.
- Added an OVAL Directives schema.
- Enhanced OVAL Results directives.
- Added many new tests and entities to the Windows, UNIX, Linux, Solaris, and Mac OS component schemas.
- Corrected inconsistencies across item, object, and state entity names, types, and multiplicity.



# **Refactored Datatype Constraints**





#### Datatype restrictions are now primarily enforced with XML Schema.

- Removed thousands of Schematron rules.
- Simplified document validation.
- Improved schema readability and maintenance.
- Leading to higher quality OVAL Content.

### What changed?

- Added a xsd:fixed attribute to most entity declarations

<xsd:attribute name="datatype" type="oval:SimpleDatatypeEnumeration" use="required" fixed="binary</pre>



# **Filters on Objects**

# omeland Security Systems Engineering and Development Institute

#### The set of OVAL Items that match an OVAL Object can be filtered by any relevant property of the OVAL Item.

- Huge savings of processing time and memory usage.
- Greatly reduces the size of an OVAL Results document and helps to limit the results to only the important information.

### What Changed?

- Added an optional filter element to all OVAL Objects.

<xsd:element ref="oval-def:filter" minOccurs="0" maxOccurs="unbounded"/>

Leverages the existing filter concept.

Data collectors need to apply each filter to determine if an Item matches.

### Example: World writable files are not permitted

- Before filters on Objects Data collection on a test system resulted in OVAL Items for 148745 files.
- With filters on Objects Data collection on a test system resulted in OVAL Items for 1254 files.



# **OVAL Results Directives**



#### Allows for tailoring of OVAL Results to include only the relevant information.

- No need to include source OVAL Definitions.
- Control OVAL Results by type of OVAL Definition and result value.
- Defined format for specifying the directives to be used during evaluation

#### What Changed?

- Added an attribute to explicitly indicate whether the source OVAL Definitions document should be included in the OVAL Results or not.
- Added optional directives by definition class.
- Added a new standalone directives document.

#### Example:

- 2,293KB Full OVAL Results for FDCC on Windows XP
- 1,110KB Tailored OVAL Results for FDCC on Windows XP
  - Excludes source OVAL Definitions
  - Minimal details for true compliance results and inventory results
  - Full details for compliance failures







The central meeting place for the community to discuss, analyze, store, and disseminate OVAL Definitions.

- Active community contributing OVAL Definitions for the latest vulnerabilities.
- Coverage for a diverse set of applications and operating systems
  - Microsoft, Debian, Mozilla, Solaris, Adobe, Apple, and more...
- **10,000 Definition Milestone September 16, 2010**



# **OVAL Adoption**

Total Participants: Organizations: 17 Products & Services: 25



- Provides a channel to both educate organizations about OVAL and receive constructive technical feedback to evolve the standard.
  - Best practice usage guidance
  - Vendor formal self-assertions
  - Provides MITRE deeper insights into how OVAL is or could be utilized

## Defines requirements for how to use OVAL.

- Authoring Tool
- Definition Evaluator
- Definition Repository
- Result Consumer
- System Characteristics Producer





# **Get Involved!**

#### Come to the OVAL Workshop

- Explore the need for a major revision and other future considerations for the OVAL Language.
- Wednesday from 2:15pm 3:00pm

### Join the OVAL mailing lists

- OVAL-Announce General news and announcements about OVAL
- OVAL Developer's Forum Public forum for discussing the OVAL Language, addressing OVAL implementation issues, and for assisting other developers with OVAL.
- OVAL Repository Forum Public forum for discussing OVAL Repository content.

https://oval.mitre.org/community/registration.html

### Participate in the OVAL Adoption Program

- Help shape the effort

https://oval.mitre.org/adoption/



