


Yearend Zirconium Powder Metal Price (Dollars per kilogram)



Significant events affecting zirconium prices

1957-62 Improved production methods and increased scale of operations and capacity led to declining prices1977-78 Number of producers reduced to one; inflation, and lack of competition; demand increasing for high-purity specialty

powders and metal

Zirconium metal is sold in three basic forms-powder, sponge, and crystal bar. Martin H. Klaproth discovered the element in Germany in 1789 by analyzing zircon (Weeks and Leicester, 1968). Production of the first impure zirconium metal was by Jöns Jakob Berzelius in 1824 (Berzelius, 1825). Commercial quantities of the ductile metal were not produced until 100 years later when Anton Eduard van Arkel and Jan Hedrik de Boer discovered the iodide, or crystal bar, process (van Arkel and de Boer, 1925). Powdered zirconium metal was available on domestic markets as early as 1930, when it was used primarily for its pyrophoric and alloying properties. Principal uses were for ammunition primers, vacuum-tube getters, flash powder used in photography, and corrosion-resistant steel alloys (Kalish, 1953). An economic process to produce zirconium metal sponge (Kroll, or magnesium-reduction, process) was developed in the mid-1940's and became commercially available in the early 1950's (Kroll, 1937; Kroll, Schlechten, and Yerkes, 1946; Kroll, Schlechten, and others, 1947; Kroll, Anderson, and others, 1948). Zirconium sponge is used in the production of zirconium metal and alloys, especially for use in nuclear fuel cladding, corrosion resistant piping in chemical processing plants, and heat exchangers. Crystal bar, which is a very high purity form of zirconium metal that is used mostly in research and special applications, is not covered in this report.

Zirconium Sponge

In January 1945, the U.S. Bureau of Mines (USBM) began research to develop a commercial process for making zirconium sponge metal (Etherington, Dalzell, and Lillie, 1955). By 1947, the USBM was operating a 27-kilogram (60-pound)-per-week pilot plant in Albany, OR, using the Kroll process. In response to the U.S. Navy's interest in zirconium for possible use in nuclear powered submarines, capacity at the pilot plant was expanded in 1949 (11,800 kilograms), 1950, and twice in 1951 (Shelton and others, 1956). By 1951, USBM capacity had reached about 136,000 kilograms (300,000 pounds) per year. That same year, commercial price quotations for zirconium sponge began at \$22 per kilogram (\$10 per pound). In 1952, the Atomic Energy Commission (AEC) contracted with Carborundum Metals Co., Akron, NY, to supply the metal for 5 years. By 1955, the Carborundum plant was producing more sponge than was needed for the U.S. Navy's nuclear submarine program. At this time, the USBM's zirconium plant was converted to a metallurgical research facility. From 1959 to

1977, the price of zirconium sponge remained fairly stable, averaging from about \$14 to \$17 per kilogram (\$31-\$37 per pound). The decline was also attributed to the slowing of the nuclear submarine program and the use of substitute materials for commercial powerplants. Beginning in 1978, prices for zirconium sponge increased, following the pattern of zirconium powder. The substantial price increase has been attributed primarily to the U.S. economy because lagging U.S. economic activity and double-digit inflation increased operating costs throughout the industry. The twofold price increase for zirconium sponge may have been associated with the 50% reduction in capacity by the sole domestic producer, the cost of implementing process environmental controls to regulate naturally occurring radioactive materials, and the continued demand for replacement fuel cladding and structural repairs at nuclear powerplants (Templeton, 1993).

In the 1980's and 1990's, the use of zirconium sponge in military and commercial nuclear powerplants, heat exchangers, and specialty chemical piping for corrosive environments eventually overshadowed the use of the metal in powder and crystal bar applications (Hedrick, 1989). With no new domestic construction of nuclear powerplants, demand for zirconium metal is expected to remain stable.

Zirconium Powder

In 1932, the price quoted for powdered metal of 98% purity was \$13.23 per kilogram (\$6 per pound) or less, depending on the quantity. The price remained stable throughout the next two decades, and the uses of the powder expanded to include applications in the ceramic, glass, and steel industries. The price for powdered zirconium declined to a record low of \$8.82 per kilogram (\$4 per pound) by 1957 as the Kroll process was commercialized and the demand and scale of operations increased. Increases in production and demand for zirconium sponge in the 1950's also probably contributed to the decline in the price of powder during this period. Beginning in 1977, prices for zirconium metal were tied to many factors, including the U.S. economy, as lagging U.S. economic activity and double-digit inflation increased operating costs throughout the industry. Increased energy costs were also a factor for the substantial price increases for zirconium powder and sponge. During the late 1970's, the number of zirconium powder producers declined to one for a short time, and requirements for high-grade powder started to increase. These events, including the development of the hydrogen embrittlement technique (hydride-dehydride

process) to facilitate the conversion of sponge to powder and improved demand for replacement fuel cladding and structural repairs at nuclear powerplants, contributed to the increasing prices during this period.

Prices for zirconium powder stabilized during the 1980's and 1990's as market growth decreased and demand leveled off.

References Cited

- Berzelius, J.J., 1825, Zirconium reducirt aus flusfspathfaurem Zirconkali, und einige Eigenschaften der Zirconerde [Zirconium obtained by the reduction of potassium-zirconium fluoride, and certain properties of zirconium earth (oxide)]: Leipzig, Germany, (Poggendorf), Annalen der Physik, v. 4, p. 121-156.
- Etherington, H., Dalzell, R.C., and Lillie, D.W., 1955, Zirconium and its applications to nuclear reactors, chap. 1 *of* The metallurgy of zirconium: New York, McGraw-Hill, p. 1.
- Hedrick, J.B., 1989, Zirconium and hafnium, *in* Minerals Yearbook 1988, v. I: U.S. Bureau of Mines, p. 1049-1057.
- Kalish, H.S., 1953, The preparation of zirconium powder, chap. 5 of Zirconium and zirconium alloys: Cleveland, OH, American Society for Metals, p. 5-36.

- Kroll, W.J., 1937, The formation of titanium and zirconium: Zeitschrift für Anorganishe Chemie, v. 234, p. 42.
- Kroll, W.J., Schlechten, A.W., and Yerkes, L.A., 1946, Ductile zirconium from zircon sand: Transcripts of the Electrochemistry Society, v. 89, p. 263.
- Kroll, W.J., Schlechten, A.W., Carmody, W.R., Yerkes, L.A., Holmes, H.P., and Gilbert, H.L., 1947, Recent progress in the metallurgy of malleable zirconium: Transcripts of the Electrochemistry Society, v. 92, p. 99.
- Kroll, W.J., Anderson, C.T., Holmes, H.P., Yerkes, L.A., and Gilbert, H.L., 1948, Large scale laboratory production of ductile zirconium: Transcripts of the Electrochemistry Society, v. 94, p. 1.
- Shelton, S.M., and others, 1956, Zirconium—Its production and properties: U. S. Bureau of Mines Bulletin 561, p. 1.
- Templeton, D.A., 1993, Zirconium, *in* Metal prices in the United States through 1991: U.S. Bureau of Mines, p. 197-199.
- van Arkel, A.E., and de Boer, J.H., 1925, Preparation of pure titanium, zirconium, hafnium, and thorium metal: Zeitschrift für Anorganishe und Allgemeine Chemie, v. 148, p. 345-350.
- Weeks, M.E., and Leicester, H.M., 1968, Discovery of the elements (7th ed.): Easton, PA, Journal of Chemical Education, p. 517-520.

Yearend Zirconium Sponge Metal Price

Year	Price	Year	Price	Year	Price	Year	Price
1959	13.78	1969	13.78	1979	23.15	1989	33.07
1960	14.05	1970	13.78	1980	26.46	1990	23.15
1961	13.78	1971	13.78	1981	31.97	1991	23.15
1962	13.50	1972	13.78	1982	31.97	1992	23.15
1963	16.53	1973	13.78	1983	31.97	1993	23.15
1964	16.53	1974	13.78	1984	31.97	1994	23.15
1965	16.53	1975	13.78	1985	31.97	1995	23.15
1966	16.53	1976	13.78	1986	31.97	1996	23.15
1967	16.53	1977	15.98	1987	31.97	1997	23.15
1968	13.23	1978	26.46	1988	33.07	1998	23.15

(Dollars per kilogram¹)

¹ Prices are an average of a range and converted from dollars per pound.

Sources: American Metal Market (1959-62, 1969-98), Engineering & Mining Journal (1963-67), and Wah Chang Albany Corp., Albany, OR (1968).

Yearend Zirconium Powder Metal Price (Dollars per kilogram¹)

Price Price Year Price Year Year Price Year 1959 8.82 1969 27.56 1979 187.39 1989 242.51 1960 8.82 1970 27.56 1980 220.46 1990 248.02 27.56 1981 206.68 248.02 1961 8.82 1971 1991 1962 22.05 1972 22.05 1982 206.68 1992 248.02 248.02 1963 22.05 1973 22.05 1983 206.68 1993 22.05 1974 35.27 1964 1984 248.02 1994 248.02 1965 22.05 1975 35.27 1985 248.02 1995 248.02 1966 22.05 1976 35.27 1986 248.02 1996 248.02 248.02 1967 22.05 1977 187.39 1987 231.49 1997 1968 22.05 1978 187.39 1988 242.51 1998 248.02

¹ Prices are an average of a range and converted from dollars per pound.

Source: American Metal Market.