

Section 508 Checklist for §1194.24 Video and multimedia products.

For more information on the Standard refer to the United States Access Board description at the following URL: http://www.access-board.gov/sec508/guide/1194.24.htm.

ID	1194.24 Standard Criteria & Checklist Questions	Evaluation
(a)	All analog television displays 13 inches and larger, and computer equipment that includes analog television receiver or display circuitry, shall be equipped with caption decoder circuitry which appropriately receives, decodes, and displays closed captions from broadcast, cable, videotape, and DVD signals. As soon as practicable, but not later than July 1, 2002, widescreen digital television (DTV) displays measuring at least 7.8 inches vertically, DTV sets with conventional displays measuring at least 13 inches vertically, and stand-alone DTV tuners, whether or not they are marketed with display screens, and computer equipment that includes DTV receiver or display circuitry, shall be equipped with caption decoder circuitry which appropriately receives, decodes, and displays closed captions from broadcast, cable, videotape, and DVD signals.	
a.1	Does an analog television with displays measuring at least 7.8 inches vertically have the capability to decode and display captions from broadcast, cable, videotape, and DVD signals?	
a.2	Does a digital television measuring at least 13 inches vertically have the ability to decode and display captions from broadcast, cable, videotape, and DVD signals?	

ID	1194.24 Standard Criteria & Checklist Questions	Evaluation
a.3	Do stand-alone DTV tuners have the ability to decode and display captions from broadcast, cable, videotape, and DVD signals?	
a.4	Does computer equipment that includes DTV receiver or display circuitry have the ability to decode and display captions from broadcast, cable, videotape, and DVD signals?	
(b)	Television tuners, including tuner cards for use in computers, shall be equipped with secondary audio program playback circuitry.	
b.1	Do television tuners, including tuner cards for use in computers, have secondary audio program playback circuitry?	
(c)	All training and informational video and multimedia productions which support the agency's mission, regardless of format, that contain speech or other audio information necessary for the comprehension of the content, shall be open or closed captioned.	
c.1	Are all video and multimedia programs that contain speech or meaningful audio information open or closed captioned?	
c.2	Are captions synchronized with the speech and audio information?	
c.3	Is the current speaker indicated in the captions?	
	(Note this is a function of §1194.31 Functional Performance Criteria)*	
c.4	Is a text transcript provided for audio only presentations?	
c.5	Are captions provided for podcasts?	

ID	1194.24 Standard Criteria & Checklist Questions	Evaluation
(d)	All training and informational video and multimedia productions which support the agency's mission, regardless of format, that contain visual information necessary for the comprehension of the content, shall be audio described.	
d.1	Do all video and multimedia programs have video descriptions for meaningful visual information?	
d.2	Is a text transcript provided for video only presentations?	
(e)	Display or presentation of alternate text presentation or audio descriptions shall be user-selectable unless permanent.	
e.1	Can captioning be turned on or off by the viewer?	
e.2	Can video descriptions be turned on or off by the viewer?	

*§1194.31 Functional Performance Criteria

- (a) At least one mode of operation and information retrieval that does not require user vision shall be provided, or support for assistive technology used by people who are blind or visually impaired shall be provided.
- (b) At least one mode of operation and information retrieval that does not require visual acuity greater than 20/70 shall be provided in audio and enlarged print output working together or independently, or support for assistive technology used by people who are visually impaired shall be provided.
- (c) At least one mode of operation and information retrieval that does not require user hearing shall be provided, or support for assistive technology used by people who are deaf or hard of hearing shall be provided.
- (d) Where audio information is important for the use of a product, at least one mode of operation and information retrieval shall be provided in an enhanced auditory fashion, or support for assistive hearing devices shall be provided.
- (e) At least one mode of operation and information retrieval that does not require user speech shall be provided, or support for assistive technology used by people with disabilities shall be provided.
- (f) At least one mode of operation and information retrieval that does not require fine motor control or simultaneous actions and that is operable with limited reach and strength shall be provided.

VA Section 508 Program Office (C10A) 810 Vermont Ave. N.W Washington, DC 20240 Section508@va.gov (202) 273-6543 http://www.va.gov/accessible/