



Melamine: The cause of the Pet Food and Infant Formula Recalls

Renate Reimschuessel VMD PhD Center for Veterinary Medicine, FDA


MANY OTHERS CONTRIBUTED TO THE WORK I AM PRESENTING TODAY (within FDA and outside the Agency in academia and industry)

Renate Reimschuessel VMD, PhD




Practicing Veterinarian

Aquatic Diagnostic Pathology




Kidney Research




Center for Veterinary Medicine



Triazines - Melamine





3 N's






- Menu Foods announced recall
- 60 million containers, "cuts and gravy" style food;100 brands
- Company had received complaints, animals in kidney failure

Contaminated Pet Food/Animal Feed Incident – 2007 Sequence of Events

3/19/07 4/11/07 4/12/07 4/13/07 4/18/07



Slide courtesy of Tracy Forfa

Vet Pathologists Reported: "Unusual Crystals"


 Pathologists saw crystals in kidney but

not enough to cause kidney failure


Pathology photos sent to FDA

Collaborations with American Veterinary Medical Association American Association of Veterinary Laboratory Diagnosticians were key components to solving the mystery

Crystal Morphology



Michigan State University- Apr 3, 2007



Needle like crystals arranged in a radial sphere


These crystals looked familiar to me




Received April 3, 2007

Human Gout – Uric acid crystals






Fiechtner et al. JAMA 1981 245:1533-6



Uric acid crystals dissolve in Formaldehyde, the routine fixative

Uric acid nephropathy



Crystals obstruct tubules – vascular compromise

Locations vary depending on species

Massive literature search on melamine

2 year rat melamine cancer study

Bladder stones: Melamine:Uric acid – 1:1

Microcrystals in renal pelvis

Ogasawara, et al (1995) Urinary bladder carcinogenesis induced by melamine in F344 male rats: Correlation between carcinogenicity and urolith formation. *Carcinogenesis*, 16, 2773–2777.



Hypothesis



Could a combination of melamine with uric acid or cyanuric acid be toxic?

Is the pathogenesis similar to Acute uric acid nephropathy?




Submitted April 6, 2007



April 20, 2007 – CYANURIC ACID


Another Triazine - high nitrogen compound was found in pet food



Test the Hypothesis Wet mounts



Received April 13, 2007



Response to Formalin

60 hours later no crystals

Kidney unfixed Friday PM




Formalin fixed Monday AM

Dirt on slide


Same field – photo taken unfixed, then flooded with formalin, left on microscope over weekend. Crystals not visible on Monday (same field)

Cat crystals consistent with Melamine:Cyanurate spectrum





FDA Forensic Chemistry Center

Fourier Transform Infrared Spectroscopy



Why does the combination cause crystals?





wikipedia

FDA studies 2007 - 2008

 Because livestock feeds had also been contaminated FDA developed methods to detect melamine in feeds and animal tissues

Conducted Residue depletion studies



Sept 11, 2008 News - Melamine In Infant Formula in China

- Melamine in formula as high as 5000 ppm (Sanlu)
- Primary contaminant MELAMINE –pure (very very little cya)



What was happening?

 Melamine was being added to watered down milk by dairy farmers

(arrests with melamine in possession)

• Melamine was being added to watered down milk by producers/distributers.

(arrests with melamine in possession)









Sept 11, 2008 News - Melamine In Formula

- Children on formula a long time
- Bloody urine
- Sandy urine
- Stones urinary obstruction
- Renal Failure (Obstruction)
- Formula contained **MELAMINE**





300,000 infants diagnosed

8 mo female 0.15 cm² sand-like calculus




Sun et al 2010 Eur J. Pediatr

10 mo male 0.6-0.4 cm² stone-like calculus



Sun et al 2010 Eur J. Pediatr



Wet et al. Journal of Urology

Grases F et al. Urology. 2009 Melamine Urinary Bladder Stone. 11 mo infant girl born Nov 2007 STONES


Melamine-Uric Acid

0.7 x 1.2 cm stone

THE

CRYSTALS Melamine-Cyanurate

VS



MELAMINE EVENTS

2007 – Pet food

Dogs and Cats

SCRAP- Melamine plus Cyanuric acid

Kidney Failure-Crystals Death

100s - 1000s

2008 – Infant Formula

Babies

PURE Melamine (no Cyanuric acid)

Kidney Stones No signs, Pain, Death (6)

300,000

Many milk products were affected worldwide

DAILY=NEWS | Money

HOME | AUTOS | REAL ESTATE | JOBS | CLASSIFIEDS | IN PRINT | BUY TICKETS | CONTESTS

MORTGAGE HOME EQUITY RETIREMENT CHECKING & SAVINGS CREDIT CARDS PER

Candy with melamine, chemical in Chinese milk, found in Conn.

THE ASSOCIATED PRESS

Updated Wednesday, October 1st 2008, 4:48 PM

HARTFORD, Conn. — An industrial chemical blamed for sickening thousands of infants in China has been found in candy in four Connecticut stores this week, a state official said Wednesday.

Connecticut Consumer Protection Commissioner Jerry Farrell Jr. said Wednesday that tests on White Rabbit Creamy Candy found melamine in two New Haven stores. a West Hartford market and a Haven store days after the







http://www.chicagotribune.com/news/nationworld/sns-ap-as-asia-tainted-milk,0,781111.story

Zoo animals with kidney stones



http://www.msnbc.msn.com/id/26886627/



http://gorilladoctors.wildlifedirect.org/2008/06/29/ndakasis-fight-to-survive-revisited-part-2-one-year-ago/



Zoo animals also victims of tainted milk crisis

All were fed milk powder made by company at the heart of China scandal

msnbc.com news services updated 11:34 a.m. ET, Thurs., Sept. 25, 2008



An officer prepares to destroy unqualified milk powder which was confiscated, in Shanghai November 14, 2008. REUTERS/Stringer

China Milk Recall 2008 Unearths Another 170 Tons of Melamine Milk Powder in 2010



Published February 10, 2010 by: Sylvia Cochran View Profile | Follow | Add to Favorites

Adjust font-size: + -

More: Chinese Product Person China Recair Melamine Google Chin

Milk Problems in China Packed for Resale

In 2008, melamine tainted powdered milk and infant formula led to the de of another 860 babies and two executions of guilty parties. Now more po



Feb 2010





9 July 2010 Last updated at 05:20 ET

July 2010 64 Tons

China dairy products found tainted with melamine

Chinese food safety officials have seized 64 tonnes of raw dairy materials contaminated with the toxic industrial chemical melamine.

The Chinese state news agency, Xinhua, reported that the quality watchdog in Qinghai province took the material from a dairy plant there.

Test samples showed the milk powder carried up to 500 times the maximum allowed level of the chemical.



Six babies died and 300,000 were ill

Importance of truly getting rid of contaminated products



http://en.wikipedia.org/wiki/Image:Melamine_biscuits.jpg



Questions? Further Info.

- Reimschuessel et al. Evaluation of the renal effects of experimental feeding of melamine and cyanuric acid to fish and pigs. Am. J. Vet. Res. 69:1217-1228. 2008.
- Andersen et al. Determination and confirmation of melamine residues in catfish, trout, tilapia, salmon, and shrimp by LC-MS-MS. J Agri Food Chemistry. 56:4340–4347. 2008.
- Karbiwnyk et al. **Determination of cyanuric acid residues in catfish, trout, tilapia**, salmon and shrimp by liquid chromatography-tandem mass spectrometry. Analytica Chimica Acta 637: 101–111. 2008.
- Dobson et al. Identification and characterization of toxicity of contaminants in pet food leading to an outbreak of renal toxicity in cats and dogs. Toxicological Sciences 106:251-262, 2008.
- Heller et al. Simultaneous determination and confirmation of melamine and cyanuric acid in animal feed. Rapid Comm in Mass Spectrometry 22::3624-32. 2008.
- Reimschuessel et al. Residue depletion of melamine and cyanuric acid in catfish rainbow trout following oral administration Journal of Veterinary Pharmacology and and Therapeutics. 2009 33, 172–182, 2010.
- Reimschuessel et al. Renal crystal formation after combined or sequential oral administration of melamine and cyanuric acid. Food and Chemical Toxicology, 48:2898-2906. 2010
- Karbiwnyk et al. Bioaccumulation of cyanuric acid in edible tissues of shrimp following experimental feeding. Food Additives & Contaminants: Part A pub on line at: http://dx.doi.org/10.1080/19440049.2010.517221 2010

Jacob et al. Dose-response assessment of nephrotoxicity from a seven-day combined-exposure to melamine and cyanuric acid in F344 rats. Toxicological Sciences 2010 IN PRESS

Questions?

If you would like to send a question to the CVM Home Page write us directly at: AskCVM@fda.hhs.gov