AIRPORT DIAGRAMS HOT SPOTS

An "Airport surface hot spot" is a location on an aerodrome movement area with a history or potential risk of collision or runway incursion, and where heightened attention by pilots/drivers is necessary.

A "hot spot" is a runway safety related problem area on an airport that presents increased risk during surface operations. Typically it is a complex or confusing taxiway/taxiway or taxiway/runway intersection. The area of increased risk has either a history of or potential for runway incursions or surface incidents, due to a variety of causes, such as but not limited to: airport layout, traffic flow, airport marking, signage and lighting, situational awareness, and training. Hot spots are depicted on airport diagrams as open circles or polygons designated as "HS 1", "HS 2", etc. and tabulated in the list below with a brief description of each hot spot. Hot spots will remain charted on airport diagrams until such time the increased risk has been reduced or eliminated.

CITY/AIRPORT	HOT SPOT	DESCRIPTION IT
DANBURY	OOMMEOTIOO	'1
DANBURY MUNI (DXR)	HS 1	Maintain vigilance confusing twy configuration.
DANBORT MONI (DXK)	HS 2	Area not visible from the twr.
	нs 2 НS 3	
		Active ramp adjacent to twy.
	HS 4	Hold position marking on Twy C for Rwy 26 is further from the rwy than the std location. It will appear before you expect it.
GROTON (NEW LONDON)		
GROTON-NEW LONDON (GON)	HS 1	When Idg Rwy 15–33 and exit on Twy C, you immediately enter the parallel Twy B.
	HS 2	When Idg Rwy 15–33 and exit on Twy J, you immediately enter the parallel Twy B.
HARTFORD		
HARTFORD-BRAINARD (HFD)	HS 1	Helipad is in close proximity to the intersection of Twy A and Twy H.
WINDSOR LOCKS		
BRADLEY INTL (BDL)	HS 1	Twy C and Twy E Complex intersection in close proximity to Rwy 01–19.
	HS 2	Acft on Twy S missing Twy C may enter Rwy 24.
	HS 3	Acft on Twy J missing Twy S may enter Rwy 33.
	DISTRICT OF COL	IIMBIA
WASHINGTON	210111101 01 002	
RONALD REAGAN		
WASHINGTON	HS 1	Twy M and Twy J intersection in close proximity of
NATIONAL (DCA)		the rwy.
	HS 2	Twy N, Twy K, Twy L, and Twy J complex intersection in close proximity of the rwy.
	MARYLAND	in close proximity of the rmy.
BALTIMORE		
BALTIMORE/WASHINGTON INTL		
THURGOOD MARSHALL (BWI)	HS 1	Uncontrolled stop bar. No crossing allowed.
mendoob withering (bwi)	HS 2	Caution Rwy 10—28 in close proximity to Twy P1
	HS 3	intersection. Twy E and Twy P intersect in close proximity to
	н5 3	
EASTON		Rwy 10-28.
EASTON/NEWNAM FIELD (ESN)	HS 1	Acft taxiing southbound on Twy A to Rwy 33 inadvertently miss the turn onto Twy B and enter Rwy 33 without a clearance. Twy A and Twy B
		intersection in close proximity to the rwy.
FREDERICK		
FREDERICK MUNI (FDK)	HS 1	Eastbound tfc on Twy B and North and Southbound tfc on Twy A must remain alert for the tfc exiting Rwy 05–23 at Twy B.
	HS 2	Northbound tfc on Twy A must remain alert as to not miss Twy D when taxiing to Rwy 30 and Southeast bound tfc on Twy D as not to miss Twy A when taxiing to Rwy 23.
	HS 3	Northbound tfc on Twy A need to be alert as not to miss Twy D and inadvertently taxi onto Rwy 30.
	HS 4	Southeast bound tfc on Twy D need to be alert as not to miss Twy A and inadvertently taxi onto Rwy 23.

AIRPORT DIAGRAMS

MASSACHUSETTS

BEDFORD		
LAURENCE G. HANSCOM FIELD (BED)	HS 1	Pilots become confused with the wide expanse of pavement and convergence of numerous twys.
BEVERLY BEVERLY MUNI (BVY)	HS 1	Prepare to hold short of Rwy 16–34 immediately after exiting the East Ramp.
	HS 2	Acft taxiing SE on Twy E fail to turn on Twy H and enter Rwy 27 without authorization.
BOSTON GENERAL EDWARD LAWRENCE		one in wy 27 wallout duthon zacion.
LOGAN INTL (BOS)	HS 1	Watch for Rwy ''04L APCH'' when taxiing on Twy B to Rwy 04R and Rwy 09.
	HS 2	Maintain vigilance when taxiing outbound on Twy C to Rwy 33L when Rwy 09–27 is active.
	HS 3	Maintain vigilance when taxiing on Twy E and Twy K at Rwy 09 when Rwy 04L–22R is active.
	HS 4	Maintain vigilance when taxiing inbound on Twy E from Rwy 27 when Rwy 22L is active.
LAWDENOF	HS 5	Maintain vigilance when taxiing outbound on Twy C and Twy D to Rwy 27 when Rwy 33L is active.
LAWRENCE LAWRENCE MUNI (LWM)	HS 1	Maintain vigilance approaching Rwy 05–23 hold lines.
	HS 2	Maintain vigilance on Twy A; hold line to Rwy 14–32 appears quickly.
	HS 3	Maintain vigilance approaching Rwy 05–23 hold lines.
NANTUCKET		
NANTUCKET MEMORIAL (ACK)	HS 1	Maintain vigilance while taxiing. High tfc area.
	HS 2	Maintain vigilance while taxiing, High tfc area.
	HS 3	Maintain vigilance while taxiing. High tfc area.
NORWOOD		
NORWOOD MEMORIAL (OWD)	HS 1	Hold position marking on Twy A for Rwy 35 is further from the rwy than the standard location. It will appear before you expect it.
WORCESTER WORCESTER RGNL (ORH)	HS 1	Maintain vigilance on Twy D and Twy F, converging twys in close proximity to Rwy 15–33.
	NEW JERSEY	
CALDWELL		
ESSEX CO (CDW)	HS 1	Pilots taxiing to Rwy 28 northbound on Twy P should exercise caution at intersection of Twy P and Twy N due to close proximity to Rwy 28.
NEWARK		
NEWARK LIBERTY INTL (EWR)	HS 1	Eastbound tfc on Twy Z approaching Rwy 04R-22L must remain aware so as to not mistake Twy ZB for Twy Z.
	HS 2	Northbound tfc on Twy P turning left onto Twy Z must remain aware of the close proximity of Rwy 04L–22R.
	HS 3	Southbound tfc on Twy S from General Aviation parking must remain aware so as not to mistake Rwy 11–29 for Twy Z.
TETERBORO TETERBORO (TEB)	HS 1	Tfc taxiing on Twy B between Rwy 01–19 and Rwy 06–24 should maintain vigilance due to close proximity to both rwys. Distance between rwy hold
	HS 2	short lines limited to 16 ft. Maintain vigilance on Twy L at Rwy 06–24. High tfc area.
	HS 3	Maintain vigilance on Twy G at Rwy 06–24. High tfc area.

that Hold Line as applying to a single rwy only. The Hold Line applies to Rwy 27 and Rwy 30.

RHODE ISLAND

PROMPENOE	RHUDE ISLA	INU
PROVIDENCE THEODORE FRANCIS GREEN STATE (PVD)	HS 1	Maintain vigilance at Twy M and Twy C due to vast amount of pavement and multiple rwy hold lines in close proximity of rwy.
	HS 2	Intersection of Rwy 16–34, Twy V, Twy N, and Twy T – complex intersection with a convergence of numerous twys with Rwy 16–34.
	HS 3	Twy M at the intersection of Twy B use extra vigilance due to vast amount of pavement and multiple hold lines in close proximity of rwy.
BUB. WOTON	VERMONT	T in the second of the second
BURLINGTON BURLINGTON INTL (BTV)	HS 1	Wrong rwy departure risk. Pilots instructed to depart Rwy 19 mistakenly depart wrong rwy–Rwy 15.
	VIRGINIA	
LYNCHBURG LYNCHBURG RGNL/PRESTON GLENN FLD (LYH)	HS 1	Acft taxiing northeast on Twy C may miss the left turn onto Twy B and inadvertently enter Rwy 04–22 without authorization.
RICHMOND RICHMOND INTL (RIC)	110.4	West and describe side. Piloto industrial to
RICHIVIOND INTE (RIC)	HS 1	Wrong rwy departure risk. Pilots instructed to depart Rwy 20 or Rwy 16 mistakenly depart the adjacent rwy due to close proximity of thlds. Acft ldg Rwy 34 unable to exit Twy C expect to cross the departure end of Rwy 02 to clear the rwy.
ROANOKE ROANOKE RGNL/WOODRUM FIELD	HS 1	
(ROA)	H3 I	Northbound tfc on Twy A for Rwy 24 sometimes fail to make the turn at Twy G and enter Rwy 06–24 without a clearance.
HUNTINGTON	WEST VIRGI	NIA
HUNTINGTON		

UNTINGTON		
TRI-STATE/MILTON J. FERGUSON	HS 1	Maintain vigilance, Twy A does not lead to the end
FIELD (HTS)		of Rwy 12. Full length departures rqr rwy crossing.
	HS 2	Area not visible from the twr.
	HS 3	Maintain vigilance, Twy B relocated 200' southeast.
		Former twy is partially blocked and used as a
		vehicle access road.