Cost-to-Charge Ratio Files:

2009 Kids' Inpatient Database (KID) User Guide

1. Purpose

The purpose of this data file is to provide Healthcare Cost and Utilization Project (HCUP) data users with ratios that will allow the conversion of charge data to cost estimates. The file is constructed using all-payer, inpatient cost and charge information from the detailed reports by hospitals to the Centers for Medicare and Medicaid Services (CMS). It provides an estimate of all-payer inpatient cost-to-charge (CCR) for nearly every HCUP KID hospital in 2009. Where permitted by HCUP State Partners, the data set provides a hospital-specific CCR and a weighted group average. The KID is an all-payer inpatient care database for children ages 20 and younger and contains data drawn from 44 State Inpatient Databases.

The file can be linked to the 2009 file of KID discharges using the HOSPID variable. The HOSPID variable on the CCR CSV text file is enclosed in quotations in order to preserve leading zeros in Excel. As a result, some software applications may interpret HOSPID as a character variable which in turn would not match the numeric version of HOSPID on the KID. This data element should be loaded as numeric or converted to numeric prior to merging with the KID.

The cost of inpatient care for a discharge can then be estimated by multiplying TOTCHG (from the discharge record) by either the hospital-specific cost-to-charge ratio (APICC), or the group weighted average CCR ratio (GAPICC). The KID CCR file differs from other CCR files offered by AHRQ in that long-term care cost centers, such as skilled nursing facilities, are excluded from the calculation of APICC.

2. File Format

The data set contains one record for each of 3956 of 4121 total HCUP KID hospitals in 2009 (unduplicated HOSPIDs). All HCUP hospitals in the file are also in the American Hospital Association (AHA) 2009 survey.

Analysts might want to use the hospital-specific cost-to-charge when available (3628 cases approximating 92%) and the weighted group average when the hospital-specific CCR is not available (328 cases). Alternatively, one might use the group average in all cases.

06/27/11 -1-

To obtain national cost estimates for a set of cases, users will need to re-weight all discharges to account for cases where cost estimates are missing. The original case weight (DISCWT) should be multiplied by the following: Total weight of original cases divided by total weights, after excluding cases with missing cost. By performing these calculations, the weights for remaining cases are increased.

3. Internal Validation Studies

A regression analysis of the all-payer inpatient CCR was performed this year and in earlier years. This analysis used all clean HCUP and non-HCUP records with both AHA and CMS data. (Clean records are defined as having complete CMS schedules and worksheets, containing key variables within an acceptable range.) This was a weighted OLS regression using acute medical-surgical beds as the weighting variable, with separate state constant terms. Factors leading to significant differences in the CCR were: investor-ownership, rural location, large size (more than 300 beds), and a high ratio of interns and residents per bed (top 5%). Several of the state constant terms were also significant. The results tended to validate the "peer-grouping" method used here to create weighted group averages for each HCUP record.

In 2001 a study was performed for two states where different methods of calculating cost by DRG were compared. Hospital-wide CCRs as provided here, although not as accurate as departmental CCRs, are more accurate than gross charges in estimating relative cost by DRG. In more recent years, studies involving a dozen states with detailed charges have been done. These studies produced more accurate CCRs because they use departmental CCRs as opposed to hospital-wide CCRs. Users interested in quantifying potential biases due to use of the hospital-wide CCRs should contact HCUP user support (hcup@ahrq.gov). A methods report with correction factors by CCS and APR-DRG for 2006 data can be found at: http://hcup-us.ahrq.gov/reports/2008_04.pdf. More recent correction factors by MS-DRG and CCS using 2009 data are available.

Weighted Group Average—GAPICC

The group average CCR (GAPICC) is a weighted average for the hospitals in the group (defined by state, urban/rural, investor-owned/other, and bedsize), using the proportion of group beds as the weight for each hospital. For the KID, only hospitals serving children are used in the peer group weighted averages. The groups are defined based on all clean HCUP and non-HCUP records for community hospitals with matching AHA 2009 Annual Survey data and CMS accounting database records as of March 31, 2011. Both operating costs and capital-related costs are included.

06/27/11 -2-

In cases where a peer group average is not possible, the "group" average is the statewide average.

5. Hospital Type for Grouping—HTYPE

Although HTYPE is not provided on the KID Cost-to-Charge file, it is helpful to know how this variable is defined to create peer groups within each state using all hospitals – not only those selected for the KID. Some researchers will find the information below useful with respect to replicability, and reviewers for journal articles might find this more detailed description especially valuable.

The following are values for the HTYPE variable:

1= investor-owned, under 100 beds

2= investor-owned, 100 or more beds

3= not-for-profit, rural, under 100 beds

4= not-for-profit, rural, 100 or more beds

5= not-for-profit, urban, under 100 beds

6= not-for-profit, urban, 100-299 beds

7= not-for-profit, urban, 300 or more beds

Unfortunately, data about the ratio of interns and residents per bed are not available on the AHA survey, so a high value of this indicator of teaching status could not be used for grouping. *Urban* is defined as being part of a Metropolitan Statistical Area (MSA); *beds* are the total hospital beds set up (2009 AHA survey). State and local hospitals are included in the not-for-profit categories.

Area Wage Index—WI_X

The Area Wage Index is an index computed by CMS to measure the relative hospital wage level in a geographic area compared to the national average hospital wage level. It is provided on the file to allow researchers to analyze cost differences geographically or to control for price factors beyond the hospital's control. Hospital cost variation has a .8 elasticity with the area wage index in some AHRQ published studies, meaning that variation in the hospital cost is roughly proportional to the variation in overall hospital costs. Multivariate studies should not assume strict proportionality. The index is computed for each urban Core-Based Statistical Area (CBSA). All rural areas in each state are combined for a single wage index. This information is available for download from CMS. For the HCUP KID hospitals in 2009, all hospitals were matched to an area wage index using CMS files , the AHA survey, and the Area Resource File in cases where the AHA survey was incomplete.

7. Geographic Adjustment Factor (GAF)

06/27/11 -3-

The Capital cost adjustment index for Core Based Statistical Areas is included on the file. It is used in calculating the Medicare reimbursement payments for capital costs. This data element may prove useful in regression calculations. However, for a number of states contributing *hospital* data in the KID, release of the GAF is not permitted.

8. Variable List

There are seven variables in the KID Cost-to-Charge data file in 2009. The following list summarizes the variables (and their respective labels) included in this file.

HOSPID	HCUP hospital identification number
WI_X	Wage Index, source CMS, edited
Z013	State postal code
APICC	All-payer inpatient CCR, hosp-specific
GAPICC	Group avg. all-payer inpatient CCR
YEAR	Year for linking to HCUP records
GAF	Capital cost adjustment index for Core Based
	Statistical Areas

06/27/11 -4-