



STATISTICAL BRIEF #146

January 2013

Costs for Hospital Stays in the United States, 2010

Anne Pfuntner, Lauren M. Wier, M.P.H., and Claudia Steiner, M.D., M.P.H.

Introduction

Inpatient hospital services account for a small share of health care utilization (7 percent) but constitute the largest share of total health care spending in the United States (29 percent in 2009). As health care costs continue to rise and the population ages, policymakers are increasingly concerned about the growing burden of hospital-based medical care expenses on the government, insurers, patients, and employers.

This Statistical Brief presents data from the Healthcare Cost and Utilization Project (HCUP) on costs of hospital stays in the United States in 2010. Both aggregate hospital costs and the average costs per hospital stay are presented, by age and primary payer. The most costly inpatient conditions are identified, and the cost difference and components of growth in hospital costs are provided for these conditions between 1997 and 2010. All differences between estimates noted in the text are statistically significant at the .001 level or better.

Findings

Hospital costs by age, 2010 In 2010, the average cost per hospital stay was \$9,700 and the aggregate cost for all hospital stays totaled \$375.9 billion. Figures 1 and 2 show the distribution of aggregate hospital costs and stays by age and the average hospital cost per stay by age, respectively.

Adults ages 45–64 and 65–84 had the highest average cost per stay (\$12,100 and \$12,300, respectively). These 2 age groups accounted for nearly two-thirds of aggregate hospital costs and about half of hospital stays. Adults age 85 and older accounted for 8 percent of aggregate costs and hospital stays, and had an average hospital cost that was similar to the overall average cost per stay. Infants (children younger than 1 year) accounted for 5

Highlights

- In 2010, the aggregate cost for all hospital stays was \$375.9 billion; the average cost per stay was \$9.700.
- Adults ages 45–64 and 65–84 accounted for nearly two-thirds of aggregate costs in 2010 and had the highest average cost per stay (\$12,100 and \$12,300, respectively).
- Medicare was responsible for nearly half of aggregate costs in 2010 and had the highest average cost per stay (\$11,600).
- When conditions were grouped by Major Diagnostic Category, circulatory conditions accounted for the largest share—nearly onefifth—of hospital costs in 2010.
- Of the 20 most expensive conditions in 2010, septicemia ranked first in aggregate costs and experienced the fastest average annual percentage change since 1997 (11.2 percent).
- Five conditions with the highest aggregate costs had approximately double the average cost per stay in 2010 (\$9,700): septicemia, complication of device, acute myocardial infarction, respiratory failure, and intracranial injury. Three conditions had well below the average cost per stay in 2010: liveborn (newborn infants), chronic obstructive pulmonary disease, and mood disorders.
- Aggregate inflation-adjusted costs for hospital stays grew 3.8 percent annually between 1997 and 2010, with 2.9 percent attributed to an increase in the intensity of services (cost per stay) and 1.0 percent attributed to growth in the population.

¹ Kashihara, D. and Carper, K. *National Health Care Expenses in the U.S. Civilian Noninstitutionalized Population, 2009.* MEPS Statistical Brief #355. January 2012. Agency for Healthcare Research and Quality, Rockville, MD. http://www.meps.ahrq.gov/mepsweb/data_files/publications/st355/stat355.pdf. (Accessed August 22, 2012).

percent of aggregate costs and 12 percent of hospitalizations. Infants also had the lowest average cost per stay (\$4,500), which was less than half the overall average cost per stay.

33% 35% Hospital costs 31% 30% ■ Hospital stays 26% 25% 25% 25% Percentage 18% 20% 15% 12% 8% 8% 10% 5% 4% 4% 5% 0% <1 1-17 18 - 4445-64 65-84 85+ Age group

Figure 1. Distribution of aggregate hospital costs and stays by age, 2010

Source: AHRQ, Center for Delivery, Organization, and Markets, Healthcare Cost and Utilization Project, Nationwide Inpatient Sample, 2010




Figure 2. Average hospital cost per stay by age, 2010

Source: AHRQ, Center for Delivery, Organization, and Markets, Healthcare Cost and Utilization Project, Nationwide Inpatient Sample, 2010

Hospital costs by expected primary payer, 2010

The distribution of aggregate hospital costs and stays by payer and the average hospital cost per stay by payer are shown in figures 3 and 4, respectively.

Medicare and Medicaid accounted for 61 percent of aggregate hospital costs in 2010. Medicare was responsible for 45 percent of all costs and 37 percent of stays. Medicare also had the highest average cost per stay (\$11,600). Medicaid accounted for 16 percent of aggregate hospital costs and 21 percent of hospital stays. The average cost per stay billed to Medicaid (\$7,500) was lower than the overall average cost per stay (\$9,700). Private insurance accounted for nearly one-third of aggregate costs and hospital stays, and the average cost per stay was similar to that for all stays.




Figure 3. Distribution of aggregate hospital costs and stays by payer, 2010

Source: AHRQ, Center for Delivery, Organization, and Markets, Healthcare Cost and Utilization Project, Nationwide Inpatient Sample, 2010




Figure 4. Average hospital cost per stay by payer, 2010

Source: AHRQ, Center for Delivery, Organization, and Markets, Healthcare Cost and Utilization Project, Nationwide Inpatient Sample, 2010

Hospital costs by diagnostic category, 2010

In 2010, 70 percent of aggregate hospital costs were attributable to 7 Major Diagnostic Categories (figure 5). Circulatory conditions accounted for the largest share—nearly one-fifth—of hospital costs. Other diagnostic categories that accounted for high shares of aggregate hospital costs included

musculoskeletal conditions (14 percent), respiratory conditions (11 percent), digestive conditions (9 percent), and nervous system conditions (8 percent). Infectious and parasitic diseases and pregnancy and childbirth each accounted for 5 percent of hospital costs.




Figure 5. Distribution of aggregate hospital costs by diagnostic category, * 2010

Total aggregate costs: \$375.9 billion

Hospital costs by diagnosis, 1997–2010

Aggregate inflation-adjusted hospital costs across all conditions increased 62 percent from \$232.3 billion in 1997 to \$375.9 billion in 2010. Table 1 shows the 20 principal diagnoses with the highest aggregate hospital costs in 2010.

Of the 20 most costly conditions, septicemia experienced the fastest average annual percentage change in aggregate hospital costs since 1997 (11.2 percent annually). Septicemia ranked ninth in aggregate costs in 1997 and ranked first in aggregate costs in 2010.

Other conditions with high aggregate cost increases (greater than 5 percent annually) were osteoarthritis; complications of devices, implants, and grafts; disc disorders and other back problems; respiratory failure; cardiac dysrhythmias; complications of surgical or medical care; and intracranial injury.

The most costly type of conditions overall involved the circulatory system, with 5 of the 20 most costly conditions—acute myocardial infarction, coronary atherosclerosis, congestive heart failure, acute cerebrovascular disease, and cardiac dysrhythmias. These 5 conditions accounted for 13 percent of aggregate hospital costs in 2010.

The cost per stay for 5 principal diagnoses was approximately double the average cost per stay in 2010 (\$9,700): septicemia (\$18,400), complication of device (\$17,600), acute myocardial infarction (\$18,200), respiratory failure (\$22,300), and intracranial injury (\$18,000). Conversely, the cost per stay for 3 principal diagnoses was substantially lower than the average cost per stay in 2010: liveborn (newborn infants) (\$3,200 per stay), chronic obstructive pulmonary disease (\$7,400 per stay), and mood disorders (\$4,800 per stay). These 3 conditions were among the highest in aggregate hospital costs in 2010 because of their high frequency of hospitalization.

^{*} Based on principal diagnosis defined by Major Diagnostic Category (MDC)
Source: AHRQ, Center for Delivery, Organization, and Markets, Healthcare Cost and Utilization Project, Nationwide Inpatient Sample, 2010

Table 1. Aggregate costs for hospital stays by principal diagnosis, 1997 and 2010

	Aggregate inflation-adjusted hospital costs in billions (2010 dollars)		Mean cost per stay, inflation-adjusted (2010 dollars)		Average annual percentage change in aggregate costs
Principal CCS diagnosis	1997	2010	1997	2010	1997-2010
All diagnoses	\$232.3	\$375.9	\$6,700	\$9,700	3.8%
Septicemia (except in labor)	\$4.3	\$17.1	\$10,400	\$18,400	11.2%
Osteoarthritis	\$5.0	\$14.7	\$11,900	\$15,100	8.7%
Liveborn	\$8.4	\$12.2	\$2,200	\$3,200	2.9%
Complication of device; implant or graft	\$5.9	\$12.0	\$11,900	\$17,600	5.6%
Acute myocardial infarction	\$9.7	\$11.0	\$13,200	\$18,200	0.9%
Spondylosis; intervertebral disc disorders; other back problems	\$3.6	\$10.9	\$6,800	\$16,400	8.9%
Coronary atherosclerosis and other heart disease Pneumonia (except that caused by	\$15.5	\$10.6	\$11,000	\$16,500	-2.9%
tuberculosis or sexually transmitted disease)	\$9.4	\$10.2	\$7,700	\$9,300	0.6%
Congestive heart failure; nonhypertensive	\$7.1	\$10.1	\$7,100	\$10,500	2.8%
Acute cerebrovascular disease	\$5.7	\$8.5	\$9,300	\$14,500	3.1%
Respiratory failure; insufficiency; arrest (adult)	\$3.5	\$8.1	\$17,600	\$22,300	6.6%
Cardiac dysrhythmias	\$3.8	\$7.3	\$6,600	\$9,500	5.2%
Complications of surgical procedures or medical care	\$3.1	\$6.5	\$8,700	\$12,500	5.9%
Chronic obstructive pulmonary disease and bronchiectasis	\$3.5	\$5.2	\$6,400	\$7,400	3.1%
Rehabilitation care; fitting of prostheses;					
and adjustment of devices	\$4.0	\$5.1	\$10,100	\$12,500	2.0%
Biliary tract disease	\$3.5	\$5.0	\$7,700	\$10,600	2.7%
Diabetes mellitus with complications	\$2.9	\$4.9	\$7,100	\$9,000	4.1%
Fracture of neck of femur (hip)	\$3.4	\$4.6	\$10,200	\$15,100	2.4%
Intracranial injury	\$2.1	\$4.4	\$13,600	\$18,000	5.8%
Mood disorders	\$3.3	\$4.3	\$5,100	\$4,800	2.0%

CCS: Clinical Classifications Software

Source: AHRQ, Center for Delivery, Organization, and Markets, Healthcare Cost and Utilization Project, Nationwide Inpatient Sample, 1997 and 2010


Cost factors accounting for change in hospital costs by diagnosis, 1997–2010 Figure 6 shows the average annual percentage change in aggregate hospital costs between 1997 and 2010 for the 20 principal diagnoses with the highest aggregate costs in 2010.

Aggregate inflation-adjusted costs for hospital stays grew 3.8 percent annually between 1997 and 2010. Across all conditions, *intensity of services* provided during the hospital stay (cost per stay) increased by an average of 2.9 percent annually, *population* grew 1.0 percent annually, and the *number of stays per population* remained stable.

The number of stays per population was the most important factor in cost growth for 5 of the 20 most costly conditions, including osteoarthritis and septicemia. Higher intensity of services accounted for a large proportion of growth in hospital costs for another 5 conditions, including spondylosis and complication of device. Both intensity of services and stays per population had similar contributions to cost growth for one condition, chronic obstructive pulmonary disease. Finally, for the remaining 9 most

costly conditions, including coronary atherosclerosis and acute myocardial infarction, cost growth in service intensity was offset by a decrease in stays per population. Overall population growth contributed a small amount to cost growth for all conditions.

Figure 6. Average annual percentage change* in inflation-adjusted aggregate hospital costs by principal diagnosis, 1997–2010



Average annual percentage change

Source: AHRQ, Center for Delivery, Organization, and Markets, Healthcare Cost and Utilization Project, Nationwide Inpatient Sample, 1997 and 2010

^{*} Bar segments depict the portion of change attributable to each of the factors listed in the key. The net average annual percentage change is noted in the axis label.

Data Source

The estimates in this Statistical Brief are based upon data from the HCUP 2010 NIS. Historical data were drawn from the 1997 NIS and the 2003 NIS. Supplemental sources included data on national population estimates from Intercensal Estimates of the Resident Population by Single Year of Age, Sex, Race, and Hispanic Origin for the United States: April 1, 2000 to July 1, 2010," Population Division, U.S. Census Bureau, Release date: September 2011. (http://www.census.gov/popest/data/intercensal/national/nat2010.html).

Supplemental sources also included data on national population estimates from "Intercensal Estimates of the United States Resident Population by Age and Sex, 1990-2000: Selected Months," Population Division, U.S. Census Bureau, Release date: August 2004. (http://www.census.gov/popest/data/intercensal/national/index.html).

Many hypothesis tests were conducted for this Statistical Brief. Thus, to decrease the number of false-positive results, we reduced the significance level to .001 for individual tests.

Definitions

Average Annual Percentage Change

Average annual percentage change is calculated using the following formula:

Average annual percentage change =
$$\left(\frac{\text{End value}}{\text{Beginning value}} \right)^{\frac{1}{\text{change in years}}} - 1 x 100$$

In this Statistical Brief, 1997 and 2010 were the base years used to calculate the average annual percentage change in aggregate hospital costs, cost per stay, population, and stays per 10,000 population. Average annual percentage change was calculated over 13 years:

Average annual percentage change =
$$\left(\left(\frac{2010 \text{ value}}{1997 \text{ value}} \right)^{\frac{1}{13}} - 1 \right) \times 100$$

Diagnoses, ICD-9-CM Clinical Classifications Software (CCS), Diagnosis-Related Groups (DRGs), and Major Diagnostic Categories (MDCs)

The *principal diagnosis* is that condition established after study to be chiefly responsible for the patient's admission to the hospital. Secondary diagnoses are concomitant conditions that coexist at the time of admission or that develop during the stay. All-listed diagnoses include the principal diagnosis plus these additional secondary conditions.

ICD-9-CM is the International Classification of Diseases, Ninth Revision, Clinical Modification, which assigns numeric codes to diagnoses. There are about 14,000 ICD-9-CM diagnosis codes.

CCS categorizes ICD-9-CM diagnoses into a manageable number of clinically meaningful categories. This "clinical grouper" makes it easier to quickly understand patterns of diagnoses. CCS categories identified as -Other" are typically not reported; these categories include miscellaneous, otherwise unclassifiable diagnoses that may be difficult to interpret as a group.

DRGs comprise a patient classification system that categorizes patients into groups that are clinically coherent and homogeneous with respect to resource use. DRGs group patients according to diagnosis, type of treatment (procedures), age, and other relevant criteria.

² HCUP Clinical Classifications Software (CCS). Healthcare Cost and Utilization Project (HCUP). U.S. Agency for Healthcare Research and Quality, Rockville, MD. Available at http://www.hcup-us.ahrq.gov/toolssoftware/ccs/ccs.jsp. Updated March 2012. (Accessed August 22, 2012).

MDCs are broad groups of DRGs that relate to an organ or a system and not to an etiology (for example, MDC 06, Diseases and Disorders of the Digestive System). Each hospital stay has one DRG and one MDC assigned to it.

Types of hospitals included in HCUP

HCUP is based on data from community hospitals, defined as short-term, non-Federal, general, and other hospitals, excluding hospital units of other institutions (e.g., prisons). HCUP data include obstetrics and gynecology, otolaryngology, orthopedic, cancer, pediatric, public, and academic medical hospitals. Excluded are long-term care, rehabilitation, psychiatric, and alcoholism and chemical dependency hospitals. However, if a patient received long-term care, rehabilitation, or treatment for psychiatric or chemical dependency conditions in a community hospital, the discharge record for that stay will be included in the NIS.

Unit of analysis

The unit of analysis is the hospital discharge (i.e., the hospital stay), not a person or patient. This means that a person who is admitted to the hospital multiple times in one year will be counted each time as a separate "discharge" from the hospital.

Costs and charges

Total hospital charges were converted to costs using HCUP Cost-to-Charge Ratios based on hospital accounting reports from the Centers for Medicare & Medicaid Services (CMS). Costs will reflect the actual expenses incurred in the production of hospital services, such as supplies and utility costs; *charges* represent the amount a hospital billed for the case. For each hospital, a hospital-wide cost-to-charge ratio is used. Hospital charges reflect the amount the hospital billed for the entire hospital stay and do not include professional (physician) fees. For the purposes of this Statistical Brief, costs are reported to the nearest hundred.

Payer

Payer is the expected primary payer for the hospital stay. To make coding uniform across all HCUP data sources, payer combines detailed categories into more general groups:

- Medicare: includes fee-for-service and managed care Medicare patients
- Medicaid: includes fee-for-service and managed care Medicaid patients. Patients covered by the State Children's Health Insurance Program (SCHIP) may be included here. Because most State data do not identify SCHIP patients specifically, it is not possible to present this information separately.
- Private Insurance: includes Blue Cross, commercial carriers, and private HMOs and PPOs
- Other: includes Worker's Compensation, TRICARE/CHAMPUS, CHAMPVA, Title V, and other government programs
- Uninsured: includes an insurance status of "self-pay" and "no charge."

When more than one payer is listed for a hospital discharge, the first-listed payer is used.

About HCUP

HCUP is a family of powerful health care databases, software tools, and products for advancing research. Sponsored by the Agency for Healthcare Research and Quality (AHRQ), HCUP includes the largest all-payer encounter-level collection of longitudinal health care data (inpatient, ambulatory surgery, and emergency department) in the United States, beginning in 1988. HCUP is a Federal-State-Industry Partnership that brings together the data collection efforts of many organizations—such as State data organizations, hospital associations, private data organizations, and the Federal government—to create a national information resource.

³ HCUP Cost-to-Charge Ratio Files (CCR). Healthcare Cost and Utilization Project (HCUP). 2001–2009. U.S. Agency for Healthcare Research and Quality, Rockville, MD. Available at http://www.hcup-us.ahrq.gov/db/state/costtocharge.jsp. Updated August 2011. (Accessed August 22, 2012).

HCUP would not be possible without the contributions of the following data collection Partners from across the United States:

Alaska State Hospital and Nursing Home Association

Arizona Department of Health Services

Arkansas Department of Health

California Office of Statewide Health Planning and Development

Colorado Hospital Association

Connecticut Hospital Association

Florida Agency for Health Care Administration

Georgia Hospital Association

Hawaii Health Information Corporation

Illinois Department of Public Health

Indiana Hospital Association

Iowa Hospital Association

Kansas Hospital Association

Kentucky Cabinet for Health and Family Services

Louisiana Department of Health and Hospitals

Maine Health Data Organization

Maryland Health Services Cost Review Commission

Massachusetts Center for Health Information and Analysis

Michigan Health & Hospital Association

Minnesota Hospital Association

Mississippi Department of Health

Missouri Hospital Industry Data Institute

Montana MHA - An Association of Montana Health Care Providers

Nebraska Hospital Association

Nevada Department of Health and Human Services

New Hampshire Department of Health & Human Services

New Jersey Department of Health

New Mexico Department of Health

New York State Department of Health

North Carolina Department of Health and Human Services

Ohio Hospital Association

Oklahoma State Department of Health

Oregon Association of Hospitals and Health Systems

Oregon Health Policy and Research

Pennsylvania Health Care Cost Containment Council

Rhode Island Department of Health

South Carolina Budget & Control Board

South Dakota Association of Healthcare Organizations

Tennessee Hospital Association

Texas Department of State Health Services

Utah Department of Health

Vermont Association of Hospitals and Health Systems

Virginia Health Information

Washington State Department of Health

West Virginia Health Care Authority

Wisconsin Department of Health Services

Wyoming Hospital Association

About the NIS

The HCUP Nationwide Inpatient Sample (NIS) is a nationwide database of hospital inpatient stays. The NIS is nationally representative of all community hospitals (i.e., short-term, non-Federal, nonrehabilitation hospitals). The NIS is a sample of hospitals and includes all patients from each hospital, regardless of payer. It is drawn from a sampling frame that contains hospitals comprising more than 95 percent of all

discharges in the United States. The vast size of the NIS allows the study of topics at both the national and regional levels for specific subgroups of patients. In addition, NIS data are standardized across years to facilitate ease of use.

About HCUPnet

HCUPnet is an online query system that offers instant access to the largest set of all-payer health care databases publicly available. HCUPnet has an easy step-by-step query system, allowing for tables and graphs to be generated on national and regional statistics, as well as trends for community hospitals in the United States. HCUPnet generates statistics using data from HCUP's Nationwide Inpatient Sample (NIS), the Kids' Inpatient Database (KID), the Nationwide Emergency Department Sample (NEDS), the State Inpatient Databases (SID), and the State Emergency Department Databases (SEDD).

For More Information

For more information about HCUP, visit http://www.hcup-us.ahrq.gov/.

For additional HCUP statistics, visit HCUPnet, our interactive query system, at http://hcupnet.ahrq.gov/.

For information on other hospitalizations in the United States, download *HCUP Facts and Figures:* Statistics on Hospital-Based Care in the United States in 2009, located at http://www.hcup-us.ahrq.gov/reports.jsp.

For a detailed description of HCUP, more information on the design of the NIS, and methods to calculate estimates, please refer to the following publications:

Introduction to the HCUP Nationwide Inpatient Sample, 2010. Online. May 2012. U.S. Agency for Healthcare Research and Quality. Available at http://www.hcup-us.ahrq.gov/db/nation/nis/NISIntroduction2010.pdf. (Accessed August 22, 2012).

Houchens R, Elixhauser A. *Final Report on Calculating Nationwide Inpatient Sample (NIS) Variances,* 2001. HCUP Methods Series Report #2003-2. Online. June 2005 (revised June 6, 2005). U.S. Agency for Healthcare Research and Quality. Available at

http://www.hcup-us.ahrq.gov/reports/CalculatingNISVariances200106092005.pdf. (Accessed August 22, 2012).

Houchens RL, Elixhauser A. *Using the HCUP Nationwide Inpatient Sample to Estimate Trends. (Updated for 1988–2004).* HCUP Methods Series Report #2006–05. Online. August 18, 2006. U.S. Agency for Healthcare Research and Quality. Available at

http://www.hcup-us.ahrq.gov/reports/methods/2006_05_NISTrendsReport_1988-2004.pdf. (Accessed August 22, 2012).

Suggested Citation

Pfuntner, A (Truven Health Analytics), Wier, LM (Truven Health Analytics), Steiner, C (AHRQ). Costs for Hospital Stays in the United States, 2010. HCUP Statistical Brief #146. January 2013. Agency for Healthcare Research and Quality, Rockville, MD. Available at http://www.hcup-us.ahrq.gov/reports/statbriefs/sb146.pdf.

Acknowledgments

The authors would like to acknowledge the contributions of Eva Witt of Truven Health Analytics.

* * *

AHRQ welcomes questions and comments from readers of this publication who are interested in obtaining more information about access, cost, use, financing, and quality of health care in the United States. We also invite you to tell us how you are using this Statistical Brief and other HCUP data and tools, and to share suggestions on how HCUP products might be enhanced to further meet your needs. Please e-mail us at hcup@ahrq.gov or send a letter to the address below:

Irene Fraser, Ph.D., Director Center for Delivery, Organization, and Markets Agency for Healthcare Research and Quality 540 Gaither Road Rockville, MD 20850