The Crash Outcome Data Evaluation System (CODES) And Applications to Improve Traffic Safety Decision-Making





at azo

MII

The Crash Outcome Data Evaluation System

CONTRIBUTING AUTHORS

Alabama: Glenn Cummings, Center for the Study of Rural Vehicular Trauma Connecticut: Justin Peng and Marian Storch, Connecticut Department of Public Health Delaware: Steven Blessing and Laurie Lin, Delaware Office of EMS Georgia: Denise Yeager, Georgia Dept. of Human Resources./Div. of Public Health/Injury Prevention Illinois: Mehdi Nassirpour, Illinois DOT Division of Traffic Safety Indiana: Jose Eduardo Thomaz, Center for Road Safety, Purdue University Iowa: Suning Cao, Iowa Dept. of Public health/Center for Vital Records and Health Statistics; Scott Falb, Office of Driver Services/Iowa Dept. of Transportation Kentucky: Huifang (Jenny) Qin and Michael Singleton, Kentucky Injury Prevention and **Research** Center Maine: Karl Finison, Maine Health Information Center Maryland: Timothy Kerns, University of Maryland/National Study Center for Trauma and EMS Massachusetts: Heather Rothenberg, University of Massachusetts Minnesota: Tina Folch and Scott Hedger, Minnesota Dept. of Public Safety/Office of Traffic Safety; Anna Gaichas and Mark Kinde, Minnesota Dept. of Health Missouri: Mark Van Tuinen, Missouri Department of Health and Senior Services Nebraska: Ming Qu, Nebraska Department of Health and Human Services New York: Motao Zhu and Susan Hardman, New York State Department of Health Ohio: Kristen Conner and Dr. Gary Smith, Children's Research Institute/Ohio State University Rhode Island: Ted Donnelly, Rhode Island Department of Health South Carolina: Mary Tyrell and Tracy Joyce, South Carolina State Budget and Control Board Utah: Larry Cook, Intermountain Injury Control Research Center, University of Utah Virginia: Michael Lundberg and Kathleen Bernard, Virginia Health Information

From NHTSA's National Center for Statistics and Analysis: Augustus "Chip" Chidester, Director, Office of Data Acquisitions Barbara Rhea, Chief, State Data Reporting Systems Division John Kindelberger, Team Leader, State Data and Quality Assurance Xuemei Pan, Advanced Systems Technology and Management, Inc., for NHTSA/NCSA Morrie O'Neil, Advance Systems Technology and Management, Inc.

Governors Highway Safety Association for NHTSA/NCSA: Sandra Johnson Michael McGlincy, Ph.D., Strategic Matching Inc.

TABLE OF CONTENTS

EXECUTIVE SUMMARY	1
I. THE CRASH OUTCOME DATA EVALUATION SYSTEM	3
Introduction and Background	3
Implementation and Data Enhancement	3
Federal Use of CODES Data	4
Document Purpose and Structure	
CODES State-Level Applications Summarized	5
Table 1: State CODES Applications Supporting Traffic Safety Problem Identification	6
Table 2: State CODES Applications Supporting Traffic Safety Decision-Makers	7
Table 3: State CODES Applications Supporting Traffic Safety Legislation	8
Table 4: State CODES Applications Supporting Public Educations	9
Table 5: Web Sites of CODES Programs in the NHTSA CODES Network	10
II. APPLICATIONS TO IMPROVE TRAFFIC-SAFETY DECISION-MAKING	
Alabama CODES	12
Connecticut CODES	13
Delaware CODES	17
Georgia CODES	19
Illinois CODES	21
Indiana CODES	22
Iowa CODES	23
Kentucky CODES	26
Maine CODES	28
Maryland CODES	31
Massachusetts CODES	33
Minnesota CODES	37
Missouri CODES	40
Nebraska CODES	43
New York CODES	45
Ohio CODES	47
Rhode Island CODES	49
South Carolina CODES	51
Utah CODES	53
Virginia CODES	55
III. APPENDICES	57
Appendix 1: Frequently Asked Questions Regarding CODES	
Appendix 2: Probabilistic Linkage Using Multiple Imputation	60
References	62

EXECUTIVE SUMMARY

The Crash Outcome Data Evaluation System (CODES) is a program facilitated by the National Highway Traffic Safety Administration as a component of its State Data Program. CODES uniquely uses probabilistic methodology to link crash records to injury outcome records collected at the scene and en route by emergency medical services, by hospital personnel after arrival at the emergency department or admission as an inpatient and/or, at the time of death, on the death certificate.

CODES is designed to foster and cultivate crash-outcome data linkage for highway safety applications at the State level, supporting State Highway Safety Offices, State Public Health and Injury Prevention Departments, State Emergency Medical Services Agencies, State transportation departments, and other such agencies; and to facilitate participation in NHTSAcoordinated multistate studies using linked data at the Federal level. This document is intended to inform traffic safety professionals, from those in CODES programs to those in the agencies they support, as well as all others interested in traffic safety, on best-practice applications available through linked CODES data.

To support CODES program objectives, NHTSA sponsors cooperative agreements that provide software access, technical assistance, and program assistance to CODES State programs to link information about State-reported crashes and their consequences, and to analyze and disseminate the information. Analyses of linked data help inform State traffic safety professionals and coalitions to determine and implement data-driven traffic safety priorities

CODES evolved from a need to quantify and report on the benefits of safety equipment and legislation in terms of mortality, morbidity, injury severity, and health care costs, and has built proactive partnerships between the traffic safety and public health agencies, which own the State data, and NHTSA, which provides access to the software and training resources that make the linkage feasible. NHTSA maintains a CODES facilitating infrastructure to provide technical support and assistance to sites while also encouraging each site to build State-level collaborations and perform relevant analyses within their States.

Topics of interest addressed by CODES have included pre-hospital, emergency department, inpatient, rehabilitation, and other health care charges by payer source (private, workers' compensation, Medicare, Medicaid, etc.), and associations with the consequences of motor vehicle crashes; crash injury patterns by type and severity, and hospital charges, by such variables as safety equipment use, vehicle type, geographical location, and others. In recent years, as outlined in abstracts in this paper, such information has been used to:

• Identify Traffic Safety Problems:

CODES data has been used to identify traffic safety issues in numerous ways, which include examining whether the increased crash rates for teen drivers is accompanied by an increased injury to their passengers (New York and Minnesota); determining hospital charges and length of hospital stay for motorcycle-related injuries (Georgia); identifying the effect of seat belt usage in preventing injuries and fatalities (Kentucky, New York, Ohio, and Utah); studying injury patterns among children riding with unbuckled adults compared to buckled adults (Utah); researching the types and frequency of injuries to children in passenger motor vehicles (Connecticut and Missouri); and analyzing the characteristics and outcomes of crashes involving teen drivers (Delaware and Minnesota).

• Support Traffic Safety Decision-Makers:

CODES data has been used to inform and educate traffic safety decision-makers as the State and local level. Examples of CODES activities being used to support decision-makers include providing State legislators with the CODES report on the effectiveness of seat belt use in preventing injuries and fatalities (Kentucky); delivering data and expertise to the State Highway Administration to assist in the development of a long-term, statewide strategic plan to guide the future direction of traffic records and highway safety (Maryland); presenting CODES-related fact sheets and reports to the State Traffic Records Coordinating Committee (TRCC) (Massachusetts, Virginia); using CODES data to present a report to the Governor's Highway Safety Office and State legislators on the effect that enacting a standard enforcement seat belt law would have on hospital charges, direct medical costs, and the impact to the State's Medicaid system (Ohio); and developing media products on the medical and financial consequences of the under-the-influence drivers involved in crashes (South Carolina).

• Support Traffic Safety Legislation:

CODES research has been used at the State level to inform legislators about traffic safety issues in their State and traffic safety legislation. These activities included providing legislators with information in support of upgrading existing graduated driver's license (GDL) laws (Delaware and Minnesota); using CODES data to expand a mandatory seat belt law to include back-seat passengers (Indiana); creating a fact sheet to help support legislation for motorcycle helmet use (Iowa); and providing data to a children's safety advocacy group to help convince legislators to change child passenger safety (CPS) laws (Connecticut).

• Educate the Public:

As a means to informing the public about traffic safety issues, CODES data has been used to give a presentation to a State TRCC about the length of hospital stay, injury body region, and nature of injury for older vehicle occupants (Massachusetts); post a fact sheet comparing the crash rate severity of State drivers against non-State drivers on the State's Health and Human Services Department Web site (Nebraska); publish a paper on backseat seat belt use in the *Journal of Safety Research* (New York); and launch a Web site that contains five years of CODES data from which the user can select standard reports or create online queries based on selected criteria (Virginia).

NHTSA is also using CODES multi-State data in a variety of studies as CODES States enable submission of standardized, non-identifiable data for research purposes. Through streamlining of programs and continuing methodological innovations, CODES is expected to continue leadership on traffic safety research in the 21st century.

I. THE CRASH OUTCOME DATA EVALUATION SYSTEM

Introduction and Background

Evolving from a need to quantify and report on the benefits of safety equipment and legislation in terms of mortality, morbidity, injury severity, and health care costs at State and national levels, the Crash Outcome Data Evaluation System has built proactive partnerships between the traffic safety and public health agencies, which own the State data, and NHTSA, which provides access to the software and training resources that make the linkage feasible. NHTSA maintains a CODES facilitating infrastructure to provide technical support and assistance to sites while also encouraging each site to build State-level collaborations and perform relevant analyses within their States.

The intent of CODES data linkages is to ensure that traffic safety coalitions have access to crash outcome analyses to help determine and implement data-driven traffic safety priorities. As a result of these linkages, the availability of population-based, comprehensive, and representative crash outcome data is maintained to assist existing traffic safety coalitions in the selection and implementation of data-driven traffic safety priorities. A properly implemented State CODES program supports State Highway Safety Offices, State Public Health and Injury Prevention departments, State EMS Agencies, State transportation departments, and other such agencies to target their resources and evaluate the potential impact on preventing mortality and morbidity, reducing injury severity, and lowering health care costs.

Implementation and Data Enhancement

Through NHTSA-sponsored cooperative agreements, CODES provides access to linkage software and technical assistance in the form of software support, linkage training, and analysis training to State CODES programs. Technical assistance is disseminated through means such as software documentation, Web seminars, individual assistance, and periodic technical assistance meetings. Once trained, State CODES programs add to the available knowledge about State-reported crashes and their consequences by linking crash data to data systems such as EMS records and statewide hospital discharge records.

The CODES program links crash records to injury outcome records collected at the scene and en route by emergency medical services, by hospital personnel after arrival at the emergency department or admission as an inpatient and/or, at the time of death, on the death certificate. Although crash data indicate the occurrence of injury, they include only limited information about type and severity and no information about health care costs or International Classification of Diseases (ICD) coding. Similarly, hospital injury datasets with ICD codes and billing charges do not include information about the characteristics of the crash or vehicles involved. CODES linkage integrates the two subject matters, and as a result, CODES provides statewide, real-world crash outcome data that can provide population-based information on crash outcomes in terms of deaths, specific injury type/region/severity, and costs.

As linkage expands into other data systems, as it has in some States, it can enhance other participating data systems in a variety of ways. For example, EMS and hospitals obtain information about the time of onset to evaluate the responsiveness of the trauma system;

roadway inventories expand to include injury outcome information by location point; driver licensing information is augmented with the medical and financial consequences caused by drivers who are impaired or repeat offenders; and vehicle characteristics can be related to specific types of injuries and their costs. In addition, data quality can improve as previously undiscovered problems are identified and corrected during linkage.

Federal Use of CODES Data

In the original NHTSA Report to Congress (1996) on the Benefits of Safety Belts and Motorcycle Helmets, data on crashes from seven States was compiled as part of the first CODES program. This report employed probabilistic linkage techniques to combine data gathered from police crash reports, emergency medical services, hospital emergency departments, and hospital discharge files to more fully describe motorcycle crash events and their outcomes. Among other findings, this report revealed an increase in hospital charges for motorcycle operators who were unhelmeted at the time of their crashes, and motorcycle helmet effectiveness of 67 percent in the reduction of brain injuries.

Though not catalogued in this report, the Federal-State collaboration that successfully implemented CODES at the State level has led to the planning of new CODES applications at the Federal level. States that have successfully linked at least two years of crash and injury outcome data may receive the benefits of the NHTSA CODES facilitation as part of the CODES Data Network. These projects also share their expertise and, under certain privacy considerations, can contribute specific standardized model variables for multi-State studies. NHTSA is currently working with CODES Data Network States to expand this capability, in order to provide support to NHTSA program needs with multi-State crash data analyzed by crash conditions, safety equipment, and other crash variables in terms of injury types, level of care, discharge status, payer, charges, and other outcome variables not available in unlinked crash data.

Document Purpose and Structure

This document is designed to well-inform traffic safety professionals, from those in CODES programs to those in the agencies they support, as well as all others interested in traffic safety, on best-practice applications available through linked CODES data. To distribute information on many applications in a compact way, this paper presents abstracts of applications presented by CODES members at CODES annual meetings. Abstracts are presented as prepared for the years 2006 and 2007. Each summarizes the population and traffic safety issue targeted, the format and methodology used, and impacts, actions or follow-ups on the targeted subject matter.

Since the State-specific applications presented are limited to those reported at the CODES meetings in 2006 and 2007, they do not represent a complete inventory of all of the applications developed by the States during this period. Thus, for example, not all of the CODES States actively involved in developing and supporting the State TRCC are listed in Table 2.

For convenience, abstracts are summarized in four categories, with summary tables allowing reference and page location by category and subject matter. After the summaries, full abstracts are presented in State alphabetical order. Following the abstracts, two appendices offer responses

to frequently asked questions regarding the CODES program and a more technical description of the statistical methodologies used to achieve representative linked data statewide.

CODES State-Level Applications Summarized

This section summarizes presented State CODES applications in four broad objectives: (1) traffic safety problem identification, (2) traffic safety decision-making support, (3) safety legislation development and support, and (4) public education. For each grouping, a table summarizes and references State applications in the category.

Objective 1: Identify Traffic Safety Problems

CODES data is population-based, so the large volume of data generated as the result of annual linkage in most CODES States can help identify safety issues including infrequent but potentially significant crash outcomes. Table 1 provides a reference to traffic-safety problem-identification applications as documented in their abstracts in Part 2 of this report.

Objective 2: Support Traffic Safety Decision-Makers

With limited resources, decision-makers need to identify and justify priorities assigned to improving traffic safety in relation to other public health issues. CODES data can provide statewide information to support safety efforts initiated by elected officials, and CODES data reported at the county or local level can be used in planning priorities of the coordinating agencies such as the Traffic Records Coordinating Committees (TRCCs), funding/planning agencies such as the State Highway Safety Offices and departments of public health/injury control, or data users such as the members of the CODES advisory committee. Many CODES projects also have played key roles in helping to define the traffic safety agenda of their State TRCC committees. Table 2 summarizes examples of these traffic-safety decision-making support applications as documented in their abstracts in Part 2 of this report.

Objective 3: Support Traffic Safety Legislation

Traffic safety efforts must be targeted where they will have the most impact on improving crash outcome. When the increase in deaths, injury, severity, and health care costs becomes unacceptable, legislation may be necessary to change public behavior. In these instances, the State-specific medical and financial information generated by CODES can demonstrate the expected savings, in terms of decreased health care costs and injury severity, to taxpayers with the adoption of specific traffic safety legislation. Table 3 summarizes examples of legislation-support applications as documented in their abstracts in Part 2 of this report.

Objective 4: Educate the Public

If an educated public can help improve traffic safety, then traffic safety information must be readily available in a format that meets the public's needs. In support of public education, State CODES programs often use 1– or 2-page fact sheets to disseminate traffic safety information to the public. In addition, the Internet has increased accessibility to linked crash outcome results while complying with State privacy legislation and regulations. Some States provide online interactive reports or detailed data tables. Table 4 summarizes examples of public education applications as documented in their abstracts in Part 2 of this report, and Table 5 lists the Web sites for the CODES States and NHTSA as of March 2009.

State and A	pplication by Type of Subject Matter	Page
1. Aggressiv	ve Drivers	
Delaware	Aggressive Driving Study Descriptive statistics and rate ratios (RRs) were used to compare the crash outcomes between 16- and 17-year-old drivers with and without passengers.	18
2. Older Driv	vers	
Rhode Island	<i>Elder Occupants in Motor Vehicle Crashes: Forecasting Health</i> <i>Burden</i> Statistically, Rhode Island's older occupants are more likely to be hospitalized or fatally injured after motor vehicle crashes. CODES data was used to examine the differences and the age distribution of the population to help in developing planning policies on future highway safety interventions.	50
3. Teen Driv	ers	
Minnesota	The Epidemiology of Motor Vehicle Crashes Involving 16- and 17- Year-Old Drivers in Minnesota and Associated Hospital Charges CODES data were used to determine the per mile rate of teenage driver motor vehicle crash involvement and the characteristics of these crashes in Minnesota. Measure medical care charges and the severity of injuries associated with motor vehicle crashes involving teenage drivers.	38
New York	Using Multiply-Imputed CODES Data to Identify Risk Factors and Reveal Societal Costs in Teen Driving Police crash reports, emergency department and hospital discharge data were examined to determine the risk factors and societal costs for drivers age 16 to 20. Teen drivers and 25- to 49-year-old drivers were compared for traffic crash and injury rates, emergency department visit rates, hospitalization rates, and crash contributing factors.	46
4. Non-Resi	dent Drivers	
Nebraska	Comparing Crashes That Occurred in Nebraska Involving Nebraska and Non-Nebraska Drivers Comparing the crashes occurring in Nebraska from 1999 to 2003 by the driver's State of residence, CODES data explored the patterns and the contributing risks factors of the crashes. Crashes involving non-Nebraska drivers tended to be more severe, resulting in more deaths and serious injuries than crashes involving Nebraska drivers.	44
5. Roadway		
Nebraska	Why Is It So Risky to Drive on the Roadways Where the Posted Speed Limit Is 50 Miles Per Hour? The crashes that occurred on roadways with posted speed limits of 50 mph resulted in severe crash outcomes with the highest injury rate and a higher death rate than those crashes that took place on other roadways. This CODES study examines the causes and consequences of crashes occurring on Nebraska roads with posted speed limits of 50 mph.	43
6. Traumatio	s Brain Injury	
Iowa	Motor Vehicle Crash (MVC) Related to Traumatic Brain Injuries in Iowa To demonstrate the growing crash and injury rates among motorcycle riders in Iowa from 2001–2005, CODES data was used to examine the five years' crash rates per 1,000 motorcyclist licensed drivers—including fatality and injury rates— and were calculated to demonstrate low rates of helmet use in Iowa.	23
7. Data Qua	lity Issues	•
Maine	Adjusting for Seat Belt Reporting: The Problem of Differential Misclassification CODES reviewed the problem of differential misclassification of seat belt use in police crash reports and explored a method of correcting for missing data and differential misclassification using CODES linked data.	30

Table 1: State CODES	Applications Supporti	ng Traffic Safety	Problem Identification
Table 1. State CODES	Applications Support	ng manne barety	I I UDICIII Iucintintation

State and Appli	cation by Type of User	Page
1. Elected Offic	als: Governor and Legislators	
Missouri	Safety Device Use for Children Age 4 to 8 CODES data was used to measure the effect of safety device use on emergency department (ED) and inpatient charges, ejection, hospitalization, traumatic brain injury (TBI), and death for children age 4 to 8.	40
South Carolina	Providing Information to Support Decision Making CODES data was used to develop various media products distributed to members of the South Carolina legislature and traffic safety decision makers.	51
2. Coordinating Planning	Agencies: Traffic Records Coordinating Committee and Strategic	
Connecticut	The Importance of CODES Involvement in the Connecticut TRCC C ontent about the CODES project was submitted as part of the Connecticut TRCC's 5- Year Strategic Plan. The Strategic Plan identified CODES as one of the top priorities for State traffic records improvements. The needs of CODES, as highlighted in the Strategic Plan, will help advocate for the program both within the Connecticut Department of Public Health (DPH) and statewide.	13
Iowa	Iowa Motor Vehicle Crash Injury Facts Among Emergency Department Visits: A Profile of Unbelted Occupants of Passenger Cars and Vans/SUVs (2003) CODES data analysis was presented at a TRCC meeting and to the Prevention of Disability Council Meeting. The data was also used for occupant restraint task force group within the TRCC.	24
	<i>Motorcycle Quick Facts in Iowa – 2001 to 2005</i> Helmets were evaluated and a fact sheet was distributed at the Iowa Motorcycle Safety Forum 2007. The data results have been included in Iowa's Safety Management Systems within Traffic Safety and are being used to support Iowa goals.	25
Maryland	Using Data for Strategic Planning and TRCC The CODES project has contributed data and expertise to the State Highway Administration to assist in the development of a statewide strategic plan that will guide the direction of traffic records and highway safety in the State for the next several years.	31
Massachusetts	Crash Outcomes for Older Occupants of Motor Vehicles in Crashes CODES Data results were presented in several formats including fact sheets, reports, and presentations to the Massachusetts CODES advisory board and Massachusetts Traffic Records Coordinating Committee.	35
3. Funding Age	ncies: Highway Traffic Safety Offices, Strategic Planning	
Massachusetts	Evaluation of Frequency and Injury Outcomes of Lane Departure Crashes Lane departure data analysis has been an ongoing project for MassHighway and the dialogue between the MassHighway safety analysts and UMassSAFE have included a discussion of how the CODES data can be used and the benefits of using CODES data in addition to traditional crash data.	33
Virginia	408 Funding Award for Virginia's Traffic Safety Information System CODES staff developed a study for the Governor of Virginia, members of the Virginia General Assembly, the Traffic Records Coordinating Committee, the Highway Safety Office, and the Injury Control Office.	56
4. Users of Traf	fic Safety Data: CODES Advisory Committee, Injury Control	
Illinois	<i>Inpatient Charges and Utilization Patterns of Crash Victims in Illinois</i> Preliminary CODES findings have been presented to the Illinois CODES Advisory Group and made available to the Illinois Traffic Records Coordinating Committee.	21
Ohio	Boost Advisory Board Interest in CODES The CODES team used input from the advisory board to focus on topics of interest to the traffic safety community.	47

Table 2: State CODES	Applications Supporting	Traffic Safety Decision-Makers
	ipplications supporting	

Table 3: State CODES	Applications Supporting	Traffic Safety Legislation
	ppncutions supporting	

State and App	lication by Type of Issue	Page
1. Convert Sec	condary to Primary Safety Belt Law	
Minnesota	Estimating Minnesota Hospital Charge Savings With the Adoption of a Standard Enforcement Seat Belt Law A CODES report on seat belts was used to gather support in the Minnesota Senate for passage of a primary seat belt bill.	37
Ohio	The Impact of a Standard Enforcement Safety Belt Law on Fatalities and Hospital Charges in Ohio: An Analysis Using 2003 Ohio CODES Data The Ohio Governor's Highway Safety Office at ODPS assisted in publicizing and sharing CODES results with the Governor and other legislators.	48
Utah	Primary Safety Belt Enforcement Efforts A fact sheet titled "The Cost of Being Unbuckled," was given to every State legislator.	54
2. Expand Prin	nary Belt Legislation to Include Backseat Passengers	
New York	The Importance of Promoting Backseat Safety Belt Use A presentation was made during the New York State Highway Safety Conference and a paper on backseat seat belt use was published in Journal of Safety Research.	45
3. Expand Prin	nary Belt Legislation to Include Pickup Trucks	
Georgia	<i>Effects of Pickup Trucks Seat Belt Exemption</i> Georgia CODES provided data to support the House bill to eliminate the current exemption in Georgia code pertaining to the use of seat belts in pickup trucks.	20
Indiana	<i>Effect of Seat Belt Usage on Hospital Charges by Vehicle Type</i> CODES research was used to support House Bill 1237, which now requires all occupants, including backseat passengers in all vehicles to buckle up.	22
4. Improve Ch	ild Passenger Safety	
Connecticut	Usefulness of CODES Data for CODES Advisory Board Members and Using CODES Data to Improve Connecticut's Child Passenger Safety Law Staff met with the Director of Connecticut Safe Kids, a member of the advisory board, to identify analyses and presentation formats that will be most effective in supporting improvements to Connecticut's child passenger safety laws.	15
Kentucky	Economic Costs of Low Safety Belt Usage in Kentucky The Kentucky legislature passed a primary seat belt enforcement bill in the General Assembly. The Kentucky CODES report was one of the efforts that preceded its passage.	26
5. Strengthen	Graduated Driver Licensing	
Delaware	Support for Passenger Limitations on 16- and 17-Year-Old Drivers A CODES fact sheet was forwarded to legislative liaisons to support upgrading Delaware's Graduated Driver's License (GDL) law.	17
Utah	Using CODES Data to Strengthen Utah's GDL Law CODES findings were published in several newspapers and aired on local television news programs. As a result, local traffic safety advocates asked Utah CODES to prepare fact sheets about GDL, which were given to legislators and presented in committee meetings.	53
6. Reduce DUI		
Rhode Island	Rhode Island CODES Provides Expert Participation Rhode Island's CODES linked data results and other highway safety and public health information has been used in support of stricter laws against driving under the influence.	49
South Carolina	The Continuing Saga of DUI Legislation Media products are distributed to legislators and traffic safety decision makers to illustrate the medical and financial consequences of under-the-influence drivers involved in crashes. The data are analyzed at a local level to show local consequences.	52
7. Support Hel	met Legislation	
Georgia	Motorcycles in Georgia Fact sheets on motorcycle crash injuries in Georgia were developed for different audiences during unsuccessful efforts to repeal Georgia's motorcycle helmet law.	19

	lication by Subject or Format	Page
FACT SHEETS		
1. Motorcycles		
Georgia	<i>Motorcycles in Georgia</i> Two fact sheets were developed by Georgia CODES staff to inform policy makers and the general public about motorcycle crashes and motorcycle hospitalizations.	19
Iowa	<i>Motorcycle Quick Facts in Iowa 2001–2005</i> A fact sheet was created by Iowa CODES staff and distributed at the Iowa Motorcycle Safety Forum.	25
2. Seat belts		
Georgia	Safety Belts and Pickup Trucks A fact sheet was developed by Georgia CODES staff to inform policy makers and the general public about issues relating to seat belts and pickup trucks.	20
Minnesota	Estimating Minnesota Hospital Charge Savings With the Adoption of a Standard Enforcement Seat Belt Law A CODES report and fact sheet were distributed through statewide e-mail distribution lists to law enforcement, public health educators, and other traffic safety advocates. The report was highlighted on the Office of Traffic Safety and Department of Health's Web sites. CODES data will continue to be used in various publications and presentations that discuss the economic impact of crashes.	37
3. Teen Drivers	8	
Delaware	Passenger Limitations for 16- and 17-Year-Old Drivers CODES staff created a fact sheet that highlighted CODES data and supports passenger limitation for 16- and 17-year-old drivers.	17
Kentucky	<i>Injuries to Booster-Age Children in Kentucky</i> Kentucky CODES created a fact sheet that focused on the outcomes (injury type, hospital charges, hospital length of stay, etc.) for restrained and unrestrained children age 4 to 8, compared with other age groups.	27
4. Non-Nebras	ka Drivers	
Nebraska	 Non-Nebraska Drivers Involved in Motor Vehicle Crashes Occurring in Nebraska A fact sheet was created by Nebraska CODES staff and posted on the Nebraska Health and Human Services System's Web site. 	44
DATA ACCESS	S VIA THE INTERNET	
Missouri	Update of Web Application The Missouri CODES Web application allows users to develop tables of CODES data that relate to seat belt/helmet use, alcohol involvement, driver gender and age, crash type, speed zone, and vehicle type to level of medical care/death, ejection, and TBI. Five years of CODES data are now on the Web site	41
Virginia	Virginia CODES Web site Virginia's CODES Web site, <u>www.vacodes.org</u> , was launched in May 2006 and currently contains five years of data from which the user can select standard reports or create online queries based on selected criteria.	55

Table 4: State CODES Applications Supporting Public Educations

State	Web Address (current March 2009)
Delaware	www.dhss.delaware.gov/dhss/dph/EMS/codeshome.html
Indiana	http://cats.ecn.purdue.edu/CODES.aspx
Iowa	http://www.idph.state.ia.us/apl/codes.asp
Kentucky	www.kiprc.uky.edu/projects/CODES
Maine	www.mhic.org/CODES
Maryland	http://medschool.umaryland.edu/NSCforTrauma//codes.asp
Massachusetts	www.ecs.umass.edu/umasssafe/codes.htm
Minnesota	www.health.state.mn.us/injury/topic/topic.cfm?gcTopic=9
Missouri	www.dhss.mo.gov/MICA/index.html (Select motor vehicle crashes)
Nebraska	http://www.hhss.ne.gov/codes/
Ohio	http://sharedoc.nchri.org/CIRP/Pages/CODES.aspx
Rhode Island	www.health.ri.gov/chic/statistics/codes.php
South Carolina	www.ors2.state.sc.us (select SC CODES project)
Utah	http://www.utcodes.org
Virginia	www.vacodes.org

 Table 5: Web Sites of CODES Programs in the NHTSA CODES Network

II. APPLICATIONS TO IMPROVE TRAFFIC-SAFETY DECISION-MAKING

To disseminate exemplary data uses and promising practices throughout the CODES Data Network and beyond, abstracts of presentations given at CODES annual meetings are presented on the following pages. Abstracts are in alphabetical order by State, and each one describes an application that was presented at a national CODES Technical Assistance meeting held in either 2006 or 2007. At these meetings, State CODES programs are encouraged to share ideas and progress in the program realm as well as the technical areas. The abstracts are offered as an exemplary yet partial representation of programmatic and technical CODES endeavors and achievements undertaken in recent years.

Title: Doe In	State Appl es Increa. Rural M	Alabama CO er for the Study of Rural ication Presented at CODI sed EMS Pre-Hospita fotor Vehicle Crashes	Vehicular ES Annual I <i>l Time Aff</i> ? A Statev	Meeting, 2 fect Pati vide Ana	ent Mortality lysis.	
		is to link and analyze Ala ects patient mortality from			-hospital data and	l identify
Contact Person and number		ummings, 251-471-7501 Center for the Study of R	ural Vehicu	ılar Traum	ıa	
Population Targeted	Rural vel	hicular trauma patients				
Purpose	Reduce r	nortality rates due to rural	vehicular t	rauma		
Type of Decision Maker Targeted		Department of Public He			e ;	
Description of linked data and analyses	-	of data from police motor Care Reports	vehicle cra	sh and En	nergency Medical	Services
	transport times in rural and urban settings. During a two-year period (January 2001 – December 2002) 34,341 people (75%) and 11,422 people (25%) were injured in rural and urban settings, respectively. The data also showed that 611 (1.78%) fatalities occurred in rural settings, and 103 (.90%) fatalities occurred in urban settings (p <0.001). The overall mean EMS pre-hospital time when fatalities occurred was 42.0 minutes in the rural setting versus 24.8 minutes in the urban setting (p <0.001).					
		Pre-Hospital Times for ll Fatalities (min)	Rural	Urb an	p-value	
		Mean EMS Response Time	10.67	6.50	< 0.0001	
		Mean EMS Scene Time (excludes DOS and extrication)	18.87	10.8 3	< 0.0001	
		Mean EMS Transport Time (excludes DOS)	12.45	7.43	< 0.0001	
		Overall Mean EMS Pre-Hospital Time	42.0	24.8	< 0.0001	
Dissemination Formats	 Presentation at the American Association for Surgery of Trauma. Expected publication in the Journal of Trauma Presentation to the Alabama Department of Public Health, State Emergency Medical Control Committee Presentation at the Alabama Chapter of the American College of Surgeons. 					
Impact, Follow-Up, or Later Development on the Targeted Issue	Alabama has sugg	's Department of Public H ested further investigation nes, and transport times in	ealth, Divis	sion of En use of inci	nergency Medical	Services,

Connecticut CODES Connecticut Department of Public Health

State Application Presented at CODES Annual Meeting, 2006

Title: The Importance of CODES Involvement in the Connecticut TRCC

Abstract: The core focus of most CODES projects is typically on the technical aspects of data linkage, analysis of linked data, and the development of State-specific applications of the data. However, building relationships with key stakeholders is an important activity that CODES staffs undertake. Involvement in the State's Traffic Records Coordinating Committee (TRCC) is a way to learn about key data systems and programs, inform constituents about the CODES project, and identify ways to collaborate with partners to meet each other's needs. Connecticut CODES staff takes an active role in the State's TRCC. Most recently, content about the CODES project was submitted as part of the TRCC's 5-Year Strategic Plan. The Connecticut CODES staff was able to highlight positive attributes of the program, identify deficiencies and barriers to progress, and recommend ways in which these issues can be addressed. The Strategic Plan identified CODES as one of the top priorities for State traffic records improvements. The Strategic Plan was only recently submitted. The needs of CODES, as highlighted in the Strategic Plan, will help advocate for the program both within the Connecticut Department of Public Health (DPH) and statewide.

Tublic Health (DI	H) and statewide.
Contact Person	Justin Peng, 860-509-7774
and Number	Marian Storch, 860-509-7791
Population	Administrators with decision-making authority
Targeted	
Traffic Safety	Data Quality and Content
Issue Targeted	Expansion of the State crash reporting form and enhancements to the electronic database.
	Program Support
	Increase human resources to sufficiently staff the project.
	Institutionalization of the project in the agency.
	Collaboration with internal and external constituents.
Targeted	Connecticut TRCC members, Connecticut Department of Transportation Traffic Records
Audience	Section and Transportation Safety Division, Connecticut Department of Public Health
	Administration.
Methodology	• Provide updates at TRCC meetings and promote the CODES project and uses of the data.
	Submit content about CODES to be included in the Connecticut TRCC's 5-year Strategic Plan.
	A "Combined STRAW Model" was used to identify attributes and deficiencies for each project
	area, and provide recommendations for improvement.
Results	Meetings:
	TRCC meetings used as an opportunity to:
	Gain insight about crash data from DOT data analyst.
	• Promote future collaboration with University of Connecticut traffic researchers.
	Build and maintain support from TRCC members who, if needed, can advocate on behalf of
	the project.
	Strategic Plan:
	 CODES was identified as a priority area for the TRCC.
	 Attributes: CODES generates linked motor vehicle crash and injury outcome data;
	generates population-based outcome information to better characterize crashes and their
	associated costs; uses linked crash and injury data to guide initiatives surrounding motor
	vehicle and pedestrian safety in Connecticut geared toward reducing crash-related injuries
	and deaths.
	Barriers: Staffing challenges have affected the progress of the CODES Project;
	Connecticut must purchase inpatient and ED data from a private entity, and delays have
	been faced in obtaining more recent (2000-2004) data for linkage and analysis.

	Connecticut CODES			
Connecticut Department of Public Health				
	State Application Presented at CODES Annual Meeting, 2006			
Tit	le: The Importance of CODES Involvement in the Connecticut TRCC			
Results (cont'd)	 Recommendations: There are several ways in which the Connecticut CODES project can be enhanced, including: Increasing program capacity through additional staffing; Enhancing the crash data system (quality and content); Expanding the crash reporting form to include fields important to CODES (e.g., gender for passengers, if injured person was transported, increased detail on the type of occupant protection used); Linking crash and hospital data sources to EMS data (once available); Expanding linkage efforts to include other data sources such as mortality, trauma registry, and medical examiner data; and Linking ancillary data sources (e.g., DMV driver and vehicle data) to provide additional data for linkage and/or analysis. CODES staff were recruited to be part of a subcommittee working on improvements to the crash reporting system (quality and content), including conforming to Model Minimum Uniform Crash Criteria Standards. 			
Dissemination	Meetings: Reinforced the value of CODES data, but also discussed barriers to progress			
Formats	(primarily, delayed receipt of the hospital data). The TRCC facilitator included updates about CODES on nearly every meeting agenda. Strategic Plan : Provided written content for the Strategic Plan for CODES. Also presented information, informally, at TRCC meetings.			
Impact, Follow- Up, or Later Development on the Targeted Issue	The Strategic Plan was only recently submitted. The needs of CODES, as highlighted in the Strategic Plan, will help advocate for the program both within DPH and statewide. CODES staff will continue to use the TRCC meetings as a way to network with potential collaborators, data owners and/or data users, and to build support among the traffic records and safety community. The TRCC is submitting an application for "State Traffic Safety Information System Improvement" funds. If funded, several of the proposed projects will improve the quality and content of traffic records data, which will benefit all traffic data system users, including the Connecticut CODES project.			

Connecticut CODES Connecticut Department of Public Health

State Application Presented at CODES Annual Meeting, 2007 Title: Providing and Improving Usefulness of CODES Data for CODES Advisory Board Members and Using CODES Data to Improve Connecticut's Child Passenger Safety Law

Abstract: For 2006–2007, Connecticut Crash Outcome Data Evaluation System primarily focused on data linkage activities and the formal establishment of Connecticut CODES advisory board. Connecticut CODES has built strong relationships with key CODES stakeholders through constant communications in the past, but an advisory board was not formally established till 2006. An analysis using 1999 linked data was presented to the advisory board, focusing on motor vehicle occupant protection system or restraint use. Data presented included characteristics of people involved in crashes, characteristics of people not using protection systems, and outcomes of protection system use. The Director of Connecticut Safe Kids, a member of the advisory board, expressed an interest in focusing on child passenger safety (CPS). CODES Staff met with the Director of Connecticut Safe Kids to identify specific analyses of CODES data and the data presentation formats that will be most effective in convincing legislators to change the CPS law. Connecticut child passenger safety advocates, including the State and local Safe Kids Coalitions, plan to advocate for legislative changes that will bring Connecticut's law in closer compliance with national "best practice" recommendations.

Contact Person and	Justin Peng, 860-509-7774
Number	Marian Storch, 860-509-7791
Population/ Problem Targeted	Injuries to children in passenger motor vehicle crashes
Targeted Issue	Improve Connecticut child passenger safety (CPS) laws. Connecticut's current law, effective in 2005, requires children age 6 or younger and children up to 60 pounds to ride in a child restraint system. Connecticut child passenger safety advocates, including the State and local Safe Kids Coalitions, are planning to advocate for legislative changes that will bring Connecticut's law in closer compliance with national "best practice" recommendations.
Requesting Office or Targeted Audience	Requesting Offices: Connecticut Safe Kids Coalition and the Connecticut Department of Public Health Injury Prevention Program. Targeted Audiences: State and local Safe Kids Coalition members and other injury prevention advocates, Connecticut CODES advisory board members. Legislators (reached through the State and local Safe Kids members and other advocates.)
Data Used	Linked/imputed data from 1999 crash, inpatient, and emergency department visit were used for this application. Only data from 1999 were available at the time of application development, and updated analyses using more recent linked data will be provided in the future. The crash data contain all crash records statewide and have most of the data elements needed for this application. The inpatient and ED visit data contain data from 30 out of 31 acute care hospitals in Connecticut and have all needed data elements for this application.
Methodology and Analytical Results	Data presented to the advisory board include characteristics of people involved in crashes, characteristics of people not using protection systems, and outcomes of protection system use. Further analyses focused on the outcomes of using versus not using child safety seats among children less than 5 years of age. The results found that any restraint use significantly reduced the likelihood of injury, likelihood of seeking medical care, medical charges, and length of stays. The results also found that the use of child restraint system has a further effect, although not statistically significant, on all above mentioned outcomes when compared to the use of seat belt without child restrain system. A brief explanation of the linkage imputation techniques was discussed to let the audience appreciate the complicity involved in the linkage process, but the explanation was kept simple to avoid confusion.

Connecticut CODES

Connecticut Department of Public Health State Application Presented at CODES Annual Meeting, 2007

Title: Providing and Improving Usefulness of CODES Data for CODES Advisory Board Members and Using CODES Data to Improve Connecticut's Child Passenger Safety Law

Dissemination Formats	A PowerPoint presentation and handouts were used to communicate the data-driven message at the quarterly Connecticut CODES advisory board meeting. The presentation started with an overview of linkage and analytical methods. It then moved into describing the characteristics of people involved in crashes and the characteristics of people not using protection systems. Finally, it ended with describing the medical outcomes of protection system use. Most results were presented in graphical formats with data values appearing on the graphs. This format was effective in providing visualizations and getting the message across.
Impact, Follow-Up, or Later Development on the Targeted Issue	Connecticut CODES staff met with the director of Connecticut Safe Kids, a member of the advisory board, to identify specific analyses of CODES data and the data presentation formats that will be most effective in convincing legislators to change the CPS law. It was agreed that Connecticut CODES will provide further analyses to Safe Kids Coalitions using most recent linked data and focusing on trends of child restraint system use, CRS use by age, injury severity, level of care received, average medical charges, and length of stays on statewide and county levels. Based on past experience, it is most useful for Safe Kids Coalitions to receive results in tabular format with key points highlighted. This will allow State and local level Safe Kids Coalitions the flexibility to customize the formats used to present data as needed (i.e., fact sheets, constituent letter or post card campaigns, information packets for legislators and testimony at public hearings). The Connecticut Safe Kids is now starting to plan for introduction of legislation during Connecticut's Spring 2008 legislative session. Police crash reports were the only State-Specific data set available to support previous legislative initiatives. The linked data provided by the Connecticut CODES Project to the Connecticut and local Safe Kids Coalitions will provide more comprehensive information and help them better advocate with legislators for changes to the CPS law.

	Delaware CODES	
	Delaware CODES Delaware Office of Emergency Medical Services	
	www.dhss.delaware.gov/dhss/dph/EMS/codeshome.html	
	State Application Presented at CODES Annual Meeting, 2006	
Title: S	Title: Support for Passenger Limitation on 16- and 17-Year-Old Drivers	
	le crashes are the leading cause of death among teens. Because of the high crash rate for	
	emented a graduated driver licensing (GDL) program on July 1, 1999. One of the high-risk	
	-year-old drivers involved in crashes is carrying passengers. Amending the Delaware GDL	
system to include a lin	nit of <i>one passenger</i> is expected to further reduce crashes among these drivers.	
Contact Person and	Laurie Lin, 302-378-5205 or 302-744-5400	
Number		
Population Targeted	Teen Driver	
Traffic Safety Issue Targeted	Graduated Driver Licensing	
Requesting Office or	State Highway Safety Office	
Targeted Audience	State legislative liaisons	
Description of linked data	Data Sources: Delaware crash reports, EMS, and hospital discharge data years used: Linked data 1998-2003	
Analytical Results	Descriptive statistics and rate ratios (RRs) were used to compare the crash outcomes	
	between 16- and 17-year-old drivers with and without passengers. The majority of	
	passengers riding in cars driven by 16- and 17-year-olds involved in crashes were between	
	15 and 19 years old. Compared to driving alone or with one teenage passenger, 16- and	
	17-year-old drivers with more than one teenage passenger were:	
	(a) 1.65 times more likely to involve speeding;	
	(b) 2.19 times more likely to involve drinking and driving;	
	(c) 28 percent less likely to wear seat belts; and	
	(d) When hospitalized, spent one more day in the hospital and at an average charge of \$500 more for the hospital charges.	
Dissemination	A fact sheet highlighting the information of data supports passenger limitation for 16- and	
Formats	17-year-old drivers.	
Impact, Follow-Up,	After reviewing the fact sheet by CODES stakeholders and highway safety offices, these	
or Later	stakeholders forwarded the fact sheet to their legislative liaisons to support upgrading the	
Development on the	GDL law. Rep. John F. Van Sant, the sponsor of the bill, when he was interviewed by the	
Targeted Issue	<i>News Journal</i> said he believed the bill stands a good chance of passage after the General	
Commonto	Assembly returns on May 30.	
Comments	Delaware's GLD program has been successful and recent legislation helps address	
	concerns with cell phone distractions. This component of House Bill 256 w/HA 5 provides additional safeguards for Delaware's driving youth by increasing the minimum age for a	
	Level 1 Learner's Permit—also known as the graduated driver's license—from 15 years, 10 months to 16 years old. It further makes the program 18 months long, in two segments	
	of 9 months each, adopting the restrictions of the current 1-year program, except that	
	instead of allowing two passengers during the period of restriction, the bill allows only	
	one passenger. In addition, the bill would require the permit holder not only to carry the	
	permit while driving, but also require the permit holder to post a sticker or other	
	identifying marker on the car being driven by the permit holder, indicating that he or she is	
	operating the vehicle under a graduated driver's license. In addition, the bill requires the	
	permit holder and all passengers under 18 to wear a seat belt or be secured in a child	
	safety seat when the vehicle is in motion.	

Delaware CODES

Delaware Office of Emergency Medical Services

www.dhss.delaware.gov/dhss/dph/EMS/codeshome.html State Application Presented at CODES Annual Meeting, 2007

Title: Aggressive Driving Study

Abstract: Aggressive driving has become increasingly the focus of study for traffic safety because it is an unsafe driving behavior. In 2003, aggressive driving-related crashes contributed to 53 percent of all fatal crashes in Delaware. The purpose of this study is to analyze/identify aggressive driving behavior—and its consequences in terms of crashes, injuries, and fatalities— in order to improve the safety of Delaware's roadways.

Toadways.	
Contact Person and Number	Laurie Lin, 302-378-5205 or 302-744-5400
Population/	Aggressive drivers
Problem Targeted	
Targeted Issue	Reduce injuries from aggressive driving-related crashes
Requesting Office or	State Highway Safety Office
Targeted Audience	CODES stakeholders
Data Used	Data Sources: Delaware crash reports, EMS, and hospital discharge data
	Years used: Probabilistically linked data 1998–2003
Methodology and Analytical Results	Aggressive driving is defined by one or more of the following traffic violations: speeding, failing to yield right of way, passing stop sign, disregarding traffic signal, driving left of center, passing improperly, following too close, and making an improper turn.
	In 2003, 52 percent of traffic-related fatalities in Delaware were aggressive driving- related, which was higher than the 47 percent aggressive driving-related fatalities in Delaware in 1998. The top three primary contributing circumstances for fatal aggressive driving-related crashes from 1998 to 2003 were failing to yield right of way, speeding, and driving left of center.
	For aggressive-driving-related crashes, the death rate per 100,000 for the 15to 19 age group increased from 16.9 in 1998 to 25.1 in 2003. Male drivers accounted for 57 percent of drivers involved in aggressive driving-related crashes.
	Average hospital charges for people who were unrestrained were larger than for those who were restrained in aggressive driving-related crashes. Unrestrained people involved in aggressive driving crashes had charges \$1,000 higher for inpatients when compared to restrained people.
Dissemination Formats	The result of the study was presented using a PowerPoint format. Crash statistics such as percentages, averages, and rates were used to show the effects of aggressive driving.
Impact, Follow-Up, or Later Development	Continue to monitor and analyze aggressive driving-related data
on the Targeted Issue	Support the aggressive driver public awareness campaign from Office of Highway Safety

Georgia CODES

Georgia Department of Human Resources, Department of Public Health

State Application Presented at CODES Annual Meeting, 2006

Title: Motorcycles in Georgia

Abstract: Two separate fact sheets about injuries due to motorcycle crashes in Georgia were developed to meet the information needs of different audiences. One fact sheet consisted of a one-page summary created to inform policy makers and the general public. The other fact sheet was a more detailed descriptive analysis on motorcycle crashes and motorcycle hospitalizations that was intended for health and safety professionals. The fact sheets included crash and hospitalization data displaying crash numbers and rates, helmet use, injury severity, and contributing factors. The hospital data set contributed information about hospitalization numbers, injury severity, total hospitalization charges, and injured body region. The 2001 linked data sets were used to evaluate how motorcycle helmets were protective against traumatic brain injury.

injury.	-
Contact Person and	Denise Yeager, 404-657-4776
Number	
Population Targeted	Motorcycle operators and riders
Traffic Safety Issue	Support helmet use on motorcycles and reduce the number of deaths and severity
Targeted	of injuries
Requesting Office or Targeted Audience	Analysis requested by the CODES Board of Directors through its chair, the director of Governor's Office of Highway Safety. Other targeted audience include the general population, legislators, highway safety office/plan, injury prevention
	section, and public health/academic professionals.
Description of Linked Data	Data sources included the 2001 crash and hospital inpatient discharge data sets. The 2001 CODES linked data used the probability methods current at the time. The data quality of the crash and hospital data set was complete and validated. Since date of birth is only available from drivers in the crash data set, there was a limitation with the data among the motorcycle rider passengers.
Analytical Results	Linked data from crash records and hospitalizations for motorcycle related injuries were analyzed for median and average hospital charges and length of hospital stay. Primary payer sources, age-specific injury hospitalization rate, and primary injured body region were also analyzed. The odds ratio of a person having TBI without helmet usage compared to those who wore helmets was calculated to obtain TBI risk reduction of helmet usage among motorcycle riders. At least 12 percent of motorcycle riders in Georgia involved in crashes were not wearing helmets. Helmets are estimated to be 37 percent effective in preventing motorcycle fatalities and 67 percent effective in preventing brain injuries. In 2003, helmets saved an estimated 53 lives in Georgia. Significant findings were that riders wearing helmets. were 30 percent less likely to have TBI than riders not wearing helmets.
Dissemination Formats	Two fact sheets were developed. One fact sheet consisted of a one-page summary with bullets and two pie charts to inform policy makers and the general public about motorcycle crashes. The other fact sheet was a front and back detailed descriptive analysis on motorcycle crashes and motorcycle hospitalizations also using bullets, charts, and graphs. These fact sheets were presented and distributed during a CODES board meeting and put on the injury prevention Web site. One is currently posted at http://health.state.ga.us/pdfs/prevention/MotorycycleFactSheet-Professionals.pdf
Impact, Follow-Up,	Each year there are efforts to repeal the Georgia law (OCGA 40-6-315) that
or Later Development on the Targeted Issue	requires all motorcycle riders to wear a helmet. Efforts to repeal Georgia's motorcycle helmet law during the 2005-06 legislative session were unsuccessful.
	The fact sheets were discussed during a meeting of the Governor's Strategic Highway Safety Plan Risk, Analysis and Evaluation Team, and a summary of data related to motorcycles is included in the Strategic Highway Safety Plan emphasis area.

Georgia CODES

Georgia Department of Human Resources, Department of Public Health

State Application Presented at CODES Annual Meeting, 2007 Title: *Effects of Pickup Trucks Seat Belt Exemption*

Abstract: Currently, pickup trucks are exempt from the primary seat belt law in Georgia. Georgia CODES provided data to support the House bill to eliminate the current exemption in Georgia code pertaining to the use of seat belts in pickup trucks. Pickup truck occupants with no restraints were 2.7 times more likely to be admitted to the hospital than those who wore seat belts. The average total hospitalization cost for an unrestrained pickup truck occupant is \$44,000 compared to \$25,000 for restrained pickup truck occupants. Child occupants in pickup trucks had the highest proportion of unrestraint use in all passenger vehicles.

Contact Person and	Denise Yeager, 404-657-4776
Number	
Population/ Problem Targeted	Pickup truck crash injury rates statewide.
Targeted Issue	Seat belts as worn in both the front and back seat of all passenger vehicles including pickup trucks.
Requesting Office or Targeted Audience	Analysis requested by the CODES board of directors through its chair, the director of Governor's Office of Highway Safety. Other targeted audiences include the Division of Public Health, legislators, highway safety office/plan, injury prevention section.
Data Used	The years of imputed linked data used were 2001 and 2002. The 2001 linked data included crash, EMS, and hospital Inpatient data only. The 2002 linked data included crash, EMS, and hospital emergency department and inpatient discharge data. Missing values were not imputed. The hospital and crash data were in most cases complete and representative with the full crash data using vehicle type.
Methodology and Analytical Results	Linked data from crash records and inpatient hospitalizations for pickup truck related injuries were analyzed for median and average hospital charges, length of hospital stay, and primary payer sources. The odds ratio of a person that is admitted to the hospital without a seat belt compared to those who used seat belts was calculated. Significant findings were that occupants not wearing seat belts were 2.7 times more likely to be admitted to the hospital than those using seat belts.
Dissemination Formats	Information was included in the internal legislative impact statement for the Division of Public Health. A narrative was included in this statement and included a statement that CODES data was used. A fact sheet was developed and is viewable online at http://www.legis.state.ga.us/legis/2005_06/house/ Committees/motorVehicles/motorAgendas/MVhand2.pdf
Impact, Follow-Up, or Later Development on the Targeted Issue	Highway Safety Office and Division of Public Health supported House Bill 608 and Senate Bill 86 to eliminate the exception. The House did not vote on HB 608 and SB 86 passed the Senate.

Illinois CODES

Illinois Department of Transportation, Division of Traffic Safety

http://www.dot.il.gov/trafficsafety/IRTCC.html

State Application Presented at CODES Annual Meeting, 2007

Title: Inpatient Hospital Charges and Utilization Patterns of Crash Victims in Illinois

Abstract: Illinois has linked 2002 crash and augmented hospital inpatient discharge data to obtain information on traffic-related injury cases discharged from Illinois hospitals. Specifically, the data contains information on the number of discharges, average charges, average length of stay, primary injuries, types of crash controlling for demographics (age and gender), region, expected payment source and discharge status, vehicle type (passenger car, light truck, motorcycle), occupant restrained used, and several factors. Preliminary findings have been presented to the Illinois CODES Advisory Group and made available to the Illinois Traffic Records Coordinating Committee.

Committee.	
Contacts	Mehdi Nassirpour, 217-785-8905 Susan Fitzpatrick, 217-785-0281 Kristopher Boyer, 217-785-3041
Population/ Problem Targeted	All individuals involved in crashes in 2002 are included in this study of hospital inpatient charges and utilization patterns, and the health consequences of unrestrained drivers and passengers.
Targeted Issue	Develop support for safety legislation (primary belt for back seat passengers and helmet use).
Requesting Office or Targeted Audience	The Illinois CODES project was initiated by the Division of Traffic Safety at IDOT in cooperation with the Illinois Department of Public Health. Preliminary results of the linked crash and hospital discharge data were presented to the Illinois CODES Advisory Group, ITRCC, and Highway Safety Planning committee at IDOT.
Data Used	Illinois linked 2002 hospital inpatient discharge records with 2002 trauma discharge records in order to replace missing E-codes on hospital inpatient records with E-codes found on probabilistically linked trauma records. Illinois linked 2002 person level crash records with the 2002 augmented hospital inpatient discharge records using CODES2000's probabilistic record linkage procedures to create five separate multiply imputed data sets of linked records.
Methodology and Analytical Results	The imputed linkage results served as the input data set to SAS' PROC MI to create multiple imputations replacing missing values with estimated values. SAS' PROC MIANALYZE was used to evaluate means and standard errors from the PROC MI results.
Dissemination Formats	The following reports were presented to the CODES Advisory Committee and made available to the Illinois Traffic Records Coordinating Committee to illustrate the linkage process and overall results: • Descriptive statistics (e.g., number, mean, median) for charges and length of stay from four data sources: the source hospital inpatient data, the augmented hospital inpatient data, high probability linkages and imputed linkages. • Descriptive statistics for charges from the four data sources by three E-code response categories (motor vehicle traffic crash, other than motor vehicle traffic crash, and missing). Preliminary results were presented and discussed at the Illinois CODES Advisory Group meeting. These results included estimated average charges and length of stay by hospitalization variables (i.e., discharge status, site of first injury, payer type) and by crash variables (i.e., belt status, collision type, gender, helmet usage, intersection related, KABCO, number of vehicles, occupant position, region, road type, severity, time of day, and weekday/weekend).
Impact, follow-up, or later development	The presentation generated much useful discussion and suggestions for improvements in the linkage and reporting process. It also sparked increased interest in the CODES Project as evidenced by prompt follow-up to questions and suggestions.

Indiana CODES Indiana Department of Homeland Security http://cats.ecn.purdue.edu/CODES.aspx

State Application Presented at CODES Annual Meeting, 2007

Title: Effect of Seat Belt Usage on Hospital Charges by Vehicle Type

Abstract: Indiana has made significant strides in improving Statewide seat belt usage rates, with rates increasing from 62 percent in 2000 to around 84 percent in December 2006. New legislation that mandated front seat passengers to buckle up was largely responsible for this increase. Pickup trucks, however, were excluded from the law and usage rates for pickup trucks remained flat in Indiana from 2003–2006. As a new bill to close the exclusion for pickup trucks was being debated in the Indiana State House and Senate, CODES data were used in an attempt to show the financial and physical consequences of not wearing a seat belt. Crash, EMS, and hospital data for the years of 2003-2005 were linked using NHTSA's CODES2000 software.

The CODES data showed that on a yearly basis in Indiana, there were around 330,000 crash occupants, 130,000 EMS patients, and 550,000 in- and out-patients (filtered to include only patients that had an injury). Occupants of cars and pickup trucks that were linked to hospital data had their charges and length of stay cross tabulated as a function of their restraint usage status. Restrained occupants showed between 40 percent and 50 percent lower charges than nonrestrained occupants. The results were displayed in a fact sheet and presented to the Indiana TRCC and eventually passed on to legislators. House Bill 1237 passed the Senate 31 to 16 and the House 58 to 42 and was signed into law. This bill ended the exception in Indiana's mandatory seat belt law, and now requires all occupants, including backseat passengers in all vehicles, to buckle up.

occupants, including c	ackseat passengers in all venicles, to buckle up.
Contact Person and	Jose Eduardo Thomaz, Data Warehousing Administrator, Center for Road Safety, Purdue
Number	University, 765-406-1350, jthomaz@ecn.purdue.edu
Population/	Pickup trucks occupants were exempted from Indiana's seat belt law. The study was
Problem Targeted	targeted to legislators to demonstrate the effects of that legal exemption on hospitalization
	charges and length of stay.
Targeted Issue	Indiana seat belt laws only required seat belt use by front seat occupants, and exempted
	more than 1.4 million vehicles registered as pickup trucks (as well as vans and SUVs
	whose owners have paid an additional fee at the Bureau of Motor Vehicles to get a truck
	plate). The CODES team hoped to demonstrate the difference in hospital charges and length of stay of restrained and nonrestrained occupants, for both classes of vehicles, to
	support changing the legislation to close the pickup truck exception.
Requesting Office or	The preliminary results of the study were presented to the TRCC board, at the request of
Targeted Audience	the Indiana Criminal Justice Institute, Traffic Safety Division. A fact sheet was then
Turgeteu Tuurenee	passed on to the legislators.
Data Used	Crash, EMS and hospital data for the years of 2003–2005 were linked using NHTSA's
2	CODES2000 software. On a yearly basis, there were around 330,000 crash occupants,
	130,000 EMS patients and 550,000 in- and out-patients (filtered to include only patients
	that had an injury). Overall, between 4,500 and 5,000 vehicle occupants involved in
	crashes were successfully linked to EMS and hospital data. Another 21,000 vehicle
	occupants were linked to hospital data, but not to an EMS transport.
Methodology and	The analysis data underwent imputation during the linkage and the modeling process. The
Analytical Results	model was adjusted to accommodate Indiana data reliability levels, giving more emphasis
	on hospital data as covariates whenever possible, since hospital data have the highest
	reliability.
Dissemination	The CODES analysis was summarized in a fact sheet with tables and charts that broke
Formats	down hospital charges and lengths of stay by vehicle type, restraint use, and injury
	severity. This analysis made clear that charges for nonrestrained occupants were almost
	double those of restrained ones. These tables were discussed during the CODES/TRCC
	monthly meeting and quickly passed on to the Indiana senate members debating House Bill 1237.
Impact, Follow-Up,	House Bill 1237 passed the Senate 31 to 16 and the House 58 to 42 and was signed into
or Later	law. This bill closed the loophole in Indiana's mandatory seat belt law, and now requires
Development on the	all occupants, including back-seat passengers in all vehicles, to buckle up.
Targeted Issue	an occupanto, moracing back seat passengers in an venicles, to backle up.
1 an Botton 105000	

Iowa CODES Iowa Department of Public Health/Center for Vital Records and Health Statistics

http://www.idph.state.ia.us/apl/codes.asp

State Application Presented at CODES Annual Meeting, 2006

Title: Motor Vehicle Crash Related Traumatic Brain Injuries in Iowa (2001-2003)

Abstract: Analys	Abstract: Analyses were conducted to demonstrate the magnitudes of motor vehicle crash (MVC) injuries in Iowa,	
especially the traumatic brain injuries caused by MVC, to compare the differences between TBI and other injury		
type by risk facto	ors such as vehicle type, crash type, safety equipment, and financial consequences.	
Contact Person	Suning Cao, 515-281-3983	
and Number	Scott Falb, 515-237-3154	
Population/	Statewide MVC injured people who were hospitalized (2001–2004). Those who were linked to	
Problem	crash records (2001–2003) were analyzed by vehicle type, crash type, restraint use, age group,	
Targeted	and alcohol involvement by comparing injury type: TBI and non-TBI.	
Issue Targeted	Vehicle type, crash type, restraint use, younger riders, impaired drivers, and their interrelations.	
Requesting	As the co-chairperson of Statewide Traffic Records Coordinating Committee (STRCC), Scott	
Office or	Falb requested this study and we presented it together to the full member meeting of STRCC.	
Targeted	Also used for occupant restraint task force group within STRCC and Iowa's Safety	
Audience	Management Systems; Presented at Prevention of Disability Council meeting. Published at	
	IDPH CODES Web site to educate the public.	
Data Used	Three-year imputed crash-inpatient links (4,551 records, 2001–2003) were studied, including	
	occupants of passenger cars, van, pickups or SUVs, pedestrians, bikers, and unknown vehicle	
	type riders, who were hospitalized in Iowa.	

Methodology and Analytical Results

First, using Iowa hospital inpatient discharge data (2001–2004), to demonstrate the estimated medical costs of MVC-related TBI versus other injury type; children and younger riders versus adults:

- Each year about 2,000 people injured in MVC are hospitalized;
 - 27 percent of the hospitalized sustained TBI;

• Total medical costs for MVC TBI patients account for 60 percent of all MVC-related injuries costs. Second, an analysis compared linked cases (4,550 records, 2001–2003) by variables of vehicle type, crash type, impaired drivers and restraint use, etc. in two groups: TBI (n=1,292, 28%) and other injury (3,258, 72%). The odds ratios were calculated. Results:

- Not wearing a seat belt or helmet is a significant risk factor in sustaining TBI for MVC victims.
- Unrestrained pickup/SUV occupants were twice as likely to sustain TBI as the restrained, while unrestrained passenger car occupants were 1.5 times more likely to suffer TBI than restrained occupants.
 - 24 percent of passenger car occupants hospitalized were not wearing seat belts; 35 percent of pickup/SUV riders did not wear a seat belt

The TBI rate between pickup/SUV and passenger cars was not statistically different.

- Injured bicyclists were the most vulnerable to sustain TBI once involved in MVC: 54 percent of bicyclists were children between the age of 5 and 14.
- Injured pedestrians were the second most vulnerable group in suffering TBI. Pedestrians were 1.8 times more likely to sustain TBI than passenger car riders. 33 percent of the pedestrians sustaining TBI were under the age of 15.
- Impaired-drivers accounted for 15 percent of all hospitalized MVC injuries and they were 1.4 times more likely to sustain TBI than nonimpaired drivers.
- 44 percent of hospitalized MVC injuries occurred in single-vehicles crashes in Iowa, and single vehicle crashes were 1.3 times more likely to cause TBI than multiple-vehicle crashes.

TBI patients were 5 times more likely to die at the hospital than non-TBI patients.

Third, cost estimations demonstrated that:

• Estimated medical costs in Iowa for a TBI patient was \$120,060 (median value, 2003) versus \$11,924 for a non-TBI patients.

Estimated other costs for a TBI patient was \$127,654 versus \$61,728 for a non-TBI patient.		
Dissemination	Presented the analysis to STRCC meeting and to the Prevention of Disability Council	
Formats	Meeting	
Impact, Follow-up, or	The Iowa task groups are still finalizing all data resources. These data are included as	
Later Development	part of the proposed legislation for rear passenger safety-belt mandates.	

Iowa CODES

Iowa Department of Public Health/Center for Vital Records and Health Statistics

State Application, 2007

http://www.idph.state.ia.us/apl/codes.asp

Title: Iowa Motor Vehicle Crash Injury Facts Among Emergency Department Visits: A Profile of Unbelted Occupants of Passenger Cars and Vans/SUVs (2003)

Abstract: Analyses were conducted to demonstrate the magnitude of MVC injured people who visited Iowa emergency departments (2003), compare the differences among them by discharge status and seat belt use, and analyze the impact of non-belt use on ED patients' outcomes and medical charges.

	-
Contact Person and	Suning Cao, 515-281-3983
Number	Scott Falb, 515-237-3154
Population/ Problem Targeted	Statewide MVC injured people who visited emergency department and were linked to crash records.
Targeted Issue	Seat belt use and its association with age, gender, alcohol use or drug influence, ejection, air bag, crash location, seating position, collision type, and vehicle damage.
Requesting Office or Targeted Audience	As the co-chairperson of Statewide Traffic Records Coordinating Committee (STRCC), Scott Falb requested this study and we presented it together to the full member meeting of STRCC.
	Used for occupant restraint task force group within Statewide Traffic Records Coordinating Committee (STRCC) and Iowa's Safety Management Systems. Published at IDPH CODES Web site to educate the public.
Data Used	10,475 (95.5% of total crash and ED linked/imputed data for 2003) occupants of passenger cars, van, pickups or SUV, 16 or older, who were treated at ED's, were studied. Seat belt analysis excluded the cases where seat belt use was unknown (28% of ED links).
Methodology and Analytical Results	 First, crash-ED linked patients were compared in the demographic, TBI, medical charges, safety devices, vehicle, collision, and environment variables by three discharge status: 1. Discharged from ED; 2. Hospital Admission from ED; 3. Died at ED.
	Second, an analysis was narrowed down to the non-missing belt information cases by belted and nonbelted groups for comparisons.
	The result was that unbelted occupants are more likely to become inpatients and have a higher percentage of TBI than belted occupants.
Dissemination Formats	Distributed the fact sheet during STRCC meeting to show that by adding ED links the imputed linked cases increased to about 12,000 annually from about 2,000 inpatient links only.
Impact, Follow-Up, or Later Development on the Targeted Issue	Task groups are still finalizing all data resources. These data are included as part of the proposed legislation for rear passenger safety-belt mandates.

T D		
Iowa Do	epartment of Public Health/Center for Vital Records and Health Statistics	
	http://www.idph.state.ia.us/apl/codes.asp	
	State Application Presented at CODES Annual Meeting, 2007	
	Title: Motorcycle Quick Facts in Iowa – 2001-2005	
	rate the growing crash and injury rates among motorcycle riders in Iowa from 2001–2005,	
	ates per 1,000 motorcyclist licensed drivers – including fatality and injury rates – were	
	vas to show the growing number of injured riders (especially for people age 45 to 64) by	
	id the cost impact on government payer sources. Using 2003 crash-ED-inpatient-linked data	
	ociation between helmet use and brain injury and higher costs for the unhelmeted riders.	
Contact Person and	Suning Cao, 515-281-3983	
Number	Scott Falb, 515-237-3154	
Population/	Statewide motorcycle injured people, those who visited ED and those who were	
Problem Targeted	hospitalized, with regard to helmet use and brain injury.	
Targeted Issue	The high crash rate among young riders (age 15 to 24).	
	The increased crash rate among riders in the 35-to-54 age group.	
Degraating Office on	Helmet protection from brain injury and a lower helmet use in Iowa.	
Requesting Office or	As the cochairperson of Statewide Traffic Records Coordinating Committee, Scott Falb requested this study and we presented it together to the full member meeting of STRCC.	
Targeted Audience	requested this study and we presented it together to the full member meeting of STRCC.	
	Published at IDPH CODES Web site to educate the public.	
Data Used	One year crash-ED-inpatient imputed links (2003). For the fact sheet, only the first	
	imputed linked data set was analyzed, where cases without helmet use information (11%	
	of the total inpatient links) were excluded.	
Methodology and	First, using Iowa crash data from 2001–2005, motorcycle crash rate, fatality rate and	
Analytical Results	injury rate were calculated for each year to demonstrate the increasing crash and injury	
	rates in the State. By analyzing the crash rates by age groups, the results showed that younger motorcyclists, age 15 to 24, were 7.5 times as likely to have a crash than riders	
	older than age 24 on the five years average.	
	older than age 24 on the rive years average.	
	Second, using 2003–2005 Outpatient ED data, 2,510 motorcycle-related ED visits were	
	analyzed by age group, medical charges, and dispositions.	
	Third, using 2001–2005 inpatient data to show the increasing growth trend – a 9 percent	
	increase from 2001 to 2005-in Iowa's motorcycle-related hospitalizations. Among them,	
	the age groups 45 to 54 and 55 to 64 had the highest rate increases, 76 percent and 190	
	percent, respectively.	
	By using 2003 CODES linked data to demonstrate the strong link between not wearing a	
	helmet and sustaining severe TBI, CODES data show that while 24 percent of unhelmeted	
	riders had TBI, none of the helmeted riders suffered severe TBI and that there were higher	
	hospital charges for unhelmeted riders (2.3 times higher than for helmeted riders).	
	Conclusion: From the view of public health and safety, there is repeated evidence that	
	helmets prevent head injury and reduce the likelihood of a crash fatality.	
Dissemination	The fact sheet was distributed at the Iowa Motorcycle Safety Forum 2007.	
Formats		
Impact, Follow-Up,	These data results have been included in Iowa's Safety Management Systems within	
or Later	Traffic Safety. The data results are being used to support legislation and Iowa's goal of	
Development on the	mandating helmet use.	
Targeted Issue		

Kentucky CODES Kentucky Injury Prevention and Research Center www.kiprc.uky.edu/projects/CODES

State Application Presented at CODES Annual Meeting, 2006

Title: Economic Costs of Low Seat belt Usage in Kentucky

Abstract: NHTSA has published estimates of the effectiveness of seat belts in preventing fatal and nonfatal injuries. The estimated effectiveness varies depending on the type of vehicle (passenger car versus light truck), the type of seat belt used (lap belt only versus lap and shoulder belt, and the occupant's seating position. Linked collision report and hospital discharge data were used to estimate Kentucky's overall seat belt effectiveness for preventing moderate-to-critical injury at 55 percent. This number was then used to calculate medical cost savings for Kentucky's Medicaid program and other payers that would result from enactment of a primary enforcement law. Particular attention was given to traumatic brain injuries and spinal cord injuries because they often result in medical costs for multiple years after the original injury.

Contact Person and Number	Michael Singleton, 859-257-5809, msingle@email.uky.edu
Population Targeted	Motor vehicle occupants
Traffic Safety Issue Targeted	Support for primary belt use
Requesting Office or Targeted Audience	Requested by the Kentucky Transportation Cabinet, Dept of Highway Safety. Target audience also includes governor and State legislators.
Description of linked data	The primary data sources were the State hospital discharge databases for 2000–2004. The CODES database, with multiply imputed links for 2003, was used to generate a Kentucky-specific estimate of the effectiveness of seat belt usage in preventing injuries and fatalities, which varies depending on seating position, vehicle type, and seat belt type.
Analytical Results	It was determined that with the passage of a primary seat belt law in 2006, 57 lives could be saved and 307 hospitalizations could be prevented annually, an overall savings of at least \$118 million in direct medical costs over the ten-year period from 2006 to 2015. Of this total, \$34 million could be saved in total direct medical costs to Medicare alone. In addition, there would be at least \$68 million saved in medical costs to commercial insurers, \$23.3 million to Medicare, \$3.3 million to Worker's Compensation, and \$11.2 million to other sources.
Dissemination Formats	The Kentucky Transportation Cabinet provided copies of the report to all legislators. Many legislators, as well as the Governor, used the information regarding the number of lives saved during the debate and press conferences. The Transportation Cabinet led 12 "Saved by the Belt" rallies across the State and the information from the report was used in these rallies.
Impact, Follow-Up, or Later Development on the Targeted Issue	The Kentucky legislature passed a primary enforcement bill in the 2006 General Assembly. The CODES report was one of a number of factors that preceded its passage. In addition to the injury prevention and Medicaid considerations, there were several million dollars of federal highway incentive funds available to the State contingent on passage of the bill. There was debate in the legislature on Medicaid cost savings, but the main debate focused on saving lives and the incentive funding for highways.
Notes	These savings would be a direct result of an increase in the number of Kentuckians who would wear a seat belt if a primary enforcement law were in place. States that have enacted primary enforcement legislation have experienced increases in seat belt use of as much as 18 percentage points. NHTSA has stated that the average increase is between 10 and 15 percentage points. The savings given above assume that Kentucky would experience an increase of 14 percentage points, which would move the State's usage rate from 67 percent to 80 percent, which was the national average in 2004.

Kentucky CODES Kentucky Injury Prevention and Research Center www.kiprc.uky.edu/projects/CODES

State Application Presented at CODES Annual Meeting, 2006 Title: Injuries to Booster-Age Children in Kentucky, 2000-2004

Abstract: Kentucky passed a primary seat belt law in 2006 without passing a booster seat law, which left many children age 4 to 8 at risk, due to being improperly restrained in lap/shoulder belts only. According to NHTSA, 80 percent to 90 percent of all children in the U.S. who should be restrained in a booster seat are not. Kentucky's linked, imputed crash and hospital database was used to compare injury diagnoses between restrained 4 to 8 year old occupants and restrained occupants of other ages. The findings confirmed that among restrained occupants who were hospitalized, a principal diagnosis of abdominal injury was more common among booster-age children than other age groups. A fact sheet was created that focused on the outcomes (injury type, hospital charges, hospital length of stay, etc.) for restrained and unrestrained children 4 to 8 years old, compared with other age groups.

Contact Person and Number	Mike Singleton, 859-257-5809, msingle@email.uky.edu
Population/	Children of booster seat age (typically between age 4 to 8 years) who should be
Problem Targeted	restrained in booster seats, but usually are not.
Targeted Issue	Advocate for increased use of booster seats and passage of booster seat legislation to reduce injury severity among young children.
Requesting Office or Targeted Audience	Booster seat coalition, Legislators, Governor's Executive Committee on Highway Safety
Data Used	Kentucky's 2000–2004 crash data, inpatient data, and the linked, imputed data were used to do this application. The data linkages were performed using CODES2000 version 6.1.
Methodology and Analytical Results	Using the linked, imputed data, injuries to children ages 4 to 8 who were restrained in a child safety seat (CSS) were compared to those who were not restrained in a CSS, according to the police crash report. Those children who were restrained in a CSS were 40 percent less likely to be hospitalized than those who were not; they also had lower hospital charges, length of stay in hospital, and overall injury severity score.
Dissemination Formats	At the 2007 Kentucky Lifesavers Conference in April, which is sponsored annually by the Department of Transportation Safety, the findings were presented. Video clips were used to demonstrate the biomechanical and injury issues related to booster seat usage. Tables and charts based on CODES data were also presented.
Impact, Follow-Up, or Later Development on the Targeted Issue	The Kentucky legislature passed a booster seat bill during the 2008 General Assembly that applied to kids age 4 to 7. The law went into effect on July 15, 2008.

Maine CODES Maine Health Information Center

www.mhic.org/CODES

State Application Presented at CODES Annual Meeting, 2006 Title: *Maine CODES Claims Data Bank Project*

Abstract: In 2001, the Maine Legislature and Governor King approved LD 1304 An Act to Create the Maine Health Data Processing Center (MHDPC). The MHDPC collects administrative eligibility, medical, pharmacy, and dental insurance claims from all payers providing insurance to Maine residents. 2003 was the first year of data collected for this new claims data bank (DBANK).

As one of the first projects to use this new data resource, the Maine CODES project has linked 2003 CODES injured occupants to 2,463 people in the claims data bank. For these 2,463 people, a total of 200,845 service line claims tracking up to 18 months of medical care post-crash. An algorithm was developed to determine which post-crash claims were related to the crash injuries and which were pre-existing or new medical claims for each person.

Overall, the post-crash expense—on a per-person, per-month basis—increased by 140 percent with higher rates of increase for crashes involving moose, rollovers, alcohol-related, and rural locations. The average expense for an unrestrained injured occupant (\$9,272) was 3.7 times a restrained occupant (\$2,491).

Of the \$10.5 million in crash-related injury expenses, \$4.5 million (39%) were non-hospital provider claims. Among the 2,463 occupants, claims data indicated that 3 percent were hospitalized in ICU, 8 percent had an operation, 436 (18%) had a CT-Scan, and 299 (12%) had follow-up physical therapy. Furthermore, 425 (17%) of these occupants were still receiving care and treatments for their crash injuries 90 days or more after the crash.

Contact Person and Number	Karl Finison, Maine Health Information Center (MHIC), 207-430-0632, kfinison@mhic.org
Population Targeted	All 2003 Maine CODES occupants with linked medical records linked to statewide medical insurance claims data.
Traffic Safety Issue Targeted	Provides new information about the long-term medical impact and expense of motor vehicle crashes. Provides new outcome metrics that incorporate information beyond the hospital setting.
Requesting Office or Targeted Audience	The Data Bank project was a separately funded project we developed with NHTSA support. It was supported by all Maine offices represented on the Maine Advisory group. The Maine Health Data Organization is the State office that controls the statewide claims data base that was linked and used in this analysis. Other potential audiences include the Governor, Legislators, Highway Safety and Injury Prevention Programs.
Description of linked data	2003 Maine CODES crash occupants with linked medical records were linked to new statewide claims data bank. 2,643 injured occupants linked to the claims data bank. For these 2,643 people, 200,845 service line medical and pharmacy claim line services were identified for the 18-month period from January 2003 to June 2004 (most current data available). The claims data contains ICD-9 diagnosis (up to 10) to identify injury types as well as CPT, Revenue, and RX NDC coding to identify types of service. This is a first look at services provided or billed outside of the hospital setting.
	Algorithms were developed to distinguish the claims that were related to injuries resulting from the crash from non-injury or pre-existing injuries using the Barell Matrix coding, which was used to assist in the process and Maine incorporated ICD-9 codes and medication for "pain."
	Limitations: The Maine claims data bank is currently limited to Maine residents with private medical insurance; work continues to add Medicaid and Medicare claims. Claims paid by auto insurance are not included.

Maine CODES	
	Maine Health Information Center
	www.mhic.org/CODES
	State Application Presented at CODES Annual Meeting, 2006
	Title: Maine CODES Claims Data Bank Project
Analytical Results	The resulting CODES-DBANK is a longitudinal data base. 2,463 people with 200,845 claims were linked (47,452 claims were crash-related injury claims). Analyses had the following parameters:
	1. Claim Type: Claims are categorized as crash-related injury or non-crash-related (e.g., mammogram, office visit for sore throat, inpatient maternity hospitalization, pre-existing injury claims). For the 2,463 people linked, the per member per month (PMPM) claims expense increased from \$328 pre-crash to \$786 post-crash. \$358 of the PMPM increase was due to claims identified as crash-related injury claims.
	2. Time from crash: Injury claims by time interval post-crash (days, weeks, and months). 425 (17%) of the occupants were still receiving care and treatments for their crash injuries 90 days or more after the crash. 154 (6%) were still using prescription pain medication for their injury 90 days or more after the crash.
	3. Injury types: Crash-related injury claims are reported by the Barell Body Region of Injury (ISRSITE2) and Barell Nature of Injury (ISRCODE). Fractures of the lower extremities, TBI, internal torso, spinal and vertebral column injuries were leading contributors to medical claims expense. 177 (7%) had a TBI injury and 143 (6%) had a lower extremity fracture.
	 4. Service types: Crash-related injury claims are reported by setting (e.g., inpatient, outpatient hospital, professional) and types of service (e.g., ICU, operating room, CT scans, physical therapy, office visits). Of \$10.5 million in crash-related injury expenses, \$4.5 million (39%) were non-hospital claims. The 2,463 occupants claims indicated that 69 (3%) were hospitalized in ICU, 197 (8%) had an operation, 436 (18%) received a CT Scan, 299 (12%) had physical therapy.
	5. Crash variables and selected outcome metrics: Crash-related injury claim selected indicators (e.g., claims expense, ICU, CT scans, occurrence of crash-related injury claims more than 30 days post-crash) are tabulated by selected police-reported crash variables (e.g., age of occupant, gender of occupant, seating position of occupant, vehicle type, crash type, speed limit on roadway, alcohol-related, and safety device use—such as seat restraints, air bags, and helmets). The highest increase in post-crash expenses PMPM were motorcyclists without helmets (1048%), crashes involving moose (968%), and rollovers (430%). Furthermore, 9 percent of occupants in alcohol-related crashes were hospitalized in ICU compared to 2 percent in non-alcohol related.
Dissemination Formats	Maine CODES creates written reports and PowerPoint presentations. <u>www.mhic.org/CODES</u> . In cooperation with the Maine Office of Data, Research, and Vital Statistics, Maine CODES creates fact sheets that are distributed via the Maine Bureau of Health Web site <u>http://www.maine.gov/dhhs/bohodr/fact_sheet_index.htm</u>
Impact, Follow-Up, or Later Development on the Targeted Issue	Data is new and has not been released. Results will be reviewed with Maine CODES Advisory Committee on May 24, 2006.

Maine CODES Maine Health Information Center www.mhic.org/CODES

State Application Presented at CODES Annual Meeting, 2007

Title: Adjusting for Seat Belt Reporting: The Problem of Differential Misclassification

Abstract: During the past 15 years, efforts to increase the use of seat belts in Maine resulted in passage of a secondary seat belt law in 1997 and a primary seat belt law in 2007. At the request of the Maine CODES Advisory Committee, CODES data has been used to support efforts to identify the benefits of seat belts, increase usage, and support legislative review. Differential misclassification of seat belt use results in inaccurate surveillance reports and exaggeration of the benefit of seat belts; the Maine project has adjusted the analyses for this problem. This presentation reviews the problem of differential misclassification of seat belt use in police crash reports and explores a method of correcting for missing data and differential misclassification using CODES linked data.

Contact Person and Number	Karl Finison, Maine CODES, 207-430-0632. kfinison@mhic.org
Population/ Problem Targeted	Differential misclassification of seat belts in police crash reports. Uninjured or slightly injured occupants in crashes have an opportunity and often a motive to say they were wearing seat belts when they were not. This results in differential misclassification of seat belts in FARS, CODES, and other data based on police-reported information. The problem results in over-reporting of belt use rates in surveillance reports and biased estimates of the effectiveness of belts.
Targeted Issue	Increase understanding of seat belt usage and improved analyses
Requesting Office or Targeted Audience	This was a special project developed for the Charleston CODES Technical Assistance meeting in order to focus attention on a need and examine possible solutions. The methods developed have been used over the years for a variety of reporting and analyses of the seat belt issue in Maine, requested by our Maine Advisory group – primarily the Maine Bureau of Highway Safety.
Data Used	Maine CODES has used linked data since the 1991 crash data year for five different reports/analyses on seat belts. In this presentation, an example using 2003 linked imputed data compares risk estimates, adjusted for missing values, and adjusted for missing values and differential misclassification.
Methodology and Analytical Results	Different methodologies are described. Methodology and results using imputed methods to adjust for differential misclassification and results are presented,
Dissemination Formats	Surveillance reports, analytical reports, fact sheets, and PowerPoint presentations have been used, and the results have been provided to the Maine CODES Advisory Committee, the Maine Bureau of Health, the Governor's Office, and the State TRCC. The results have also been published on the Internet at: www.mhic.org/CODES
Impact, Follow-Up, or Later Development on the Targeted Issue	Fact sheets developed by Maine Bureau of Health from CODES data. CODES data used by Governor's office and various committees supporting seat belt legislation over a 15- year period. A primary seat belt law was passed in 2007.

Maryland CODES

National Center for Trauma/EMS, University of Maryland-Baltimore http://medschool.umaryland.edu/NSCforTrauma//codes.asp State Application Presented at CODES Annual Meeting, 2006

Title: CODES Data Warehouse Using Data for Strategic Planning and TRCC

Abstract: Over the years, the CODES program in Maryland has evolved to become a defacto Data Warehouse for statewide Highway Safety Data. In addition to the three core data sets (crash, EMS, hospital) the Maryland CODES has added a significant number of ancillary data sets including licensing, registration, citation, motorcycle training, trauma registry and other that have been used individually and collectively for a variety of highway safety topics. In addition to responding to numerous data queries CODES has developed general and program-specific fact sheets, contributed data for use in the State's Highway Safety Office's annual and benchmark reports, been a regular participant in the State's Traffic Records Coordinating Committee and provided data for problem identification to each of Maryland's twenty four subdivisions. Recently, Maryland CODES has also been able to use ancillary data sets to improve blood alcohol content test reporting for NHTSA's Fatality Analysis Reporting System. During the past year, the CODES project has contributed data and expertise to the State Highway Administration to assist in the development of a statewide strategic plan that will guide the direction of traffic records and highway safety in the State for the next several years. Data supplied through CODES has been used to help the planning committee develop a list of priorities to be addressed by each program area subcommittee. Currently CODES data is being used by the Highway Safety Office to support strengthened impaired driving and young driver bills for the current legislative session and to support the 408 grant application process by providing measurable performance measures.

Contact Person and Number	Timothy Kerns, University of Maryland/National Study Center for Trauma and EMS, 410- 328-4244, tkerns@som.umaryland.edu
Population Targeted	CODES data is available as a resource for all State and local agencies as well as other stakeholders in highway safety.
Traffic Safety Issue Targeted	Maryland CODES is becoming established as a principal source of data and analysis for highway safety questions within the State.
Requesting Office or Targeted Audience	The TRCC, the Strategic Planning Committee, State Highway Administration and State legislators.
Description of linked data	Data sources: Crash reports, hospital discharge, citations, trauma registry, licensing, registration, motorcycle training, and other smaller data sets related to highway safety.
Analytical Results	Extensive analysis of various program areas including younger and older drivers, impaired driving, aggressive driving, inattentive driving. Development of a Traffic Safety Fact Book modeled on the version published by NHTSA along with program and county specific fact sheets for use within the State.
Dissemination Formats	Presentations given at recent strategic planning committee meetings and TRCC meetings, summary analysis reports and fact sheets. All information can be obtained through a Web site that is currently being updated to focus on CODES activities.
Impact, Follow-Up, or Later Development on the Targeted Issue	Data provided through CODES were used extensively in setting priority areas for strategic planning, problem identification, safety analysis, and program evaluation.

Maryland CODES National Center for Trauma/EMS, University of Maryland-Baltimore <u>http://medschool.umaryland.edu/NSCforTrauma//codes.asp</u> State Application Presented at CODES Annual Meeting, 2007 Title: Comprehensive Crash Outcome Data Evaluation System

Abstract: Data available through the Maryland CODES project are compiled into multiple annual reports covering a number of program areas that are used extensively by State highway safety partners for problem identification and program evaluation. These reports include: (1) Impact Objectives; (2) State of the State; (3) State of the County; (4) Crash-Crime clocks; (5) Program Area Over-Representation; and (6) Comprehensive State and County Fact Books. Further, CODES data are used in the annual benchmark report provided by the State's Highway Safety Office to the regional NHTSA office and in their annual report provided to the Maryland Department of Transportation. Also, CODES data have been used in the preparation of Maryland's 408 application, to support Maryland's Traffic Records Coordinating Committee, and to provide data for motorcycle and impaired driving assessments. Contact Person and Timothy Kerns University of Maryland/National Study Center for Trauma and EMS, 410-Number 328-4244, tkerns@som.umaryland.edu Population/ Impaired driving, young drivers, older drivers, motorcycles, inattentive driving, aggressive Problem Targeted driving, occupant protection, and pedestrians. Targeted Issue To provide data-driven problem identification and evaluation for a variety of highway safety topics in Maryland. Requesting Office or Maryland Highway Safety Office, Community Traffic Safety Program, Maryland Targeted Audience Legislators Data Used A variety of data available through the CODES project is used in the development of our standardized reports. The data include crash, EMS, emergency department, hospital, citation, licensing, toxicology, and vehicle registrations which are used individually and through the use of linkage to develop the most appropriate reports. Normally, the most recent three years of data are included in the analysis. Imputed data sets are used as appropriate and, with the development of the data model tools, will become increasingly incorporated into our annual reporting. Methodology and The methodology for the use of imputed data follows the model developed by the CODES Analytical Results work group. Other reports use simple frequencies, means, and medians. Comparisons are most commonly made using chi-square and t-tests.

Dissemination	Data and reports are provided on paper and in electronic formats. These reports are also
Formats	made available through the Internet at http://nsc.umaryland.edu. In addition,
	approximately 20 data presentations are given to various highway safety groups
	throughout the year in Maryland.
Impact, Follow-Up,	Through the comprehensive approach, CODES has played an increasingly crucial role in
or Later	the development of the State's Strategic Highway Safety Plan and in the identification of
Development on the	emerging highway safety problems and the evaluation of current programs.
Targeted Issue	

Massachusetts CODES UMassSAFE, University of Massachusetts

www.ecs.umass.edu/umasssafe/codes.htm

State Application Presented at CODES Annual Meeting, 2006

Title: Evaluation of Frequency and Injury Outcomes of Lane Departure Crashes

Abstract:

Abstract: Lane departure crashes account for approximately 19 percent of all crashes in Massachusetts but almost 46 percent of crashes involving fatal injuries. A lane departure crash occurs when a vehicle leaves the travel lane resulting in a collision. Lane departure crashes typically involve running off the road onto the right or left shoulder and hitting a fixed object, such as a tree, a pole or even a parked vehicle. However, lane departures could involve crossing into an opposite lane and colliding with a vehicle traveling in the opposite direction. Although the vast majority of lane departure crashes are collisions with fixed objects, it can be argued that lane departures resulting in crashes between two moving vehicles are potentially more severe and costly. Therefore, countermeasure implementation strategies should consider not only frequency but also crash costs and severity.

Crash data alone are insufficient to effectively evaluate crash injury and cost outcomes. Additional injury data can be gathered by complementing crash data with medical information. The CODES links data collected at the crash scene to hospital databases that contain specific injury data; this provides an enhanced understanding of crash injury outcomes by tracking crash victims through the health care system. Massachusetts CODES data were analyzed to examine injury outcomes of lane departure crashes considering hospital charges and length of stay. Results of the analysis would provide a basis for determining where to implement countermeasures based on crash cost and severity rather than frequency alone.

frequency alone	frequency alone.	
Contact Heather Rothenberg, UMassSAFE, 413-577-4304		
Population	Requested in conjunction with other related analyses by the Massachusetts Highway Department;	
Targeted	other targeted audiences include Safety Analysts and Traffic Engineers working on Mass. issues	
Traffic Safety	This analysis served to provide a preliminary overview of outcomes associated with lane departure	
Issue Targeted	crashes to guide programming and countermeasure implementation. Specifically, the differences in	
	outcomes (charges and length of stay) for head-on crashes in comparison to single vehicle run-off-	
	road crashes were examined. Although single vehicle run-off-road crashes are far more frequent, the	
	hypothesis was that head-on collisions had higher charges and were more injurious; therefore,	
	countermeasure implementation should consider not only crash frequency but also severity.	
Requesting	Massachusetts Highway Department, Safety Analysts and Traffic Engineers	
Office or		
Targeted		
Audience		
Description of	Crash data were linked to inpatient discharge data for FY2003 (data available at time of linkage).	
linked data	Both high probability and multiply imputed links were used in the analysis. For the 12 months of	
	linked data, the average number of links in the imputed data was 3,362 linked record pairs. Of those,	
	the average number of pairs identified as cases resulting from lane departure crashes was 1,021 cases,	
	which corresponds to 30 percent of all linked pairs. Furthermore, 240 cases were categorized as lane	
	departure head on crashes (23 percent of lane departures) and 781 cases were categorized as single	
Analytical	vehicle run-off-road crashes (77 percent of lane departures). Hospital charges were found to be higher for lane departure crashes than for all crash types (\$18,460	
Results	versus \$16,302). In addition, when examining the two specific categories, lane departure head on	
Results	crashes showed higher hospital charges than single vehicle run-off-road crashes (\$20,413 versus	
	\$17,918). In terms of length of stay in hospital associated with crash injuries, there were no	
	differences between all crashes and lane departures crashes. However, median length of stay	
	associated with injuries from lane departure head-on crashes was found to be one day longer than	
	length of stay associated with single-vehicle run-off-road crashes.	
	ingle of surf associated with single ventore fail off foud effolies.	

Massachusetts CODES UMassSAFE, University of Massachusetts www.ecs.umass.edu/umasssafe/codes.htm State Application Presented at CODES Annual Meeting, 2006			
Title	Evaluation of Frequency and Injury Ou	-	
Analytical Results (continued)	Median charges and length of stay were also crashes that were single vehicle run-off-road collided with. Hospital cases resulting from c median were the two types that had the highe of stay in hospital.	examined for injuries as crashes broken down by ollisions with trees and	sociated with lane departure the object the vehicle run-off-road left or crossing
	Object Collided With	Median Hospital Charges	Median Length of Stay (days)
	Tree	\$22,197	4.0
	Post, utility pole or light pole	\$15,709	3.0
	Guardrail, median barrier or crash cushion	\$16,289	3.0
	Curb, ditch, or embankment	\$16,361	3.0
	Parked vehicle	\$18,480	4.0
	Ran off road left or cross median	\$21,281	3.0
	Ran off road right	\$14,838	3.0
	Other/unknown	\$17,827	3.5
Impact, Follow- Up, or Later Development on the Targeted	of Transportation Engineers in August 2006 a Compendium of Papers. Lane departure data analysis has been an ong between the MassHighway safety analysts an CODES data can be used and the benefits of data.	oing project for MassHi d UMassSAFE have inc	ghway and the dialogue luded a discussion of how the
Issue Comments	Data from NHTSA's National Automotive Sa (NASS-CDS) and FARS were used to evalual consider the two categories of lane departures Conclusions: Lane departure crashes result in other types of crashes, which makes them a s reduce the frequency and severity of these type engineers. By complementing the analysis cra- given that allows for not only injury severity, lane departure crashes. The two categories of compared in terms of injury severity, hospital crashes were found to result in more severe in stay in hospital than single vehicle run-off-ro single vehicle crashes colliding with a tree or collisions with trees and single vehicle runnin charges and days in hospital among single ve	te lane departure crashe s defined for study. a a much higher proporti erious concern in traffic pes of collision should b ash data with CODES da but also the associated l charges, and length of njuries and had higher as ad crashes. Crash data s a pole. CODES data sh ng-off-left or crossing m	s for 2002–2004 and to on of severe injuries than safety. Countermeasures to e a priority for transportation ata, additional information is cost of injuries resulting from identified in this study were stay. Lane departure head-on ssociated costs and lengths of howed higher frequency of owed that single vehicle

Massachusetts CODES

UMassSAFE, University of Massachusetts

www.ecs.umass.edu/umasssafe/codes.htm

State Application Presented at CODES Annual Meeting, 2007

Title: Crash Outcomes for Older Occupants of Motor Vehicles in Crashes

Abstract: Greater fragility has been shown to contribute to high fatality rates among older road users. This project used linked crash and hospital data to examine charges, length of stay, injury body region, and nature of injury for two categories of older vehicle occupants (65 to 84 and 85+) with adults (25 to 64) as comparison. Results were presented in several formats including fact sheets, report, and presentation to the Massachusetts CODES Advisory Board and Massachusetts Traffic Records Coordinating Committee. The findings of these analyses have provided information for the ongoing discussion around older vehicle occupants involved in crashes, specifically around older drivers. Previously, similar analyses were coupled with a review of policy and legislation around teen drivers to support decision-making around Massachusetts Graduated Driver Licensing laws. This review will integrate these results as part of the work aimed at identifying options for improved licensing practices for older drivers and assessing alternative transportation methods for older residents of Massachusetts (such as improved transit, etc).

transit, etc).	
Contact	Heather Rothenberg, Project Coordinator/Lead Analyst, University of Massachusetts Traffic Safety Research Program, 413-577-4304, hrothenb@acad.umass.edu
Population/ Problem Targeted	Older drivers and older occupants of motor vehicles in crashes
Targeted Issue	Initial review of older driver/older person safety in Massachusetts with focus on policy issues around older drivers.
Requesting Office or Targeted Audience	Requested in conjunction with other related analyses by the Massachusetts Traffic Records Coordinating Committee, particularly the Registry of Motor Vehicles and Department of Public Health
Data Used	Data used: 2002-2003 for inpatient discharge, emergency department, crash, and citation. The use of multiple datasets allowed for an examination of older driver and older occupants of motor vehicles in a manner that would not have been possible using any one dataset alone. The use of linked data allowed for the consideration of older driver behavior as well as the crash outcomes associated with older people involved in crashes. The high quality associated with both hospital and citation data led to results that were considered highly reliable by members of the TRCC.
Methodology and Analytical Results	The analysis of data was presented using the results of the CODES linkage based on multiple imputations of missing links. Analyses included descriptive statistics for fields such as violations and crash frequency. In addition, the analysis of linked data considered charges for emergency department and inpatient separately due to scale (median charges) and the use of the Barell Matrix and odds ratios for six injury types and six injury locations on the body. Analyses considered older people (65 to 84) and much older (85+). When there were not enough cases for the much older category, the two were combined (65+). Some of the key findings are below; additional findings can be found in the report or fact sheet. TBI type 1 injuries were two times more likely in <i>older</i> occupants and four times more
	IBI type I injuries were two times more likely in <i>older</i> occupants and four times more likely in <i>much older</i> occupants, when compared to <i>adults. Older</i> and <i>much older</i> vehicle occupants have a greater likelihood of suffering injuries to all body regions than <i>adults</i> , with the exception of spine and back injuries.

	Massachusetts CODES
	UMassSAFE, University of Massachusetts
	www.ecs.umass.edu/umasssafe/codes.htm
	State Application Presented at CODES Annual Meeting, 2007
Title:	Crash Outcomes for Older Occupants of Motor Vehicles in Crashes
Methodology and Analytical Results (continued)	 Older and much older vehicle occupants have lower inpatient charges resulting from crash injuries but have significantly higher emergency department charges than adults used as a comparison. When considering charges, the only age group where there was a significant difference between drivers and passengers was for inpatient charges for older occupants. There are no notable differences in emergency department or inpatient charges between drivers and passengers for adults or much older occupants. Older and much older occupants were also more likely to suffer fractures, internal organ injuries, open wounds and superficial injuries/contusions than adults; they were less likely to suffer sprains and strains. The proportion of movement related violation (lane violations, failure to stop, turning violations) were notably higher for older drivers (65+) than for other drivers (<65). Broad scope violations (leaving the scene, general violations, severe violations) accounted for a small percentage of violations for older drivers (65+) and other drivers (65+).
	• For both older drivers and other drivers, risky behavior violations (alcohol, seat belt use, and speeding) accounted for the largest proportion of violations issued. The proportion of risky behavior violations were similar for older drivers (65+) and other drivers (<65).
Dissemination	Results of the analysis were presented in three formats:
Formats	Report: A report on the findings, specifically around the analysis of linked crash and hospital data, included a description of the linkage process, statistical methods, used, etc. as well as results. This document was designed for someone such as an analyst at another State agency. The use of specific information and more detailed formulas made this document most effective for the designated audience.
	Fact Sheet: The fact sheet presented a brief summary of findings with no explanation of the linkage. This fact sheet was designed for someone in a State agency who has some experience "reading numbers" but who is not necessarily an analyst. The inclusion of "dollars" made this document especially appealing to those considering traffic safety from a policy perspective.
	TRCC Presentation: A presentation was given to the TRCC outlining the process and the findings. This presentation included some basic information on the linkage and analysis but focused primarily on findings followed by a discussion on how TRCC members might use the information and data that might be added to the linkage to provide additional detail for future analyses. The combination of results and process made this most effective for the TRCC as TRCC members are interested in where the data came from, how it was analyzed, and what the results show. This presentation was the same as the presentation given to the CODES advisory board.
Impact, Follow-Up, or Later Development on the Targeted Issue	Based on the continued interest in older drivers and data-driven policy making, the Massachusetts Registry of Motor Vehicles has submitted a project problem statement to the Executive Office of Transportation's Cooperative Research Program to undertake a data-driven policy and legislative review. This review will integrate the findings of the data to identify options for improved licensing practices for older drivers and assess alternative transportation methods for older residents of Massachusetts.

	Minnesota CODES
	Minnesota Department of Public Safety/Department of Health
	www.health.state.mn.us/injury/topic/topic.cfm?gcTopic=9
	State Application Presented at CODES Annual Meeting, 2006
	Title: Estimating Minnesota Hospital Charge Savings With the
	Adoption of a Standard Enforcement Seat Belt Law
Study Coole: M	leasure hospital medical care charges associated with unrestrained motor vehicle occupants in
Minnesota. Det	ermine cost impact on government payer sources and estimate the likely impact of a standard (primary)
enforcement sea	
Contact	Anna Gaichas, 651-201-5478, anna.gaichas@state.mn.us
Person and Number	Mark Kinde, 651-201-5447, mark.kinde@state.mn.us Scott Hedger, 651-201-7066, scott.hedger@state.mn.us
Number	(Historical) Tina Folch, Minnesota Department of Public Safety Office of Traffic Safety
Population	The study focused on motor vehicle occupants and seat belt use. Emphasis was placed on two types of
Targeted	injuries caused by traffic crashes, traumatic brain injury and spinal cord injury.
Traffic Safety	Unrestrained motor vehicle occupants in Minnesota.
Issue	omestanica notor venere occupants in transcoord.
Targeted	
Requesting	After numerous failed attempts to pass the primary seat belt enforcement law, it became apparent that
Office or	a measure of the economic impact of not wearing a seat belt was necessary. The Minnesota
Targeted	Departments of Public Safety and Health along with the Minnesota Safety Council initiated this study.
Audience	The target audience was policy makers, such as the Minnesota Governor and the Minnesota State
	Legislature.
Description of	Individuals in Minnesota crashes that occurred during 2002 were linked with hospital emergency room
linked data	and inpatient treatment information, the Traumatic Brain Injury Registry, and death certificate data.
	The linked data are referred to in this report as the 2002 CODES dataset. Although the TBI/SCI
	Registry and the hospital discharge dataset which were linked to the 2002 crash record have external
	cause of injury codes (E-codes) – for the purposes of the analysis, only cases that linked to a crash
	report were used. For this report, analysis only included people who were motor vehicle occupants.
	Seat belt use was imputed for those cases where seat belt use was unknown. Lastly, cost savings were
	only calculated for those cases where the individual was not belted and the linked hospital record had
A	an injury coded (versus a non-injury coded).
Analytical	If Minnesota upgraded its seat belt law to standard enforcement in 2006 and reached a use rate of 94
Results	percent, the cumulative charge savings to all government payer sources is projected to be \$85.2 million by 2015. Injuries availed in the first user alone would gave Medicaid \$2.4 million. The
	million by 2015. Injuries avoided in the first year alone would save Medicaid \$3.4 million. The cumulative savings to Medicaid would be \$70.9 million by 2015.
Dissemination	A 26-page report and accompanying fact sheet were produced for distribution. On behalf of the
Formats	Minnesota Seat Belt Coalition, the Minnesota Safety Council held a press conference at the State
1 officials	Capitol focusing on the results of the CODES report and the need for a belt law-upgrade to pass.
	Senate leaders spoke on the proposed primary seat belt bill and its potential economic impact in
	Minnesota. Later that day, the Senate passed the primary belt bill—with a floor vote showing a 2 to 1
	margin in favor of the bill. Because of the passage of the Senate bill, media around the State
	disseminated the story by television, radio, and print communications. The fact sheet and full report
	were distributed through statewide e-mail distribution lists to law enforcement, public health
	educators, and other traffic safety advocates. The report was highlighted on the Office of Traffic
	Safety and Department of Health's Web sites and is currently available at
	http://www.dps.state.mn.us/ots/crashdata/CODES/MNCODES_BELTS_REPORT_March13_2006.pdf
	Data will continue to be used in various publications and presentations that discuss the economic
	impact of crashes.
Later	The report was used to gather support in the Minnesota Senate for passage of a primary belt bill, which
development	was successfully signed into law on May 21, 2009. However, prior to 2009, the House of
on the	Representatives continued to display strong opposition to a belt law upgrade. During negotiations of
targeted issue	the Transportation Omnibus Bill conference committee, the economic impact data was one strategy
	used by the Senate conference committee.

Minnesota CODES			
Minnesota Department of Public Safety/ Department of Health			
	www.health.state.mn.us/injury/topic/topic.cfm?gcTopic=9		
	State Application Presented at CODES Annual Meeting, 2007		
Title: The E	pidemiology of Motor Vehicle Crashes Involving 16–17-Year-Old Drivers in		
	Minnesota and Associated Hospital Charges		
Abstract: Determine	e the per mile rate of teenage driver motor vehicle crash involvement and the characteristics of		
these crashes in Min	nnesota. Measure medical care charges and the severity of injuries associated with motor vehicle		
crashes involving te			
Contact	Scott Hedger, 651-201-7066, scott.hedger@state.mn.us		
	Anna Gaichas, 651-201-5478, anna.gaichas@state.mn.us		
	Mark Kinde, 651-201-5447, mark.kinde@state.mn.us		
	(Historical) Tina Folch, 651-201-7063, tina.folch@state.mn.us		
Population/	Crash involvement and injury rates for 16–17-year-old drivers statewide		
Problem Targeted			
Targeted Issue	Demonstrate problems posed by inexperienced drivers and heighten public awareness of high crash involvement rate of 16-17-year-old drivers.		
Requesting Office	The Minnesota Departments of Public Safety and Health and the Minnesota Safety Council		
or Targeted	determined that a fact sheet on the epidemiology of teen driver crashes would be useful		
Audience	supporting material for the legislative initiative to strengthen Minnesota's GDL law. The target		
	audiences were the general public (especially parents and teens), safety advocates, the		
	Minnesota State Legislature, and the Minnesota Governor.		
Data Used	Nearly 27,000 Minnesota 2002 crash records were probabilistically linked with hospital		
	emergency room and inpatient treatment information, the Traumatic Brain Injury Registry, and		
	death certificate data, using ten linkage imputations. Linked data were assessed for quality by		
	assuring high agreement between like variables on the crash and hospital sides, ensuring the		
	percent missing was not higher than expected for variables of interest, and comparing the		
	linked data to the crash data.		
Methodology and Analytical Results	Hospital charges were calculated for linked/imputed cases. Miles driven were calculated using a Minnesota weighted proportion of regional responses to the National Household Travel		
	Survey 2001 and limited to miles driving a car, van, SUV, or pickup truck. Maximum Abbreviated Injury Scale (MAIS) score for grouping severity was calculated using ICDMAP-		
	90 software. Non-injured hospital cases with ICD-9-CM diagnosis codes other than 800-999		
	were included in the linkage and given their own category when analyzing severity. These		
	cases have diagnoses that conceivably could follow a crash, e.g., observation following motor		
	vehicle crash, neck/back pain, and chemical abuse.		
	Total hospital charges for 16- and 17-year-old drivers and for all people injured in a crash		
	involving a 16- and 17-year-old driver were calculated. Overall, fatal, nighttime (10 p.m. –		
	4:59 a.m.), and two-or-more-passenger crash involvement rates per miles driven were		
	calculated for 16- and 17-year-old drivers and a comparison group of adult drivers (25 to 59		
	years old), using crash data.		
	Even though teens drive less than do adults, teenage drivers are overrepresented in motor		
	vehicle crashes. In 2002, drivers age 16 and 17 comprised 3.2 percent of the State's licensed		
	drivers and accounted for 2.1 percent of all the miles driven. Yet this group accounted for 8.7		
	percent of drivers in all crashes, 8.8 percent of drivers in injury crashes, and 8.6 percent of		
	drivers in fatal crashes. The per miles driven fatal crash involvement rate of 16- and 17-year-		
	old drivers was 4.5 times that of adult drivers. The per miles driven crash involvement rate of		
	16- and 17-year-old drivers was 3 times that of adult drivers. The per miles driven nighttime		
	injury crash involvement rate of 16- and 17-year-old drivers was nearly 4 times that of adult		
	drivers.		

	Minnesota CODES	
	Department of Public Safety/ Department of Health	
www.health.state.mn.us/injury/topic/topic.cfm?gcTopic=9		
	State Application Presented at CODES Annual Meeting, 2007	
Title: The Ep	pidemiology of Motor Vehicle Crashes Involving 16–17-Year-Old Drivers in	
	Minnesota and Associated Hospital Charges	
Methodology and Analytical Results (continued)	Sixteen- and 17-year-old drivers with two or more passengers in their vehicles were twice as likely to be involved in a fatal crash and 1.5 times more likely to be involved in an injury crash than adult drivers with two or more passengers. Inpatient and emergency department charges for teenage drivers in motor vehicle crashes were nearly \$5 million and nearly \$11 million for all people in motor vehicle crashes involving teenage drivers. Average hospital charges are greater for others in crashes involving 16- and 17-year-old drivers than the teen drivers.	
Dissemination Formats	Initially, a presentation highlighting low seat belt use rates, over involvement in nighttime crashes and the relationship between number of passengers and crash involvement and severity was delivered at the annual Minnesota Towards Zero Deaths Conference in November 2006. The presentation was made available for traffic safety advocates and Public Health Liaisons to use as an educational tool through the Minnesota Office of Traffic Safety Web site.	
	Because teen crashes receive particular attention between prom and high school graduations, it was decided that a one-page fact sheet be developed for use during this time period. In May 2007, the fact sheet, <i>The Epidemiology of Motor Vehicle Crashes Involving 16–17-Year-Old Drivers in Minnesota and Associated Hospital Charges</i> , was finalized after receiving feedback from CODES board members. The informational sheet focused on defining major issues associated with teen driver crashes. The Department of Public Safety Communications Office worked in conjunction with the Minnesota Hospital Association and Department of Health in releasing a news advisory to statewide media outlets. The piece was picked up by major TV networks (lead story on one of the Twin Cities area nightly newscasts) and print papers statewide. The materials were also distributed via email to law enforcement agencies, public health advocates, other traffic safety partners statewide, and Traffic Records Coordinating Committee members.	
	After soliciting input from key advocates involved in teen traffic safety initiatives, it was determined that a full report exploring the potential impact of upgrading Minnesota's graduated drivers licensing law be developed.	
	The fact sheet mentioned is available for viewing at <u>www.dps.state.mn.us/ots/crashdata/CODES/TeenDrivers.pdf</u> .	
Impact, Follow-Up, or Later Development on the Targeted Issue	 Traffic safety advocates will incorporate the CODES information into their educational outreach efforts with parents, teens, the media, and policy decision makers. The Minnesota Legislature adopted a bill to strengthen Minnesota's Graduated Driver's License Law. Parents are encouraged to more closely monitor teen drivers and restrict teen driving during the evening and with passengers. 	

	Missouri CODES		
Missouri Department of Health and Senior Services			
www.dhss.mo.gov/MICA/index.html (Select motor vehicle crashes)			
_	State Application Presented at CODES Annual Meeting, 2006		
	Title: Safety Device Use for Children Age 4–8		
Abstract: Provided, or	request, CODES data relating to the effect of safety device use on emergency department		
	ejection, hospitalization, traumatic brain injury, and death for children age 4 to 8.		
Contact Person and	Mark Van Tuinen, 573-751-6300		
Number			
Population Targeted	Children age 4 to 8		
Traffic Safety Issue Targeted	Modifying the child safety seat law to require that children age 4 to 8 be secured in passenger restraint systems.		
Requesting Office or Targeted Audience	Legislators, Hospital Administrators, Child Passenger Safety Advocates		
Description of linked data	For this study, high-probability links (ED and inpatient; mortality beginning in 2003) were used, though a few from .80 to .89 are included based on inspection of person and crash identifiers. Data years 2001, 2003 were included. Over 90 percent of hospital ED and inpatient records have person name and E-codes; 99 percent have date of birth, sex, admit and discharge dates; up to 23 diagnoses are collected. All acute care hospitals report. Regarding crash records, 20,000 of 365,000 (5%) have few identifiers.		
Analytical Results	Tables were prepared that showed statistically significant increased rates of ejection, hospitalization, TBI and death for nonusers of seat belts / child safety seats for children age 4 to 8. There were 3090 children age 4 to 8 for whom seat belt usage was known. Children who did not use seat belts were more likely to be ejected from the vehicle and admitted to the hospital. These children were also more likely to incur traumatic brain injuries or fatal injuries than children using seat belts. In 2003, the average inpatient charge for nonusers of seat belts was \$16,240 higher than the average for users, and the median inpatient charge was \$5252 higher. In 2001 the median inpatient charge was higher for nonusers. The average inpatient charge was slightly higher for users of seat belts but not significant. The average ED charge was higher for nonusers in 2003. The average ED charge was higher for nonusers in 2001 as well, but the difference was not statistically significant. Government pay sources (primarily Medicaid) accounted for 61 percent of nonusers of seat belts, compared to 40 percent for users. Nonusers had over a million (\$1,000,772) in charges for the Government pay source.		
Dissemination Formats	Tables and text to explain the tables.		
Impact, Follow-Up, or Later Development on the Targeted Issue	Hospital staff are now using the data to train safety seat technicians, advise families on the need for safety seats, and for grant applications. The bill was eventually passed.		

	Missouri CODES		
	Missouri Department of Health and Senior Services		
<u>W</u>	www.dhss.mo.gov/MICA/index.html (Select motor vehicle crashes)		
	State Application Presented at CODES Annual Meeting, 2006		
	Title: Update of Web Application		
belt/helmet use, alcoho	i CODES Web application allows users to develop tables of CODES data which relate of involvement, driver gender and age, crash type, speed zone, and vehicle type to level of ection, and traumatic brain injury. Five years of CODES data is now on the Web site		
Contact Person and Number	Mark Van Tuinen, 573-751-6300		
Population Targeted	Drivers of motor vehicles		
Traffic Safety Issue Targeted	Speeding, helmet and belt use, alcohol use, age, and sex of driver as related to health outcomes of death, TBI, ejection, hospitalization.		
Requesting Office or Targeted Audience	Highway safety professionals, policymakers, legislators, community leaders.		
Description of linked data	Probabilistic linkage - emergency departments and inpatient; mortality beginning in 2003 - though a few from .80 to .89 are included based on inspection person and crash identifiers. Data years 1993, 1996, 1999, 2001, and 2003 are included. Over 90 percent of hospital ED and inpatient records have person name and E-codes; 99 percent have date of birth, sex, admit and discharge dates; up to 23 diagnoses are collected. All acute care hospitals report. Regarding crash records, 20,000 of 365,000 (5%) have few identifiers.		
Analytical Results	The Web site allows one to construct tables relating crash variables to medical care variables, as in showing the percent of helmeted versus unhelmeted motorcycle drivers who die, are admitted, visit the emergency room or receive no hospital care.		
Dissemination Formats	The Web site is available to all individuals with Web access.		
Impact, Follow-Up, or Later Development on the Targeted Issue	During January to April 2006, an average of 40 department and 279 outside users per month visited the CODES Web site, for a 4-month total of 161 department and 953 external visitors.		

Missouri CODES Missouri Department of Health and Senior Services www.dhss.mo.gov/MICA/index.html (Select motor vehicle crashes) State Application Presented at CODES Annual Meeting, 2007 Title: CODES Data Highlights the High Cost of Not Buckling Up Abstract: CODES data were used to relate seat belt use to the level of care needed, ejection, urban/rural crash site, driver impairment, inpatient and emergency department (E/D) charges, and expected pay source.	
Contact Person and Number	Mark Van Tuinen, 573-751-6300
Population/ Problem Targeted	Unbelted and belted drivers of passenger vehicles in crashes statewide
Targeted Issue	Statewide effort to get a primary seat belt law passed
Requesting Office or Targeted Audience	Legislator
Data Used	Probabilistic linkage for 2004 linked crash-inpatient-ED-mortality records. Crash data are from all crashes in Missouri in which an injury or \$500 damage occurred. Inpatient-ED data are from all acute care hospitals in Missouri as well as from a number of hospitals in neighboring States. Mortality data are for all Missouri resident deaths regardless of where they died. Approximately 65 percent of inpatient and ED records noting an E-code in the 810-819 were linked to crash records.
Methodology and Analytical Results	Probabilistic linkages from an initial linkage were used. Inpatient-ED-mortality records were unduplicated prior to linkage, and likely repeat health care visits for the same person were omitted. Chi-square and t-tests were used to compare belted and unbelted drivers on the dependent variables.
Dissemination Formats	Tables with explanatory footnotes were emailed to the requestor, a member of the Traffic Records Coordinating Committee and one of the leaders in the statewide effort to generate support for a primary seat belt law.
Impact, Follow-Up, or Later Development on the Targeted Issue	Passage of the bill was unresolved at the time of this abstract.

	Nebraska CODES		
Nebraska Department of Health and Human Services (NDHHS)			
	Division of Public Health		
	http://www.dhhs.ne.gov/codes/		
т	State Application Presented at CODES Annual Meeting, 2006		
1	itle: Why Is It So Risky to Drive on the Roadways Where the		
	Posted Speed Limit Is 50 Miles per Hour?		
	that occurred on roadways with a posted speed limit of 50 mph resulted in severe crash		
	hest injury rate and a higher death rate than those crashes that took place on other roadways.		
	he causes and consequences of crashes occurring on roads with posted speed limit 50 mph in		
Nebraska.			
Contact Person and	Ming Qu, 402-471-0566		
Number			
Population Targeted	Nebraska drivers		
Traffic Safety Issue	Reduce the number of crashes that take place and prevent injuries from occurring to those		
Targeted	involved in crashes.		
Requesting Office or	Analysis planned in conjunction with the State Highway Safety Office; other audiences		
Targeted Audience	includes State Department of Motor Vehicles and Driver Safety Schools		
Description of	CODES 1999–2000 results obtained by linking crash, EMS, and hospital discharge data		
linked data	using probabilistic linkage with acceptable linkage rates and limitations.		
Analytical Results	Using descriptive analyses and multiple logistic regression modeling, the study indicated that, for those crashes that took place on roadways with a posted speed limit of 50 mph, there was a higher risk of death and severe injury. Contributing risk factors include involving teen drivers, low restraint use, alcohol, single-vehicle fixed objects, and/or lane departures resulting from speeding or driving too fast for conditions on two-lane roads with a gravel surface.		
Dissemination Formats	 Made presentations at CODES Advisory Committee Meeting, the Statewide Highway Advocate Meeting, and the 2005 Traffic Records Forum. In addition, a special meeting was held at the Nebraska Office of Highway Safety to present this study and discuss recommendations for prevention Published articles about this study in two local newspapers. Published the paper in the <i>Journal of Safety Research</i>. Produced a fact sheet that was distributed at the Nebraska Department of Health and Human Services (NDHHS) Manager Meeting, and posted it on the NDHHS Web Site 		
Impact, Follow-Up, or Later Development on the Targeted Issue	Nebraska Office of Highway Safety took recommendation to add the gravel road driving training component into <u>Getting Your Driver's License in Nebraska: A Guide for Teens</u>		

Nebraska CODES Nebraska Department of Health and Human Services (NDHHS) Division of Public Health

http://www.dhhs.ne.gov/codes/

State Application Presented at CODES Annual Meeting, 2007 Title: Comparing CrashesTthat Occurred in Nebraska Involving

Nebraska and Non-Nebraska Drivers

Abstract: Motor vehicle crashes occurring in Nebraska involved both State drivers and non-State drivers. Comparing the crashes occurring in Nebraska from 1999 to 2003 by the driver's State of residence, this study explores the patterns and the contributing risks factors of the crashes. The 1999–2003 data from the Nebraska CODES are used to describe the demographics of occupants involved in these crashes and crash characteristics. The study is designed to evaluate outcomes of these crashes and identify their causes—including drivers' and environmental contributing factors.

Contact Person and Number	Ming Qu, 402-471-0566, ming.qu@nebraska.gov
Population/ Problem Targeted	Nebraska and non-Nebraska drivers who drive on the roadways in Nebraska
Targeted Issue	Reduce and prevent crashes occurring in Nebraska and their corresponding injuries and fatalities
Requesting Office or Targeted Audience	Analysis planned in conjunction with the State Highway Safety Office; other audiences include Traffic Records Coordinating Committee and Travel Information Center
Data Used	This study used the Nebraska 1999–2003 CODES data, a result of linking the crash to hospital discharge data with probabilistic linkage.
Methodology and Analytical Results	 Using descriptive analysis, this study compared the Nebraska and non-Nebraska driver involved crashes and showed that crashes involving non-Nebraska drivers tended to be more severe, resulting in more deaths and serious injuries than crashes involving Nebraska drivers. The crashes involving non-Nebraska drivers had the following characteristics: The most common reasons for the crashes were failure to yield, following too close and speeding, bad weather, and animals in roadways were cited as well. The crashes were more likely to happen during the summer. The crashes frequently occurred in rural areas or on State and interstate highways. The vehicles driven by non-Nebraska drivers were: Most likely to be passenger cars Disproportionately more likely to be heavy trucks or semi-trailer trucks.
Dissemination Formats	 Presentations were made at the CODES advisory committee meeting, the Statewide Highway Advocate meeting, and the 2006 Traffic Records Forum. A special meeting was held at the Nebraska Office of Highway Safety to present this study and discuss recommendations for prevention. Local newspapers published articles about this study. Produced a fact sheet that was posted on the Nebraska Department of Health and Human Services' Web site. It is viewable online at http://www.dhhs.ne.gov/CODES/Non-NE-Drivers.pdf
Impact, Follow-Up, or Later Development on the Targeted Issue	Worked with the Nebraska Office of Highway Safety, Nebraska Injury Prevention Advisory Committee, and the media to send out the message to the Tourist Information Center, Truck Association, and State Patrol.

New York CODES New York State Department of Health, Bureau of Injury Prevention State Application Presented at CODES Annual Meeting, 2006 Title: Using CODES and Imputation to Demonstrate the Importance of Promoting Backseat Seat belt Use Abstract: The study applied imputation methodology to address the seat belt use over-reporting and no-reporting problems in police crash reports and imputed the backseat seat belt use. The results were then examined in relation to various potential risk factors including driver's age, gender, and crash time. The belted and unbelted backseat passengers were compared in Barell injury groups, hospital charges, and length of hospital stay. The research was presented during the New York State Highway Safety Conference. New York State Association of Traffic Safety Boards (NYSATSB) members attended the meeting. The paper on backseat seat belt use was

published in Journal or	f Safety Research.
Contact Person and	(Historical) Motao Zhu, former NYS CODES Project Manager
number	(Current) Michael Bauer, Susan Hardman, 518-473-1143
Population Targeted	Backseat passengers 16 and older.
Traffic Safety Issue	Increase backseat seat belt use and promote backseat seat belt legislation.
Targeted	
Type of Decision	New York State Association of Traffic Safety Boards
Maker Targeted	
Requesting Office or	The New York State, Bureau of Injury Prevention initiated this project to meet needs of
Targeted Audience	the NYS traffic safety community. There has been a continual effort in the NYS traffic
	safety community to get backseat seat belt legislation passed.
Description of	Linked Police Crash Reports and Hospital Discharge Data, 2002; imputation for backseat
linked data	seat belt use; missing links were imputed. As limitations, sensitivity and specificity of
	imputation model are unknown.
Analytical Results	Statistical methodologies: descriptive analysis, multivariate analysis. The results:
	• Unreliable reported seat belt use was set to missing and a logistic regression
	model was applied to impute backseat seat belt use. The imputation adjusted the
	backseat seat belt use from 69 percent to 35 percent.
	• Backseat seat belt use was tabulated by various potential risk factors. Driver's
	alcohol involvement, being male, and nighttime were associated with decreased
	restraint use. Barell Injury Matrix, hospital charges and stay were tabulated by
	backseat seat belt use. Nonuse of backseat seat belts was related to higher rates in
	hospitalization, traumatic brain injury, and vertebral cord injury.
Dissemination	A presentation was made during the New York State Highway Safety Conference with
Formats	NYSATSB in attendance. It is a statewide organization for county traffic safety boards
	and agencies, companies, and individuals working in traffic safety and injury prevention.
	It proposes traffic safety legislation and offers traffic safety education programs.
Impact, Follow-Up,	NYSATSB are planning to conduct health educational campaigns to increase backseat seat
or Later	belt use and promote a traffic safety law requiring passengers 16 or older to buckle up in
Development on the	the backseat.
Targeted Issue	
Comments	Seat belt use recorded in police crash reports has been criticized for misclassification
	because occupants might falsely report the seat belt use to avoid traffic violation fines or
	tickets. New York CODES imputed missing values of seat belt use and adjusted the totals
	to account for over-reporting. Imputation adjusted 2002 New York backseat belt use from
	the recorded 69 percent to 35 percent, which was more consistent with estimated national
	rate of 47 percent. Driver's alcohol involvement, male gender, and nighttime crashes were
	associated with nonuse of seat belts by adult backseat occupants. Backseat belt use
	percentage after imputations was 8.1 percent for driver's alcohol involvement, 35.3
	percent for no driver's alcohol involvement, 29.7 percent for male, 40 percent for female,
	27.8 percent at night, and 38.2 percent during the day, respectively.

New York CODES New York State Department of Health, Bureau of Injury Prevention State Application Presented at CODES Annual Meeting, 2007

Title: Using Multiply Imputed CODES Data to Identify Risk Factors and Reveal Societal Costs in Teen Driving

Abstract: The linked and multiply imputed 2005 Police Crash Reports, Emergency Department and Hospital Discharge Data were examined to determine the risk factors and societal costs for drivers who were aged 16-20. Teen drivers and 25–49-year-old drivers were compared for traffic crash and injury rates, emergency department visit rates, hospitalization rates, and crash contributing factors. These data were used to estimate the societal costs for vehicle occupants riding with teen drivers involved in crashes, and vehicle occupants involved in crashes when the teen driver was at fault or speeding. The analysis results were used to prioritize the contents for the New York State Department of Health, Bureau of Injury Prevention's annual training workshops for local health departments and traffic safety agencies. The CODES application on teen drivers was also presented during the training. (Historical) Motao Zhu, former New York CODES Project Manager Contact Person and Number (Current) Michael Bauer, Susan Hardman, 518-473-1143 Teen drivers (16–20 years old) Population/ Problem Targeted Targeted Issue Reduce traffic crashes, injuries, and societal costs due to teen drivers. Requesting Office or New York's Bureau of Injury Prevention initiated this project to better understand the **Targeted Audience** issues surrounding teen drivers. This is an important issue in New York and the information gathered from the CODES analysis will help the New York traffic safety community prioritize there agenda around this problem Data Used Data sources: crash, emergency department, inpatient Data year: 2005 Quality, comprehensiveness, representativeness: missing links were imputed, missing values were imputed, multiply imputed data were analyzed Methodology and Statistical methodologies and descriptive analysis. The results: Analytical Results The crash-related emergency department visit and hospitalization per 1,000 licensed drivers were 15.7 and 1.2 for 16- to 20-year-old drivers, which were double the rates for 25- to 49-year-old drivers. The societal costs for vehicle occupants riding with teen drivers involved in • crashes was \$1.8 billion in 2005. Dissemination 1) Tables and talks within the NYSDOH and the development of a training plan. 2) Oral presentation during the training focused on topics related to revealing the risk Formats factors and societal costs for teen drivers for local health departments and traffic safety agencies. Impact, Follow-Up, 1) The NYSDOH and BIP used the CODES application to prioritize the training contents. or Later 2) Local health departments and traffic safety agencies will use the CODES application to Development on the develop strategies to reduce teen driver crashes, injuries, and societal costs. Targeted Issue

	Ohio CODES			
	Center for Injury Research and Policy, Nationwide Children's Hospital			
http://sharedoc.nchri.org/CIRP/Pages/CODES.aspx				
State Application Presented at CODES Annual Meeting, 2006				
	Title: Boost Advisory Board Interest in CODES			
	y completed its first CODES data linkage, and thus, new information regarding motor vehicle			
crashes and their medical and financial outcomes are now available. An advisory board meeting was held to announce this				
achievement. A presentation was given to review information about CODES and to show preliminary results to generate				
	e discussion. Discussions allowed the CODES team to hear the suggestions of traffic safety partners.			
	w were still in progress at the time of this abstract, as data linkage had only recently been completed.			
Contact Person and	Gary Smith, M.D., Dr.P.H., Principal Investigator, 614-722-2400			
Number	(Historical) Kristen Conner, M.P.H., former CODES Data Manager			
Population Targeted	Restrained/Unrestrained, Alcohol Impaired, Teen Drivers			
Traffic Safety Issue	Restrained/Unrestrained: Support for primary belt use.			
Targeted	Alcohol Impaired: Support BAC .08 law.			
	Teen Drivers: Support GDL law.			
Requesting Office or	Advisory Board (representation of groups with traffic safety interests in Ohio).			
Targeted Audience	Eventually will target legislators			
Description of	Preliminary results analysis used crash records linked with hospital inpatient data for 2002. Data			
linked data	were linked using multiple imputations of missing links.			
Analytical Results	Linked imputed CODES data were analyzed using SAS. Median length of stay and median total			
	hospital charges were reported.			
	1. Data Model for Restraint Use:			
	"Restrained" included any indicator of belt use or a child safety seat. "Unrestrained" indicated that the vehicle occupant had no form of restraint use. These two categories were compared by age			
	groupings.			
	Results: Graphs of hospital charges were effective in displaying the benefits of restraint use.			
	2. Data Model for Alcohol Use:			
	"Alcohol involved" included any person with an indication that alcohol or alcohol and drugs were			
	suspected in a crash. "No alcohol involved" included people who had no alcohol exposure, who			
	had been drinking but were not impaired, or where drugs only were suspected. Again, these two			
	categories were compared by age groupings.			
	Results: Length of stay showed no effects. Alcohol use had higher charges for most age groups.			
	Data is reported for all occupants involved in a crash; however, the alcohol flag indicates alcohol			
	use by drivers in crashes.			
	3. Data Model for Teen Drivers:			
	Flagged for "Drivers" only, age 15 to 19. Compared single-occupant crashes (driver alone) to			
	crashes with four total occupants.			
	Results: Length of stay and charges showed no effects for number of occupants. This may be due			
	to the small number of crashes with four occupants. Crashes with two or more occupants are			
	compared with single-occupant crashes.			
Dissemination	A presentation was given that reviewed the origins of CODES, Ohio CODES goals, and linkage			
Formats	techniques. Results were presented in frequency tables and bar charts. Bar charts displaying			
Lungost Estimate	differences between groups for hospital charges effectively communicated the results of analyses.			
Impact, Follow-Up,	The CODES team noted the input from the advisory board. The CODES team is working closely with the Ohio Department of Public Sofety to focus on analysis of tension of interport to the traffic			
or Later	with the Ohio Department of Public Safety to focus on analysis of topics of interest to the traffic			
Development on the	evelopment on the safety community. New results will be presented when available. More useful results will be obtained when the above suggestions are taken into account during future analyses to generate CODES reports, fact sheets, etc.			
rargeteu issue				

Ohio CODES			
Center for Injury Research and Policy, Nationwide Children's Hospital			
Center	http://sharedoc.nchri.org/CIRP/Pages/CODES.aspx		
State Application Presented at CODES Annual Meeting, 2006			
Title: The Impact of a Standard Enforcement Safety Belt Law on Fatalities and Hospital			
Charges in Ohio: An Analysis Using 2003 Ohio CODES Data			
	Abstract: The effect that enactment of a standard enforcement seat belt law in Ohio would have on		
hospital charges and direct medical costs due to motor vehicle crashes was analyzed with a focus on the			
impact to the State's M			
Contact Person and			
	Gary Smith, M.D., Dr.P.H., Principal Investigator, 614-722-2400		
Number	(Historical) Kristen Conner, M.P.H., former CODES Data Manager		
Population/ Problem Targeted	Unrestrained motor vehicle occupants in Ohio		
Problem Targeted Targeted Issue	Support for primary enforcement seat belt legislation		
Requesting Office or	Analysis was planned in conjunction with the Governor's Highway Safety Office		
Targeted Audience			
Targeted Audience	to support Ohio Department of Public Safety and Ohio Seatbelt Coalition;		
D (U 1	handouts provided to Ohio legislators		
Data Used	This analysis used crash records linked with hospital emergency department and		
	inpatient data for 2003. Multiple imputation of missing links (five imputations)		
	and multiple imputation for missing data were used to analyze the data.		
Methodology and	Unrestrained motor vehicle crash victims in the linked database were divided into		
Analytical Results	three categories based on the nature of injury: TBI, SCI, and all other injuries. In		
	order to accurately apply NHTSA-reported seat belt effectiveness rates, the		
	analysis was limited to occupants of a passenger car or light truck who were older		
	than 4 with a motorist safety equipment code of lap belt only, lap/shoulder belt,		
	child safety seat, or unknown. The resulting data set included 51,960 linked crash		
	and hospital records with charges totaling \$108.8 million (n=51,313).		
	<u>Results</u> : Overall, 12 percent ($n=6,113$) of our linked population was unbelted.		
	Total hospital charges for the unbelted occupants was \$29.2 million (n=6,031).		
	Medicaid was the primary payer for 10 percent (n=5,612) of occupants. Using our		
	estimated increase in seat belt use to 92 percent, the projected total direct medical		
	cost savings to Medicaid over 10 years for hospitalizations that occur in 2007		
	alone was \$15.4 million. Assuming passage of a standard enforcement seat belt		
	law in 2007, cumulative costs savings to Ohio's Medicaid system over 10 years		
	was projected to be more than \$91.2 million. In addition, it was estimated that a		
	minimum of 18 fatalities would be prevented in 1 year. Our estimates are		
	considered underestimates as we were unable to ascertain costs associated with		
	injuries treated in a non-hospital setting; only motor vehicle occupants older than		
	4 were included; and the costs associated with those motor vehicle crash victims		
	who died at the scene were not included.		
Dissemination	A formal report and a brief, one-page summary sheet were prepared and submitted		
Formats	to the Ohio Department of Public Safety. The Governor's Highway Safety Office		
	joined us in publicizing and sharing our results with the Governor and other		
	legislators. The report and summary are posted at:		
	http://sharedoc.nchri.org/CIRP/CODES/Abstract_StdEnforcement.pdf		
	http://sharedoc.nchri.org/CIRP/CODES/Full%20Report_StdEnforcement.pdf		
	The Ohio Seatbelt Coalition used our findings on cost savings in a FAQ sheet		
	developed for the most recent attempt to pass a primary enforcement law. That		
	FAQ is at <u>http://www.morpc.org/pdf/FAQs_media.pdf</u>		
Impact, Follow-Up, or	The GHSO took note of the results and potential impact. The report was shared		
Later Development on	with the director of ODPS, the Governor of Ohio, and other legislators. The		
the Targeted Issue standard enforcement legislation was re-introduced in the Ohio legislature in			
	but was defeated.		

	Rhode Island CODES		
Rhode Island Department of Health, Center for Health Data and Analysis			
www.health.ri.gov/chic/statistics/codes.php			
State Application Presented at CODES Annual Meeting, 2006			
	Title: Rhode Island CODES Provides Expert Participation		
	CODES-linked data results and other highway safety and public health information		
	of stricter laws against driving under the influence.		
Contact Person and	Ted Donnelly, 401-222-5142, Edward.Donnelly@health.ri.gov		
Number	Ted Donneny, 401 222 5142, Edward.Donneny@nearm.n.gov		
Population Targeted	All drivers in Rhode Island.		
Traffic Safety Issue	Reduce the percentage of highway traffic fatalities that are alcohol-related.		
Targeted	Breathalyzer refusals are high in Rhode Island due to weak law and light penalty.		
Requesting Office or	Legislators and policy-makers		
Targeted Audience			
Description of linked	Rhode Island CODES links Crash, EMS, hospital, and fatality records data. Crash		
data	records are available for all people in reported crashes and hospital data is complete		
	and of high quality. Rhode Island CODES has five years of linked records, from 2000 to 2004.		
Analytical Results	Standard descriptions with median and mean hospital charges, length of stay, and		
Analytical Results	mortality are reported as outcomes. Mortality reports, enhanced with data from the		
	Fatality Analysis Reporting System, are presented.		
Dissemination Formats	This application derived from a presentation at the CODES annual national		
Dissemination formats	Technical Assistance meeting of 2005.		
	Formal presentations were delivered to highlight the significant number of fatal		
	crashes that were alcohol-related and call for stricter laws and more rigorous		
	enforcement. Part of the argument was that although other New England States had		
	improved on this measure in recent years, Rhode Island had not shown measurable		
	improvement.		
	Substance Abuse and Mental Health Services Administration tables were also		
	created showing that Rhode Island is among the States with highest rates of binge		
	drinking and illicit drug use. At the same time, Rhode Islanders were among those		
	least likely to see binge drinking and illicit drug use as problems.		
Impact, Follow-Up, or	Legislation to stiffen penalties for breathalyzer refusal is making its way through		
Later Development on	committee with multiple sponsors and strong support.		
the Targeted Issue			

Rhode Island CODES			
Rhode I	Rhode Island Department of Health, Center for Health Data and Analysis		
www.health.ri.gov/chic/statistics/codes.php			
	State Application Presented at CODES Annual Meeting, 2007		
	Occupants in Motor Vehicle Crashes: Forecasting Health Burden		
Abstract: Statistically, Rhode Island's older occupants are more likely to be hospitalized or fatally injured			
	after a motor vehicle crash. Understanding the differences and considering the age distribution of the		
	planning policies on future highway safety interventions.		
Contact Person and Number	Ted Donnelly, 401-222-5142, Edward.Donnelly@health.ri.gov		
Population/	Compares older occupants with other age groups by hospital outcomes, including		
Problem Targeted	length of stay, charges, payer, and discharge status.		
Targeted Issue	Highway safety interventions will be targeted and the age structure of the population in the future will be considered.		
Requesting Office or	Rhode Island CODES Professional Advisory Committee, which includes data		
Targeted Audience	owners, public interest groups (e.g., Mother Against Drunk Driving), injury control, and law enforcement.		
Data Used	This analysis used CODES probabilistic linkages of 2003 records from Crash, EMS, and hospital discharge data. Missing values were multiply imputed as were missing record linkages.		
Methodology and Analytical Results	Analysis included the distribution of occupants in crashes by sex, age group, and level of care. Occupants admitted to the hospital differed in charges and length of stay by age group and payer. Restraint use is not uniformly associated with lower charges or shorter hospital stays.		
Dissemination Formats	This material was presented at a number of venues, culminating with a meeting of the Rhode Island CODES Professional Advisory Committee. The Rhode Island CODES presentations emphasized the use of Bayesian probabilistic linkage without providing a detailed explanation of the method. Those who attended these presentations expressed interest in graphic representations of the progression of large and small age cohorts through the lifespan.		
Impact, Follow-Up, or Later Development on the Targeted Issue	This analysis and presentation further supports the continued emphasis on interventions with older people.		

	South Carolina CODES		
South C	arolina State Budget and Control Board, Office of Research and Statistics		
South C	www.ors2.state.sc.us (select SC CODES project)		
State Application Presented at CODES Annual Meeting, 2006			
Title: Providing Information to Support Decision Making			
Abstract: South Caroli	ina CODES data are used each year to support proposed changes to traffic related laws that		
	th Carolina Legislature.		
Contact Person and	Tracy Joyce Smith 803-898-9948		
Number	11acy Joyce Siniui 803-898-9948		
Population Targeted	Targeted problems are those in which traffic safety legislation is being considered:		
Topulation Targeteu	motorcycle riders and driving under the influence.		
Traffic Safety Issue	Legislative issues being considered in current session:		
Targeted	1. Driving-under-the-influence crashes		
Targetea	 Motor vehicle crash outcome by primary payer, State total, South Carolina, 		
	2003.		
	 Hospital and emergency department charges at the State and county level. 		
	 Motor vehicle crash outcome by driver gender for crashes with at least one 		
	driver under the influence, State and county level.		
	2. Motorcycle crashes		
	Estimated economic cost of motorcycle crashes, injuries, and fatalities in South		
	Carolina for the last five years.		
	 Estimated economic cost of motorcycle crashes, injuries and fatalities at 		
	signalized intersections.		
	 Estimated economic impact from red light running crashes. 		
Requesting Office or	The requesting office for the majority of requests is the SC DOT, Office of Highway		
Targeted Audience	Safety. The OHS then combines our analysis with information gathered from other		
sources to create profiles at the State and county levels. The OHS then distribute			
	profiles to the appropriate traffic safety stakeholders, legislators, etc. Legislators receive		
	information specific to their represented counties, etc.		
Description of	The South Carolina CODES project links crash reports with inpatient hospitalizations and		
linked data	emergency department visits from 1998 to 2000, which included emergency medical		
	services as well. South Carolina's data linkage is of a high quality due to the identifiers		
	available to the project. These links are representative of the population based on		
	statistical testing of these data.		
Analytical Results	The analytical reports for these various legislative initiatives were customized to the		
5	audience. Reports addressing the topic were targeted to legislator's districts, county safety		
	coalitions, or other geographic areas of interest. The ability to customize specific safety		
	reports on short notice makes the information "local."		
Dissemination	The Office of Research and Statistics provides the data to the South Carolina Department		
Formats	of Transportation and the Department of Public Safety, both partners in the CODES		
	project. Resources from these organizations tailor the information to fact sheets, reports,		
	PowerPoint presentations, and other means of dissemination.		
Impact, Follow-Up,	Linked CODES data was instrumental in the passage of legislation to raise the fine for		
or Later	children who were not properly restrained. South Carolina Governor Mark Sanford vetoed		
Development on the	legislation raising the fine from \$25 to \$150. Both the House and Senate over-rode the		
Targeted Issue	veto and the legislation has become law.		
	Reports on motorcycle issues were requested by the House of Representatives to address		
	issues related to red lights, redefining classes of motor vehicles, and evaluating the safety		
	issues for a variety of legislation. Reports on motorcycle use supported changes in		
	legislation, which included revising definitions for types of motor vehicles, addressing the		
	increase in injuries for people under 18, and other safety issues.		

Abstract: CODES data Carolina legislature ar	South Carolina CODES arolina State Budget and Control Board, Office of Research and Statistics WWW.OrS2.state.sc.us (select SC CODES project) State Application Presented at CODES Annual Meeting, 2007 Title: The Continuing Saga of DUI Legislation a is used to develop various media products that are distributed to members of the South ad traffic safety decision-makers to illustrate the medical and financial consequences of ivers involved in crashes. The data is analyzed at a local level to show local consequences. Tracy Joyce Smith, 803-898-9948 The South Carolina application provides data that support revising the current legislation (a colspan="2">Colspan="2"Colspan="2"Colspan="2"Colspan="2"Colspan="2"Cols	
Requesting Office or Targeted Audience	(per South Carolina's DUI law) to clarify ambiguities in the original legislation. The requesting office for most requests such as this is the South Carolina Dept. of Transportation, Office of Highway Safety, which combines our analysis with information gathered from other sources to create profiles at the State and county levels and then distributes these profiles to the appropriate traffic safety stakeholders, such as the South Carolina legislators; other targeted audiences include groups for DUI legislation (e.g., Mothers Against Drunk Driving).	
Data Used	South Carolina's State-specific application includes linked data for 2001 through 2004, which includes crash records, inpatient hospitalizations, and emergency department visits. The high-probability linked data was used for this application. Analysis done on both high-probability and imputed datasets showed that the identifiers used in the linkage are highly discriminatory, corresponding to the imputed data.	
Methodology and Analytical Results	 Reports were generated for each of the 46 counties in South Carolina. Each report contained: Number of impaired drivers involved; number and percent linked; Total and mean charges by level of care (emergency department versus inpatient); Total and mean length of stay (inpatient only); Primary pay source (Medicaid, Medicare, insurance, self/indigent). The objective was to show that all counties, large and small, urban and rural, are affected by crashes where drivers are under the influence. 	
Dissemination Formats	The South Carolina Office of Research and Statistics is a partner agency with the South Carolina Department of Transportation (SC DOT). The reports primarily are in Excel spreadsheets and occasionally as a static SAS report; all information is electronically submitted to the SC DOT. The SC DOT, in turn, reformats and presents the information to legislators and advocacy groups for use in legislative hearings and other educational endeavors. The objective is to show what is happening in each legislator's specific county.	
Impact, Follow-Up, or Later Development on the Targeted Issue	The debate on stiffer legislation for those driving under the influence is an ongoing effort, much like the primary seat belt enforcement that took over five years to pass. A bill designed to close many of the loopholes and enact stiffer penalties in the existing DUI laws, which was introduced during last year's session, was not passed. There will be another attempt to secure passage of this bill next session.	
	The legislature did pass, and the Governor did sign, a comprehensive bill to reduce underage drinking and underage access to alcohol. The bill also included strengthened provisions for the use of alcohol ignition interlock devices. The CODES data (for drivers age 15 to 20 who were DUI) have been used extensively in court testimony during the penalty phase of trials for vendors who have had repeat sales of alcohol to minors.	

Utah CODES University of Utah Intermountain Injury Control Research Center http://www.utcodes.org State Application Presented at CODES Annual Meeting, 2006

Title: Using CODES Data to Strengthen Utah's GDL Laws

	Ittle: Using CODES Data to Strengthen Utah's GDL Laws			
	999 and 2000 Utah legislative sessions several aspects of a graduated driver licensing			
	ed. These included a mandatory minimum number of practice hours, as well as nighttime			
	and passenger restrictions. Using a combination of crash and citation rates per licensed teen driver, Utah CODES			
studied the effectiveness of these new laws. The results found that while there was an overall reduction in the				
	-olds, this reduction was much smaller than what has been observed in other States. In			
	reduction in the rate of crashes resulting in an emergency department visit, hospital			
	admission, or death. Finally, it was found that there were very few citations issued for violating the GDL laws.			
The results were shared in presentations at national conferences and published in Annals of Emergency Medicine.				
These findings were then published in newspapers and aired on local news outlets. Utah traffic safety advocates				
	to be presented in a fact sheet form to support legislation to strengthen the GDL system.			
During the 2006 legislative session, the fact sheet was distributed to all legislators and the findings were used in				
	he new GDL legislation. The GDL bill passed both the House of Representatives and the			
Senate and was signed	l into law by the Governor.			
Contact Person and	Larry Cook, 801-585-9760, larry.cook@hsc.utah.edu			
Number				
Population Targeted	Licensed novice 16-year-old drivers.			
Traffic Safety Issue	Utah's GDL system			
Targeted				
Requesting Office or	This work was planned in conjunction with the Coalition for Utah Traffic Safety (of which			
Targeted Audience	the State Highway Safety Office and Utah Department of Health are members), the			
C .	Legislative Task Force for Traffic Safety, and the child advocate at Primary Children's			
	Medical Center. Target audience also includes the Governor and the Legislature.			
Description of	We studied crashes involving teenage drivers between 1996 and 2001. These crashes were			
linked data	probabilistically linked to driver license, citation/conviction, emergency department, and			
	hospital inpatient data. All data sources are statewide databases. Imputation was not used			
	for this analysis.			
Analytical Results	Outcomes examined included overall crash rates, nighttime crashes, crash severity			
2	indicators, seat belt usage, licensure status, and citations. Rate ratios, chi-square tests, and			
	interventional time series analyses were used to assess changes before and after GDL			
	implementation. The results showed that there were 27,304 16-year-old driver crashes			
	during the study period. The overall crash rate per 1,000 licensed 16-year-old drivers			
	decreased by 5 percent, and a time-series analysis showed a reduction of 0.8 crashes per			
	month per 1,000 licensed drivers after GDL implementation. The nighttime crash rate did			
	not change. In addition, there was no decrease in the rates for crashes resulting in			
	emergency department visits, hospital admissions, or death. These results pale in			
	comparison to some States that have reported reductions in crashes between 20 percent			
	and 30 percent. Few GDL licensing citations were issued by law enforcement. In addition,			
	only five citations were written for violation of GDL.			
Dissemination	Originally, the results were presented at the American Public Health Association's annual			
Formats	meeting. A manuscript was developed from this presentation, which was published in			
	Annals of Emergency Medicine. The findings were also published in several newspapers			
	and aired on local television news programs. As a result, local traffic safety advocates			
	asked us to prepare some fact sheets about GDL along with talking points. The fact sheets			
	were given to legislators and the data were presented in committee meetings. Since the			
	data was published in a peer-reviewed journal, the results had more legitimacy for many			
	of the legislators.			
Impact, Follow-Up,	The new GDL bill passed both the Utah House and Senate and has been signed into law.			
or Later	Ongoing efforts will be made to analyze the impact of the new law in the coming years.			
Development on the				
Targeted Issue				
Comments	The results suggest that GDL may have contributed to a reduction in young driver crashes,			
	but the effects were minimal compared with those shown in many other GDL evaluations.			
	It appears that the GDL is not being enforced as expected.			

Utah CODES University of Utah Intermountain Injury Control Research Center

http://www.utcodes.org

State Application Presented at CODES Annual Meeting, 2007

Title: Primary Safety Belt Enforcement Efforts

Abstract: Utah's current seat belt law only provides for secondary enforcement for adults. This year Utah CODES continued its ongoing efforts to support primary seat belt legislation. This support came in form of filling data requests, providing talking points, distributing fact sheets, and giving presentations. Working with an Emergency Medicine physician at Primary Children's Hospital, the researchers examined injuries to children riding with adults stratified by belt use status. The research found differences in injury patterns for children riding with unbuckled adults compared to children riding with buckled adults. In addition, when the analysis is limited to only restrained children, children with unbuckled adults are more likely to be hospitalized compared to children riding with buckled as abstracts titled, "Are adults who use child safety restraints for children using seat belts themselves?" and presented at the Traffic Records Forum meeting in Palm Desert, CA, and the American Public Health Association meeting in Boston, MA. Efforts are also underway to prepare this research for publication.

To prepare for the legislative session, Utah CODES provided talking points to safety advocates to use in their testimony and meetings with legislators. Also, Utah CODES prepared a fact sheet titled, "The Cost of Being Unbuckled," which was given to every legislator. The primary seat belt bill passed the Senate and for the first time made it to the floor of the House. However, the final vote did not pass in the House.

Contact Person and Number	Larry Cook, 801-585-9760, larry.cook@hsc.utah.edu	
Population/ Problem Targeted	Crash injury rates statewide	
Targeted Issue	Advocate for primary seat belt use	
Requesting Office or Targeted Audience	This analysis was conducted at the request of the Coalition for Utah Traffic Safety (of which the State Highway Safety Office and Utah Department of Health are members); Primary Children's Medical Center, and a physician testifying on behalf of the American Academy of Pediatrics. Target audience also includes legislators.	
Data Used	Crash data linked to emergency department and inpatient from 1996 to 2004 were used. The data include all occupants involved in crashes and probabilistic linkage was used.	
Methodology and Analytical Results	Utah CODES used a combination of logistic regression and descriptive statistics to analyze the importance of seat belts at reducing injuries. Utah CODES found that young adults were more likely to restrain the children in their vehicles but not themselves. Also, older adults were the most likely group to restrain themselves but not the children in their vehicles. Utah CODES also found that among restrained children, those riding in vehicles with unrestrained adults were more likely to be injured and link to a hospital record compared to restrained children riding with restrained adults. The Utah CODES fact sheet showed that nearly two-thirds of the charges billed to government insurance came from unrestrained occupants. Also, the average charges were 25 percent higher for unrestrained occupants compared to restrained occupants. Finally, unrestrained occupants were six times more likely to be admitted to a hospital following a crash and three times more likely to be treated at the ED compared to restrained occupants.	
Dissemination Formats	The results comparing injury outcomes between restrained children stratified by adult seat belt use was presented at two national meetings: the Traffic Records Forum and the American Public Health Association. The fact sheets were also given to traffic safety advocates in Utah as well as given to individual legislators.	
Impact, Follow-Up, or Later Development on the Targeted Issue	Information from both the presentation and fact sheets were presented during this year's legislative session. As has been the case for the past two years, the primary seat belt bill passed the Senate. However, the bill was defeated 33 to 39 in the House.	

Virginia CODES Virginia Dept. of Motor Vehicles, VA Highway Safety Office, Traffic Records Management, Reporting and Analysis

www.vacodes.org

State Application Presented at CODES Annual Meeting, 2006 Title: Virginia CODES Web site www.vacodes.org

Abstract: The Virginia CODES program was established to reduce deaths and injuries from motor vehicle crashes by providing relevant and actionable information from linked crash, EMS, and hospital discharge data. The primary means for accomplishing these goals is through informed transportation safety policy and public education.

The Virginia CODES program designed a freestanding Web site to communicate the results of linked crash information to the public. Web sites from across the country were studied to identify ways to present information in a variety of formats for different audiences. An independent Web site was created to highlight the importance of this information as an independent and objective information source for all interested parties.

Following review of other State CODES Web sites, active involvement by the CODES Board of Directors and CODES advisory board, <u>www.vacodes.org</u> was launched in May 2006.

CODES advisory board, <u>www.vacodes.org</u> was radicited in Way 2000.		
Contact Person and Number	Angelisa Jennings 804-367-2026	
Population Targeted	Information is developed to support report creation by geographic area,	
	gender, age, vehicle type, major factors, outcomes, and other groupings.	
Traffic Safety Issue Targeted	Major areas regarding crashes are currently available for review. There is	
	also an online query tool to allow users to create a custom report to the	
	user's specifications.	
Requesting Office or Targeted	Transportation safety professionals, legislators, the general public.	
Audience		
Description of Linked Data	The linked data included 2001, 2002, and 2003 Virginia DMV crash data,	
	EMS data, and hospital discharge data.	
Analytical Results	Many variables—such as injury rates, fatality rates, length of stay,	
	hospitalization rates, and total hospital charges—are available for analysis by	
	area of interest.	
Dissemination Formats	Ready-to-use reports are instant-access reports covering a variety of crash	
	areas from age to vehicle type. These reports are available as a PDF	
	document.	
	Create-a-Report is a function for instant development of custom reports for	
	specific questions by the Web visitor. These reports may currently be	
	printed. Under development is a capability for e-mail and the creation of an	
	Excel file or a PDF document.	
	Fact Sheets are being developed on major areas of interest such as driver	
	distraction, teen driving, and speed as a factor in crashes and alcohol use.	
	Research Briefs are planned using topic and background information	
	developed for CODES States.	
T (1(' ('		
Impact, resulting action, or	Virginia's General Assembly will begin its next session in January. The	
Impact, Follow-Up, or Later	impact of CODES data on informing legislation as well as policy will be	
Development on the Targeted	monitored. Use of Virginia CODES data by advocacy organizations will	
Issue	also be tracked.	
	1	

Virginia CODES Virginia Dept. of Motor Vehicles, VA Highway Safety Office, Traffic Records Management, Reporting and Analysis

www.vacodes.org

State Application Presented at CODES Annual Meeting, 2007

Title: 408 Funding Award for Virginia's Traffic Safety Information System

Abstract: Virginia CODES was a significant factor in the Commonwealth of Virginia's 408 Strategic Plan for Traffic Safety Information System. This plan, which secured an \$855,000 Federal funding award, listed three major projects that were key to enhancing the State's traffic records information systems over the next three years. CODES serves as a key database to provide Virginia with medical costs related to traffic crashes in Virginia.

Contact Person and Number	Angelisa Jennings 804-367-2026			
Population Targeted	Crash injury rates statewide and by cities, counties and towns, vehicle safety, data quality, and a means to disseminate information to the public			
Traffic Safety Issue Targeted	Reduce injuries and severity, improve traffic records, and inform the public of injury costs			
Requesting Office or Targeted Audience	A study developed for the Governor of Virginia, members of the Virginia General Assembly, Traffic Records Coordinating Committee, State Highway Safety Office, Injury Control Office and the public			
Data Used	The linked and imputed data included 2001 through 2005 Virginia DMV crash data, EMS data and hospital discharge data			
Analytical Results	The Bayesian Method, which is a branch of logic that looks at solving problems by using probabilities, has many advantages over more traditional methods of direct one-to- one linkage and may be the only way to solve problems with known missing data elements.			
	In CODES, three data sets are imported and standardized: crash (DMV), EMS, and hospital (VHI). These data sets are then matched together in the following way:			
	1. Crash (DMV) data to EMS data			
	2. EMS data to Hospital (VHI) data			
	3. Crash (DMV) data to Hospital (VHI) data			
All three of these data sets have the possibility of missing or incorrect data a CODES performs the Markov Chain Monte Carlo imputation with crash (D EMS and hospital (VHI) data. By running 5 to 10 imputations, data sets can produced with the same results as if they did not have any missing or incorr information within the calculable error rate of standard deviation among all imputed data sets.				
Dissemination Formats	• Virginia's CODES Web site, <u>www.vacodes.org</u> , was launched in May 2006 and currently contains five years of data from which the user can select standard reports or create online queries based on selected criteria			
	• New to the Web site are fact sheets and posters that can be printed and displayed in emergency departments, schools, DMV locations, or other public offices to disseminate detailed, specific messages about general crash facts, motorcycles, alcohol, and speeding.			
Impact, Follow-Up, or Later Development on the Targeted Issue	CODES data and information assisted DMV in securing the 408 Federal funding for their strategic plan for Traffic Safety Information System; <u>www.vacodes.org</u> is also a beneficial portal of information used by State police, Mothers Against Drunk Driving, and other groups who want to quickly obtain specific and statewide data.			

III. APPENDICES

Appendix 1: Frequently Asked Questions Regarding CODES

1. What Is the Crash Outcome Data Evaluation System?

CODES, a program facilitated by the U. S. Department of Transportation's National Highway Traffic Safety Administration, provides software and technical assistance to States to study the population of all occupants in police reported crashes and to use the results to improve traffic safety. Crashes not meeting the State's police reporting threshold or out-of-State crashes involving victims treated in-State are excluded. CODES evolved from a congressional direction and has become institutionalized in many States, producing data analyses on crash outcomes in terms of mortality, morbidity, injury severity, and health care costs. To date, NHTSA has funded 30 States to implement CODES.

Police-reported crash data is the major source of population-based information about crashes statewide. Thus, they are crucial for traffic safety decision-making. However, because the impact of the crash on the occupants of the vehicles involved is not usually known at the scene, crash data does not include the injury outcome information that traffic safety analyses could use to evaluate effectiveness in terms of decreased mortality, morbidity, injury severity, and hospital costs. As with all routinely collected State data used for administrative purposes, they also are limited by the reporting threshold and by missing and inaccurate data. Additional information is needed to identify such characteristics of the person, vehicle, and/or event that are likely to result in specific injury outcomes for comparative purposes or for population estimates.

In contrast, the injury data files are created for public health purposes. They include medical details about the type and severity of the injury and the subsequent costs (billed charges) for all people treated for an injury, regardless of the cause of that injury. Injury data describes the injury outcome at the location of treatment, either at the scene or en route, at the emergency department or after admission as an inpatient. Different entities manage and control access to this data. Injury data does not contain information on the crash that generated the injury. Thus, traffic safety professionals cannot use the injury data alone to obtain the outcome information it needs to target State resources.

CODES is designed to address integrated needs by linking person-specific motor vehicle crash and injury State data to obtain the crash injury outcome information needed to analyze where improvements could be made to traffic safety. In addition, the linkage techniques enable the inclusion of other traffic safety State data — such as vehicle registration, driver licensing and citation data — that expand the comprehensiveness of the crash outcome information generated.

2. What does CODES provide that other crash data sets cannot provide?

CODES linked crash outcome data are a unique resource because they identify crash characteristics for both the injured and the non-injured. Analyses are less likely to be biased when data include characteristics of people involved in crashes who have unexpected outcomes: people who are injured in spite of using safety equipment and people who are not injured in spite of not using safety equipment.

The CODES program is designed to enhance the existing State data without the expense of additional data collection. For example, the crash outcome linkage may provide EMS and hospitals with the time of the crash in order to calculate a measure of the responsiveness of the trauma system; roadway inventories may be enhanced with the inclusion of injury type and severity by location; and licensing data may be enhanced when driver information is linked to the injury severity and health care costs associated with factors such as driving under the influence, aggressive driving, or speeding.

In pursuit of traffic safety goals, the CODES program promotes collaboration between the State traffic safety and health communities. Owners of the State crash and injury data serve on a CODES board of directors, which is responsible for ensuring that State data is available for linkage and for developing the policies that control release of the linked data in compliance with State privacy legislation/regulations. The success of these proactive partnerships spills over into other areas of traffic safety, which also depend upon a collaborative approach to improve crash outcome. This collaborative approach is consistent with the NHTSA's Highway Safety Program Guidelines and the Data Improvement Grants. States with CODES programs have found that CODES helps meet guidelines for traffic records assessments and had already established much of the structure required for data improvement funding.

CODES data and analyses have also been useful to promote public policy, including safety legislation. Because the CODES crash-outcome data are State-specific, they are more relevant to State legislators assessing primary belt laws, graduated drivers license provisions, or helmet use legislation. The ability to compare State-specific results to national estimates provides further clarification about the need for action.

3. How does CODES generate the linked crash outcome data?

Each State links person-specific crash records to the statewide ambulance run reports, hospital emergency department and inpatient records, and death certificate records, all of which are also person-specific. Few States include in the State data unique identifiers, such as social security numbers. Instead, indirect identifiers that discriminate among the events and the people involved are matched. Some States augment the person-specific crash outcome data with driver-specific data from the State licensing files, vehicle-specific data from the State registration data files, and roadway-specific data from the roadway inventory data files to facilitate the linkages.

The linkage is a sophisticated process. In the real world, it cannot be known for certain which crash and injury records are true matches. The lack of unique identifiers, weak indirect identifiers, records (crash or injury) missing for occupants known to have been injured—in addition to the expected problems of missing, and/or inaccurate data—all contribute uncertainty. After evaluating the quality of the State data, State CODES programs implement advanced methods of linkage using CODES2000 software, which estimates the probability that a possible record pair is a valid match.

4. How does CODES handle missing links?

Not all valid matches have high probabilities. This occurs when either the crash or injury record is missing or when the identifiers are unable to discriminate among the crashes and the people involved or are weakened because of missing, inaccurate or inconsistent values. Conclusions based only on high probability linked pairs cannot be presented as representative of the population. Linked pairs, excluded because of low probabilities caused by weak identifiers or incomplete data, may in fact be valid. To compensate for the imperfect data, CODES constructs ("imputes") multiple sets of data that can be used to statistically summarize estimates about the crash population. These estimates are representative of the population from which they were derived, just as a scientifically selected survey sample is representative of the population from which it was drawn.

5. How are imputed datasets analyzed?

Once the missing links have been identified, standard techniques for handling missing values are used to analyze the linked datasets. In SAS, the procedures used are PROC MI and PROC MIANALYZE. These techniques provide confidence intervals that accurately reflect uncertainty caused by missing data.

6. Who can access the CODES data?

CODES data remains in the States due to various issues concerning privacy and data ownership. Access to the CODES statewide linked data is controlled by the data owners in the States through the State CODES programs. Many sites maintain Web sites where CODES data can be accessed in the form of data runs or aggregate reports. When CODES data are used for NHTSA-sponsored studies, the submissions are in standardized analysis variables defined and derived specifically for the study, rather than an entire data set. NHTSA does not maintain a national CODES database.

Appendix 2: Probabilistic Linkage Using Multiple Imputation

The Crash Outcome Data Evaluation System links crash reports to injury outcome records—such as ambulance run reports (EMS), emergency department, or hospital discharge records—in order to evaluate injuries and medical charges associated with crashes. In addition, other traffic safety data sets including roadway inventory, vehicle registration, driver licensing and citations, and insurance claims may also be linked to provide a more comprehensive picture. Most CODES data sets do not have common unique identifiers. Consequently, CODES applies a statistical methodology to link the data sets. The probability that two records are a true link is determined by comparing all event characteristics (e.g., date and place) and all person characteristics (e.g., age and sex) that are common to both records. These characteristics are called *quasi-identifiers*.

CODES record linkage is conducted using CODES2000, commercially available software that implements an extension of Fellegi and Sunter's statistical theory of record linkage (Fellegi & Sunter, 1969; McGlincy, 2004, 2006). CODES2000 determines the posterior odds for a true link by applying Bayes' rule for odds (Gelman et al., 2004, pg. 9), "the posterior odds are equal to the prior odds multiplied by the likelihood ratio." Parameters of the linkage model are determined using Markov Chain Monte Carlo data augmentation (Schafer, 1997, pg. 72). CODES linkage concepts are summarized in Table A-2-1.

Table A-2-1. CODES Linkage Concepts (Pr X means Probability of X)			
Concept	Definition	Calculation	
Probabilistic Record Linkage	Bayes' Rule for Odds applied to record linkage: Posterior odds for a true match equal the prior odds multiplied by the likelihood ratio.	Posterior Odds = $(M / U) X (m / u)$	
Prior Odds for a True Match	Odds for a true match estimated from prior information. Posterior odds after comparing one match field become prior odds for next.	M / U = Estimated # of Matched Pairs / Estimated # of Unmatched Pairs	
m Probability	Conditional probability for a comparison result (agreement, disagreement, or missing) for true matched pairs.	m Agreement = Pr(Reported) X Pr(Correct) X Pr (Field has Given Value for Matched Population)	
u Probability	Conditional probability for a comparison result (agreement, disagreement, or missing) for true unmatched pairs.	u Agreement = Pr(Reported) X Pr(Correct) X Pr (Field has Given Value for Crash Population) X Pr (Field has Given Value for Hospital Population)	
Likelihood Ratio for a True Match	Likelihood for comparison result for true matched pairs/Likelihood for comparison result for true unmatched pairs.	Likelihood Ratio Agreement = (m Agreement / Pr (Agreement)) / (u Agreement / Pr (Agreement)) = m Agreement / u Agreement	

Missing values and reporting errors in the data collection processes may lead to low probabilities being assigned to many true matches. If only high-probability links are selected, then lowprobability false negatives can make selected links unrepresentative of the total population of true linked pairs. To be able to include these low-probability matches in outcome studies, CODES2000 completes five linkage imputations; that is, missing links are determined five times resulting in five complete datasets. (Note that multiple imputation does not attempt to identify each missing link but instead constructs samples representative of the distribution of low to high probability links. As a result, analyses yield valid statistical inferences that reflect the uncertainty associated with having low-probability true links.) Standard statistical analyses are performed on each of the five datasets and then combined to produce final results using procedures in SAS.

References

Fellegi, I.P., & Sunter, A.B. (1969). A Theory for Record Linkage. *Journal of the American Statistical Association*, 64, 1183–1210.

McGlincy, M. A. (2004, August 9). Bayesian Record Linkage Methodology for Multiple Imputation for Missing Links. Joint Statistical Meeting, 2004.

McGlincy, M. A. (2006, August 10). Using Test Databases to Evaluate Record Linkage Models and Train Linkage Practitioners. Joint Statistical Meeting, 2006.

Gelman, A., Carlin, J. B., Stern, H. S., & Rubin, D. B. (2004). *Bayesian Data Analysis*. Boca Raton, FL: Chapman & Hall/CRC.

Schafer, J. L. (1997). Analysis of Incomplete Multivariate Data. Boca Raton, FL: Chapman & Hall/CRC.

SAS OnlineDoc: Version 8. Chapter 9, The MI Procedure. <u>http://v8doc.sas.com/sashtml/</u> Accessed July 7, 2006. DOT HS 811 181 April 2010



