

Introduction to HL7 Standards: v 2.x

W. Ed Hammond
February 25, 2008



Why use data interchange standards?

- Use of standards is becoming more universal. HL7 standards are likely to be in use already
- EHRVA and the vendor community support and use HL7 standards
- As new items are collected, the HL7 standard is easier to accommodate
- Maintenance is not a cost or a problem
- Less work required for new organizations to join project
- The work is already done



Choices for data interchange

- HL7 v2.n series
- HL7 v3 standard
 - Model-based
- HL7 Clinical Data Architecture
 - Continuity of Care Document
 - Common Document Types



Which choice?

- Version 2.x is my immediate recommendation
- Messages are straight forward and the OBX segment can carry any data content
- Version 2.x is easy and straight forward to implement
- An Implementation Manual with conformance agreement for common data elements and the use of a common terminology will provide controlled interoperability
- Version 2.6 is the latest release



version 2.x messaging standard

- Based on an implicit information model
- Focused initially on needs of HIS, later versions expanded horizontally into other areas including ambulatory care
- Most widely used HL7 standard (>90% provider organizations)
- Events not tightly coupled to profiles
- Makes no formal attempt to define process
- Available with delimiter syntax or with XML syntax
- Most currently implemented version is v2.3
- Messages initiated by trigger events



v2.x messaging standard (2)

- Uses segments whose contents are positionally defined; segments are made up of data fields which are made up of data elements
- Fields may be repeating
- Much data sent as name-value pairs
- Accommodates any HL7 registered terminology expressed as code, name, terminology ID triplet



v2.x messaging standard (3)

- Is easy to use and understand; quick implementation
- Works well within a single enterprise where both sender and receiver are tightly bound; does not work well when sender and receiver are not connected
- Has saved money on cost of interfaces
- Will continued to be supported by HL7 in the future and will continue to be implemented by users



v2.x Functional areas

- ADT, Registration, Orders, Results, patient financial, query language, immunization reporting, clinical trials, adverse drug reactions, scheduling, referrals, medical records, patient care, problem lists and goals, waveforms, personnel management, clinical lab automation transactions, master files




Version 2.6 chapters

1. Introduction
 2. Control
 3. Patient Administration
 4. Order Entry
 5. Queries
 6. Financial Management
 7. Observation Reporting
 8. Master Files
 9. Medical Records/
Information
Management
 10. Scheduling
 11. Patient Referral
 12. Patient Care
 13. Clinical Laboratory
Automation
 14. Application
Management
 15. Personnel Management
 16. Non-US Claims
 17. Materials Management
- Appendix:***
- A. Data Definition Tables***
 - B. Lower Layer Protocol***
 - C. BNF Definitions***
 - D. Glossary***




The HL7 basic “Transaction Model”



HL7 Message


Message Header - MSH

Addressing the envelope:



HL7 Message - PID Segment

Identify the patient:



HL7 Message PV1 Segment

Define the visit or encounter



HL7 Message OBR Segment



HL7 Result Message (ORU)

```
MSH | ^~\& | | | | 19981105131523 | | ORU^R01<cr>  
PID | | | 100928782^9^M11 | | Smith^John^J<cr>  
OBR | | | Z0063-0^^LN<cr>  
OBX | | XCN | Z0063-0^^LN | | 2093467^Smits^J^<cr>  
OBX | | Z0092-0^^LN | | 203BE0004Y^^X12PTX<cr>
```

Segment

Data Field

Component



OBX: the flexible segment

Other data fields include: date of observation, identity of provider giving observation, normal ranges, abnormal flags

A code that identifies the *datatype* of OBX-5

OBX-5: Data

Status

OBX | | NM | 11289-6^^LN | | 38 | C^^ISO+ | | | | | F

A code that identifies the data in OBX-5 (Temp Reading)

A code that identifies the units of numerical data in OBX-5



OBX: with a coded value

A code that identifies the *datatype* as a coded element

The code is from LOINC

The code is from SNOMED

OBX||CE|883-9^Blood Group^LN||F-D1250^Group O^SM|

A code that identifies the data in OBX-5 (ABO Blood Group)

OBX-5: Data
A code for Group O



v2.x Syntax

```
MSH|^~\&|REGADT|MCM|FENG||199112311501||ADT^A04^ADT_A01|000001|P|2.4||  
EVN|A04|199901101500|199901101400|01||199901101410  
PID|||191919^^GENHOS^MR~371-66-9256^^^USSA^SS  
|253763|MASSIE^JAMES^A||19560129|M|||171 ZOBERLEIN^^ISHPEMING^MI^49849^""^|  
|(900)485-5344|(900)485-5344||S^^HL70002|C^^HL70006|10199925^^^GENHOS^AN  
|371-66-9256||  
NK1|1|MASSIE^ELLEN|SPOUSE^^HL70063|171 ZOBERLEIN^^ISHPEMING^MI^49849^""^  
|(900)485-5344|(900)545-1234~(900)545-1200|EC1^FIRST EMERGENCY CONTACT^HL70131  
NK1|2|MASSIE^MARYLOU|MOTHER^^HL70063|300 ZOBERLEIN^^ISHPEMING^MI^49849^""^  
|(900)485-5344|(900)545-1234~(900)545-1200|EC2^SECOND EMERGENCY CONTACT^HL70131  
NK1|3  
NK1|4|||123 INDUSTRY WAY^^ISHPEMING^MI^49849^""^|(900)545-1200  
|EM^EMPLOYER^HL70131|19940605||PROGRAMMER|||ACME SOFTWARE COMPANY  
PV1||O|O/R|||0148^ADDISON,JAMES|0148^ADDISON,JAMES||AMB|||  
|0148^ADDISON,JAMES|S|1400|A|||GENHOS|||199501101410|  
PV2|||199901101400|||199901101400  
ROL||AD|CP^^HL70443|0148^ADDISON,JAMES  
OBX||NM|3141-9^BODY WEIGHT^LN||62|kg|||F  
OBX||NM|3137-7^HEIGHT^LN||190|cm|||F  
DG1|1|19||0815^BIOPSY^ACODE||00|  
GT1|1||MASSIE^JAMES^""^""^""^""^||171 ZOBERLEIN^^ISHPEMING^MI^49849^""^  
|(900)485-5344|(900)485-5344|||SE^SELF^HL70063|371-66-9255|||MOOSES AUTO CLINIC  
|171 ZOBERLEIN^^ISHPEMING^MI^49849^""^|(900)485-5344|  
IN1|0|0^HL70072|BC1|BLUE CROSS|171 ZOBERLEIN^^ISHPEMING^M149849^""^|  
|(900)485-5344|90|||50 OK|
```

