Clinical Analysis of Adverse Drug Reactions

Christine Chamberlain, Pharm.D., BCPS
Clinical Center Pharmacy Department
National Institutes of Health

March 2011

Objectives

- Define adverse drug reactions
- Discuss epidemiology and classification of ADRs
- Describe basic methods to detect, evaluate, and document ADRs
- FDA adverse drug reaction initiatives


Definition - WHO

- WHO

- response to a drug that is noxious and unintended and that occurs at doses used in humans for prophylaxis, diagnosis, or therapy of disease, or for the modification of physiologic function
- Purposely excludes therapeutic failures, overdose, drug abuse, noncompliance, and medication errors

Definition - FDA

- Adverse drug reaction according to the U.S. Food and Drug Administration (FDA)
 - Any undesirable experience associated with the use of a medical product in a patient.



Pharmacovigilance

- The science of adverse drug reactions
- detection, assessment, understanding and prevention of adverse effects
- Regulatory agencies, pharmaceutical companies and individual healthcare providers enact a system

Epidemiology of ADRs

- substantial morbidity and mortality
- estimates of incidence vary with study methods, population, and ADR definition
- 4th to 6th leading cause of death among hospitalized patients*
- 6.7% incidence of serious ADRs*
- 0.3% to 7% of all hospital admissions
- annual dollar costs in the billions

*JAMA. 1998;279:1200-1205.

Epidemiology

- 82% of American adults take at least one medication and 29% take five or more
- 700,000 emergency department visits and 120,000 hospitalizations are due to ADEs annually
- \$3.5 billion is spent on extra medical costs of ADEs annually
- At least 40% of costs of ambulatory (nonhospital settings) ADEs are estimated to be preventable

http://www.cdc.gov/MedicationSafety/basics.html

Increase in Adverse Drug Events

- Development of new medications
- Discovery of new uses for older medications
- Aging American population
- Increase in the use of medications for disease prevention
- Increased coverage for prescription medications

http://www.cdc.gov/MedicationSafety/basics.html

Classification - Onset - Severity Type Classification - Onset of event: Acute » within 60 minutes » Anaphylactic shock, bronchoconstriction Sub-acute » 1 to 24 hours » Rash, serum sickness, abx associated colitis Latent » > 2 days » Eczematous eruptions, tardive dyskinesia **Classification - Severity** Severity of reaction: » bothersome but requires no change in therapy » Metallic taste with metronidazole Moderate » requires change in therapy, additional treatment, hospitalization » Amphotericin induced hypokalemia Severe » disabling or life-threatening » QT interval prolongation, kidney failure

Classification - Severity

- FDA Defines Serious ADR
 - · Result in death
 - Life-threatening
 - Require hospitalization
 - Prolong hospitalization
 - Cause disability
 - Cause congenital anomalies
 - Require intervention to prevent permanent injury

Classification

Type A

- » extension of pharmacologic effect
- » often predictable and dose dependent
- » responsible for at least two-thirds of ADRs
- » e.g., propranolol and heart block, anticholinergics and dry mouth

Type B

- » idiosyncratic or immunologic reactions
- » rare and unpredictable
- » e.g., chloramphenicol and aplastic anemia
- » Rash caused by beta lactam antibiotics

IMMUNE REACTION	MECHANISM	CLINICAL MANIFESTATION	TIMING OF REACTION
Type I (IgE mediated)	Drug-IgE binding to mast cells, release of histamine, inflam mediators	Urticaria, angioedema, bronchospasm, pruritis	Minutes to hours after exposure
Type II (cytotoxic)	Specific IgG or IgM antibodies directed at drug-hapten coated cells	Hemolytic anemia, neutropenia, thrombocypenia	Variable
Type III (immune complex)	Tissue deposition of drug-antibody complexes with complement activation, inflam.	Serum sickness, fever, rash, arthralgias, lympadenopathy, urticaria, vasculitis	1-3 weeks after exposure
Type IV (delay hypersensitivity)	MHC presentation of drug molecules on T cells , cytokine and inflam. med. release	Allergic contact dermatitis, maculopapular rash	2 to 7 days after cutaneous drug exposure
	form Am Fam Bhariainn 0		

Common Causes of ADRs Antibiotics Antineoplastics* Anticoagulants Cardiovascular drugs* Hypoglycemics Antihypertensives NSAID/Analgesics Diagnostic agents CNS drugs* *account for 69% of fatal ADRs **Body Systems Commonly Involved** Hematologic CNS • Dermatologic/Allergic Metabolic Cardiovascular Gastrointestinal Renal/Genitourinary Respiratory Sensory **ADR Risk Factors** Age (children and elderly) Multiple medications Multiple co-morbid conditions · Inappropriate medication prescribing, use, or monitoring End-organ dysfunction Altered physiology

Prior history of ADRs

Genetic predisposition

• Extent (dose) and duration of exposure

ADR Detection

- Subjective report
 - patient complaint
- Objective report:
 - · direct observation of event
 - abnormal findings
 - » physical exam
 - » laboratory test
 - » diagnostic procedure

ADR Detection

- Medication order screening
 - · abrupt medication discontinuation
 - · abrupt dosage reduction
 - orders for "tracer" or "trigger" substances
 - orders for special tests or serum drug concentrations
- Spontaneous reporting
- Medication utilization review
 - Computerized screening
 - · Chart review and concurrent audits

ADR Detection in Clinical Trials

- Methods
 - Standard laboratory tests
 - Diagnostic tests
 - Complete history and physical
 - Adverse drug event questionnaire
 - » Extensive checklist of symptoms categorized by body system
 - » Review-of-systems approach
 - » Qualitative and quantitative

ADR Detection in Clinical Trials

Limitations

- exposure limited to few individuals
 - » rare and unusual ADRs not detected
 - » 3000 patients at risk are needed to detect ADR with incidence of 1/1000 with 95% certainty
- exposure is often short-term
 - » latent ADRs missed
- external validity
 - » may exclude children, elderly, women of childbearing age; and patients with severe form of disease, multiple co-morbidities, and those taking multiple medications

ADR Reporting in Clinical Trials 21 CFR 312

- Changes to safety information reporting during clinical trials starting March 2011
- Suspected adverse reaction possibly, probably or definitely related to study agent
- Adverse reaction caused by study agent

Preliminary Assessment

- Preliminary description of event:
 - · Who, what, when, where, how?
 - · Who is involved?
 - What is the most likely causative agent?
 - Is this an exacerbation of a pre-existing condition?
 - Alternative explanations / differential diagnosis
 - When did the event take place?
 - · Where did the event occur?
 - How has the event been managed thus far?

Preliminary Assessment

- Determination of urgency:
 - What is the patient's current clinical status?
 - · How severe is the reaction?
- Appropriate triage:
 - · Acute (ER, ICU, Poison Control)

Detailed Description of Event

- History of present illness
- Signs / Symptoms:
 - · Provoking or palliative factors
 - Quality (character or intensity)
 - · Response to treatment,
 - Severity / extent, Site (location)
 - Temporal relationship (onset, duration, frequency)
 - Other associated signs and symptoms

Pertinent Patient/Disease Factors

- -Demographics
 - age, race, ethnicity, gender, height, weight
- -Medical history and physical exam
 - Concurrent conditions or special circumstances
 - » e.g., dehydration, autoimmune condition, HIV infection, pregnancy, dialysis, breast feeding
 - Recent procedures or surgeries and any resultant complications
 - » e.g., contrast material, radiation treatment, hypotension, shock, renal insufficiency

Pertinent Patient/Disease Factors

- End-organ function
- Review of systems
- Laboratory tests and diagnostics
- Social history
 - » tobacco, alcohol, substance abuse, physical activity, environmental or occupational hazards or exposures
- Pertinent family history
- Nutritional status
 - » special diets, malnutrition, weight loss

Pertinent Medication Factors

- -Medication history
 - Prescription medications
 - Non-prescription medications
 - Alternative and investigational therapies
 - Medication use within previous 6 months
 - Allergies or intolerances
 - · History of medication reactions
 - · Adherence to prescribed regimens
 - Cumulative medication dosages

Pertinent Medication Factors

- Medication
 - Indication, dose, diluent, volume
- Administration
 - Route, method, site, schedule, rate, duration
- Formulation
 - · Pharmaceutical excipients
 - » e.g., colorings, flavorings, preservatives
 - Other components
 - » e.g., DEHP, latex

,	
,	
,	

Pertinent Medication Factors -Pharmacology -Pharmacokinetics (LADME) -Pharmacodynamics -Adverse effect profiles -Interactions · drug-drug drug-nutrient · drug-lab test interference -Cross-allergenicity or cross-reactivity **ADR Information** · Incidence and prevalence Mechanism and pathogenesis · Clinical presentation and diagnosis Time course Dose relationship Reversibility · Cross-reactivity/Cross-allergenicity Treatment and prognosis **ADR Information Resources** Tertiary » Reference books - Medical and pharmacotherapy textbooks - Package inserts, PDR, AHFS, USPDI - Specialized ADR resources Meyler's Side Effects of Drugs

Textbook of Adverse Drug Reactions

Drug interactions resourcesMicromedex databases (e.g., TOMES,

POISINDEX, DRUGDEX)

»Review articles

ADR Information Resources • Secondary

- » MEDLARS databases (e.g., Medline, Toxline, Cancerline, Toxnet)
- » Excerpta Medica's Embase
- »International Pharmaceutical Abstracts
- »Current Contents
- »Biological Abstracts (Biosis)
- » Science Citation Index
- »Clin-Alert and Reaction
- »Scopus

ADR Information Resources

- Primary
 - »Spontaneous reports or unpublished data
 - -FDA
 - Manufacturer
 - »Anecdotal and descriptive reports
 - Case reports, case series
 - »Observational studies
 - Case-control, cross-sectional, cohort
 - »Experimental and other studies
 - -Clinical trials
 - Meta-analyses

Causality Assessment

- Prior reports of reaction
- Temporal relationship
- De-challenge
- · Re-challenge
- Dose-response relationship
- Alternative etiologies
- Objective confirmation
- Past history of reaction to same or similar medication

_		
_		
_		
_		
_		
_		
_		
_		
_		
_		
_		
_		
_		
_		
_		
_		
_	<u> </u>	
_		
_		
_		
_		
_		
_		

Causality Assessment

- -Examples of causality algorithms
 - Kramer
 - Naranjo and Jones
- -Causality outcomes
 - Highly probable
 - Probable
 - Possible
 - Doubtful

	To as	sess the adverse drug i	reaction, please answer the following qu	westeownas	re and gn	e the periment score.	
	_			Yes	No	Do Not Know	Score
	1.	Are there previo	ous conclusive reports on	+1	0	0	
	2.	Did the adverse	event appear after the was administered?	+2	-1	0	_2_
	3.	Did the adverse	reaction improve when the atinued or a specific	+1	0	0	<u>_l</u> _
Naranjo ADR	4.		reactions appear when the	+2	-1	0	_0_
Probability Scale	5.	Are there altern	ative causes (other than the l on their own have caused	-1	+2	0	_2_
	6.		reappear when a placebo	-1	+1	0	_0_
	7.	Was the drug de	etected in the blood (or concentrations known to be	+1	0	0	<u>_l</u> _
Naranjo CA. Clin Pharmacol Ther	8.	Was the reactio	n more severe when the sed, or less severe when the	+1	0	0	_0_
1981;30:239-45	9.	Did the patient	have a similar reaction to ilar drugs in <i>any</i> previous	+1	0	0	_0_
	10.		e event confirmed by any	+1	0	0	_1_
		,				Total Score	_8_
	Tota	ıl Score	ADR Probability Classifican	tion			
	9		Highly Probable				
	5-8		Probable Possible				
	0		Doubtful				

Management Options

- Discontinue the offending agent if:
 - » it can be safely stopped
 - » the event is life-threatening or intolerable
 - » there is a reasonable alternative
 - » continuing the medication will further exacerbate the patient's condition
- Continue the medication (modified as needed) if:
 - » it is medically necessary
 - » there is no reasonable alternative
 - » the problem is mild and will resolve with time

Management Options

- Discontinue non-essential medications
- Administer appropriate treatment
 - » e.g., atropine, benztropine, dextrose, antihistamines, epinephrine, naloxone, phenytoin, phytonadione, protamine, sodium polystyrene sulfonate, digibind, flumazenil, corticosteroids, glucagon
- Provide supportive or palliative care
 e.g., hydration, glucocorticoids, warm / cold compresses, analgesics or antipruritics
- Consider rechallenge or desensitization

Follow-up and Re-evaluation

- Patient's progress
- Course of event
- Delayed reactions
- · Response to treatment
- Specific monitoring parameters

Reporting ADRs

Reportable

 All significant or unusual adverse drug reactions as well as unanticipated or novel events that are suspected to be drug related

Reporting ADRs

Reportable

- Hypersensitivity
- Life-threatening
- Cause disability
- Idiosyncratic
- Secondary to Drug interactions
- Unexpected detrimental effect
- Drug intolerance
- Any ADR with investigational drug


Documentation and Reporting

- Medical record
 - Description
 - Management
 - Outcome
- Reporting responsibility
 - JCAHO-mandated reporting programs
 - · Food and Drug Administration
 - » post-marketing surveillance
 - » particular interest in serious reactions involving new chemical entities
 - · Pharmaceutical manufacturers
 - Publishing in the medical literature

Components of an ADR Report


- Product name and manufacturer
- Patient demographics
- Description of adverse event and outcome
- Date of onset
- Drug start and stop dates/times
- Dose, frequency, and method
- Relevant lab test results or other objective evidence
- De-challenge and re-challenge information
- Confounding variables


_		
-		
_		
_		
_		
_		
_		
_		
_		
-		
-		
_		
-		
-		
- -		
-		
-		
-		
-		
-		
_		
-		
- -		
_		
-		
-		
-		
-		
-		
- -		
- - -		
-		
- - -		
-		
- - -		
-		
- - -		
-		
- - - -		



MedWatch Direct Reports

- Reports submitted directly to FDA through MedWatch by
 - Internet on line reporting form
 - Mail or Fax
 - Telephone 1-800-FDA-1088





ISMP – QuarterWatch™ 2010 Quarter 2

- Analyzed computer excerpts from 33,068 reports
- Continued increase in reports up 12% compared to Q2 2009
- Reports from manufacturers increased 24%
- Reports from consumers and health care professionals were 25% fewer

ISMP – QuarterWatch™ 2010 Quarter 2

Table 1. Selected Drug Safety Signals 2010 Quarter 2					
Drug Names	Brand Names*	Adverse Effect	Cases	PRR#**	P Value
fenta NYL	DURAGESIC	Maladministrations	447	12.6	< 0.01
QUEtiapine	SEROQUEL	Diabetes	191	16.5	< 0.01
in FLIX imab	REMICADE	Skin cancers	154	101.3	< 0.01
alendronate	FOSAMAX	Lower limb fracture	126	50.4	< 0.01
exenatide	BYETTA	Inflammation of pancreas	118	32.5	< 0.01
* May have other	names ** Proportio	nal reporting ratio			

FDA Drug Safety Communications

- FDA provides easy access to important drug safety information
- Risk of Progressive Multifocal
 Leukoencephalopathy (PML) with the use of
 Tysabri (natalizumab) and increases with number
 of infusions
 - 31 confirmed cases of PML received by the FDA as of January 21, 2010
 Additional information for patients and prescribers provided on website

 - This information will be included on the drug label and patient Medication Guide
 - · Limited distribution prescribing system is in place

Risk Evaluation and Mitigation Strategy (REMS)

- Risk management plan that utilizes strategies that go beyond professional labeling to ensure drug benefits outweigh
- The FDA Amendments Act of 2007 (FDAAA) granted the FDA the authority to require the submission and implementation of a REMS
- **REMS** are designed to meet specific serious risk mitigation goals

REMS Considerations

- Does the product fill a significant unmet need?
- What is the magnitude of the risk?
- Do the data suggest ways to mitigate the risk?

REMS Components

- Medication Guide for patients
- Communication Plan for healthcare professionals
- Elements to Assure Safe Use (previously "restricted distribution")
- Implementation system

Medication Guide Requirement

- Patient labeling could help prevent serious adverse events
- The product has serious risks that could affect a patient's decision
- Patient adherence to directions is crucial to product effectiveness

Communication Plan

- If FDA determines a communication plan is needed, it can include:
 - · Letters to healthcare providers
 - Disseminating information through professional societies about serious risk of the drug and any elements to assure safe use

Elements to Assure Safe Use

- Prescriber training or certification
- Certification of dispensers
- Drug administration limited to certain health care settings
- Documentation of safe use prior to dispensing
- Required monitoring of patients
- **Enrollment of patients in a registry**

REMS Example Victoza® (Liraglutide)

- Goal is to inform providers of the risk of acute pancreatitis (including necrotizing pancreatitis) and potential risk of medullary thyroid carcinoma
- Medication guide will be dispensed with each prescription
- Communication Plan
 - Dear doctor letter
 - Direct mail letter each year x 3 yrs
 - Highlighted information for prescribers will be distributed by manufacturer representatives

Sample of Victoza® Medication Guide

- Before taking Victoza, tell your healthcare provider if you have had:
- pancreatitis

- pancreatitis
 stones in your gallbladder (gallstones)
 a history of alcoholism
 high blood triglyceride levels
 These medical conditions can make you more likely to get
 pancreatitis in general. It is not known if having these conditions
 will lead to a higher chance of getting pancreatitis while taking
 Victoza.
- Victoza.
 While taking Victoza:
 Stop taking Victoza and call your healthcare provider right away if you have pain in your stomach area (abdomen) that is severe and will not go away. The pain may happen with or without vomiting. The pain may be felt going from your abdomen through to your back. This type of pain may be a symptom of pancreatitis.

_	

How to get FDA Drug Safety Alerts

- FDA Drug Safety Newsletter
 - http://www.fda.gov/Drugs/DrugSafety/DrugSafetyNewsle tter/default.htm
- MedWatch Safety Alerts
 - http://www.fda.gov/Safety/MedWatch/ucm1684 22.htm
- FDA Patient Safety News
 - · Video news show for health professionals
 - http://www.accessdata.fda.gov/scripts/cdrh/cfd ocs/psn/index.cfm

Future

- I-phone apps for MedWatch
- Hospital systems to report adrs directly to FDA
- FAERS FDA Adverse Event Reporting System (enhanced analysis)
- Standardization of reporting to include data from Japan and Europe
- Federal Adverse Event Task Force (FAET)
- Innovative ways to increase reporting and identification of adverse drug reactions

Federal Adverse Event Reporting Portal Individual Case Safety Report (ICSR) FAET Agencies Wee User User Voluntary Physicians Patients Consumers Local DSMB IRB Institutional Database

Safety Reporting Portal

- Launched in May of 2010, testing phase
- FDA safety issues involving: Human or animal reportable foods
 - Animal drugs
 - Pet foods
- NIH safety issues involving:
 NIH gene-transfer research





Questions ???	