NIH Clinical Pharmacology 3-25-10


Nonclinical Drug Development: With Examples from Oncology Therapeutics

Chris H. Takimoto, MD, PhD, FACP Translational Medicine Ortho Biotech Oncology R&D

25 March 2010



- Employment: Ortho Biotech Oncology R&D/Centocor R&D, Inc., a member of the Johnson & Johnson family of companies
- Stock: Johnson & Johnson
- Off Label Use: I will not discuss off label use of any product but I will refer to previously presented Phase I investigational study data



Drug Development Drug discovery & screening Nonclinical development Animal scale up Phase I studies Phase II studies Phase III studies

Specific examples from anticancer drug development

NIH Clinical Pharmacology 3-25-10

Guidance for Industry

S9 Nonclinical Evaluation for Anticancer Pharmaceuticals


U.S. Department of Health and Human Services Food and Drug Administration Center for Drug Evaluation and Research (CDER) Center for Biologics Evaluation and Research (CBER)

> March 2010 ICH

Goals of Nonclinical Testing of Small Molecule Drugs and Biologicals

- Identify the pharmacologic properties of a pharmaceutical
- Establish a safe initial dose level of the first human exposure
- Understand the toxicological profile of a pharmaceutical
 - e.g., identification of target organs, exposureresponse relationships, and reversibility

-- S9 Guidance for Industry, 2010



Nonclinical Pharmacology Evaluation

- Select appropriate models based on target and MofA
- These studies can:
 - Provide nonclinical proof of principle regarding mechanism of action and efficacy
 - Guide schedule and dose escalation schemes
 - Provide information for selection of test species
 - Aid in start dose selection
 - Selection of investigations biomarkers
 - Justify pharmaceutical combinations
 - Understand pharmacodynamic properties
- -- S9 Guidance for Industry, 2010

Nonclinical Pharmacology Evaluation: In Vitro Studies

- In vitro studies performed in cell lines, cell-free systems
 - Often form the basis for screening and optimization during discovery
- Cellular uptake and membrane transport
 - MDR, MRP, etc
 - Predictions of bioavailability and distribution
- In vitro drug metabolism:
 - P450 isoenzyme inhibition or induction
- Effects on hERG channels (prolonged QT interval risk)
- Preliminary protein binding studies

-- S9 Guidance for Industry, 2010





- Animal screening is too expensive for routine use
- Efficacy demonstrated in disease specific animal models: Proof of therapeutic principle

 Groundwork for clinical development planning
- Evaluation of therapeutic index
 - Toxicity versus efficacy
- Animal pharmacokinetics can guide dose and schedule selction
 - ADME data can be generated in parallel with clinical development
- Preliminary evaluation of candidate biomarkers

-- S9 Guidance for Industry, 2010


NIH Clinical Pharmacology 3-25-10







In Vivo Efficacy Models in Cancer


- Spontaneous tumors
 - Idiopathic
 - Carcinogen-induced
 - Transgenic/gene knockout animals: p53, RB, etc
- Transplanted tumors
 - Animal tumors: Lewis lung, S180 sarcoma, etc
 - Human tumor xenografts: human tumor lines implanted in immunodeficient mice (current NCI standard in vivo efficacy testing system)
 - Human tumors growing in vivo in implantable hollow fibers




NIH Clinical Pharmacology 3-25-10









Xenograft Disadvantages

- Brain tumors difficult to model
- Different biological behavior, metastases rare
 - Survival not an ideal endpoint: death from bulk of tumor, not invasion
- Shorter doubling times than original growth in human
- Less necrosis, better blood supply
- Difficult to maintain animals due to infection risks
- Host directed therapies (angiogenesis, immune modulation) may not be applicable
 - Human vs. murine effects
 - Ability to mimic the human tumor microenvironment is limited

Other Efficacy Models

- Orthotopic animal models: Tumor cell implantation in target organ
 - Metastatic disease models
- Transgenic Animal Models
 - P53 or other tumor suppressor gene knockout animals
 - Endogenous tumor cell development
 - May be of high value for mAb therapies
- Three-dimensional co-culture models
 - Reconstitution of the tumor microenvironment
- Low passage xenograft tumors
 - Direct implantation from patients to animals

Nonclinical Safety Studies

- Safety pharmacology
- · Pharmacokinetic and toxicokinetics studies
- Genotoxicity studies
- Reproductive toxicity studies
- Carcinogenicity studies
- Formal toxicology studies
 - Single dose toxicity studies
 - Repeated dose toxicity studies
- Excellent references
 - Anticancer Drug Development Guide, 2nd edition, BA Teicher and PA Andrews, editors, Humana Press, Totowa, NJ, 2004
 - For oncology agents, FDA Guidance for Industry, S9 Nonclincial evaluation for anticancer pharmaceuticals, March 2010

Nonclinical Toxicology Studies in Oncology

- GLP Toxicology is expected
 - Use the same route and formulation
 - Use the approximate clinical schedule
- For small molecules, general toxicology testing ususally includes rodents and non-rodents (i.e., dogs)
 - Non-human primates for biologicals
- Assessment of the potential to recover from toxicity should be provided
- Embryofetal toxicity studies of oncology agents should be available when marketing application is submitted
- Genotoxicity studies not essential for clinical trials in advanced cancer
 - Perform to support marketing
- Carcinogenicity studies not warranted for advanced cancer
- -- S9 Guidance for Industry, 2010


Treatment Schedules to Support Initial Oncology Trials

(S9 Guidance for Industry, March 2010)

Clinical Schedule	Nonclinical Treatment Schedule *
Once every 3-4 wks	Single dose
Daily for 5 days every 3 wks	Daily for 5 day
Daily for 5-7 days, alternating wks	Daily for 5-7 days, alternating wks (2-dose cycles)
Once a week for 3 wks, 1 wk off	Once a week for 3 weeks
Two or three times a week	Two or three times a week for 4 wks
Daily	Daily for 4 wks
Weekly	Once a week for 4-5 doses

Maximum Recommended Starting Dose (MRSD) for FIH Trials

- Step 1: Determination of the No Observed Adverse Effect Level (NOAEL)
- Step 2: Conversion of NOAEL to Human Equivalent Dose (HED)
- Step 3: Selection of the most appropriate animal species
- Step 4: Application of a safety factor to determine MRSD
- Step 5: Compare MRSD with pharmacologically active dose (PAD)





Step 1: Determination of No Observed Adverse Effect Level (NOAEL)

- NOAEL Definition
 - The highest dose level that does not produce a significant increase in adverse effects in comparison to the control group
 - Not the same as the no observed effect level
- Review all available data in all species tested
- Adverse events can be overt toxicities, surrogate laboratory markers, or exaggerated PD effects
 - Adverse effects defined as events that are considered unacceptable if produced by the initial dose in a Phase I clinical trial




- Normalization of toxic dose levels across species often based upon body surface area
 - Deviations from BSA normalization must be justified
- Animal dose in mg/kg is converted to mg/m² and reconverted to mg/kg
 - Many cancer treatments are dosed based on BSA (mg/m²)








- After the NOAEL from all toxicology studies are converted to HED, then the MRSD must be derived from the most appropriate species
- By default, use the most sensitive species, but must also consider...
 - Pharmacokinetic ADME differences
 - Class pharmacodynamic effects
 - Agent pharmacology, receptor cross reactivity, etc
- Example
 - Phosphorothioate antisense DLT in humans and monkeys is complement activation
 - Does not occur in rodents



Altering the Safety Factor

- Increasing the safety factor
 - Steep dose response curve
 - Severe toxicities anticipated
 - Non-monitorable toxicity
 - Toxicities without premonitory signs
 - Variable bioavailability
 - Irreversible toxicity
 - Unexplained mortality
 - Large PK variability
 - Non-linear PK
 - Inadequate dose-response data

- Novel therapeutic target
- Animal models with limited utility
- Decreasing the safety factor
 - Requires highest quality toxicology data
 - Well characterized class of drugs
 - If NOAEL is based on toxicity studies of longer duration than the proposed clinical trial





- In oncology, the start dose at 1/10 the severely toxic dose in 10% of animals (STD10) in rodents
- If non-rodent is most appropriate species, then 1/6 the highest non-severely toxic dose (HNSTD)
 - HNSTD is the highest dose level that does not produce evidence of life-threatening toxicities or irreversible findings

-- S9 Guidance for Industry, 2010

Biologicals: MABEL Instead of NOAEL, MAYBE ?

- In the wake of the Tegenero FIH disaster, new recommendations exist for starting dose selection in Europe
 - EMEA Guidelines, 2007
- MABEL: minimal anticipated biological effect level
 - The anticipated dose level leading to a minimal biological effect level in humans
 - Consider differences in sensitivity for the mode of action across species
- Consider selection of starting doses based upon reduction from the MABEL, not NOAEL dose

Calculation of MABEL

(EMEA Guidelines, 2007)

- MABEL calculations should utilize all in vitro and in vivo information from PK/PD experiments, including...
 - Target binding and receptor occupancy data in target cells in vitro in human and animals
 - Concentration-response curves in vitro in target human cells and dose/exposure-response in vivo in relevant animals
 - Exposures at pharmacological doses in relevant animals
- Wherever possible an integrated PK/PD modeling approach should be used
- Apply a safety factor to the MABEL for the recommended starting dose
- If NOAEL method gives a different estimation, use the lowest value unless otherwise justified

The Biomarker Hypothesis

(adapted from N Dracopoli)

- Increase probability of technical and registrational success
 - Predictive toxicology
 - Early proof of mechanism of action
 - Deeper PK/PD exploration
 - Precise determination of biologically effective dose
- Permit focused clinical studies with higher probability of demonstrating clinical benefit
 - Adaptive trial designs
 - Prospective screening of patients for enrollment in clinical trials
- Enable more cost-effective delivery of healthcare
 - Personalized medicine
 - Value-based pricing

Biomarkers in Drug Development

Pharmacodynamic/Mechanism of Action Biomarkers

- Inform about a drug's pharmacodynamic actions
- Most relevant to early development
 - Dose and schedule selection
 - Define pharmacological behavior in patients
 - · Goal: Improve efficiency of early development

Predictive Biomarkers


- Identify patients who will/will not respond to treatment
- Most relevant to mid/late development
 - · Basis for stratified/personalized medicine
 - Develop co-diagnostic biomarker assays
 - Goal: Enrich treatment population to maximize benefit


NIH Clinical Pharmacology 3-25-10

An Oncology Example: How Preclinical Studies Can Drive Clinical Drug Development

Why New Strategies for Oncology Drug Development are Needed


- Poor efficiency of historical oncology drug development efforts
 - Yet costs continue to rise
 - Oncologic diseases face specific challenges
- Modern treatments are molecularly targeted in contrast to conventional cytotoxic chemotherapy
 - Previously, mechanism of action was irrelevant to clinical trial design
- Emphasis on biomarkers and individualized drug therapies





Characteristics of Molecularly Targeted Therapies (adapted from Paoletti 2005)

Characteristic	Cytotoxic Agents	Targeted Agents
Discovery	Cell based, empirical	Receptor based screen, rationale
Mechanism	Often unknown	Basis for screening
Pharmacological Effect	Cytotoxic	Cytostatic
Specificity	Non-selective	Selective
Dose and schedule	Pulsed, cyclical at MTD	Continuous, at tolerable dose
Development Strategy	Biomarkers for decision making is rare	Biomarkers for PD/MofA and patient selection



The Pharmacological Audit Trail

Vol. 2, 131–138, February 2003

Molecular Cancer Therapeutics 131

Commentary

Auditing the Pharmacological Accounts for Hsp90 Molecular Chaperone Inhibitors: Unfolding the Relationship between Pharmacokinetics and Pharmacodynamics¹


Paul Workman² Cancer Research UK Centre for Cancer Therapeutics, Institute of Cancer Research, Sutton, Surrey SN2 5NG United Kingdom fect (e.g., the inhibition of proliferation, cell cycle progression, survival, invasion, or angiogenesis); and (f) the achievement of a clinical response. By making measurements at each of these hierarchical levels of drug action, it is possible





-- Paul Workman, Mol Cancer Therap 2003 and Current Pharmaceut Design 2003

The Pharmacological Audit Trail

- A series of sequential questions or benchmarks to evaluate in early drug development
 - Likelihood of failure decreases as each successive benchmark is addressed
- Stepwise approach to proof of principle
 - Modulation of the intended target results in clinical benefit
- Organize strategic thinking about early development assets
 - Allows for critical decision making based upon biomarker and clinical endpoints
- Applies equally to preclinical and early clinical development







PK-PD Model-Based Drug Development


- Model-Based Drug Development
 - Preclinical PK/PD/biomarker models with direct relevance to clinical setting
- Requires extensive resource investment preclinical pharmacology studies
 - Discovery Research -- Clinical Pharmacology
 - Biomarkers -- Clinical/Transl Medicine
- Essential for evaluation of the PhAT benchmarks in first-in-human Phase 0 or 1 clinical trials

NIH Clinical Pharmacology 3-25-10



A New Approach

- Translational Phase I study with Biomarker Defined Endpoints
 - A new study design for targeted oncology agents
- PD/MOA biomarkers are formal study endpoints
 - Biologically effective dose (BED): biomarker defined
 - Maximum tolerated dose (MTD): toxicity defined
 - Recommended Phase 2 dose range: toxicity and biomarker defined
- Allows for the objective evaluation of the PhAT benchmarks



New Phase I Study Design Requirements

- Validated/qualified PD/MOA biomarker assay
 - Robust and reproducible
- Measurable signal in normal and malignant tissues
 - Surrogate tissues: skin, buccal mucosa, PBMC, etc.
 - Tumor biopsies
- Prestudy definition of a positive biomarker signal
 What change is associated with antitumor activity?
- Phase I centers and study support staff comfortable with tissue biopsies

Example


Phase 1 Pharmacokinetic (PK) and Pharmacodynamic (PD) Study of JNJ-26854165 (Serdemetan*) in Patients with Advanced Refractory Solid Tumors

Josep Tabernero¹, Luc Dirix², Patrick Schöffski³, Andrés Cervantes⁴, Jose Antonio Lopez-Martin⁵, Jaume Capdevila¹, José Baselga¹, Ludy van Beijsterveldt⁶, Brett Hall⁶, Hans Winkler⁶, Silvija Kraljevic⁶, Janine Arts⁶, Sen Hong Zhuang⁶

¹Vall d' Hebron University Hospital, Barcelona, Spain; ²AZ Sint Augustinus, Wilrijk, Belgium; ³University Hospitals Leuven, UZ Gasthuisberg, Belgium; ⁴Hospital Clínico Universitario de Valencia, Spain; ⁵Hospital Universitario 12 de Octubre, Madrid, Spain; ⁶Ortho Biotech Oncology Research and Development, a Division of Johnson & Johnson Pharmaceuticals, Beerse, Belgium



- Designed to modulate p53 expression
- Increased p53 levels lead to:
 - Apoptosis
 - Senescence
 - Cell cycle arrest
 - Block of angiogenesis
 & metastasis



Study Design


- Standard 3 + 3 patient Phase I dose escalation design
 - Toxicity defined endpoints: Dose limiting toxicity (DLT) and Maximum tolerated dose (MTD)
- Continuous PK-PD monitoring
 - Pharmacokinetics: standard PK profiling, drug-drug interaction (DDI) profile and food intake effect
 - Pharmacodynamic (PD) activity
 - Sequential and skin biopsies in all patients for IHC for p53, Ki67, TUNEL
 - Selected tumor biopsies for IHC (similar to skin)
 - Plasma: MIC-1 (p53 response gene product), CK18 (apoptosis); LC/MS: proteomics and metabolomics


- Anti-tumor activity


Actual Dose Escalation Cohorts


Cohort No.	Dose (mg QD)	Number of patients treated (evaluated*)	DLT
C 1	4	4 (3)	None
C 2	8	3	None
C 3	20	3	None
C 4**	40	4 (3)	None
C 5	60	4	None
C 6	90	4	None
C 7	150	4	None
C 8	225	7	None
C 9	300	7	1 (Gr 3 QTc)
C 10	350	4 (3)	None
C 11	400	3	2 (Gr 3 QTc, Gr 3 rash)


*Subjects evaluated for DLT determination **Drug Drug Interaction (DDI) cohort











Phase I Study of JNJ-26854165 (Serdemetan)

- Study accrual is completed
- This trial was not originally designed with formal biomarker-defined endpoints, but clinical trial data matches well with this study design
- Further work on this class of agents is ongoing

Conclusions

- PK-PD model-based drug development is the cornerstone for our early development strategy
 - Requires substantial investments in preclinical testing
- The Pharmacological Audit Trail can help organize strategic thinking for the early development of molecularly targeted therapies
- Novel study designs are required for the optimal implementation of this strategy
 - Example: Translational Phase I study with biomarkerdefined endpoints
- It is a great time to be working in oncology drug development!!

