Coercion and Undue Inducement in Research

Alan Wertheimer, Ph.D.

Professor Emeritus of Political Science
University of Vermont

Senior Research Scholar

Department of Bioethics

Clinical Center

National Institutes of Health

October 2012

Disclaimer and Acknowledgement

 The views expressed are my own. They do not necessarily represent any position or policy of the National Institutes of Health or the Department of Health and Human Services.

The basic problem

- Research requires subjects
- In some cases, recruitment is easy
- But in some cases, recruitment is difficult
- Participation may be risky, inconvenient, painful
- Altruism is limited
- Subject accrual is often slow. Many studies do not complete. More studies are not proposed.

The basic problem

- "Lack of study volunteers hobbles cancer fight" (NYT Headline, August, 2009)
- 3% of adult cancer patients participate
- More than 1/5 trials sponsored by NIC failed to enroll a single subject and only half reached minimum needed for a meaningful result

Recruitment as Collective Action Problem

- It is in everyone's interest that research be conducted
- It is sometimes in an individual's interest NOT to participate
- In some areas of social life we use government coercion to solve a collective action problem
- Not in research

The basic problem

- Consent is required
- We may use incentives to get people to participate
- Not a new phenomenon

Walter Reed

- Yellow fever studies in Cuba (1900).
- Intentional exposure.
- Paid \$100 in gold.
- \$100 bonus for successful infection.
- Payable to family in the event of death.



Payment Today

- "Make \$1,000's... Get paid hundreds weekly in additional cash income, part-time, while relaxing in a million-dollar, get paid research study... Yes, there are thousands of cash paying studies and even free medical care available!"
- "Get paid up to \$1,000 weekly for safe sex research?"

http://www.rxgetpaid.com



Other Incentives

- Free treatment (or chance of treatment)
- Free medical examinations
- Experimental Treatment
- Post-trial treatment
- Ancillary Care or Incidental Findings

Payment in the U.S.

- Payments made in Phase I, II, III
- At least 23% of protocols at academic institutions paid subjects.
 - Few have any method of tracking paid studies
- Frequency of payment higher at independent IRBs and pharmaceutical companies.

Dickert, Grady, and Emanuel. *Annals of Int Med*. 2002

Amount of Money Being Paid (n=467 studies)

< \$100	30.4%	
\$100-249	33.6%	
\$250-499	21.2%	
\$500-999	10.5%	
\$>1,000	4.3%	
Mean	\$266	
Median	\$155	

Amounts shown in U.S. dollars

Grady, Dickert, Jawetz, and Emanuel.

Why do we pay research subjects?

- Reimbursement
- Compensation for time and burdens
- Compensation for risk
- Avoid exploitation
- Incentive for recruitment
- Some reasons are more accepted than others


Results: Reasons for paying and views about paying healthy and patient volunteers

% who agree or strongly agree that it is acceptable to	Healthy Volunteer	Patient-subjects with no prospect of benefit	Patient-subjects with a prospect of benefit
Offer Money	86.8%	78.7%	71.1%
Reimburse for expenses	97.9%	95.4%	92.8%
Compensate for time, effort, inconvenience	94.5%	90.7%	86.2%
Offer money as an incentive	58.3%	56.2%	50.2%
Offer money to compensate for risk	36.4%	36.9%	34.6%

The State of Payment in the U.S.

- Payment is very common.
- All types of subjects are paid.
- Payment is erratic with little institutional guidance or consistency.
- Payment is generally modest.
- Significant disagreement over payment as incentive or for risk.
- Lots of worrying

Results: concern about payment



What are the worries?

- Consent
 - Coercion
 - Undue Influence
- Other
 - Commodification Guinea Pigging
 - Trust in research enterprise
 - Scientific
 - Conceal information
 - Feign illness (psychiatric research)
 - Reporting adverse events
 - Skewing population

Anecdotal Evidence

- Anecdotal evidence suggests that many IRB members think that payment or offers of medical care do or can coerce or constitute undue influence
- Our study showed that this hypothesis is correct

What's the problem?

- To the extent that IRB members' attitudes regarding payment are ethically sound, they appropriately influence payment practices
- studies should not be approved if participants' consent is likely to be compromised by coercion or undue influence.
- If IRB members' concerns are based on conceptual or ethical misconceptions, unnecessary limits may be placed on payments to research participants and impede valuable research without ethical cause.

Consequences of the worries

- Fact that payments are frequently made does not show that worries make no difference (speed limits)
- Not how many protocols are disapproved
- But how many protocols that would otherwise pass muster are not proposed or even considered?
- Does research progress more slowly?

Our Thesis

- Many of the prevalent concerns about payment are largely misguided.
- Payment never coerces.
- Payment raises ethical concerns with respect to consent only when it unduly influences participants by distorting their perception of research risks and benefits.
- In the absence of evidence that such distortions occur, IRBs should be reluctant to conclude that offers of payment undermine the validity of consent

Emily A. Largent, Christine Grady, Franklin G. Miller, and Alan Wertheimer, "Misconceptions about Coercion and Undue Inducement: Reflections on a Survey of IRB Members, *Bioethics forthcoming*.

Regulatory Statements

The Common Rule

"An investigator shall seek such consent only under circumstances that provide the prospective subject or the representative sufficient opportunity to consider whether or not to participate and that minimize the possibility of coercion or undue influence."

45 CFR 46, 116

FDA

"The IRB should review both the amount of payment and the proposed method and timing of disbursement to assure that neither are coercive or present undue influence." FDA Information Sheets, 1998

OHRP

"... the IRB should review both the amount of payment and the proposed method of disbursement to assure that neither entails problems of coercion or undue influence. Such problems might occur, for example, if the entire payment were to be contingent upon completion of the study or if the payment were unusually large. Payments should reflect the degree of risk, inconvenience, or discomfort associated with participation."

Office of Human Research Protection. IRB Guidebook.

How do IRB members understand coercion?

Results: Respondent views on coercion and undue

influence

% of respondents who	Then	Then
agreed or strongly agreed	it is	it is undue
that if the research	coercion	influence
participants		
are threatened with harm	91.2%	
will participate with	64.8%	81.0%
payment when otherwise		
they would not		
feel they have no	81.6%	79.2%
reasonable alternative but		
to participate because of		
payment		
ability to accurately		98.2%
perceive risks and benefits		
is distorted when offered		
payment		

- Some people think that offers of payment are coercive if and when they get someone to agree to participate in research when they would otherwise not.
- There are numerous ways of motivating people to do things that they would otherwise not do
 - A persuades B to give blood or go to a movie or invest in a mutual fund
 - A offers the teenager next door \$20 to mow his lawn.
 - As a general proposition, offers do not coerce.
 - Offers can be indecent and immoral but they do not coerce

- A coerces B to do consent to do X in a way that invalidates B's consent only if A proposes to harm B if B does not consent to do X
- The Belmont Report: "Coercion occurs when an overt threat of harm is intentionally presented by one person to another in order to obtain compliance."
- Examples
 - Gunman case
 - Extortion
 - The Godfather's Offer

- Threats v. offers
- Threats reduce options
- Offers enhance options

- Some people think that people are coerced to participate in research when they have no reasonable alternative but to consent to participate.
- Appeal to gunman case
 - "but we could not say that my handing over the wallet was an autonomous, let alone a consenting act since I was, after all, under threat. I had no other "real", i.e. reasonable alternative."

Thomas Schramme, "Coercive Threats and Offers in Psychiatry"

Lack of Income

 "Nevertheless, many in the field worry that lower-income patients who either need the money or cannot afford conventional treatment are subject to a different kind of pressure. It is 'coercion through lack of income,' explains David J. Rothman . . . 'Monetary need may cloud a patient's decision-making, exposing the individual to a greater level of risk than he or she might otherwise accept'."

Gabriella Rosen, "Studying Drugs in All the Wrong People" Scientific American Mind, September 6, 2012.

No Reasonable Alternative

- Attractive but mistaken view
- In most cases of coercion, target has no reasonable alternative but to agree.
- "Give me your money or I'll beat you up."
- But it does NOT follow that she is coerced
 BECAUSE she has no alternative but to agree.

- We do not say that a patient who agrees to surgery or chemotherapy because the only alternative is death has been coerced to consent or that her consent to treatment is involuntary or invalid.
- We do not describe people as coerced if they take an unpleasant job in order to provide for their families.
- It is 'coercion through lack of income' (Rothman)

Coercion and Jesse Gelsinger

- Jesse Gelsinger, 18, had a mild form of a rare metabolic disorder
- In 1999, enrolled in Phase I gene-therapy trial at U Penn.
- On Sept 13, he was injected with a weakened cold virus carrying corrective genes. Four days later he died from an immune reaction to the virus vector

Coercion and Jesse Gelsinger

- Gene therapy not designed for treatment of people like Jesse who had mild form of disease, but for neonates with a more severe and almost always fatal form.
- Researchers had planned to test treatment on terminal neonates
- They were persuaded to test it on adults because adults could give consent

Coercion and Jesse Gelsinger

- Arthur Caplan: The parents of dying infants are incapable of giving informed consent –
 "They are coerced by the disease of the child"
- In my view, Caplan is wrong.

Coercion

- Issue is not merely semantic
- Issue is the regulatory and decisional effects of describing or labeling payment as coercive

Coercion is Rare in Research

- Cases where retribution is conceivable.
 - A physician may threaten to abandon a patient who refuses to participate in a study.
 - Explicit v. tacit threats
- Perceived coercion is possible.
 - Patient participates in a study run by his PCP because the patient mistakenly fears his care is contingent on participation.

A clear answer?

- "How large a payment constitutes "undue influence" or a coercive offer to participate in research is a question . . . for which no clear answer is forthcoming." (Ruth Macklin)
- A clear answer is forthcoming: offers of payment do not coerce
- Stop worrying about coercion

Undue Influence

- When do offers of payment constitute undue influence?
- A different question

Inducement

- Inducements are offers that get people to do things they would not otherwise do.
- Inducements are typically unproblematic
 - Jobs
 - Market transactions
 - Parenting

Undue Inducement

"...monetary inducements may be undue if they alter patients' decision-making processes such that they do not appropriately consider the risks of participating." Halpern, et. al. Arch. Intern Med. 2004

Undue Inducement

"An offer one could not refuse is essentially coercive (or "undue"). Undue inducements may be troublesome because offers that are too attractive may blind prospective subjects to the risks or impair their ability to exercise proper judgment . . . "

Office of Human Research Protection. IRB Guidebook.

The Core of Undue Inducements

- Inducements are problematic when they distort the target's decision-making.
- Tunnel Vision
 - Focusing on gain
 - Ignoring cost
- Myopia
 - Overweighting short term gains
 - Underweighting long term costs
 - Hyperbolic discounting

Undue Influence

- "Monetary need may cloud a patient's decision-making, exposing the individual to a greater level of risk than he or she might otherwise accept" (David Rothman)
- Half right

Risky Jobs

- Coal mining
- Logging
- Commercial fishing
- Structural Steel
- Fire fighters
- Soldiers
- Is research different?

How much should subjects receive?

Level

- Reimbursement
- Inconvenience
- Time
- Risk
- Market or opportunity cost

Equality

- Everyone receives the same absolute payment
- Everyone receives payment tied to opportunity cost

Wage Payment Model

- Opportunity cost model would not be accepted
 - Jury compensation
- Treats research as a form of unskilled labor
- Standardized payment for time and for procedures.

Wage Payment Model-Advantages

- Provides consistency.
- Treats research participation as labor.
- Offers appropriately limited protection from undue inducement.
- Prevents unfair advantage exploitation by ensuring reasonable standard payment tied to the nature of the work
- Controls research costs.

Wage Payment -- Disadvantages

- Insufficient incentive
- Unfair to high wage earners
- Fair subject selection and demographic disproportionality

Conclusion

- Does payment or paying more compromise the voluntariness of consent? It might, but probably less than is often thought.
- Does non-payment or paying too little increase the likelihood of exploitation? It might, but stay tuned.