NCTVL Standard Operating Procedure (SOP)					
Title:	Immunofluorescence Assay for Circulating Tumor Cells Using the CellSearch				Page 1 of 24
Doc. #:	LHTP003.8.1	Revision:	D	Effective Date:	4/6/2012

Pharmacodynamic Assay Development and Implementation Section (PADIS)

Applied Developmental Directorate

SAIC-Frederick, Inc.

Frederick National Laboratory for Cancer Research

Technical Reviewer:	Lihua Wang	Date: 4-6-2012
Secondary Reviewer:	QA Review	Date: 4-9-2012
PADIS Approval:	Robert J. Kinders	Date: 4-10-2012
LHTP Approval:	Ralph E. Parchment	Date: 12, 2012
DCTD OD Approval:	Joseph E. Tomaszewski Joseph E. Tomaszewski	Date: May 30, 2012

Change History

Revision	Approval Date	Description	Originator	Approval
	9/28/2009	New Document	LW, TP	RJK
А	7/07/2010	Format SOP, add Batch Record, and Appendices	YAE	RJK
В	12/23/2010	Updates based on first training course	LW, TP	RJK
С	9/13/2011	Removed shipping instructions for off-site blood processing and referenced SOP LHTP003.08.03 for blood collection and shipping. Section added to Batch Record to record MagNest information.	LW	RJK
D	4/6/2012	Removed specific references to use of the γH2AX- AF488 antibody Generalized SOP for use with any		RJK

Please check for revision status of the SOP at

http://dctd.cancer.gov/ResearchResources/ResearchResources-biomarkers.htm

and be sure to use the current version.







NCTVL Standard Operating Procedure (SOP)					
Title:	Title:Immunofluorescence Assay for Circulating Tumor Cells Using the CellSearch System				Page 2 of 24
Doc. #:	LHTP003.8.1	Revision:	D	Effective Date:	4/6/2012

TABLE OF CONTENTS

OVERV	VIEW OF ASSAY SAMPLE PROCESSING	3
1.0	PURPOSE	4
2.0	SCOPE	4
3.0	ABBREVIATIONS	4
4.0	INTRODUCTION	4
5.0	ROLES AND RESPONSIBILITIES	5
6.0	MATERIALS AND EQUIPMENT REQUIRED	
7.0	OPERATING PROCEDURES	9
8.0	CONTROL SAMPLE ANALYSIS AND QUALITY CONTROL	16
9.0	CLINICAL SAMPLE ANALYSIS	17
10.0	ARCHIVING DATA	18
APPEN	IDIX 1: BATCH RECORD	19
APPEN	IDIX 2: CELLSEARCH SYSTEM MAINTENANCE	23
APPEN	IDIX 3: DAILY SYSTEM VERIFICATION	24





		NCTVL Standar	d Operating P	rocedure (SOP))	
Title:	Immunofluorescence System	e Assay for Circu	ulating Tumo	r Cells Using th	e CellSearch	Page 3 of 24
Doc. #:	LHTP003.8.1	Revision:	D	Effective	Date:	4/6/2012
OVERVI		SAMPLE P Blood ample 596 h	ROCESS	ING		
	d using	$ \underbrace{ \begin{array}{c} \bullet \\ \text{are blood} \\ \text{buffer in} \\ \Gamma C \text{ Kit} \\ \hline \\ \hline \\ \hline \\ \hline \\ \end{array} } \underbrace{ \begin{array}{c} \bullet \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ $	Prepare contr from Control 1 (once/day)			
	CellTracks AutoPrep	CellTracks Auto • CTC Kit • Ab-FITC • MagNest Do for ≥ 20 min. Tr	evices in dark		Qualified Ab-FIT similar) antibo conjugate	
	CellTracks AnalyzerII	CellTracks Ana	lyzer II			
	FAIL FAIL Run a 2 nd control samp AutoPrep and Analyzer. I	 Images: Control Sample Clinical Sample Control Sam QC 	s nple P Analyz Sai Generate Sa	ASS e Clinical nples mple Report: Ab-FITC-		
	sample fails, discard all sar Veridex technical	nples and contact		ell numbers		







	110		nu Operating	Tiocedule (SOT)	
Title:	Title:Immunofluorescence Assay for Circulating Tumor Cells Using the CellSearch System				
Doc. #:	LHTP003.8.1	Revision:	D	Effective Date:	4/6/2012

1.0 PURPOSE

To standardize the method for immunomagnetic selection of circulating tumor cells (CTCs) and immunofluorescent identification of CTCs positive for pharmacodynamic (PD) biomarkers, nuclear or cytoplasmic, as measures of chemotherapeutic agents.

2.0 SCOPE

This procedure applies to all personnel responsible for the collection and processing of clinical samples for biomarker analysis of CTCs using a qualified primary antibody conjugated to FITC (or similar; Ab-FITC), and those responsible for performing the Immunofluorescence assay (IFA) for CTCs on these samples using the CellSearch[®] System CellTracks[®] AutoPrep[®] and Analyzer II. The goal of the SOP and associated training is to ensure consistency of biomarker measurement for CTCs between clinical sites.

3.0 ABBREVIATIONS

=	Antibody
=	Primary Antibody Conjugated to FITC (or similar) Reporter
=	Circulating Tumor Cell
=	4',6-Diamidino-2-Phenylindole
=	Division of Cancer Treatment and Diagnosis
=	Deionized
=	Fluorescein Isothiocyanate
=	Immunofluorescence Assay
=	Laboratory of Toxicology and Pharmacology
=	Pharmacodynamic Assay Development and Implementation Section
=	Pharmacodynamic
=	Pathology/Histotechnology Laboratory
=	Quality Control
=	Room Temperature
=	Standard Operating Procedure

4.0 INTRODUCTION

The IFA for CTCs is an immunohistochemistry-based staining assay developed to quantify CTCs positive for a biomarker of interest using a qualified antibody conjugate. The assay uses a qualified primary antibody conjugated to FITC (or similar) reporter for immunofluorescent identification of cells. CTCs are enriched from whole blood and isolated using the CellSearch System, an automated system for the purification and enumeration of CTCs with the capability of detecting a single CTC in 7.5 mL of whole blood.







NCTVL Standard Operating Procedure (SOP)							
Title:	Immunofluorescence A System	Assay for Cir	culating Tum	Page 5 of 24			
Doc. #: LHTP003.8.1 Rev		Revision:	D	Effective Date:	4/6/2012		
5.0 RO	LES AND RESPONSIB	ILITIES					
Lab	oratory Director/Supervis	superv for the Labora within	ises technical proper perfor atory Director, the laboratory	ector/Supervisor, directs laborat personnel, reporting of finding mance of all laboratory proced /Supervisor oversees the persor v and is responsible for ensuring ficient experience to handle clin	s, and is responsible ures. The anel running SOPs g this person(s) is		
Lab	Laboratory Scientist		d 5 years of e l testing labor atory Technici ng specialized atory Supervis tory procedure oring Batch Ro	ist should have at least a PhD a sperience in assay validation an atory setting. Laboratory Scien ans, review SOP results, perfor l scientific skills, and, in the ab or, is responsible for the proper es. The Laboratory Scientist is ecord preparation and following P performance that qualify as a	nd have worked in a ntists supervise m assay steps sence of the r performance of all also responsible for g-up on any issues		
Certified Assay Operator		been c Assay Directe SOP(s other p equipt	A Certified Assay Operator must be a Laboratory Scientist who has been certified through DCTD training on this SOP. The Certified Assay Operator works under the guidance of the Laboratory Director/Supervisor. This person, in accordance with the current SOP(s), performs laboratory procedures and examinations and any other procedures conducted by a laboratory, including maintaining equipment and records and performing quality assurance activities related to performance.				

- **5.1** It is the responsibility of the Laboratory Director/Supervisor to ensure that all Certified Assay Operator meet the criteria for the role defined as Laboratory Scientist.
- **5.2** It is the responsibility of the Laboratory Director/Supervisor to ensure that the Certified Assay Operator has received <u>training by Veridex, LLC</u> in the use, operation, and maintenance of the CellSearch System, including the CellTracks AutoPrep System and the CellTracks Analyzer II. Veridex certification is <u>required</u> for performance of this SOP. In addition the Certified Assay Operator must have documented <u>DCTD training</u> and certification on this SOP prior to the actual handling and processing of specimens from clinical trial patients.
- 5.3 It is the responsibility of the Laboratory Director/Supervisor to ensure that the Certified Assay Operator qualifies all new batches of Ab-FITC conjugate and the laboratory completes laboratory proficiency testing during initial laboratory set up, any time a new certified assay operator is added to the laboratory, and each time a new batch of Ab-FITC conjugate is qualified. As an example, SOP LHTP003.8.1.1 for qualification of γH2AX-AF488 is available on the DCTD Biomarkers Web site as is a requirements document for community-provided antibody qualification methods.
- **5.4** It is the responsibility of the Laboratory Director/Supervisor of the specimen collection laboratory to confirm scheduled specimen collection time points, print all labels in advance, check documentation for accuracy, and verify that the required collection tubes, supplies, and equipment are available for successful isolation and preparation of CTCs.





	110		nu Operating	Tiocedule (SOI)	
Title:	Immunofluorescence A System	Page 6 of 24			
Doc. #:	LHTP003.8.1	Revision:	D	Effective Date:	4/6/2012

- **5.5** Certified Assay Operators following this SOP are required to be certified in working safely with bloodborne pathogens in research laboratories in accordance with OSHA Bloodborne Pathogen Standard (29 CFR 1910.1030).
- **5.6** It is the responsibility of the Certified Assay Operator to ensure timely transport and processing of the samples, enter and review all of the required collection and processing data, and archive all data sheets in the appropriate files.
- **5.7** The Certified Assay Operator responsible for carrying out the assay is to follow this SOP and complete the required tasks and associated documentation. The Batch Record (Appendix 1) must be completed in *real-time* for each experimental run, with each page *dated and initialed*, and placed with the clinical sample information.
- **5.8** The Certified Assay Operator is to check the DCTD Biomarkers Web site (<u>http://dctd.cancer.gov/ResearchResources/ResearchResources-biomarkers.htm</u>) to verify that the latest SOP version is being followed.



SAIC

NCTVL Standard Operating Procedure (SOP)	
------------------------------------------	--

	NC	TVL Standa	rd Operating	Procedure (SOP)		
Title: Immunofluorescence Assay for Circulating Tumor Cells Using the CellSearch System System				Page 7 of 24		
Doc. #:	LHTP003.8.1	Revision:	D	Effective Date:	4/6/2012	
6.0 MA						
6.1 6.2 6.3	6.2 Electronic pipette					
6.4 6.5 6.6 6.7	50-mL polypropylen	e tubes (Bect ner Scientific	ton Dickinsor c, Cat#: 11-99	96)		
6.8 6.9 6.10 6.11	 filtered according to a final volume of 2 L Deionized (DI) water Qualified primary an similar dyes include 	similar dyes include Alexa Fluor 488 and DyLight 488.				
6.13 6.14 6.15 6.10 6.17 6.18 6.19	 6.12 CellTracks AutoPrep System (Veridex, Cat#: 9541); system includes 8 MagNest[®] devices and reagent carousel 6.13 CellTracks Analyzer II (Veridex, Cat#: 9555) 6.14 MagNest Device, blue cover, 1-pack (Veridex, Cat#: CT4247) 6.15 CellSave Preservative Tubes, 100-pack (Veridex, Cat#: 7900005) 6.16 CellSearch Printer Paper (Veridex, Cat#: CT1828) 6.17 CellSearch Circulating Tumor Cell Kit (Veridex, Cat#: 7900001) 6.18 CellSearch Circulating Tumor Cell Control Kit (Veridex, Cat#: 7900003) 6.19 CellTracks System Buffer, 20 L cubitainer (Veridex, Cat.# 7901003) 				est [®] devices and	
 6.20 CellTracks System Verification Cartridge, 2-pack (Veridex, Cat#: CT9566) 6.21 Sorvall Legend RT centrifuge (Fisher Scientific, Cat#: 75-006-434) with a swing bucket rotor 6.22 Vortex-Genie (Scientific Industries, Inc.) 6.23 Monthly maintenance kit (Veridex, Cat#: 9554) 6.24 Class II Type A2 biosafety cabinet/tissue culture hood 6.25 4°C refrigerator 						

6.26 Optional: SOP LHTP003.08.03: CellSave Tube: Human Blood Collection and Specimen Submission. Provided during Certified Assay Operator training and available on the DCTD **Biomarkers Web site**

* If instruments and/or reagents differ from those specified above, the Certified Assay Laboratory performing the assay must prove their comparability or equivalence to those recommended using the manufacturer's specifications and experimental validation data.





Title:	Immunofluorescence A System	Page 8 of 24			
Doc. #:	LHTP003.8.1	Revision:	D	Effective Date:	4/6/2012

THIS PAGE LEFT BLANK ON PURPOSE






Title:	Immunofluorescence A System	Page 9 of 24			
Doc. #:	LHTP003.8.1	Revision:	D	Effective Date:	4/6/2012

7.0 OPERATING PROCEDURES

Note: The general blood collection and processing procedures follow the CellSearch CTC Kitrecommended protocol.

- 7.1 All new batches of Ab-FITC conjugate need to be qualified for use with the Cell Search System before using this SOP. As an example, SOP LHTP003.8.1.1 for qualification of γ H2AX-AF488 is available on the <u>DCTD Biomarkers Web site</u> as is a requirements document for community-provided antibody qualification methods.
- **7.2** Record the name, Veridex certification number, and DCTD certification number of the Certified Assay Operator and the facility running the SOP in the Batch Record (Appendix 1). Be sure to review all actions required for successful assay setup.
- **7.3** Two identical, pre-printed specimen labels should be prepared for each blood collection time point. Labels should include Sample ID, clinical trial number, collection time point, collection date, and space to write the actual collection time.

The specimen ID includes the CTEP protocol number followed by a unique patient identifier and a specimen ID; NCI collections for CTC PD sampling are series 400 with consecutive numbers identifying the collection time point as defined in the Clinical Protocol. Sample pre-printed label:



7.4 Blood Collection

- **7.4.1** Blood sample collection laboratory personnel should ensure that the phlebotomist is using the recommended CellSave Preservative Tube to draw the blood samples. If necessary, supply the phlebotomist with the correct tubes. A minimum of 7.5 mL of blood should be collected into the tubes.
- **7.4.2** The research nurse is to notify the laboratory of scheduled PD specimen collections, preferably giving at least 24-h notice. A laboratory technician is to arrive at the blood collection site at least 5 min ahead of the scheduled time point(s) to ensure rapid transport to the laboratory after collection.
- **7.4.3** Place one of the pre-printed labels onto the freshly collected CellSave Preservative Tube and give the second label to the research nurse to place in the patient record sheet.
- **7.4.4** Samples should be mixed immediately by gently inverting the tube 8 times to prevent clotting. Write the actual time of blood sample collection on the specimen label.
- **7.4.5** Samples should be kept at RT (15°C to 25°C); <u>do not</u> place on ice or refrigerate. Patient blood samples are stable for 96 h in CellSave Preservative Tubes at RT.





Title:	Immunofluorescence A System	Immunofluorescence Assay for Circulating Tumor Cells Using the CellSearch System				
Doc. #:	LHTP003.8.1	Revision:	D	Effective Date:	4/6/2012	

- **7.4.6** If shipping blood to PADIS for processing, follow SOP LHTP003.08.03: CellSave Tube: Human Blood Collection and Specimen Submission provided during Certified Assay Operator training and available on the <u>DCTD Biomarkers Web site</u>; otherwise, store blood samples at RT for no longer than 96 h prior to sample preparation following SOP Step 7.5.
 - 7.4.6.1 If shipping blood samples to a secondary site other than PADIS for PD biomarker analysis, follow the same general guidelines outlined in SOP LHTP003.08.03.

7.5 Sample Preparation

- **7.5.1** Record the serial numbers of key equipment in the Batch Record (Appendix 1, Section 1A). All reagents and kits should be labeled with date of receipt and date opened. Reagents should be stored under the specified conditions for no longer than the recommended duration.
- **7.5.2** Upon receipt of blood samples from the clinic, verify that each patient sample is labeled with the Sample ID, clinical trial number, collection time point, collection date, and collection time. If any of this information is missing, notify the Laboratory Supervisor, and they will contact the clinical monitor to obtain the missing information.

Important: Patient blood samples are stable for up to 96 h after collection in CellSave Preservative Tubes at RT (15°C to 25°C). **Do not** place on ice or refrigerate.

- **7.5.3** Remove the CellSearch CTC Kit and CTC Control Kit (if needed) from the refrigerator 30 min prior to use and allow to warm to RT.
 - 7.5.3.1 One control sample from the Control Kit needs to be run and pass QC on **each day** of clinical sample testing and each time a new lot of the CTC Kit is used.
 - 7.5.3.2 For one experimental run, a maximum of 8 samples (including control) can be processed.
- **7.5.4** The first sample run each day should be a control sample
 - 7.5.4.1 If a control sample has already passed QC for the day, indicate "Yes" in the Batch Record (Appendix 1, Section 2) and skip to SOP Step 7.5.6.
 - 7.5.4.2 If a control sample has not yet passed QC for the day, indicate "No" in the Batch Record (Appendix 1, Section 2) and proceed to SOP Step 7.5.5. Once a control sample passes QC during this assay run, indicate this by placing your initials at the top of the Sample Information Table as indicated (Appendix 1, Section 2).







(CT (E Standard Operating Floeddare (SOF)							
Title:	Immunofluorescence A System	Immunofluorescence Assay for Circulating Tumor Cells Using the CellSearch System					
Doc. #:	LHTP003.8.1	Revision:	D	Effective Date:	4/6/2012		

7.5.5 Control Sample – Control Kit (once/day)

- 7.5.5.1 If a control sample has not yet been run for the day, enter the control sample information as tube number 1 in the Sample Information Table of the Batch Record (Appendix 1, Section 2).
- 7.5.5.2 From the Control Kit, affix a supplied orange barcode label vertically to one of the provided 15-mL AutoPrep tubes and place in a tube rack. **Note**: The barcodes are lot-specific and should not be used with other Control Kits.
- 7.5.5.3 Vortex one of the supplied 3-mL control bottles gently for 5 sec and then mix by inverting 5 times.
- 7.5.5.4 Pour the contents of the control bottle into the AutoPrep tube. Use a pipettor to ensure any residual liquid is transferred to the AutoPrep tube.

7.5.6 Clinical Sample(s) – CTC Kit

7.5.6.1 Record the Sample ID, clinical trial number, collection time point, collection time and date, and collection site for each sample in the Sample Information Table of the Batch Record (Appendix 1, Section 2). The order the tubes are recorded in the table will also be the order the tubes are processed in the AutoPrep.

IMPORTANT: **DO NOT assign a generic in-house sample ID**, enter the clinical Sample ID so results can be directly tracked back to the unique clinical patient ID.

Clinical sample preparation must begin within 96 h of blood collection.

- 7.5.6.2 For each patient sample, label one of the provided 15-mL AutoPrep tubes with the Sample ID. Place the AutoPrep tubes in a tube rack, in order, according to the Sample Information Table.
- 7.5.6.3 Using a 10-mL pipette, transfer 7.5 mL of blood from a CellSave Preservative Tube into the corresponding labeled 15-mL AutoPrep tube, and then add 6.5 mL Dilution Buffer (15°C to 25°C, included with the CTC Kit); be sure buffer has reached RT before adding. Record the date and time sample preparation begins in the Batch Record (Appendix 1, Section 3).

Discard any remaining blood and the CellSave Preservative Tubes in the appropriate biohazardous waste containers.

- 7.5.6.4 Cap the AutoPrep tubes, mix by inversion 5 times, and then centrifuge the samples in a swing bucket rotor at 800 x g for 10 min at 15°C to 18°C, without the brake.
- 7.5.6.5 Samples must be loaded into the CellTracks AutoPrep System within 1 h of sample preparation. <u>Do not</u> place on ice or refrigerate.





Title:	Immunofluorescence A System	Assay for Cir	culating Tum	or Cells Using the CellSearch	Page 12 of 24
Doc. #:	LHTP003.8.1	Revision:	D	Effective Date:	4/6/2012

7.6 CellTracks AutoPrep System

- 7.6.1 If the AutoPrep is off, turn it on and let it warm up for 30 min prior to use.
- **7.6.2** Be sure the following solution bottles are filled and attached:
 - 7.6.2.1 <u>Waste bottle</u> empty and then fill with 400 mL DI water
 - 7.6.2.2 <u>Cleaning solution bottle</u> fill with 0.26% bleach
 - 7.6.2.3 <u>Instrument buffer bottle</u> System Buffer, refill using 20-L cubitainer

7.6.3 Prepare the Ab-FITC working solution

- 7.6.3.1 Record the lot number and expiration date for the Bond Primary Antibody Diluent, the name of the Ab-FITC conjugate to be used, date the Ab-FITC conjugate was received and qualified, and the recommended dilution of the Ab-FITC stock solution in the Batch Record (Appendix 1, Section 1B).
 - Generally, Ab-FITC stock solutions should be used within 1 y of date of receipt. Order and qualify a new Ab-FITC conjugate if older than 1 y.
- 7.6.3.2 Using the calculations in Appendix 1, Section 4A, determine the total volume of working solution needed for all samples and volume of Ab-FITC needed to make the working solution.
- 7.6.3.3 Prepare the Ab-FITC working solution in Bond Primary Antibody Diluent using the calculations in Appendix 1, Section 4B. Pipette the calculated volumes of Ab-FITC stock solution and Bond Primary Antibody Diluent into a 1.5-mL Sarstedt screw cap tube and gently pipette up and down to mix. Cap and set aside with the CTC Kit.

7.6.4 Running a Batch

- 7.6.4.1 On Main Menu, click on **Run Batch** and press **Enter**. Enter user password to log into the AutoPrep. If you have not run the Daily Cleaning protocol in the past 72 h, it will need to be done prior to running clinical samples (see Appendix 2, Section 1 for details).
- 7.6.4.2 Enter the following information for **Batch Setup**, pressing **Enter** after each. Information for the batch will be updated in the upper right-hand corner of the screen as information is entered.

Field	Fill in		
Select Reagent Kit	CellSearch CTC kit		
Select Marker Test	User Defined Assay		
	Example: "gH2AX" or "p16INK4"		
Select Control	Select <i>Yes</i> or <i>No</i> to indicate if this batch contains a control sample		
Select Total number of	Select the <i>batch size</i>		
Samples	(e.g., for 1 control + 7 samples, select 8)		





Title:			1 0	or Cells Using the CellSearch	Page 13 of 24	
Doc. #:						

7.6.5 Loading AutoPrep

- 7.6.5.1 The screen will prompt you to "**Load Reagent Kit**" with a reminder to load the antibody tube. Remove cap from the 1.5-mL Ab-FITC working solution tube and place it into position 1 of the reagent carousel and then press **Enter**.
- 7.6.5.2 The screen will again prompt you to "**Load Reagent Kit.**" Remove caps from each bottle of the CTC Kit and load the kit onto the reagent carousel. Place carousel in the AutoPrep and then press **Enter**.
 - Save the caps from the CTC Kit bottles to recap bottles for storage after the run is completed; caps preserve liquid volume better than the provided evaporation cover.
- 7.6.5.3 Prepare one MagNest for each sample to be processed by placing a cartridge (supplied with CTC Kit) into each MagNest and then placing the loaded MagNest into the AutoPrep. Press **Enter** after each MagNest is loaded; the cartridge ID will appear on the screen as it is scanned.
- 7.6.5.4 Load samples into the AutoPrep following the on-screen instructions, with bar codes facing forward, in the order recorded in the Sample Information Table (Appendix 1, Section 2). If a control sample is being run, it should be the first tube loaded.
 - If a new Control Kit lot number is detected by the system, you will be requested to scan the barcode from the Control Kit **box** and follow the onscreen instructions.
- 7.6.5.5 After each sample is loaded, press Enter. The screen will prompt "Run Marker Test?"
 - For the control sample, arrow down and select **NO**.
 - For the clinical samples, press **Enter** to select **YES** this will ensure the Ab-FITC solution is run with the samples.
 - Once the run starts, the marker status cannot be changed.
- 7.6.5.6 Update the clinical sample information as follows. Select **Edit**, press **Enter**, select **Edit sample information**, and press **Enter** again. Use the arrows keys to select the sample to be edited and press **Enter**.
 - For each clinical sample, enter the clinical Sample ID from the Sample Information Table (Appendix 1, Section 2) and select **Save**.
 - **DO NOT use a generic in-house sample ID**, enter the clinical Sample ID so results can be directly tracked back to the unique clinical patient ID.
 - Clinical sample information can be edited any time prior to the completion of a sample run. Time can be saved by editing sample information during the run.
- 7.6.5.7 Once all samples are loaded, select **Start** and press **Enter** to start the run. The predicted completion time for each sample will be listed under the Time Ready column on the **Processing Samples** screen. Record the time the AutoPrep run begins in the Batch Record (Appendix 1, Section 5) this should be **within 1 h** of sample preparation.



SAIC.

NCTVL Standard	Operating	Procedure	(SOP)
1.01.12.0000000	operating	11000000000	(~~

Title:	Immunofluorescence A System	Page 14 of 24			
Doc. #:	LHTP003.8.1	Revision:	D	Effective Date:	4/6/2012

7.7 Unloading Samples From AutoPrep

Note: Samples can be unloaded after the entire batch is complete or as each sample is finished processing.

- **7.7.1** Once a sample is completed, the Status column updates to "Complete," and the MagNest door will open for a brief period of time to allow removal of the MagNest. If this time window is missed, the MagNest for that sample can only be removed once the batch is completed; other MagNests can be removed as they are completed.
- **7.7.2** Upon batch completion, the system will display an **Unload** button. Press **Enter** and follow the on-screen prompts to remove the remaining MagNests.
- **7.7.3** Remove MagNests from the AutoPrep and immediately cap them, tapping the side of the MagNest to minimize bubbles. Lay each capped MagNest flat, in the dark (e.g., in a drawer), and wait 20 min (max 24 h) before starting analysis (SOP Step 7.8). For each MagNest, record the Sample ID, Cartridge number, and time placed in the dark in the Batch Record (Appendix 1, Section 6).
- **7.7.4** Unload the 15-mL AutoPrep tubes and discard in appropriate biohazardous waste container.
- **7.7.5** Unload the reagent carousel and discard any unused Ab-FITC working solution. If there are remaining solutions in the CTC Kit, recap all bottles, return to the CTC Kit box, and store at 2°C to 8°C until next use.
- **7.7.6** If this was the last AutoPrep run of the day, run the Daily Cleaning protocol (Appendix 2, Section 1).

7.8 CellTracks Analyzer II Image Acquisition

- **7.8.1** Turn the Analyzer on and then the computer. The Analyzer software will boot automatically. When prompted, enter the user password to log into the Analyzer. **Note**: One sample (MagNest) will be processed at a time in the Analyzer.
 - 7.8.1.1 The Home Screen has tabs across the top, called folders, which when selected display additional subfolders. The buttons across the bottom of the Home Screen are for the tool bar.
- **7.8.2** Select the Lamp button on the tool bar and click **YES** in the dialog box to turn on the lamp. Wait at least 15 min for the lamp to warm up. An indicator will flash green during warm up and will remain steady once the lamp is ready.
- **7.8.3** If a control sample has not yet passed QC for the day, analyze the control sample first by following the protocol in SOP Section 8.0.
- **7.8.4** To analyze a clinical sample, select the **Patient Data** folder on the Home Screen and then the **Sample Data** subfolder.
 - 7.8.4.1 The Analyzer will prompt you if **System Verification** is required (see Appendix 3 for details).
- **7.8.5** Once a clinical sample has sat in the dark for at least 20 min, take the MagNest out, wipe the cover slip of the cartridge with lens paper, and then insert it into the Analyzer. For each MagNest, record the scan time in the Batch Record (Appendix 1, Section 6).



Title:	Immunofluorescence A System	Page 15 of 24			
Doc. #:	LHTP003.8.1	Revision:	D	Effective Date:	4/6/2012

- **7.8.6** The sample data stored on the data button of the MagNest from the AutoPrep will be uploaded into the Analyzer. Visually verify that the sample information is correct. Click the **Edit** button and change the ***Test Protocol** field to **Research**. Correct any errors and add comments as needed. Select **Save** to continue.
- 7.8.7 Click the **Start** button to begin a scan.
- **7.8.8** Confirm edge detection.
 - 7.8.8.1 If the "# of Frames" is less than 175 (bottom left-hand corner of screen) or if the green line in any of the images does not line up with the image edges, the cartridge may not be inserted properly select the **Cancel** button, remove and reinsert the MagNest, and restart the scan.

If the green lines still do not line up with the image edges, first click **OK** to clear the dialog box, and then click on the image. Line up the green line with the image edges by making fine movements using the Arrow keys, medium movements using the Shift key + Arrow keys, and coarse movements using the Ctrl key + Arrow keys.

Click **Enter** in the dialog box to confirm the changes and then the **Accept** button to continue.

- 7.8.8.2 If the edges of the cartridge are detected correctly, click **OK** to clear the dialog box, and then the **Accept** button to continue.
- **7.8.9** Confirm auto focus by clicking **OK** to clear the dialog box and then clicking the **Accept** button to continue.
- **7.8.10** The Analyzer will scan the cartridge. Image acquisition will take approximately 10 min for all 4 filters. A scan can be cancelled at any time by clicking the **Cancel** button; however, all of the images collected will be deleted.
- **7.8.11** A pop-up window will state **Scan complete**; click **OK** to continue. Open the sample door and remove the MagNest. The next MagNest can be inserted and scanned immediately. Return to SOP Step 7.8.4 to scan additional clinical samples.
- **7.8.12** If this is the last scan of the day, select the **Lamp** button on the tool bar and click **YES** in the dialog box to turn off the lamp.
- **7.9** Review and finalize the Batch Record (Appendix 1) and obtain required signatures. Document ANY and ALL deviations from this SOP in the Batch Record (Appendix 1, Section 7).
- 7.10 Proceed to SOP Section 9.0 to analyze clinical samples.







Title:			1 0	or Cells Using the CellSearch	Page 16 of 24
Doc. #:	LHTP003.8.1	Revision:	D	Effective Date:	4/6/2012

8.0 CONTROL SAMPLE ANALYSIS AND QUALITY CONTROL

A control sample from the Control Kit checks the overall CellSearch System performance. One control sample should be run on each day of clinical sample testing and each time a new CTC Kit lot is used.

8.1 CellTracks Analyzer II Image Acquisition

- 8.1.1 Select the QC Test folder and then the Control Data subfolder.
- **8.1.2** Once the control sample has sat in the dark for at least 20 min, take the MagNest out, wipe the cover slip of the cartridge with lens paper, and insert it into the Analyzer.
- **8.1.3** The control sample data, including expected low and high control ranges, are stored on the data button of the MagNest from the AutoPrep and will be uploaded to the Analyzer. Visually verify that the Control Kit information is correct. Use the **Edit** button to correct errors or add comments and select **Save** to continue.
- 8.1.4 Click the **Start** button to begin a scan.
- **8.1.5** Confirm edge detection.
 - 8.1.5.1 If the "# of Frames" is less than 175 (bottom left-hand corner of screen) or if the green line in any of the images does not line up with the image edges, the cartridge may not be inserted properly select the **Cancel** button, remove and reinsert the MagNest, and restart the scan.

If the green lines still do not line up with the image edges, first click **OK** to clear the dialog box, and then click on the image. To line up the image edges with the green line, make fine movements using the Arrow keys, medium movements using the Shift key + Arrow keys, and coarse movements using the Ctrl key + Arrow keys.

Click **Enter** in the dialog box to confirm the changes and then the **Accept** button to continue.

- 8.1.5.2 If the edges of the cartridge are detected correctly, click **OK** to clear the dialog box, and then the **Accept** button to continue.
- **8.1.6** Confirm auto focus by clicking **OK** to clear the dialog box, and then clicking the **Accept** button to continue.
- **8.1.7** The Analyzer will scan the cartridge. A pop-up window will state **Scan complete**; click **OK** to continue. Open the sample door and remove the MagNest.

8.2 Identification of Control CTCs

- **8.2.1** Select the **QC Data** folder and then the **Control** subfolder. Click on the row matching the control sample just processed and then select the **Review** subfolder. Sample details for the row selected will be displayed at the bottom of the **Control** subfolder screen.
- **8.2.2** Select a cell image in the image gallery to classify as a high or low control cell. The Control Kit sample contains both high (~1000 cells) and low (~50 cells) control cells; each cell population is labeled with a different fluorescent membrane dye for identification.





	NCTVL Standard Operating Procedure (SOP)	
Title:	Immunofluorescence Assay for Circulating Tumor Cells Using the CellSearch System	Page 17 of 24

D

Revision:

8.2.3	high controls in the gallery	s will be pres and classify	ented in the in them as high	utomatically assigned mage gallery for user a or low control cells.	review. (The resu	Click on the images lting counts must	
		-	0 0	n and low controls as 1 be SOP Step 8.3).	recorded	from the barcode	
					GH L coll	le clossify it as a	

8.2.3.1 For images containing CK-PE+/DAPI+/LOW-/HIGH+ cells, classify it as a high control cell by clicking on the HIGH image.

Effective Date:

4/6/2012

- 8.2.3.2 For images containing CK-PE+/DAPI+/LOW+/HIGH- cells, classify it as a low control cell by clicking on the LOW image.
- 8.2.3.3 For images containing both high and low control cells in the same frame, classify it as a low control cell by clicking on the LOW image.
- 8.2.4 Once all high and low control cells have been assigned, click **Done** on the right-hand side of the screen.

8.3 **Control Sample Quality Control (QC)**

LHTP003.8.1

Doc. #:

- 8.3.1 Next, select the QC Data folder and then the Control Table subfolder. Select the row matching the control sample just analyzed.
- 8.3.2 Select the **Report** subfolder and verify that the high and low control counts in the Results section are within defined Control Kit ranges. The Status on the Control Report will be assigned as either Pass or Fail for the control kit.
- 8.3.3 If the control sample passes QC, write "Pass" in the Collection Location column of the Sample Information Table for the control sample and place your initials at the top of the table as indicated in the Batch Record (Appendix 1, Section 2).
- If the control sample fails QC, run a second control sample through the AutoPrep and 8.3.4 Analyzer. If the second control sample fails QC, any patient samples run with the initial control sample should be discarded, and Veridex technical support should be contacted.
- 8.4 Once the control sample passes QC, return to SOP Step 7.8.4 to start Image Acquisition for clinical samples.

CLINICAL SAMPLE ANALYSIS 9.0

9.1 Identification of CTCs and Ab-FITC-Positive CTCs

- 9.1.1 Select the **Patient Data** folder and then the **Sample Table** subfolder. Click on the row matching the clinical sample to be analyzed and then select the **Review** subfolder. Sample details for the row selected will be displayed at the bottom of the **Sample Table** subfolder screen.
- 9.1.2 A gallery of acquired cell images for that sample will be displayed. Page down to view all images. Cell type assignments are performed manually. Columns that are marked with the Immunicon logo may be selected.
- Click on cell images in the DAPI/CK-PE column to classify them as CTCs. CTCs are 9.1.3 DAPI+, CK-PE+, FITC-, and CD45/APC-. Detailed criteria are discussed during the Veridex training course.





Frederick

NCTVL Standard Operating Procedure (SOP)									
Title:	Title:Immunofluorescence Assay for Circulating Tumor Cells Using the CellSearch SystemPage 18 of 24								
Doc. #:	4/6/2012								

- 9.1.4 Click on cell images in the FITC column to classify them as Ab-FITC-positive CTCs. These should be DAPI+, CK-PE+, FITC+, and CD45/APC-.
- 9.1.5 Click Done after all images have been reviewed.

9.2 **Generate Sample Reports**

- 9.2.1 Select the **Patient Data** folder and then the **Sample Table** subfolder. Click on the row to select a sample and then select the **Report** subfolder.
- 9.2.2 A preview of the report appears on the screen. A report can only be printed if **Done** was selected after clinical sample analysis (SOP Step 9.1.5). Once all of the patient samples have been processed, the sample reports should be printed and attached to the Batch Record.
- 9.3 A second certified Veridex user should review the Batch Record and sample reports and sign the Batch Record affirming the data contained within the reports are correct (Appendix 1, Section 8).
- 9.4 The Laboratory Director/Supervisor should review the Batch Record and sample reports and sign the Batch Record affirming the data contained within the reports are correct (Appendix 1, Section 9).
- 9.5 Copies of the sample reports should be printed and sent to the clinical protocol PI.

10.0 ARCHIVING DATA

Due to the large amount of data collected with each analysis, data will need to be archived at regular intervals. The Archive function is used to move data and images off of the Analyzer and onto DVD+Rs for long-term storage. Archive samples only after image **Review** is complete (SOP Step 9.1.5).

- **10.1.1** Use only high-quality DVD+Rs (Section 6.0) to ensure data integrity.
- **10.1.1** Depending on the number of images associated with each sample, data from several samples can be stored on a DVD+R. It is recommended to store data in numerical order by specimen ID.
- **10.1.2** Select the **Archive** folder. You can select specific samples to archive together, or archive in numerical order. Press the CTRL key on the keyboard and click the samples that you want to archive together.
- **10.1.3** The system will display a dialog box stating the number of samples being archived and will assign a disk number. Insert a blank DVD+R and click the **Start** button.
- **10.1.4** Label the DVD+R with the archive (disk) number and sample information. Record the archive number for each sample in the Sample Information Table.
- **10.1.5** Archived data will no longer be stored in the Analyzer. Archived samples will be identified in the Patient Data folder under the Archived Disk column.
- **10.1.6** Maintain the DVD+Rs in a local storage location until the clinical trial is completed, then move the DVD+Rs to a secure storage location.





11	tle:	Immunofluorescence A System	ssay for Circ	culating Tumor	Cells Using the CellSearch	Page 19 of 24
Do	c. #:	LHTP003.8.1	Revision:	D	Effective Date:	4/6/2012
A PP	END	IX 1: BATCH RE(ORD			
IOTI				tch Record), a	maximum of 8 samples (inclu	ding control) car
IOTI	<u>E:</u>	Record times using m	ilitary time	(24-h designat	ion); e.g., specify 16:15 to ind	dicate 4:15 PM.
Certifi	ied Ass	ay Operator:				
	Veric	lex certification number:				
	DCT	D certification number:				
Date:		/ /				
racilit	ty/Labo	ratory Running SOP:				
	А.					
		<u>Equipment</u> Microcentrifuge	Make/Mc	odel·		
		<u>Equipment</u> Microcentrifuge				
		Microcentrifuge	Serial #:			
			Serial #: Make/Mo	odel:		
		Microcentrifuge	Serial #: _ Make/Mo Serial #: _	odel:		
		Microcentrifuge Swing Bucket Rotor	Serial #: _ Make/Mc Serial #: _ CellTrack	odel: <s autoprep="" se<="" td=""><td></td><td></td></s>		
	B.	Microcentrifuge Swing Bucket Rotor	Serial #: _ Make/Mc Serial #: _ CellTrack	odel: <s autoprep="" se<="" td=""><td>rial #:</td><td></td></s>	rial #:	
	B.	Microcentrifuge Swing Bucket Rotor Cell Search System	Serial #: _ Make/Mo Serial #: _ CellTrack CellTrack	odel: <s autoprep="" se<="" td=""><td>rial #:</td><td></td></s>	rial #:	
	B.	Microcentrifuge Swing Bucket Rotor Cell Search System <u>Reagents</u>	Serial #: _ Make/Mo Serial #: _ CellTrack CellTrack	odel: <s autoprep="" se<br=""><s analyzer="" ii="" s<="" td=""><td>rial #: Serial #:</td><td></td></s></s>	rial #: Serial #:	
	B.	Microcentrifuge Swing Bucket Rotor Cell Search System <u>Reagents</u>	Serial #: <u>.</u> Make/Mo Serial #: <u>.</u> CellTrack CellTrack	odel: <s autoprep="" se<br=""><s analyzer="" ii="" s<br="">Lot #: Expiration D</s></s>	rial #: Serial #:	
	B.	Microcentrifuge Swing Bucket Rotor Cell Search System <u>Reagents</u> Bond Primary Antibo	Serial #: <u>_</u> Make/Mc Serial #: <u>_</u> CellTrack CellTrack dy Diluent	odel: cs AutoPrep Se cs Analyzer II S Lot #: Expiration D ujugate:	rial #: Serial #: ate:/	
	B.	Microcentrifuge Swing Bucket Rotor Cell Search System <u>Reagents</u> Bond Primary Antibo Primary antibody in A	Serial #: <u>_</u> Make/Mc Serial #: <u>_</u> CellTrack CellTrack dy Diluent	odel: cs AutoPrep Se cs Analyzer II S Lot #: Expiration D ujugate:	rial #: Serial #: ate:/	

Date Ab-FITC Stock qualified:/ /Recommended DILUTION for Ab-FITC Stock:1 :

INITIALS _____

NCT VE Standard Operating Trocedure (SOT)									
Title:	Immunofluorescence A System	Page 20 of 24							
Doc. #:	LHTP003.8.1	4/6/2012							

2. Sample Information Table

Has a control sample passed QC today? \Box Yes \Box No

If <u>No</u>, run a control sample with this assay (tube #1). **Initial Here** _____, once QC is passed.

Tube Order	Sample ID	Clinical Protocol #	Collection Time Point	Collection Time*	Collection Date MM/DD/YY	Collection Location	DVD+R Archive No.
Example	1234-001026-400	12-C-0000	D1 Pre-dose	14:15	03/01/12	NCI	12
1†				:	/ /		
2				:	/ /		
3				:	/ /		
4				:	/ /		
5				:	/ /		
6				:	/ /		
7				:	/ /		
8				:	/ /		

* Blood preparation (Section 3, below) must begin within 96 h of collection time.

[†] The <u>first</u> sample run <u>each day</u> should be a CTC control sample.

				CTVL Standa							
Ti	tle:	Immuno: System	•								
Do	c. #:	LHT	P003.8.1	003.8.1Revision:DEffective Date:4/6/2							
3.	Clin	ical Samp	le Preparati	ion							
	Samj	ple Prepara	ation Begins	:		Date:	/ /				
	>	*Must be v	within 96 h	of blood collec	ction.	Time:	:				
4.	Prep	aration of	f Ab-FITC V	Working Solu	tion (SOP s	Step 7.6	3)				
	А.	<u>Ab-FI</u>	<u>FC Working</u>	Solution Calc	ulations						
		a.	Total Vol.	Calculation (µ	uL)						
			Total numb	er of samples	to be proces	ssed:					
				2	x 150 µL/sai	nple		=		μL	
			Plus 300 µl	L residual volu	ume			+	300	μL	
			Total Vol.	needed for sta	ining			=		μL	
		b.	Vol. Ab-FI	TC Stock Cale	ulation (µL)						
			Recomm	tal Vol. (μL) ended <i>DILUTIα</i> -FITC <i>Stock</i>	$\frac{1}{2N \text{ of}} =$	<u>XX.X</u> μ	L (Vol. Ab-FITC	Stock)			
			(Dn	μL	=	!	ıL (Vol. Ab-FITC	C Stock	;)		
	B.	<u>Ab-FI</u>	FC Working	Solution Prep	aration_						
			μL μL	(nd Primary A (Total Vol. - FITC Stock	•	Diluent -FITC Stock)				

5. AutoPrep Run Started

Time: _____:

*Must be within 1 h of sample preparation

Title:	Immunofluorescence System	Assay for Cir	culating Tum	or Cells Using the CellSearch	Page 22 of 24
Doc. #:	LHTP003.8.1	Revision:	D	Effective Date:	4/6/2012

6. Image Acquisition

Tube Order	Sample ID	Cartridge No.	Time MagNest Placed in Dark	Time MagNest Scanned
1			:	:
2			:	:
3			:	:
4			:	:
5			:	:
6			:	:
7			:	:
8			:	:

7. Notes, including any deviations from the SOP:

8.	Secondary Review of	Clinical Samples	
	Certified Assay Opera	tor:	(PRINT)
			(SIGN)
	Veridex certification r	umber:	
	Date: /	/	
9.	Laboratory Director	Supervisor Review of Batch Record	
	Laboratory Director/S	upervisor:	(PRINT)
			(SIGN)
	Date: /	/	
BATC	H RECORD:	INITIALS I	DATE:

NCTVL Standard Operating Procedure (SOP)									
Title: Immunofluorescence Assay for Circulating Tumor Cells Using the CellSearch System Page 23									
Doc. #:	LHTP003.8.1	Revision:	D	Effective Date:	4/6/2012				

APPENDIX 2: CELLSEARCH SYSTEM MAINTENANCE

1. Daily

a.

The AutoPrep will prompt you to run a Daily Cleaning if the machine was just turned on for the first time of the day, or if it has been > 72 h (3 days) since the last Daily Cleaning.

- A. On the Main Menu click on **Daily Cleaning** and press **Enter**.
- B. Prepare and attach the following solution bottles:
 - Waste bottle empty and then fill with 400 mL DI water
 - Empty in appropriate biohazardous waste container
 - b. <u>Cleaning solution bottle</u> fill with 0.26% bleach, diluted in DI water
 - c. <u>Instrument buffer bottle</u> remove and replace with full DI water bottle
- C. Press **Enter** to Start Daily Cleaning (takes about 1 h).
- D. Once completed, prepare and attach the following solution bottles:
 - a. <u>Waste bottle</u> empty and then fill with 400 mL bleach, full strength
 - Empty in appropriate biohazardous waste container
 - b. <u>Cleaning solution bottle</u> fill with 0.26% bleach, diluted in DI water
 - c. <u>DI water bottle</u> remove and replace with full instrument buffer bottle

Remember to switch the instrument buffer bottle back to buffer before running samples. Refer to the CellTracks AutoPrep User's Guide for additional details.

2. Weekly and Monthly Maintenance Cleaning

Follow the recommended CellTracks AutoPrep weekly and monthly maintenance cleaning schedule; refer to the User's Guide for detailed instructions. It is recommended to maintain a maintenance log with the CellTracks AutoPrep System to ensure cleaning is being completed as specified and on schedule.





NCTVL Standard Operating Procedure (SOP)					
Title:	Immunofluorescence Assay for Circulating Tumor Cells Using the CellSearch System				Page 24 of 24
Doc. #:	LHTP003.8.1	Revision:	D	Effective Date:	4/6/2012

APPENDIX 3: DAILY SYSTEM VERIFICATION

1. System Verification

The CellTracks Analyzer II will prompt you to run a System Verification before scanning the first sample if the machine was just turned on for the first time of the day, if the software was restarted, or if it has been 10 h since the last System Verification.

- A. Select the **QC Test** folder and then select the **Verification** subfolder.
- B. Prepare a system verification cartridge and its associated MagNest.
 - a. Be sure it is before the expiration date of the cartridge.
 - b. Wipe the cover slip of the cartridge with lens paper and load it into the Analyzer.
 - c. If a new verification cartridge is being used, click **edit verification settings**, enter the new cartridge ID number, and then click **OK**.
- C. Click the **Start** button in the system verification box located at the bottom of the screen.
- D. Remove the system verification cartridge from the instrument when the procedure is complete.
- E. Select the **QC Data** folder and then select the **Verification** subfolder to access the verification list.
- F. Verify that the system verification Result was Pass. If system verification fails, Veridex technical support should be contacted.



SAIC.