

4-deoxycytidine">

Valid 05/2003 - 07/2003

Sigma-Aldrich Chemie B.V.
 Stationsplein 4, Postbus 27
 NL-3330 AA Zwijndrecht Nederland
 tel.: (31)-(0)78-6205411
 gratis tel.: 0800-0229088

M A T E R I A L S A F E T Y D A T A S H E E T

SECTION 1. - - - - - CHEMICAL IDENTIFICATION - - - - -
 CATALOG #: A3656
 NAME: 6-AZA-2'-DEOXYCYTIDINE

SECTION 2. - - - - - COMPOSITION/INFORMATION ON INGREDIENTS - - - - -
 CAS #: 2353-33-5
 MF: CBH12N4O4
 EC NO: 219-089-4

ADDITIONAL INFORMATION
 CONTAINS METHYL ALCOHOL, CHEMICAL ABSTRACTS REGISTRY NUMBER 67-56-1.

SYNONYMS
 4-AMINO-1-(2-DEOXY-BETA-D-ERYTHRO-PENTOFURANOSYL)-S-TRIAZIN-2(1H)-ONE
 * 5-AZADEOXYCYTIDINE + 5-AZA-2'-DEOXYCYTIDINE + 1,3,5-TRIAZIN-2(1H)-ONE, 4-AMINO-1-(2-DEOXY-BETA-D-ERYTHRO-PENTOFURANOSYL)- (9CI) *

SECTION 3. - - - - - HAZARDS IDENTIFICATION - - - - -
 LABEL PRECAUTIONARY STATEMENTS
 TOXIC
 MAY CAUSE HARM TO THE UNBORN CHILD.
 HARMFUL BY INHALATION, IN CONTACT WITH SKIN AND IF SWALLOWED.
 MAY CAUSE SENSITIZATION BY SKIN CONTACT.
 IRRITATING TO EYES, RESPIRATORY SYSTEM AND SKIN.
 POSSIBLE MUTAGEN.
 TARGET ORGAN(S):
 BONE MARROW
 IMMUNE SYSTEM
 IN CASE OF ACCIDENT OR IF YOU FEEL UNWELL, SEEK MEDICAL ADVICE IMMEDIATELY (SHOW THE LABEL WHERE POSSIBLE).
 IN CASE OF CONTACT WITH EYES, RINSE IMMEDIATELY WITH PLENTY OF WATER AND SEEK MEDICAL ADVICE.
 WEAR SUITABLE PROTECTIVE CLOTHING, GLOVES AND EYE/FACE PROTECTION.
 DO NOT BREATHE DUST.

SECTION 4. - - - - - FIRST-AID MEASURES - - - - -
 IN CASE OF CONTACT, IMMEDIATELY FLUSH EYES OR SKIN WITH COPIOUS AMOUNTS OF WATER FOR AT LEAST 15 MINUTES WHILE REMOVING CONTAMINATED CLOTHING AND SHOES.
 ASSURE ADEQUATE FLUSHING OF THE EYES BY SEPARATING THE EYELIDS WITH FINGERS.
 IF INHALED, REMOVE TO FRESH AIR. IF NOT BREATHING GIVE ARTIFICIAL RESPIRATION. IF BREATHING IS DIFFICULT, GIVE OXYGEN.
 IF SWALLOWED, WASH OUT MOUTH WITH WATER PROVIDED PERSON IS CONSCIOUS.
 CALL A PHYSICIAN.
 WASH CONTAMINATED CLOTHING BEFORE REUSE.

SECTION 5. - - - - - FIRE FIGHTING MEASURES - - - - -
 EXTINGUISHING MEDIA
 WATER SPRAY.
 CARBON DIOXIDE, DRY CHEMICAL POWDER OR APPROPRIATE FOAM.
 SPECIAL FIREFIGHTING PROCEDURES
 WEAR SELF-CONTAINED BREATHING APPARATUS AND PROTECTIVE CLOTHING TO PREVENT CONTACT WITH SKIN AND EYES.
 UNUSUAL FIRE AND EXPLOSIONS HAZARDS

EMITS TOXIC FUMES UNDER FIRE CONDITIONS.
 SECTION 6. ----- ACCIDENTAL RELEASE MEASURES-----
 WEAR RESPIRATOR, CHEMICAL SAFETY GOGGLES, RUBBER BOOTS AND HEAVY RUBBER GLOVES.
 SWEEP UP, PLACE IN A BAG AND HOLD FOR WASTE DISPOSAL.
 AVOID RAISING DUST.
 VENTILATE AREA AND WASH SPILL SITE AFTER MATERIAL PICKUP IS COMPLETE.
 SECTION 7. ----- HANDLING AND STORAGE-----

REFER TO SECTION 8.
 SECTION 8. ----- EXPOSURE CONTROLS/PERSONAL PROTECTION-----
 WEAR APPROPRIATE NIOSH/MSHA-APPROVED RESPIRATOR, CHEMICAL-RESISTANT GLOVES, SAFETY GOGGLES, OTHER PROTECTIVE CLOTHING.
 USE ONLY IN A CHEMICAL FUME HOOD.
 SAFETY SHOWER AND EYE BATH.
 DO NOT BREATHE DUST.
 DO NOT GET IN EYES, ON SKIN, ON CLOTHING.
 AVOID PROLONGED OR REPEATED EXPOSURE.
 WASH THOROUGHLY AFTER HANDLING.
 TERATOGEN.
 SENSITIZER.
 POSSIBLE MUTAGEN.
 IRRITANT.
 KEEP TIGHTLY CLOSED.

SECTION 9. ----- PHYSICAL AND CHEMICAL PROPERTIES -----
 APPEARANCE AND ODOR
 SOLID.
 PHYSICAL PROPERTIES
 MELTING POINT: 201 TO 202 °C
 SOLUBILITY: 5% ACETIC ACID SOLUBLE

SECTION 10. ----- STABILITY AND REACTIVITY -----
 STABILITY
 STABLE.
 INCOMPATIBILITIES
 STRONG OXIDIZING AGENTS
 HAZARDOUS COMBUSTION OR DECOMPOSITION PRODUCTS
 TOXIC FUMES OF:
 CARBON MONOXIDE, CARBON DIOXIDE
 NITROGEN OXIDES
 HAZARDOUS POLYMERIZATION
 WILL NOT OCCUR.

SECTION 11. ----- TOXICOLOGICAL INFORMATION -----
 ACUTE EFFECTS
 HARMFUL IF SWALLOWED, INHALED, OR ABSORBED THROUGH SKIN.
 CAUSES EYE AND SKIN IRRITATION.
 MATERIAL IS IRRITATING TO MUCOUS MEMBRANES AND UPPER RESPIRATORY TRACT.
 MAY CAUSE ALLERGIC SKIN REACTION.
 EXPOSURE CAN CAUSE MYELOSUPPRESSION AND VOMITING.
 CHRONIC EFFECTS
 MAY CAUSE CONGENITAL MALFORMATION IN THE FETUS.
 LABORATORY EXPERIMENTS HAVE SHOWN MUTAGENIC EFFECTS.
 TARGET ORGAN(S):
 BONE MARROW
 IMMUNE SYSTEM
 EYES
 KIDNEYS
 LIVER
 HEART

RTCS #: X23012000
 5-TRIAZIN-2(1H)-ONE, 4-AMINO-1-(2-DEOXY-BETA-D-ERYTHRO-PENTOFURANOSYL)-

TOXICITY DATA
 IPR-MUS LD50: 190 MG/KG
 IVN-MUS LD50: 22 MG/KG

CNREA8 37,3684,1977
 DCTODJ 4,373,1981

REVISION 3

TARGET ORGAN DATA

BLOOD (LEUKOPENIA)
BLOOD (THROMBOCYTOPENIA)
EFFECTS ON FERTILITY (POST-IMPLANTATION MORTALITY)
EFFECTS ON EMBRYO OR FETUS (FETOTOXICITY)
SPECIFIC DEVELOPMENTAL ABNORMALITIES (MUSCULOSKELETAL SYSTEM)
NUTRITIONAL AND GROSS METABOLIC (WEIGHT LOSS OR DECREASED WEIGHT GAIN)
ONLY SELECTED REGISTRY OF TOXIC EFFECTS OF CHEMICAL SUBSTANCES
(RTECS) DATA IS PRESENTED HERE. SEE ACTUAL ENTRY IN RTECS FOR
COMPLETE INFORMATION.

SECTION 12. ----- ECOLOGICAL INFORMATION -----
DATA NOT YET AVAILABLE.

SECTION 13. ----- DISPOSAL CONSIDERATIONS -----
DISSOLVE OR MIX THE MATERIAL WITH A COMBUSTIBLE SOLVENT AND BURN IN A
CHEMICAL INCINERATOR EQUIPPED WITH AN AFTERBURNER AND SCRUBBER.
OBSERVE ALL FEDERAL, STATE AND LOCAL ENVIRONMENTAL REGULATIONS.

SECTION 14. ----- TRANSPORT INFORMATION -----
CONTACT SIGMA CHEMICAL COMPANY FOR TRANSPORTATION INFORMATION.

SECTION 15. ----- REGULATORY INFORMATION -----
EUROPEAN INFORMATION

TOXIC

R 61

MAY CAUSE HARM TO THE UNBORN CHILD.

R 20/21/22

HARMFUL BY INHALATION, IN CONTACT WITH SKIN AND IF SWALLOWED.

R 43

MAY CAUSE SENSITIZATION BY SKIN CONTACT.

R 36/37/38

IRRITATING TO EYES, RESPIRATORY SYSTEM AND SKIN.

S 45

IN CASE OF ACCIDENT OR IF YOU FEEL UNWELL, SEEK MEDICAL ADVICE
IMMEDIATELY (SHOW THE LABEL WHERE POSSIBLE).

S 26

IN CASE OF CONTACT WITH EYES, RINSE IMMEDIATELY WITH PLENTY OF
WATER AND SEEK MEDICAL ADVICE.

S 36/37/39

WEAR SUITABLE PROTECTIVE CLOTHING, GLOVES AND EYE/FACE
PROTECTION.

S 22

DO NOT BREATHE DUST.

TLV AND SOURCE

FOR METHYL ALCOHOL - SKIN:

ACGIH TLV-TWA: 200 PPM (260 MG/M3); STEL: 250 PPM (310 MG/M3).

OSHA PEL: 8 H TWA 200 PPM (260 MG/M3); STEL: 250 PPM (310 MG/M3).

U.S. INFORMATION

MAY CONTAIN UP TO:

1% METHANOL 67-56-1

THIS PRODUCT IS SUBJECT TO SARA SECTION 313 REPORTING REQUIREMENTS.

SECTION 16. ----- OTHER INFORMATION -----

THE ABOVE INFORMATION IS BELIEVED TO BE CORRECT BUT DOES NOT PURPORT TO
BE ALL INCLUSIVE AND SHALL BE USED ONLY AS A GUIDE. SIGMA, ALDRICH,
FLUKA SHALL NOT BE HELD LIABLE FOR ANY DAMAGE RESULTING FROM HANDLING
OR FROM CONTACT WITH THE ABOVE PRODUCT. SEE REVERSE SIDE OF INVOICE OR
PACKING SLIP FOR ADDITIONAL TERMS AND CONDITIONS OF SALE.

COPYRIGHT 2001 SIGMA-ALDRICH CO.

LICENSE GRANTED TO MAKE UNLIMITED PAPER COPIES FOR INTERNAL USE ONLY