

National Elevation Dataset

June, 2012 Release Notes Gayla Evans, Geographer, Elevation Project Manager U.S. Geological Survey (USGS), Earth Resources Observation and Science (EROS) Center

THE NATIONAL MAP

Contents

| Latest Release 2 Highlights 2 Resolutions of Data Available 4 High-Resolution (1/9-arc-second) Data 4 1/3-arc-second Data 6 Updates from High-Resolution Data 8 Mexico Available in the 1-arc-second Layer 9 Parts of Canada Available in the 1-arc-second Layer 9 Alaska Highlights 10 Currency 11 Datums 11 Production Methods 11 Source Data 13 NED Tile Processing 14 How to Obtain NED Data 15 Lidar Point Cloud Data Availability 15 Additional Information Availabile 15 Distribution Statistics 16 Terminology 17 | Contents | 1 |
|---|--|----|
| Resolutions of Data Available 4 High-Resolution (1/9-arc-second) Data 4 1/3-arc-second Data 6 Updates from High-Resolution Data 8 Mexico Available in the 1-arc-second Layer 9 Parts of Canada Available in the 1-arc-second Layer 9 Alaska Highlights 10 Currency 11 Datums 11 Production Methods 11 Source Data 13 NED Tile Processing 14 How to Obtain NED Data 15 Lidar Point Cloud Data Availability 15 Additional Information Available 15 Distribution Statistics 16 | Latest Release | 2 |
| Resolutions of Data Available 4 High-Resolution (1/9-arc-second) Data 4 1/3-arc-second Data 6 Updates from High-Resolution Data 8 Mexico Available in the 1-arc-second Layer 9 Parts of Canada Available in the 1-arc-second Layer 9 Alaska Highlights 10 Currency 11 Datums 11 Production Methods 11 Source Data 13 NED Tile Processing 14 How to Obtain NED Data 15 Lidar Point Cloud Data Availabile 15 Distribution Statistics 16 | Highlights | 2 |
| 1/3-arc-second Data 6 Updates from High-Resolution Data 8 Mexico Available in the 1-arc-second Layer 9 Parts of Canada Available in the 1-arc-second Layer 9 Alaska Highlights 10 Currency 11 Datums 11 Production Methods 11 Source Data 13 NED Tile Processing 14 How to Obtain NED Data 15 Lidar Point Cloud Data Availability 15 Additional Information Available 15 Distribution Statistics 16 | Resolutions of Data Available | 4 |
| 1/3-arc-second Data 6 Updates from High-Resolution Data 8 Mexico Available in the 1-arc-second Layer 9 Parts of Canada Available in the 1-arc-second Layer 9 Alaska Highlights 10 Currency 11 Datums 11 Production Methods 11 Source Data 13 NED Tile Processing 14 How to Obtain NED Data 15 Lidar Point Cloud Data Availability 15 Additional Information Available 15 Distribution Statistics 16 | High-Resolution (1/9-arc-second) Data | 4 |
| Mexico Available in the 1-arc-second Layer9Parts of Canada Available in the 1-arc-second Layer9Alaska Highlights10Currency11Datums11Production Methods11Source Data13NED Tile Processing14How to Obtain NED Data15Lidar Point Cloud Data Availability15Additional Information Available15Distribution Statistics16 | | |
| Parts of Canada Available in the 1-arc-second Layer9Alaska Highlights10Currency11Datums11Production Methods11Source Data13NED Tile Processing14How to Obtain NED Data15Lidar Point Cloud Data Availability15Additional Information Available15Distribution Statistics16 | Updates from High-Resolution Data | 8 |
| Parts of Canada Available in the 1-arc-second Layer9Alaska Highlights10Currency11Datums11Production Methods11Source Data13NED Tile Processing14How to Obtain NED Data15Lidar Point Cloud Data Availability15Additional Information Available15Distribution Statistics16 | Mexico Available in the 1-arc-second Layer | 9 |
| Currency11Datums11Production Methods11Source Data13NED Tile Processing14How to Obtain NED Data15Lidar Point Cloud Data Availability15Additional Information Available15Distribution Statistics16 | | |
| Currency11Datums11Production Methods11Source Data13NED Tile Processing14How to Obtain NED Data15Lidar Point Cloud Data Availability15Additional Information Available15Distribution Statistics16 | Alaska Highlights | 10 |
| Datums11Production Methods11Source Data13NED Tile Processing14How to Obtain NED Data15Lidar Point Cloud Data Availability15Additional Information Available15Distribution Statistics16 | Currency | 11 |
| Source Data 13 NED Tile Processing 14 How to Obtain NED Data 15 Lidar Point Cloud Data Availability 15 Additional Information Available 15 Distribution Statistics 16 | | |
| Source Data 13 NED Tile Processing 14 How to Obtain NED Data 15 Lidar Point Cloud Data Availability 15 Additional Information Available 15 Distribution Statistics 16 | Production Methods | 11 |
| How to Obtain NED Data | | |
| Lidar Point Cloud Data Availability | NED Tile Processing | 14 |
| Additional Information Available | How to Obtain NED Data | 15 |
| Additional Information Available | Lidar Point Cloud Data Availability | 15 |
| | Additional Information Available | 15 |
| Terminology | Distribution Statistics | 16 |
| | Terminology | 17 |

Latest Release

The June, 2012 update of the National Elevation Dataset (NED) 1-, 1/3- and 1/9-arc-second collections were released on June 12, 2012. This marks the 66th update of the 1-arc-second layer since bi-monthly revisions began in June, 2000. This release incorporates new light detection and ranging (lidar) data in addition to new standard production 10-meter digital elevation models (DEMs).

The next release is scheduled for August 7, 2012.

Highlights

The first set of topobathymetric data has been added to the <u>NED</u>. Topobathymetric data are created by merging topography (land elevation) and bathymetry (water depth) into a seamless elevation product useful for applications such as modeling sea level rise and storm surge. The initial dataset is centered over Mobile Bay, Alabama and was constructed using a combination of 71 disparate topographic and bathymetric datasets from the U.S. Geological Survey (USGS), the National Oceanic and Atmospheric Administration, and the U.S. Army Corps of Engineers; ranging in temporal variation from 1917 to 2011. It was developed in collaboration between the USGS Coastal and Marine Geology Program (CMGP) and the USGS National Geospatial Program. In the next five years, the CMGP has plans to expand its research and modeling along the northern Gulf of Mexico coastline, and San Francisco and Chesapeake Bays.




Figure 1. NED 1/9-arc-second first topobathymetric dataset—Mobile Bay, Alabama.

Areas where new data were incorporated in this and other recent releases are indicated in Figure 2.




Figure 2. NED updated areas by release date -- June, 2012 release.

Resolutions of Data Available




Figure 3. Composite of source data by resolution – June, 2012 release.

High-Resolution (1/9-arc-second) Data

The 1/9-arc-second NED is being developed from high resolution source data (3-meter or better point spacing from lidar, photogrammetry, or other sources). Higher resolution layers are being populated through the integration of data from various sources using new technologies, and are acquired through partnerships with Federal, State, and local partners, who provide access to the best available local information. As data are acquired and made available in the public domain, they are incorporated into the NED at a 1/9-arc-second resolution. Figure 4 shows the areas that reside in the NED 1/9-arc-second layer, as of June, 2012.




Figure 4. Available 1/9-arc-second data from all sources – June, 2012 release.

The following are NED 1/9-arc-second datasets released during the June update.

- Alabama—Mobile Bay topobathymetric data merge, 2012
- Arkansas---Dardanelle Reservoir, 2011
- Arkansas---Northwestern Pulaski county, 2010
- California---Golden Gate National Recreation Area, 2010
- Florida---Portions of southern and central Pasco County, 2011
- Georgia—Charlton and Ware counties, 2010
- Iowa—Central northeast, north central, and southeast areas of Iowa's statewide, 2008
- Massachusetts—Portion of eastern Massachusetts, 2011
- Missouri---Western flood plain area of Livingston County, 2011
- Missouri—City of Rolla, 2011
- Missouri—City of Steelville, 2011
- Oklahoma---Lower North Canadian River region of McIntosh, Oklahoma, Pottawatomie and Seminole counties, 2011
- South Carolina---Florence County, 2009
- Virginia---Portion of six counties in northern Virginia, 2011
- Washington---Two area in central Kittitas, 2010
- Washington---Pierce County, 2011
- Wisconsin—Brown County, 2010
- Wisconsin—Two small areas in Oconto County, 2010




Figure 5. Available and anticipated high-resolution data – June, 2012 release.

1/3-arc-second Data

NED contains data for all of the contiguous United States, Hawaii, and many Pacific Islands at a resolution of 1/3-arc-second (~10-meters). The current release of 1/3-arc-second NED (June 12, 2012) includes all USGS 10-meter as of May 4, 2012 (Figure 6).




Figure 6. Available 1/3-arc-second NED.

Source data with a resolution of 10-meters or higher currently exists for 99% of the United States (excluding Alaska). To complete 1/3-arc-second coverage for areas outside the State of Alaska, the remaining areas are derived by oversampling 30-meter source data. Figure 7 shows the distribution of source data resolutions. The spatial metadata delivered with each order describe the resolution of the source data used over any given area. As higher resolution source data become available, the 1/3-arc-second data derived from 30-meter DEMs are being replaced. It is anticipated that all oversampled 30-meter source data will be replaced by the end of fiscal year 2012.




Figure 7. 1/3-arc-second NED, June, 2012 release, by source resolution.

Updates from High-Resolution Data

As higher resolution datasets are released into the 1/9-arc-second layer, they are evaluated as a source to revise the NED 1- and 1/3-arc-second layers (Figure 8). Several higher resolution datasets were used as source data for other NED layers for this update cycle. The intention was to keep the 1/9-arc-second layer in sync with both the 1- and 1/3-arc-second layers (allowing for a time delay because of differences in the data processing flows). Some 1/9-arc-second datasets do not meet certain criteria, such as the flattened water bodies or bare-earth DEM specifications, which are required for the NED 1- and 1/3-arc second layers and, therefore, will not be used as source for updates for those layers.

In Alaska there are only specific areas covered in the NED 1/3-arc-second layer. Also, Puerto Rico, the Virgin Islands, Mexico, and parts of Canada are only supported in the NED 1-arc-second layer.




Figure 8. Migration status of NED 1/9 to other NED layers—June, 2012 release.

Mexico Available in the 1-arc-second Layer

Elevation data for the country of Mexico were added to the 1-arc-second NED in October, 2008. These data are a result of collaboration between USGS and Mexico's National Institute of Statistics and Geography (INEGI). The data were provided and quality control conducted by INEGI. Topographic staff at USGS EROS processed the data to improve edge matching, making the dataset seamless within itself and along the US / Mexico border.

Parts of Canada Available in the 1-arc-second Layer

Elevation data along the U. S. and Canada borders have been added to the 1-arc-second NED layer during the April and June, 2012 updates. These data are the result of collaboration between USGS and Natural Resources Canada (NRCAN) Centre for Topographic Information–Sherbrook, Ottawa. The Canadian data and accompanying metadata were provided by NRCAN. USGS EROS employees improved the topographic information along the international border by making the U.S. / Canada elevation data seamless in the 1-arc-second NED. These data complete the watersheds originating in the U.S. and fill a small void that existed between the two elevation datasets.

Alaska Highlights

Portions of Alaska are now available at resolutions of 1-, 1/3-, and 1/9-arc-second. The recent additions to the Alaska collection consist of either Interferometric Synthetic Aperture Radar (IFSAR) or lidar data. Per the statewide elevation plan, IFSAR will be the primary source for elevation data over Alaska. Currently, 15.77% of Alaska is covered by 10-meter or better source data.

Timeline of Alaska additions:

- August, 2008—Addition of Shuttle Radar Topography Mission (SRTM) data in the Aleutian chain
- December, 2008—Addition of the first lidar collection in Alaska over the port city of Valdez
- September, 2009—Lidar area of the Kenai Peninsula
- July-August, 2010—Lidar over Yukon Flats and additional areas of Kenai Peninsula
- February, 2011—Lidar over a central Kenai Peninsula
- April, 2011—Pilot area of mid-accuracy 5-meter IFSAR and a small piece of lidar along the northeast coast
- August, 2011-April 2012— Addition of 27 more 1 degree cells of mid-accuracy 5-meter IFSAR central Alaska

The resolution of available and anticipated Alaska data for the coming year are shown below in Figure 9.




Figure 9. Available and anticipated Alaska elevation data.

Currency

Data currency (Figure 10) is an important aspect of a multiple source dataset such as the NED. Note that NED currency represents when the original source was generated or acquired depending on the data type. However, if the data is reprocessed due to new and improved processing techniques the data still retains the original date the source was generated or acquired.




Figure 10. Currency of the NED shown by acquisition year – June, 2012.

Datums

All NED data are currently distributed in the North American Datum of 1983 (NAD83). Prior to April, 2008, NED data over Alaska were cast in the North American Datum of 1927 (NAD27).

Production Methods

Figure 11 shows the production methods used to produce NED data. Older production methods are small and will disappear as 30-meter data are replaced by higher resolution data. Production method in conjunction with data resolution, source and other factors can be used to determine data quality.




Figure 11. NED source data by production method – June, 2012 release.

The production methods are:

- Lidar, IFSAR and other active sensors including SRTM
- Complex linear interpolation from contours, often including hydrography (LT4X)
- Photogrammetrically compiled mass points and break lines
- Digital camera correlation, usually from line camera such as Leica ADS40
- Polynomial interpolation from contours, mass points, and break lines (ANUDEM)
- Simple linear interpolation from contours, (DLG2DEM and DCASS)
- Manual profiling via a mechanical or analytical stereo-plotter
- Gestalt Photomapper II (electronic image correlation)

Source Data

NED source data are selected from an ever-growing inventory of DEMs produced by USGS standard and other processes. With first consideration always being given to data quality, the selections to be integrated into the NED are made according to the following ranking and listed in the order of descending priority:

- High-resolution data, typically derived from lidar or digital photogrammetry, are often break line enforced. If collected at a ground sample distance no coarser than 5-meters, such data may also be offered within the NED at a resolution of 1/9-arc-second.
- Moderate-resolution data, other than that compiled from cartographic contours. These data may also be derived from lidar or digital photogrammetry, or less often by airborne IFSAR. A typical ground sample distance is ~10-meters commonly called "1/3-arc-second data."
- 10-meter DEMs derived from cartographic contours and mapped hydrography. Most often, such data
 are produced by or for the USGS as a standard elevation product, and they currently account for the
 bulk of the NED.
- 30-meter (Level 2) cartographically derived DEMs. Similar in most respects to their 10-meter counterparts, though usually of lower overall quality.
- 30-meter (Level 1) photogrammetrically derived DEMs. These are the oldest DEMs in the 7.5-minute series. These data were derived directly from stereo photography, either by a human operator or by an early form of electronic image correlation. They are typically marred by erroneous production artifacts that are addressed to the greatest practical extent by digital filtering within the NED production process.
- 2 arc-second DEMs are a standard USGS product. They are derived from cartographic contours at a scale of 1:63,360 over the state of Alaska, and a scale of 1:100,000 elsewhere.
- 1-arc-second SRTM data to date are only used in preference to 3-arc-second data in the Aleutian Islands.
- 3-arc-second DEMs are another standard USGS product, and are generally only used within the NED as a source of fill values over large water bodies.

The composition of source data within the June, 2012 NED release continues the trend seen in previous releases with an increase in coverage from 10-meter or better sources (Figure 12).

NED Source Data High Resolution Source 10-meter and 1/3-arc-second (7.5-minute DEM) 30-meter Level 2 (7.5-minute DEM) 90% 30-meter Level 1 (7.5-minute DEM) 80% 70% Percent of 1-arc-second NED layer 60% 50% 40% 30% 20% 10% 0% feoo. OCT NG - Kepol Jumot COCK ST ~ <e^{v 08} OCTAN OCTNS ~ Kervos OCT.DS Kep 09 OCTNO Kep 10 Jumon Kep St OCLAR Ken OS JUNOG Junge JUIT OS Ì. Release date

Figure 12. Type of 1-arc-second NED source data by release date.

NED Tile Processing


To address practical concerns of data processing and storage, with the exception of the 1/9-arc-second resolution, the NED is processed in 1x1-degree tiles coincident with integer degree boundaries of the Geodetic Reference System 1980 (GRS80) ellipsoid. A small amount of overlap is added to ensure that adjacent tiles are logically seamless. Additional tiles are added as required to accommodate new areas of coverage. (Table 1)

| Release date | Number of tiles | Note |
|---------------|-----------------|--|
| June, 2000 | 1,367 | CONUS: 925 tiles; AK: 428 tiles; HI: 14 tiles |
| April, 2001 | 1,375 | 8 tiles added: Puerto Rico and Virgin Islands |
| June, 2001 | 1,387 | 12 tiles added: Pacific islands |
| August, 2001 | 1,392 | 5 tiles added: Pacific islands |
| October, 2008 | 1,651 | 259 tiles added: Country of Mexico |
| April, 2012 | 2073 | 422 tiles added: Canadian data adjoining U.S. |
| June, 2012 | 2159 | 86 tiles added: Canadian data adjoining Alaska |


Table 1. Number of NED tiles and changes by release date.

In the current release, 151 tiles were updated, representing 16% of NED, excluding Alaska and Mexico, for which the extent of coverage is resolution-specific (Figure 13).

NED Update Processing



Release date



How to Obtain NED Data

A number of tools are available for accessing elevation data and mapping services at http://seamless .usgs.gov. Newly released and existing elevation data of the National Geospatial Program are available for download as tiled datasets via *The National Map* Viewer (<u>http://viewer.nationalmap.gov/viewer/</u>) or The National Map Seamless Server (<u>http://seamless.usgs.gov/website/seamless/viewer.htm</u>). For NED bulk data delivery via hard drive, contact USGS EROS Customer Service – <u>custserv@usgs.gov</u> (605-594-6151).

Lidar Point Cloud Data Availability

Most of the high-resolution DEM are being generated from lidar bare earth point data. NED distributes the elevation data but does not distribute the bare earth point cloud data. A complementary USGS activity to the NED is the Center for Lidar Information Coordination and Knowledge (CLICK) which provides lidar point cloud data for download (<u>http://lidar.cr.usgs.gov/</u>).


Additional Information Available

The following are available from the NED Web site (http://ned.usgs.gov/Ned/metadata.asp):


- the NED spatial metadata in shapefile (.shp) format
- the NED data dictionary with definitions of the attributes of the spatial metadata coverage
- previous issues of the NED Release Notes
- spatial metadata shapefiles of previous releases

No new information was added to the FAQ list on the NED home page (http://ned.usgs.gov)


Distribution Statistics



Download Statistics NED 1 Arc Second Online Downloads (Gbytes)



SDDS NED 1/9 Arc Second Online Downloads (Gbytes)



Terminology

lidar – light detection and ranging – an optical remote sensing technology that can measure the distance to, or other properties of, a target by illuminating the target with light, often using pulses from a laser.

IFSAR – Interferometric Synthetic Aperture Radar – a radar remote sensing technology that can measure the distance to, or other properties of, a target by illuminating the target with radar.

SRTM – Shuttle Radar Topography Mission – a joint project between the National Imagery and Mapping Agency (now the National Geospatial-Intelligence Agency) and the National Aeronautics and Space Administration (NASA) to produce digital topographic data for 80% of the Earth's land surface (all land areas between 60° north and 56° south latitude), with data points located every 1-arc-second (approximately 30 meters) on a latitude/longitude grid using a radar interferometry sensor on the space shuttle.