Guidelines for Egg and Oocyte Harvesting in Xenopus laevis

Amphibian oocytes are used for studies in molecular biology, embryology and biochemistry.

Unfertilized eggs are collected by gently squeezing eggs from females which have been injected with human chorionic gonadotropin (HCG) - 500 IU injected into the dorsal lymph sac. Females should begin laying eggs 12 hours after the HCG injection. When properly performed by technically proficient research personnel, female *Xenopus* are not harmed by the egg stripping procedure and can be used again after a recovery period of 3-6 months.

Stage I-VI oocytes are obtained by surgical laparotomy. Multiple surgeries on a single animal may be justified considering the reduction in the total number of animals used over the long term. However, the total number of animals used must be considered relative to the pain or distress experienced by an individual animal.

- 1. The total number of laparotomies should be limited and will depend on the condition of the animal and quality of the oocytes as well as the life span of the animal and the duration of egg production. Up to five recovery surgeries (the 6th would be terminal) per animal are acceptable. Additional survival surgeries should have approval of the individual ACUC.
- 2. Surgeries should be performed by trained personnel using appropriate anesthesia such as tricaine methane-sulfonate (MS-222). MS-222 solution should be buffered to a neutral pH of 7.0. Choice of anesthetic agent should be based on familiarity of the investigator with its use and in consultation with the attending veterinarian.
- 3. Surgeries should be done as aseptically as practical including the use of sterilized instruments and powderless gloves. Instruments should be sterilized by autoclaving or using a glass-bead sterilizer. The use of cold sterilants should be avoided so that these potentially toxic chemicals are not inadvertently introduced into the surgical site or onto permeable amphibian skin.
- 4. The use of surgical drapes and preparation of the surgical site remains controversial for aquatic species. The use of a sterile drape and preparation of the surgical site with dilute povidone iodine solution has been recommended. The use of these chemical agents may disrupt the normal skin flora of the patient and the constant mucous production of *Xenopus* skin makes any sterilization effort transient. When chemical surgical preps are used, they should be limited to the immediate area around the incision site and should only be solutions, not scrubs containing soaps or detergents.

Similarly, arguments have been presented regarding the use of surgical drapes. Drapes may be useful to keep mucus from getting on instruments and suture material, and can be moistened to keep skin from drying during surgery. However, amphibian skin can be easily damaged and paper drapes that become wet pose no barrier to bacteria. NIH veterinarians report that the incidence of clinical complications following surgical oocyte harvesting is rare.

Use of aseptic technique may improve oocyte quality by preventing cross contamination of the sample by frog skin bacterial flora.³

The decisions regarding the use of surgical drapes and performing single surgical site skin preps are left to the discretion of the NIH scientist in consultation with his/her IC veterinary staff and with approval by the ACUC.

- 5. Careful selection of suture materials and patterns can minimize post surgical complications². Monofilament sutures such as nylon have been shown to cause less inflammatory reaction in Xenopus skin. Closure in two layers (muscle layer and skin) is recommended particularly for surgical approaches that are off of the midline. Sutures should be removed no later than 2 weeks.
- 6. Single housing or small group housing for several days after surgery should be considered as part of the post surgical care of animals undergoing laparotomy. Frogs should be monitored daily during this period for appetite as well as for any complications such as dehiscence or infection. Such adverse effects would be reasons for immediate euthanasia.
- 7. Adequate recovery time should be allowed between laparotomies. The investigator can alternate oocyte collection between left and right ovaries and consider rotation of frogs so that the interval between surgeries in any individual is maximized. Ideally frogs should be rested at least two months between laparotomies; shorter resting periods may be appropriate if only small amounts of tissue are harvested. Recovery time of less than one month should have approval of the individual ACUC.

References:

- 1. DP O'Rourke and TW Schultz, Biology and Diseases of Amphibians, Laboratory Animal Medicine, 2nd Edition, Academic Press, 2002
- 2. AD Tuttle et al, 2006. Evaluation of the Gross and Histologic Reactions to Five Commonly Used Suture Materials in the Skin of African Clawed Frogs (*Xenopus laevis*) JAALAS 45(6): 22-26
- 3. HA Elsner et al, 2000. Poor Quality of Oocytes from *Xenopus laevis* Used in Laboratory Experiments: Prevention by Use of Antiseptic Surgical Technique and Antibiotic Supplementation, Comparative Medicine 50(2): 206-211

Approved – 6/12/96 Reapproved – 10/10/2001 Revised – 2/10/1999, 4/13/2005, 10/10/2007, 7/14/2010