## Cutaneous Melanoma Histology Coding Rules – Matrix C440-C449 (Excludes melanoma of all other sites)

| Rule   | Melanoma Specimen   | Histology   | Behavior                | Notes and Examples   | Code  |  |  |  |
|--|---|---|-------------------------|--|---|--|--|--|
| SINGLE MELANOMA OR MULTIPLE MELANOMAS ABSTRACTED AS A SINGLE PRIMARY |   |   |                         |  |   |  |  |  |
| H1   | No pathology/cytology<br>specimen or the<br>pathology/cytology report is<br>not available |   |                         | <ul> <li>1: Priority for using documents to code the histology</li> <li>Documentation in the medical record that refers to pathologic or cytologic findings</li> <li>Physician's reference to type of melanoma in the medical record</li> <li>PET scan</li> <li>2: Code the specific histology when documented.</li> </ul>               | The histology<br>documented by the<br>physician |  |  |  |
| H2   | None from primary site  |   |                         | Code the behavior /3   | The histology from metastatic site              |  |  |  |
| H3   |   | One type  |                         |  | The histology                                   |  |  |  |
| H4   |   |   | Invasive<br>and in situ |  | The invasive<br>histologic type                 |  |  |  |
| H5   |   | Regressing<br>melanoma and a<br>histologic type           |                         | <i>Example:</i> Nodular melanoma with features of regression. Code 8721 (Nodular melanoma).  | The histologic type                             |  |  |  |
| H6   |   | Regressing melanoma                                       |                         | <i>Example:</i> Malignant melanoma with features of regression. Code 8723.   | 8723 (Malignant<br>melanoma,<br>regressing)     |  |  |  |
| H7   |   | Lentigo maligna<br>melanoma and a<br>histologic type      |                         |  | The histologic type                             |  |  |  |
| H8   |   | Lentigo maligna<br>melanoma                               |                         |  | 8742 (Lentigo<br>maligna melanoma)              |  |  |  |
| H9   |   | Melanoma, NOS<br>(8720) with a<br>single specific<br>type |                         | <ol> <li>The specific type for in situ lesions may be identified as pattern, architecture, type, subtype, predominantly, with features of, major, or withdifferentiation.</li> <li>The specific type for invasive lesions may be identified as type, subtype, predominantly, with features of, major, or withdifferentiation.</li> </ol> | The most specific<br>histologic term            |  |  |  |

## Cutaneous Melanoma Histology Coding Rules – Matrix C440-C449

(Excludes melanoma of all other sites)

| Rule | Melanoma Specimen               | Histology          | Behavior | Notes and Examples | Code            |
|------|---------------------------------|--------------------|----------|--------------------|-----------------|
| H10  | None of the above conditions ar | The histology with |          |                    |                 |
|      |                                 |                    |          |                    | the numerically |
|      |                                 |                    |          |                    | higher ICD-O-3  |
|      |                                 |                    |          |                    | code            |