## Cutaneous Melanoma Histology Coding Rules – Text C440-C449 with Histology 8720-8780 (Excludes melanoma of any other site)

## SINGLE MELANOMA OR MULTIPLE MELANOMAS ABSTRACTED AS A SINGLE PRIMARY

Code the histology documented by the physician when there is no pathology/cytology specimen or the pathology/cytology

	report is <b>not available</b> .
	<ul> <li>Note 1: Priority for using documents to code the histology</li> <li>Documentation in the medical record that refers to pathologic or cytologic findings</li> </ul>
	<ul> <li>Documentation in the medical record that refers to pathologic or cytologic findings</li> <li>Physician's reference to type of melanoma in the medical record</li> </ul>
	PET scan
	Note 2: Code the specific histology when documented.
Rule H2	Code the histology from the metastatic site when there is <b>no pathology/cytology specimen from the primary site</b> . <i>Note:</i> Code the behavior /3.
Rule H3	Code the histology when only <b>one histologic type</b> is identified.
Rule H4	Code the invasive histologic type when there are <b>invasive and in situ</b> components.
Rule H5	Code the <b>histologic type</b> when the diagnosis is <b>regressing</b> melanoma <b>and</b> a <b>histologic</b> type. <i>Example:</i> Nodular melanoma with features of regression. Code 8721 (Nodular melanoma).
Rule H6	Code 8723 (Malignant melanoma, regressing) when the diagnosis is <b>regressing melanoma</b> . <i>Example</i> : Malignant melanoma with features of regression. Code 8723.
Rule H7	Code the <b>histologic type</b> when the diagnosis is <b>lentigo maligna</b> melanoma <b>and</b> a <b>histologic</b> type.
Rule H8	Code 8742 (Lentigo maligna melanoma) when the diagnosis is <b>lentigo maligna</b> melanoma.
Rule H9	Code the most specific histologic term when the diagnosis is melanoma, NOS (8720) with a single specific type.  Note 1: The specific type for in situ lesions may be identified as pattern, architecture, type, subtype, predominantly, with features of, major, or withdifferentiation  Note 2: The specific type for invasive lesions may be identified as type, subtype, predominantly, with features of, major, or withdifferentiation.

Rule H1

## Cutaneous Melanoma Histology Coding Rules – Text C440-C449 with Histology 8720-8780 (Excludes melanoma of any other site)

**Rule H10** Code the histology with the **numerically higher** ICD-O-3 code.

This is the end of instructions for Single Melanoma or Multiple Melanomas Abstracted as a Single Primary. Code the histology according to the rule that fits the case.