Absolute Ionosphere Slant Delays From Ambiguous Carrier Phase Data

Dru A. Smith, Ph.D.
National Geodetic Survey
National Oceanic and Atmospheric Administration

ION NTM 2005 January 25, 2005 San Diego, CA

Topics of Discussion

Motivation for NGS ionosphere

Model/Equations


Comparisons/Analysis

Conclusions


Geodetic need for ionosphere delays

- Dominant Frequency-dependent signals in GPS:
 - Ambiguities
 - Ionosphere
- Difficult to separate quickly
- NGS decision: model the ionosphere to get ambiguities faster
- Data wasn't an issue: CORS

CORS Coverage - December 2004



Symbol color denotes sampling rates: (1 sec) (5 sec) (10 sec) (15 sec) (30 sec) (Decommissioned)
Craig 12/22/2004




Nearly every part of the ionosphere above CONUS is viewed by CORS 12+ times daily (some >100 times a day)

Tools and Terms

- Terms:
 - Track = Sequential L1&L2 data for one
 CORS/SV combo without extended loss of lock
 - <u>TECS</u>=Total Electron Content along satellite/receiver vector

CORS yields about 20-30k tracks every day



Smith, D.A., Absolute Ionosphere, ION NTM 2005


Primary Objective

 Model <u>absolute TECS</u> data and <u>maintain</u> <u>high resolution</u> details of TECS for every track over CONUS

• Focus on *fast*, *accurate* ionosphere delays; not on modeling 4-D electron distribution

Getting TECS from carrier data

- For 1 track, between any two epochs (i, j):
 - $-i_{,j}\Delta TECS = k("40.3", f_1, f_2) \times (i_{,j}\Delta L1 i_{,j}\Delta L2)$
- Thus, every track has:
 - Very accurately known <u>shape</u> of ∂TECS/∂time (from carrier phase data)
 - One unknown TECS bias
- As per the Primary Objective:
 - Solve 1 TECS bias per track




Solving for biases

- Consider: Two receiver-satellite vectors of two different tracks "sufficiently close" to each other in time & space.
 - Call this a <u>crossover</u>
- Assumption at a crossover:
 - TECS(t, $\underline{\text{track a}}$) = f [TECS(t±dt, $\underline{\text{track b}}$)]
 - "sufficiently close" must be defined
 - Find an acceptable mapping function "f"

Mapping Functions


- Any mapping function can be used
 - Linear or non-linear
 - But, how good is your mapping function?

- NGS currently using the "vertical column equality" assumption
 - Crossovers defined by nearness of the two vectors at their 300 km altitude points
 - "Sufficiently close" generally at 0.1° x 0.1° x 60 sec



Using Crossovers

- By itself, one crossover has:
 - -1 condition (TECS₁ = f[TECS₂])
 - 2 unknowns (TECS biases for 2 tracks)
 - Thus, unsolvable as is
- Need conditions ≥ unknowns
- Closed polygons is the solution




Polygon Crossover Equations

$$\begin{bmatrix} {}^{A}_{1}\Delta TECS & \cos {}^{A}_{1}z' - {}^{A}_{3}\Delta TECS & \cos {}^{A}_{3}z' \\ {}^{B}_{1}\Delta TECS & \cos {}^{B}_{1}z' - {}^{B}_{2}\Delta TECS & \cos {}^{B}_{2}z' \\ {}^{C}_{2}\Delta TECS & \cos {}^{C}_{2}z' - {}^{C}_{3}\Delta TECS & \cos {}^{C}_{3}z' \end{bmatrix}$$


$$= \begin{bmatrix} -\cos \frac{A}{1}z' & 0 & +\cos \frac{A}{3}z' \\ -\cos \frac{B}{1}z' & +\cos \frac{B}{2}z' & 0 \\ 0 & -\cos \frac{C}{2}z' & +\cos \frac{C}{3}z' \end{bmatrix} \begin{bmatrix} b_1 \\ b_2 \\ b_3 \end{bmatrix}$$

Smith, D.A., Absolute Ionosphere, ION NTM 2005




Initial Tests(NGS)

- Small "tracknets" of 10-12 tracks formed
- Proof-of-concept
- Absolute delays converted to double difference delays
- DD delays good to 0.1± 0.01 TECUs against "truth" (Ambiguity resolving software)




Initial Tests(OSU)

- The Ohio State University compared various Ionosphere estimates at Ohio CORS stations
- Double-difference mode
- Crossovers restricted to 40 degrees above the horizon
 - Avoids erroneous biases from low-elevation crossovers
 - Reduces number of tracks immediately solvable from tracknets (unsolved tracks need interpolation from nearby solved tracks)



"Large" z' makes the mapping of TECS₁ into TECS₂ questionable



"Small" z' makes the mapping of TECS₁ into TECS₂ more reliable

Report for NOAA/NGS

On:

Accuracy analysis of various NGS ionosphere estimation models

Dorota Grejner-Brzezinska, Pawel Wielgosz, Israel Kashani

Department Of Civil & Environmental Engineering & Geodetic Science
The Ohio State University
470 Hitchcock Hall, 2070 Neil Avenue, Columbus, OH 43210

Tel: 614-292-0169; Fax: 614-292-2957

Email: dbrzezinska@osu.edu Email: kashani.1@osu.edu Email: wielgosz.1@osu.edu




Fig. 22 NGSa DD iono (day-time)




Fig. 23 NGSa DD iono differences from the "truth" (daytime)




Fig. 24 NGSb DD iono (day-time)




Fig. 25 NGSb DD iono differences from the "truth" (daytime)

NOAA's "Magic" model

This model

Initial Tests(Results)

In double-differenced mode, this method yields
 ~0.3 TECU agreement with independent estimates
 of the ionosphere

Caveats:

- One outlying bias can skew results of many tracks
- Cycle slip detection/correction may be too strict
- This method behaved worse in A.R. than MAGIC

Absolute TECS Sensitivity Analysis

 While mathematically consistent, this method is sensitive to choices:

- What is a crossover?
 - "Sufficiently close" definition
- How are the mapping functions applied?
 - Which one is used and where is it applied?

Absolute TECS Sensitivity Analysis (Crossover definition)

- Sensitivity to definitions of "sufficiently close"
 - Tested 5 different definitions for day 298 of 2004

| 0.20° x 0.20° x 300 s | 14,657 tracks solvable |
|-------------------------|------------------------|
| 0.15 ° x 0.15 ° x 150 s | 13,941 tracks solvable |
| 0.10 ° x 0.10 ° x 60 s | 12,698 tracks solvable |
| 0.05 ° x 0.05 ° x 30 s | 9,129 tracks solvable |
| 0.01 ° x 0.01 ° x 10 s | 0 tracks solvable |

Sensitivity of TECS values: ±1.98 TECU

Absolute TECS Sensitivity Analysis (Mapping Function Location)

- Sensitivity to location of mapping function
 - Tested 5 different locations for day 298 of 2004

| 250 km | 12,041 tracks solvable |
|--------|------------------------|
| 300 km | 12,698 tracks solvable |
| 350 km | 12,680 tracks solvable |
| 400 km | 12,905 tracks solvable |
| 450 km | 13,044 tracks solvable |


Sensitivity of TECS values: ±1.26 TECU

ICON: Prototype Model

- After internal testing, a prototype production was established at NGS (Nov 1, 2004) to encourage independent validations
- Daily solutions (~15k crossovers, ~30k tracks)
 - Sparse matrix solution = 2 minutes
 - Reading data/uncompressing/gridding/making pretty pictures = 3 hours
- "ICON" (Ionosphere over CONus)
- www.ngs.noaa.gov/ionosphere


Absolute Comparison with IGTEC

- ~ 1 month of data (Dec 2004)
- ICON IGTEC
- Daily bias between models ~ -3 to -4 TECU
- Daily σ around bias $\sim \pm 2$ to 3 TECU
- Possible causes:
 - Resolution differences
 - Model errors



Absolute Comparison with MAGIC(NGS)


- Data generally unavailable currently
- ICON MAGIC
- Daily bias between models ~ +1 TECU
- Daily σ around bias $\sim \pm 2$ to 3 TECU
- Possible causes:
 - Resolution differences
 - Model errors






 As a secondary product, ICON produces radial TEC (TECR) on a grid in IONEX and GIF formats


- Mostly for analysis: Grid to slant delays introduce another error source
 - Useful for seeing outliers, storms and small ionosphere features



Smith, D.A., Absolute Ionosphere, ION NTM 2005



Smith, D.A., Absolute Ionosphere, ION NTM 2005



Nov 6-7, 2004

Nov 7-8, 2004

Summary and Conclusions

- Absolute TECS is mathematically determinable from ambiguous carrier phase data under 4 assumptions:
 - Network of Ground Stations
 - Dual Frequency
 - $-i_{,j}\Delta TECS = k("40.3", f_1, f_2) \times (i_{,j}\Delta L1 i_{,j}\Delta L2)$
 - TECS₁ = f[TECS₂] when "sufficiently close"

Summary and Conclusions

- Relying on simple cosine mapping functions, a model for the ionosphere can be computed as an entire network
 - to ~4 TECU RMS (absolute)
 - to ~0.3 TECU RMS (5 cm on L1) agreement with Double Difference estimates, subject to cycle-slip fixing and outlier biasing
- Interpolation can yield ± 5 cm (L1) biases from nearby tracks

Future Work

 Removal of outliers and general improvement in regional correlation

• Usefulness of method in A.R. must be improved

 Move from daily solutions to progressive epoch by epoch solutions

Contact Information

- Dr. Dru A. Smith
- 301-713-3202 x 149
- Fax: 301-713-4172
- Dru.Smith@noaa.gov
- www.ngs.noaa.gov/ionosphere

Questions?

Extra Slides

Conclusions

- Average a-posteriori σ_{bias} of ± 1.1 TECU reasonable, but larger than hoped for
- Sub-TECU crossover residuals show tight "locking" or consistency of tracknet
- Overall noise in grids needs improvement
- General conclusion:
 - "Promising" but not by any means "done"
 - Initial analysis indicates <u>near-horizon crossovers are</u>
 <u>the primary error source</u> (TECS=TECR/cos z' unreliable)

Summary and Conclusions (cont)

- Further sensitivity studies:
 - Removing near-horizon crossovers (nearly done)
 - Shell height
 - CORS thinning
- Independent tests forthcoming:
 - Against other ionosphere models
 - In ambiguity resolving software
- Production:
 - Daily solutions expected to begin in Fall 2004

| 2.10 teqc 2000Jul20 dqua XXX CORS/NGS/NOAA 3735A20424 3328A68603 -395445.7142 -527 0.0000 | TRM14532.00 | unt OSSI | 7.19 13 | | 3UTCPGM / MARKEI MARKEI OBSERV REC # ANT # APPROS | VERSION / TYPE RUN BY / DATE R NAME R NUMBER /FER / AGENCY / TYPE / VERS / TYPE K POSITION XYZ NA: DELTA H/E/N |
|---|---|-------------------|--------------------------------|-------------------|---|--|
| 1 1 | *************************************** | ****** | *********** | | ~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~ | NGTH FACT L1/2 |
| 8 Cî Li | L2 P1 | P2 | D1 D | 2 <mark>I1</mark> | 2516.000.04396.7 | YPES OF OBSERV |
| 30.0000 | 0 A 0 12521 | - | | | INTER | |
| Forced Modulo Decim | | | 000 | ana | COMMEN | |
| 2004 1 7 This is an IINEX fi | 0 0 | 0.0000 | | GPS | COMMEN | OF FIRST OBS |
| The difference is t | | | | ting | COMMEN | 8-3-1 () () () () () () () () () (|
| the computed Ionosp | | | | | COMMEN | |
| has been introduced | | | | | COMMEN | |
| always be positive. | | | 3 0000000 | 7. | COMMEN | |
| I1 was computed by | Dru Smith, NOA | A/NGS w | ith the | followin | g COMMEN | <mark>IT</mark> |
| parameters (see D. | Smith for deta | ils): | | | COMMEN | <mark>vT</mark> |
| Year = 2004 Day of | Year = 2004 Day of Year = 007 | | | | | |
| | Shell Height (km) = 0300 | | | | | <mark>IT</mark> |
| Track Cleaning Crit | | : 001 | | | COMMEN | <mark>IT</mark> |
| Crossover Spacing C | | | | | COMMEN | |
| Tracknet Formation | VVVVVVVV | ~~~~ | | | COMMEN | |
| LSA Weighting Schem | | : 004 | | | COMMEN | VVV |
| Flag for post-LSA i | nterpolation | : 000 | | | COMMEN | |
| 04 1 7 0 0 0. | 0000000 0 9G | FC10C0 | 40 6015 | 6106 4600 | | F HEADER |
| · · · · · · · · · · · · · · · · · · · | 0363943.65748 0.00000 | 81425 | 14.0074 15.799 | | W | 0 0.000000000 21696361.84440 |
| 25107871.38340 | 3708841.58542 | 22595 | 56.0294 | 15 | 0.00000 | 25107875.26240 |
| -3307.67240 | 0.00000 | <mark>-999</mark> | 99.000 | | | *************************************** |
| -3686.29740 | 0.00000 | -999 | 29.9734 <mark>99.000</mark> | | 0.00000 | 21512363.50440 |
| 23862591.76640 - | 1725935.55946 | -11506 | 92.5904 | 15 | 0.00000 | 23862597.87140 |
| 706.65640 | 0.00000 | | 24.278 | | | |
| | 3655026.98748 | 28922 | 49.1324 | 17 | 0.00000 | 21126136.67640 |
| -1809.82840 | 0.00000 | | 9.850 | | | |
| 20301784.44540 - | 5022796.20048 | | 05.2534 | 17 | 0.00000 | 20301789.52040 |
| -1548.39140 | 0.00000 | | 99.000 | | | |
| ~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~ | 1863677.08547 | | 73.8204 | 6 | 0.00000 | 24034694.44540 |
| -4906.23440 | 0.00000 | | 99.000 | (6) | 0.00000 | 04860086 04045 |
| 21762273.85940 | | -1479 | 89.8224 | ю | 0.00000 | 21762278.34840 |
| -1713.00040 24560456.50840 | 0.00000 -45620.85743 | | 16.644 0.0000 | 10: | 0.00000 | 0.00000 |
| 704.09440 | 0.00000 | _gac | 99.000 | ,0 | 9.00000 | 0.00000 |
| 101.05110 | 0.00000 | 223 | JJ.000 | | | |

CORS Network

- *Currently 400+ 24/7 receivers*
 - Dual frequency, carrier-phase
 - Multi-agency
 - Administered by NGS
 - All 50 states, Central America, others
 - Ideally suited to serve as an ionosphere monitoring network for geodetic applications in the USA

Equations

$${}^{i}R_{k} = b_{k} + {}^{i}r + c({}^{i}\delta t) + {}^{i}T + {}^{i}I_{k}(+{}^{i}m_{k}) = \lambda_{k} {}^{i}\Phi_{k}^{RINEX}$$
 (biased range, m, epoch "i", freq "k")
$$I_{k} = -\frac{40.3}{f_{k}^{2}}TECS$$
 (m)

$$\therefore \lambda_1^{i} \Phi_1^{\text{RINEX}} - \lambda_2^{i} \Phi_2^{\text{RINEX}} = (b_1 - b_2) + (iI_1 - iI_2)$$

$$\therefore iTECS = \left(\frac{1}{40.3}\right) \left(\frac{1}{f_1^2} - \frac{1}{f_2^2}\right)^{-1} \left[\lambda_1^{i} \Phi_1^{RINEX} - \lambda_2^{i} \Phi_2^{RINEX}\right]$$
$$-\left(\frac{1}{40.3}\right) \left(\frac{1}{f_1^2} - \frac{1}{f_2^2}\right)^{-1} (b_1 - b_2)$$

$$\therefore$$
 $^{i,j}\Delta TECS = ^{j}TECS - ^{i}TECS$

$$= \left(\frac{1}{40.3}\right) \left(\frac{1}{f_1^2} - \frac{1}{f_2^2}\right)^{-1} \left(\lambda_1^{i,j} \Delta \Phi_1^{RINEX} - \lambda_2^{i,j} \Delta \Phi_2^{RINEX}\right)$$

Smith, D.A., Absolute Ionosphere, ION NTM 2005

Closed Polygons

- Altimetry or Leveling ($\Delta H \& H$ -equality):
 - # conditions = # vertices 1
- Ionosphere (ΔTECS & TECR-equality)
 - # conditions = # vertices
- Any time that a closed polygon is formed we have:
 - # Conditions = # Unknowns

Polygon Crossover Equations


$$\begin{bmatrix} {}^{A}_{1}\Delta TECS & \cos {}^{A}_{1}z' - {}^{A}_{3}\Delta TECS & \cos {}^{A}_{3}z' \\ {}^{B}_{1}\Delta TECS & \cos {}^{B}_{1}z' - {}^{B}_{2}\Delta TECS & \cos {}^{B}_{2}z' \\ {}^{C}_{2}\Delta TECS & \cos {}^{C}_{2}z' - {}^{C}_{3}\Delta TECS & \cos {}^{C}_{3}z' \end{bmatrix}$$


$$= \begin{bmatrix} -\cos \frac{A}{1}z' & 0 & +\cos \frac{A}{3}z' \\ -\cos \frac{B}{1}z' & +\cos \frac{B}{2}z' & 0 \\ 0 & -\cos \frac{C}{2}z' & +\cos \frac{C}{3}z' \end{bmatrix} \begin{bmatrix} b_1 \\ b_2 \\ b_3 \end{bmatrix}$$

Smith, D.A., Absolute Ionosphere, ION NTM 2005

Polygon Crossover Equations

- The existence of the cos z' values on the RHS allows for matrix inversion
 - (as opposed to +1,0 and -1 for altimetry)
- Solvability
- Can we have redundancy?
 - YES





Initial Tests

• Parameters:

- Crossover height = 300 km
- Crossover definition: 0.1° x 0.1° x 1 min
- Cut-off angle: 10° (for data and crossovers)

Initial Tests (all contain the 4 base tracks)


- Solution 1 (smallest tracknet possible containing the 4 base tracks)
 - 8 tracks, No polygons, PR-fit 6 of 8 tracks
- Solution 2
 - 10 tracks, 2 polygons, PR-fit 7 of 10 tracks
- Solution 3
 - 10 tracks, 2 polygons, no PR-fitting
- Solution 4
 - 10 tracks, 2 polygons, PR-fit 1 of 10 tracks

Formal σ_{bias} estimates for first tracknet tests (in TECU)

| | | Г | | |
|-------------|--|--|-----------------------------------|--|
| Track # | Soln 1 (PR fit to 6 of 8; no polygons) | Soln 2 (PR fit to 7 of 10; 2 polygons) | Soln 3 (No PR fit; 2 polygons) | Soln 4 (PR fit to 1 of 10; 2 polygons) |
| 4300 (base) | 3.5 | 2.9 | 0.1 | 1.2 |
| 4303 (base) | 8.8 | 4.7 | 0.2 | 2.1 |
| 9484 (base) | 9.3 | 4.6 | 0.2 | 2.0 |
| 9487 (base) | 9.4 | 3.1 | 0.1 | 1.3 |
| 2253 | 13.6 | 5.9 | 0.3 | 2.5 |
| 10146 | 9.7 | 3.3 | 0.1 | 1.4 |
| 11416 | 6.5 | 4.9 | 0.2 | 2.0 |
| 12565 | 6.1 | 3.9 | 0.2 | 1.6 |
| 2224 | - | 4.3 | 0.2 | 1.7 |
| 11580 | - | 3.0 | 0.1 | 1.2 |

Initial Tests (cont)

- Individual ionosphere delays for each SV/CORS combo were estimated:
 - I₄₃₀₀(SV1/GODE), I₄₃₀₃(SV2/GODE), I₉₄₈₄(SV1/RED1),
 I₉₄₈₇(SV2/RED1) all estimated individually (as well as for all other tracks in the tracknet)
- Double Difference delays were then computed:
 - I_{DD}=(I₄₃₀₀-I₉₄₈₄)-(I₄₃₀₃-I₉₄₈₇) computed and compared to independent estimates from NGS ambiguity resolving software



First tracknet tests

- Pseudo-range fitting tends to bias the tracknet
- Better fit to Double Difference estimated ionosphere by using just polygons and no P-R fitting

Full day solution (cont)

- Interpolation from tracks to grids and/or other tracks:
 - Track-to-grid-to-Track
 - Useful for grid-distributed Ionosphere model and animations
 - 0.00 ± 0.38 TECU (± 6 cm on L1)
 - Track-to-Track
 - Useful for <u>RINEX-distributed</u> Ionosphere model
 - 0.00 ± 0.25 TECU (± 5 cm on L1)
- Full day solution was gridded and animated

Example 2. 17:00-18:00 UT (day-time)

The "truth" DD ionospheric delays are presented in figure 14 with the corresponding satellite elevation map in figure 15. Figures 16–25 represents the derived DD ionosphere form each method and the difference from the "truth" (in pairs). The mean and standard deviation of the ionospheric residuals from the "truth" are shown in Table 2.




Fig. 14 "Truth" DD iono (day-time)




Fig. 15 Satellite elevations




Fig. 16 P4 DD iono (day-time)




Fig. 18 GIM DD iono (day-time)




Fig. 17 P4 DD iono differences from the "truth" (day-time)




Fig. 19 GIM DD iono differences from the "truth" (daytime)

Smoothed Pseudorange Estimates

> OSU's MPGPS method

