# SEER RESEARCH DATA RECORD DESCRIPTION

CASES DIAGNOSED IN 1973-2009\*

Submission: November 2011

Follow-up Cutoff Date: December 31, 2009

**Documentation Version:** April 2012

Diagnosis Years: 1973-2009

\* This documentation describes the data files in the incidence/yr1973\_2009.seer9, yr1992\_2009.sj\_la\_rg\_ak, yr2000\_2009.ca\_ky\_lo\_nj\_ga, and yr2005.lo\_2nd\_half directories. Refer to individual variable definitions to determine the differences between the directory files.

Cervix in situ cases after 1995 are not included.

PATIENT ID NUMBER	. 11
REGISTRY ID	. 11
MARITAL STATUS AT DX	
RACE / ETHNICITY	. 13
SPANISH / HISPANIC ORIGIN	
NHIA DERIVED HISPANIC ORIGIN	
SEX	
AGE AT DIAGNOSIS	
BIRTHDATE—YEAR	
BIRTHPLACE	
SEQUENCE NUMBERCENTRAL	
MONTH OF DIAGNOSIS	
YEAR OF DIAGNOSIS	
PRIMARY SITE	
LATERALITY	
HISTOLOGY (92-00) ICD-O-2	
BEHAVIOR (92-00) ICD-O-2	
HISTOLOGIC TYPE ICD-O-3	
BEHAVIOR CODE ICD-O-3	
GRADE	
DIAGNOSTIC CONFIRMATION	
TYPE OF REPORTING SOURCE	
EOD—TUMOR SIZE	
EOD-EXTENSION	
EOD—EXTENSION PROST PATH	
EOD—LYMPH NODE INVOLV	
REGIONAL NODES POSITIVE	
REGIONAL NODES EXAMINED	
EOD—OLD 13 DIGIT	
EOD—OLD 2 DIGIT	
EOD—OLD 4 DIGIT	
CODING SYSTEM FOR EOD	
TUMOR MARKER 1	
TUMOR MARKER 2	
TUMOR MARKER 3	
CS TUMOR SIZE	
CS EXTENSION	
CS LYMPH NODES	
CS METS AT DX	
CS SITE-SPECIFIC FACTOR 1	
CS SITE-SPECIFIC FACTOR 2	
CS SITE-SPECIFIC FACTOR 3	
CS SITE-SPECIFIC FACTOR 4	
CS SITE-SPECIFIC FACTOR 5	
CS SITE-SPECIFIC FACTOR 6	
CS SITE-SPECIFIC FACTOR 25	
DERIVED AJCC-6 T	
DERIVED AJCC-6 N	
DERIVED AJCC-6 M	
DERIVED AJCC-6 STAGE GRP	
DERIVED SS1977	
	· • •

DERIVED SS2000	41
DERIVED AJCC—FLAG	42
DERIVED SS1977—FLAG	42
DERIVED SS2000—FLAG	43
CS VERSION INPUT ORIGINAL	43
CS VERSION DERIVED	43
CS VERSION INPUT CURRENT	44
RX SUMM—SURG PRIM SITE	44
RX SUMM—SCOPE REG LN SUR	45
RX SUMM-SURG OTH REG/DIS	45
RX SUMM-REG LN EXAMINED	46
RECONSTRUCTION-FIRST COURSE (1998-2002)	46
REASON FOR NO SURGERY	
RX SUMM—RADIATION	48
RX SUMM—RAD TO CNS	48
RX SUMM—SURG/RAD SEQ	49
RX SUMM-SURG TYPE	
RX SUMM—SURG SITE 98-02	
RX SUMM—SCOPE REG 98-02	
RX SUMM—SURG OTH 98-02	
SEER RECORD NUMBER	
OVER-RIDE AGE/SITE/MORPH	
OVER-RIDE SEQNO/DXCONF	
OVER-RIDE SIT/LAT/SEQNO	
OVER-RIDE SURG/DXCONF	
OVER-RIDE SITE/TYPE	
OVER-RIDE HISTOLOGY	
OVER-RIDE REPORT SOURCE	
OVER-RIDE ILL-DEFINE SITE	
OVER-RIDE LEUK, LYMPHOMA	
OVER-RIDE SITE/BEHAVIOR	
OVER-RIDE SITE/EOD/DX DT	
OVER-RIDE SITE/LAT/EOD	
OVER-RIDE SITE/LAT/MORPH	
SEER TYPE OF FOLLOW-UP	
AGE RECODE <1 YEAR OLDS	
SITE RECODE	
SITE RECODE WITH KAPOSI SARCOMA AND MESOTHELIOMA	
RECODE ICD-O-2 TO 9	
RECODE ICD-O-2 TO 10	
ICCC SITE RECODE ICD-O-2	
SEER MODIFIED ICCC SITE RECODE ICD-0-2	
ICCC SITE RECODE ICD-0-3	
ICCC SITE RECODE EXTENDED ICD-O-3	
BEHAVIOR RECODE FOR ANALYSIS	
HISTOLOGY RECODE—BROAD GROUPINGS	
HISTOLOGY RECODE—BRAIN GROUPINGS	
CS SCHEMA V0203	
RACE RECODE (WHITE, BLACK, OTHER)	
RACE RECODE (WHITE, BLACK, OTHER) RACE RECODE (W, B, AI, API)	
ORIGIN RECODE (W, B, AI, AI)	
SEER HISTORIC STAGE A	
	14

AJCC STAGE 3 <sup>RD</sup> EDITION (1988-2003)	73
SEER MODIFIED AJCC STAGE 3 <sup>RD</sup> ED (1988-2003)	74
SEER SUMMARY STAGE 1977	75
SEER SUMMARY STAGE 2000	75
NUMBER OF PRIMARIES	
FIRST MALIGNANT PRIMARY INDICATOR	76
STATE-COUNTY RECODE	76
SURVIVAL TIME RECODE	
CAUSE OF DEATH TO SEER SITE RECODE	
COD TO SITE REC KM	78
VITAL STATUS RECODE	78
IHS LINK	78
SUMMARY STAGE 2000 (1998+)	
AYA SITE RECODE	
LYMPHOMA SUBTYPE RECODE	
SEER CAUSE-SPECIFIC DEATH CLASSIFICATION	80
SEER OTHER CAUSE OF DEATH CLASSIFICATION	80
CS TUMOR SIZE EXT/EVAL	
CS LYMPH NODES EVAL	81
CS METS EVAL	
PRIMARY BY INTERNATIONAL RULES	
ER STATUS RECORD BREAST CANCER (1990+)	82
PR STATUS RECORD BREAST CANCER (1990+)	82
CS SCHEMA—AJCC 6 <sup>TH</sup> ED (PREVIOUSLY CALLED V1)	83
CS SITE-SPECIFIC FACTOR 8	85
CS SITE-SPECIFIC FACTOR 10	
CS SITE-SPECIFIC FACTOR 11	
CS SITE-SPECIFIC FACTOR 13	
CS SITE-SPECIFIC FACTOR 15	86
CS SITE-SPECIFIC FACTOR 16	87
LYMPH VASCULAR INVASION	87

Item Name	Applicable Years	NAACCR Item #	Positions	Length
Patient ID number		20	1-8	8
Registry ID		40	9-18	10
Marital Status at DX		150	19	1
Race/Ethnicity		160	20-21	2
Spanish/Hispanic Origin		190	22	1
NHIA Derived Hispanic Origin		191	23	1
Sex		220	24	1
Age at diagnosis		230	25-27	3
Year of Birth		240	28-31	4
Birth Place		250	32-34	3
Sequence Number—Central		380	35-36	2
Month of diagnosis		390	37-38	2
Year of diagnosis		390	39-42	4
Primary Site		400	43-46	4
Laterality		410	47	1
Histology (92-00) ICD-O-2		420	48-51	4
Behavior (92-00) ICD-O-2		430	52	1
Histologic Type ICD-O-3		522	53-56	4
Behavior Code ICD-O-3		523	57	1
Grade		440	58	1
Diagnostic Confirmation		490	59	1
Type of Reporting Source		500	60	1
EOD—Tumor Size	1988-2003	780	61-63	3
EOD—Extension	1988-2003	790	64-65	2
EOD—Extension Prost Path	1985-2003	800	66-67	2
EOD—Lymph Node Involv	1988-2003	810	68	1
Regional Nodes Positive	1988+	820	69-70	2
Regional Nodes Examined	1988+	830	71-72	2
EOD—Old 13 Digit	1973-1982	840	73-85	13
EOD—Old 2 Digit	1973-1982	850	86-87	2
EOD—Old 4 Digit	1983-1987	860	88-91	4
Coding System for EOD	1973-2003	870	92	1
Tumor Marker 1	1990-2003	1150	93	1
Tumor Marker 2	1990-2003	1160	94	1
Tumor Marker 3	1998-2003	1170	95	1
CS Tumor Size	2004+	2800	96-98	3
CS Extension	2004+	2810	99-101	3
CS Lymph Nodes	2004+	2830	102-104	3
CS Mets at Dx	2004+	2850	105-106	2
CS Site-Specific Factor 1	2004+	2880	107-109	3
CS Site-Specific Factor 2	2004+	2890	110-112	3

Item Name	Applicable Years	NAACCR Item #	Positions	Length
CS Site-Specific Factor 3	2004+	2900	113-115	3
CS Site-Specific Factor 4	2004+	2910	116-118	3
CS Site-Specific Factor 5	2004+	2920	119-121	3
CS Site-Specific Factor 6	2004+	2930	122-124	3
CS Site-Specific Factor 25	2004+	2879	125-127	3
Derived AJCC T	2004+	2940	128-129	2
Derived AJCC N	2004+	2960	130-131	2
Derived AJCC M	2004+	2980	132-133	2
Derived AJCC Stage Group	2004+	3000	134-135	2
Derived SS1977	2004+	3010	136	1
Derived SS2000	2004+	3020	137	1
Derived AJCC—Flag	2004+	3030	138	1
Derived SS1977—Flag	2004+	3040	139	1
Derived SS2000—Flag	2004+	3050	140	1
CS Version Input Original	2004+	2935	141-146	6
CS Version Derived	2004+	2936	147-152	6
CS Version Input Current	2004+	2937	153-158	6
RX Summ—Surg Prim Site	1998+	1290	159-160	2
RX Summ—Scope Reg LN Sur	2003+	1292	161	1
RX Summ—Surg Oth Reg/Dis	2003+	1294	162	1
RX Summ—Reg LN Examined	1998-2002	1296	163-164	2
RX Summ—Reconstruct 1 <sup>st</sup>	1998-2002	1330	165	1
Reason for no surgery		1340	166	1
RX Summ—Radiation		1360	167	1
RX Summ—Rad to CNS	1988-1997	1370	168	1
RX Summ—Surg / Rad Seq		1380	169	1
RX Summ—Surgery Type	1973-1997	1640	170-171	2
RX Summ—Surg Site 98-02	1998-2002	1646	172-173	2
RX Summ—Scope Reg 98-02	1998-2002	1647	174	1
RX Summ—Surg Oth 98-02	1998-2002	1648	175	1
SEER Record Number		2190	176-177	2
Over-ride age/site/morph		1990	178	1
Over-ride seqno/dxconf		2000	179	1
Over-ride site/lat/seqno		2010	180	1
Over-ride surg/dxconf		2020	181	1
Over-ride site/type		2030	182	1
Over-ride histology		2040	183	1
Over-ride report source		2050	184	1
Over-ride ill-define site		2060	185	1
Over-ride Leuk, Lymph		2070	186	1
Over-ride site/behavior		2071	187	1
Over-ride site/eod/dx dt		2072	188	1

# FIELD DESCRIPTIONS

Item Name	Applicable Years	NAACCR Item #	Positions	Length
Over-ride site/lat/eod		2073	189	1
Over-ride site/lat/morph		2074	190	1
SEER Type of Follow-up		2180	191	1
Age Recode <1 Year olds		N/A	192-193	2
Site Recode		N/A	194-198	5
Site Rec with Kaposi and Mesothelioma		N/A	199-203	5
Recode ICD-O-2 to 9		N/A	204-207	4
Recode ICD-O-2 to 10		N/A	208-211	4
ICCC site recode ICD-O-2		N/A	212-214	3
SEER modified ICCC site recode ICD-O-2		N/A	215-217	3
ICCC site recode ICD-O-3		N/A	218-220	3
ICCC site recode extended ICD-O-3		N/A	221-223	3
Behavior Recode for Analysis		N/A	224	1
Histology Recode—Broad Groupings		N/A	226-227	2
Histology Recode—Brain Groupings		N/A	228-229	2
CS Schema v0203		N/A	230-232	3
Race recode (White, Black, Other)		N/A	233	1
Race recode (W, B, AI, API)		N/A	234	1
Origin recode NHIA (Hispanic, Non-Hisp)		N/A	235	1
SEER historic stage A		N/A	236	1
AJCC stage 3 <sup>rd</sup> edition (1988-2003)		N/A	237-238	2
SEER modified AJCC Stage 3 <sup>rd</sup> ed (1988-2003)		N/A	239-240	2
SEER Summary Stage 1977 (1995-2000)	1995-2000	N/A	241	1
SEER Summary Stage 2000 (2001-2003)	2001-2003	N/A	242	1
Number of primaries		N/A	243-244	2
First malignant primary indicator		N/A	245	1
State-county recode		N/A	246-250	5
Survival time recode		N/A	251-254	4
Cause of Death to SEER site recode		N/A	255-259	5
COD to site rec KM		N/A	260-264	5
Vital Status recode		N/A	265	1
IHS Link		192	266	1
Summary stage 2000 (1998+)	1998+	N/A	267	1
AYA site recode		N/A	268-269	2
Lymphoma subtype recode		N/A	270-271	2
SEER Cause-Specific Death Classification		N/A	272	1
SEER Other Cause of Death Classification		N/A	273	1
CS Tumor Size/Ext Eval	2004+	2820	274	1
CS Lymph Nodes Eval	2004+	2840	275	1
CS Mets Eval	2004+	2860	276	1
Primary by international rules		N/A	277	1
ER Status Recode Breast Cancer (1990+)	1990+	N/A	278	1

Item Name	Applicable Years	NAACCR Item #	Positions	Length
PR Status Recode Breast Cancer (1990+)	1990+	N/A	279	1
CS Schema -AJCC 6th ed (previously called v1)		N/A	280-281	2
CS Site-Specific Factor 8	2004+	2862	282-284	3
CS Site-Specific Factor 10	2004+	2864	285-287	3
CS Site-Specific Factor 11	2004+	2865	288-290	3
CS Site-Specific Factor 13	2004+	2867	291-293	3
CS Site-Specific Factor 15	2004+	2869	294-296	3
CS Site-Specific Factor 16	2004+	2870	297-299	3
Lymph vascular invasion		1182	300	1

## PATIENT ID NUMBER

## NAACCR Item #: 20 SEER\*Stat Name: Patient ID Item Length: 8

*Field Description:* This field is used in conjunction with SEER registry to uniquely identify a person. One person can have multiple primaries but the same Patient ID. See the sequence number for more information about the primary. This is a dummy number and is not the number used by the registry to identify the patient. The same number is not used across all submissions for each patient.

#### **REGISTRY ID**

## NAACCR Item #: 40 SEER\*Stat Name: SEER Registry Item Length: 10

*Field Description:* A unique code assigned to each participating SEER registry. The number identifies the registry sending the record and what population the data are based on.

#### Codes

0000001501	San Francisco-Oakland SMSA (1973)
0000001502	Connecticut (1973)
0000001520	Metropolitan Detroit (1973)
0000001521	Hawaii (1973)
0000001522	Iowa (1973)
0000001523	New Mexico (1973)
0000001525	Seattle (Puget Sound) (1974)
0000001526	Utah (1973)
0000001527	Metropolitan Atlanta (1975)
0000001529	Alaska*
0000001531	San Jose-Monterey*
0000001535	Los Angeles*
0000001537	Rural Georgia*
0000001541	Greater California (excluding SF, Los Angeles & SJ)**
0000001542	Kentucky**
0000001543	Louisiana**
0000001544	New Jersey**
0000001547	Greater Georgia (excluding AT and RG)**
/	

(Year in parentheses refers to first diagnosis year data reported to SEER.)

\*Note: The incidence/yr1992\_2009.sj\_la\_rg\_ak directory files contain cases for Alaska, San Jose-Monterey, Los Angeles and Rural Georgia registries beginning in 1992. Cases have been collected by SEER for these registries prior to 1992 but have been excluded from the SEER Research Data file.

(Continued on next page)

(Continued from Registry ID)

\*\*Note: The incidence/yr2000\_2009.ca\_ky\_lo\_nj\_ga directory files contain cases for Greater California, Kentucky, Louisiana, New Jersey and Greater Georgia registries beginning in 2000. For the year 2005, only January through June diagnoses are included for Louisiana. The July through December incidence cases can be found in the yr2005.lo\_2<sup>nd</sup>\_half directory.

# MARITAL STATUS AT DX

# NAACCR Item #: 150 SEER\*Stat Name: Marital status at diagnosis Item Length: 1

*Field Description:* This data item identifies the patient's marital status at the time of diagnosis for the reportable tumor.

## Codes

1	Single (never married)
2	Married (including common law)
3	Separated
4	Divorced
5	Widowed
6	Unmarried or domestic partner (same sex or opposite sex or
	unregistered)
9	Unknown

# **RACE / ETHNICITY**

# NAACCR Item #: N/A SEER\*Stat Name: Race/ethnicity Item Length: 2

*Field Description:* Recode which gives priority to non-white races for persons of mixed races. Note that not all codes were in effect for all years.

# Codes

01	White
02	Black
03	American Indian, Aleutian, Alaskan Native or Eskimo (includes all indigenous populations of the Western hemisphere)
04	Chinese
05	Japanese
06	Filipino
07	Hawaiian
08	Korean (Effective with 1/1/1988 dx)
10	Vietnamese (Effective with $1/1/1988$ dx)
11	Laotian (Effective with 1/1/1988 dx)
12	Hmong (Effective with $1/1/1988 dx$ )
13	Kampuchean (including Khmer and Cambodian) (Effective with
	1/1/1988  dx)
14	Thai (Effective with $1/1/1994 dx$ )
15	Asian Indian or Pakistani, NOS (Effective with 1/1/1988 dx)
16	Asian Indian (Effective with $1/1/2010 dx$ )
17	Pakistani (Effective with 1/1/2010 dx)
20	Micronesian, NOS (Effective with 1/1/1991)
21	Chamorran (Effective with 1/1/1991 dx)
22	Guamanian, NOS (Effective with 1/1/1991 dx)
25	Polynesian, NOS (Effective with 1/1/1991 dx)
26	Tahitian (Effective with $1/1/1991 dx$ )
27	Samoan (Effective with 1/1/1991 dx)
28	Tongan (Effective with $1/1/1991 dx$ )
30	Melanesian, NOS (Effective with $1/1/1991 dx$ )
31	Fiji Islander (Effective with 1/1/1991 dx)
32	New Guinean (Effective with 1/1/1991 dx)
96	Other Asian, including Asian, NOS and Oriental, NOS
	(Effective with $1/1/1991 dx$ )
97	Pacific Islander, NOS (Effective with 1/1/1991 dx)
98	Other
99	Unknown

SEER Participants San Francisco, San Jose-Monterey, and Los Angeles are permitted to use codes 14 and 20-97 for cases diagnosed after January 1, 1987. Greater California is permitted to use codes 14 and 20-97 for cases diagnosed after January 1, 1988. Other SEER participants may choose to recode cases diagnosed prior to 1991 using 14 and 20-97 if all cases in the following race codes are reviewed: 96 Other Asian; 97 Pacific Islander, NOS; 98 Other; and 99 unknown.

# **SPANISH / HISPANIC ORIGIN**

## NAACCR item #: 190 SEER\*Stat Name: Spanish surname or origin Item Length: 1

*Field Description:* This data item is used to identify patients with Spanish/Hispanic surname or of Spanish origin. Persons of Spanish or Hispanic surname/origin may be of any race.

## Codes

0	Non-Spanish/Non-Hispanic
1*	Mexican (includes Chicano)
2*	Puerto Rican
3*	Cuban
4*	South or Central American (except Brazil)
5*	Other specified Spanish/Hispanic origin (includes European; excludes Dominican Republic)
6	Spanish, NOS; Hispanic, NOS; Latino, NOS ( <i>There is evidence, other than surname or maiden name, that the person is Hispanic but he/she cannot be assigned to any of the categories 1-5</i> ).
7**	Spanish surname only (effective with diagnosis on or after 1/1/1994) ( <i>The only evidence of the person's Hispanic origin is the surname or</i> <i>maiden name and there is no contrary evidence that the patient is</i> <i>not Hispanic.</i> )
8	Dominican Republic (effective with diagnosis on or after 1/1/2005)
9	Unknown whether Spanish/Hispanic or not

\*Note: Code began to be used for 1988+ diagnoses. For cases prior to 1988 it was only used if the person also had a diagnosis of an independent primary after 1987.

\*\*Note:Code began to be used for 1994+ diagnoses. For cases prior to 1994 it was only used if the person also had a diagnosis of an independent primary after 1993.

## NHIA DERIVED HISPANIC ORIGIN

## NAACCR Item #: 191 SEER\*Stat Name: NHIA Derived Hispanic Origin Item Length: 1

*Field Description:* The NAACCR Hispanic Identification Algorithm (NHIA) is a computerized algorithm that uses a combination of variables to directly or indirectly classify cases as Hispanic for analytic purposes.

## Codes

- 0 Non-Spanish-Hispanic-Latino
- 1 Mexican
- 2 Puerto Rican
- 3 Cuban
- 4 South or Central American excluding Brazil
- 5 Other specified Spanish/Hispanic Origin including Europe
- 6 Spanish/Hispanic/Latino, NOS
- 7 NHIA Surname Match Only
- 8 Dominican Republic

#### SEX

## NAACCR Item #: 220 SEER\*Stat Name: Sex Item Length: 1

Field Description: This data item identifies the sex of the patient at diagnosis.

#### Codes

1 Male

2 Female

## AGE AT DIAGNOSIS

## NAACCR Item #: 230 SEER\*Stat Name: Age at diagnosis Item Length: 3

*Field Description:* This data item represents the age of the patient at diagnosis **for this cancer**. The code is three digits and represents the patient's actual age in years.

#### Codes

000-130	Actual age in years
999	Unknown age

## **BIRTHDATE**—YEAR

## NAACCR Item #: 240 SEER\*Stat Name: Year of birth Item Length: 4

*Field Description:* The SEER dates on this file do not have the corresponding date flag included.

#### Codes

1850-YYYY	Patient's year of birth
Blank	Unknown year of birth

#### BIRTHPLACE

# NAACCR Item #: 250 SEER\*Stat Name: Place of birth Item Length: 3

*Field Description:* See the following link for a list of SEER birthplace codes and definitions. <u>http://seer.cancer.gov/manuals/2007/SPCSM\_2007\_AppendixB.pdf</u>

#### SEQUENCE NUMBER--CENTRAL

## NAACCR Item #: 380 SEER\*Stat Name: Sequence number Item Length: 2

*Field Description:* Sequence Number-Central describes the number and sequence of all reportable malignant, in situ, benign, and borderline primary tumors, which occur over the lifetime of a patient. The sequence number may change over the lifetime of the patient. If an individual previously diagnosed with a single reportable malignant neoplasm is subsequently diagnosed with a second reportable malignant neoplasm, the sequence code for the first neoplasm changes from 00 to 01.

This sequence number counts all tumors that were reportable in the year they were diagnosed even if the tumors occurred before the registry existed, or before the registry participated in the SEER Program. The purpose of sequencing based on the patient's *lifetime* is to truly identify the patients for survival analysis who only had one malignant primary in their lifetimes.

(Continued on next page)

# (Continued from SEQUENCE NUMBER-CENTRAL)

## Codes

## In Situ/Malignant as Federally Required based on Diagnosis Year

00	One primary only in the patient's lifetime
01	First of two or more primaries
02	Second of two or more primaries
	(Actual number of this primary)
41	Forty-first of forty-one or more primaries
99	Unspecified or unknown sequence number of Federally required in situ or malignant tumors. Sequence number 99 can be used if there is a malignant tumor and its sequence number is unknown. (If there is known to be more than one malignant tumor, then the tumors must be sequenced.)

## Non-malignant Tumor as Federally Required based on Diagnosis Year

60	Only one non-malignant tumor or central registry-defined neoplasm
61	First of two or more non-malignant tumors or central registry-defined neoplasms
62	Second of two or more non-malignant tumors or central registry-defined neoplasms
87	Twenty-seventh of twenty-seven
88	Unspecified or unknown sequence number of non-malignant tumor or central-registry defined neoplasms. (Sequence number 88 can be used if there is a non-malignant tumor and its sequence number is unknown. If there is known to be more than one non-malignant tumor, then the tumors must be sequenced.)

## MONTH OF DIAGNOSIS

## NAACCR Item #: 390 SEER\*Stat Name: Month of diagnosis Item Length: 2

*Field Description:* The month of diagnosis is the month the tumor was first diagnosed by a recognized medical practitioner, whether clinically or microscopically confirmed. For analysis purposes, months coded to 99 (unknown) have been replaced with values 01 through 12.

# $\frac{\text{Allowable values}}{\text{MM} = 01 - 12}$

## YEAR OF DIAGNOSIS

## NAACCR Item #: 390 SEER\*Stat Name: Year of diagnosis Item Length: 4

*Field Description:* The year of diagnosis is the year the tumor was first diagnosed by a recognized medical practitioner, whether clinically or microscopically confirmed.

 $\frac{\text{Allowable values}}{\text{YYYY} = 1973 - \text{forward}}$ 

#### PRIMARY SITE

## NAACCR Item #: 400 SEER\*Stat Name: Primary Site Item Length: 4

*Field Description:* This data item identifies the site in which the primary tumor originated. See the *International Classification of Diseases for Oncology*, Third Edition (ICD-O-3) for topography codes. The decimal point is eliminated.

Cases diagnosed 1977-1991 were coded using the *International Classification of Diseases for Oncology*, 1976 Edition (ICD-O-1976). Prior to 1977 diagnoses, cases were coded using the *Manual of Tumor Nomenclature and Coding*, 1968 (MOTNAC).

All cases 1973-1991 were machine-converted to ICD-O-2 codes without complete hand review.

# LATERALITY

## NAACCR Item #: 410 SEER\*Stat Name: Laterality (1973+) Item Length: 1

*Field Description:* Laterality describes the side of a paired organ or side of the body on which the reportable tumor originated. Starting with cases diagnosed January 1, 2004 and later, laterality is coded for select invasive, benign, and borderline primary intracranial and CNS tumors.

See <u>http://seer.cancer.gov/manuals/primsite.laterality.pdf</u> for a list of sites for which SEER requires information on laterality.

## Codes

- 0 Not a paired site
- 1 Right: origin of primary
- 2 Left: origin of primary
- 3 Only one side involved, right or left origin unspecified
- 4 Bilateral involvement, lateral origin unknown; stated to be single primary
  - Both ovaries involved simultaneously, single histology
  - Bilateral retinoblastomas
  - Bilateral Wilms's tumors
- 5 Paired site: midline tumor
- 9 Paired site, but no information concerning laterality; midline tumor

# HISTOLOGY (92-00) ICD-O-2

NAACCR Item #: 420 SEER\*Stat Name: Histology (92-00) ICD-O-2 Item Length: 4

*Field Description:* NOTE: ALL CASES DIAGNOSED 1973-91 HAVE BEEN CONVERTED TO THE *INTERNATIONAL CLASSIFICATION OF DISEASES FOR ONCOLOGY*, SECOND EDITION (ICD-O-2, 1992).

The SEER program has used several different, but related, coding systems for morphology over time. One should be extremely careful when doing any analysis of trends related to morphology. It is suggested that these analyses start with diagnoses no earlier than 1977 and that special attention be paid to the changes for 1986-91 cases due to the use of the *International Classification of Disease for Oncology, Field Trial Edition, March 1988* and for 1992+ cases due to the use of ICD-O-2.

Analyses of morphology data are usually limited to microscopically confirmed cases only.

(Continued on next page)

(Continued from HISTOLOGY (92-00) ICD-O-2)

# HISTOLOGY CODING

# FOR CASES DIAGNOSED 1973-85:

Histologic types are defined in the morphology section of the *International Classification of Diseases for Oncology*, 1976 Edition (ICD-O, 1976). However prior to the introduction of ICD-O, 1976, morphology was coded using the *Manual of Tumor Nomenclature and Coding*, 1968 (MOTNAC). With the introduction of ICD-O, 1976, all cases previously coded using MOTNAC were machine converted without hand review using the conversion table, *Conversion of Morphology Sections (neoplasms) of 1968 Manual of Tumor Nomenclature and Coding (MOTNAC) and 1965 Systematized Nomenclature of Pathology (SNOP) to 1976 International Classification of Diseases for Oncology*, developed by Constance Percy. The morphology codes of ICD-O, 1976, are more specific than those of MOTNAC. Thus, less detailed information on morphology is available for cases diagnosed 1973-76. For example, when using MOTNAC large cell carcinoma is included with carcinoma, not otherwise specified (NOS); when using ICD-O, 1976, large cell carcinoma is a separate entity having its own code. All have been machine converted to ICD-O-2.

# FOR CASES DIAGNOSED 1973-85:

In addition, the following special morphology codes were used by the SEER Program:

Breast — All years

8522/3	Infiltrating duct carcinoma and lobular carcinoma
8523/3	Infiltrating duct carcinoma and lobular carcinoma in situ
8524/3	Intraductal carcinoma and lobular carcinoma
8522/2	Intraductal carcinoma and lobular carcinoma in situ
8543/3	Paget's disease with intraductal carcinoma
<u>All sites –</u>	- Introduced for coding in approximately 1982
9616/3	Lennert's lymphoma
9624/3	Malignant lymphoma, large cell, cleaved, diffuse
9634/3	
	Malignant lymphoma, large cell, non-cleaved, diffuse

(Continued on next page)

(Continued from HISTOLOGY (92-00) ICD-O-2)

# FOR CASES DIAGNOSED 1986-91:

Histologic types are defined in the morphology section of the *International Classification of Diseases for Oncology, Field Trial Edition, 1986* (ICD-O FT). (This volume is no longer available. It was replaced by the *International Classification of Diseases for Oncology, Field Trial Edition, March 1988* (ICD-O FT 1988). Pages i-vi, 23 of the latter volume list the differences between the two Field Trials, present a summary of the changes to ICD-O, 1976, and define the symbols used in the morphology section. These were converted to ICD-O-2.

# FOR CASES DIAGNOSED 1992-2000:

Histologic types are defined in the morphology section of ICD-O-2. See pages 137+ in ICD-O-2 for additions and changes.

# FOR CASES DIAGNOSED AFTER 2000:

All cases diagnosed after 2000 were converted from ICD-O-3 to ICD-O-2.

# **BEHAVIOR (92-00) ICD-O-2**

## NAACCR Item #: 430 SEER\*Stat Name: Behavior code ICD-O-2 Item Length: 1

Field Description: Behavior codes are also defined in ICD-O-2, 1992.

Note: For bladder only, all in situs (/2) are converted to invasives (/3) before inclusion on this file.

Cervix in situ not required after 1995.

FOR CASES DIAGNOSED AFTER 2000:

All cases diagnosed after 2000 were converted from ICD-O-3 to ICD-O2.

## **HISTOLOGIC TYPE ICD-O-3**

# NAACCR Item #: 522 SEER\*Stat Name: Histologic Type ICD-O-3 Item Length: 4

*Field Description:* The data item Histologic Type describes the microscopic composition of cells and/or tissue for a specific primary. The tumor type or histology is a basis for staging and determination of treatment options. It affects the prognosis and course of the disease. The *International Classification of Diseases for Oncology*, Third Edition (ICD-O-3) is the standard reference for coding the histology for tumors diagnosed in 2001 and later.

All ICD-O-2 histologies for 1973-2000 were converted to ICD-O-3.

# **BEHAVIOR CODE ICD-O-3**

## NAACCR Item #: 523 SEER\*Stat Name: Behavior code ICD-O-3 (1973+) Item Length: 1

*Field Description:* SEER requires registries to collect malignancies with in situ /2 and malignant /3 behavior codes as described in ICD-O-3. SEER requires registries to collect benign /0 and borderline /1 intracranial and CNS tumors for cases diagnosed on or after 1/1/2004. Behavior is the fifth digit of the morphology code after the slash (/). See ICD-O-3 (page 66) for a discussion of the behavior code.

# Codes

0	Benign (Reportable for intracranial and CNS sites only)
÷	Uncertain whether benign or malignant, borderline malignancy, low
1	malignant potential, and uncertain malignant potential (Reportable for
	intracranial and CNS sites only)
2	Carcinoma in situ; intraepithelial; noninfiltrating; noninvasive
3	Malignant, primary site (invasive)

All ICD-O-2 behaviors for 1973-2000 were converted to ICD-O-3.

# GRADE

# NAACCR Item #: 440 SEER\*Stat Name: Grade Item Length: 1

*Field Description:* Grading and differentiation codes of 1-4, 9 are defined in ICD-O-2; 1992. Grade information may be incomplete for cases diagnosed before 1977.

In the early 1980's, additional codes specifying T-cell, B-cell, or null cell involvement in lymphomas and leukemias (histologies M9590-9940) were introduced by SEER. Because the reporting requirements and medical terminology have changed over time, care should be exercised when analyzing this information.

## Codes

1	Grade I; grade i; grade 1; well differentiated; differentiated, NOS
2	Grade II; grade ii; grade 2; moderately differentiated; moderately differentiated; intermediate differentiation
3	Grade III; grade iii; grade 3; poorly differentiated; differentiated
4	Grade IV; grade iv; grade 4; undifferentiated; anaplastic
5	T-cell; T-precursor
6	B-cell; Pre-B; B-Precursor
7	Null cell; Non T-non B;
8	N K cell (natural killer cell)
9	cell type not determined, not stated or not applicable

## **DIAGNOSTIC CONFIRMATION**

## NAACCR Item #: 490 SEER\*Stat Name: Diagnostic Confirmation Item Length: 1

*Field Description*: This data item records the best method used to confirm the presence of the cancer being reported. The data item is not limited to the confirmation at the time of diagnosis; it is the best method of confirmation during the entire course of the disease.

# Codes

Microscopically Confirmed

- 1 Positive histology
- 2 Positive cytology
- 4 Positive microscopic confirmation, method not specified

(Continued on next page)

# (Continued from DIAGNOSTIC CONFIRMATION)

Not Microscopically Confirmed

5	Positive laboratory test/marker study
6	Direct visualization without microscopic confirmation
7	Radiology and other imaging techniques without microscopic
	confirmation
8	Clinical diagnosis only (other than 5, 6, or 7)

# Confirmation Unknown

9	Unknown whether microscopically confirmed; death certificate
	only

# TYPE OF REPORTING SOURCE

# NAACCR Item #: 500 SEER\*Stat Name: Type of Reporting Source Item Length: 1

*Field Description:* The Type of Reporting Source identifies the source documents used to abstract the case. This is not necessarily the original document that identified the case; rather, it is the source that provided the best information.

## Codes

1	Hospital inpatient; Managed health plans with comprehensive, unified medical records
	(new code definition effective with diagnosis on or after 1/1/2006)

- 2 Radiation Treatment Centers or Medical Oncology Centers (hospital-affiliated or independent) (effective with diagnosis on or after 1/1/2006)
- 3 Laboratory Only (hospital-affiliated or independent)
- 4 Physician's Office/Private Medical Practitioner (LMD)
- 5 Nursing/Convalescent Home/Hospice
- 6 Autopsy Only
- 7 Death Certificate Only
- 8 Other hospital outpatient units/surgery centers (effective with diagnosis on or after 1/1/2006)

## **EOD**—TUMOR SIZE

# NAACCR Item #: 780 SEER\*Stat Name: EOD 10—size (1988-2003) Item Length: 3

*Field Description:* This item is part of the 10-digit EOD (Item #779). It records the largest dimension of the primary tumor in millimeters. Unknown size=999.

This field is only coded for cases diagnosed 1988-2003. See *SEER Extent of Disease, 1988: Codes and Coding Instructions*, Third Edition for site-specific codes and coding rules, at <a href="http://seer.cancer.gov/manuals/EOD10Dig.pub.pdf">http://seer.cancer.gov/manuals/EOD10Dig.pub.pdf</a>.

Note: For 2004+, similar type of information was collected in CS Tumor Size (2004+) in the collaborative stage variables.

#### **EOD**—EXTENSION

## NAACCR Item #: 790 SEER\*Stat Name: EOD 10—extent (1988-2003) Item Length: 2

*Field Description:* This item codes the farthest documented extension of tumor away from the primary site, either by contiguous extension or distant metastases. Allowable values = 00-99.

This field is only coded for cases diagnosed 1988-2003. See *SEER Extent of Disease, 1988: Codes and Coding Instructions*, Third Edition for site-specific codes and coding rules, at <a href="http://seer.cancer.gov/manuals/EOD10Dig.pub.pdf">http://seer.cancer.gov/manuals/EOD10Dig.pub.pdf</a>.

Note: For 2004+, similar type of information was collected in CS extension (2004+) and CS Mets at DX (2004+) in the collaborative stage variables.

#### EOD—EXTENSION PROST PATH

## NAACCR Item #: 800 SEER\*Stat Name: EOD 10—Prostate path ext (1995-2003) Item Length: 2

*Field Description:* This is an additional field for prostate cancer only to reflect information from radical prostatectomy, effective with 1995 diagnoses. The field is left blank for all other primaries. Allowable values = 00-99.

This field is only coded for prostate cases diagnosed 1995-2003. See *SEER Extent of Disease, 1988: Codes and Coding Instructions*, Third Edition for site-specific codes and coding rules, at <a href="http://seer.cancer.gov/manuals/EOD10Dig.pub.pdf">http://seer.cancer.gov/manuals/EOD10Dig.pub.pdf</a>.

Note: For 2004+, similar type of information was collected in CS SSF 3 in the collaborative stage variables.

## EOD-LYMPH NODE INVOLV

## NAACCR Item #: 810 SEER\*Stat Name: EOD 10—nodes (1988-2003) Item Length: 1

*Field Description:* This item records the highest specific lymph node chain that is involved by the tumor. Allowable values = 0-9.

This field is only coded for cases diagnosed 1988-2003. See SEER Extent of Disease, 1988: Codes and Coding Instructions, Third Edition for site-specific codes and coding rules, at <a href="http://seer.cancer.gov/manuals/EOD10Dig.pub.pdf">http://seer.cancer.gov/manuals/EOD10Dig.pub.pdf</a>.

Note: For 2004+, similar type of information was collected in CS Lymph Nodes (2004+) in the collaborative stage variables.

## **REGIONAL NODES POSITIVE**

## NAACCR Item #: 820 SEER\*Stat Name: Regional nodes positive (1988+) Item Length: 2

*Field Description:* Records the exact number of regional lymph nodes examined by the pathologist that were found to contain metastases.

## Codes

00	All nodes examined are negative
01-89	e
	Exact number of nodes positive
90	90 or more nodes are positive
95	Positive aspiration of lymph node(s) was performed
97	Positive nodes are documented, but number is unspecified
98	No nodes were examined
99	Unknown whether nodes are positive; not applicable; not
	stated in patient record

## **REGIONAL NODES EXAMINED**

# NAACCR Item #: 830 SEER\*Stat Name: Regional nodes examined (1988+) Item Length: 2

*Field Description:* Records the total number of regional lymph nodes that were removed and examined by the pathologist.

Codes	
00	No nodes were examined
01-89	Exact number of nodes examined
90	90 or more nodes were examined
95	No regional nodes were removed, but aspiration of regional nodes was performed
96	Regional lymph node removal was documented as a sampling, and the number of nodes is unknown/not stated
97	Regional lymph node removal was documented as a dissection, and the number of nodes is unknown/not stated
98	Regional lymph nodes were surgically removed, but the number of lymph nodes is unknown/not stated and not documented as a sampling or dissection; nodes were examined, but the number is unknown
99	Unknown whether nodes were examined; not applicable or negative; not stated in patient record

# EOD-OLD 13 DIGIT

NAACCR Item #: 840 SEER\*Stat Name: Expanded EOD(1) – Expanded EOD (13) Item Length: 13

*Field Description:* Detailed site-specific codes for EOD used by SEER for selected sites of cancer for tumors diagnosed 1973-1982, except death-certificate-only cases.

For details, reference the following website: http://seer.cancer.gov/manuals/historic/EOD 1977.pdf

# EOD-OLD 2 DIGIT

## NAACCR Item #: 850 SEER\*Stat Name: 2-Digit NS EOD / 2-Digit SS EOD Item Length: 2

*Field Description:* Site-specific codes for EOD used by SEER for tumors diagnosed from January 1, 1973, to December 31, 1982, for cancer sites that did not have a 13-digit scheme. For details, reference the following website: <u>http://seer.cancer.gov/manuals/historic/EOD\_1977.pdf</u>

# EOD-OLD 4 DIGIT

	860 : EOD 4 – size (first two digits) EOD 4 – extent (third digit) EOD 4 – nodes (fourth digit)
Item Length: 4	
Field Description	Codes for site-specific EOD used by SEER for tumors diagnosed from January 1, 1983 to December 31, 1987 for all cancer sites. For details, reference the following website: http://seer.cancer.gov/manuals/historic/EOD_1984.pdf

# CODING SYSTEM FOR EOD

NAACCR Item#: 870 SEER\*Stat Name: Coding system—EOD (1973-2003) Item Length: 1

*Field Description:* Indicates the type of SEER EOD code applied to the tumor.

## Codes

0	2-Digit Nonspecific Extent of Disease (1973-82)
1	2-Digit Site-Specific Extent of Disease (1973-82)
2	13-Digit (expanded) Site Specific Extent of Disease (1973-82)
3	4-Digit Extent of Disease (1983-87)
4	10-Digit Extent of Disease, 1988 (1988-2003)
Blank	EOD coding scheme not applicable for cases diagnosed
	2004+.

# **TUMOR MARKER 1**

## NAACCR Item #: 1150 SEER\*Stat Name: Tumor Marker 1 (1990-2003) Item Length: 1

*Field Description:* This data item records prognostic indicators for breast cases (ERA 1990-2003), prostate cases (PAP 1998-2003) and testis cases (AFP 1998-2003).

## Codes

0	None Done
1	Positive
2	Negative
3	Borderline; undetermined whether positive or negative
	positive or negative
8	Ordered, but results not in chart
9	Unknown or no information

## For Testicular Cancer Cases (AFP 1998-2003)

0	None Done (SX)
---	----------------

- 2 Within normal limits (S0)
- 4 Range 1 (S1) <1,000 ng/ml
- 5 Range 2 (S2) 1,000 10,000 ng/ml
- 6 Range 3 (S3) >10,000 ng/ml
- 8 Ordered, but results not in chart
- 9 Unknown or no information

## For All Other Cases

9 Not applicat	ble
----------------	-----

All sites except Breast diagnosed 1990-1997 are coded 9.

All diagnoses before January 1, 1990 are coded 9.

All diagnoses after 2003 are blank.

For Breast and Testis cases diagnosed 2004+, this information is collected using CS Site-Specific Factor 1 (NAACCR Item #2880). For Prostate cases diagnosed 2004+, information is no longer collected.

For breast cancer cases, ERA over time is available in ER Status Recode Breast Cancer (1990+).

# **TUMOR MARKER 2**

## NAACCR Item #: 1160 SEER\*Stat Name: Tumor Marker 2 (1990-2003) Item Length: 1

*Field Description:* This data item records prognostic indicators for breast cases (PRA 1990-2003), prostate cases (PSA 1998-2003), and testis cases (hCG 1998-2003).

# Codes

0	None Done
1	Positive
2	Negative
3	Borderline; undetermined whether
	positive or negative
8	Ordered, but results not in chart
9	Unknown or no information

For Testicular Cancer Cases (hCG 1998-2003)

None Done (SX)
Within normal limits (S0)
Range 1 (S1) <5,000 mlU/ml
Range 2 (S2) 5,000 – 50,000 mlU/ml
Range 3 (S3) to >50,000 mlU/ml
Ordered, but results not in chart
Unknown or no information

For All Other Cases

9 Not applicable

All sites except Breast diagnosed 1990-1997 are coded 9.

All diagnoses before January 1, 1990 are coded 9.

All diagnoses after 2003 are blank.

For Breast, Prostate and Testis cases diagnosed 2004+, this information is collected using CS Site-Specific Factor 2 (NAACCR Item #2890).

For breast cancer cases PRA over time is available in PR Status Recode Breast Cancer (1990+).

# **TUMOR MARKER 3**

# NAACCR Item #: 1170 SEER\*Stat Name: Tumor Marker 3 (1998-2003) Item Length: 1

*Field Description:* This data item records prognostic indicators for testis cases (LDH 1998-2003)

## Codes

0	None Done (SX)
2	Within normal limits (S0)
4	Range 1 (S1) <1.5 x upper limit of normal
	for LDH assay
5	Range 2 (S2) $1.5 - 10$ x upper limit of
	normal for LDH assay
6	Range 3 (S3) >10 x upper limit of normal
	for LDH assay
8	Ordered, results not in chart
9	Unknown or no information

All sites except testis diagnosed 1998-2003 are coded 9.

All diagnoses before 1998 are coded 9.

All diagnoses after 2003 are blank.

For Testis cases diagnosed 2004+, this information is collected using CS Site-Specific Factor 3 (NAACCR Item # 2900).

# **CS TUMOR SIZE**

## NAACCR Item #: 2800 SEER\*Stat Name: CS tumor size (2004+) Item Length: 3

Field Description: Information on tumor size. Available for 2004+. Earlier cases may be converted and new codes added which weren't available for use prior to the current version of CS. For more information, see http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage.

## Codes

000	Indicates no mass or no tumor found; for example, when a
	tumor of a stated primary site is not found, but the tumor has
	metastasized.
001-988	Exact size in millimeters
989	989 millimeters or larger
990	Microscopic focus or foci only; no size of focus is given
991	Described as less than 1 cm
992	Described as less than 2 cm
993	Described as less than 3 cm
994	Described as less than 4 cm
995	Described as less than 5 cm
996-998	Site-specific codes where needed
999	Unknown; size not stated; not stated in patient record
888	Not applicable

## **Examples:**

Examples.	
Mammogram shows 2.5 cm breast malignancy	Code as 025 (2.5 cm = 25 millimeters)
CT of chest shows 4 cm mass in RUL	Code as 040 (4 cm = 40 mm)
Thyroidectomy specimen yields 8 mm carcinoma	Code as 008
Prostate needle biopsy shows 0.6 mm carcinoma	Code as 001 (round up six-tenths of mm)

## **CS EXTENSION**

## NAACCR Item #: 2810 SEER\*Stat Name: CS extension (2004+) Item Length: 3

*Field Description*: Information on extension of the tumor. Available for 2004+. Earlier cases may be converted and new codes added which weren't available for use prior to the current version of CS. For more information, see http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage.

Note: This item was originally a 2-digit field and was expanded to 3 digits during conversion. Generally, a zero was added to the right of the existing 2-digit field, except for 99 which became 999.

## **CS LYMPH NODES**

## NAACCR Item #: 2830 SEER\*Stat Name: CS lymph nodes (2004+) Item Length: 3

*Field Description:* Information on involvement of lymph nodes. Available for 2004+. Earlier cases may be converted and new codes added which weren't available for use prior to the current version of CS. For more information, see <a href="http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage">http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage</a>.

Note: This item was originally a 2-digit field and was expanded to 3 digits during conversion. Generally, a zero was added to the right of the existing 2-digit field, except for 99 which became 999.

# CS METS AT DX

## NAACCR Item #: 2850 SEER\*Stat Name: CS mets at dx (2004+) Item Length: 2

*Field Description:* Information on distant metastasis. Available for 2004+. Earlier cases may be converted and new codes added which weren't available for use prior to the current version of CS. For more information, see <u>http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage</u>.

## **CS SITE-SPECIFIC FACTOR 1**

## NAACCR Item #: 2880 SEER\*Stat Name: CS site-specific factor 1 (2004+) Item Length: 3

*Field Description:* Each CS site-specific factor (SSF) is schema dependent. They can provide information needed to stage the case, clinically relevant information, or prognostic information. Available for varying years and schemas depending on standard setter requirements. Earlier cases may be converted and new codes added which weren't available for use prior to the current version of CS.

For more information, see <u>http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage</u>.

## **CS SITE-SPECIFIC FACTOR 2**

## NAACCR Item #: 2890 SEER\*Stat Name: CS site-specific factor 2 (2004+) Item Length: 3

*Field Description:* Each CS site-specific factor (SSF) is schema dependent. They can provide information needed to stage the case, clinically relevant information, or prognostic information. Available for varying years and schemas depending on standard setter requirements. Earlier cases may be converted and new codes added which weren't available for use prior to the current version of CS.

For more information, see <u>http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage</u>.

## **CS SITE-SPECIFIC FACTOR 3**

## NAACCR Item #: 2900 SEER\*Stat Name: CS site-specific factor 3 (2004+) Item Length: 3

*Field Description:* Each CS site-specific factor (SSF) is schema dependent. They can provide information needed to stage the case, clinically relevant information, or prognostic information. Available for varying years and schemas depending on standard setter requirements. Earlier cases may be converted and new codes added which weren't available for use prior to the current version of CS.

For more information, see <u>http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage</u>.

## **CS SITE-SPECIFIC FACTOR 4**

## NAACCR Item #: 2910 SEER\*Stat Name: CS site-specific factor 4 (2004+) Item Length: 3

*Field Description:* Each CS site-specific factor (SSF) is schema dependent. They can provide information needed to stage the case, clinically relevant information, or prognostic information. Available for varying years and schemas depending on standard setter requirements. Earlier cases may be converted and new codes added which weren't available for use prior to the current version of CS.

For more information, see <u>http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage</u>.

# **CS SITE-SPECIFIC FACTOR 5**

## NAACCR Item #: 2920 SEER\*Stat Name: CS site-specific factor 5 (2004+) Item Length: 3

*Field Description:* Each CS site-specific factor (SSF) is schema dependent. They can provide information needed to stage the case, clinically relevant information, or prognostic information. Available for varying years and schemas depending on standard setter requirements. Earlier cases may be converted and new codes added which weren't available for use prior to the current version of CS.

For more information, see <u>http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage</u>.

## **CS SITE-SPECIFIC FACTOR 6**

## NAACCR Item #: 2930 SEER\*Stat Name: CS site-specific factor 6 (2004+) Item Length: 3

*Field Description:* Each CS site-specific factor (SSF) is schema dependent. They can provide information needed to stage the case, clinically relevant information, or prognostic information. Available for varying years and schemas depending on standard setter requirements. Earlier cases may be converted and new codes added which weren't available for use prior to the current version of CS.

For more information, see <u>http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage</u>.

## CS SITE-SPECIFIC FACTOR 25

## NAACCR Item #: 2879 SEER\*Stat Name: CS site-specific factor 25 (2004+) Item Length: 3

*Field Description:* Each CS site-specific factor (SSF) is schema dependent. They can provide information needed to stage the case, clinically relevant information, or prognostic information. Available for varying years and schemas depending on standard setter requirements. Earlier cases may be converted and new codes added which weren't available for use prior to the current version of CS.

For more information, see <u>http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage</u>.

# **DERIVED AJCC-6 T**

#### NAACCR Item #: 2940 SEER\*Stat Name: Derived AJCC T, 6<sup>th</sup> ed (2004+) Item Length: 2

*Field Description:* This is the AJCC "T" component that is derived from CS coded fields, using the CS algorithm, effective with 2004+ diagnosis. See the CS site-specific schema for details (<u>http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage</u>).

99	ТХ
00	Т0
01	Та
05	Tis
06	Tispu (Urethra only)
07	Tispd (Urethra only)
10	T1
11	T1mic
19	T1 NOS
12	T1a
13	Tlal
14	T1a2
15	T1b
16	T1b1
17	T1b2
18	T1c
20	T2
29	T2 NOS
21	T2a
22	T2b
23	T2c
30	T3
39	T3 NOS
31	T3a
32	T3b
33	T3c
40	T4
49	T4 NOS
41	T4a
42	T4b
43	T4c
44	T4d
80	T1a NOS
81	T1b NOS
88	Not applicable

# **DERIVED AJCC-6 N**

#### NAACCR Item #: 2960 SEER\*Stat Name: Derived AJCC N, 6<sup>th</sup> ed (2004+) Item Length: 2

*Field Description:* This is the AJCC "N" component that is derived from CS coded fields, using the CS algorithm, effective with 2004+ diagnosis. See the CS site-specific schema for details (<u>http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage</u>).

99	NX
00	N0
01	N0(i-)
02	N0(i+)
03	N0(mol-)
04	N0(mol+)
10	N1
19	N1 NOS
11	Nla
12	N1b
13	N1c
18	N1mi
20	N2
29	N2 NOS
21	N2a
22	N2b
23	N2c
30	N3
39	N3 NOS
31	N3a
32	N3b
33	N3c
88	Not applicable

#### **DERIVED AJCC-6 M**

# **NAACCR Item #: 2980** SEER\*Stat Name: Derived AJCC M, 6<sup>th</sup> ed (2004+) Item Length: 2

Field Description: This is the AJCC "M" component that is derived from CS coded fields, using the CS algorithm, effective with 2004+ diagnosis. See the CS site-specific schema for details (http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage).

#### Codes

99	MX
00	M0
10	M1
11	M1a
12	M1b

- 13 M1c
- 19
- M1 NOS
- 88 Not applicable

#### **DERIVED AJCC-6 STAGE GRP**

#### NAACCR Item #: 3000 SEER\*Stat Name: Derived AJCC Stage Group, 6<sup>th</sup> ed (2004+) Item Length: 2

Field Description: This is the AJCC "Stage Group" component that is derived from CS detailed site-specific codes, using the CS algorithm, effective with 2004+ diagnosis. See the CS site-specific schema for details (http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage).

# Codes

00	Stage 0
01	Stage 0a
02	Stage 0is
10	Stage I
11	Stage I NOS
12	Stage IA
13	Stage IA1
14	Stage IA2
15	Stage IB
16	Stage IB1
17	Stage IB2
18	Stage IC
19	Stage IS
23	Stage ISA (lymphoma only)

(Continued from DERIVED AJCC-6 STAGE GRP)

24	Stage ISB (lymphoma only)	
20	Stage IEA (lymphoma only)	
21	Stage IEB (lymphoma only)	
22	Stage IE (lymphoma only)	
30	Stage II	
31	Stage II NOS	
32	Stage IIA	
33	stage IIB	
34	Stage IIC	
35	Stage IIEA (lymphoma only)	
36	Stage IIEB (lymphoma only)	
37	Stage IIE (lymphoma only)	
38	Stage IISA (lymphoma only)	
39	Stage IISB (lymphoma only)	
40	Stage IIS (lymphoma only)	
41	Stage IIESA (lymphoma only)	
42	Stage IIESB (lymphoma only)	
43	Stage IIES (lymphoma only)	
50	Stage III	
51	Stage III NOS	
52	Stage IIIA	
53	Stage IIIB	
54	Stage IIIC	
55	Stage IIIEA (lymphoma only)	
56	Stage IIIEB (lymphoma only)	
57	Stage IIIE (lymphoma only)	
58	Stage IIISA (lymphoma only)	
59	Stage IIISB (lymphoma only)	
60	Stage IIIS (lymphoma only)	
61	Stage IIIESA (lymphoma only)	
62	Stage IIIESB (lymphoma only)	
63	Stage IIIES (lymphoma only)	
	70 Stage IV	
	71 Stage IV NOS	
	72 Stage IVA	
73	0	
74	0	
88		
90	Stage Occult	
99	Stage Unknown	

#### **DERIVED SS1977**

#### NAACCR Item #: 3010 SEER\*Stat Name: Derived SS1977 (2004+) Item Length: 1

*Field Description:* This item is the derived "SEER Summary Stage 1977" from the CS algorithm, effective with 2004+ diagnosis.

#### Codes

- 0 In Situ
- 1 Localized
- 2 Regional, direct extension
- 3 Regional, lymph nodes only
- 4 Regional, extension and nodes
- 5 Regional, NOS
- 7 Distant
- 8 Not applicable
- 9 Unknown/Unstaged

#### **DERIVED SS2000**

#### NAACCR Item #: 3020 SEER\*Stat Name: Derived SS2000 (2004+) Item Length: 1

*Field Description:* This item is the derived "SEER Summary Stage 2000" from the CS algorithm, effective with 2004+ diagnosis.

- 0 In Situ
- 1 Localized
- 2 Regional, direct extension
- 3 Regional, lymph nodes only
- 4 Regional, extension and nodes
- 5 Regional, NOS
- 7 Distant
- 8 Not applicable
- 9 Unknown/Unstaged

# DERIVED AJCC-FLAG

# NAACCR Item #: 3030 SEER\*Stat Name: Derived AJCC—Flag (2004+) Item Length: 1

*Field Description:* Flag to indicate whether the derived AJCC stage was derived from CS or EOD codes.

#### Codes

1	AJCC Sixth Edition derived from Collaborative Staging Manual and Coding Instructions, Version 1.0
2	AJCC Sixth Edition derived from EOD (prior to 2004)
Blank	Not derived

#### DERIVED SS1977—FLAG

#### NAACCR Item #: 3040 SEER\*Stat Name: Derived SS1977—Flag (2004+) Item Length: 1

*Field Description:* Flag to indicate whether the derived SEER Summary Stage 1977 was derived from CS or EOD codes.

	SS1977 derived from Collaborative Staging Manual and
	Coding Instructions, Version 1.0
2	SS1977 derived from EOD (prior to 2004)
Blank	Not derived

#### DERIVED SS2000-FLAG

#### NAACCR Item #: 3050 SEER\*Stat Name: Derived SS2000—Flag (2004+) Item Length: 1

*Field Description:* Flag to indicate whether the derived SEER Summary Stage 2000 was derived from CS or EOD codes.

#### Codes

1	SS2000 derived from Collaborative Staging Manual and
	Coding Instructions, Version 1.0
2	SS2000 derived from EOD (prior to 2004)
Blank	Not derived

#### **CS VERSION INPUT ORIGINAL**

#### NAACCR Item #: 2935 SEER\*Stat Name: CS version input (2004+) Item Length: 6

*Field Description:* This item indicates the number of the version used to initially code CS fields. The first two digits represent the major version number; the second two digits represent minor version changes; and, the last two digits represent even less significant changes, such as corrections of typographical errors that do not affect coding or derivation of results.

This data item along with CS version input current gives info on what document to use for the CS codes. For more information, see <a href="http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage">http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage</a>.

#### **CS VERSION DERIVED**

#### NAACCR Item #: 2936 SEER\*Stat Name: CS version latest (2004+) Item Length: 6

*Field Description:* This item indicates the number of the version of the CS used most recently to derive the CS output fields. The first two digits represent the major version number; the second two digits represent minor version changes; and, the last two digits represent even less significant changes, such as corrections of typographical errors that do not affect coding or derivation of results.

# **CS VERSION INPUT CURRENT**

#### NAACCR Item #: 2937 SEER\*Stat Name: CS version input current (2004+) Item Length: 6

*Field Description:* This item indicates the number of the version of the CS after input fields have been updated or recoded. The first two digits represent the major version number; the second two digits represent minor version changes; and, the last two digits represent even less significant changes, such as corrections of typographical errors that do not affect coding or derivation of results.

This data item along with CS version input original gives info on what document to use for the CS codes. For more information, see <a href="http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage">http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage</a>.

# **RX SUMM—SURG PRIM SITE**

#### NAACCR Item #: 1290 SEER\*Stat Name: RX Summ--Surg Prim Site (1998+) Item Length: 2

*Field Description:* Surgery of Primary Site describes a surgical procedure that removes and/or destroys tissue of the primary site performed as part of the initial work-up or first course of therapy.

See Appendix C of the SEER Program Coding and Staging Manual 2007 with 2008 Revisions at <u>http://seer.cancer.gov/tools/codingmanuals/historical.html</u> for detailed codes and coding instructions.

#### **General Coding Structure**

00	None; no surgical procedure of primary site; diagnosed at autopsy only
10-19	Site-specific codes. Tumor destruction; no pathologic specimen or unknown whether there is a pathologic specimen
20-80	Site-specific codes. Resection; pathologic specimen
90	Surgery, NOS. A surgical procedure to the primary site was done, but no information on the type of surgical procedure is provided.
98	Special codes for hematopoietic, reticuloendothelial, immunoproliferative, myeloproliferative diseases; ill- defined sites; and unknown primaries (See site-specific codes for the sites and histologies), except death certificate only
99	Unknown if surgery performed; death certificate only

For diagnosis years 1998-2002, SEER registries were required to convert field RX Summ—Surg Site 98-02 (NAACCR Item #1646) to RX Summ—Surg Prim Site.

# **RX SUMM—SCOPE REG LN SUR**

#### NAACCR Item #: 1292 SEER\*Stat Name: RX Summ--Scope Reg LN Sur (2003+) Item Length: 1

*Field Description:* Scope of Regional Lymph Node Surgery describes the procedure of removal, biopsy, or aspiration of **regional** lymph nodes performed during the initial work-up or first course of therapy at all facilities.

Changed to Unknown or Not Applicable for breast cancer cases. See <u>http://seer.cancer.gov/seerstat/variables/seer/regional\_ln/</u> for more information.

#### Codes

0	No regional lymph nodes removed or aspirated; diagnosed
	at autopsy.
1	Biopsy or aspiration of regional lymph node, NOS
2	Sentinel lymph node biopsy [only]
3	Number of regional lymph nodes removed unknown, not
	stated; regional lymph nodes removed, NOS
4	1 to 3 regional lymph nodes removed
5	4 or more regional lymph nodes removed
6	Sentinel node biopsy and code 3, 4, or 5 at same time or
	timing not noted
7	Sentinel node biopsy and code 3, 4, or 5 at different times
9	Unknown or not applicable; death certificate only

#### **RX SUMM-SURG OTH REG/DIS**

#### NAACCR Item #: 1294 SEER\*Stat Name: RX Summ--Surg Oth Reg/Dis (2003+) Item Length: 1

*Field Description:* Surgical procedure of Other Site describes the surgical removal of distant lymph node(s) or other tissue(s) or organ(s) beyond the primary site.

- 0 None; diagnosed at autopsy
- 1 Nonprimary surgical procedure performed
- 2 Nonprimary surgical procedure to other regional sites
- 3 Non-primary surgical procedure to distant lymph node(s)
- 4 Nonprimary surgical procedure to distant site
- 5 Combination of codes 2, 3, or 4
- 9 Unknown; death certificate only

# **RX SUMM-REG LN EXAMINED**

#### NAACCR Item #: 1296 SEER\*Stat Name: Num of regional lym nd exam (1998-2002) Item Length: 2

*Field Description:* This data item records the number of regional lymph nodes examined in conjunction with surgery performed as part of the first course of treatment at all facilities. This item is only available for cases diagnosed 1998-2002.

#### Codes

00	No regional lymph nodes examined
01	One regional lymph node examined
02	Two regional lymph nodes examined
	(Actual number of lymph nodes examined)
90	90 or more regional lymph nodes examined
95	No regional lymph nodes examined
96	Regional lymph node removal documented as sampling, and number of lymph nodes unknown/not stated
97	Regional lymph node removal documented as dissection, and number of lymph nodes unknown/not stated
98	Regional lymph nodes surgically removed, but number of lymph nodes unknown/not stated and not documented as sampling or dissection
99	Unknown; not stated; death certificate-only

# **RECONSTRUCTION-FIRST COURSE (1998-2002)**

#### NAACCR Item #: 1330 SEER\*Stat Name: First course of reconstruct (1998-2002) Item Length: 1

*Field Description:* The SEER program collects information in this field only for breast cancer and only for reconstruction begun as part of first course of treatment. This item is only available for diagnosis years 1998-2002.

0	No reconstruction/restoration
1	Reconstruction, NOS (unknown if flap)
2	Implant; reconstruction WITHOUT flap
3	Reconstruction WITH flap, NOS
4	Latissimus dorsi flap
5	Abdominus recti flap
6	Flap, NOS plus implant
7	Latissimus dorsi flap plus implant
8	Abdominus recti plus implant
9	Unknown; not stated; death certificate only

# **REASON FOR NO SURGERY**

# NAACCR Item #: 1340 SEER\*Stat Name: Reason no cancer-directed surgery Item Length: 1

*Field Description:* This data item documents the reason that surgery was not performed on the primary site.

#### Codes

0 Surgery performed

No surgery

1*	Surgery not recommended
2*	Contraindicated due to other conditions; Autopsy Only case
5	Patient died before recommended surgery
6	Unknown reason for no surgery
7*	Patient or patient's guardian refused

Unknown if surgery performed

8	Recommended, unknown if done
9	Unknown if surgery performed; Death Certificate Only case

\*Codes not used prior to 1988. Code '2' used only for Autopsy Only cases prior to 1988.

#### **RX SUMM—RADIATION**

#### NAACCR Item #: 1360 SEER\*Stat Name: Radiation Item Length: 1

*Field Description:* This data item indicates the method of radiation therapy performed as part of the first course of treatment.

#### Codes

0 None; diagnosed at autopsy 1 Beam radiation 2 Radioactive implants 3 Radioisotopes 4 Combination of 1 with 2 or 3 5 Radiation, NOS - method or source not specified 6 Other radiation (1973-1987 cases only) 7 Patient or patient's guardian refused radiation therapy 8 Radiation recommended, unknown if administered 9 Unknown if radiation administered

#### **RX SUMM—RAD TO CNS**

#### NAACCR Item #: 1370 SEER\*Stat Name: Radiation to Brain or CNS (1988-1997) Item Length: 1

*Field Description:* This variable was only collected for years 1988-1997 for lung and leukemia cases only. This data item codes for radiation given to the brain or central nervous system at all facilities as part of the first course of therapy.

0	None
1	Radiation
7	Refused
8	Recommended, unknown if administered
9	Unknown

# RX SUMM—SURG/RAD SEQ

#### NAACCR Item #: 1380 SEER\*Stat Name: Radiation sequence with surgery Item Length: 1

*Field Description:* This field records the order in which surgery and radiation therapies were administered for those patients who had **both surgery and radiation**.

#### Codes

0	No radiation and/or surgery as defined above
2	Radiation before surgery
3	Radiation after surgery
4	Radiation both before and after surgery
5	Intraoperative radiation therapy
6	Intraoperative radiation with other radiation
	given before or after surgery
9	Sequence unknown, but both surgery and
	radiation were given

# **RX SUMM-SURG TYPE**

#### NAACCR Item #: 1640 SEER\*Stat Name: Site specific surgery (1983-1997) Item Length: 2

*Field Description:* The actual coding schemes for individual sites and time periods can be viewed at <u>http://seer.cancer.gov/manuals/historic/AppendD.pdf</u>. The discussion below summarizes the information available by site and time period.

This field specifies information on surgery during first course of therapy whether it was cancer-directed or not. (Prior to 1988 SEER did not collect information on surgical procedures if not cancer-directed.) The Reason for No Cancer-directed Surgery field must be used to distinguish among no cancer-directed surgery performed; cancer-directed surgery recommended, unknown if performed; and unknown if cancer-directed surgery performed.

#### FOR CASES DIAGNOSED 1973-82:

All cases were coded using the following nonspecific scheme:

No Cancer-Directed Surgery/Unknown<sup>1</sup>

00 No surgical procedure09 Unknown if surgery done

(Continued from RX SUMM-SURG TYPE)

Type of Cancer-Directed Surgery

90 Surgery, NOS

<sup>1</sup>Code '09' must be used in conjunction with Reason for No Cancer-directed Surgery to distinguish "No cancer directed surgery" from "Unknown if cancer-directed surgery performed" and "Cancer-directed surgery recommended but unknown if given." Code '00' is only used for cases diagnosed only at autopsy.

# FOR CASES DIAGNOSED 1983-87:

Detailed schemes were in place for the following sites:

ICD-O Codes	Primary Site
.C16.0-C16.9	Stomach
C18.0-C18.9	Colon
C19.9, C20.9	Rectosigmoid, Rectum
C34.0-C34.9	Bronchus and Lung
C44.0-C44.9	Skin (melanomas only)
C50.0-C50.9	Breast
C53.0-C53.9	Cervix Uteri
C54.0-C54.9	Corpus Uteri
C56.9	Ovary
C61.9	Prostate
C67.0-C67.9	Bladder
C64.9, C65.9, C66.9	Kidney, Renal Pelvis, Ureter

All other sites are coded to the same nonspecific scheme used for 1973-82 cases (above).

# FOR CASES DIAGNOSED 1988-1997:

In addition to the above sites, detailed schemes for the following sites were put into place:

ICD-O Codes	Primary Site
.C00.0-C14.8	Oral Cavity
C25.0-C25.9	Pancreas
C32.0-C32.9	Larynx
C42.2	Spleen
C41.0-C41.9	Connective tissue
C47.0-C47.9,C49.0-C49.9	Bone
C62.0-C62.9	Testis
C73.9	Thyroid
C77.0-C77.9	Lymph nodes

A general scheme was used for all other sites. (Continued on next page)

(Continued from RX SUMM-SURG TYPE)

#### FOR CASES DIAGNOSED 1998-2002:

Surgery information is collected in fields:

RX Summ—Surg Site 98-02 (NAACCR Item #1646) RX Summ—Scope Reg 98-02 (NAACCR Item #1647) RX Summ—Surg Oth 89-02 (NAACCR Item #1648

#### FOR CASES DIAGNOSED 2003+

Surgery information is collected in fields:

RX Summ—Surg Prim Site (NAACCR Item #1290) RX SUmm—Scope Reg LN Sur (NAACCR Item #1292) RX Summ—Surg Oth Reg/Dis (NAACCR Item #1294)

#### RX SUMM—SURG SITE 98-02

#### NAACCR Item #: 1646 SEER\*Stat Name: Surgery of primary site (1998-2002) Item Length: 2

*Field Description:* Site-specific codes for the type of surgery to the primary site performed as part of the first course of treatment at all facilities for cases diagnosed 1998-2002.

See <u>http://seer.cancer.gov/manuals/historic/AppendC.pdf</u> for a list of valid codes.

#### RX SUMM—SCOPE REG 98-02

#### NAACCR Item #: 1647 SEER\*Stat Name: Scope of reg lymph nd surg (1998-2002) Item Length: 1

*Field Description:* This field describes the removal, biopsy or aspiration of regional lymph node(s) at the time of surgery of the primary site or during a separate surgical event at all facilities for cases diagnosed 1998-2002.

Changed to Unknown or Not Applicable for breast cancer cases. See <u>http://seer.cancer.gov/seerstat/variables/seer/regional\_ln/</u> for more information.

See <u>http://seer.cancer.gov/manuals/historic/AppendC.pdf</u> for a list of valid codes.

#### RX SUMM—SURG OTH 98-02

#### NAACCR Item #: 1648 SEER\*Stat Name: Surgery of oth reg/dis sites (1998-2002) Item Length: 1

*Field Description:* This field records the removal of distant lymph nodes or other tissue(s)/organ(s) beyond the primary site given at all facilities as part of the first course of treatment for cases diagnosed 1998-2002.

See <u>http://seer.cancer.gov/manuals/historic/AppendC.pdf</u> for a list of valid codes.

#### **SEER RECORD NUMBER**

#### NAACCR Item #: 2190 SEER\*Stat Name: Record number Item Length: 2

*Field Description:* The Record Number is a unique sequential number. The highest number for each patient identifies the number of records that have been submitted to SEER for that particular patient. This data item is helpful in record linkage. The record number is generated by the computer system for each SEER submission. The record numbers are sequential starting with the number 01.

#### Codes

01 02	First (or only) record for the person Second record for the person
nn	Last of nn records for person

#### **OVER-RIDE AGE/SITE/MORPH**

#### NAACCR Item #: 1990 SEER\*Stat Name: Age-site edit override Item Length: 1

#### Field Description: Codes

blank	Not reviewed
1	Reviewed and confirmed that age/site/histology combination is correct as coded
	combination is correct as coded
2	Reviewed and confirmed that case was diagnosed in
	utero
3	Reviewed and confirmed that conditions 1 and 2
	apply

#### **OVER-RIDE SEQNO/DXCONF**

#### NAACCR Item #: 2000 SEER\*Stat Name: Sequence number-dx conf override Item Length: 1

*Field Description:* Codes

blank	Not reviewed
1	Reviewed: Multiple primaries of special sites in
	which at least one diagnosis has not been
	microscopically confirmed have been reviewed.

#### **OVER-RIDE SIT/LAT/SEQNO**

#### NAACCR Item #: 2010 SEER\*Stat Name: Site-type-lat-seq override Item Length: 1

*Field Description:* Codes

blank	Not reviewed
1	Reviewed: Multiple primaries of the same histology (3
	digit) in the same primary site group have been reviewed.

#### **OVER-RIDE SURG/DXCONF**

# NAACCR Item #: 2020 SEER\*Stat Name: Surgery-diagnostic conf override Item Length: 1

*Field Description:* Codes

	Not reviewed
1	Reviewed: A patient who had (cancer-directed) surgery, but the tissue removed was not sufficient for microscopic confirmation.

#### **OVER-RIDE SITE/TYPE**

#### NAACCR Item #: 2030 SEER\*Stat Name: Site-type edit override Item Length: 1

Field Description: Codes

blank	Not Reviewed
1	Reviewed: The coding of an unusual combination of
	primary site and histologic type has been reviewed.

#### **OVER-RIDE HISTOLOGY**

#### NAACCR Item #: 2040 SEER\*Stat Name: Histology edit override Item Length: 1

Field Description: Codes

blank	Not Reviewed
1	Unusual Histology behavior combination reviewed.
2	Unusual Diagnostic Confirmation/Behavior combination reviewed.
3	Both scenarios above reviewed

#### **OVER-RIDE REPORT SOURCE**

#### NAACCR Item #: 2050 SEER\*Stat Name: Report source sequence override Item Length: 1

Field Description: Codes

blank	Not reviewed
1	Reviewed: A second or subsequent primary with a reporting source
	of death certificate only has been reviewed and is indeed an
	independent primary.

#### **OVER-RIDE ILL-DEFINE SITE**

NAACCR Item #: 2060 SEER\*Stat Name: Seq-ill-defined site override Item Length: 1

*Field Description:* Codes

blank	Not reviewed
	Reviewed: A second or subsequent primary reported with an ill-defined primary site (C76.0-C76.8, C80.9) has been reviewed and is an independent primary.

#### **OVER-RIDE LEUK, LYMPHOMA**

#### NAACCR Item #: 2070 SEER\*Stat Name: Leuk-Lymph dx confirmation override Item Length: 1

Field Description:

Codes

blank	Not reviewed
1	Reviewed: A patient was diagnosed with leukemia or
	lymphoma and the diagnosis was not microscopically confirmed.

#### **OVER-RIDE SITE/BEHAVIOR**

#### NAACCR Item #: 2071 SEER\*Stat Name: Site-behavior override Item Length: 1

*Field Description:* The IF39 edit does not allow in situ cases of nonspecific sites, such as gastrointestinal tract, NOS; uterus, NOS; female genital tract, NOS; male genital organs, NOS; and others. This over-ride indicates that the conflict has been reviewed.

#### Codes

blank	Not reviewed
1	Reviewed: A patient has an in situ cancer of a nonspecific site
	and no further information about the primary site is available.

#### **OVER-RIDE SITE/EOD/DX DT**

#### NAACCR Item #: 2072 SEER\*Stat Name: Site-EOD-dx date override Item Length: 1

*Field Description:* The IF40 edit does not allow "localized" disease with non-specific sites, such as mouth, NOS; colon, NOS (except histology 8220); bone, NOS; female genital system, NOS; male genital organs, NOS; and others. This over-ride indicates that the conflict has been reviewed.

blank	Not reviewed
1	Reviewed: A patient had "localized" disease with a non-specific
	site and no further information about the primary site is available.

#### **OVER-RIDE SITE/LAT/EOD**

#### NAACCR Item #: 2073 SEER\*Stat Name: Site-laterality-EOD override Item Length: 1

*Field Description:* The IF41 edit for paired organs does not allow EOD to be specified as in situ, localized, or regional by direct extension if laterality is coded as "bilateral, side unknown" or "laterality unknown." This over-ride indicates that the conflict has been reviewed.

#### Codes

blank	Not reviewed
1	Reviewed: A patient had laterality coded non-specifically and
	EOD coded specifically.

#### **OVER-RIDE SITE/LAT/MORPH**

#### NAACCR Item #: 2074 SEER\*Stat Name: Site-laterality-morph override Item Length: 1

*Field Description:* The IF42 edit does not allow behavior code of "in situ" with non-specific laterality codes. This over-ride indicates that the conflict has been reviewed.

blank	Not reviewed
1	Reviewed: A patient had behavior code of "in situ" and laterality is not stated as right: origin of primary; left: origin of primary; or only one side involved, right or left origin not specified.

#### SEER TYPE OF FOLLOW-UP

#### NAACCR Item #: 2180 SEER\*Stat Name: Type of follow-up expected Item Length: 1

Field Description: This item codes the type of follow-up expected for a SEER case.

#### Codes

	"Autopsy Only" or "Death Certificate Only" case
2	Active follow up case
3	In situ cancer of the cervix uteri only

- 4 Case not originally in active follow up, but in active follow
- up now (San Francisco-Oakland only)

# AGE RECODE <1 YEAR OLDS

#### NAACCR Item #: N/A SEER\*Stat Name: Age recode with <1 year olds Item Length: 2

*Field Description*: The age recode variable is based on Age at Diagnosis (single-year ages). The groupings used in the age recode variable are determined by the age groupings in the population data. This recode has 19 age groups in the age recode variable (< 1 year, 1-4 years, 5-9 years, ..., 85+ years).

00	Age 00
----	--------

- 02 Ages 05-09
- 03 Ages 10-14
- 04 Ages 15-19
- 05 Ages 20-24
- 06 Ages 25-29
- 07 Ages 30-34
- 08 Ages 35-39
- 09 Ages 40-44
- 10 Ages 45-49
- 11 Ages 50-54
- 12 Ages 55-59
- 13 Ages 60-64
- 14 Ages 65-69
- 15 Ages 70-74
- 16 Ages 75-79
- 17 Ages 80-84
- 18 Ages 85+
- 99 Unknown Age

#### SITE RECODE

#### NAACCR Item #: N/A SEER\*Stat Name: Site recode Item Length: 5

*Field Description:* A recode based on Primary Site and ICD-O-3 Histology in order to make analyses of site/histology groups easier. For example, the lymphomas are excluded from stomach and included with Lymphoma.

Note: In this recode, Kaposi and mesothelioma are not separate categories based on histology. To match the site groupings in the CSR, do NOT use this recode -- use 'Site rec with Kaposi and mesothelioma'. For more information, see <u>http://seer.cancer.gov/siterecode/icdo3\_d01272003</u>.

#### SITE RECODE WITH KAPOSI SARCOMA AND MESOTHELIOMA

NAACCR Item #: N/A SEER\*Stat Name: Site rec with Kaposi and mesothelioma Item Length: 5

*Field Description:* A recode based on Primary Site and ICD-O-3 Histology in order to make analyses of site/histology groups easier. For example, the lymphomas are excluded from stomach and Kaposi and mesothelioma are separate categories based on histology. For more information, see <u>http://seer.cancer.gov/siterecode/icdo3\_d01272003</u>.

#### **RECODE ICD-O-2 TO 9**

#### NAACCR Item #: N/A SEER\*Stat Name: Recode ICD-O-2 to 9 Item Length: 4

Field Description: The primary site and morphology are recoded to ICD-9 codes using the Conversion of Malignant Neoplasms by Topography and Morphology from the International Classification of Disease for Oncology, Second Edition (ICD-0-2) to International Classification of Diseases, 9th Revision (ICD-9) and the International Classification of Diseases, 9th Revision, Clinical Modification, Fourth Edition (ICD-9-CM) 4th Ed., 1992 edited by Constance Percy. All tumors not originally coded in ICD-0-2 were first converted from ICD-0-1 or ICD-0-3 and then converted to ICD-9.

#### **RECODE ICD-O-2 TO 10**

NAACCR Item #: N/A SEER\*Stat Name: Recode ICD-O-2 to 10 Item Length: 4

*Field Description:* The primary site and morphology are converted to ICD-10 codes using the *Conversion of Malignant Neoplasms by Topography and Morphology from the International Classification of Disease for Oncology, Second Edition (ICD-O-2) to International Classification of Diseases and Related Health Problems, 10th Revision, 1998 edited by Constance Percy. All tumors not* originally coded in ICD-O-2 were first converted from ICD-O-1 or ICD-O-3 and then converted to ICD-10.

#### **ICCC SITE RECODE ICD-O-2**

#### NAACCR Item #: N/A SEER\*Stat Name: ICCC site recode ICD-O-2 Item Length: 3

*Field Description:* A site/histology recode based on the International Classification of Childhood Cancer (ICCC) is mainly used to analyze data on children. The recode was applied to all cases no matter the age in order that age comparisons can be made with these groupings. Based on ICD-O-2. Note that cases diagnosed before 1992 were not coded under ICD-O-2 and were converted to ICD-O-2 and may not have the specificity of cases after 1991 that were coded directly under ICD-O-2 or 3. For more information on this site recode, see http://seer.cancer.gov/iccc.

#### SEER MODIFIED ICCC SITE RECODE ICD-O-2

#### NAACCR Item #: N/A SEER\*Stat Name: SEER modified ICCC site recode ICD-O-2 Item Length: 3

*Field Description:* A site/histology recode based on the International Classification of Childhood Cancer (ICCC) with slight modifications is mainly used to analyze data on children. The recode was applied to all cases no matter the age in order that age comparisons can be made with these groupings. Based on ICD-O-2. Note that cases diagnosed before 1992 were not coded under ICD-O-2 and were converted to ICD-O-2 and may not have the specificity of cases after 1991 that were coded directly under ICD-O-2 or 3. For more information on this site recode, see <u>http://seer.cancer.gov/iccc</u>.

#### **ICCC SITE RECODE ICD-O-3**

#### NAACCR Item #: N/A SEER\*Stat Name: ICCC site recode ICD-O-3 Item Length: 3

*Field Description:* A site/histology recode that is mainly used to analyze data on children. The recode was applied to all cases no matter the age in order that age comparisons can be made with these groupings. Based on ICD-O-3. Note that cases diagnosed before 2001 were not coded under ICD-O-3 and were converted to ICD-O-3 and may not have the specificity of cases after 2000 that were coded directly under ICD-O-3. For more information on this International Classification of Childhood Cancer (ICCC) site recode, see <a href="http://seer.cancer.gov/iccc">http://seer.cancer.gov/iccc</a>.

#### **ICCC SITE RECODE EXTENDED ICD-O-3**

#### NAACCR Item #: N/A SEER\*Stat Name: ICCC site recode extended ICD-O-3 Item Length: 3

*Field Description:* Based on ICD-O-3. For more information on this International Classification of Childhood Cancer (ICCC) site/histology recode, see <u>http://seer.cancer.gov/iccc</u>. While the recode is normally used for childhood cancers, it is on the file for all ages so that childhood cancers could be compared across age groups.

#### **BEHAVIOR RECODE FOR ANALYSIS**

# NAACCR Item #: N/A SEER\*Stat Name: Behavior recode for analysis Item Length: 1

*Field Description*: This recode was created so that data analyses could eliminate major groups of histologies/behaviors that weren't collected consistently over time, for example benign brain, myelodyplastic syndromes, and borderline tumors of the ovary. Created from ICD-O-3 behavior and histology. For more information, see <a href="http://seer.cancer.gov/behavrecode">http://seer.cancer.gov/behavrecode</a>.

- 0 Benign
- 1 Borderline malignancy
- 2 In situ
- 3 Malignant
- 4 Only malignant in ICD-O-3
- 5 No longer reportable in ICD-O-3

# HISTOLOGY RECODE—BROAD GROUPINGS

### NAACCR Item #: N/A SEER\*Stat Name: Histology recode - broad groupings Item Length: 2

Field Description: Based on Histologic Type ICD-O-3.

# Codes

00	8000-8009 : unspecified neoplasms
01	8010-8049 : epithelial neoplasms, NOS
02	8050-8089 : squamous cell neoplams
03	8090-8119 : basal cell neoplams
04	8120-8139 : transitional cell papillomas and carcinomas
05	8140-8389 : adenomas and adenocarcinomas
06	8390-8429 : adnexal and skin appendage neoplams
07	8430-8439 : mucoepidermoid neoplasms
08	8440-8499 : cystic, mucinous and serous neoplams
09	8500-8549 : ductal and lobular neoplams
10	8550-8559 : acinar cell neoplasms
11	8560-8579 : complex epithelial neoplams
12	8580-8589 : thymic epithelial neoplams
13	8590-8679 : specialized gonadal neoplams
14	8680-8719 : paragangliomas and glumus tumors
15	8720-8799 : nevi and melanomas
16	8800-8809 : soft tissue tumors and sarcomas, NOS
17	8810-8839 : fibromatous neoplasms
18	8840-8849 : myxomatous neoplasms
19	8850-8889 : lipomatous neoplasms
20	8890-8929 : myomatous neoplasms
21	8930-8999 : complex mixed and stromal neoplasms
22	9000-9039 : fibroepithelial neoplasms
23	9040-9049 : synovial-like neoplasms
24	9050-9059 : mesothelial neoplasms
25	9060-9099 : germ cell neoplasms
26	9100-9109 : trophoblastic neoplasms
27	9110-9119 : mesonephromas
28	9120-9169 : blood vessel tumors
29	9170-9179 : lymphatic vessel tumors

# (Continued from HISTOLOGY RECODE-BROAD GROUPINGS)

- 30 9180-9249 : osseous and chondromatous neoplasms
- 31 9250-9259 : giant cell tumors
- 32 9260-9269 : miscellaneous bone tumors (C40.\_,C41.\_)
- 33 9270-9349 : odontogenic tumors ( C41.\_)
- 34 9350-9379 : miscellaneous tumors
- 35 9380-9489 : gliomas
- 36 9490-9529 : neuroepitheliomatous neoplasms
- 37 9530-9539: meningiomas
- 38 9540-9579 : nerve sheath tumors
- 39 9580-9589 : granular cell tumors & alveolar soft part sarcomas
- 40 9590-9599 : malignant lymphomas, NOS or diffuse
- 41 9650-9669 : hodgkin lymphomas
- 42 9670-9699 : nhl mature b-cell lymphomas
- 43 9700-9719 : nhl mature t and nk-cell lymphomas
- 44 9720-9729 : nhl precursor cell lymphoblastic lymphoma
- 45 9730-9739 : plasma cell tumors
- 46 9740-9749 : mast cell tumors
- 47 9750-9759 : neoplasms of histiocytes and accessory lymphoid cells
- 48 9760-9769 : immunoproliferative diseases
- 49 9800-9805: leukemias, nos
- 50 9820-9839 : lymphoid leukemias (C42.1)
- 51 9840-9939 : myeloid leukemias (C42.1)
- 52 9940-9949 : other leukemias (C42.1)
- 53 9950-9969 : chronic myeloproliferative disorders (C42.1)
- 54 9970-9979 : other hematologic disorders
- 55 9980-9989 : myelodysplastic syndrome
- 98 other

# HISTOLOGY RECODE—BRAIN GROUPINGS

# NAACCR Item #: N/A SEER\*Stat Name: Histology recode - Brain groupings Item Length: 2

Field Description: Based on Histologic Type ICD-O-3.

01	Diffuse astrocytoma (protoplasma, fibrillary)
02	Anaplastic astrocytoma
03	Glioblastoma
04	Pilocytic astrocytoma
05	Unique astrocytoma variants
06	Oligodendroglioma
07	Anaplastic oligodendroglioma
08	Ependymoma/anaplastic ependymoma
09	Ependymoma variants
10	Mixed glioma
11	Astrocytoma, NOS
12	Glioma, NOS
13	Choroid plexus
14	Neuroepithelial
15	Benign & malignant neuronal/glial, neuronal & mixed
16	Pineal parenchymal
17	Embryonal/primitive/medulloblastoma
18	Nerve sheath, benign and malignant
19	Meningioma, benign and malignant
20	Other mesenchymal, benign and malignant
21	Hemangioma and hemagioblastoma
22	Lymphoma
23	Germ cell tumors, cysts, and heterotopias
24	Chordoma/chondrosarcoma
25	Pituitary
26	Craniopharyngioma
27	Neoplasm, unspecified, benign and malignant
97	Other Brain Histologies
98	Not Brain

# CS SCHEMA v0203

#### NAACCR Item #: N/A SEER\*Stat Name: CS Schema – v 0203 Item Length: 3

*Field Description:* CS information is collected under the specifications of a particular schema based on site and histology. This recode should be used in any analysis of AJCC 7th ed stage and T, N, M.

# Codes

001	AdnexaUterineOther
002	AdrenalGland
003	AmpullaVater
004	Anus
005	Appendix
006	BileDuctsDistal
007	BileDuctsIntraHepat
008	BileDuctsPerihilar
009	BiliaryOther
010	Bladder
011	Bone
012	Brain
013	Breast
014	BuccalMucosa
015	CarcinoidAppendix
016	Cervix
017	CNSOther
018	Colon
019	Conjunctiva
020	CorpusAdenosarcoma
021	CorpusCarcinoma
022	CorpusSarcoma
023	CysticDuct
024	DigestiveOther
025	EndocrineOther
026	EpiglottisAnterior
027	Esophagus
028	EsophagusGEJunction

-

029EyeOther030FallopianTube031FloorMouth032Gallbladder033GenitalFemaleOther034GenitalMaleOther035GISTAppendix036GISTColon037GISTEsophagus038GISTPeritoneum039GISTRectum040GISTSmallIntestine041GISTStomach042GumLower043GumOther044GumUpper045HeartMediastinum046HemeRetic047Hypopharynx048IIIDefinedOther049IntracranialGland050KaposiSarcoma051KidneyParenchyma052KidneyRenalPelvis053LacrimalGand054LarynxGlottic055LarynxSubglottic059LipLower060LipOther061LipUpper062Liver063Lung		
031FloorMouth032Gallbladder033GenitalFemaleOther034GenitalMaleOther035GISTAppendix036GISTColon037GISTEsophagus038GISTPeritoneum039GISTRectum040GISTSmallIntestine041GISTStomach042GumLower043GumUpper044GumUpper045HeartMediastinum046HemeRetic047Hypopharynx048IllDefinedOther049IntracranialGland050KaposiSarcoma051KidneyParenchyma052KidneyRenalPelvis053LacrimalSac055LarynxOther056LarynxSubglottic057LarynxSupraglottic058LarynxSupraglottic059LipUpper060LipUpper061LipUpper062Liver	029	EyeOther
032Gallbladder033GenitalFemaleOther034GenitalMaleOther035GISTAppendix036GISTColon037GISTEsophagus038GISTPeritoneum039GISTRectum040GISTSmallIntestine041GISTStomach042GumLower043GumOther044GumUpper045HeartMediastinum046HemeRetic047Hypopharynx048IIIDefinedOther049IntracranialGland050KaposiSarcoma051KidneyParenchyma052KidneyRenalPelvis053LacrimalSac054LarynxOther055LarynxSubglottic058LarynxSupraglottic059LipUpper060LipUpper061LipUpper062Liver	030	FallopianTube
033GenitalFemaleOther034GenitalMaleOther035GISTAppendix036GISTColon037GISTEsophagus038GISTPeritoneum039GISTRectum040GISTSmallIntestine041GISTStomach042GumLower043GumUpper044GumUpper045HeartMediastinum046HemeRetic047Hypopharynx048IllDefinedOther049IntracranialGland050KaposiSarcoma051KidneyParenchyma052KidneyRenalPelvis053LacrimalGland054LarynxGlottic055LarynxQlottic058LarynxSubglottic059LipLower060LipOther061LipUpper062Liver	031	FloorMouth
034GenitalMaleOther035GISTAppendix036GISTColon037GISTEsophagus038GISTPeritoneum039GISTRectum040GISTSmallIntestine041GISTStomach042GumLower043GumUpper044GumUpper045HeartMediastinum046HemeRetic047Hypopharynx048IllDefinedOther049IntracranialGland051KidneyParenchyma053LacrimalSac054LacrimalSac055LarynxSubglottic058LarynxSupraglottic059LipUper060LipUpper061LipUpper062Liver	032	Gallbladder
035GISTAppendix036GISTColon037GISTEsophagus038GISTPeritoneum039GISTRectum040GISTSmallIntestine041GISTStomach042GumLower043GumOther044GumUpper045HeartMediastinum046HemeRetic047Hypopharynx048IIIDefinedOther049IntracranialGland050KaposiSarcoma051KidneyParenchyma053LacrimalGland054LacrimalGland055LarynxGlottic056LarynxSubglottic057LarynxSubglottic058LarynxSupraglottic059LipUpper060LipOther061LipUpper062Liver	033	GenitalFemaleOther
036GISTColon037GISTEsophagus038GISTPeritoneum039GISTRectum040GISTSmallIntestine041GISTStomach042GumLower043GumOther044GumUpper045HeartMediastinum046HemeRetic047Hypopharynx048IIIDefinedOther049IntracranialGland050KaposiSarcoma051KidneyParenchyma052KidneyRenalPelvis053LacrimalSac055LarynxGlottic056LarynxSupraglottic059LipLower060LipOther061LipUpper062Liver	034	GenitalMaleOther
037GISTEsophagus038GISTPeritoneum039GISTRectum040GISTSmallIntestine041GISTStomach042GumLower043GumOther044GumUpper045HeartMediastinum046HemeRetic047Hypopharynx048IIIDefinedOther049IntracranialGland050KaposiSarcoma051KidneyParenchyma052KidneyRenalPelvis053LacrimalGland054LacrimalGland055LarynxGlottic056LarynxOther057LarynxSubglottic058LarynxSupraglottic059LipLower060LipOther061LipUpper062Liver	035	GISTAppendix
038GISTPeritoneum039GISTRectum040GISTSmallIntestine041GISTStomach042GumLower043GumOther044GumUpper045HeartMediastinum046HemeRetic047Hypopharynx048IIIDefinedOther049IntracranialGland050KaposiSarcoma051KidneyParenchyma052KidneyRenalPelvis053LacrimalGland054LacrimalGland055LarynxGlottic056LarynxOther057LarynxSupraglottic058LarynxSupraglottic059LipLower060LipOther061LipUpper062Liver	036	GISTColon
039GISTRectum040GISTSmallIntestine041GISTStomach042GumLower043GumOther044GumUpper045HeartMediastinum046HemeRetic047Hypopharynx048IllDefinedOther049IntracranialGland050KaposiSarcoma051KidneyPenenchyma052KidneyRenalPelvis053LacrimalGland054LacrimalGland055LarynxGlottic056LarynxSubglottic057LarynsSubglottic058LarynxSupraglottic059LipLower060LipOther061LipUpper062Liver	037	GISTEsophagus
040GISTSmallIntestine041GISTStomach042GumLower043GumOther044GumUpper045HeartMediastinum046HemeRetic047Hypopharynx048IIIDefinedOther049IntracranialGland050KaposiSarcoma051KidneyParenchyma052KidneyRenalPelvis053LacrimalGland054LacrimalGland055LarynxGlottic056LarynxSubglottic057LarynxSubglottic058LarynxSupraglottic059LipOther060LipOther061LipUpper062Liver	038	GISTPeritoneum
041GISTStomach042GumLower043GumOther044GumUpper045HeartMediastinum046HemeRetic047Hypopharynx048IIIDefinedOther049IntracranialGland050KaposiSarcoma051KidneyParenchyma052KidneyRenalPelvis053LacrimalGland054LacrimalGland055LarynxGlottic056LarynxSubglottic057LarynxSubglottic058LarynxSupraglottic059LipOther061LipUpper062Liver	039	GISTRectum
042GumLower043GumOther044GumUpper045HeartMediastinum046HemeRetic047Hypopharynx048IllDefinedOther049IntracranialGland050KaposiSarcoma051KidneyParenchyma052KidneyRenalPelvis053LacrimalGland054LacrimalGland055LarynxGlottic056LarynxOther057LarynxSubglottic058LarynxSupraglottic059LipOther060LipOther061LipUpper062Liver	040	GISTSmallIntestine
043GumOther044GumUpper045HeartMediastinum046HemeRetic047Hypopharynx048IllDefinedOther049IntracranialGland050KaposiSarcoma051KidneyParenchyma052KidneyRenalPelvis053LacrimalGland054LacrimalGland055LarynxGlottic056LarynxSubglottic057LarynxSubglottic058LarynxSupraglottic059LipOther061LipUpper062Liver	041	GISTStomach
044GumUpper045HeartMediastinum046HemeRetic047Hypopharynx048IllDefinedOther049IntracranialGland050KaposiSarcoma051KidneyParenchyma052KidneyRenalPelvis053LacrimalGland054LacrimalSac055LarynxGlottic056LarynxOther057LarynxSubglottic058LarynxSupraglottic059LipLower060LipOther061LipUpper062Liver	042	GumLower
045HeartMediastinum046HemeRetic047Hypopharynx048IllDefinedOther049IntracranialGland050KaposiSarcoma051KidneyParenchyma052KidneyRenalPelvis053LacrimalGland054LacrimalGland055LarynxGlottic056LarynxOther057LarynxSubglottic058LarynxSupraglottic059LipLower060LipOther061LipUpper062Liver	043	GumOther
046HemeRetic047Hypopharynx048IllDefinedOther049IntracranialGland050KaposiSarcoma051KidneyParenchyma052KidneyRenalPelvis053LacrimalGland054LacrimalSac055LarynxGlottic056LarynxSubglottic057LarynxSubglottic058LarynxSupraglottic059LipOther061LipUpper062Liver	044	GumUpper
<ul> <li>047 Hypopharynx</li> <li>048 IIIDefinedOther</li> <li>049 IntracranialGland</li> <li>050 KaposiSarcoma</li> <li>051 KidneyParenchyma</li> <li>052 KidneyRenalPelvis</li> <li>053 LacrimalGland</li> <li>054 LacrimalSac</li> <li>055 LarynxGlottic</li> <li>056 LarynxOther</li> <li>057 LarynxSubglottic</li> <li>058 LarynxSupraglottic</li> <li>059 LipLower</li> <li>060 LipOther</li> <li>061 LipUpper</li> <li>062 Liver</li> </ul>	045	HeartMediastinum
048IllDefinedOther049IntracranialGland050KaposiSarcoma051KidneyParenchyma052KidneyRenalPelvis053LacrimalGland054LacrimalGland055LarynxGlottic056LarynxOther057LarynxSubglottic058LarynxSupraglottic059LipLower060LipOther061LipUpper062Liver	046	HemeRetic
049IntracranialGland050KaposiSarcoma051KidneyParenchyma052KidneyRenalPelvis053LacrimalGland054LacrimalSac055LarynxGlottic056LarynxOther057LarynxSubglottic058LarynxSupraglottic059LipLower061LipUpper062Liver	047	Hypopharynx
050KaposiSarcoma051KidneyParenchyma052KidneyRenalPelvis053LacrimalGland054LacrimalSac055LarynxGlottic056LarynxOther057LarynxSubglottic058LarynxSupraglottic059LipLower060LipOther061LipUpper062Liver	048	IllDefinedOther
051KidneyParenchyma052KidneyRenalPelvis053LacrimalGland054LacrimalSac055LarynxGlottic056LarynxOther057LarynxSubglottic058LarynxSupraglottic059LipLower060LipOther061LipUpper062Liver	049	IntracranialGland
052KidneyRenalPelvis053LacrimalGland054LacrimalSac055LarynxGlottic056LarynxOther057LarynxSubglottic058LarynxSupraglottic059LipLower060LipOther061LipUpper062Liver	050	KaposiSarcoma
053LacrimalGland054LacrimalSac055LarynxGlottic056LarynxOther057LarynxSubglottic058LarynxSupraglottic059LipLower060LipOther061LipUpper062Liver	051	KidneyParenchyma
054LacrimalSac055LarynxGlottic056LarynxOther057LarynxSubglottic058LarynxSupraglottic059LipLower060LipOther061LipUpper062Liver	052	KidneyRenalPelvis
<ul> <li>055 LarynxGlottic</li> <li>056 LarynxOther</li> <li>057 LarynxSubglottic</li> <li>058 LarynxSupraglottic</li> <li>059 LipLower</li> <li>060 LipOther</li> <li>061 LipUpper</li> <li>062 Liver</li> </ul>	053	LacrimalGland
056LarynxOther057LarynxSubglottic058LarynxSupraglottic059LipLower060LipOther061LipUpper062Liver	054	LacrimalSac
<ul> <li>057 LarynxSubglottic</li> <li>058 LarynxSupraglottic</li> <li>059 LipLower</li> <li>060 LipOther</li> <li>061 LipUpper</li> <li>062 Liver</li> </ul>	055	LarynxGlottic
058LarynxSupraglottic059LipLower060LipOther061LipUpper062Liver	056	LarynxOther
<ul> <li>059 LipLower</li> <li>060 LipOther</li> <li>061 LipUpper</li> <li>062 Liver</li> </ul>	057	LarynxSubglottic
060LipOther061LipUpper062Liver	058	LarynxSupraglottic
<ul><li>061 LipUpper</li><li>062 Liver</li></ul>	059	LipLower
062 Liver	060	LipOther
	061	LipUpper
063 Lung	062	Liver
	063	Lung

064	Lymphoma
065	LymphomaOcularAdnexa
066	MelanomaBuccalMucosa
067	MelanomaChoroid
068	MelanomaCiliaryBody
069	MelanomaConjunctiva
070	MelanomaEpiglottisAnterior
071	MelanomaEyeOther
072	MelanomaFloorMouth
073	MelanomaGumLower
074	MelanomaGumOther
075	MelanomaGumUpper
076	MelanomaHypopharynx
077	MelanomaIris
078	MelanomaLarynxGlottic
079	MelanomaLarynxOther
080	MelanomaLarynxSubglottic
081	MelanomaLarynxSupraglottic
082	MelanomaLipLower
083	MelanomaLipOther
084	MelanomaLipUpper
085	MelanomaMouthOther
086	MelanomaNasalCavity
087	MelanomaNasopharynx
088	MelanomaOropharynx
089	MelanomaPalateHard
090	MelanomaPalateSoft
091	MelanomaPharynxOther
092	MelanomaSinusEthmoid
093	MelanomaSinusMaxillary
094	MelanomaSinusOther
095	MelanomaSkin
096	MelanomaTongueAnterior
097	MelanomaTongueBase
098	MerkelCellPenis

099	MerkelCellScrotum
100	MerkelCellSkin
101	MerkelCellVulva
102	MiddleEar
103	MouthOther
104	MycosisFungoides
105	MyelomaPlasmaCellDisorder
106	NasalCavity
107	Nasopharynx
108	NETAmpulla
109	NETColon
110	NETRectum
111	NETSmallIntestine
112	NETStomach
113	Orbit
114	Oropharynx
115	Ovary
116	PalateHard
117	PalateSoft
118	PancreasBodyTail
119	PancreasHead
120	PancreasOther
121	ParotidGland
122	Penis
123	Peritoneum
124	PeritoneumFemaleGen
125	PharyngealTonsil
126	PharynxOther
127	Placenta
128	Pleura
129	Prostate
130	Rectum
131	RespiratoryOther
132	Retinoblastoma
133	Retroperitoneum

- 134 SalivaryGlandOther
- 135 Scrotum136 SinusEthmoid
- 137 SinusMaxillary
- 138 SinusOther
- 139 Skin
- 140 SkinEyelid
- 141 SmallIntestine
- 142 SoftTissue
- 143 Stomach
- 144 SubmandibularGland
- 145 Testis
- 146 Thyroid
- 147 TongueAnterior
- 148 TongueBase
- 149 Trachea
- 150 Urethra
- 151 UrinaryOther
- 152 Vagina
- 153 Vulva

# **RACE RECODE (WHITE, BLACK, OTHER)**

#### NAACCR Item #: N/A SEER\*Stat Name: Race recode (White, Black, Other) Item Length: 1

*Field Description:* Race recode is based on the race variables and the American Indian/Native American IHS link variable. This recode should be used to link to the populations for white, black and other. It is independent of Hispanic ethnicity.

For more information, see <a href="http://seer.cancer.gov/seerstat/variables/seer/race">http://seer.cancer.gov/seerstat/variables/seer/race</a> ethnicity.

- 1 White
- 2 Black
- 3 Other (American Indian/AK Native, Asian/Pacific Islander)
- 7 Other unspecified (1991+)
- 9 Unknown

# RACE RECODE (W, B, AI, API)

#### NAACCR Item #: N/A SEER\*Stat Name: Race recode (W, B, AI, API) Item Length: 1

*Field Description:* Caution should be exercised when using this variable. For more information, see <u>http://seer.cancer.gov/seerstat/variables/seer/race\_ethnicity</u>.

#### Codes

- 1 White
- 2 Black
- 3 American Indian/Alaska Native
- 4 Asian or Pacific Islander
- 7 Other unspecified (1991+)
- 9 Unknown

# **ORIGIN RECODE NHIA (HISPANIC, NON-HISP)**

#### NAACCR Item #: N/A SEER\*Stat Name: Origin recode NHIA (Hispanic, Non-Hisp) Item Length: 1

# *Field Description:* Caution should be exercised when using this variable. For more information, see <u>http://seer.cancer.gov/seerstat/variables/seer/race\_ethnicity</u>.

#### Codes

0 Non-Spanish-Hispanic-Latino1 Spanish-Hispanic-Latino

# SEER HISTORIC STAGE A

#### NAACCR Item #: N/A SEER\*Stat Name: SEER historic stage A Item Length: 1

# *Field Description:* Derived from Collaborative Stage (CS) for 2004+ and Extent of Disease (EOD) from 1973-2003. It is a simplified version of stage: in situ, localized, regional, distant, & unknown. Over time several different EOD schemes have been used. Thus caution should be used when doing trend analysis.

For more information including sites and years for which it isn't calculated, see <u>http://seer.cancer.gov/seerstat/variables/seer/lrd-stage</u>.

0	In situ — A noninvasive neoplasm; a tumor which has not penetrated the basement membrane nor extended beyond the epithelial tissue. Some synonyms are intraepithelial (confined to epithelial tissue), noninvasive and noninfiltrating.
1	Localized — An invasive neoplasm confined entirely to the organ of origin. It may include intraluminal extension where specified. For example for colon, intraluminal extension limited to immediately contiguous segments of the large bowel is localized, if no lymph nodes are involved. Localized may exclude invasion of the serosa because of the poor survival of the patient once the serosa is invaded.
2	Regional — A neoplasm that has extended 1) beyond the limits of the organ of origin directly into surrounding organs or tissues; 2) into regional lymph nodes by way of the lymphatic system; or 3) by a combination of extension and regional lymph nodes.
4	Distant — A neoplasm that has spread to parts of the body remote from the primary tumor either by direct extension or by discontinuous metastasis (e.g., implantation or seeding) to distant organs, issues, or via the lymphatic system to distant lymph nodes.
8	Localized/Regional – Only used for Prostate cases.
9	Unstaged — Information is not sufficient to assign a stage.

# AJCC STAGE 3<sup>rd</sup> EDITION (1988-2003)

## NAACCR Item #: N/A SEER\*Stat Name: AJCC stage 3rd edition (1988-2003) Item Length: 2

*Field Description:* Derived by algorithm from extent of disease (EOD). Not available for all years or for all sites.

## Codes

0	In Situ	31	IIIA
10	Ι	32	IIIB
11	IA	33	IIIC
12	IB	39	III, NOS
13	IC	40	IV
18	In Situ and I combined for bladder only	41	IVA
19	I, NOS	42	IVB
20	П	49	IV, NOS
21	IIA	88	Recode scheme not yet available
22	IIB	90	Unstaged
23	IIC	98	Not applicable
29	II, NOS	99	Error condition
30	III		

#### Coded only for 1988-2003 cases with the following ICD-O site codes:

Colon	C180:C189
Rectum	C199,C209
Lung and Bronchus	C340:C349
Breast	C500:C509
Cervix	C530:C539
Corpus uteri	C559, C530:C539
Ovary	C569
Vagina	C529
Vulva	C519
Oth fem gen	C510:C512, C589
Prostate	C619
Bladder	C670:C679

For staging criteria, please refer to <u>http://seer.cancer.gov/manuals/historic/comp\_stage1.1.pdf</u>

# SEER MODIFIED AJCC STAGE 3<sup>rd</sup> ED (1988-2003)

## NAACCR Item #: N/A SEER\*Stat Name: SEER modified AJCC stage 3rd (1988-2003) Item Length: 2

*Field Description:* Derived by algorithm from extent of disease (EOD). Not available for all years or for all sites. The modified version stages cases that would be unstaged under strict AJCC staging rules. For example, it assumes NX is N0.

0         In Situ         31         IIIA           10         I         32         IIIB           11         IA         33         IIIC           12         IB         39         III, NOS           13         IC         40         IV           18         In Situ & I combined for bladder only         41         IVA           19         I, NOS         42         IVB           20         II         49         IV, NOS           21         IIA         88         Recode scheme not yet available           22         IIB         90         Unstaged           23         IIC         98         Not applicable           29         II, NOS         99         Error condition           30         III         11         11	Cod	es		
11IA33IIIC12IB39III, NOS13IC40IV18In Situ & I combined for bladder only41IVA19I, NOS42IVB20II49IV, NOS21IIA88Recode scheme not yet available22IIB90Unstaged23IIC98Not applicable29II, NOS99Error condition	0	In Situ	31	IIIA
12IB39III, NOS13IC40IV18In Situ & I combined for bladder only41IVA19I, NOS42IVB20II49IV, NOS21IIA88Recode scheme not yet available22IIB90Unstaged23IIC98Not applicable29II, NOS99Error condition	10	Ι	32	IIIB
13IC40IV18In Situ & I combined for bladder only41IVA19I, NOS42IVB20II49IV, NOS21IIA88Recode scheme not yet available22IIB90Unstaged23IIC98Not applicable29II, NOS99Error condition	11	IA	33	IIIC
18In Situ & I combined for bladder only41IVA19I, NOS42IVB20II49IV, NOS21IIA88Recode scheme not yet available22IIB90Unstaged23IIC98Not applicable29II, NOS99Error condition	12	IB	39	III, NOS
19I, NOS42IVB20II49IV, NOS21IIA88Recode scheme not yet available22IIB90Unstaged23IIC98Not applicable29II, NOS99Error condition	13	IC	40	IV
20II49IV, NOS21IIA88Recode scheme not yet available22IIB90Unstaged23IIC98Not applicable29II, NOS99Error condition	18	In Situ & I combined for bladder only	41	IVA
21IIA88Recode scheme not yet available22IIB90Unstaged23IIC98Not applicable29II, NOS99Error condition	19	I, NOS	42	IVB
22IIB90Unstaged23IIC98Not applicable29II, NOS99Error condition	20	Ш	49	IV, NOS
23IIC98Not applicable29II, NOS99Error condition	21	IIA	88	Recode scheme not yet available
29     II, NOS     99     Error condition	22	IIB	90	Unstaged
	23	IIC	98	Not applicable
30 III	29	II, NOS	99	Error condition
	30	III		

Codes

## Coded only for 1988-2003 cases with the following ICD-O- codes:

Colon	C180:C189
Rectum	C199,C209
Lung and Bronchus	C340:C349
Breast	C500:C509
Cervix	C530:C539
Corpus uteri	C559,C530:C539
Ovary	C569
Vagina	C529
Vulva	C519
Oth fem gen	C510:C512,C589
Prostate	C619
Bladder	C670:C679

For staging criteria, refer to <u>http://seer.cancer.gov/manuals/historic/comp\_stage1.1.pdf</u>

## **SEER SUMMARY STAGE 1977**

#### NAACCR Item #: 760 SEER\*Stat Name: SEER summary stage 1977 (1995-2000) Item Length: 1

*Field Description:* Based on SEER Extent of Disease (EOD) following a SEER algorithm. This variable is provided on the NAACCR call for data. For more information, see <u>http://seer.cancer.gov/manuals/historic/ssm\_1977.pdf</u>.

#### Codes

0	In situ
1	Localized only
2	Regional by direct extension only
3	Regional lymph nodes involved only
4	Regional by both direct extension and lymph
5	Regional, NOS
7	Distant site(s)/node(s) involved
9	Unknown/unstaged/unspecified/DCO

# SEER SUMMARY STAGE 2000

## NAACCR Item #: 759 SEER\*Stat Name: SEER summary stage 2000 (2001-2003) Item Length: 1

*Field Description:* Based on SEER Extent of Disease (EOD) following a SEER algorithm. This variable is provided on the NAACCR call for data. For more information, see http://seer.cancer.gov/tools/ssm/

0	In situ
1	Localized only
2	Regional by direct extension only
3	Regional lymph nodes involved only
4	Regional by both direct extension and lymph
5	Regional, NOS
7	Distant site(s)/node(s) involved
9	Unknown/unstaged/unspecified/DCO

## NUMBER OF PRIMARIES

#### NAACCR Item#: N/A SEER\*Stat Name: Number of primaries Item Length: 2

*Field Description:* Based on the total number of tumors in SEER, not necessarily this database file. This value is the same across all tumors for a person.

Codes

01-36 Actual number of primaries

#### FIRST MALIGNANT PRIMARY INDICATOR

## NAACCR Item #: N/A SEER\*Stat Name: First malignant primary indicator Item Length: 1

*Field Description:* Based on all the tumors in SEER. Tumors not reported to SEER are assumed malignant.

#### Codes

0	no
1	yes

#### STATE-COUNTY RECODE

## NAACCR Item #: N/A SEER\*Stat Name: State-county Item Length: 5

*Field Description:* This item is a state-county combination where the first two characters represent the state FIPS code. The last three digits represent the FIPS county code.

## SURVIVAL TIME RECODE

#### NAACCR Item #: N/A SEER\*Stat Name: Survival time recode (month) Survival time recode (year)

#### Item Length: 4

*Field Description:* The Survival Time Recode is calculated using the date of diagnosis and one of the following: date of death, date last known to be alive, or follow-up cutoff date used for this file (see title page for date for this file). Thus a person diagnosed in May 1976 and who died in May 1980 has a Survival Time Recode of 04 years and 00 months.

#### Codes

YYMM where:

- YY = number of completed years
- MM = number of completed months
- 9999 = unknown--Survival Time Recode cannot be calculated for this case

#### EXAMPLE:

Assume December 1985 is used as a follow-up cutoff date:

- 1. If a person was known to be alive in April of 1986, December 1985 is used to compute Survival Time Recode.
- 2. A person known to have died in May 1987 is considered alive and Survival Time Recode computed using December 1985 as date of last contact.
- 3. If the last information on a person is that s/he was alive in April 1980, then April 1980 is used.

## CAUSE OF DEATH TO SEER SITE RECODE

#### NAACCR Item #: N/A SEER\*Stat Name: COD to site recode Item Length: 5

*Field Description:* This recode was introduced to account for several newly valid ICD-10 codes and includes both cancer and non-cancer causes of death.

See the following website for details: http://seer.cancer.gov/codrecode/1969+ d09172004/index.html

## COD TO SITE REC KM

#### NAACCR Item #: N/A SEER\*Stat Name: COD to site rec KM Item Length: 5

*Field Description:* This is a recode based on underlying cause of death to designate cause of death into groups similar to the incidence site recode with KS and mesothelioma. For more information, see <u>http://seer.cancer.gov/codrecode/1969+\_d04162012</u>. Study cutoff date has been applied, i.e. coded as alive if death occurred after study cutoff.

## VITAL STATUS RECODE

## NAACCR Item #: N/A SEER\*Stat Name: Vital status recode (study cutoff used) Item Length: 1

*Field Description:* Any patient that dies after the follow-up cut-off date is recoded to alive as of the cut-off date.

#### Codes

1	Alive
4	Dead

### IHS LINK

## NAACCR Item #: 192 SEER\*Stat Name: IHS Link Item Length: 1

*Field Description:* Incidence files are periodically linked with Indian Health Service (IHS) files to identify Native Americans. The race recode uses information from this field and race to determine if a person is Native American or not. See <a href="http://www.seer.cancer.gov/seerstat/variables/seer/race\_ethnicity">http://www.seer.cancer.gov/seerstat/variables/seer/race\_ethnicity</a>.

1 Record sent for linkage, IHS match
i incessite sent for mixage, into materi
Blank Record not sent for linkage

#### SUMMARY STAGE 2000 (1998+)

#### NAACCR Item #: N/A SEER\*Stat Name: Summary Stage 2000 (1998+) Item Length: 1

*Field Description:* Summary Stage 2000 is derived from Collaborative Stage (CS) for 2004+ and Extent of Disease (EOD) from 1998-2003. It is a simplified version of stage: in situ, localized, regional, distant, & unknown. Used in the SEER CSR and more recent SEER publications. For more information including sites and years for which it isn't calculated, see <u>http://seer.cancer.gov/seerstat/variables/seer/lrd-stage</u>.

#### AYA SITE RECODE

## NAACCR Item #: N/A SEER\*Stat Name: AYA site recode Item Length: 2

*Field Description:* A site/histology recode that is mainly used to analyze data on adolescent and young adults. The recode was applied to all cases no matter the age in order that age comparisons can be made with these groupings. For more information, see http://www.seer.cancer.gov/ayarecode/index.html.

## LYMPHOMA SUBTYPE RECODE

NAACCR Item #: N/A SEER\*Stat Name: Lymphoma subtype recode Item Length: 2

*Field Description:* A site/histology recode that is mainly used to analyze data on adolescent and young adults. The recode was applied to all cases no matter the age in order that age comparisons can be made with these groupings. For more information, see <u>http://www.seer.cancer.gov/ayarecode/index.html</u>.

## SEER CAUSE-SPECIFIC DEATH CLASSIFICATION

## NAACCR Item #: N/A SEER\*Stat Name: SEER cause-specific death classification Item Length: 1

*Field Description*: Created for use in cause-specific survival. This variable designates that the person died of their cancer for cause-specific survival. For more information, see <u>http://seer.cancer.gov/causespecific</u>.

#### Codes

0	Alive or dead of other cause
1	Dead
9	N/A not first tumor

## SEER OTHER CAUSE OF DEATH CLASSIFICATION

## NAACCR Item #: N/A SEER\*Stat Name: SEER other cause of death classification Item Length: 1

# *Field Description*: Created for use in left-truncated life table session. This variable designates that the person died of causes other than their cancer. For more information, see <u>http://seer.cancer.gov/causespecific</u>.

0	Alive or dead due to cancer
1	Dead
9	N/A not first tumor

#### CS TUMOR SIZE EXT/EVAL

#### NAACCR Item #: 2820 SEER\*Stat Name: CS Tumor Size/Ext Eval (2004+) Item Length: 1

*Field Description*: Available for 2004+, but not required for the entire timeframe. Will be blank in cases not collected. For more information, see <u>http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage</u>.

#### CS LYMPH NODES EVAL

## NAACCR Item #: 2840 SEER\*Stat Name: CS Reg Nodes Eval (2004+) Item Length: 1

*Field Description*: Available for 2004+, but not required for the entire timeframe. Will be blank in cases not collected. For more information, see <u>http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage</u>.

## CS METS EVAL

#### NAACCR Item #: 2860 SEER\*Stat Name: CS Mets Eval (2004+) Item Length: 1

*Field Description*: Available for 2004+, but not required for the entire timeframe. Will be blank in cases not collected. For more information, see <u>http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage</u>.

## PRIMARY BY INTERNATIONAL RULES

#### NAACCR Item #: N/A SEER\*Stat Name: Primary by International Rules Item Length: 1

*Field Description*: Created using IARC multiple primary rules. Did not include benign tumors or non-bladder in situ tumors in algorithm. No tumor information was modified on any records.

0	No
1	Yes
9	Excluded from IARC multiple primary algorithm due to behavior

## ER STATUS RECORD BREAST CANCER (1990+)

## NAACCR Item #: N/A SEER\*Stat Name: ER Status Recode Breast Cancer (1990+) Item Length: 1

*Field Description*: Created by combining information from Tumor marker 1 (1990-2003) (NAACCR Item #=1150), with information from CS site-specific factor 1 (2004+) (NAACCR Item #=2880). This field is blank for non-breast cases and cases diagnosed before 1990.

#### Codes

1	Positive
2	Negative
3	Borderline
4	Unknown
9	Not 1990+ Breast

## PR STATUS RECORD BREAST CANCER (1990+)

## NAACCR Item #: N/A SEER\*Stat Name: PR Status Recode Breast Cancer (1990+) Item Length: 1

*Field Description*: Created by combining information from Tumor marker 2 (1990-2003) (NAACCR Item #=1150), with information from CS site-specific factor 2 (2004+) (NAACCR Item #=2880). This field is blank for non-breast cases and cases diagnosed before 1990.

1	Positive
2	Negative
3	Borderline
4	Unknown
9	Not 1990+ Breast

# CS SCHEMA—AJCC 6<sup>TH</sup> ED (PREVIOUSLY CALLED V1)

## NAACCR Item #: N/A SEER\*Stat Name: CS Schema- AJCC 6<sup>th</sup> ed Item Length: 2

*Field Description*: CS information is collected under the specifications of a particular schema based on site and histology. This recode should be used in any analysis of AJCC 6th ed stage and T, N, M. Based on CS version 1, it should not be used for SSFs collected or modified under CS v02. http://cancerstaging.org/cstage/schema.html.

01	LipUpper
02	LipLower
03	OthLip
04	BaseTongue
05	AntTongue
06	GumUpper
07	GumLower
08	OthGum
09	FOM
10	HardPalate
11	SoftPalate
12	OthMouth
13	BuccalMucosa
14	ParotidGland
15	SubmandibularGland
16	OthSalivary
17	Oropharynx
18	AntEpiglottis
19	Nasopharynx
20	Hypopharynx
21	OthPharynx
22	Esophagus
23	Stomach
24	SmallIntestine
25	Colon
26	Rectum
27	Anus
28	Liver
29	Gallbladder
30	ExtraHepaticDucts
31	Ampulla
32	OthBiliary
33	PancreasHead
34	PancreasBodyTail

- 35 OthPancreas
- 36 OthDigestive
- 37 NasalCavity
- 38 MiddleEar
- 39 MaxillarySinus
- 40 EthmoidSinus
- 41 OthSinus
- 42 GlotticLarynx
- 43 SupraLarynx
- 44 SubLarynx
- 45 OthLarynx
- 46 Trachea
- 47 Lung
- 48 HeartMediastinum
- 49 Pleura
- 50 OthRespiratory
- 51 Bone
- 52 Skin
- 53 SkinEyelid
- 54 Melanoma
- 55 MF
- 56 SoftTissue
- 57 Peritoneum
- 58 Breast
- 59 Vulva
- 60 Vagina
- 61 Cervix
- 62 Corpus
- 63 Ovary
- 64 FallopianTube
- 65 OthAdnexa
- 66 OthFemaleGen
- 67 Placenta
- 68 Penis
- 69 Prostate
- 70 Testis
- 71 OthMaleGen
- 72 Scrotum
- 73 Kidney
- 74 RenalPelvis
- 75 Bladder
- 76 Urethra
- 77 OthUrinary
- 78 Conjunctiva
- 79 MelanomaConjunctiva
- 80 OthEye

81	MelanomaIrisCiliary
82	MelanomaChoroid
83	MelanomaOthEye
84	LacrimalGland
85	Orbit
86	Retinoblastoma
87	Brain
88	OthCNS
89	Thyroid
90	OthEndocrine
91	KS
92	Lymphoma
93	HemeRetic
94	OthIllDef

## **CS SITE-SPECIFIC FACTOR 8**

## NAACCR Item #: 2862 SEER\*Stat Name: CS site-specific factor 8 (2004+) Item Length: 3

*Field Description:* Each CS site-specific factor (SSF) is schema dependent. They can provide information needed to stage the case, clinically relevant information, or prognostic information. Available for varying years and schemas depending on standard setter requirements. Earlier cases may be converted and new codes added which weren't available for use prior to the current version of CS.

For more information, see <u>http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage</u>.

#### **CS SITE-SPECIFIC FACTOR 10**

## NAACCR Item #: 2864 SEER\*Stat Name: CS site-specific factor 10 (2004+) Item Length: 3

*Field Description:* Each CS site-specific factor (SSF) is schema dependent. They can provide information needed to stage the case, clinically relevant information, or prognostic information. Available for varying years and schemas depending on standard setter requirements. Earlier cases may be converted and new codes added which weren't available for use prior to the current version of CS.

For more information, see <u>http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage</u>.

#### **CS SITE-SPECIFIC FACTOR 11**

#### NAACCR Item #: 2865 SEER\*Stat Name: CS site-specific factor 11 (2004+) Item Length: 3

*Field Description:* Each CS site-specific factor (SSF) is schema dependent. They can provide information needed to stage the case, clinically relevant information, or prognostic information. Available for varying years and schemas depending on standard setter requirements. Earlier cases may be converted and new codes added which weren't available for use prior to the current version of CS.

For more information, see <u>http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage</u>.

## **CS SITE-SPECIFIC FACTOR 13**

#### NAACCR Item #: 2867 SEER\*Stat Name: CS site-specific factor 13 (2004+) Item Length: 3

*Field Description:* Each CS site-specific factor (SSF) is schema dependent. They can provide information needed to stage the case, clinically relevant information, or prognostic information. Available for varying years and schemas depending on standard setter requirements. Earlier cases may be converted and new codes added which weren't available for use prior to the current version of CS.

For more information, see <u>http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage</u>.

#### CS SITE-SPECIFIC FACTOR 15

## NAACCR Item #: 2869 SEER\*Stat Name: CS site-specific factor 15 (2004+) Item Length: 3

*Field Description:* Each CS site-specific factor (SSF) is schema dependent. They can provide information needed to stage the case, clinically relevant information, or prognostic information. Available for varying years and schemas depending on standard setter requirements. Earlier cases may be converted and new codes added which weren't available for use prior to the current version of CS.

For more information, see <u>http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage</u>.

## **CS SITE-SPECIFIC FACTOR 16**

## NAACCR Item #: 2870 SEER\*Stat Name: CS site-specific factor 16 (2004+) Item Length: 3

*Field Description:* Each CS site-specific factor (SSF) is schema dependent. They can provide information needed to stage the case, clinically relevant information, or prognostic information. Available for varying years and schemas depending on standard setter requirements. Earlier cases may be converted and new codes added which weren't available for use prior to the current version of CS.

For more information, see <u>http://seer.cancer.gov/seerstat/variables/seer/ajcc-stage</u>.

## LYMPH VASCULAR INVASION

## NAACCR Item #: 1182 SEER\*Stat Name: Lymph-vascular Invasion (2004+) Item Length: 1

*Field Description:* LVI is required for cases originally coded under CSv2 or diagnosed 2010+ for the schemas for penis and testis only. On the research file LVI is shown only for testis because it is needed for AJCC 6th ed staging. For penis, LVI is needed for AJCC 7th ed staging only which isn't calculated until 2010.

0	Lymph-vascular Invasion Not Present (absent)/Not Identified
1	Lymph-vascular Invasion Present/Identified
8	Not Applicable
9	Unknown/Indeterminate