Department of Commerce • National Oceanic & Atmospheric Administration • National Weather Service

## NATIONAL WEATHER SERVICE INSTRUCTION 10-813 April 5, 2012

Operations and Services
Aviation Weather Services, NWSPD 10-8
TERMINAL AERODROME FORECASTS

**NOTICE:** This publication is available at: <a href="http://www.nws.noaa.gov/directives/">http://www.nws.noaa.gov/directives/</a>.

**OPR:** W/OS23 (C.Sims) Certified by: W/OS23 (C. Abelman)

**Type of Issuance:** Routine

**SUMMARY OF REVISIONS:** Supersedes NWS Instruction 10-813, *Terminal Aerodrome Forecasts*, and dated December 19, 2008. Changes include:

Added Appendix F and hosted it as a link to a website. Other updates and changes to 10-813 listed here.

Section 4: TAFs should not exceed 6 lines

Section 4.2.c - More emphasis and detail should be included in the first 12 hours of the TAF.

Section 4.11 – Update frequency

Section 4.14 – PROB and TEMPO groups

Section 7 - The Aviation Focal Points may view individual stats for their forecasters

Appendix B, Section 1.2.7.3 – Update to Cloud Type definition

Appendix B, Section 1.2.9.1 – Special Thunderstorm Consistency Guidance

Appendix C, Section 1.3.1 – Categorical Amendment Criteria

Appendix D, Section 1.1 – Clarification of Observation Requirement to Initiate New TAF Service

Signed 03/22/12

David B. Caldwell

Date

Director, Office of Climate, Water, and Weather Services

<u>Ta</u>	ble of Contents	Page				
1.	General	3				
2.	Background					
3.	Responsibility					
4.	Terminal Aerodrome Forecast					
•••	4.1 Coordination.					
	4.2 Composing the TAF					
	4.3 TAFs for Automated Systems					
	4.4 Format					
	4.5 Contractions					
	4.6 TAF Corrections					
	4.7 TAF Amendments					
	4.8 TAF Collectives					
	4.9 Issuance Times.					
	4.10 Time References.					
	4.11 Update Frequency					
	4.12 Length of TAF Change Groups					
	4.13 Sites with Scheduled Part-Time Observations.					
	4.14 PROB and TEMPO Groups.					
5.	-					
<i>5</i> .	Records Retention					
7.						
/.	verification of Terminal Polecasts	/				
Ap	ppendices:					
	A. Contractions Used In NWS TAFs					
	B. TAF Code Elements.					
	C. Unscheduled TAFs					
	D. New TAF Service, Observation Requirements and Terminating TAF Service					
	E. TAF Code Format, Terminology, and Significant Weather Matrices					
	F. NWS TAF Locations by Responsible Region and Weather Forecast Office (W	FO) and				

1. <u>General</u>. This instruction describes Terminal Aerodrome Forecast (TAF) preparation by

National Weather Service (NWS) Weather Forecast Offices (WFOs). TAFs, also known as Aerodrome Forecasts, are a critical element of NWS aviation weather services because they are a key product in decisions for flight planning and for aircraft movement within the National Airspace System (NAS).

- 2. <u>Background</u>. TAFs are used by a variety of aviation users, including domestic and international commercial airlines, general aviation (GA), civilian, and military operators. TAFs will be prepared, issued, and distributed on a timely basis to meet requirements of the U.S. Aviation Meteorological Authority, the Federal Aviation Administration (FAA), and the International Civil Aviation Organization (ICAO) using a code format designed by the World Meteorological Organization (WMO) for both domestic and international use.
- 3. Responsibility. WFO Meteorologists in Charge (MICs) are responsible for maintaining a consistent and accurate aviation forecast program for their offices. TAFs will be prepared by designated NWS offices for the sites listed in Appendix E. TAF sites are listed alphabetically by region, by WFO within each region, and by TAF sites, indicated by the 4-letter ICAO identifier and the location (city, town, or airport). The Office of Climate, Water, and Weather Services (OCWWS), NWS Headquarters (NWSH) will update Appendix E as needed.
- 4. <u>Aerodrome Forecast.</u> A NWS TAF consists of the expected meteorological conditions significant to aviation at an airport for a specified time period. For the U.S., this is the area within five (5) statute miles (SM) of the center of an airport's runway complex. Forecasters will prepare and monitor TAFs using the best professional judgment to optimize timeliness and representativeness, with an awareness of the potential operational impact of each forecast element. TAFs should remain as concise as possible to describe changes in flight conditions and not exceed 6 lines (excluding a TEMPO group) except when absolutely necessary to describe relevant weather conditions.

TAFs in the U.S. will be prepared in the international standard for TAF code, with U.S. modifications, described in WMO Manual on Codes, WMO No. 306, Volume I.I, Part A, FM 51-X Ext. TAF, Aerodrome Forecast. U.S. modifications will be held to a minimum.

- 4.1 <u>Coordination</u>. Forecasters will coordinate with the servicing Center Weather Service Unit (CWSU) in accordance with NWSI 10-803, *Support to Air Traffic Control Facilities*. Forecasters should coordinate with adjacent NWS offices to prevent inconsistencies between TAFs. TAFs should be consistent with public and other aviation products. The forecaster is the final authority for the forecasts they issue.
- 4.2 <u>Composing the TAF</u>. A complete TAF will include a forecast of surface wind (speed and direction), surface visibility, weather, obstructions to vision (if any), clouds (or vertical visibility into a surface-based obscuration), Low Level Wind Shear (LLWS), and any expected significant change(s) to one or more of these elements during the specified time period, ordinarily 24 hours. However specified International airports require 30 hour TAFs.

Forecasters should keep the following in mind when composing a TAF:

a. Be aware of operationally significant weather for the airport.

- b. Be aware of amendment criteria when formulating the forecast, but do not forecast to satisfy criteria.
- c. More emphasis and detail should be included in the first 12 hours of the TAF. The latter hours in the TAF may contain less detail and highlight significant events, as this is used for strategic planning.

TAFs may also include specified significant meteorological phenomena expected to occur in the airport's vicinity (VC) during any part of the valid period as VC weather codes (VCFG, VCSH, VCTS). In the United States, vicinity is defined as an area between 5 and 10 statute miles (SM) from the center of the runway complex of an airport.

The forecaster will maintain a watch of weather conditions for all pertinent TAF sites, including sites with scheduled part-time observation, automated observing sites requiring part-time augmentation, and non-augmented automated observing sites.

- 4.3 TAFs for Automated Systems. TAFs for Automated Surface Observing System (ASOS) and Automated Weather Observing System (AWOS) sites will contain the element value(s) and the type(s) and intensity of weather and/or obstructions the forecaster expects, regardless of whether the automated system can report or differentiate between those conditions and other, similar conditions. For example, if the forecaster expects clouds above 12,000 feet, zero visibility, ice pellets, or snow showers, the TAF should reflect these conditions. Even when an automated system reports CLR (which indicates clear below 12,000 feet AGL), M1/4SM (which indicates visibility of LT 1/4 SM), or rain or snow when ice pellets or snow showers may be occurring, the TAF will be representative of what is expected to occur.
- 4.4 <u>Format</u>. The format of the TAF will follow ICAO standards as outlined in Appendix B. The length of a line will not exceed 69 spaces, including typed characters, spaces, returns, and the end-of-report separator.
- 4.5 <u>Contractions</u>. The only contractions used in NWS TAFs will be those terms defined in this instruction and its appendices, which have been derived from the WMO Codes Manual and from the ICAO document ICAO Abbreviations and Codes. In a very few cases, plain language English terms may be used. All valid contractions for TAFs are included in Appendix A.
- 4.6 <u>TAF Corrections</u>. Corrections to the TAF should be issued as soon as the forecaster becomes aware of the error. Normally a correction is issued within a half hour of the issuance of the original forecast. Corrections made later than one hour after a TAF has been issued should be sent as an amendment; with forecast conditions updated as the original mistake is corrected.
- 4.7 <u>TAF Amendments</u>. The decision to amend the TAF relies on the forecaster's assessment of existing conditions and expectations. If conditions change earlier or later than forecast but the TAF shows the expected trend and will soon recover, an amendment may not be needed. Additionally, small fluctuations in the observation should not result in a minor adjustment to the TAF (chasing the observation). However, if improving weather conditions occur sooner than forecast, then an amended TAF is necessary.

TAF amendments will be issued promptly when:

- a. Conditions meeting amendment criteria are expected or have occurred and those conditions will, in the forecaster's estimation, persist, or
- b. New guidance/information indicates future conditions are expected to be in a different category than originally forecast, especially in the 1-12 hour time-period.

Forecasters should maintain a weather watch and amend forecasts prior to weather conditions meeting amendment criteria. Application programs designed to notify when a TAF does not meet current criteria can be used but may also delay amendment issuance. Additionally, forecasters should issue TAF AMDs for significant forecast changes immediately rather than waiting for the next regularly scheduled TAF release time, even if that release time is within a half hour after the amendment time.

TAF Amendment Criteria is located in Appendix C.

- 4.8 <u>TAF Collectives</u>. When a WFO transmits more than one TAF in a collective, each forecast will be started on the line immediately following the previous TAF with the location identifier at the left margin. Each complete TAF will be followed by an end-of-report separator (an equal sign [=]), which denotes the end of a complete TAF for each location. The end-of-report separator will be followed by a return. The TAF order should be decided by the respective RH and remain unchanged as much as possible. Newly added airports should generally be placed at the end of the bulletin.
- 4.9 <u>Issuance Times</u>. Scheduled TAFs prepared by NWS offices are issued at least four times a day, every six (6) hours, according to the following schedule:

Scheduled Issuance	Valid Period	30 Hour	Issuance Window
0000 UTC	0000 to 0000 UTC	0600 UTC	2320 to 2340 UTC
0300 UTC (AMD)	0300 to 0000 UTC	0600 UTC	
0600 UTC	0600 to 0600 UTC	1200 UTC	0520 to 0540 UTC
0900 UTC (AMD)	0900 to 0600 UTC	1200 UTC	
1200 UTC	1200 to 1200 UTC	1800 UTC	1120 to 1140 UTC
1500 UTC (AMD)	1500 to 1200 UTC	1800 UTC	
1800 UTC	1800 to 1800 UTC	0000 UTC	1720 to 1740 UTC
2100 UTC (AMD)	2100 to 1800 UTC	0000 UTC	

Each Office with TAF responsibility is required to issue four scheduled TAFs per day.

- 4.10 <u>Time References</u>. The times in TAFs will be stated in Universal Time Coordinated (UTC). Time references should be as detailed and specific as supporting data and present science allow. The letter Z is appended to the end of the date-time group of forecast origin. The contraction UTC does not appear in either the WMO abbreviated heading or the forecast text.
- 4.11 <u>Update Frequency.</u> Each WFO may choose to routinely issue TAFs more frequently than every six hours as a method of keeping the TAF as representative as possible. Those offices providing TAFs for the FAA's core airports will provide TAFs every 3 hours. These

intermediate TAFs will be issued as amendments using the TAF AMD header though they will actually be issued on a scheduled basis. Offices not issuing for these airports may issue more frequent updates after coordinating the change with their Regional Headquarters.

- 4.12 <u>Length of TAF Change Groups</u>. To forecast a change in weather conditions starting at a particular time, the FM (from) contraction will be used and will always be a single time, to the nearest minute if the expected change can be forecast to that degree of accuracy. Temporary (TEMPO) groups will not exceed four (4) hours. Probability (PROB) groups will be six (6) hours or less. More information on Change Groups can be found in the appendices.
- 4.13 <u>Sites With Scheduled Part-Time Observations</u>. For TAFs with LT 24-hour observational coverage, the TAF will be valid to the end of the routine scheduled forecast period even when observations end prior to that time. The time observations are scheduled to end and/or resume will be indicated by expanding the AMD NOT SKED statement. Expanded statements will include:
  - Observation ending time (AFT Y1Y1HHmm, e.g., AFT 120200),
  - Scheduled observation resumption time (TIL Y1Y1HHmm, e.g., TIL 171200Z) or
  - Period of observation unavailability (Y1Y1HH/YeYehh, e.g., 2502/2512).

TIL should be used only when the beginning of the scheduled TAF valid period coincides with the time of the last observation or when observations are scheduled to resume prior to the next scheduled issuance time. When used, these remarks will immediately follow the last forecast group. If a routine TAF issuance is scheduled to be made after observations have ceased, but before they resume, the remark AMD NOT SKED will immediately follow the valid period group of the scheduled issuance. After sufficient data using the total observation concept has been received, the AMD NOT SKED remark should be removed.

#### Examples:

```
TAF AMD

KRWF 150202Z 1502/1600 {TAF text}

AMD NOT SKED 1505/1518=

TAF AMD

KPSP 190230Z 1903/1924 {TAF text}

AMD NOT SKED=
```

- 4.14 <u>PROB and TEMPO Groups</u>. PROB and TEMPO groups are used to forecast potential or temporary changes to the forecast for specific windows of time. PROB and TEMPO are defined as follows:
  - a. PROB: Probability of occurrence of a thunderstorm or precipitation event, with associated weather elements as necessary (wind, visibility, and/or sky condition) whose occurrences are directly related to, and simultaneous with, the thunderstorm or precipitation event. Only PROB30 (30% probability of the specified element occurring) groups will be used in NWS TAFs.

b. TEMPO: Temporary fluctuations in forecast meteorological conditions which are expected to last less than one (1) hour in each instance and, in the aggregate, to cover LT half of the indicated period. The period of time covered by a TEMPO group should be the minimum necessary, not to exceed 4 hours. Use TEMPO groups for high probability (greater than 50%) expectations only.

Forecasters should remember the lowest meteorological condition contained in a TAF, regardless of any conditional language, including those forecasted in the PROB or TEMPO groups drive user operational decisions. PROB30 and TEMPO should describe short duration forecast weather changes and should be used as sparingly as possible.

5. <u>NWS Forecaster Liability</u>. The NOAA/NWS General Counsel advised that NWS forecasters are generally protected from liability when issuing TAFs employing the total observation concept:

NWS forecasters employ their discretion in issuing forecasts, including utilizing the "total observation concept" for writing and issuing TAFs. In the performance of their jobs, where NWS forecasters utilize their discretion, they are covered under the discretionary function exemption of the Federal Tort Claims Act, 28 U.S.C. §§ 2671 et seq.

- 6. <u>Records Retention</u>. Records of disseminated TAFs, including amendments, corrections, and delayed issuances, will be maintained in accordance with NWSI 10-2003, *Records Retention*.
- 7. Quality Assurance of TAFs. Performance reports to the office staff and stakeholders (airport managers/individual airlines) are encouraged to let them know how the office is supporting their mission. In aviation forecasting, the goal is to continually improve forecast service by identifying forecasting weaknesses and developing methods to strengthen those weaknesses. NWS uses Stats-on-Demand as the primary program for performing verification on TAFs and WFOs will verify their respective TAFs in this manner. The Aviation Focal Points (AFPs) may view individual stats for their forecasters. See NWSI 10-1601, Section 6.1.3. (NOTE: Verification is covered by two documents: NWSI 10-1601, Verification Process, and NWSM 10-1609, Verification Procedures and Methods.) Forecast and verification results tracked using the Stats-on-Demand verification program should never be used against forecasters.

## Appendix A Contractions Used in NWS TAFs

AAx Code used in the WMO abbreviated heading to indicate an amended TAF, where

x is the letter A through X (see Appendix D, Section 1.1). NOTE: AAx is not

used in the forecast text.

AFT After

AMD Amended TAF. Used in the forecast text only. AMD is not used in the WMO

abbreviated heading.

BC Patches

BKN Broken cloud layer (5 to 7 oktas cloud amount). Clouds may be transparent or

opaque. Lowest broken layer is implied to be the ceiling.

BL Blowing

BR Mist

CB Cumulonimbus cloud

CCCC Generic WMO format code group for a four-letter location identifier. Four-letter

location identifiers for specific airports are listed in ICAO document 7910,

Location Identifiers.

CCx Code used in

the WMO abbreviated heading to indicate a corrected forecast, where x is the letter A through X

(see Appendix D, Section 1.3). CCx is not used in the forecast text.

CLD Cloud

DR Low drifting

DS Dust storm

DU Dust

DZ Drizzle

FC Funnel cloud

FEW Few clouds (greater than 0 oktas to 2 oktas cloud amount)

FG Fog

FMYYGGgg From the date (YY) and time (UTC) indicated by GGgg. Generic WMO format

#### NWSI 10-813 April 5, 2012

code group, indicating a significant and rapid (in less than one hour) change to a new set of prevailing conditions. GG is in whole hours, gg is in minutes. See Appendix C, Section 1.2.9.1.

FU Smoke

FZ Freezing

G (Gust) Defined as rapid fluctuations in wind speed with a variation of 10 knots or more

between peaks and lulls within a 10 minute time period.

GR Hail (largest hailstone diameter GTE 1/4 inch)

GS Small hail and/or snow pellets (largest hailstone diameter LT 1/4 inch)

GT Greater than

GTE Greater than or equal to

HZ Haze

IC Ice crystals

KT Knots

LT Less than

LTE Less than or equal to

LTD Limited

MI Shallow

NSW No Significant Weather. An indication that significant weather conditions, as

expressed by WMO Code Table 4678, are forecast to end. See Appendix C,

Section 1.2.6.

OVC Overcast cloud layer [eight (8) oktas cloud amount]

P6SM Visibility forecast greater than six (6) statute miles

PL Ice pellets

PO Well-developed dust/sand whirls

PR Partial

PROBC2C2 Probability of occurrence of a thunderstorm (and associated precipitation) or

#### NWSI 10-813 April 5, 2012

precipitation event, along with associated weather elements (wind, visibility, and/or sky condition) directly related to the thunderstorm or precipitation event. C2C2 refer to the probability of the event. Only PROB30 is allowed. See Appendix C, Section 1.2.9.4.

PY Spray

RA Rain

RRx Code used in the WMO abbreviated heading to indicate a delayed TAF, where "x" is the letter A through X (Appendix D, Section 1.2). RRx is not used in the TAF

text.

SA Sand

SCT Scattered cloud layer [three (3) to four (4) oktas cloud amount]

SG Snow grains

SH Shower

SKC Sky clear. No clouds; zero oktas cloud amount. The contraction CLR is not used

in the TAF.

SKED Scheduled

SM Statute miles

SN Snow

SQ Squall

SS Sandstorm

TAF Terminal Aerodrome Forecast code format. The international standard for the

TAF code, FM 51-X Ext. TAF, is included in WMO Manual on Codes, WMO

No. 306, Volume I.1, Part A.

TEMPO Temporarily. Indicator of temporary fluctuations to forecast conditions which are

expected to last LT 1 hour in each instance and, in the aggregate, to cover LT half of the indicated period. The period of time covered by a TEMPO group should be the minimum necessary, not exceed four (4) hours. See Appendix C, Section

1.2.9.2.

TS Thunderstorm

VA Volcanic ash

VC Vicinity - it has two definitions:

NWS: A donut-shaped area encompassed between circles with radii of 5 and 10 SM, respectively, from the center of the runway complex of an airport. VC will only be used in the initial time period or in FM groups, all of which forecast prevailing conditions, and will only be used in combination with fog (FG), shower(s) (SH), and thunderstorm(s) (TS).

WMO: (An area encompassed) within eight (8) kilometers [five (5) statute miles] of the aerodrome but not at the aerodrome (Words in parentheses inferred. See Note 1 under WMO Regulation 15.8.10). Only used in METARs/SPECIs.

VIS Visibility

VRB Variable wind direction. Wind direction is considered variable when it is impossible to forecast a mean wind direction due to its expected variability, e.g., for very light winds [LTE six (6) knots] or during convective activity.

VV Vertical Visibility

Z Indicator letter (an abbreviated symbol for Coordinated Universal Time - UTC) appended to the date-time of forecast origin group.

### Appendix B TAF Code Elements

Ta	Table of Contents		
1.	Terminal I	Forecast Coding	12
		etin Headings	
	1.2 Forecast Text		13
	1.2.1	Location Identifier.	13
	1.2.2	Date/Time of Forecast Origin Group	13
		Valid Period and Routine Issuances.	
	1.2.4	Wind Group	14
		1.2.4.1 Wind Gusts	
		1.2.4.2 Wind Direction	14
		1.2.4.3 Variable Wind	
		1.2.4.4 Squalls	14
	1.2.5	Visibility Group	
		1.2.5.1 Tall Tower	16
	1.2.6	Significant Weather Group	16
		1.2.6.1 Examples of Encoding Multiple Precipitation Types	17
		1.2.6.2 Qualifiers	
		1.2.6.3 Visibility as Significant Weather	19
		1.2.6.4 Vicinity	
	1.2.7	Cloud and Vertical Obscuration Groups	21
		1.2.7.1 Cloud Group	
		1.2.7.2 Vertical Obscuration Group	22
		1.2.7.3 Cloud Type	
	1.2.8	Non-Convective LLWS Group	23
	1.2.9	Forecast Change Indicator Groups	
		1.2.9.1 Special Thunderstorm Consistency Guidance	24
		1.2.9.2 FMYYGGgg	
		1.2.9.3 TEMPO Y1Y1GG/YeYeGeGe	
		1.2.9.4 PROBC2C2 Y1Y1GG/YeYeGeGe	26

- 1. <u>Terminal Forecast Coding</u>. Each group of the TAF code used in NWS TAFs is described in the following sections. Each section includes partial or complete examples of one or more TAFs to clarify descriptions in the text.
- 1.1 <u>Bulletin Headings</u>. TAF bulletins begin with a WMO heading where the four letter ICAO identifier is the issuing office. For example:

FTUS42 KMFL 141100 AAx TAFFLL TAF (AMD) or (COR) KFLL 141123Z 1412/1512 etc...

FT TAF whose valid period exceeds 12 hours

US Denotes CONUS airport location

42 CONUS group location (usually by geographical area)

KMFL Issuing WFO

141100 First 2 digits are issuance date; the last four are cardinal hour prior to forecast

valid hour, required to meet international requirements for scheduled TAFs.

AAx Used to identify a non-scheduled TAF (corrections, delayed TAFs, amendments,

etc.). If not used, simply omit (as in regularly scheduled TAFs). The indicators used are AAx for TAF amendments, RRx for delayed routine TAFs, and CCx for corrections of previously transmitted TAFs. The x is the letter A through X, used sequentially which indicate the subsequent use of the heading. For example, the

first correction would be CCA, the second CCB, etc.

TAFFLL First three (3) letters identify a TAF, the last three are the site the TAF is for (this

line is deleted when the gateway collects TAFs after transmission for

disbursement as a group).

TAF (AMD/COR) Identifies TAF as the product (AMD indicates an amendment/COR

indicates correction)

KFLL ICAO identifier of the TAF site

141123Z Time of preparation 1412/1512 Valid time of new TAF

ICAO location identifiers in the CONUS begin with the letter K, those in the North Pacific (Hawaii, Alaska, and Guam) begin with a P, those in the Caribbean (Puerto Rico, Virgin Islands, etc.) begin with a T, and those in the South Pacific begin with an N.

1.2 <u>Forecast Text</u>. The first line of text in a TAF consists of the contraction TAF or TAF AMD or TAF COR. This indicates if the product is scheduled, amended, or corrected. This information appears only once, on a separate line at the beginning of the product, regardless of how many TAFs it contains. Delayed TAFs are not identified in the text; that information is included at the end of the first line on the WMO header.

The format of text in a NWS TAF is comprised of code groups shown below. Each term and group is described in Sections 1.2.1 through 1.2.9 below and in the same sequence as they are required to appear in each forecast group.

#### GENERIC FORMAT OF THE FORECAST TEXT OF A NWS-PREPARED TAF

{TAF or TAF AMD or TAF COR}

CCCC YYGGggZ YlY1G1G1/Y2Y2G2G2 dddffGfmfmKT VVVV w'w' (NSW) VVhshshs (SKC)

WShwshws/dddftKT TTGGgg FMY1Y1GGGeGe TEMPO Y1Y1GG/YeYeGeGe PROB30Y1Y1GG/YeYeGeGe

- 1.2.1 <u>Location Identifier (CCCC)</u>. After the line containing either TAF or TAF AMD or TAF COR, each TAF will begin with its four-letter ICAO location identifier. ICAO Document 7910 contains a complete list of all identifiers.
- 1.2.2 <u>Date/Time of Forecast Origin Group</u>. The date/time of forecast origin group (YYGGggZ) follows the terminal's location identifier. It contains the day of the month in two (2) digits (YY) and time in four (4) digits (GGgg in hours and minutes) the forecast is completed and ready for

transmission, with a Z appended to denote UTC. This time is entered by the forecaster. Section 4.9 of this instruction contains a table of issuance time windows for scheduled TAFs.

1.2.3 <u>Valid Period and Routine Issuances</u>. The TAF valid period (Y1Y1G1G1/Y2Y2G2G2) is the next group. The first two digits (Y1Y1) are the day of the month for the start of the TAF. The next two digits (G1G1) are the starting hour. Y2Y2 is the day of the month for the end of the TAF, and the last two digits (G2G2) are the ending hour of the valid period. A forecast period that begins at midnight UTC will be annotated as 00. If the end time of a valid period is at midnight UTC, it is annotated as 24. For example, a 00Z TAF issued on the 9<sup>th</sup> of the month would have a valid period of 0900/0924.

A TAF issued at one of the airports designated to have a 30-hour valid period will also be formatted Y1Y1G1G1/Y2Y2G2G2. For example, a 00Z TAF issued on the 11<sup>th</sup> of the month for 30 hours would have a valid period of 1100/1206.

1.2.4. <u>Wind Group</u>. The initial time period and any subsequent FM groups will begin with a mean surface wind forecast (dddffGfmfmKT) for that period. Wind forecasts will be expressed as the mean three-digit direction (ddd - relative to true north) rounded to the nearest ten degrees and the mean wind speed in knots (ff) for the time period.

The forecaster should strive to forecast a mean wind direction with low wind speeds if weather is expected to, or has already impacted the TAF site. Wind direction forecasts, even at low speeds, can be critical if the runway(s) are contaminated by ice, snow, or water, creating tighter tailwind and crosswind aircraft tolerances. There are no amendment criteria for low wind speed conditions (see Section 4.5.1).

- 1.2.4.1 <u>Wind Gusts</u>. If wind gusts, defined as rapid fluctuations in wind speeds with a variation of 10 knots or more between peaks and lulls, are forecast, they are indicated immediately after the mean wind speed by the letter G, followed by the peak gust speed expected. KT is appended to the end of the wind forecast group. Any wind speed of 100 knots or more will be encoded in three digits. Encode calm winds as 00000KT.
- 1.2.4.2 <u>Wind Direction</u>. The prevailing wind direction will be forecast for any speed greater than or equal to seven (7) knots.
- 1.2.4.3 <u>Variable Wind</u>. The forecast wind direction will be encoded as VRBffKT when forecasting a prevailing surface wind direction is not possible due to its expected variability (variations in wind direction GTE 30 degrees). Meteorologists should avoid using VRB and provide the best forecast direction possible. This enables users to use the wind group for planning purposes. If necessary, two conditions where this can occur are very light winds and convective activity. Variable wind direction for very light winds should have a wind speed of one (1) through six (6) knots inclusive. For convective activity, the wind group may be encoded as VRBffGfmfmKT, where Gfmfm is the maximum expected wind gusts. VRB will not be used in the non-convective LLWS group (refer to Section 1.2.8).

When forecasting variable wind direction, there is no requirement to specify direction variability limits in remarks.

1.2.4.4 <u>Squalls</u>. Squalls are forecast in the wind group as gusts (G), but should be identified in the significant weather group with the code SQ (Appendix B, Section 4, Footnote 19).

#### **EXAMPLES:**

TAF

KPIT 231732Z 2318/2418 23010KT 4SM -SHRA BKN030 FM232200 28020G35KT P6SM OVC020 FM232330 30015KT P6SM SCT060 TEMPO 2401/2404 BKN060 FM240500 30004KT P6SM SCT080=

The above example demonstrates rapid changes in wind associated with a frontal passage. Also note the correct format for gusts.

TAF

KCSG 060537Z 0606/0706 VRB03KT etc.=

This example above shows the correct format and use of variable wind direction with light winds at the beginning of the valid period (0600 UTC).

TAF

KROW 021726Z 0218/0318 30008KT 5SM HZ BKN030 PROB30 0304/0306 27020G45KT 1SM TSRA OVC012CB etc.=

This example above depicts using high winds in an organized event.

TAF

KAMA 171130Z 1712/1812 00000KT etc.=

This example above shows the correct format for calm winds.

TAF

PASN 010530Z 0106/0206 080100G140KT etc.=

This example above shows the correct format of wind speed of 100 knots or more with the wind from 80 degrees at 100 knots gusting to 140 knots.

TAF

KORD 161725Z 1618/1718 27020G35KT P6SM TS FEW020CB TEMPO 1618/1619 29040G56KT SQ FM161930 30015G25KT P6SM etc.=

This example shows the correct format for squalls.

1.2.5 <u>Visibility Group</u>. The initial time period and any subsequent FM groups will include a visibility forecast (VVVV) in statute miles. The valid values for visibility forecasts in NWS TAFs are shown below. Visibility will be forecast rounded down to the next lowest reported

value. The contraction SM is appended to the end of the visibility forecast group.

Visibility Fore	ecast Values in	
Statute Miles (SM)		
0	1/4	
1/2	3/4	
1	11/2	
2	3	
4	5	
6	P6SM	

When the prevailing visibility is forecast to be less than or equal to six (6) SM, one or more significant weather groups (see Section 1.2.6) will be included. However, drifting dust (DRDU), drifting sand (DRSA), drifting snow (DRSN), shallow fog (MIFG), partial fog (PRFG), and patchy fog (BCFG) may be forecast with prevailing visibility greater than or equal to seven (7) statute miles.

When a whole number and a fraction are used to forecast visibility, a space will always be included between them (e.g., 1 1/2SM). Visibility greater than six (6) statute miles will be encoded as P6SM.

Prevailing visibility as described by Federal Meteorological Handbook No. 1 (FMH-l), will be used if the visibility is not expected to be the same in different directions.

When VA is forecast in the significant weather group, visibility will be included in the forecast, even if it is unrestricted (P6SM). For example, an expected reduction of visibility to 10 statute miles by volcanic ash will be encoded in the forecast as P6SM VA.

- 1.2.5.1 <u>Tall Tower Airports</u>. Tall tower airports report the lower visibility of tower or surface visibility as the prevailing visibility in the main body of the observation with the higher visibility in the remarks section. Forecasters need to monitor these airport observations closely to maintain awareness of the surface visibility.
- 1.2.6 <u>Significant Weather Group</u>. The significant weather group (w'w') consists of the appropriate qualifier(s) and weather phenomenon contraction(s) (shown in Appendix B, Section 3 and described in FMH-1) or NSW, and Section 4 of Appendix B shows all possible valid combinations of weather phenomena codes and should be used to encode w'w'.

Forecasters will use their judgment when determining how many weather phenomena groups are included. NWS forecasters may include up to three separate w'w' groups if necessary to accurately describe the expected conditions. Forecaster judgment will be used to resolve situations not addressed by these guidelines.

The following guidance should be used for this group:

• If the initial forecast period and subsequent FM groups do not contain an explicit significant weather group, the significant weather group will be omitted.

- Do not use NSW in the initial forecast time period or FM groups.
- Tornadic activity, including tornadoes, waterspouts, and funnel clouds, should only be included in TAFs when absolutely necessary. Although the probability of occurrence at a specific site is low, it is possible.
- One or more significant weather group(s) is (are) required when the visibility is forecast to be 6SM or less (see Section 1.2.5).
- With the exception of VA, DRDU, DRSA, DRSN, MIFG, PRFG, and BCFG, obstructions to vision are only forecast when the prevailing visibility is less than 7 statute miles or, in the judgment of the forecaster, is considered operationally significant.
- VA will always be forecast when expected. When VA is included in the significant weather group, visibility will be included in the forecast as well, even if the visibility is unrestricted (P6SM).
- NSW will be used in place of w'w' in a TEMPO group (Section 1.2.9.2) to indicate when significant weather included in a previous subdivided group is expected to end. This includes vicinity.
  - o After NSW is used in a significant weather group, any subsequent significant weather groups will either be omitted or selected from the phenomena listed in Appendix B, Section 4.
  - o No two consecutive TEMPO groups will contain NSW as the significant weather group.
  - o P6SM NSW will be used together in a TEMPO group when the significant weather is forecast to end and the visibility is forecast to be greater than 6 statute miles after, regardless of visibility before the TEMPO event.
- When more than one type of significant weather is forecast in the same forecast time period, the order will be:
  - o Thunderstorms with/without associated precipitation.
  - o Significant weather in order of decreasing dominance based on intensity.
  - o Left to right in Appendix B, Section 3 (columns 1 through 5.
- Non-precipitation significant weather elements are encoded after any precipitation, in their own group, separated by a space (e.g., -SHSN BLSN BR). The same is true for encoding w'w' groups: first, the appropriate qualifier for intensity or proximity, then the appropriate contraction for the descriptor, and finally the contraction for the observed weather phenomenon or combinations thereof, all without any spaces.
- Multiple precipitation elements are encoded in a single group (e.g., -TSRASN).
  - o up to three appropriate precipitation contractions can be combined in a single group (with no spaces) with the predominant type of precipitation being first.
  - o In this single group, the intensity will refer to the total precipitation and be used with either one or no intensity qualifier.
    - The intensity qualifiers (light, moderate, and heavy) refer to the intensity of the precipitation and not to the intensity of any thunderstorms associated with the precipitation.
- 1.2.6.1 Exception for encoding multiple precipitation types. When more than one type of precipitation is forecast in a time period, any precipitation type associated with a descriptor (e.g., FZRA) should be encoded first in the precipitation group, regardless of the predominance or intensity of the other precipitation types. Descriptors will not be encoded with the second or third precipitation type in the group. The intensity is associated with the first precipitation type

of a multiple precipitation type group.

For example, a forecast of heavy snow and light freezing rain is properly coded as -FZRASN, even though the intensity of the snow is greater than the freezing rain. This is why the descriptor (FZ) and the intensity is associated with this precipitation type should be encoded first. In this example, since heavy snow is forecast, it would have to be inferred by a visibility forecast of less than 1/4SM.

- 1.2.6.2 <u>Qualifiers.</u> A qualifier will precede (with no space) the phenomena including descriptor to which it applies. There are two categories of qualifiers (see Appendix B, Section 3): intensity/proximity or descriptor. Except for VCSH and VCTS, only one intensity or proximity qualifier and descriptor will be used for each weather phenomena group. The intensity qualifiers are light (-), moderate (no qualifier), and heavy (+).
  - Refer to FMH-l for criteria in determining intensity associated with these weather elements. Intensity will be coded with precipitation types using the following guidance:
  - ice crystals and hail will not have an intensity qualifier.
  - No intensity will be ascribed to
    - o blowing dust (BLDU),
    - o blowing sand (BLSA),
    - o blowing snow (BLSN)
    - o thunderstorms
    - o ice crystals
    - o hail.
  - Only moderate or heavy intensity will be ascribed to sandstorm (SS) and dust storm (DS).

If a significant weather code group has been used and conditions are forecast to change, the significant weather entry in the next TEMPO group (Section 1.2.9.2) should be a different code group or NSW. If the significant weather group does not differ in subsequent TEMPO groups, no change to the significant weather group is necessary and the current significant weather group will apply.

EXAMPLES (combinations of one precipitation and one non-precipitation weather phenomena):

-DZ FG	Light drizzle and fog (obstruction which reduces visibility to LT 5/8 SM)
RA BR	Moderate rain and mist (obstruction which reduces visibility to LT 7 SM but GTE 5/8 SM)
-SHRA FG	Light rain showers and fog (visibility LT 5/8 statute miles)
+SN FG	Heavy snow and fog

EXAMPLES (showing combinations of more than one type of precipitation:

**-RASN FG HZ** Light rain and snow (light rain predominant), fog and haze

**TSSNRA** Thunderstorm with moderate snow and rain (moderate snow

predominant)

**FZRASNPL** Moderate freezing rain, snow, and ice pellets (freezing rain

mentioned first due to the descriptor, followed by other

precipitation types in order of predominance)

**SHSNPL** Moderate snow showers and ice pellets

**EXAMPLE TAF:** 

TAF

KFAR 091739Z 0918/1018 21030G60KT 1/4SM +TSRAGR BKN050CB...

Winds southwest at 30 knots, with gusts to 60 knots. Visibility 1/4 SM, thunderstorm (severe because of 60KT gusts) with heavy rain and hail. NOTE: the + qualifier is associated with the precipitation (RA) and not the thunderstorm. Broken cumulonimbus (CB) clouds (ceiling) at 5,000 feet.

In the following cases the TS descriptor is treated differently than other descriptors:

1) When dry thunderstorms are forecast, TS may be encoded as the sole significant weather phenomenon; and 2) When forecasting thunderstorms with freezing precipitation (FZRA or FZDZ), include the TS descriptor first, followed by the intensity and weather phenomena.

See the following example:

**EXAMPLE:** 

TAF

KMCI 252335Z 2600/2700 31015KT 1 1/2SM TS -FZRA BKN010CB...

Winds northwesterly at 15 knots. Visibility 1 1/2 SM, thunder with light freezing rain, broken CB clouds (ceiling) at 1,000 feet.

When a TS is included in the significant weather group (even in vicinity - VCTS), the cloud group (NsNsNshshsh) will include a forecast cloud type of CB. See the following example for encoding VCTS:

TAF

KMCI 252335Z 2600/2700 31015KT 1 1/2SM -FZRA VCTS BKN010CB...

Winds northwesterly at 15 knots. Visibility 1 1/2 SM and light freezing rain, broken CB clouds (ceiling) at 1,000 feet, TS in the vicinity.

1.2.6.3 Visibility as Significant Weather. A visibility threshold should be met before a forecast

for fog (FG) may be included in the TAF. When forecasting a fog-restricted visibility from 5/8SM to 6SM, the phenomena will be coded as BR (mist). When forecasting a fog-restricted visibility that is LT 5/8SM, use code FG. Never encode weather obstruction as mist (BR) when the forecast visibility is GT 6 statute miles (P6SM).

The following fog-related terms will only be used as described below:

Freezing Fog (FZFG): Any fog (visibility LT 5/8 SM) consisting predominantly of water

droplets at temperatures LTE 32°F/0°C, whether or not rime ice is expected to be deposited. FZBR is not a valid significant weather

combination and will not be used in TAFs.

Shallow Fog (MIFG): The visibility at 6 feet above ground level is GTE 5/8 SM and the

apparent visibility in the fog layer is LT 5/8 SM.

Patchy Fog (BCFG): Fog patches covering part of the airport. The apparent visibility in

the fog patch or bank is LT 5/8 SM, with the foggy patches

extending to at least 6 feet above ground level.

Partial Fog (PRFG): A substantial part of the airport is expected to be covered by fog

while the remainder is expected to be clear of fog (e.g., a fog bank).

NOTE: MIFG, PRFG and BCFG may be forecast with prevailing visibility of P6SM.

#### **EXAMPLES:**

#### TAF

KLWS 020530Z 0206/0306 27010KT 1/2SM FG VV008 FM021100 27010KT 3SM BR BKN010...

This example shows the proper use of FG and BR. When significant weather is not expected in a FM group, the significant weather group is omitted.

#### TAF

KBIL 211140Z 2112/2212 04005KT 1SM -RA BR OVC008 FM211715 34008KT 3SM -RA BKN050 etc.=

Change is expected at 1715Z. NOTE: The light rain is repeated in the FM211715 group to indicate that light rain remains in the forecast. The mist is omitted from the FM211715 group, which indicates it is forecast to end at 1715Z.

#### TAF

KMPV 021130Z 0212/0312 04006KT 3SM -DZ OVC008 FM021800 36010KT P6SM SCT025...

Conditions improve at 1800Z to winds from 360 degrees at 10 knots, visibility GT 6SM (unrestricted), and no significant weather.

1.2.6.4 <u>Vicinity</u>. In the United States, vicinity (VC) is defined as a donut-shaped area between 5 and 10SM from the center of the airport's runway complex. The FAA requires TAFs to include certain meteorological phenomena which may directly affect flight operations to and from the airport. Therefore, NWS TAFs should include prevailing condition forecasts of fog, showers and thunderstorms in the airport's vicinity (GTE 50% probability and expected to occur for more than ½ of the sub-divided forecast time period) in the significant weather section of the TAF. Prevailing conditions are forecast in the initial time period and FM groups. Significant weather in the vicinity will not be included in TEMPO or PROB groups.

The following significant weather phenomena are valid for use in prevailing portions of NWS TAFs in combination with VC:

Phenomenon	Coded as**
Fog*	VCFG
Shower(s)	VCSH
Thunderstorm	VCTS

<sup>\*</sup>Always coded as VCFG regardless of visibility in the obstruction, and without qualification as to intensity or type (frozen or liquid)

1.2.7 <u>Cloud and Vertical Obscuration Groups</u>. The initial forecast period and any subsequent FM groups will include a cloud group (NsNsNshshs) used as appropriate to indicate the cumulative amount (NsNsNs) of all cloud layers in ascending order and height (hshshs) or to indicate a clear sky (SKC) and an obscuration if appropriate to indicate vertical visibility (VVhshshs) into a surface-based obstructing medium.

All cloud layers and obscurations will be considered opaque, defined as when more than 50% of the sky is hidden by the clouds at any layer.

1.2.7.1 <u>Cloud Group</u>. The cloud group (NsNsNshshs) will be used to forecast cloud amount for the airport and its vicinity out to 10 NM as follows:

Sky Cover Contraction	Sky Coverage
SKC	0 oktas
FEW	1 to 2 oktas
SCT	3 to 4 oktas
BKN	5 to 7 oktas
OVC	8 oktas

When zero (0) oktas is forecast, the cloud group will be replaced by SKC. The contraction CLR, which is used in the METAR code, will not be used in TAFs.

Height of cloud (hshshs) will be forecast in hundreds of feet AGL at the following resolution:

<sup>\*\*</sup>The VC group, if used, should be the last entry in any w'w' group.

NWSI 10-813 April 5, 2012

Range of Height Values	Reportable Increment
LT 3,000	To nearest 100
GTE 3,000 but LT 5,000	To nearest 500
GTE 5,000	To nearest 1,000

In general, the number of cloud layers in each sub-divided time period should not exceed three.

Additionally, scattered cloud layers will not be forecast at a higher level than broken or overcast cloud layers, and broken cloud layers will not be forecast at a higher level than overcast layers. Using the principle of at/below, the lowest level at which the cumulative cloud cover equals 5/8 or more of the celestial dome is understood to be the forecast ceiling. For example, VV008, BKN008 or OVC008 all indicate an 800 foot ceiling.

1.2.7.2 <u>Vertical Obscuration Group</u>. The vertical obscuration group (VVhshshs) is used to forecast, in hundreds of feet AGL, the vertical visibility (VV) into a surface-based total obscuration. VVhshshs is this ceiling at the height indicated in the forecast. TAFs will not include forecasts of partial obscurations (i.e., FEW000, SCT000, or BKN000).

#### **EXAMPLE:**

TAF
KCPR 110537Z 1106/1206 24015KT P6SM SKC
FM110820 24015KT 1SM BR VV008...

Note that the wind in the FM group is the same as in the initial forecast period, but is repeated since all elements are required to be included in a FM group.

1.2.7.3 <u>Cloud Type</u>. The only cloud type included in the TAF is CB. CB follows cloud or obscuration height (hshshs) without a space. Whenever TS are included in w'w', even if TS are only forecast in the vicinity (VCTS), CB should be included in NsNsNshshshs or VVhshshs. CB may only be mentioned in the TAF when TS or VCTS is mentioned. CB may not be used alone, as it can be confusing to the users and cause difficulty in air traffic planning.

#### **EXAMPLES**:

TAF

KORD 110537Z 1106/1206 06008KT P6SM FEW050 SCT100 FM111115 11010KT 2SM -RA OVC012...

Note the initial forecast period (beginning at 0600Z) does not contain w'w'. When significant weather is not expected in the initial period of an FM group, w'w' is omitted.

TAF
KDAY 221730Z 2218/2318 19010G25KT P6SM BKN040
FM222230 26025G45KT 1/2SM TSSN OVC010CB...

Significant change at 2230Z to wind from 260 degrees at 25 knots gusting to 45 knots, visibility ½ SM in a thunderstorm with moderate snow, overcast clouds (ceiling) at 1,000 feet, including

CB.

TAF

KSYR 230532Z 2306/2406 29012KT 1/2SM SHSN FZFG OVC003 TEMPO 2306/2309 29014G28KT 1/4SM +TSSNPL BLSN VV004CB FM231445 36011KT P6SM FEW008 BKN025 FM232300 VRB03KT P6SM SKC...

Significant change at 1445Z to wind from 360 degrees at 11 knots, visibility GT 6 SM (unrestricted), few clouds at 800 feet and broken clouds at 2,500 feet. Change at 2300Z to variable wind direction (light winds), wind speed 3 knots, and clear skies.

1.2.8 Non-Convective LLWS Group. Forecasts of LLWS in the TAF will refer only to non-convective LLWS from the surface up to and including 2,000 feet AGL (LLWS is always assumed to be present in convective activity). It will be included in TAFs on an as-needed basis to focus the aircrew's attention on LLWS problems which currently exist or are expected. Non-convective LLWS may be associated with the following: frontal passage, inversion, low-level jet, lee side mountain effect, sea breeze front, Santa Ana winds, etc. Mentioning LLWS whenever conditions are present or possible to occur is highly encouraged as it provides the TAF user with valuable information.

LLWS should be included in the TAF if a value of 30kts or greater is determined. The height of the WS should be encoded in the TAF as follows; Example WS018/27055kts, thus, inferring that the LLWS starts at 1,800 feet and persists to the surface.

If LLWS is not in the TAF, but one or more of the PIREPs are received of non-convective LLWS within 2000 feet of the surface, causing an indicated air speed loss or gain of 20 knots or more, the forecast should be amended to include LLWS.

If meteorological conditions are such that non-convective LLWS of intensities similar to those described above are expected and/or could be inferred from less detailed PIREPs or other sources, the forecaster should include a WS group in either the initial time period, or a FM group of the TAF.

When LLWS conditions are expected, the non-convective LLWS code WS will be included in the TAF as the last group (after cloud forecast). Once in the TAF, the WS group remains the prevailing condition until the next FM change group or the end of the TAF valid period. Forecasts of non-convective LLWS will not be included in TEMPO or PROB groups.

The format of the non-convective low-level wind shear group is WShwshwshws/dddffKT, where:

WS Indicator for non-convective LLWS

hwshwshws Height of the top of the WS layer in hundreds of feet AGL

ddd True direction in ten degree increments at the indicated height (see Note

below)

ff Speed in knots of the forecast wind at the indicated height

KT Unit indicator for wind

NOTE: VRB will not be used for direction in the non-convective LLWS forecast group.

#### **EXAMPLE:**

TAF

KPUB 181122Z 1812/1912 13012KT 5SM -RA SCT010 OVC035 WS020/27055KT

FM181400 32010KT P6SM FEW008 BKN045

In this forecast, the wind shear is a prevailing condition from 1200Z until the beginning of the next FM group. The same is true for the following example, except it's prevailing from 0600Z until the beginning of the next FM group.

TAF

KDFW 220539Z 2206/2306 21010KT 3SM BR SCT030 WS015/29065KT FM221100 24015KT 1SM TSRA BR OVC010CB FM221830...

In both examples above, the indicator "WS" is followed by a three-digit number which is the top of the wind shear layer (KPUB - 020, KDFW - 015). LLWS is forecast to be present from the surface to this level. After the solidus (/), the five digit wind group is the wind direction and speed at the top of the wind shear layer. It is not a value for the amount of shear.

- 1.2.9 <u>Forecast Change Indicator Groups</u>. Forecast change indicator groups, FMYYGGgg and TEMPO YYGG/YeYeGeGe, are contractions which will be used to sub-divide the forecast period (24 or 30-hours for scheduled TAFs; less for amended or delayed forecasts) according to significant changes in the weather. Forecasters should be aware conditions described in TEMPO and PROB30 groups have just as much effect on user decisions as the prevailing conditions and should be used sparingly.
- 1.2.9.1 <u>Special Thunderstorm Consistency Guidance</u>. To ensure consistency between forecasts, forecasters will use the following guidance:

When the Collaborative Convective Forecast Product (CCFP) forecasts thunderstorms with high confidence and medium coverage at an FAA Core Airport, thunderstorms should be mentioned in the TAFs. TEMPO can be used in the first 9 hours of the TAF and PROB30 for thunderstorms can be used in the later periods. When the CCFP forecasts high confidence and/or high coverage at the FAA Core Airports, thunderstorms should be forecast as prevailing conditions or TEMPO.

When the Public Forecast has 60% chance of thunderstorms or greater, forecasters should include thunderstorms in the TAFs at all TAF sites.

1.2.9.2 <u>FMYYGGgg</u>. The FM change indicator group (FMYYGGgg) will be used to indicate when prevailing conditions are expected to change significantly over a period of less than one hour. In these instances, the forecast will be sub-divided into time periods using the contraction FM followed, without a space, by four digits indicating the time (in hours and minutes in UTC)

the change is expected to occur. While the use of a four-digit time in whole hours (e.g., 2100) is acceptable, if a forecaster should make every effort to forecast changes with higher temporal resolution. All forecast elements following FMYYGGgg will relate to the period of time from the indicated time (GGgg) to the end of the valid period of the terminal forecast, or to the next FMYYGGgg if the terminal forecast valid period is divided into additional periods.

The FM group will be followed by a complete description of the weather and all forecast conditions given before the FMYYGGgg group are superseded by those following the group. All elements of the TAF (surface wind, visibility, significant weather, clouds, obscurations, and when expected, non-convective LLWS) will be included in each FM group, regardless if they are forecast to change or not. The only exception to this involves significant weather. If no significant weather is expected in the FM time period group, then significant weather is omitted. For example, if forecast cloud and visibility changes warrant a new FM group but the wind does not, the new FM group will include a wind forecast, even if it is the same as the most recently forecast wind.

One or more FM groups may be included depending on the prevailing weather conditions expected. In the interest of clarity, each FM group will start on a new line of forecast text, indented five spaces.

#### **EXAMPLES:**

TAF

KDSM 022336Z 0300/0400 20015KT P6SM BKN015 FM030230 29020G35KT 1SM +SHRA OVC005 TEMPO 0303/0304 30030G45KT 3/4SM -SHSN FM030500 31010G20KT P6SM SCT025...

Note that significant weather is omitted from the initial forecast period, beginning at 0000 Z, since none was expected.

```
TAF
```

```
KAPN 312330Z 0100/0200 13008KT P6SM SCT030
FM010320 31010KT 3SM -SHSN BKN015
FM010500 31010KT 1/4SM +SHSN VV007...
```

Note the wind in the FM010500 group is the same as the previous FM group, but is repeated since all elements are required to be included in a FM group.

1.2.9.3 <u>TEMPO YYGG/YeYeGeGe</u>. The TEMPO change-indicator group (TEMPO YYGG/YeYeGeGe) will be used to indicate temporary fluctuations to forecast meteorological conditions which are expected to:

- a. Have a high percentage (greater than 50%) probability of occurrence and,
- b. Last for one hour or less in each instance and,
- c. In the aggregate, to cover less than half of the period YYGG to YeYeGeGe.

Temporary changes described by TEMPO groups occur during a period of time defined by a two-digit beginning and two-digit ending time, both in whole hours (GMT or Zulu). If the TEMPO

condition is expected to last more than one (1) hour, a FMYYGGgg group should be used to forecast conditions different from those forecast prior to GG. If the TEMPO condition is expected to last more than half the time period indicated (YYGG/YeYeGeGe), then the TEMPO condition is considered predominant and should instead be entered in the initial forecast period, or following a FM group. TEMPO groups will not exceed four hours.

The TEMPO group should be placed on a new line in the TAF within the first six hours of the TAF, indented six (6) spaces from the left margin. The TEMPO identifier is followed by a description of all the elements in which a temporary change is forecast. A previously forecast element which has no change during the TEMPO period is understood to remain the same. Only those weather elements forecast to temporarily change are required to be included in the TEMPO group. However, when a significant reduction in visibility is forecast in a TEMPO group, the significant weather causing the deterioration will also be included. If a significant change is expected in the cloud forecast, all cloud layers, including any significant layer not expected to change will be given.

Consecutive TEMPO groups will not be used during the initial forecast period or following any subsequent FM group(s). TEMPO groups will not include forecasts of either significant weather in the vicinity (VC) or non-convective LLWS.

#### **EXAMPLES**:

TAF

KDDC 221130Z 2212/2312 29010G25KT P6SM SCT025 TEMPO 2215/2217 30025G35KT 1 1/2SM SHRA BKN010...

TAF

KSEA 091125Z 0912/1012 19008KT P6SM SCT010 BKN020 OVC090 TEMPO 0912/0915 -RA SCT010 BKN015 OVC040...

Note the TEMPO 0912/0915 group. All three cloud layers are included though the lowest layer is not forecast to change from the initial time period.

TAF

KBOI 091735Z 0918/1018 24007KT P6SM SCT025 BKN040 TEMPO 0918/0922 -SHSN BKN025 BKN040...

1.2.9.4 <u>PROB30 YYGG/YeYeGeGe</u>. The PROB30 group (PROB30 YYGG/YeYeGeGe) will only be used to forecast a 30 percent chance of occurrence of a thunderstorm or precipitation event and its associated weather and obscuration elements (wind, visibility and/or sky condition) when occurrence of those elements are directly related to the thunderstorm or precipitation event. Although the TAF area is limited to a 5SM mile radius from the center of a runway complex, forecasters should maintain forecast consistency between the TAF and other aviation and public products to reduce confusion for the users.

The PROB30 group will not be used within in the first nine (9) hours of the TAF valid period. Only one PROB30 group will be used in the initial forecast period and in any subsequent FM group.

PROB30 is followed by a space, then eight digits (YYGG/YeYeGeGe) stating the beginning and ending time (in hours) of the expected condition. <u>PROB30 is the only PROB group used in NWS TAFs.</u>

The PROB30 group will be located within the same line of the prevailing condition group, continuing on the line below if necessary.

PROB30 groups will not include forecasts of significant weather in the vicinity (VC) or non-convective LLWS.

The PROB30 group will not be used by NWS offices as a direct modifier of TEMPO. Similarly, TEMPO groups may not be used by NWS offices as a direct modifier of the PROB30 group e.g., TEMPO PROB30 YY23/YeYe24.

#### Appendix C Unscheduled TAFs.

#### **Table of Contents**

1.	Unscheduled TAFs	28
	1.1 Amended TAFs	28
	1.2 Amendment Coding	
	1.3 Amendment Criteria.	
	1.3.1 Categorical Amendment Criteria	30
	1.3.2 Additional U.S. TAF Amendment Criteria	
2.	Delayed TAFs	31
	Corrected TAFs	
	3.1 Correcting Amended or Delayed Forecasts	

1. <u>Unscheduled TAFs</u>. Unscheduled TAFs are issued on an as-needed basis as amended, delayed, or corrected messages. They contain the same elements and use the same format as scheduled issuances. The only differences are the date and time of forecast origin (YYGGgg) and beginning valid times (for amended and delayed forecasts only). The entire text of each individual TAF which has not yet expired, not just the amended, corrected, or delayed portion, will be transmitted.

Amended, delayed, and corrected forecasts will include the appropriate BBB group in the WMO abbreviated heading. Amended (AAx), delayed (RRx), and corrected (CCx) forecasts are counted (lettered) independently. For example, the first correction to a scheduled forecast would be CCA. If that same corrected forecast needed to be amended, the amendment would be AAA, indicating it is the first amendment of the scheduled TAF, etc. The following table demonstrates the procedures for multiple combinations of corrected, amended and delayed TAFs:

Time (UTC)	Forecast Issued	BBB Indicator
0615	First delayed terminal forecast	RRA
0714	First amendment to terminal forecast	AAA
1042	Second amendment to terminal forecast	AAB
1045	First correction to terminal forecast	CCA

1.1 Amended TAFs. Amendments (AMDs) are an effective method to optimize the quality of the TAF. Forecasters should remember the TAF is designed for the end user. The sooner the forecaster provides an amended TAF to the end user, the better. Unforeseen weather changes can have a rippling effect with delays in the NAS. The decision to amend the TAF relies on the forecaster's assessment of existing conditions and expectations. If conditions change earlier or later than forecast but the TAF shows the expected trend and will soon recover, an amendment may not be needed. Additionally, small fluctuations in the observation should not result in a minor adjustment to the TAF (chasing the observation). However, if improving weather conditions occur sooner than forecast, then an amended TAF is recommended. Further, forecasters should exercise good judgment when using automated observations. Because of their sensitivity, AWOS/ASOS observation data are more likely to fall outside the forecast amendment

ranges.

TAF amendments will be issued promptly when:

- a. Conditions meeting amendment criteria are imminent or have occurred and those conditions will, in the forecaster's estimation, persist for 30 minutes or longer, or
- b. New guidance/information indicates future conditions are expected to be in a different category than originally forecast, especially in the 1-6 hour time-period.

Forecasters should use application programs designed to notify them when a TAF does not meet current criteria. Forecasters should issue TAF AMDs for significant forecast changes immediately rather than update at the next regularly scheduled TAF release time, even if that release time is within a half hour after the amendment time.

1.2 <u>Amendment Coding.</u> An amended TAF will be identified in the WMO abbreviated heading by the contraction AAx following the date/time group, where x is the letter A through X. For example, AAA would indicate the first amendment of a particular scheduled terminal forecast, AAB, the second amendment of the same scheduled forecast, etc. An amended forecast will also be identified by TAF AMD (in place of TAF) on the first line of the forecast text. The date/time group in the WMO abbreviated heading of an amended terminal forecast will be the whole hour of issuance.

The amended TAF will cover all of the remaining valid period of the original scheduled forecast. Expired portions of the amended forecast or references to weather occurring before the issuance time will be omitted from the amendment.

In an amended forecast, the date and time of the forecast origin group (YYGGggZ) will reflect the time the amended forecast was prepared. In the forecast valid period group (Y1Y1G1G1/Y2Y2G2G2), the first four digits (Y1Y1G1G1) will reflect the UTC date and time of the beginning of the valid period of the amended TAF. With an issuance time (YYGGggZ) of H+00 to H+29, use the current hour (based on UTC) to denote the beginning valid time; for H+30 to H+59, use the next hour (based on UTC). In either case the forecast will be valid from the time of forecast origin (YYGGgg) to the valid period ending time of the original scheduled terminal forecast.

Example of amended TAF:

Original Amended

FTAK31 PAFC 030500 FTAK31 PAFC 030500 AAA

TAF AMD

PAEN 030540Z 0306/0406... PAEN 031012Z 0310/0406...

The scheduled forecast was sent, and 4 ½ hours later, the forecaster prepared the first amendment to that forecast (indicated by AAA), at 1012Z on the 3rd day of the month. The amended TAF shows the time of the original scheduled TAF in the WMO abbreviated header (0500Z).

1.3 <u>Amendment Criteria</u>. Amendment criteria values are operationally significant to aircraft and airports. Discrete flight category value changes for VFR, MVFR, IFR and LIFR have

significant operational impact (i.e., fuel requirements, alternates) and the TAF should be especially accurate regarding those values. Further, specific airports may have other values which are locally important to operations. Forecasters should be aware of these values when amendments are required and issued.

1.3.1 Categorical Amendment Criteria (CAC). All WFOs should utilize CAC for ceiling and visibility thresholds. See Table 1 for specific CAC categories. An NWS/FAA approved list of thresholds can be found in Appendix F.

Table 1. Categorical Amendment Criteria

Forecast Element/	TAF Ceiling and	Visibility
Occurrence	Amendment Crit	eria
Ceiling or Visibility observed	Category	Limits
to decrease to less than, or if below, when both elements	A (note 2)	200' – 1/2SM
<ul><li>increase to equal or exceed</li><li>See notes for specific details</li></ul>	B (note 3)	600' – 2SM 1,000' – 3SM
•	D	3,000' – 5SM
	E E	See note 4
	F	See note 5
	visibility value  2. Or the lowest published a minimums apply  3. Or higher thresholds as a requirements  4. Amendments required for >3SM.	ermined by the lowest ceiling or airfield minimum, where higher determined by specific airport or ceiling <2,000' when visibility ermined by air traffic management

- 1.3.2 <u>Additional U.S. TAF Amendment Criteria.</u> The following are recommended amendment thresholds for NWS TAFs in additional to the Categorical Amendment Criteria (CAC) for ceiling and visibility thresholds (See 4.6.2).
  - a. Weather. If thunderstorms, freezing precipitation or ice pellets occur and are not forecasted, or, if forecasted, do not occur.
  - b. Wind Direction, Speed and Gusts. Forecast mean refers to the mean wind direction or speed expected for the specified forecast group time period.
    - (1) Mean wind direction: differs by 30 degrees or more, with an accompanying mean wind speed of GTE 12 knots.

- (2) Forecast mean wind speed: actual mean wind speed will differ from forecast group mean speed by GTE 10 knots, and:
  - (a) The original mean wind speed was GTE 12 knots, or
  - (b) The newly expected mean wind speed is GTE 12 knots.
- (3) Forecast peak gust (or forecast of no gust): GTE 10 knots above <u>observed</u> gust (or above the <u>observed</u> mean wind speed if no gusts are forecast) occur or are expected.
- e. Non-Convective LLWS (up to 2,000 feet). Amend the TAF if non-convective LLWS is forecasted and does not occur, or if LLWS occurs and is not forecast.

Wind Shear (WS) is defined in NOAA Technical Memorandum NWS FCST-23, as "...a change in horizontal wind speed and/or direction, and/or vertical speed with distance, measured in a horizontal and/or vertical direction." Wind shear is a vector difference, composed of wind direction and wind speed, between two wind velocities. A sufficient difference in wind speed, wind direction, or both, can severely impact airplanes, especially within 2,000 feet AGL because of limited vertical airspace for recovery. The following, emphasizing the importance of wind shear, is taken from ICAO Circular 186-AN/122:

"Wind shear cannot be calculated by simple scalar subtraction of the wind speeds, except in the specific case where the directions of the two winds concerned are exactly the same or are exact reciprocals...The scalar shear (i.e., direct subtraction of wind speeds taking no account of their directions) is always less than or equal to the vector shear and thus for most cases underestimates the actual shear magnitude." Forecasters may use NOAA Technical Memorandum NWS FCST-23 as a reference for non-convective LLWS forecasting. The procedures described below are based on that study.

2. <u>Delayed TAFs</u>. Delayed TAFs will be issued as soon as possible after correction of the problem (electrical, mechanical or other) that caused the delay.

A delayed TAF will be identified in the WMO abbreviated heading by the contraction RRx following the date/time group, where x is the letter A through X, as described in Section 1. For example, RRA would indicate the first delayed issuance of a particular scheduled TAF. Only offices issuing TAFs in collectives would need to issue a second (or greater) delayed TAF. No contraction in the TAF text indicates a TAF is delayed; the contraction RRx only appears in the WMO abbreviated heading line.

The delayed TAF is valid from the UTC date/time of actual forecast origin (YYGGggZ) until the end of the previously scheduled TAF valid period. The date and time of actual forecast origin is determined by the UTC date/time of issue of the delayed TAF. With an issuance time of H+00 to H+29, use the current hour (based on UTC) to denote the beginning valid time; for H+30 to H+59, use the next hour (based on UTC). The TAF will be valid from the time of forecast origin to the end of the valid period of the original scheduled TAF.

Example of delayed TAF:

Delayed FTPA31 PHFO 030500 RRA TAF PHMK 031012Z 0310/0406...

The forecaster prepared the first delayed TAF (indicated by RRA) at 1012Z on the 3rd day of the month (as shown in the date/time of forecast origin in the text of the TAF). The delayed terminal shows the time of the original scheduled forecast in the WMO abbreviated header (0500 UTC).

3. <u>Corrected TAFs</u>. Corrected TAFs will be issued as soon as possible after discovery of an error (typographical or other mistake). A corrected TAF will be identified in the WMO abbreviated heading by the contraction CCx, which follows the date/time group (x is the letter A through X, as described in Section 1). CCA would indicate the first correction of a scheduled TAF, CCB the second correction of the same TAF, etc. There is no contraction in the forecast text to indicate a TAF is corrected; the contraction CCx only appears in the WMO abbreviated heading.

The date/time group in the WMO abbreviated heading of a corrected TAF will be the same as that of the original TAF unless the date/time group in the WMO abbreviated header contained the error. Refer to the example below.

Example of corrected TAF:

Original Corrected

FTAK31 PAFG 030500 FTAK31 PAFG 030500 CCA

TAF COR

PAOM 030540Z 0306/0406... PAOM 030551Z 0306/0406...

The scheduled TAF was sent and 11 minutes later, the forecaster discovered an error and prepared the first corrected TAF (indicated by CCA), at 0551Z on the 3rd day of the month (typed in by the forecaster). The corrected TAF shows the time of the original scheduled TAF in the WMO abbreviated header (0500Z).

3.1 <u>Correcting Amended or Delayed Forecasts</u>. If an amended or delayed TAF contains an error, it should be corrected following the same procedures described in Section 1. An example of a corrected amendment is shown below:

Example of corrected amendment:

Amendment (containing an error):

FTUS43 KTOP 271100 AAA

TAF AMD

KMHK 271522Z 2715/2812 VRB03KT P6SM SCT012

TEMPO 2715/2717 BKN012

FM271700 11000KT P6SM SCT035

FM280100 10003KT P6SM SKC

Corrected amendment:

FTUS43 KTOP 271100 CCA

TAF COR

KMHK 271602Z 2715/2812 VRB03KT P6SM SCT012

TEMPO 2715/2717 BKN012

FM271700 11005KT P6SM SCT035

FM280100 10003KT P6SM SKC

The amended TAF was prepared on the 27th day of the month at 1522Z (date/time of forecast origin in the forecast text of the amended TAF), and valid from 1500Z on the 27th until 1200Z the next day (the 28th). The amendment contains an error in the FM1700 group: winds incorrectly encoded as 110 degrees at 00 knots. The forecaster notices the error, and prepares the first correction (CCA) of the TAF at 1602Z (date/time of forecast origin in the forecast text of the corrected TAF). Note the following in the corrected amendment: 1) the CCA replaces the AAA in the WMO abbreviated heading which appeared in the first amendment; 2) the first line of the forecast text becomes TAF COR; 3) the TAF valid period in the forecast text is the same as the original amendment (1500Z-1200Z); 4) the error in the FM1700 group has been corrected.

# Appendix D New TAF Service, Observation Requirements and Terminating TAF Service

ble of	f Conte	nts	Page
Req	uests fo	or Preparation of New TAF Service/Changing Existing Part-Time TAF Service	34
1.1	Obser	vation Requirement to Initiate New TAF Service	34
1.2	Minin	num Observational Requirements for Routine TAF Issuance and Continuation.	34
1.3	<b>TAFs</b>	with Incomplete or Missing Observations	35
	1.3.1	NIL TAFs.	35
	1.3.2	Automated Observing Sites Requiring Part-Time Augmentation	35
	1.3.3	Non-augmented Automated Observing Sites	36
Terr	ninatin	g TAF Service	37
	Req 1.1 1.2 1.3	Requests for 1.1 Obser 1.2 Minim 1.3 TAFs 1.3.1 1.3.2 1.3.3	Requests for Preparation of New TAF Service/Changing Existing Part-Time TAF Service  1.1 Observation Requirement to Initiate New TAF Service

1. Requests for Preparation of New TAF Service/Changing Existing Part-Time TAF Service. Requests to establish new TAF service should be sent to the appropriate Regional Aviation Meteorologist (RAM) (or equivalent) for evaluation. The Region Headquarters (RH) will evaluate the request based on availability of data and NWS resources to support the newly requested TAF(s). Upon endorsement, the RAM forwards the RH recommendation to OCWWS, If OCWWS approves the TAF recommendation, then the RH completes a request for change (RC) and forwards it to the Data Review Group Change Management (DRGCM). Upon DRGCM approval of the RC, or concurrent with the RC approval process, the RH will prepare a National Technical Information Notice (TIN) and forward to OCWWS for processing and transmission. The TIN will be prepared according to instruction in NWSI 10-1805, Service Outreach. The RC will be prepared according to NWSI 10-101 Change Management Process.

Part-time TAF service will increase to 24 hours after RH prepares a TIN and forwards it to OCWWS for processing and transmission. An RC to expand TAF service to 24 hours is not required because the TAF identifier and communications nodes already exist.

1.1 <u>Observation Requirement to Initiate New TAF Service</u>. The following elements, at a minimum, are required for NWS approval of new TAF locations: wind (speed and direction), visibility, sky condition, temperature, dew point, and altimeter setting. Weather and obstructions to vision are desired to initiate new TAF requests, but a TAF may be produced upon coordination with National and Regional Headquarters if those elements are not available. Section 5.2.2 provides guidance for these situations.

These elements can be obtained from commissioned ASOS or AWOS-III observation sites or manual observer sites with equipment. Augmentation will be provided in accordance with the agency agreements with augmenters (refer to FAA document 7900.5B, *Surface Weather Observing - METAR*.

1.2 <u>Minimum Observations Requirements for Routine TAF Issuance and Continuation.</u> The aviation forecaster should have certain information for the preparation and issuance of each TAF. Although integral to the TAF writing process, the complete observation is not required. Forecasters should use the "total observation concept" to write TAFs with data including nearby observations, radar, satellite, radiosonde, model data, ACARS, MDCRS, and other sources. When communication problems prevent receiving observations into AWIPS, forecasters should

call the ASOS/AWOS to get observation data.

- 1.3 TAFs with Incomplete or Missing Observations. If information sources, such as surface observations, are missing, unreliable, or not complete, forecasters should append AMD NOT SKED to the end of a TAF. The use of AMD NOT SKED indicates the forecaster has enough data, using the total observation concept, to issue a forecast but will not provide updates. This allows airport operations to continue using a valid TAF. Use of the total observation concept, and AMD NOT SKED as needed, is strongly encouraged. No documentation is necessary for the use of AMD NOT SKED.
- 1.3.1 <u>NIL TAF</u>. A NIL TAF should not be issued except in rare situations. In cases where observations have been missing for extended periods of time (i.e., more than one TAF cycle of six hours), and the total observation concept cannot provide sufficient information to construct a TAF, then a NIL TAF may be used. Upon issuance of a NIL TAF, the WFO forecast team should provide written documentation on the circumstances leading to the decision to issue a NIL TAF. The documentation should include:
  - a. Station Location, time of NIL TAF, and expected duration of NIL TAF,
  - b. The condition of the total observation,
  - c. Which systems or elements were not available,
  - d. Actions taken to resolve the situation before using NIL TAF,
  - e. Synoptic or mesoscale events affecting the site, or forecast to do so, and
  - f. The overall reasoning used to make the NIL TAF decision.

The report should be forwarded to the RAM via the MIC.

NIL TAF disrupt airline operations, causes inconvenience to the traveling public, forces users to seek weather information from other sources, and should only be used as an "instrument of last resort."

1.3.2 <u>Automated Observing Sites Requiring Part-Time Augmentation</u>. Each NWS office with TAF responsibility will maintain the latest copy of FAA document 7900.5X, (*Surface Weather Observing – METAR*), where "X" is the current version. Chapter Four (4) of this document is entitled "General Procedures at Automated Weather Stations" and Chapter Five (5) is entitled "Augmentation at Automated Weather Stations".

TAFs for AWOS-III sites which have part-time augmentation will be prepared using the procedures for part-time manual observation sites detailed in the previous section, with one exception. This exception is the remark used when the automated system is unattended. Specifically, the time an augmented automated system is scheduled to go into unattended operation and/or the time augmentation resumes will be included in a remark unique to automated observing sites: AMD LTD TO CLD VIS AND WIND (AFT YYHHmm, or TIL YYhhmm, or YYHH/YYhh), where YY is the date, HHmm is the time, in hours and minutes, of

the last augmented observation and hhmm is the time, in hours and minutes, the second complete observation is expected to be received. This remark, which does not preclude amendments for other forecast elements, will be appended to the last scheduled TAF issued prior to the last augmented observation. It will also be appended to all subsequent amendments until augmentation resumes.

The AMD LTD TO (elements specified) remark is a flag for users and differs from the AMD NOT SKED AFT Z remark for part-time manual observation sites. AMD LTD TO (elements specified) means users should expect amendments only for those elements and the times specified. The AMD LTD TO (elements specified) remark may also be used without any specified times upon coordination with the region headquarters. In this form the remark flags that certain elements may not be amended at the AWOS-III site. The remark should be by itself as a separate last line of text in the TAF so the forecast user does not overlook it.

Example:

```
TAF AMD
KCOE 150202Z 1502/1600 text
AMD LTD TO CLD VIS AND WIND 1505/1518=
```

The amended forecast indicates that amendments will only be issued for wind, visibility and clouds, between 0500Z and 1800Z.

Example:

```
TAF
KTVL 160520Z 1606/1706 text
AMD LTD TO CLD VIS AND WIND=
```

The forecast indicates that amendments are only issued for wind, visibility, and clouds. Other elements are included, as noted in the next paragraph, when the forecast is updated for changes in wind, visibility, or clouds.

An amendment will include forecasts for all appropriate TAF elements, even those not reported when the automated site is not augmented. If unreported elements are judged crucial to the representativeness of a TAF and cannot be adequately determined (e.g., fog versus moderate snow), TAF amendments should be suspended (i.e., issue an amended TAF stating "AMD NOT SKED").

AWOS-III systems with part-time augmentation, which the forecaster suspects are providing unreliable information when not augmented, should be reported for maintenance and treated the same as part-time manual observation sites. In such cases, the AMD NOT SKED AFT YYaaZ remark will be used.

1.3.3 <u>Non-augmented Automated Observing Sites</u>. TAF amendments issued for a non-augmented ASOS site may be suspended in the event the forecaster is notified of, or strongly suspects, an outage or unrepresentative data. Forecasters may also consider suspension of TAF amendments when an element the forecaster judges to be critical is missing from the observation

#### NWSI 10-813 April 5, 2012

and cannot be obtained using the total observation concept. The term AMD NOT SKED will be appended, on a separate line and indented five spaces, to the end of an amendment to the existing TAF when appropriate.

2. <u>Terminating TAF Service.</u> If a TAF site experiences a drastic, permanent reduction in aviation services, the MIC may evaluate whether TAF service should continue for that site. If the MIC believes the TAF service should be terminated, the MIC will forward a recommendation with justification through the RAM and RH to OCWWS. The Aviation Services Branch (ASB) of OCWWS will coordinate TAF termination with the FAA, and also with other interested agencies as needed. ASB will coordinate a TIN and RC as the final step in terminating TAF service.

#### TAF Code Format, Terminology, and Significant Weather Matrices

#### **Table of Contents**

1.	Generic International TAF Code Format.	38
2.	International Terminology and Forecast Groups Not Used in NWS TAFS	38
3.	Significant Weather: WMO Code Table 4678	38
4.	Significant Weather Phenomena Matrix	40

1. <u>Generic International TAF Code Format</u>. The NWS forecaster should be familiar with the International TAF Code Format shown below.

TAF or TAF AMD or TAF COR

CCCC YYGGggZ YIYIGIGI/Y2Y2G2G2 dddffGfmfmKT
[Location [Date/time of [Valid period] [Wind forecast]

identifier] forecast origin]

VVVV or CAVOK w'w' or NSW NsNshshshs, Vvh,h,h, or SKC (NSC)
[Visibility forecast] [Significant weather forecast] [Cloud and obscuration forecast]

6Icchlhlhlt 5BhBhBhBt TTFTF/GFGFZ QNHPIPIPIINS
[Icing [Turbulence [Lowest altimeter]]

forecast] forecast] setting]

TTYYGGgg or TTTTT Y1Y1GG/YeYeGeGe PROBC2C2 Y1Y1GG/YeYeGeGe [Forecast change indicators] [Probability forecast]

- 2. <u>International Terminology and Forecast Groups Not Used in NWS TAFs.</u>
  - a. CAVOK: Ceiling and Visibility OK.
  - b. NSC: No Significant Clouds.
  - c. BECMG: Becoming.
  - d. PROBC2C2 Y1Y1GG/YeYeGeGe in combination with TEMPO.
  - e. Optional Groups: 6I (Icing), 5B (Turbulence), TT (Temperature), and QNH (Altimeter). There is no requirement for NWS WFOs to use these groups in NWS TAFs.
- 3. Significant Weather: WMO Code Table 4678 (next page).

#### NWSI 10-813 April 5, 2012

The w'w' groups will be constructed by considering columns 1 to 5 from the following table in sequence. For example, heavy rain shower(s) are coded as +SHRA.

Intensity or Proximity <sub>1</sub>	Descriptor <sub>2</sub>	Precipitation <sub>3</sub>	Obscuration <sub>4</sub>	Other <sub>5</sub>
				PO Well-developed
- Light	MI Shallow	DZ Drizzle	BR Mist	dust/sand swirls
Moderate (no qualifier)	BC Patches	RA Rain	FG F∘g	
	PR Partial			
	(covering part			
	of the			
	aerodrome)	SN Snow	FU Smoke	SQ Squalls
+ Heavy (or well				
developed, in the case		SG Snow		FC <sub>5</sub> (Funnel Cloud(s)
of funnel clouds)		Grains	VA Volcanic Ash	(tornado or waterspout)}
	DR Low			
	Drifting	IC Ice Crystals	DU Widespread Dust	
	<b>BL</b> Blowing	PL Ice Pellets	SA Sand	SS Sandstorm
	SH			
VC <sub>1</sub> In the vicinity	Shower(s)	GR <sub>2</sub> Hail	HZ Haze	DS Duststorm
		GS₃ Small hail		
	TS	and/or snow		
	Thunderstorm	pellets	PY Spray	
		UP <sub>4</sub> Unknown		
		Precipitation in		
		automated		
	FZ Freezing	observations		

#### Footnotes for Code Table 4678 above

- 1. The NWS definition of VC applied to the terminal forecast is: A donut-shaped area encompassed between circles with radii of 5 and 10 statute miles, respectively, from the center of the airport's runway complex.
- 2. Diameter of largest hailstone GTE 1/4"
- 3. Diameter of hailstones LT 1/4"
- 4. UP will not be used in NWS-prepared terminal forecasts
- 5. Tornadic activity, including tornadoes, waterspouts, and funnel clouds, should only be included in TAFs when absolutely necessary. Although the probability of occurrence at a specific site is low, it is possible.

									]	NWSI	10-81	3 April	5, 201
4. <u>Signi</u>	fican	t Wea	ther Ph	enome	na Ma	trix for	NWS-	issuec	l TAFs	<u>.</u>			
WEATHER PHENOMENA						Q	UALIFIE	ır.					
	Intensity or Proximity						Descriptor <sub>1</sub>						
	Zanazij vi i ivalility							Low		_			
Precipitation		Light	Moderate	Heavy	Vicinity	Shallow	Partial	Databas	Drifting3	Blowing	Shouwers	T-storm4	Freezing
тесфиация			Moderate						_				
T	D7	- 107	D7	+	VC2	MI	PR	BC	DR	BL	SH	TS	FZ
Drizzle Rain	DZ RA	-DZ -RA	DZ RA	+DZ +RA	-	-	-	-	-	-	- SHRA	- TSRA	FZDZ FZRA
Rain Snow	SN	-KA -SN	SN	+KA +SN	-	-	-	-	DRSN	BLSN	SHSN	TSSN	rzka
Snow Grains	SG	-SG	SG	+SG	-	-	-	-	- DIGIN	DESM	SHSH	13314	-
		-30		+30	-	-	-	-	-	-	-	-	-
Ice Crystals5	IC	-	IC	-	-	-	-	-	-	-	-	-	-
Ice Pellets	PL	-PL	PL	+PL	-	-	-	-	-	-	SHPL	TSPL	-
Hail <sub>5,6</sub>	GR	-	GR	-	-	-	-	-	-	-	SHGR	TSGR	-
Small Hail <sub>5,7</sub>	GS	-	GS	-	-	-	-	-	-	-	SHGS	TSGS	-
Thunderstorms,	Show	ers.Fre	ezing, and	their in	tensity o	r proxim	itv						
TS	TS	_	TS	_	VCTS <sub>2</sub>	-	-	_	-	-	_	_	-
TSRA		-TRSA	TSRA	+TSRA	-	_		_	_	_	_		_
TSSN		-TSSN	TSSN	+TSSN	_	_	_	_	_	_	_	_	_
TSPL		-TSPL	TSPL	+TSPL	-	-	_	_	-	_	-	_	_
TSGS		-	TSGS	-	-	-	-	-	-	-	-	-	-
TSGR		-	TSGR	-	-	-	-	-	-	-	-	-	-
SH	SH	-	-	-	VCSH.	-	-	-	-	-	-	-	-
SHRA		-SHRA	SHRA	+SHRA	-	-	-	_	-	-	-	_	-
SHSN		-SHSN	SHSN	+SHSN	-	-	-	-	-	-	-	-	-
SHPL		-SHPL	SHPL	+SHPL	-	_	_	_	_	-	-	_	_
SHGR		-	SHGR	-	-	-	-	-	-	-	-	-	-
SHGS		-	SHGS	-	-	-	-	-	-	-	-	-	-
FZDZ		-FZDZ	FZDZ	+FZDZ	-	-	-	_	_	-	-	-	-
FZRA		-FZRA	FZRA	+FZRA	-	-	-	-	-	-	-	-	-
FZSG		-	FZSG	-	-	-	-	-	-	-	-	-	-
Obscurations													
Mist	BR	_	BR <sub>10</sub>	_	-	-	_	<u> </u>	-	-	-	_	_
Fog	FG	_	FG <sub>11</sub>	_	VCFG <sub>12</sub>	MIFG <sub>13</sub>	PRFG <sub>14</sub>	BCFG	_	_	-	_	FZFG <sub>16</sub>
Smoke	FU	-	FU	_	-	-	-	-	_	_	_	_	-
Volcanic Ash	VA		VA <sub>17</sub>	_	_	-	_	-			-		
Widespread Dust	DŪ	-	DU	_	_	_	_	_	DRDU	BLDU	_	_	_
Sand	SA	-	SA	_	_	_	_	_	DRSA	BLSA	-	_	_
Haze	HZ		HZ	_	_	_	_	_	-	-	-	_	_
Spray	PY	_	PY	_	-	-	_	_	-	BLPY	-	_	_
Blowing													
Рћенотена													
Snow18	BLSN	_	BLSN	-	-	-	-	-	-	BLSN	-	_	-
Sand	BLSA	_	BLSA	_	_	_	_	_	_	BLSA	_	_	_
Duststorm	BLDU	-	BLDU	_	_	_	_	_	_	BLDU	_	_	_
Other			200							2220			
Sand/Dust Whirls	PO	_	PO	_	_	_	_	_	-	_	_	-	_
Squalls19	SQ	-	SQ										
				-	-	-	-	-	-	-	-	-	-
Funnel Cloud <sub>20</sub> Tornado /	FC	-	FC	-	-	-	-	-	-	-	-	-	-
Waterspout21	+FC	_	_	+FC	_	_	_	_	_	_	_	_	_
Sandstorm	SS		SS	+55	_		-	_	-		_	_	_
Nandstown '													

#### Footnotes for Weather Phenomena Matrix for NWS TAFs

- 1. Only one descriptor will be used for each weather phenomena group, e.g., BCFG.
- 2. In NWS TAFs, vicinity (VC) is defined as a donut-shaped area 5SM to 10SM from the center of the runway complex of an airport. In NWS TAFs, vicinity will be combined only with fog (VCFG), showers (VCSH), or thunderstorms (VCTS), and only when forecasting prevailing conditions (i.e., initial time period, or FM groups).
- 3. Raised by wind to LT six (6) feet above the ground.
- 4. TS may be forecast by itself if no precipitation is associated with the thunderstorm.
- 5. No intensity is ever given to hail (GR/GS [snow pellets]) or ice crystals (IC).
- 6. Largest forecast hailstone has a diameter of GTE 1/4 inch.
- 7. Forecast hailstone diameter is LT 1/4 inch.
- 8. VCTS is a valid combination for all airports with TAFs. [In the METAR code, VCTS is only reported by automated stations connected to FAA ALDARS].
- 9. VCSH will be used to forecast showers 5-10SM from the center of the airport. The type and intensity of showers in the vicinity will not be specified, i.e., +VCSHRA is not allowed.
- 10. BR will only be used when the visibility is forecast to be GT 1/2SM, but LTE 6SM.
- 11. For FG to be forecast with any qualifiers, visibility will be LTE 1/2SM.
- 12. VCFG may be used to forecast fog at any visibility value between 0 and 6SM in the vicinity (5-10SM) of the airport.
- 13. For MIFG to be forecast, the visibility at 6 feet above ground level will be GT 1/2SM and the apparent visibility in the fog layer will be expected to be LTE 1/2SM.
- 14. PRFG indicates that a substantial part of the airport is forecast to be covered by fog (visibility LTE 1/2SM) while the remainder of the airport is expected to be clear of fog.
- 15. BCFG indicates that patches of fog (visibility LTE 1/2SM) are forecast to randomly cover the airport.
- 16. FZFG is fog (visibility LTE 1/2SM) consisting predominately of water droplets at

- temperatures LTE 0C, whether or not the fog is expected to deposit rime ice.
- 17. Volcanic Ash (VA) is always included in the forecast when expected. Visibility is not a factor.
- 18. SN BLSN indicates a combination of snow falling from clouds and blowing snow.
- 19. SQ (squall) is a sudden increase in wind speed of GTE 16 knots, the speed rising to 22 knots or more and lasting for GTE one minute.
- 20. Generally, Funnel Clouds should not be forecast.
- 21. Tornadoes and Waterspouts should rarely be forecast.
- 22. SS is forecast if visibility is GT 1/4SM and LTE 1/2SM. Forecast +SS if visibility is expected to be LTE 1/4SM.
- 23. DS is forecast if visibility is GT 1/4SM and LTE 1/2SM. Forecast +DS if visibility is expected to be LTE 1/4SM.

No more than three significant weather groups will be used to forecast weather phenomena at or near the airport. If more than one significant weather phenomena is expected in the forecast, separate weather groups will be included. If more than one form of precipitation is forecast, the appropriate contractions will be combined in a single group with the predominant type of precipitation included first. One exception to this is in Appendix C, Section 1.2.6. In such a single precipitation group, the intensity will refer to the total precipitation and be used with one or no intensity qualifier, as appropriate.

### NWSI 10-813 April 5, 2012

### Appendix F NWS TAF Locations by Responsible WFO and Categorical Amendment Criteria Thresholds

NWS TAF Locations by Responsible WFO and Categorical Amendment Criteria Thresholds are now a hyperlink so they can be updated as needed, and can be viewed <a href="here">here</a>.