OPTIONAL WORKSHEET FOR CALCULATING CALL REPORT APPLICABLE INCOME TAXES

(Not to be submitted with your bank's Call Report)

For March 31, 2010

This optional worksheet is designed to assist certain banks in the calculation of applicable income taxes for the year-to-date reporting period ending March 31, 2010. Banks are <u>not</u> required to use this optional worksheet and may use any reasonable approach for reporting applicable income taxes in their Call Reports in accordance with Financial Accounting Standards Board Statement No. 109, "Accounting for Income Taxes" (FASB 109). As discussed below, this optional worksheet provides a simplified approach for calculating year-to-date applicable income taxes under FASB 109. Thus, it should not be used by banking organizations that prepare quarterly financial statements in accordance with generally accepted accounting principles (GAAP) or where it will likely result in significantly lower applicable income taxes than as calculated under GAAP. In addition, the worksheet should not be used by banks that are, for federal income tax purposes, either "S corporations" or "qualifying subchapter S subsidiaries" as of March 31, 2010, and are generally not subject to federal corporate income taxes. Item references on the optional worksheet are to the FFIEC 041 Reports of Condition and Income.

The following discussion indicates specific situations where the use of this optional worksheet is not appropriate.

<u>Applicable income taxes on income before extraordinary items</u> -- This optional worksheet assists in the calculation of applicable income taxes on Schedule RI, item 8, "Income (loss) before income taxes and extraordinary items and other adjustments." This calculation applies to banks that report no amounts in Schedule RI, item 11, "Extraordinary items and other adjustments, net of income taxes."

If your bank reports any "Extraordinary items and other adjustments" in Schedule RI-E, item 3, applicable income taxes on your bank's income (loss) (including both item 8 of Schedule RI and the "Extraordinary items and other adjustments" in items 3.a.(1), 3.b.(1), and 3.c.(1) of Schedule RI-E) generally must be computed. This amount must then be allocated between Schedule RI, item 9, "Applicable income taxes (on item 8)," and Schedule RI-E, items 3.a.(2), 3.b.(2), and 3.c.(2), "Applicable income tax effect," in a reasonable and consistent manner. State member banks should contact their Federal Reserve District Bank for additional information regarding this calculation and allocation. National banks and FDIC-supervised banks should contact the FDIC's Data Collection and Analysis Section in Washington, D.C. (800-688-FDIC).

Alternative minimum tax -- This optional worksheet is designed to assist in the calculation of a bank's applicable income taxes under the regular tax system. Some banks may be subject to higher income taxes under the alternative minimum tax (AMT) system. Because FASB 109 applies to all income taxes, banks should consider the effects of any AMT in calculating the current and deferred portions of applicable income taxes. If your bank has additional tax liability under the AMT system, consult your bank's tax advisor for assistance in estimating your bank's applicable income taxes.

Reporting applicable income taxes in interim periods -- FASB 109 does not change the guidance in Accounting Principles Board Opinion No. 28, "Interim Financial Reporting" (APB 28), with respect to accounting for income taxes in interim periods. Under APB 28, a bank should determine its best estimate of the bank's effective annual tax rate for the full year, including both current and deferred portions and including all tax jurisdictions (federal, state and local). The bank should then use this rate as the basis for determining its total year-to-date applicable income taxes at the interim date.

Under FASB 109, a bank should estimate the current portion of its applicable income taxes for the year based on its estimated taxes payable (receivable) on the tax return that will be prepared for the current year. To estimate the deferred portion of its applicable income taxes, a bank should project what its net deferred tax asset and liability (resulting from temporary differences for which the tax effect is included in net income) will be at the end of the year based on its estimated temporary differences at that date. The change in the bank's estimated net deferred tax asset or liability (resulting from temporary differences for which the tax effect is included in net income) for the year is the deferred portion of its applicable income taxes.

To arrive at the estimated annual effective tax rate, a bank should divide its estimated total applicable income taxes (current and deferred) for the year by its estimated pretax income for the year (excluding extraordinary items). This rate would then be applied to the year-to-date pretax income to determine the year-to-date applicable income taxes at the interim date.

Many banks, or their parent holding companies, will perform the calculation of income tax expense in accordance with FASB 109 and APB 28 when preparing their quarterly GAAP-based financial statements. These banks should determine their applicable income taxes for the year-to-date reporting period covered by the Call Report in a similar manner. Accordingly, these banks should not use this worksheet.

In contrast, some banks may not have determined their interim period income taxes using the estimated annual effective rate. For these banks, estimating the annual effective tax rate under the liability method may be difficult. These banks may find it less burdensome to estimate their year-to-date applicable income taxes based upon their deferred tax asset or liability balances at the end of the quarter, rather than projecting these amounts through the end of the year. This optional worksheet follows this approach. A bank may use this approach if it will not likely result in significantly lower year-to-date applicable income taxes than as calculated under FASB 109 and APB 28. Otherwise, a bank should follow some other reasonable approach for calculating applicable income taxes in interim periods in accordance with FASB 109 and APB 28.

CALCULATION OF SCHEDULE RI, ITEM 9, "APPLICABLE INCOME TAXES (ON ITEM 8)" UNDER THE REGULAR TAX SYSTEM [Applicable income taxes on Item 8 include both amounts currently due (or refundable) calculated in Section A and deferred income taxes calculated in Section B.]

Income taxes due (refundable) for the year to date

A.

	(i.e., current portion of applicable income taxes)	
A.1.	Schedule RI, Item 8, "Income (loss) before income taxes and extraordinary items and other adjustments"	
A.2.	Schedule RI, Memorandum Item 3, "Income on tax-exempt loans and leases to states and political subdivisions in the U.S."	(–)
A.3.	Schedule RI, Memorandum Item 4, "Income on tax-exempt securities issued by states and political subdivisions in the U.S."	(–)
A.4.	Other income included in Schedule RI, Items 1, 5, and 6, (if any) which is not subject to federal income taxes during the current period	(–)
A.5.	Other income <u>not</u> included in Schedule RI, Item 8, (if any) which <u>is</u> subject to federal income taxes during the current period	(+)
A.6.	Schedule RI, Memorandum Item 1, "Interest expense incurred to carry tax-exempt securities, loans, and leases acquired after August 7, 1986, that is not deductible for federal income tax purposes"	(+)
A.7.	All other expenses included in Schedule RI, Item 8, that are <u>not</u> deductible for federal income tax purposes in the current period	(+)
A.8.	Other expenses <u>not</u> included in Schedule RI, Item 8, that <u>are</u> deductible for federal income tax purposes in the current period	(–)

A.9.	Year-to-date income currently subject to federal income taxes before state and local income taxes (Line A.1 minus Lines A.2, A.3, A.4, and A.8, plus Lines A.5, A.6, and A.7)	
A.10.	State and local income taxes due (refundable) for the year to date (If the state and local tax laws applicable to your bank do not differ significantly from federal income tax laws, an estimate of state and local income taxes can be obtained by multiplying Line A.9 by the applicable state and local income tax rate.)	. (–)
A.11.	Year-to-date federal taxable income (Line A.9 minus Line A.10)	
		x 4
A.12.	Annualized federal taxable income (Line A.11 multiplied by 4)	
A.13.	Net operating loss (NOL) carryforwards available at January 1, 2010, to offset annualized federal taxable income (amount reported on this line should not exceed the amount reported on Line A.12)	. (–)
A.14.	Annualized income currently subject to federal income taxes (Line A.12 minus Line A.13)	·
A.15.	Annualized federal income taxes currently due (refundable) on amount shown on Line A.14 (Calculate this amount using the "Federal Income Tax Rates for Banks" at the end of this worksheet)	·
		x 0.25
A.16.	Year-to-date federal income taxes currently due (refundable) on amount shown on Line A.15 (Line A.15 multiplied by 0.25)	
A.17.	Year-to-date federal income tax credits (if any)	. (–)
A.18.	State and local income taxes due (refundable) for the year to date (from Line A.10 above)	. (+)
A.19.	Total income taxes currently due (refundable) for the year to date (Line A.16 minus Line A.17 plus Line A.18)	
B.	<u>Deferred income tax expense (benefit) for the year to date</u> (i.e., deferred portion of applicable income taxes)	

This section provides guidance for the determination of the deferred portion of applicable income taxes for the year to date under FASB 109. This calculation considers federal, state and local income taxes.

Deferred income tax expense (benefit) for the reporting period ending March 31, 2010, is generally measured in this worksheet as the change in the bank's net deferred tax assets or liabilities during the year-to-date period. Therefore, your bank should calculate its net deferred tax assets/liabilities at March 31, 2010, and compare this amount to the amount of your bank's net deferred tax assets/liabilities at December 31, 2009. A portion of the difference between these two amounts will be the deferred income tax expense (benefit) for the reporting period ending March 31, 2010. The remainder of the change in the net deferred tax assets/liabilities for the period generally should be charged or credited directly to the "Accumulated other comprehensive income" component of equity capital (Schedule RC, item 26.b) that includes your bank's "Net unrealized holding gains (losses) on available-for-sale securities." The following steps assist in the calculation of these amounts.

B.1. Identify types and amounts of temporary differences

Temporary differences essentially consist of all differences between the book and tax basis of a bank's assets and liabilities. In identifying these basis differences, a bank should consider assets and liabilities that may not exist on its books (such as repairs capitalized for tax purposes but expensed on the bank's books and Call Report) as well as assets and liabilities that have no tax basis (such as gains deferred on the bank's books and Call Report which have been recognized for tax purposes).

- 4 -

To ensure all temporary differences are identified, banks should consider preparing a comprehensive tax-basis balance sheet and comparing it to the balance sheet on the bank's Call Report. As these differences are identified, the bank should categorize these amounts as deductible or taxable temporary differences. Also, banks should not include those book-tax basis differences that are not considered temporary differences under FASB 109. One such example is the excess of the cash surrender value of life insurance over premiums paid (if the policy will be held until the death of the insured).

The definition of temporary differences is similar to "timing differences" used under prior GAAP (i.e., Accounting Principles Board Opinion No. 11 (APB 11)). Timing differences under APB 11 were differences between taxable income and pretax income on the bank's books. However, temporary differences as defined under FASB 109 include additional items that were not previously subject to deferred tax accounting. For example, differences between the assigned values and the tax bases of assets acquired and liabilities assumed in a purchase business combination are temporary differences. Refer to the Glossary entry for "income taxes" in the Call Report instructions and to FASB 109 for additional information about temporary differences.

Listed below are some of the assets and liabilities that are frequently reported differently on a bank's federal income tax return than they are on the bank's books and Call Report. A book-tax basis difference for a particular asset or liability may result from one or more temporary differences.

Under FASB 109, the tax effects of most temporary differences are included in a bank's net income. However, the tax effects of certain items specified by FASB 109 are charged or credited directly as a component of a bank's equity capital. The principal item of this type is identified separately below to assist banks in properly recording their income tax amounts under FASB 109.

Some of the items listed below may not involve temporary differences at your bank. Similarly, there may be other differences that exist in your bank that are not listed below. Banks should ensure that they properly identify the appropriate differences specific to their institution.

A bank that can reasonably determine its tax basis balance sheet at March 31, 2010, may use the approach in Section B.1.a. to identify some of its temporary differences. If the tax basis balance sheet information at March 31, 2010, is not readily available, the bank may use the approach in Section B.1.b. to provide a reasonable estimate of the temporary differences at that date. Any bank using Section B.1.b. should ensure that the estimation method used for each temporary difference is appropriate for its facts and circumstances. Otherwise, the bank should make appropriate adjustments to Section B.1.b. or else use Section B.1.a. All banks should complete Section B.1.c. for any other significant temporary differences.

B.1.a. Differences in book-tax basis approach (COMPLETE ONLY IF A TAX-BASIS BALANCE SHEET IS PREPARED OR AVAILABLE)

Under this approach, record your bank's book and tax bases for the six accounts listed in the following chart. Subtract the tax basis from the book basis to arrive at the difference. Then identify whether the difference is a taxable or deductible temporary difference. Note that a debit (Dr) difference indicates a taxable (T) temporary difference. A credit (<Cr>) difference indicates a deductible (<D>) temporary difference.

¹ Savings institutions that previously took bad debt deductions for tax purposes using the percentage-of-taxable-income method set forth in Section 593 of the Internal Revenue Code should treat the book allowance for loan and lease losses as a deductible temporary difference and the excess, if any, of the tax bad debt reserve (that has not yet been recaptured) over the base year reserve balance (generally 1987) as a taxable temporary difference, rather than treating the allowance and the tax bad debt reserve as one difference.

		[A] Book Basis Dr <cr></cr>	[B] Tax Basis Dr <cr></cr>	[A]-[B] Differ- ence Dr <cr></cr>	Type T <d></d>
(5)	Bank premises and equipment, net [e.g., difference due to different depreciation methods and rates for book and tax purposes]		<u> </u>	<u> </u>	
(6)	Interest earned, not collected on loans [e.g., difference due to interest on nonaccrual loans not recorded on books and Call Report but recognized on the tax return]				
B.1.b.	Rollforward of Temporary Differences Approac	h (DO NOT C WAS COM		IF SECTION E	3.1.a.
	NOTE: Changes in temporary differences from are significant in amount. If a change is not sign as of December 31, 2009, in the 3/31/10 Tempo difference indicates a taxable (T) temporary difference.	gnificant, use t orary Differen	he amount o ce column.	f the temporar Note that a de	ry difference bit (Dr)
B.1.b.1	. Temporary differences for which the tax effect	t is charged or	credited dire	ectly to equity	capital:
(1)	Available-for-sale securities (To be completed only if available-for-sale are reported differently on the books and 0		<u>Dr<cr></cr></u>	3/31/10 Temporary Difference <u>Dr<cr></cr></u>	Type T <d></d>
	than on the tax return): Balance (at fair value) of available-for-sale secon books and Call Report at 3/31/10 Less: Amortized cost of available-for-sale securities at 3/31/10 Estimated 3/31/10 temporary difference	curities			
	NOTE: See the discussion of available-for-sale consult their tax advisors when determining the				
B.1.b.2	. Temporary differences for which the tax effec	t is included in	net income:		
(2)	Loans:		<u>Dr<cr></cr></u>	3/31/10 Temporary Difference <u>Dr<cr></cr></u>	Type T <d></d>
(4)	Difference at 3/31/10 approximates the amoun deferred loan fee income, net of deferred loan origination costs, on books and Call Report at				

(3)	Allowance for loan and lease losses: ²	<u>Dr<cr></cr></u>	3/31/10 Temporary Difference Dr <cr></cr>	Type T <d></d>	
, ,	For banks on the specific charge-off method for tax purposes (i.e., for banks with no tax bad debt reserve): Difference at 3/31/10 approximates the balance of the allowance for loan and lease losses on books and Call Report at 3/31/10				-
	For banks on the reserve method for tax purposes: Temporary difference at 12/31/09 T <d> Less: Provision for loan and lease losses on books and Call Report year to date Plus: Estimated additions to tax reserve year to date* Estimated 3/31/10 temporary difference</d>				=
	* Generally, this amount may be estimated by multiplying the addition to the bank's tax reserve for 2009 by 0.25.				
(4)	Other real estate owned:				
	Choose the method from (a) and (b) below that is appropriate for your bank. Do <u>not</u> complete both (a) and (b).				
	(a) Balance of other real estate owned valuation allowances on books and Call Report at 3/31/10 T <d></d>				-
	 (b) Temporary difference at 12/31/09 T<d> Less: Provisions taken year to date on books and Call Report for properties held on 3/31/10 </d> Plus: Amount of writedowns taken before 1/1/10 on books for properties sold year to date Estimated 3/31/10 temporary difference 				=
(5)	Bank premises and equipment, net:				
	Temporary difference at 12/31/09 T <d> Less: Depreciation recorded on books and Call Report year to date Plus: Estimated tax depreciation year to date* Plus/less: Estimate of difference in book and tax basis of fixed assets sold year to date Estimated 3/31/10 temporary difference</d>				_
	* Generally, this amount may be estimated by multiplying 2009 tax depreciation by 0.25.				

² Savings institutions that previously took bad debt deductions for tax purposes using the percentage-of-taxable-income method set forth in Section 593 of the Internal Revenue Code should treat the book allowance for loan and lease losses as a deductible temporary difference and the excess, if any, of the tax bad debt reserve (that has not yet been recaptured) over the base year reserve balance (generally 1987) as a taxable temporary difference, rather than treating the allowance and the tax bad debt reserve as one difference.

(6)	Interest earned not collected on nonaccrual	loans:	<u>Dr<cr></cr></u>	3/31/10 Temporary Difference <u>Dr<cr></cr></u>	Type T <d></d>						
` '	Temporary difference at 12/31/09 T <d> Plus: Estimated additional interest on nonaccrual loans year to date Less: Interest received on nonaccrual loans year to date Estimated 3/31/10 temporary difference</d>										
B.1.c.	Other temporary differences (TO BE COMP If the bank has other material temporary differences a	erences, includere taxable or o	de those diffei deductible tem	rences below. nporary differer	Indicate nces. In						
	addition, any differences for which the tax effect is charged or credited directly to equity capital should be designated accordingly.										
	Examples of other temporary differences include: accrued liabilities or prepaid expenses recorded differently on the books and Call Report than reported on the tax return, differences in the basis of assets and liabilities resulting from business combinations, investments in stock of unconsolidated subsidiaries (undistributed earnings recognized on the books and Call Report but not in the tax return), and intangible assets which have different amortization periods and/or methods used in the tax return than those used on the books and Call Report.										
	Note that a debit (Dr) difference indicates a difference indicates a deductible (<d>) temp</d>			ence. A credit	(<cr>)</cr>						
	Other temporary differences:	[A] Book Basis Dr <cr></cr>	[B] Tax Basis Dr <cr></cr>	[A]-[B] Differ- ence Dr <cr></cr>	Type T <d></d>						
B.2.	Total temporary differences										
ć	 Total taxable temporary differences for wh in net income (sum of appropriate taxable differences marked "T," identified in Section 	temporary diff	erences, i.e.,								
ł	 Total taxable temporary differences for which the tax effect is charged or credited directly to equity capital (sum of appropriate taxable temporary differences, i.e., differences marked "T," identified in Section B.1)										
(c. Total deductible temporary differences for which the tax effect is included in net income (sum of appropriate deductible temporary differences, i.e., differences marked " <d>," identified in Section B.1. Ignore negative signs.)</d>										

	d.	or credited directly to differences, i.e., diffe	rences marked " <d>," iden</d>	ropriate deductible temporary							
B.3.		entify remaining tax ca rryforwards, if necessa		expiration dates (add additional lines for additi	onal						
	a.		IOL) carryforwards piration Date piration Date								
	ang we	y NOL carryforwards ι	used in Section A to reduce	our bank should consider the effect of taxes currently due. If any amounts ed here can be estimated with the							
		[(t	OL carryforwards available he amount of NOL carryfor a used per Line A.13) x (0.2	wards estimated to							
	b.		rds piration Date piration Date								
B.4.	<u>Ca</u>	lculate deferred tax lia	ability for federal income tax	c purposes at March 31, 2010.							
	a.		ary differences for which the ine B.2.a)	e tax effect is included							
	b.	b. Deferred tax liability resulting from taxable temporary differences for which the tax effect is included in net income (Line B.4.a multiplied by the tax rate expected to apply when the amount of taxable temporary differences result in additional taxable income in future periods) ³									
	C.		ary differences for which the equity capital (from Line B	e tax effect is charged .2.b)							
	d.	which the tax effect is (Line B.4.c multiplied of taxable temporary	resulting from taxable tempes charged or credited direct by the tax rate expected to differences result in addition	ly to equity capital apply when the amount							
	e.		bility for federal income tax B.4.b plus Line B.4.d)	purposes at							

Refer to the discussion of the "applicable tax rate" in the Glossary entry for "income taxes" in the Call Report instructions and to footnote 5 on page 11 of this worksheet for further information.

Ca	Iculate deferred tax asset for federal income tax purposes at March 31, 2010.	
a.	Total deductible temporary differences for which the tax effect is included in net income (from Line B.2.c)	
b.	Deferred tax asset resulting from deductible temporary differences for which the tax effect is included in net income (Line B.5.a multiplied by the tax rate expected to apply when the amount of deductible temporary differences are used to reduce taxable income in future periods) ⁴	
C.	Deferred tax asset resulting from net operating loss carryforwards (Line B.3.a multiplied by the tax rate expected to apply when the net operating loss carryforwards are utilized in future periods) ⁴	(+)
d.	Tax credit carryforwards available to reduce taxes payable in future periods (from Line B.3.b)	(+)
e.	Total deferred tax assets for which the tax effect is included in net income (Line B.5.b plus Line B.5.c plus Line B.5.d)	
f.	Total deductible temporary differences for which the tax effect is charged or credited directly to equity capital (from Line B.2.d)	
g.	Deferred tax asset resulting from deductible temporary differences for which the tax effect is charged or credited directly to equity capital (Line B.5.f multiplied by the tax rate expected to apply when the amount of deductible temporary differences are used to reduce taxable income in future periods) ⁴	
h.	Total deferred tax assets for federal income tax purposes before valuation allowance, if any (Line B.5.e plus Line B.5.g)	

B.6. Assessing the need for a valuation allowance

Banks must consider all available evidence, both positive and negative, in assessing the need for a valuation allowance to reduce the total deferred tax assets for federal income tax purposes in Line B.5.h to the amount that is more likely than not to be realized. The future realization of deferred tax assets ultimately depends on the existence of sufficient taxable income of the appropriate character in either the carryback or carryforward period. Four sources of taxable income may be available to realize deferred tax assets:

- (1) Taxable income in carryback years (which can be offset to recover taxes previously paid),
- (2) Reversing taxable temporary differences.
- (3) Future taxable income (exclusive of reversing temporary differences and carryforwards), and
- (4) Tax-planning strategies.

In general, positive evidence refers to the existence of one or more of the four sources of taxable income. To the extent evidence about one or more sources of taxable income is sufficient to support a conclusion that a valuation allowance is not necessary (i.e., the bank can conclude that the deferred

⁴ Refer to the discussion of the "applicable tax rate" in the Glossary entry for "income taxes" in the Call Report instructions and to footnote 5 on page 11 of this worksheet for further information.

tax asset is more likely than not to be realized), other sources need not be considered. However, if a valuation allowance is needed, each source of income must be evaluated to determine the appropriate amount of the allowance needed.

Evidence used in determining the valuation allowance should be subject to objective verification. The weight given to evidence when both positive and negative evidence exist should be consistent with the extent to which it can be objectively verified. Under FASB 109, the existence of a cumulative loss for the prior three years is significant negative evidence that would be difficult for a bank to overcome.

Refer to the discussion of the "valuation allowance" in the Glossary entry for "income taxes" in the Call Report instructions for further information.

	Line B.6: Valuation allowance to reduce the total deferred tax assets for federal income tax purposes in Line B.5.h to the amount that is more likely than not to be realized	(–)
B.7.	Deferred tax asset for federal income tax purposes, net of valuation allowance, at March 31, 2010 (Line B.5.h minus Line B.6)	
B.8.	Net deferred tax asset (liability) for federal income tax purposes at March 31, 2010 (Line B.7 minus Line B.4.e) (Report this amount in Schedule RC-F, Item 2, or Schedule RC-G, Item 2, as appropriate)	
B.9.	Net deferred tax asset (liability) for which the tax effect is included in net income for federal income tax purposes at March 31, 2010 [Line B.5.e minus (the lesser of Line B.5.e and Line B.6) minus Line B.4.b]	
B.10.	Net deferred tax asset (liability) for which the tax effect is included in net income for federal income tax purposes at December 31, 2009 [This amount is from Line B.9 of the 12/31/09 Call Report tax worksheet.]	
B.11.	Year-to-date deferred income tax expense (benefit) for federal income tax purposes (determined as the change for the period in the net deferred tax asset or liability for which the tax effect is included in net income) (Line B.10 minus Line B.9)	
	NOTE: The change in a bank's net deferred tax asset (liability) for which the tax effect is charged or credited directly to equity capital is not reported as part of a bank's deferred tax income tax expense (benefit).	
B.12.	Year-to-date deferred income tax expense (benefit) for state and local tax purposes. This amount must be computed if the tax laws of the bank's state and local tax authorities differ significantly from the federal tax laws. ⁵ Compute this amount by performing the calculation outlined in Lines B.1 through B.11, considering only deferred tax asset and liability amounts for state and local income tax purposes.	

⁵ In assessing whether a separate calculation is necessary, the bank should consider any differences in loss carryback or carryforward periods, or in other provisions of the tax law. If the tax laws of the state and local jurisdictions do not differ significantly from federal income tax laws, then the calculation of deferred income tax expense (benefit) can be made in the aggregate. The bank would complete Lines B.1 through B.11 on the worksheet considering both the federal and state and local income tax rates. The rate used should consider whether amounts paid in one jurisdiction are deductible in another jurisdiction. For example, since state and local taxes are deductible for federal income tax purposes, the aggregate combined rate generally would be (1) the federal tax rate plus (2) the state and local tax rate minus (3) the federal tax rate.

B.13.	pe	ar-te riod d ex	CO	vere	ed b	y S	che	edul	e R	l, it	em	8, "	Inc	omo	e (lo	oss)) be	fore	e ind	com	ne ta	axe					(+)			
B.14.	ap	ar-te plicate (l	able	e cu	rre	nt a	nd (defe	erre	d ir	cor	nè 1	tax	exp	ens	se (ben	efit) fo	r the	e ye	ar t	to							
* *	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*

FEDERAL INCOME TAX RATES FOR BANKS (Regular Tax System - Calendar Year 2010)

- 1. If the amount on Line A.14 above is less than or equal to \$50,000, Line A.15 is 15% of Line A.14.
- 2. If the amount on Line A.14 is greater than \$50,000 but less than or equal to \$75,000, Line A.15 is \$7,500 plus 25% of the amount by which Line A.14 exceeds \$50,000.
- 3. If the amount on Line A.14 is greater than \$75,000 but less than or equal to \$100,000, Line A.15 is \$13,750 plus 34% of the amount by which Line A.14 exceeds \$75,000.
- 4. If the amount on Line A.14 is greater than \$100,000 but less than or equal to \$335,000, Line A.15 is \$22,250 plus 39% of the amount by which Line A.14 exceeds \$100,000.
- 5. If the amount on Line A.14 is greater than \$335,000 but less than or equal to \$10,000,000, Line A.15 is 34% of Line A.14.
- 6. If the amount on Line A.14 is greater than \$10,000,000 but less than or equal to \$15,000,000, Line A.15 is \$3,400,000 plus 35% of the amount by which Line A.14 exceeds \$10,000,000.
- 7. If the amount on Line A.14 is greater than \$15,000,000 but less than or equal to \$18,333,333, Line A.15 is \$5,150,000 plus 38% of the amount by which Line A.14 exceeds \$15,000,000.
- 8. If the amount on Line A.14 is greater than \$18,333,333, Line A.15 is 35% of Line A.14.