




US Army Corps  
of Engineers®  
Engineer Research and  
Development Center

# A Bosque Riparian Community Index Model for the Middle Rio Grande, Albuquerque, New Mexico

Model Documentation  
Draft Report

Kelly A. Burks-Copes and Antisa C. Webb

December 2009





# **A Bosque Riparian Community Index Model for the Middle Rio Grande, Albuquerque, New Mexico**

## **Model Documentation**

Kelly A. Burks-Copes and Antisa C. Webb

*Environmental Laboratory  
U.S. Army Engineer Research and Development Center  
3909 Halls Ferry Road  
Vicksburg, MS 39180-6199*

Draft report

Approved for public release; distribution is unlimited. [or a restricted statement]

Prepared for U.S. Army Corps of Engineers

Under Work Unit NA

Monitored by Environmental Laboratory  
U.S. Army Engineer Research and Development Center  
3909 Halls Ferry Road, Vicksburg, MS 39180-6199

**Abstract:** Over the last century, the Middle Rio Grande was subjected to significant anthropogenic pressures producing a highly degraded ecosystem that today is poised on the brink of collapse. In 2002, the U.S. Army Corps of Engineers (USACE) (Albuquerque District) was authorized to study the river and prepare an Environmental Assessment (EA), as required under the tenets of the National Environmental Policy Act (NEPA), to evaluate the effects of proposed ecosystem restoration alternatives on the watershed's significant resources. As part of the process, a multi-agency, multi-disciplinary evaluation team was established to formulate alternatives that would address three critical problems: 1) hydrological alternations, 2) bosque (riparian) ecosystem degradation, and 3) the loss of key ecological services to the surrounding community. Between 2005 and 2008, this team designed, calibrated, and applied a community-based index model for the bosque riparian ecosystem using field and spatial data gathered from 27 reference sample sites scattered across the watershed. This unique community was modeled using 23 individual variables combined into numerous predictive community functional components (i.e., Biotic Integrity, Hydrology, and Spatial context) capable of capturing the changes to ecosystem integrity in response to changes in land and water management activities proposed by the study. The intent of this document is to provide the scientific basis upon which the model was developed, and describe the 3-year long process the team undertook to complete this effort. Although some results are presented here to demonstrate and verify the veracity of the model's calibration and subsequent outputs, readers interested in the application of this model on the Middle Rio Grande project must refer to our second report entitled, "Middle Rio Grande Bosque Ecosystem Restoration Feasibility Study Habitat Assessment Using Habitat Evaluation Procedures (HEP): Analyses, Results And Documentation" ([Burks-Copes and Webb 2009](#)).

**DISCLAIMER:** The contents of this report are not to be used for advertising, publication, or promotional purposes. Citation of trade names does not constitute an official endorsement or approval of the use of such commercial products. All product names and trademarks cited are the property of their respective owners. The findings of this report are not to be construed as an official Department of the Army position unless so designated by other authorized documents.

**DESTROY THIS REPORT WHEN NO LONGER NEEDED. DO NOT RETURN IT TO THE ORIGINATOR.**

## Contents

Abstract .....	ii
Contents .....	iii
Figures and Tables .....	v
Preface.....	x
<b>1 Introduction .....</b>	<b>1</b>
Study Background .....	5
Purpose of the Model.....	6
Contribution to the Planning Effort.....	8
Planning Model Certification .....	9
Report Objectives .....	10
Report Structure.....	11
<b>2 HEP Overview .....</b>	<b>13</b>
The HEP Process.....	13
<i>Statement of Limitations</i> .....	13
<i>HSI Models in HEP</i> .....	14
<i>Habitat Units in HEP</i> .....	14
<i>Capturing Changes Over Time in HEP Applications</i> .....	15
Developing Index Models for HEP .....	16
<i>Steps in Model Development</i> .....	16
<i>Model Review Process</i> .....	17
<b>3 Community-based HSI Models .....</b>	<b>19</b>
Model Development Workshops.....	19
Coupling Conceptual Modeling and Index Modeling.....	20
Bosque Riparian Community Characterization.....	23
<i>Reference Domain for the Models</i> .....	24
<i>Climatic Characterization</i> .....	28
<i>Vegetative Characterization</i> .....	30
<i>Hydrologic Characterization</i> .....	43
<i>Geomorphic Characterization</i> .....	48
Habitat Suitability Index (HSI) Model .....	53
<i>Model Components</i> .....	54
<i>Model Flow Diagram</i> .....	63
<i>Model Formulas</i> .....	65
<b>4 HSI Model Sampling and Calibration Protocols .....</b>	<b>69</b>
HSI Model Variables Selection Rationale .....	69
<i>A Reference-Based Modeling Approach</i> .....	76
<i>Reference Site Selection</i> .....	81

<i>Sampling Protocol – Site Preparations</i> .....	85
<i>Vegetative Data Collection</i> .....	87
<i>Spatially Explicit Data Collection</i> .....	92
<i>Hydrologic Data</i> .....	96
HSI Statistical Analysis and Curve Calibrations .....	98
Model Results .....	101
Model Verification .....	110
Model Validation .....	114
<b>5 Summary and Conclusions .....</b>	<b>117</b>
References .....	<b>119</b>
Appendix A: Notation .....	<b>A-1</b>
Appendix B: Glossary .....	<b>B-1</b>
Appendix C: Model Certification Crosswalk .....	<b>C-1</b>
Appendix D: E-Team Participants.....	<b>D-1</b>
Appendix E: HSI Curves for the Bosque Riparian Model.....	<b>E-1</b>
Appendix F Useful Field Protocols and Checklists for the Bosque Riparian Model .....	<b>F-1</b>
H&O Classification System .....	F-1
Undesirable vs. Desirable Species Lists .....	F-10
Field Sampling Protocols and Diagrams .....	F-11
<i>Point-Intercept</i> .....	F-12
<i>Line-Intercept</i> .....	F-13
<i>Point-Centered Quarter</i> .....	F-14
Appendix G: Model Review Forms and Comments .....	<b>G-1</b>
Certificate of Product Check.....	G-13

# Figures and Tables

## Figures

Figure 1. The arid Southwest often appears to be a desolate landscape, yet the presence of water offers an opportunity for fish and wildlife to find a niche (photo from <a href="http://www.wanapiteicanoe.com/trips.asp?ID=39">www.wanapiteicanoe.com/trips.asp?ID=39</a> MAY 2008). .....	1
Figure 2. Riparian corridors immediately adjacent to rivers in the arid southwest offer lush habitat for fish and wildlife species. ....	2
Figure 3. Location of the Rio Grande in the arid Southwest. Images capture the changing characteristics of the river as it flows from Colorado (top), through New Mexico (middle), and down into Texas (bottom) on its way to the Gulf of Mexico. ....	3
Figure 4. Cottonwood riparian gallery forests ablaze with fall colors along the Rio Grande. ....	4
Figure 5. The Rio Grande flows through the heart of Albuquerque (seen in the background at the base of the mountains) on its way south to the Gulf of Mexico. ....	5
Figure 6. Overview of the successive steps (1-6) of the community-based index model building and application process for ecosystem restoration, where two data sets (one for calibration and one for alternative evaluations) are used (adapted from Guisan and Zimmerman 2000). ....	21
Figure 7. A conceptual model for the MRGBER. ....	22
Figure 8. Within the conceptual modeling building framework, the various model components (color-coded for organization purposes) are pieced together to capture the essence of community functionality using the ecosystem puzzle analogy. ....	23
Figure 9. Reference domain for the Rio Grande-Albuquerque watershed index model. ....	25
Figure 10. Parks maintained inside the MRGBER Study Area. ....	27
Figure 11. At stake - the dwindling cottonwood-dominated bosque community. ....	30
Figure 12. Classic examples of Type I (Mature Riparian Forests) vegetation in the study area. ....	32
Figure 13. Classic examples of Type II (Mature Riparian Forests) vegetation in the study area. ....	33
Figure 14. Classic examples of Type III (Intermediate-aged Riparian Woodlands) vegetation in the study area. ....	34
Figure 15. Classic examples of Type IV (Intermediate-aged Riparian Woodland/Savannahs) vegetation in the study area. ....	35
Figure 16. Classic examples of Type V (Riparian Shrubs) vegetation in the study area. ....	36
Figure 17. Classic examples of Type IV (Dry Grass Meadows and Wet Marshes) vegetation in the study area. ....	37
Figure 18. Location of 2003 bosque fires (map taken from USACE 2007b). ....	38
Figure 19. The nighttime sky is aglow with the firelight coming off the bosque wildfires. ....	39
Figure 20. Untreated forests (left) carry extensive fuel loads susceptible to catastrophic fires. The District and stakeholders actively reduce fuel loads to reduce the risk (right). These areas have reduced functionality (lower habitat suitability). ....	40
Figure 21. Baseline cover type map for the project study area. ....	42
Figure 22. Acreage distribution of cover types in the MRGBER study area. ....	43

Figure 23. The hydrologic connection to the bosque is readily apparent. The diversity and health of the riparian community hinges on the restoration of natural flood pulsing to facilitate sediment deposition and subsequent cottonwood recruitment. ....	44
Figure 24. Timeline of human activities since 1880 that have affected the Rio Grande (USACE 2007a). ....	46
Figure 25. The Rio Grande River was once a heavily braided stream meandering across the arid area. ....	49
Figure 26. The historic 500-year floodplain of the Middle Rio Grande was once much wider than its current channelized state. ....	50
Figure 27. Jetty jacks lined along the bank of the Rio Grande trap sediment and plant material during flooding events, stabilized over-bank areas over the course of several years. ....	51
Figure 28. The middle Rio Grande is often characterized by numerous sandbars and a straight channel resulting from the placement of jetty jack fields and levees. ....	52
Figure 29. The challenge for the E-Team was to develop a model robust enough to capture the unique character of the Middle Rio Grande’s bosque community. ....	53
Figure 30. Vegetation response to no overbank flooding (above) versus regular flooding in the riparian zone (below) (USACE 2007a). ....	55
Figure 31. Hydrology dictates the functionality of the bosque ecosystem. ....	56
Figure 32. Along the banks of the Middle Rio Grande, anthropogenic pressures have resulted in an extremely degraded bosque community subject to catastrophic fires, exotic species encroachment and a loss of vegetative recruitment in the cottonwood riparian community. In 50 years, the bosque could be completely devoid of riparian forest without intervention. ....	58
Figure 33. Flood protection projects (e.g., levees, riverside drains and jetty jacks) have reduced the Rio Grande’s original floodplain to fraction of its size in the study area (USACE 2003a). ....	59
Figure 34. Vegetative indicators, particularly cover, densities, native species dominance and biodiversity, capture the bosque community’s habitat potential. ....	60
Figure 35. Structural complexity offers numerous benefits to resident wildlife in the bosque community. ....	61
Figure 36. The San Antonio Oxbow offers an ideal perspective from above illustrating the classic bosque mosaic of unique patches of forested habitat ribboned throughout with wetland (meadow and marsh) complexes. ....	62
Figure 37. Fragmentation and urban encroachment is a common problem for the bosque ecosystem. ....	63
Figure 38. Flow diagram depicting combinations of model components and variables to form the Bosque community index model in the MRGBER study. There are two versions of the model depending on the cover types being evaluated. Types I-V use the upper diagram, and Types VI us the lower diagram. ....	64
Figure 39. Bosque reference sites in the MRGBER study area used to calibrate the Bosque community index model. ....	84
Figure 40. Illustration of the MRGBER baseline sampling design for the Bosque Riparian HSI model components. Up to three 120-m plots (crosses) were established in a single vegetation polygon. ....	85
Figure 41. Details of the “cross” configuration used to sample the vegetative variables in the MRGBER study. ....	86
Figure 42. Example of curve calibration method using the reference mean and its standard deviation. ....	99
Figure 43. The model calibration approach was flexible enough to encourage and incorporate professional expertise into the methodology. Here, the reference data support the separation of cover types based on mean data. Type 1 and 3 classes have significantly higher tree canopy cover, shading out the herbaceous layers closer to the ground. As a result, the HSI model was calibrated to capture this unique feature. ....	100



Figure 44. Example of curve calibration method using a combination of watershed means, standard deviations and expert opinion. ....	101
Figure 45. Reaches delineated for the baseline HSI assessment of the MRGBER study .....	102
Figure 46. Baseline graphical results for the bosque community. ....	109
Figure 47. A Pearson's correlation of expert team's opinion of site functionality and the HEP results indicate that they are positively related to some degree.....	113
Figure F - 1. Illustration of the point-intercept method used to record aerial herbaceous plant cover for the MRGBER study. ....	F-12
Figure F - 2. Illustration of the line-intercept method used to record shrub cover for the MRGBER study .....	F-13
Figure F - 3. Illustration of point-centered quarter method used to record tree and root-sprout density and size.....	F-15

## Tables

Table 1. Weather averages for Albuquerque, New Mexico.....	28
Table 2. Cover types identified and mapped for the MRGBER study area.....	41
Table 3. Index formulas for the MRGBER Bosque community model. ....	66
Table 4. Variables and rationales for association in the bosque riparian community index model. ....	70
Table 5. Middle Rio Grande Reference Sites.....	82
Table 6. Field sampling protocols summarized for the variables associated with the Bosque Riparian community index model.....	88
Table 7. GIS sampling protocols summarized for the variables associated with the Bosque Riparian community index model.....	93
Table 8. Hydrologic data sampling protocols summarized for the variables associated with the Bosque Riparian community index model.....	97
Table 9. Baseline data for the five reaches used to verify the bosque riparian HSI model.....	104
Table 10. Interpretation of HSI scores resulting from HEP assessments.....	107
Table 11. Baseline tabular results for the bosque riparian community. ....	108
Table 12. Baseline results for the Bosque Riparian HSI assessment of the reference sites. ....	111
Table 13. Comparison of the baseline reference results to the E-Team's expectation of reference conditions.....	112
Table C - 1. Crosswalk between EC 1105-2-407 model certification requirements and information contained in this report.....	C-1
Table D - 1. Model development workshop(s) participants. ....	D-1
Table F - 1. Vegetation structure categories using modified Hink & Ohmart classification. ....	F-2
Table F - 2. Crosswalk between the commonly used Hink and Omart vegetative classification system and the Bosque Riparian HSI Model's cover type classification naming conventions.....	F-3
Table F - 3. List of undesirable indicator species when applying the model.....	F-10
Table F - 4. List of native indicator species when applying the model. ....	F-11
Table G - 1. Review comments.....	G-3
Table G - 2. Internal ERDC-EL Technology Transfer Review Form.....	G-9

---

Table G - 3. Security Clearance Form for ERDC-EL reports. .... G-11



## Preface

This report provides the documentation of newly developed community-based index model [based on the Habitat Evaluation Procedures (HEP)] model for the Middle Rio Grande as it runs through the heart of Albuquerque, New Mexico.

The work described herein was conducted at the request of the U.S. Army Engineer District, Albuquerque, New Mexico. This report was prepared by Ms. Kelly A. Burks-Copes and Ms. Antisa C. Webb, U.S. Army Engineer Research and Development Center (ERDC), Environmental Laboratory (EL), Vicksburg, Mississippi. At the time of this report, Ms. Burks-Copes and Ms. Webb were ecologists in the Ecological Resources Branch.

Many people contributed to the overall success of the production of the model documentation. The authors wish to thank the following people for their hard work and persistence during the intensive months over which the project was assessed: Ms. Jennifer Emerson (Bowhead Information Technology Services), Ms. Ondrea Hummel (Albuquerque District), and Mr. Seth Jones (Galveston District). We also thank Dr. Andrew Casper (ERDC), Ms. Kristine Nemecek (formerly of the Kansas City District), and Mr. Todd Kaplan (Parametrix) for their comprehensive review of the report.

This report was prepared under the general supervision of Ms. Antisa C. Webb, Chief, Ecological Resources Branch and Dr. Edmond J. Russo, Chief, Ecosystem Evaluation and Engineering Division. At the time of publication of this report, Dr. Beth Fleming was Director of EL.

This report should be cited as follows:

Burks-Copes, K. A., and A. C. Webb. 2009. A Bosque Riparian Community Index Model for the Middle Rio Grande, Albuquerque, New Mexico. Model Documentation Draft Report. U.S. Army Engineer Research and Development Center, Environmental Laboratory, Vicksburg, MS.



# 1 Introduction

The desiccated landscape of the Southwest brings to mind tumbleweeds blowing along dusty grounds, ancient petroglyphs carved in dark caves and canyon walls, cattle skulls blanching under the merciless sun, and sidewinders slithering between the cacti. But running through these harsh and arid region are ribbons of lush green; narrow corridors where rivers and streams, some ephemeral, some continually flowing, have slaked the parched desert to give rise to rare yet significant riparian ecosystems rich with life (Figure 1).



Figure 1. The arid Southwest often appears to be a desolate landscape, yet the presence of water offers an opportunity for fish and wildlife to find a niche (photo from [www.wanapiteicanoe.com/trips.asp?ID=39](http://www.wanapiteicanoe.com/trips.asp?ID=39) MAY 2008).

While only occupying a mere fraction of the land area, these riparian corridors support both the largest concentrations of animal and plant life, and the majority of species diversity in the desert Southwest ([Johnson and Jones 1977](#), [Johnson et al. 1985](#), [Knopf et al. 1988](#), [Ohmart et al. 1988](#), [Dahl 1990](#), [Johnson 1991](#), [Minckley and Brown 1994](#), [Noss et al. 1995](#), [American Bird Conservancy 2008](#)) (Figure 2).



Figure 2. Riparian corridors immediately adjacent to rivers in the arid southwest offer lush habitat for fish and wildlife species.<sup>1</sup>

Perhaps one of the more notable riparian ecosystems is found along the Rio Grande. Arising in the San Juan Mountains of southwest Colorado, the river flows southwest through the middle of New Mexico and into Texas along the Texas-Mexico border emptying finally into the Gulf of Mexico. The Rio Grande offers one of the more ecologically complex, highly resilient, and culturally significant resource in semi-arid western United States (Figure 3).

---

<sup>1</sup> Photo take from <http://www.domney.com/> (MAY 2008)




Figure 3. Location of the Rio Grande in the arid Southwest. Images capture the changing characteristics of the river as it flows from Colorado (top), through New Mexico (middle), and down into Texas (bottom) on its way to the Gulf of Mexico.

Historically, the Rio Grande was considered a braided, aggrading stream that meandered freely across a wide floodplain much larger than the current floodway ecosystem. As it meandered through time and space, the Rio Grande created and renewed the unique cottonwood riparian gallery forest communities. “Bosque” was the Spanish word that was used traditionally in the southwest to describe these unique wooded riparian ecosystems (Figure 4).





Figure 4. Cottonwood riparian gallery forests ablaze with fall colors along the Rio Grande.<sup>1</sup>

Over the last century, the Middle Rio Grande was subjected to significant anthropogenic pressures producing a highly degraded ecosystem that today is poised on the brink of collapse. Water management and flow regulation along the Middle Rio Grande during this century has decoupled the linkage between the floodplain and the river and resulted in extensive changes in the riparian forest ecosystem (Ellis et al. 1996). The elimination of flooding has disrupted the functional integrity of these disconnected forests and contributed to the decline of the Rio Grande Valley cottonwood. Estimates of riparian habitat loss in the Southwest range from 40% to 90% (Dahl 1990), and desert riparian habitats are considered to be one of this region's most endangered ecosystems (Minckley and Brown 1994, Noss et al. 1995). Decline of natural riparian structure and function of the bosque ecosystem was recognized in the 1980s as a major ecological change in the Middle Rio Grande valley (Hink and Ohmart 1984; Howe and Knopf, 1991).

---

<sup>1</sup> Photo taken from  
[http://joemonahansnewmexico.blogspot.com/uploaded\\_images/New%20Mexico%20-%20Rio%20Grande-794868.jpg](http://joemonahansnewmexico.blogspot.com/uploaded_images/New%20Mexico%20-%20Rio%20Grande-794868.jpg) MAY 2008)

## Study Background

In 2002, the USACE Albuquerque District was authorized to conduct a Reconnaissance study focused on a 17-mile long stretch of the Rio Grande flowing through the city of Albuquerque, New Mexico (USACE 2002, 2003a, 2007b, 2008a) (Figure 5).



Figure 5. The Rio Grande flows through the heart of Albuquerque (seen in the background at the base of the mountains) on its way south to the Gulf of Mexico.

The reconnaissance study determined that there was a federal interest in participating in cost-shared feasibility studies to investigate ecosystem restoration, educational/ interpretive opportunities and low-impact recreational opportunities for the Rio Grande floodway as it passes through Albuquerque, New Mexico. In 2004, a Feasibility Cost Sharing Agreement was signed between the Middle Rio Grande Conservancy District (MRGCD), as the non-Federal Sponsor, and the USACE subsequently initiated the feasibility phase of the study. The purpose of this feasibility phase study was to determine if there was a Federal

(USACE) interest in addressing the water resource problems and opportunities in the Middle Rio Grande area of Bernalillo County, New Mexico.<sup>1</sup>

In 2004, the USACE Albuquerque District contacted the U.S. Army Engineer Research and Development Center's Environmental Laboratory (ERDC-EL) to assist in these endeavors. The Middle Rio Grande study documentation identified and recommended effective, affordable and environmentally sensitive ecosystem restoration features throughout the middle reach of the Rio Grande system (USACE 2002, 2003a, 2007b, 2008a). The goal was to provide the necessary engineering, economic and environmental plans in a timely manner to establish viable projects that would be acceptable to the public, local sponsors and USACE. The intent of this collaborative effort was to provide a framework for making decisions that would result in the restoration of the bosque ecosystem's structure and function.

The District has prepared an Environmental Assessment (EA), as required under the tenets of the National Environmental Policy Act (NEPA), to evaluate the benefits of the proposed ecosystem restoration measures in the study area (USACE 2008b). As part of the process, a multi-agency evaluation team was established to (1) identify environmental issues and concerns; (2) evaluate the significance of fish and wildlife resources and select resources; (3) recommend and review environmental alternatives and studies; and (4) evaluate potential benefits of the proposed plans.

## Purpose of the Model

Planning, management, and policy decisions require information on the status, condition and trends of these complex ecosystems and their components at various scales (e.g. local, regional, watershed and system levels) to make reasonable and informed decisions about the planning management and conservation of sensitive or valued resources. One well accepted solution has been to develop index models that assess ecosystems at varying scales. By definition, index models are comprehensive, multi-scale, grounded in natural history, relevant and helpful, able to integrate

---

<sup>1</sup> An a complete list of acronyms and a glossary have been provided in [Appendix A](#) and [Appendix B](#) of this report.

terrestrial and aquatic environments, flexible and measurable (Andreasen et al. 2003). Determining the value of diverse biological resources in this study required a method that captured the complex biotic patterns of the landscape, rather than merely focusing on a single species habitat or suitability requirements within the study area. In effect, the Ecosystem Assessment Team (E-Team) made the decision to assess ecosystem benefits using community-based (functional) models rather than employing a series of species- or guild-based models.

Ecosystem functions are defined here as a series of processes that take place within an ecosystem. These include the storage of water, transformation of nutrients, growth of living matter, and diversity of plants, and they have value for the community itself, for surrounding ecosystems, and for people. Functions can be grouped broadly as habitat, hydrologic, water quality, and spatial integrity although these distinctions are somewhat arbitrary and simplistic. For example, the value of a wetland for recreation (hunting, fishing, bird watching) is a product of all the processes that work together to create and maintain the ecosystem. Not all communities perform all functions nor do they perform all functions equally well. The location and size of a community may determine what functions it will perform. For example, the geographic location may determine its habitat functions, and the location of community within a watershed may determine its hydrologic or water-quality functional capacity. Many factors determine how well a community will perform these functions: climatic conditions, quantity and quality of water entering the system, and disturbances or alteration within the community or the surrounding landscape. Disturbances may be the result of natural conditions, such as an extended drought, or human activities, such as land clearing, dredging, or the introduction of invasive species.

The purpose of this modeling effort was to broadly capture existing, (baseline) conditions of the communities, and compare changes that would occur to the resources present given different project scenarios or alternatives under the standard USACE planning paradigm (USACE 2000). The model was used to facilitate plan formulation based upon project benefits. The purpose of the model was not to exhaustively capture the full range of all chemical, physical, and biological characteristics of the project area, but to provide tools for making comparisons between potential plans in order to select plans with the highest benefits. Planning



decisions for the feasibility study were subsequently made based on the results of the model applied with the well received and respected Habitat Evaluation Procedures (HEP) ([USFWS 1980a-c](#)) framework.

## **Contribution to the Planning Effort**

The model then, helped to characterize the baseline conditions (in a quantitative manner) of the numerous ecological resources throughout the watershed. The HEP method assisted the study team in the projection of change to fundamental ecosystem processes<sup>1</sup> (without which, ecosystem restoration itself could not happen), as the multiple alternative scenarios were proposed. The study team designed the HEP assessments to evaluate the future changes both in quantity (acres) and quality (community habitat suitability) of aquatic, wetland and terrestrial ecosystems simultaneously. Outputs were calculated in terms of annualized changes anticipated over the life of the project (aka period of analysis).

As noted earlier, the E-team was convened early in the evaluation process.<sup>2</sup> Scientists from the U.S. Army Engineer Research and Development Center, Environmental Laboratory (ERDC-EL) facilitated the efforts. Representatives from the Albuquerque District, U. S. Fish and Wildlife Service (USFWS), U.S. Forest Service (USFS), Bureau of Reclamation (BOR), Interstate Stream Commission (ISC), New Mexico Department of Game and Fish (NMDGF), New Mexico State Forestry Division (NMSFD), Natural Heritage New Mexico (NHNM), Rocky Mountain Research Station (RMRS), Middle Rio Grande Conservancy District (MRGCD), City of Albuquerque Open Space Program, University of New Mexico (UNM), and Parametrix consultants actively participated in the assessment process. The remainder of this document focuses on the development of the community-based Habitat Suitability Index (HSI) model developed by the E-Team for the Middle Rio Grande Bosque Ecosystem Restoration (MRGBER) feasibility study.

---

<sup>1</sup> There are four fundamental ecosystem processes – water cycling, mineral cycling, solar energy flow, and community dynamics (aka succession).

<sup>2</sup> A list of E-Team participants can be found in [Appendix D](#).

## Planning Model Certification

As an aside, the USACE Planning Models Improvement Program (PMIP) was established to review, improve, and validate analytical tools and models for USACE Civil Works business programs. In May of 2005, the PMIP developed Engineering Circular (EC) 1105-2-407, Planning Models Improvement Program: Model Certification (USACE 2005). This EC requires the use of certified models for all planning activities. It tasks the Planning Centers of Expertise to evaluate the technical soundness of all planning models based on theory and computational correctness. EC 1105-2-407 defines planning models as,

*“ . . . any models and analytical tools that planners use to define water resources management problems and opportunities, to formulate potential alternatives to address the problems and take advantage of the opportunities, to evaluate potential effects of alternatives and to support decision-making.”*

Clearly, the community-based HSI model developed for the study must be either certified or approved for one-time use. The Albuquerque District initiated this review in 2008 and received a memo from the USACE Eco-PCX granting one-time-use approval in April 2009 (*Appendix C*). Information necessary to facilitate model certification/one-time-use approval is outlined in *Table 2* of the *EC 1105-2-407* (pages 9-11). To assist the reviewers in the certification effort for the model, the authors have developed an appendix to crosswalk the EC checklist requirements and this report (*Appendix C*).

For purposes of model certification, it is important to note that the model must be formally certified or approved for one-time-use, but the methodology under which it is applied (i.e., HEP) does not require certification as it is considered part of the application process. HEP in particular has been specifically addressed in the EC:

*“The Habitat Evaluation Procedures (HEP) is an established approach to assessment of natural resources, developed by the US Fish and Wildlife Service in conjunction with other agencies. The HEP approach has been well documented and is approved for use in Corps projects as an assessment framework that combines resource quality and quantity over time, and is appropriate*

*throughout the United States.”* (refer to [Attachment 3, page 22, of the EC](#))

The authors used the newly developed **Habitat Evaluation and Assessment Tools (HEAT)** ([Burks-Copes et al. 2008](#)) to automate the calculation of habitat units for the MRGBER study. This software is not a “shortcut” to HEP modeling, or a model in and of itself, but rather a series of computer-based programming modules that accept the input of mathematical details and data comprising the index model, and through their applications in the HEP or the Hydrogeomorphic Wetland Assessment (HGM) processes, calculates the outputs in responses to parameterized alternative conditions. The **HEAT** software contains two separate programming modules – one used for HEP applications referred to as the **EXpert Habitat Evaluation Procedures (EXHEP)** module, and a second used in HGM applications referred to as the **EXpert Hydrogeomorphic Approach to Wetland Assessments (EXHGM)** modules. The authors used the **EXHEP** module to calculate outputs for the MRGBER study. The developers of the **HEAT** tool (including both the **EXHEP** and **EXHGM** modules themselves) are pursuing certification through a separate initiative, and hope to have this tool through the process in the next year barring unforeseen financial and institutional problems.

The authors used **IWR Planning Suite**<sup>1</sup> to run the cost analyses for the restoration plans in the MRGBER study which was certified in 2008.

## Report Objectives

This document describes the development of the community-based HSI model for the bosque (riparian) community located along the banks of the Middle Rio Grande River running the heart of Albuquerque, New Mexico. The objectives of this report are to:

1. Briefly characterize the Middle Rio Grande watershed, within the study area, in central New Mexico;

---

<sup>1</sup> <http://www.pmcl.com/iwrplan/>

2. Characterize the bosque community used in the HEP evaluations and its applicable cover types;
3. Present the relationships of habitat maintenance components for the index model; and
4. Define and justify the selection of assessment variables and their associated curve calibrations used to characterize the components of the model.
5. Provide critical information to reviewers to facilitate the future certification/one-time-use approval of the index model.

## Report Structure

This report is organized in the following manner. *Chapter 1* provides the background, objectives, and organization of the document. *Chapter 2* provides a brief overview of HEP, and the method in which the model will be applied, including the procedures recommended for development and application of the HSI model. *Chapter 3* discusses the evolution of the model in terms of conceptual development, offers critical insight into the characterization of the community, provides details regarding the key functional components of the HSI model in particular (and its mathematical representations), and then concludes with the construction and testing of the HSI model over the last three years. *Chapter 4* offers insight into the HSI model's calibration approach, and offers descriptions of the assessment variables used to characterize the community including definitions, rationale for selection, and specific sampling guidelines. *Chapter 5* summarizes the model findings and discusses future research initiatives to expand its utility and context.

Several appendices are attached to this document. *Appendix A* is a list of acronyms used throughout this document. *Appendix B* is a glossary of commonly used terms regarding HSI model and the HEP evaluation. *Appendix C* offers a crosswalk between the standard requirements and information necessary to certify/approve the use of the model. *Appendix D* contains a point of contact for the formal minutes documenting the decisions made during the initial model development workshops and offers a complete list of E-Team participants. *Appendix E* provides individual index curves for the variables used in the model. *Appendix F* offers field data protocols and a crosswalk between the region's more notable vegetative classification system (Hink and Omart 1984) and the classification used in the index model described here. *Appendix E* contains



the model review forms and documents the review comments provided by the Albuquerque District and the workshop participants as the planning study proceeds through review.

## 2 HEP Overview

### The HEP Process

The HEP methodology is an environmental accounting process developed to appraise habitat suitability for fish and wildlife species in the face of potential change (USFWS 1980 a-c). Designed to predict the response of habitat parameters in a quantifiable fashion, HEP is an objective, reliable, and well-documented process used nationwide to generate environmental outputs for all levels of proposed projects and monitoring operations in the natural resources arena. When applied correctly, HEP provides an impartial look at environmental effects, and delivers measurable products to the user for comparative analysis.

In HEP, a Suitability Index (SI) is a mathematical relationship that reflects a species' or community's sensitivity to a change in a limiting factor (i.e., variable) within the habitat type. These suitability relationships are depicted using scatter plots and bar charts (i.e., suitability curves). The SI value (Y-axis) ranges from 0.0 to 1.0, where an SI = 0.0 represents a variable that is extremely limiting, and an SI = 1.0 represents a variable in abundance (not limiting) for the species or community. In HEP, an HSI model is a quantitative estimate of habitat conditions for an evaluation species or community. HSI models combine the SIs of measurable variables into a formula depicting the limiting characteristics of the site for the species/community on a scale of 0.0 (unsuitable) to 1.0 (optimal).

### Statement of Limitations

The HEP methodology can provide a rational, supportable, focused, and traceable evaluation of habitat functionality. However, the user must understand the basic HEP tenets as defined in supporting literature (USFWS 1980a-c) prior to attempting application of the methodology. Outcomes derived under HEP are dependent on the user's ability to predict future conditions and the reliability of resource data used. The user should understand that HEP is not a carrying capacity model and cannot comprehensively predict future species and species population sizes. Furthermore, HEP is not designed to compare across evaluation elements (e.g. compare prairie habitat to forest habitat). The user should not expect

HEP to provide the only predictive environmental response to project development scenarios, and should understand the limitations of the methodology's response to predictive evaluations prior to its application.<sup>1</sup>

### **HSI Models in HEP**

Users can select several indicator species to evaluate overall site fitness. In the HEP process, species are often selected on the basis of their ecological, recreational, spiritual, or economic value. In other instances, species are chosen for their representative value (i.e., one species can “represent” a group or guild of species which have similar habitat requirements). Most of these species can, in turn, be described using single or multiple habitat models and a single HSI mathematical formula. In some studies, several cover types are included in an HSI model to accurately reflect the complex interdependencies critical to the species' or community's existence. Regardless of the number of cover types incorporated within an HSI model, any HSI model based on the existence of a single life requisite requirement (e.g. food, water, cover or reproduction), uses a single formula to describe that relationship.

Some species are insufficiently examined using the simplistic approach. In these instances, a more detailed model can emphasize critical life requisites, increase limiting factor sensitivity, and improve the predictive power of the analysis. Multiple habitats and formulas are often necessary to calculate the habitat suitability of these more comprehensive HSI models. The second type of HSI model is used to capture the juxtaposition of habitats, essential dependencies, and performance requirements such as reproduction, roosting needs, escape cover demands, or winter cover that describe the sensitivity of a species or community. Multiple formula models require more extensive processing to evaluate habitat conditions.

### **Habitat Units in HEP**

HSI models can be tailored to a particular situation or application and adapted to meet the level of effort desired by the user. Thus, a single model (or a series of inter-related models) can be adapted to reflect a site's

---

<sup>1</sup> Additional support for the HEP methodology has been provided in *Appendix C, 2 Technical Quality, a. Theory.*

response to a particular design at any scale (e.g., species, community, ecosystem, regional, or global dimensions). Several agencies and organizations have adapted the basic HEP methodology for their specific needs in this manner (Inglis et al. 2006, Gillenwater et al. 2006, and Ahmadi-Nedushan et al. 2006). HEP combines both the habitat quality (HSI) and quantity of a site (measured in acres) to generate a measure of change referred to as Habitat Units (HUs). Once the HSI and habitat quantities have been determined, the HU values can be mathematically derived with the following equation:  $HU = HSI \times \text{Area (acres)}$ . Under the HEP methodology, one HU is equivalent to one acre of optimal habitat for a given species or community.

### **Capturing Changes Over Time in HEP Applications**

In studies spanning several years, Target Years (TYs) must be identified early in the process. Target Years are units of time measurements used in HEP that allow users to anticipate and direct significant changes (in area or quality) within the project (or site). As a rule, the baseline TY is always  $TY = 0$ , where the baseline year is defined as a point in time before proposed changes would be implemented. As a second rule, there must always be a  $TY = 1$  and a  $TY = X_2$ .  $TY_1$  is the first year land- and water-use conditions are expected to deviate from baseline conditions.  $TYX_2$  designates the ending target year. A new target year must be assigned for each year the user intends to develop or evaluate change within the site or project. The habitat conditions (quality and quantity) described for each TY are the expected conditions at the end of that year. It is important to maintain the same target years in both the environmental and economic analyses, and between the baseline and future analyses. In studies focused on the long-term effects, HUs generated for indicator species are estimated for several TYs to reflect the life of the project (aka period of analysis). In such analyses, future habitat conditions can be estimated for both the without-project (e.g., No Action Plan) and with-project conditions. Projected long-term effects of the project are reported in terms of Average Annual Habitat Units (AAHUs) values. Based on the AAHU outcomes, alternative designs can be formulated and trade-off analyses can be simulated to promote environmental optimization.

## Developing Index Models for HEP

Based on the USFWS's Ecological Service Manual (ESM) series on HEP ([USFWS 1980 a-c](#)), there are 11 steps involved in the application of HEP when assessing an environmental project:

1. Build a multi-disciplinary E-Team;
2. Define the project;
3. Map the site's cover types (CTs);
4. Select, modify and/or create index model(s);
5. Conduct field sampling;
6. Perform data management and statistical analyses;
7. Calculate baseline conditions;
8. Set goals and objectives, and define project life and TYs;
9. Generate Without-project (WOP) conditions and calculate outputs;
10. Generate With-project (WP) conditions and calculate outputs; and
11. Report the results of the analyses.

However, this document only addresses the development of the model used in the HEP process for this study. For further detail on each of the 11 steps, refer to the [Burks-Copes and Webb 2009](#) habitat assessment report for the MRGBER study.

### Steps in Model Development

Community assessment was identified as a priority for the District's upcoming feasibility study. However, few HSI community models were published and available for application. ERDC-EL proposed a strategy to the District to develop community models for the MRGBER study. The strategy entailed five steps:

1. Compile all available information that could be used to characterize the communities of concern.
2. Convene an expert panel in a workshop setting to examine this material and generate a list of significant resources and common characteristics (land cover classes, topography, hydrology, physical processes) of the system that could be combined in a meaningful manner to "model" the communities. In the workshop, it was important to outline study goals and objectives and then identify the desired model endpoints (e.g., outputs of the model). It was also critical for the participants to identify the limiting

factors present in the project area relative to the model endpoints and habitat requirements .The outcome of the workshop was a series of mathematical formulas that were identified as functional components (e.g., Hydrology, Vegetative Structure, Diversity, Connectivity, Disturbance, etc.) which were comprised of variables that were:

- a. biologically, ecologically, or functionally meaningful for the subject,
  - b. easily measured or estimated,
  - c. able to have scores assigned for past and future conditions,
  - d. related to an action that could be taken or a change expected to occur,
  - e. were influenced by planning and management actions, and
  - f. independent from other variables in each model.
3. Develop both a field and a spatial data collection protocol (using Geographic Information Systems or GIS) and in turn, use these strategies to collect all necessary data and apply these data to the model in both the “reference” setting and on the proposed project area
  4. Present the model results to an E-Team and revise/recalibrate the model based on their experiences, any additional and relevant regional data, and application directives.
  5. Submit the model to both internal ERDC/District/E-Team review and then request review from the initial expert panel that participated in the original workshop, as well as solicit review from independent regional experts who were not included in the model development and application process.

### **Model Review Process**

The process described in *Appendix G* is currently being implemented to assure that quality control is an integral part of model development and document production. In essence, a laboratory-directed model review process is underway, one that involves both direct-line supervisors of the model authors, and peer reviews by researchers and planning personnel outside of the model development team. It is important to note that the

District will be responsible for incorporating the ERDC-EL documents into their integrated feasibility study reports and documents.

### 3 Community-based HSI Models

As described earlier in *Chapter 2* of this report, index models can quantify the effects of change in a given ecosystem setting and can be used to account for restoration gains under the HEP assessment paradigm. This chapter describes the bosque (riparian) community found along the middle Rio Grande in central New Mexico (running through Albuquerque), and describes the process by which the E-Team developed and tested the resultant community-based HSI model. A general description of both the variables and their relationship to one another are described for the model as well. The goal of this chapter is to characterize the E-Team's effort to capture the character of the bosque ecosystem using a traditional index model-based approach.

#### Model Development Workshops

A series of ten workshops were held over the course of three years (2005-2008) to develop the model and characterize baseline conditions of the study area prior to plan formulation and alternative assessment for the ecosystem restoration study. A community-based index model (**Bosque Riparian Community**) was developed under this paradigm. Several federal state and local agencies, as well as local and regional experts from the stakeholder organizations, and private consultants, participated in the model workshops.<sup>1</sup> In the first workshop, the E-Team was briefed on the project scope and opportunities by the District planners. Land and water management activities (e.g., hydrologic alterations, urban development and agricultural production) were identified as the system's key anthropogenic drivers. The stressors (i.e., physical, chemical and biological changes to system structure and function) were identified and grouped into four categories: 1) hydrologic alteration, 2) geomorphic and topographic alteration, 3) urban encroachment and agricultural use, and 4) exotic species introductions. Each stressor altered ecosystem integrity within a water, soils, habitat and/or landscape context. For example, hydrologic alterations to the channel have caused changes not only in

---

<sup>1</sup>A list of E-Team participants can be found in *Appendix D*.



flooding frequency and duration, but have altered ecosystem function and structure across the basin. Urban encroachment has exacerbated these problems by reducing infiltration, increasing storm water runoff, and increasing disturbance regimes system-wide. These changes have ultimately led to opportunities for exotic species invasions reducing spatial complexity on a landscape scale. The direct and indirect effects of these alternations are as obvious as they are numerous – reduced hydrologic pulsing, reduced sediment transport, fragmentation, and loss of biodiversity.

### **Coupling Conceptual Modeling and Index Modeling**

Conceptual models are proving to be an innovative approach to organize, communicate, and facilitate analysis of natural resources at the landscape scale (Harwell et al. 1999, Turner et al. 2001, Henderson and O’Neil 2004, Davis et al. 2005, Ogden et al 2005, Watzin et al. 2005, Alvarez-Rogel et al. 2006). By definition a conceptual model is a representation of relationships among natural forces, factors, and human activities believed to impact, influence or lead to an interim or final ecological condition (Harwell et al. 1999, Henderson and O’Neil 2004). In most instances these models are presented as qualitative or descriptive narratives and illustrated by influence diagrams that depict the causal relationships among natural forces and human activities that produce changes in systems (Harwell et al. 1999, Turner et al. 2001, Ogden et al. 1005, Alvarez-Rogel et al. 2006). No doubt, conceptual models provide a forum in which individuals of multiple disciplines representing various agencies and outside interests can efficiently and effectively characterize the system and predict its response to potential alternatives in a descriptive manner. In theory and practice, conceptual models have proved an invaluable tool to focus stakeholders on developing ecosystem restoration goals given recognized drivers and stressors. These in turn are translated into essential ecosystem characteristics that can be established as targets for modeling activities.

For purposes of this study, a systematic framework was developed that coupled the traditional USACE planning process with an index modeling approach derived from a sound conceptual understanding of ecological principles and ecological risk assessment that characterized ecosystem integrity across spatial and temporal scales, organizational hierarchy, and ecosystem types, yet adapted to the project’s specific environmental goals.

Ideally, the development of conceptual models involves a close linkage with community-index modeling, and produces quantitative assessment of systematic ecological responses to planning scenarios (Figure 6).




Figure 6. Overview of the successive steps (1-6) of the community-based index model building and application process for ecosystem restoration, where two data sets (one for calibration and one for alternative evaluations) are used (adapted from Guisan and Zimmerman 2000).<sup>1</sup>

Under this MRGBER modeling paradigm, conceptual modeling led to the choice of an appropriate scale for conducting the analysis and to the selection of ecologically meaningful explanatory variables for the subsequent environmental (index) modeling efforts. The model was calibrated using reference-based conditions and modified when the application dictated a necessary change.

As a first step in the index model development process, ERDC-EL developed a conceptual model to illustrate the relationships between these

<sup>1</sup> It is important to note here that the same models used to evaluate alternatives should be used in the future to monitor the restored ecosystem and generate response thresholds to trigger adaptive management under the indicated feedback mechanism. As such, the District can use the models developed early-on in the process to adaptively manage the system over the long-term.

system-wide drivers and stressors and tried to highlight the ecosystem responses to these pressures across the entire Rio Grande-Albuquerque watershed (Figure 7).




Figure 7. A conceptual model for the MRGBER.

Conceptually speaking, the “Significant Ecosystem Components” (water, soils, habitat, and landscape) were characterized by parameters responsive to project design. These parameters or variables (hydroperiod, vegetative cover, disturbance, etc.) were grouped in a meaningful manner to quantify the functionality of the community in the face of change based on expert opinion and scientific literature. The effort to combine the variables in mathematical algorithms could then be viewed as community index modeling under the HEP paradigm. For purposes of organization, the community based index model was constructed from combinations of components – an analogy used was one of puzzle building. The individual model components were represented as “pieces” of the ecosystem puzzle,

that when combined captured the essence of the system's functionality (Figure 8).




Figure 8. Within the conceptual modeling building framework, the various model components (color-coded for organization purposes) are pieced together to capture the essence of community functionality using the ecosystem puzzle analogy.

Vegetation communities in the area ranged from riparian forests, shrublands, savannahs, meadows, open marshes to the river itself. Out of this effort a bosque (riparian zone) community model arose. Subsequent refinement of the model led to the identification of contributing ecosystem components, and a description of associated variables (with suggested sampling protocols) that can be used to measure ecosystem restoration benefits. The accuracy and utility of the proposed model was “tested” (e.g., validated and verified) with specific field and planning exercises on the District’s ongoing ecosystem restoration feasibility study. The application led ERDC-EL to modify the model several times over the course of the study to accommodate broader planning specifications.

### **Bosque Riparian Community Characterization**

River systems and their attendant wetland/riparian communities, referred to as “bosques” in New Mexico (derived from the Spanish word for forest), provide significant resources for both humans and wildlife in the semi-arid

western United States. Water resource management activities –diversions, dams, levees, drains, channelization and jetty jack installation–by Federal agencies and other entities, as well as ongoing urbanization, have significantly altered the hydrologic system and degraded the ecosystem function and value of the Rio Grande within New Mexico. The bosque is unique; it is a thin line of significant riparian habitat in an arid landscape of the Southwest. The habitat quality, although diminished over the past few decades, still remains one of the most significant in the region. The uniqueness of the Rio Grande system and its critical value as wildlife habitat emphasize its significance as a critical resource. Over 300 species of birds, mammals, amphibians and reptiles live in the bosque - more than double those found in any other major ecosystem in the State. In fact, the bosque serves as a critical migration route for thousands of North American birds moving along the Central Flyway.

Functional riparian systems such as the Middle Rio Grande bosque are becoming increasingly rare in the Southwest. Such systems located in the center of an urban area are rarer still. The Rio Grande with its bosque is a green ribbon that weaves together different communities of the Albuquerque metropolitan area both figuratively and physically, connecting the present-day urbanites to the original inhabitants in the region. For decades the bosque has provided ecosystem services (for example, water filtration, urban heat island mitigation, etc.) for Albuquerque and its neighboring communities. It also continues to provide unique aesthetic, cultural, educational and recreational opportunities for citizens and visitors to the region. The health of the region's many species of wildlife, as well as its human inhabitants, rests on the long-term health and viability of the Rio Grande bosque. Below we detail the classic character of New Mexico's bosque as it peppers the banks along the Rio Grande flowing through the heart of the city.

### **Reference Domain for the Models**

It is important to note that the model developed in this study is applicable to a specific domain: the riparian habitat between the levees along the 17-mile stretch of Rio Grande flowing through Albuquerque, New Mexico (Figure 9).




Figure 9. Reference domain for the Rio Grande-Albuquerque watershed index model.

The outflow of the city's North Diversion Channel forms the northern boundary of each model's domain, while the southern boundary is formed by the northern limits of the Pueblo of Isleta. The area is delimited on the east and west by the flood control levees, although the areas adjacent to the levees within the original floodplain have been considered in the calibration of the model.

The study area roughly corresponds to the *Rio Grande Valley State Park*, which runs through the center of Albuquerque and the County of Bernalillo. The park was dedicated for public uses and conservation purposes, and is one of the last intact cottonwood gallery forests along the Rio Grande. The bosque forest therein is one of the most biologically rich areas in the state and arguably one of the largest cottonwood riparian galleries in the southwestern United States (USACE 2002, 2003a, 2007b, 2008a,b).

The area is maintained as a part of the Middle Rio Grande Flood Control Acts of 1948 and 1950 and is within the Facilities of the *Middle Rio*

*Grande Project* (USACE 2002, 2003a, 2007b, 2008a,b). The bosque area within Albuquerque was designated as the *Rio Grande Valley State Park* through the Park Act of 1983 and is cooperatively managed by the City of Albuquerque Open Space Department and the MRGCD (Figure 10). The bosque within Corrales is designated as the *Corrales Bosque Preserve* and is cooperatively managed by the Village of Corrales and the Corrales Bosque Commission through an agreement with the MRGCD. *Sandia Pueblo* lands are managed by the Pueblo.





Figure 10. Parks maintained inside the MRGBER Study Area.

By definition, the model presented here can be applied within this physical and ecological domain. In all likelihood, the model can be used several miles upstream or downstream of this narrowly defined area. However, any attempt to port this model to other locations outside this domain will likely require a recalibration of the parameters and algorithms associated with the tool.



## Climatic Characterization

Albuquerque's climate is usually sunny and dry, with low relative humidity.<sup>1</sup> Brilliant sunshine defines the region, averaging more than 300 days a year; periods of variably mid and high-level cloudiness temper the sun at other times. Extended cloudiness is rare. The city has four distinct seasons, but the heat and cold are mild compared to the extremes that occur more commonly in other parts of the country.

Winters are rather brief but definite; daytime highs range from the mid-40s to upper 50s Fahrenheit, while the overnight lows drop into the low 20s to near 30 by sunrise; nights are often colder in the valley and uppermost foothills by several degrees, or during cold frontal passages from the Great Basin or Rocky Mountains (Table 1).

Table 1. Weather averages for Albuquerque, New Mexico.<sup>2</sup>

Month	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Record high	70°F (21°C)	78°F (26°C)	89°F (32°C)	89°F (32°C)	98°F (37°C)	107°F (42°C)	105°F (41°C)	101°F (38°C)	100°F (38°C)	91°F (33°C)	77°F (25°C)	72°F (22°C)
Average high	48°F (9°C)	55°F (13°C)	62°F (17°C)	71°F (22°C)	80°F (27°C)	90°F (32°C)	92°F (33°C)	89°F (32°C)	82°F (28°C)	71°F (22°C)	57°F (14°C)	48°F (9°C)
Average low	24°F (-4°C)	28°F (-2°C)	34°F (1°C)	41°F (5°C)	50°F (10°C)	59°F (15°C)	65°F (18°C)	63°F (17°C)	56°F (13°C)	44°F (7°C)	32°F (0°C)	24°F (-4°C)
Record low	-17°F (-27°C)	-6°F (-21°C)	6°F (-14°C)	12°F (-11°C)	28°F (-2°C)	37°F (3°C)	44°F (7°C)	45°F (7°C)	30°F (-1°C)	21°F (-6°C)	-7°F (-22°C)	-8°F (-22°C)
Precipitation inches (mm)	0.49 (12.4)	0.44 (11.2)	0.61 (15.5)	0.50 (12.7)	0.60 (15.2)	0.65 (16.5)	1.27 (32.3)	1.73 (43.9)	1.07 (27.2)	1.00 (25.4)	0.62 (15.7)	0.49 (12.4)

The occasional snowfall, associated with low pressure areas, fronts and troughs, often melts by the mid-afternoon; over half of the scant winter moisture occurs in the form of light rain showers, usually brief in duration. In the much higher and colder Sandia Mountains, moisture falls as snow; many years have enough snow to create decent skiing conditions at the local ski area.

<sup>1</sup> Information retrieved from Wikipedia

([http://en.wikipedia.org/wiki/Albuquerque,\\_New\\_Mexico#Climate](http://en.wikipedia.org/wiki/Albuquerque,_New_Mexico#Climate)) in September of 2008.

<sup>2</sup> [Weather.com - Monthly Averages for Albuquerque, NM](#) (SEPTEMBER 2008).

Spring time starts off windy and cool, sometimes unsettled with some rain and even light snow, though spring is usually the driest part of the year in Albuquerque. March and April tend to see many days with the wind blowing at 20 to 30 mph (32 to 48 km/h), and afternoon gusts can produce periods of blowing sand and dust. In May, the winds tend to subside, as temperatures start to feel like summer. Summer daytime highs range from the upper 80s to the upper 90's, while dropping into the low 60s to low 70s overnight; the valley and uppermost foothills are often several degrees cooler. Fall sees mild days and cool nights with less rain, though the weather can be more unsettled closer to winter.

Albuquerque's climate is classified as arid (BWk or BWh, depending on the particular scheme of the Köppen climate classification system<sup>1</sup> one uses), meaning average annual precipitation is less than half of evaporation, and the mean temperature of the coldest month is above freezing (32). Only the wettest areas of the Sandia foothills are barely semi-arid, where precipitation is more than half of, but still less than, evaporation; such areas are localized and usually lie above 6,000 feet (1,800 m) in elevation and often in arroyo drainages, signified by a slightly denser, taller growth of evergreen oak - juniper - pinon chaparral and rarely, woodland, often mixed with taller desert grasses. These elevated foothill areas still border arid areas, best described as desert grassland or desert shrub, on their west sides.

The mountains and highlands to the north and east of the city create a "rain shadow" effect, due to the drying of descending air movements; the city usually receives very little rain or snow, averaging 8-9 inches (216 mm) of precipitation per year. Valley and west mesa areas, farther from the mountains are drier, averaging 6-8 inches of annual precipitation; the Sandia foothills tend to lift any available moisture, enhancing precipitation to about 10-17 inches annually. Most precipitation occurs during the summer monsoon season (also called a chubasco in Mexico), typically starting in early July and ending in mid-September.

---

<sup>1</sup> [http://en.wikipedia.org/wiki/K%C3%B6ppen\\_climate\\_classification](http://en.wikipedia.org/wiki/K%C3%B6ppen_climate_classification) (SEPTEMBER 2008).

## Vegetative Characterization

An ecosystem's vegetation at any given time is determined by a variety of factors, including climate, topography, soils, proximity to bedrock, drainage, occurrence of fire, and human activities. Because of the temporal and spatial variability of these factors and the sensitivity of different forms of vegetation to these factors, the system's character is one of dynamic, changing juxtapositions (i.e., a fluid mosaic). For details regarding the historical conditions of the study area, refer to the District's documents ([USACE 2002](#), [2003a](#), [2007b](#), [2008a,b](#)). Of particular concern for this effort, is the state of the vegetative communities within the model domain (Figure 11).



Figure 11. At stake - the dwindling cottonwood-dominated bosque community.<sup>1</sup>

To fully quantify the habitat conditions for this area, it is useful to divide the project into manageable sections and quantify these in terms of acres per habitat type. This process, referred to as “cover typing,” allows the user

---

<sup>1</sup> Photo taken from [abgstyle.com/albuquerque\\_photo/000023.html](http://abgstyle.com/albuquerque_photo/000023.html) (MAY 2008).

to define the differences between vegetative “types” (e.g., forest, shrublands, wet/dry meadows, etc.), hydrology and soils characteristics, and clearly delineate these distinctions on a map. The final classification system, based primarily upon dominant vegetation cover, captures “natural” settings and common landuse practices in a specific and orderly fashion that accommodates USACE’s plan formulation process. The “Middle Rio Grande Biological Survey” completed by [Hink and Ohmart](#) in [1984](#) described the plant communities within the study area’s riparian zone and provided detailed information on species composition and the structure of cover types. Six general plant vegetation categories were developed by [Hink and Ohmart \(1984\)](#), based on the height of the vegetation and the make-up of the understory or lower layers:<sup>1</sup>

---

<sup>1</sup> In actuality, the Hink and Ohmart classification requires field biologists to identify vegetation at the species level, and has generated a unique naming convention based on these characterizations. Those familiar with the Hink and Ohmart system should refer to [Appendix F](#) to see a crosswalk for cover types used in this assessment and the detailed Hink and Ohmart classification.



- **Type I: Mature Riparian Forests** with tall trees ranging from 50 to 60 feet in height, closed canopies, and well established (relatively dense) understory composed of saplings and shrubs;




Figure 12. Classic examples of Type I (Mature Riparian Forests) vegetation in the study area.

- **Type II: Mature Riparian Forests** with tall trees exceeding 40 feet in height and nearly closed canopies, but limited sapling and shrub understory;




Figure 13. Classic examples of Type II (Mature Riparian Forests) vegetation in the study area.



- **Type III: Intermediate-aged Riparian Woodlands** characterized by mid-sized trees less than 30 feet in height, but with closed canopies and dense understory;




Figure 14. Classic examples of Type III (Intermediate-aged Riparian Woodlands) vegetation in the study area.

- **Type IV: Intermediate-aged Riparian Woodland/Savannahs** characterized by open stands of mid-sized trees with widely scattered shrubs and sparse herbaceous growth underneath;




Figure 15. Classic examples of Type IV (Intermediate-aged Riparian Woodland/Savannahs) vegetation in the study area.



- **Type V: Riparian Shrubs** are characterized by dense vegetation (shrubs and saplings) up to 15 ft in height, but lacking tall tree species, and often having dense herbaceous growth underneath; and




Figure 16. Classic examples of Type V (Riparian Shrubs) vegetation in the study area.

- **Type VI: Dry Grass Meadows and Wet Marshes** are characterized by scattered plant growth composed of short shrubs (less than 5 feet in height), seedlings, and grasses. This category includes both dry meadows and the rare marshes found in the oxbow of the Rio Grande River that are vegetated with cattail, bullrush, sedges, watercress and algae.




Figure 17. Classic examples of Type IV (Dry Grass Meadows and Wet Marshes) vegetation in the study area.

It should be noted, that severe fires took place in June 2003 burning 253 acres (Figure 18), and as a result, the City of Albuquerque Open Space Division (AOSD) initiated an extensive thinning project to prevent future fires in the Albuquerque area.



Figure 18. Location of 2003 bosque fires (map taken from [USACE 2007b](#)).

Unfortunately, two more fires occurred in 2004 - one between Rio Bravo and Interstate-25 (I-25) on both sides of the river burning approximately 63 acres and the other south of Bridge Blvd. on the east side of the river, burning approximately 18 acres ([USACE 2007b](#)) (Figure 19).



Figure 19. The nighttime sky is aglow with the firelight coming off the bosque wildfires.

Prior to these recent fires and in between them, the City has been thinning most areas within the *Rio Grande Valley State Park*. To date, approximately 2,300 of the 3,000 bosque acres in the park have been “treated” in some way by the AOSD, Ciudad Soil and Water Conservation District (SWCD), the Corps (through the Bosque Wildfire Project) and other agencies and private organizations. Some areas were lightly thinned while other areas were cleared of all non-native vegetation and dead material, depending on the level of fuel reduction required for the site. Clearing activities have greatly reduced the acreage of Type I, III, and V woodlands. Recently-created Type II stands are largely devoid of understory vegetation. However, Russian olive and salt cedar have begun sprouting from the root crowns of cut trees in treated stands.

Because the “treated” habitats were significantly different in terms of vegetative cover, infiltration, etc., from the “untreated” cover types in the region, the E-Team made a decision to capture these differences by dividing several of the Hink and Omart categories (namely Types II, IV,



and VI) into “Treated” and “Untreated” classifications (designated by “U’s”) to better capture the degraded habitat conditions in “fire managed” areas within the study boundary (Figure 20).<sup>1</sup>



Figure 20. Untreated forests (left) carry extensive fuel loads susceptible to catastrophic fires. The District and stakeholders actively reduce fuel loads to reduce the risk (right). These areas have reduced functionality (lower habitat suitability).

Open areas not associated with the model have been mapped, and offer potential areas of restoration and rehabilitation within the study area. To complete the characterization, a series of “Newly Developed” coverages were created as placeholders for conversion of the open areas and existing degraded areas into newly restored wetland (riparian) habitats. In the MRGBER study, twenty four unique habitat types were (i.e., cover types or CTs) were identified and mapped across the entire project study area (Table 2).

---

<sup>1</sup> Because the Albuquerque District knew that the fires and treatments had caused significant changes to the existing vegetation in the study area, an effort was undertaken to ground-truth and remap the reach in 2005 (again using the [Hink and Ohmart 1984](#) methodology and classification scheme). Details of this effort are described in [USACE 2007b](#). The 2005 updated mapping was used for this assessment.

Table 2. Cover types identified and mapped for the MRGBER study area.

No.	Code	Cover Type (and Land Use) Description
1	TYPE_1	H&O Class I not treated - MATURE RIPARIAN FOREST (Over 40' – closed canopy, established understory).
2	TYPE_2T	H&O Class II treated - MATURE RIPARIAN FOREST (Over 40' – nearly closed canopy, limited understory).
3	TYPE_2U	H&O Class II not treated - MATURE RIPARIAN FOREST (Over 40' – nearly closed canopy, limited understory).
4	TYPE_3	H&O Class III not treated - INTERMEDIATE AGED RIPARIAN WOODLAND (Closed canopy, lots of salt cedar and Russian olive).
5	TYPE_4T	H&O Class IV treated - INTERMEDIATE AGED RIPARIAN WOODLAND/SAVANNAH (Broken canopy, mostly grass understory).
6	TYPE_4U	H&O Class IV not treated - INTERMEDIATE AGED RIPARIAN WOODLAND/SAVANNAH (Broken canopy, mostly grass understory).
7	TYPE_5	H&O Class V Shrublands not treated - RIPARIAN SHRUB (no tall trees).
8	TYPE_6T	H&O Class VI dry (grass) meadow treated - SHORT SHRUBS/GRASSES – Open areas.
9	TYPE_6U	H&O Class VI dry (grass) meadow not treated - SHORT SHRUBS/GRASSES – Open areas.
10	TYPE_6W	H&O Class VI wet meadow not treated - SHORT SHRUBS/GRASSES – Open areas and Marsh.
11	OPENLAND	Open Areas
12	OPENWATER	Open Water
13	NEWTTYPE_1	Newly Developed Type 1
14	NEWTTYPE_2T	Newly Developed Type 2T
15	NEWTTYPE_2U	Newly Developed Type 2U
16	NEWTTYPE_3	Newly Developed Type 3
17	NEWTTYPE_4T	Newly Developed Type 4T
18	NEWTTYPE_4U	Newly Developed Type 4U
19	NEWTTYPE_5	Newly Developed Type 5
20	NEWTTYPE_6T	Newly Developed Type 6T
21	NEWTTYPE_6U	Newly Developed Type 6U
22	NEWTTYPE_6W	Newly Developed Type 6W
23	ISLANDS	Islands
24	UTILITY	Utility Areas

Cover types identified as "NEW" refer to newly developed areas proposed in conjunction with construction of proposed alternatives.

The existing cover types were subsequently mapped using a Geographic Information System (GIS) (and ground-truthed during the 2005 field season) (Figure 21).



Figure 21. Baseline cover type map for the project study area. <sup>1</sup>

<sup>1</sup>GIS shapefiles are available upon request - contact the District POC (Ondrea Hummel, contact information can be found in [Appendix D](#)).

Of the 5,321 acres mapped within the project boundary, the majority of the habitat was characterized as either Type I (Mature Riparian Forest – 2,111 acres) or Open Water (1,526 acres). (Figure 22).




Figure 22. Acreage distribution of cover types in the MRGBER study area.

The remaining Hink and Omart categories, namely Types II-VI, were relatively evenly represented (4-11%, 1,384 acres collectively), with the remaining acreages tied up in utility areas and open areas (253 acres or 4.4%).

### Hydrologic Characterization

Riparian wetlands develop and are maintained through time as the hydrologic cycle interacts with the landscape (Figure 23).





Figure 23. The hydrologic connection to the bosque is readily apparent. The diversity and health of the riparian community hinges on the restoration of natural flood pulsing to facilitate sediment deposition and subsequent cottonwood recruitment.<sup>1</sup>

These ecosystems then are the local manifestation of broader, large-scale processes (Bedford 1996). They occur in particular hydrogeological settings where characteristics of the landscape and climate favor the accumulation or retention of surface water and/or soil water (Winter 1988, Winter and Llamas 1993). By hydrogeologic setting, we refer here to the position of the bosque in the landscape with respect to the flows of surface water, ground water, and the geological characteristics that control the flow of water. These geological characteristics include surface relief, land surface slope, thickness and permeability of soils, and the composition, stratigraphy, and hydraulic properties of the underlying geological materials (Bedford 1996). Together, climate and the hydrogeologic setting determine the key variables that lead to the development and maintenance of the bosque community. Depending on


---

<sup>1</sup> Image from <http://flickr.com/photos/58969260@N00/1972259609/> (SEPTEMBER 2008).

the climatic setting and hydrogeologic position in the landscape, riparian wetlands receive varying proportions of their water supply from precipitation, ground water, and surface flooding.

Natural flows in the Rio Grande system are derived from two primary sources: (1) snowmelt originating predominately from the upstream, higher elevation portions of the watershed and (2) summer thunderstorms that tend to be more localized and concentrated at lower elevations (USACE 2007a). Under natural, unconstrained river conditions, the annual flow volume varies significantly from year to year, depending on climatic conditions (Waltemeyer 1987). Annual variations in the timing and volume of streamflow in the Rio Grande are strongly influenced by the El Niño-southern oscillation through its modulation of the seasonal cycles of temperature and precipitation and their effects on snow accumulation and melting (Lee et al. 2004). These cycles can be several years to decades long and can result in extended drought or wet periods. An extended period of below average precipitation occurred from the early 1940s through the mid 1970s and above average precipitation from 1981 through the mid 1990s (National Oceanic and Atmospheric Administration [NOAA] 2002). The annual flood regime varies significantly from year to year due to this natural variability in climate and precipitation.

Human activities affecting flows in the Rio Grande system have been documented back to the arrival of Spanish settlers in the late 16th century (Wozniak 1997). Significant changes in the Rio Grande occurred during the past century in response to a combination of human-induced factors (Figure 24).



Notes: cfs = cubic feet per second; LFCC = Low Flow Conveyance Channel; MRGCD = Middle Rio Grande Conservancy District

Figure 24. Timeline of human activities since 1880 that have affected the Rio Grande (USACE 2007a).

These alterations to the environment equate to significant changes in land use through time and space. Construction of reservoirs, changes to and expansion of historic irrigation conveyance systems, upland drainage networks, and bank stabilization have all served to modify the flow regime of the Rio Grande and associated groundwater recharge dynamics (Hansen and Gorbach 1997; Scurlock 1998; Wozniak 1997). Many of these alterations have resulted in the general tendency for extending runoff hydrographs, reducing peak-flow runoff events, limiting dry-channel vegetative colonization (i.e., new channel formation), and limiting lateral channel migration; resulting in a persistent and additive transition away from a more natural disturbance regime (USACE 2007a). These characteristics now dominate the nature and behavior of the Rio Grande. The eight major dams listed in Figure 24 affect flows in the river by storing and releasing water in a manner that generally decreases the flood peaks

and alters the timing of the annual hydrograph, but they do not necessarily cause significant changes in the annual flow volume.

The hydrologic characteristics of the Middle Rio Grande Reach have been characterized primarily based on flow records collected during the past century (USACE 2002, 2003a, 2007b, 2008a). These records provide a means of quantifying the most significant changes that occurred as a result of upstream flow regulation and storage, imported flows, cycles of drought and above average precipitation, and changes in land use. The following natural and human-caused hydrologic characteristics are particularly important to the existing geomorphology of the reach:

- Flows during the spring snowmelt season in April, May, and June typically make up more than half of the total annual runoff in the system. On an average annual basis, the total runoff volume was higher during the past four decades than it was in the earlier recorded period due to a combination of imported flows and higher than average precipitation during portions of that period (USACE 2007a).
- Flows associated with frequently occurring floods in the 1.5- to 10-year range are generally believed to have the most significant influence on channel form (Wolman and Gerson 1978). The morphologic characteristics of rivers in arid environments such as the Rio Grande are also strongly affected by larger, less frequent floods that create a disturbance regime that effectively “resets the clock” by altering the characteristics that develop during the intervening lower flow periods (Graf 1988). In spite of the increase in total runoff, both the average annual maximum mean daily flow (which is used to represent the mean annual flood peak) and the infrequent, large magnitude peak discharges have decreased in all reaches downstream from Cochiti Dam, presumably due to the presence of upstream dams (USACE 2007a).

The river and adjacent environs respond to cycles of drought and above average precipitation that occur over periods of several years through a variety of mechanisms, including changes in riparian vegetation, channel narrowing during drought periods, and channel widening through bank erosion and migration during wet periods. Generally, these processes vary

widely over both time and space and represent a fundamental organizing force throughout the river system. Over the passage of time, different flow regimes (both high and low) have shaped the riparian plant community by means of deposition and scour; however, widespread and large-scale human alterations in the last century have muted this pattern and disrupted the natural disturbance regime (Crawford et al. 1993; Hansen and Gorbach 1997; Scurlock 1998; Wozniak 1995).

### **Geomorphic Characterization**

River systems are often described as being in a state of dynamic equilibrium. The equilibrium actually results from a series of processes that are predicated on change. Even when large-scale hydrological factors are essentially constant over a short period of time, changes can be happening in subareas as small as the outside bank of a meander or as large as many river miles upstream or downstream from a tributary inflow. Likewise, this state of dynamic equilibrium can withstand climatic deviations from the norm that persist for periods ranging from several decades to one-day flood events (Crawford et al. 1993). Leopold et al. noted that the geomorphic processes triggered in response to a change in the magnitude or duration of a variable, regardless if it was naturally caused or human induced, will be the same (1964). A river system is constantly adjusting, trying to achieve a new equilibrium between its discharge and sediment load (Bullard and Wells 1992).

Historically, the Rio Grande River in this region was a heavily braided, aggrading stream meandering freely across a wide floodplain much larger than the current floodway ecosystem. As it meandered through time and space, the river created and renewed a mosaic of riparian communities from cottonwood riparian gallery forest and coyote willow shrublands, to wet meadows, oxbow ponds, and open water areas (Figure 25).






Figure 25. The Rio Grande River was once a heavily braided stream meandering across the arid area.

As a result of several channelization projects (installation of levees and jetty jacks) the river has become constrained to a single, narrow floodway throughout much of the Middle Rio Grande, resulting in an approximately 85 percent loss of the original floodplain ([Earth Reflections 2003](#)). Figure 26 shows the approximate location of the historic 500-year floodplain in

Albuquerque. The current floodplain is generally confined within the levees, which are also shown on the figure. Historically it was bounded by lower terraces, then by 300 to 500-foot high mesas. The mesas slope gently upward to the foot of the mountain ranges (predominantly to the east) or to plateau highlands (predominately to the west).




Figure 26. The historic 500-year floodplain of the Middle Rio Grande was once much wider than its current channelized state.

Past flood control and drainage projects implemented were widely successful in rejuvenating the declining agricultural communities and providing opportunities for expanding settlements. This occurred, however, at the expense of wetlands and marshes, which were dramatically



reduced in number and extent (Berry and Lewis 1997, Crawford et al. 1996, Leopold 1964, Hanson 1997). Although there are several small areas and former side channels in the area that function as seasonal wetlands, there are no longer any wetlands of significant size in the region.

Changes in seasonal discharges patterns have strongly impacted channel-forming processes. Discharge is the dominant variable that affects channel morphology, but sediment transport, channel bed & bank material and other hydraulic factors are also important influences. Historically, the wide shallow channel was described as a sand-bed stream (Nordin and Beverage 1965) with a braided pattern likely resulting from sediment overload (Woodson 1961). The river followed a pattern of scouring and filling during floods and was in an aggrading regime (accumulating sediment). Flood hazards associated with the aggrading riverbed prompted the building of levees along the floodway. However, the levee systems have confined the sediment and increased the rate of aggradation in the floodway. Additionally, channel stabilization activities which included the installation of jetty jacks during the 1950s and 1960s contributed to building up and stabilizing the over-bank areas in the existing bosque (Figure 27).



Figure 27. Jetty jacks lined along the bank of the Rio Grande trap sediment and plant material during flooding events, stabilized over-bank areas over the course of several years.

Construction of dams at Jemez Canyon (1953), Abiquiu (1963), Galisteo Creek (1970), and Cochiti (1973) were expected to slow aggradation or reverse the trend and promote degradation in the Middle Rio Grande Valley. The flood control improvements have reduced the sediment load in the Middle Rio Grande and accomplished flood control objectives for much of the river valley. This has caused changes in the geomorphology of the Rio Grande through the Albuquerque reach and affected the conveyance capacity of the active river channel. The result of these changes has been a reduction in the frequency of over-bank flows into the Rio Grande Bosque.

Currently within the area, the Rio Grande is predominantly a sand bed river with low, sandy banks. There are numerous sandbars, and the river channel tends to be straight due to jetty jack fields and levee placement (Crawford et al. 1993) (Figure 28).



Figure 28. The middle Rio Grande is often characterized by numerous sandbars and a straight channel resulting from the placement of jetty jack fields and levees.

In this area, the river is typified by a uniform channel width averaging approximately 600 feet. Approximately two feet of degradation has occurred in the Albuquerque reach (due to flood control measures upstream) with no significant change in bed material (Mussetter 2006).



The slope of the riverbed is less than 0.01 feet per foot (Tashjian 1999). At flows less than the bankfull, the river is establishing a sinuous configuration within the cleared floodway.

### Habitat Suitability Index (HSI) Model

The mix of water sources, and the geologic materials through which they move before reaching the riparian zone, combine to determine the elemental composition, nutrient status, and biodiversity of the unique bosque community (Figure 29).




Figure 29. The challenge for the E-Team was to develop a model robust enough to capture the unique character of the Middle Rio Grande's bosque community.

The amount of groundwater inflow relative to precipitation, and geologic materials through which the ground water flows, dictate the biogeochemistry of the bosque community. And finally, the nature and spatio-temporal dynamics of water within the bosques and between the bosque and adjacent ecosystems dictates the functionality and integrity of these unique systems. In particular, the movement of water within the bosque, the flows of water between the bosque and adjacent systems, and the consequent exchange of materials (e.g., sediments, nutrients, propagules) that occur within the bosque and the adjacent systems literally shape these unique ecosystems.

### **Model Components**

For the Bosque Riparian Community HSI Model three model components (i.e., Hydrology; Structure/Soils/Biotic Integrity; and Spatial Integrity/Disturbance) were identified as the key functional indicators necessary to model the integrity of this unique community. The following sections describe the underlying principles governing the selection of these critical functional components and provide a customized flow-diagram to indicate how they were combined to develop a HEP-compatible index model for the ecosystem restoration application.

#### *Functional Component #1: Hydrology (RIP-HYDRO)*

Water operations at the various facilities on the Rio Grande affect the surface and groundwater available to the riparian ecosystem. Periodic overbank flooding is necessary to the health of established native plant communities and literally "...creates the distribution of different communities and age classes" (Scurlock 1998). Regulated flood flows may prevent the overbank floods necessary to scour away existing vegetation and make new seedbeds for cottonwoods and other native trees (Scurlock 1998). Riparian areas that seldom receive overbank flooding show a definite lack of both structural and species diversity. Canopy trees tend to be mature, same-aged stands that are not regenerating. The understory becomes littered with deadfall, a fuel load that inhibits growth of desirable grasses, forbs, and other understory species (Figure 30).




Figure 30. Vegetation response to no overbank flooding (above) versus regular flooding in the riparian zone (below) (USACE 2007a).

Restricted flow regimes changed the nature of riparian areas in the Rio Grande, adversely affecting cottonwood and other native plants. Many areas of the Rio Grande floodplain, both inside and outside the levees, contain relic stands of mature cottonwood and willow that have not flooded for several decades. Riparian vegetation that is not regularly flooded is more vulnerable to encroachment by non-native salt cedar and is extremely vulnerable to fire because of the accumulation of debris that occurs with reduced peak flow events (Ellis et al. 1996). The timing, duration, and magnitude of peak flows are critical to habitat creation and maintenance. Peak flow variability contributes to the diversity of vegetation and wildlife. Seasonally flooded riparian zones exhibit both structural and species diversity in the canopy and understory. Banks are scoured and reshaped, forming depressions that support vital wetland areas and associated species.



Thus, the physical characteristics of natural rivers and their associated bosque riparian communities are strongly controlled by the magnitude, duration and timing of the natural, unconstrained flows that pass through them (Schumm 1977). The natural flows are in turn controlled by the climatic, geologic, and physical characteristics of the contributing watershed (Lee et al. 2004). These natural physical characteristics can be significantly altered by human activities that change infiltration and runoff patterns; that store and release water in ways that alter the natural runoff cycle and change the sediment supply; and that constrain the river to protect adjacent property from flooding and erosion (USACE 2007a). In terms of the bosque's HSI model, indicators of hydrologic function include depth to groundwater, flooding frequency and duration, as well as ratios of wetted area for depressional wetlands. The existing form of the Rio Grande's bosque community results from a combination of these factors (Figure 31).



Figure 31. Hydrology dictates the functionality of the bosque ecosystem.

*Functional Component #2 Structure/Soils/Biotic Integrity (RIP - BIOINTEG)*

Today, the bosque is comprised of a dynamic mosaic of cottonwood forests, coyote willow shrublands, wet meadows, wetlands, oxbow ponds, and open water areas with a variety of depths and flows. These wetlands and riparian forests rely entirely upon periodic flooding events to regenerate soils and create new substrates for vegetative colonization. Unlike many upland areas, the primary natural disturbance regime at work in the Rio Grande ecosystem is flooding. As a patchwork of wetlands, open water, wet meadows and woodlands, these riparian areas provide habitat to a greater number of wildlife species than any other ecological community in the region and serve as a critical travel corridor for many species, especially migratory birds moving with the change of seasons.

Although these riparian ecosystems are considered to be the most productive and biologically diverse ecosystems in the region, they are now believed to be the most threatened ([Johnson and Jones 1977](#), [Johnson et al. 1985](#), [Knopf et al. 1988](#), [Ohmart et al. 1988](#), [Johnson 1991](#), [Minckley and Brown 1994](#)). Substantial impacts from human activities, starting about 250 years ago, have resulted in compounding rates of change in structure and vegetation dynamics to the point that the bosque ecosystem is now on the verge of irreversible conversion ([Crawford et al. 1996](#)) (Figure 32).





Figure 32. Along the banks of the Middle Rio Grande, anthropogenic pressures have resulted in an extremely degraded bosque community subject to catastrophic fires, exotic species encroachment and a loss of vegetative recruitment in the cottonwood riparian community. In 50 years, the bosque could be completely devoid of riparian forest without intervention.

In ecological terms, the cumulative effects of these activities have resulted in a disruption of the original hydrologic (hydraulic) regime. This overbank flooding regime is key to the decomposition of leaf litter and dead wood, which are both fire hazards and obstacles to riparian forest regeneration. With the onset of these periodic flooding events, dissolved salts are flushed from the system, nutrients are cycled into the ecosystem, and soils are renewed. Without flooding, and with the increase demand on water resources in the region, the river banks have destabilized and now “perched” above the river itself (Figure 33).




Figure 33. Flood protection projects (e.g., levees, riverside drains and jetty jacks) have reduced the Rio Grande's original floodplain to fraction of its size in the study area (USACE 2003a).

Structural changes in the riparian vegetation were rapid and easily detected. For example, the valley lost over half its wetlands in just 50 years (Crawford et al. 1993). Similarly, cottonwood germination, which requires scoured sandbars and moisture provided by high river flows (Stromberg et al. 1991, Scott et al. 1993) has decreased, resulting in limited establishment of new trees and a predicted decline in the regional population (Howe and Knopf 1991).

Ultimately these conditions have favored the encroachment of exotic species. Salt cedar (*Tamarix ramosissima*), Siberian elm (*Ulmus pumila*), Russian olive (*Elaeagnus angustifolia* L.), tree-of-heaven (*Ailanthus altissima*), and Bermuda grass (*Cynodon dactylon*) have colonized large portions of the bosque, outcompeting and replacing the native species. These exotics do not rely upon the spring flooding regime to reproduce, consume more water than the natives, compound the fire hazards in the area, and fail to provide critical habitat for many key wildlife species. Without significant restoration and changes in the current water management, these exotics may dominate riparian forests within the next 50 to 100 years (Howe and Knopf 1991).

In terms of the bosque's HSI model, the vegetative species compositions of living plant biomass within the bosque dictate the ecological integrity of the ecosystems and suggest whether the systems can support animal

populations and guilds. The emphasis of the HSI model was therefore placed upon the dynamics of the plant community as revealed by the vegetative diversity (presence of natives and indicator species) and community structure of the habitats (Figure 34).



Figure 34. Vegetative indicators, particularly cover, densities, native species dominance and biodiversity, capture the bosque community's habitat potential.

Healthy bosque ecosystems possess a natural complexity of physical features that provide a greater variety of niches and more intricate interactions among species. Local structural complexity increases with increased canopy cover, tree densities, vegetative layering, and accumulation of organic matter. The vegetation's physical characteristics and structures within the system dictate the habitat suitability of a system to support animal populations and guilds as well. The emphasis of the model is to capture the system's ability to provide physical space for its numerous terrestrial and aquatic inhabitants to meet key life requisite requirements (breeding, feeding and cover) (Figure 35).





Figure 35. Structural complexity offers numerous benefits to resident wildlife in the bosque community.

*Functional Component #3: Spatial Integrity and Disturbance (RIP-SPATIAL)*

At the landscape level, the bosque has a characteristic pattern and connectivity of habitat patches (Figure 36).



Figure 36. The San Antonio Oxbow offers an ideal perspective from above illustrating the classic bosque mosaic of unique patches of forested habitat ribboned throughout with wetland (meadow and marsh) complexes.

The number of and the juxtaposition of these patches supports the movement of species and the transfer of materials (energy and nutrients) among habitats [U.S. Environmental Protection Agency (USEPA) 1999]. The relevance of landscape structure to biodiversity is now well accepted, thanks to the voluminous literature on habitat fragmentation (Noss 1990 and numerous references therein). Landscape features such as patch size, heterogeneity, and connectivity within the riparian zone can be major controllers of species composition and abundance, and of population viability for sensitive species (Noss and Harris 1986). Furthermore, landscape pattern has been shown to strongly influence ecological processes and characteristics (McGarigal and Marks 1995). Turner (1989) describes how spatial structure influences most fundamental ecological processes, and how landscape planning and management, in turn, influences landscape structure.



To adequately characterize the bosque's ecosystem functions, the system's "place" in the landscape must be captured along with the processes that "shape" the system (i.e., key corridors and habitat fragmentation) (Figure 37).



Figure 37. Fragmentation and urban encroachment is a common problem for the bosque ecosystem.

Therefore, landscape-level characteristics (i.e., patch size and nearest neighbors as well as the levels of disturbance immediately adjacent to the system) were thought to dictate whether flora and fauna would find the bosque ecosystem serviceable. In general, high levels of disturbance were thought to perturb sensitive species and reduce the system's ecological integrity.

### **Model Flow Diagram**

A flow diagram best illustrates the final model's design arising from the workshop and application efforts (Figure 38).




Figure 38. Flow diagram depicting combinations of model components and variables to form the Bosque community index model in the MRGBER study. There are two versions of the model depending on the cover types being evaluated. Types I-V use the upper diagram, and Types VI us the lower diagram.

Variables were selected as indicators of functionality, and have been color coded here to correlate their use in specific model components (i.e., purple = hydrologic parameters, orange = soil characteristics, etc.). Again, these model components are combined in a meaningful manner mathematically to characterize the existing reference conditions found in the watershed, and to capture the effects of change under proposed design scenarios (refer to the section below). The rationale for including variables in the model is presented in greater detail in *Chapter 4*.

### **Model Formulas**

With this information in hand, ERDC-EL (with review and oversight from the E-Team) used a systematic, scientifically-based, statistical protocol to calibrate the community index model. Modifications to the original algorithms were incorporated into the system as indicated, and the final formulas were made ready for the MRGBER application (Table 3).

Table 3. Index formulas for the MRGBER Bosque community model.

Model Component	Variable Code	CT Code	Formulas
Hydrology (RIP-HYDRO)	DEPTHGW	ALL	$\frac{(V_{\text{FLOODFREQ}} \times V_{\text{DURATION}})^{1/2} + V_{\text{DEPTHGW}} + V_{\text{WETTEDAREA}}}{3}$
	WETTEDAREA		
	FLOODFREQ		
	DURATION		
Structure, Soils, and Biotic Integrity (RIP-BIOINTEG)	CANTREE	TYPE_1 TYPE_2U TYPE_3 TYPE_4T TYPE_4U TYPE_5	$\frac{\left\{ 3 \times \left[ \left( \frac{(V_{\text{CANTREE}} \times V_{\text{NATIVETREE}} \times V_{\text{DISTBIGTR}})^{1/2} + V_{\text{CANSHRUB}}}{2} \right) \times V_{\text{SPPCOUNT}} \right]^{1/2} \right\} + (V_{\text{CANHERB}} \times V_{\text{INDICATHB}}) + V_{\text{DEPTHOM}} + [(V_{\text{COVGRND}} \times V_{\text{CTGRNDCOV}})^{1/2}]}{6}$
	CANSHRUB		
	CANHERB		
	DISTBIGTR		
	NATIVETREE		
	INDICATHB		
	SPPCOUNT		
	COVGRND		
	CTGRNDCOV		
	DEPTHOM		
	CANSHRUB	TYPE_6T TYPE_6U TYPE_6W	$\frac{(V_{\text{CANSHRUB}} \times V_{\text{SPPCOUNT}}) + (V_{\text{CANGRASS}} \times V_{\text{INDICATGR}}) + (V_{\text{CANFORB}} \times V_{\text{INDICATFB}}) + (V_{\text{CANSEEDGE}} \times V_{\text{NATIVESDG}})}{4}$
	CANGRASS		
	CANFORB		
	CANSEEDGE		
INDICATGR			
INDICATFB			
NATIVESDG			
SPPCOUNT			
Spatial Integrity and Disturbance (RIP-SPATIAL)	PATCHSIZE	ALL	$\frac{[2 \times (V_{\text{PATCHSIZE}} \times V_{\text{DISPATCH}})^{1/2}] + V_{\text{TYPDISTURB}}}{3}$
	TYPDISTURB		
	DISPATCH		
Overall Habitat Suitability Index (HSI):			$\frac{V_{\text{BBIOTA}} + V_{\text{BWATER}} + V_{\text{BLANDSCAPE}}}{3}$

It is important to note that the community-based model developed herein does not subscribe to the “limiting-factor” species-based modeling paradigm of the past, but rather attempts to capture the community’s integrity based on a series of component indicators (i.e., **Hydrology**, **Spatial Integrity/Disturbance**, and **Biotic Integrity**) that together characterize the functioning of the system. This new function-based approach does not rely on a geometric mean, but rather takes into account the compensatory nature of the system’s components. In other words, a degraded bosque might be considered “unsuitable” for a given species, but could potentially have value for others, and therefore would still be considered “functional” (although minimally so). Thus, the hydrologic connection to a bosque could be altered (possibly through channelization or tiling), and would therefore score very low (<0.2) on the Hydrology Component of the model, yet still retain some functionality – it might still provide structure or niches for disturbance-tolerant species. This approach is not new, but is a common strategy for habitat suitability modeling in the scientific literature of late ([Brook and Bowman 2006](#) and references therein, [Schluter et al. 2006](#); [Store and Jokimaki 2003](#); [Store and Kangas 2001](#); [Ruger et al. 2005](#)).

Algorithms were only the first step in the model development process. The second step was to calibrate the individual variables that together characterize the model’s components using a process that normalizes the individual variable inputs to capture ecosystem integrity on a scale of 0 to 1. Refer to [Chapter 4](#) of this document for details surrounding the individual variables described above in these algorithms, and to garner details surrounding the sampling and calibration efforts that led to the finalization of this model for the MRGBER study.





## 4 HSI Model Sampling and Calibration Protocols

This chapter describes the variables employed within the bosque riparian community index model. In an effort to support the future use of the model, we have included detailed sampling protocols, as well as rationale for the incorporation of each variable into the model, and offer scientific literature to support their inclusion therein. In order to use these parameters within a traditional HEP context, each variable must be normalized or scaled on a 0 to 1 range. Here we describe the normalization process in some detail, and have also included *Appendix E* at the end of this report to fully document the final index curves.

### HSI Model Variables Selection Rationale

As mentioned previously, ERDC-EL used a systematic, scientifically-based, statistical protocol to develop and calibrate the community model for the study using an iterative approach that involved the selection of reference sites from across the watershed and a sampling scheme that obtained numbers to assure model precision. Below, the variables associated with the bosque riparian community model (and justifications for their inclusion in the model) have been provided in tabular format (Table 4).

Table 4. Variables and rationales for association in the bosque riparian community index model.

Code	Variable Description	Rationale
CANFORB	Canopy Cover of Forb Species (%)	<p>Three distinct layers can be described in any terrestrial ecosystem (including wetlands): groundcover, understory (i.e., mid-canopy) and overstory (i.e., upper canopy). The presence of each layer offers a niche for community associations. High structural complexity promotes diversity in ecosystems. Species rarely occupy area – they occupy three-dimensional space (Giles 1978). The abundance of vegetative structure greatly influences the abundance and diversity of animals in both wetland and terrestrial ecosystems - complex habitats accommodate more species because they create more ways for species to survive (Norse 1990). Furthermore, studies indicate that physical structure may prevent generalist foragers from fully exploiting resources and thus promoting the coexistence of more species (Werner 1984). In particular, vertical stratification diversification of forests produces stratification of light and temperature, as well as providing intricate spaces for shelter and food sources for species. Thus, structural complexity plays a critical role in the presence of microclimate, food abundance, and cover that affect organism fitness (Cody 1985). The predominance of woody vegetation in riparian ecosystems provides an important habitat value, especially near grasslands, deserts, and farmlands where extensive forests are lacking (Brinson et al. 1981). Riparian forest habitats have considerable vertical structure, foliage height diversity, and foliage density which contribute to wildlife diversity and abundance. By definition, forested wetlands contain tree species in their upper and lower canopies, and tree canopy in particular exceeds 50% coverage in healthy, functioning forested wetlands (Cowardin et al. 1979; Chicago Region Biodiversity Council. 1999; Moulton, Dahl and Dall 1997; Wagner 2004; Jacob, Moulton and López 2004; and Texas Parks and Wildlife Department 2007).</p> <p><b>These variables were designed to capture the multiple layers of a healthy bosque ecosystem capturing not only future successional changes in the community, but offering target thresholds for restoration activities.</b></p>
CANGRASS	Canopy Cover of Grass Species (%)	
CANHERB	Canopy Cover of Herbaceous Vegetation (%)	
CANSEEDGE	Canopy Cover of Sedge Species (%)	
CANSHRUB	Canopy Cover of Shrubs (%)	
CANTREE	Canopy Cover of Overstory Trees (%)	
COVGRND	Ground Cover Present (%)	
CTGRNDCOV	Count of Ground Cover Categories Present	
DISTBIGTR	Distance to Biggest Tree from Sample Point (m)	
DEPTHGW	Depth to Groundwater (ft)	<p>All riparian cottonwoods are dependent on shallow alluvial groundwater that is linked to stream water, particularly in semi-arid regions (Rood et al. 2003). When alluvial groundwater is depleted as a result of river dewatering or groundwater pumping, riparian cottonwoods exhibit drought-stress responses including stomatal closure and reduced transpiration and photosynthesis, altered 13C composition, reduced predawn and midday water potentials, and xylem cavitation. These physiological responses are accompanied by morphological responses including reduced shoot growth, altered root growth, branch sacrifice and crown die-back. As stream flows become more intermittent, diversity and cover of herbaceous species along the low-flow channel also decline (Stromberg et al. 2007). As groundwater deepens, diversity of riparian plant species (particularly perennial species) and landscape patches are reduced and species composition in the floodplain shifts from wetland pioneer trees (<i>Populus, Salix</i>) to more drought-tolerant shrub species including Tamarix (introduced).</p> <p><b>The conservation and restoration of cottonwoods will rely on the provision of river flow regimes that satisfy the ecophysiological requirements for survival, growth and reproduction – this variable was included in the model to capture the critical linkage between the bosque and the riparian zone’s groundwater table.</b></p>

(Continued)

Table 4. (Continued).

Code	Variable Description	Rationale
DEPTHOM	Depth of Organic Matter (cm)	<p>Soil is mainly composed of minerals and organic matter, like decaying plants and animals, as well as living organisms. The minerals are derived from the weathering of "parent material" - bedrock and overlying sub-soil. The organic matter in soil derives from plants and animals. In a forest, for example, leaf litter and woody material falls to the forest floor. This is sometimes referred to as organic material (<a href="http://www.epa.gov/epawaste/conserva/materials/organics/index.htm">http://www.epa.gov/epawaste/conserva/materials/organics/index.htm</a>). When it decays to the point it is no longer recognizable it is called soil organic matter. When the organic matter has broken down into a stable humic substances that resist further decomposition it is called humus. Thus soil organic matter comprises all of the organic matter in the soil exclusive of the undecayed material (<a href="http://soils.usda.gov/sqi/concepts/glossary.html">http://soils.usda.gov/sqi/concepts/glossary.html</a>). Because primary production in riparian zones is extremely complex and variable, organic matter (detritus) processing becomes a key component in maintaining the trophic dynamics of these aquatic ecosystems. In general, primary energy sources for rivers are organic material from riparian vegetation (allochthonous) and organic material generated within the river (Crawford et al 1993 and numerous references therein). Rivers with high sediment load, such as the Rio Grande, generally have a paucity of aquatic vegetation and thus minimal autochthonous input. Autochthonous input from upstream is a critical source of organic carbon for these systems. Allochthonous input in the Middle Rio Grande supports bacteria and algae that assimilate carbon and thus are vital to the food chain. Course organic matter is initially attacked by microbial organisms and converted to organic matter either by natural degradation or shredder macroinvertebrates. Consumer invertebrates, such as detritivores and collectors, use the free organic matter as an energy source and are subsequently consumed by both vertebrate and invertebrate predators.</p> <p><b>This variable was included in the model as an indicator of the level of primary production within the bosque.</b></p>
DISTPATCH	Distance to Nearest Patch (aka Nearest Neighbor of Forest or Meadow) (m)	<p>Too often, ecologists perceive habitats as lone entities, when in reality they are interacting, functional components of the landscape (Noss 1991). Landscape connectivity, therefore, involves the linkage of habitats, species, communities and ecological processes at multiple spatial and temporal scales (Noss 1991). Many of the most significant human effects on biodiversity involve changes in the connectivity of habitat (Noss 1991). Human activities can reduce connectivity by creating artificial barriers to species dispersal, leading to isolated populations that become vulnerable to extinction due to reduced access to resources, genetic deterioration, increased susceptibility to environmental catastrophes and demographic accidents, and other problems (Harris 1984; Soule 1987). Connectivity of the landscape mosaic is absolutely necessary for species to survive (Noss 1991). Disturbances periodically make portions of the landscape uninhabitable. Corridors fulfill a "fire escape" function b permitting animals to flee disturbance. Corridors also aid in recolonization of the recovering site by plants and animals. Habitat patches that are isolated from similar habitat patches by great distances or inhospitable terrain are likely to have fewer species than less isolated patches because relatively few individuals of a given species will immigrate into the isolated patch, and fewer mobile species will visit isolated patches because it is inefficient to do so (Hunter 1996).</p> <p><b>This variable has been included to capture the connectivity of the habitats in the region – indicating species "source" availability.</b></p>

(Continued)

Table 4. (Continued).

Code	Variable Description	Rationale
DURATION	Average Duration of Flooding Events (days)	<p>Riparian vegetation in dry regions is influenced by low-flow and high-flow components of the surface and groundwater flow regimes. The duration of no-flow periods in the surface stream controls vegetation structure along the low-flow channel, while depth, magnitude and rate of groundwater decline influence phreatophytic vegetation in the floodplain (Stromberg et al. 2007 and references therein). Flood flows influence vegetation along channels and floodplains by increasing water availability and by creating ecosystem disturbance. Floods influence riparian biota by creating ecosystem disturbance, driving geomorphic change, and altering availability of resources including water, light and nutrients (Stromberg et al. 2007 and references therein). In arid regions, floods tend to have high magnitude but short duration. The rapidly peaking and receding waters of small floods create minor disturbance and provide a transitory water source. Floods of greater magnitude and longer duration can shape vegetation structure for decades, and mediate water availability both through short-term hydrologic processes (overbank soil wetting, groundwater recharge) and longer-term geomorphic processes (channel incision, floodplain aggradation and degradation, deposition of coarse versus fine sediments) (Stromberg et al. 2007 and references therein). On impounded rivers, changes in flood timing can simplify landscape patch structure and shift species composition from mixed forests composed of Populus and Salix, which have narrow regeneration windows, to the more reproductively opportunistic Tamarix. If flows are not diverted, suppression of flooding can result in increased density of riparian vegetation, leading in some cases to very high abundance of Tamarix patches (Stromberg et al. 2007 and references therein). Cottonwood and willow seedlings are small and particularly vulnerable to drought stress and consequently altered flow regimes often severely suppress seedling recruitment and this provides a predominant factor impacting riparian cottonwood forests (Braatne et al. 2007 and references therein). Since cottonwoods are relatively short-lived trees, typically dying within a century and seldom surviving beyond two centuries ongoing reproduction is essential to provide continuity of riparian cottonwood forests (Braatne et al. 2007 and references therein). The recruitment of cottonwood seedlings is dependent on dynamic fluvial and geomorphic processes (Braatne et al. 2007 and references therein). Seasonal flow patterns including periodic spring flooding produce moist and barren substrates that are required for seedling recruitment (Braatne et al. 2007 and references therein). After germination, the roots of young seedlings must keep pace with the receding soil moisture that is closely coordinated with the declining river stage (Braatne et al. 2007 and references therein). Thus, if river levels decline abruptly, young seedlings succumb to drought stress. Older cottonwoods also benefit from periodic flooding that recharges the alluvial groundwater table (Braatne et al. 2007 and references therein).</p> <p><b>These variables were included in the model to capture and the critical hydrologic pulsing necessary to support riparian bosque recruitment and maintenance.</b></p>
FLOODFREQ	Frequency of Flooding (#/yr)	
WETTEDAREA	Percent of Polygon that is Wet (%)	

(Continued)



Table 4. (Continued).

Code	Variable Description	Rationale
INDICATFB	Percent of Forb Canopy that is an Undesirable Indicator Species (%)	<p>Many of the most dramatic examples of population fluctuations affecting ecological processes involve the invasion of non-native (exotic) species (USEPA 1999). Through direct biotic interactions (predation and competition) and indirect interactions (ecological engineering and habitat modification), invasive species can disrupt the natural population dynamics of native species (USEPA 1999). Invasives can include noxious plants (i.e., plants that are listed by a state because of their unfavorable economic or ecological impacts), non-native, and native plants. Invasive plants may impact an ecosystem’s type and abundance of species, their interrelationships, and the processes by which energy and nutrients move through the ecosystem. These impacts can influence both biological organisms and physical properties of the site (Olson 1999). The affects range from slight to catastrophic responses depending on the species involved and their degree of dominance. Invasive species may adversely affect a site by increased water usage (e.g., salt cedar (tamarisk) in riparian areas) or rapid nutrient depletion (e.g., high nitrogen use by cheatgrass). Some invasive plants (e.g., knapweeds) are capable of invading undisturbed climax bunchgrass communities (Lacey et al. 1990) further emphasizing their use as an indicator of new ecosystem stress. Even highly diverse, species-rich plant communities are susceptible to exotic species invasion (Stohlgren et al. 1999).</p> <p><b>These variables then were included to capture the presence/absence of invasives indicating a level of functionality (when compared to the reference setting) indicative of disturbance and competition both now and in the future.</b></p>
INDICATGR	Percent of Grass Canopy that is an Undesirable Indicator Species (%)	
INDICATHB	Percent of Herbaceous Canopy that is an Undesirable Indicator Species (%)	
NATIVESDG	Percent of Sedge Canopy that is a Desirable Indicator Species (%)	<p>The assessment of ecosystem integrity based on a single index will be insufficient to account for all relevant aspects (Herman, et al. 2001). Species richness (number of species) by itself can also be an insensitive indicator of habitat quality since it is possible for a degraded site to support a similar or greater number of taxa than an intact, high quality site. Six measures of biological integrity for wetlands have been suggested by Keddy et al. 1993. These include species diversity, indicator guilds, exotic species, rare species, plant biomass, and amphibian biomass. Keddy et al. (1993) views diversity as an essential indicator of integrity, but also recommends assessing guild diversity.</p> <p><b>These variable were included to capture the number of “native” species at the site in an attempt to capture several of these key measures, namely species diversity (richness and evenness), presence specifically of “indicators,” and presence of these species tied to a specific community or guild (namely ground vegetation) - the assumption being that higher numbers of native species present signifies ecosystem health and integrity.</b></p>
NATIVETREE	Percent of Tall Overstory Tree Canopy that is a Native Species (%)	
SPPCOUNT	Number of Native Tree and Shrub Species (presence/absence)	

(Continued)

Table 4. (Continued).

Code	Variable Description	Rationale
PATCHSIZE	Size of Patch (ac)	<p>The size of habitat patches has important implications for ecological integrity (USEPA 1999). Fragmentation of habitats has been implicated in the decline of biological diversity and the ability of ecosystems to recover from disturbances (Flather et al. 1992). Large patches have more species because they provide a greater number and variety of niches. Large patches are more likely to have both common and rare species, while small patches are more likely to have only common species (i.e., area-sensitive species will be excluded in smaller patches) (Hunter 1996). Small habitat patches (e.g., habitat islands) have fewer species than large patches, and are more susceptible to extinction. Area-sensitive species that cannot maintain populations in limited areas of otherwise high quality habitat will avoid patches purely on the basis of size (USEPA 1999). Species with small home ranges, such as songbirds, may also avoid small fragments if they prefer the interior of large habitat patches (Robbins, et al. 1989) or select patches large enough to support other members of their species (Stamps 1991). Larger tracts/patches of habitat containing larger populations of targeted species have better functionality and suitability than smaller tracts/patches of habitat with small numbers of species (USEPA 1999). Larger patch fragments have a higher core to edge ratio. The greater the distance between larger and smaller patches, the more inefficient it becomes for mobile species to visit the smaller patches, affecting the number and diversity of species (Hunter 1996).</p> <p><b>This variable was included to characterize both the patch size of the various habitats as well as to capture the future urbanization threat to these ecosystems if preventative measures are not taken in the recommended plans.</b></p>

(Continued)

Table 4. (Continued).

Code	Variable Description	Rationale
TYPDISTURB	Type of Human Disturbance (aka Adjacent Landuse Within 2 km)	<p>Ecosystems do not exist in a steady-state; they are dynamic, each possessing a characteristic composition structure and function that have adapted to natural disturbances over long periods of time. At the landscape level, natural disturbances destroy patches of vegetation and restart plant succession. Human activities (both onsite and offsite) that deviate from these patterns affect individual species (and through biotic interactions many other species and ecological processes) by direct exploitation, habitat elimination, and modification of ecological processes (USEPA 1999). By changing the access of species to their food, shelter, and reproduction, human activities initiate a cascade of biotic interactions that can affect entire ecosystems (USEPA 1999). Impervious surfaces prevent infiltration and direct water away from subsurface pathways to overland flow, increasing the flashiness of streams. Urbanization and suburbanization commonly exceed the threshold of approximately 10 to 20 percent impermeable surface that is known to cause rapid runoff throughout the watershed (Center for Watershed Protection 1994). In heavily urbanized watershed, stream channelization and large amount of impervious surface result in rapid changes in flow, particularly during storm events. These artificially high runoff events increase flood frequency (Beven 1986), cause bank erosion and channel widening (Hammer 1972), and reduce baseflow during dry periods. Agricultural practices also greatly affect hydrologic patterns (USEPA 1999). Clearing forest and prairie environments generally decreases interception of rainfall by natural plant cover and reduces soil infiltration resulting in increased overland flow, channel incision, floodplain isolation, and headward erosion of stream channels (Prestegard 1988). Draining and channelizing wetlands directs flow more quickly downstream, increasing the size and frequency of floods, and reducing baseflow (USEPA 1999). Such activities can actually increase the magnitude of extreme floods by decreasing upstream storage capacity and accelerating water delivery. Human activities, such as land clearing and erosion, can cause the loss of nutrients (e.g., phosphorus), disrupt natural cycling of nutrients, and limit ecosystem productivity (USEPA 1999). At the same time, agriculture and industry can discharge excessive amounts of nutrients (e.g., nitrogen) into natural ecosystems and drastically change their trophic structure, and degrade water quality.</p> <p><b>This variable was added to the model to capture the effects of human activities immediately outside of the habitat area, and can be used as an indication of urban pressures on the remaining relictual ecosystems in the future.</b></p>

(Continued)

Baseline ecosystem characterization for this study included gathering data on water quality, hydrology, substrate conditions, flora, and fauna, and to the greatest extent possible, identifications of underlying stressors in the region. In particular, land-use activities, physical habitat alterations, and native species were identified. In addition to the physical and chemical characteristics of the study area, land ownership and regulatory jurisdictions played an important role in determining opportunities for restoration. Some of this information was geographically-based and was assessed using documented protocols in an ArcGIS environment (see below). The field data was collected from the reference sites between May and July of 2005. The landscape-level data and historical data were subsequently generated over the course of the next several years (2005-2007). These datasets, in turn, were used to characterize the baseline conditions of the study area.

To assure adequate sampling size, the District was asked to locate at least three sites per cover type spanning the range of reference conditions and representing the relative variation found across the system (described earlier in the reference-based section above). Again, an attempt was made to evenly distribute these sites across the entire watershed. To reduce data collection variability, a single three-person sampling team (a recorder and two data collectors) was used to collect all field data. To the greatest extent possible, underlying stressors in the region were described in the notes section of the field data collection sheets. In particular, land-use activities, physical habitat alterations, and indicator species were described in detail.

#### **A Reference-Based Modeling Approach**

To begin, the E-Team developed hypothetical mathematical algorithms to relate the various components to the ecosystem processes occurring throughout the watershed in this community. To test these concepts, a

series of reference sites<sup>1</sup> were used to provide relevant feedback and verification of the model's conceptual architecture.

#### *Background on Reference-based approaches*

The following information was provided to the authors in a workshop hosted by ERDC-EL in the summer of 2008 under the Ecosystem Management and Restoration Research Program's Environmental Benefits Analysis initiative by Drs. Ronald (Dan) Smith and John Nestler. In that workshop, a draft manuscript was circulated to the participants for review and comment. Here we provide excerpts from that paper, and inject local knowledge of the bosque system's reference conditions where relevant.

Reference sites in this instance refer to multiple sites in a defined geographic area (the reference domain) that were selected to represent a specific type of ecosystem (i.e., arid riparian forests and wetlands or bosques). Reference sites are most commonly described as natural settings with minimal human disturbances ([Hughes 1994](#), [Bailey et al. 2004a](#), [Chessman and Royal 2004](#), [Intergovernmental Task Force on Water Quality Monitoring 2005](#)). Reference-based conditions are therefore the range of physical, chemical, and biological values exhibited within the reference sites. When reference sites are characterized as undisturbed ecosystems, reference conditions exhibit a range of values that reflect the spatial and temporal variability that commonly occur in natural ecosystems ([Swanson et al. 1993](#); [Morgan et al. 1994](#); [White and Walker 1997](#); [Landres et al. 1999](#)). When reference sites include altered or disturbed ecosystems (as is the case in most urban-based ecosystem restoration efforts such as the MRGBER), the reference conditions exhibit a wider range of values that reflect both natural variability and variability due to human activities. In these instances, optimal conditions or "virtual" references can be established using a variety of techniques including literature values, historical data, paleoecological data, and expert opinion ([Society for Ecological Restoration International 2004](#); [Ecological](#)

---

<sup>1</sup> Choosing the relevant reference conditions in a region is a matter of judgment ([Andreasen et al. 2001](#)). In some instances, the natural state might be reconstructed from historic records or based on scientific knowledge such as reconstruction of potential vegetation. ERDC-EL assisted the Albuquerque District in locating a series of 27 sample sites across the entire study area that were considered both reference standard (optimal) or degraded (sub-optimal) that represented the range of conditions existing within the reference domain.



[Restoration Institute 2008](#)). Regardless of how reference conditions are established, ecosystem restoration evaluations can use the reference-based approach as a template for model development, restoration planning, and alternative analysis.

Various types of reference-based approaches have been developed for a variety of ecosystems including streams ([Barbour et al. 1999](#), [Karr and Chu 1999](#), [Bailey et al. 2004b](#)), large rivers ([Angradi 2006](#), and [Flotemersch et al. 2006](#)), wetlands ([Smith et al. 1995](#), [Brinson and Rheinhardt 1996](#), [Smith 2001](#), [USEPA 2002](#)), grasslands ([Prober et al. 2002](#)), forests ([Fule et al. 1997](#), [Moore et al. 1999](#), [Tinker et al. 2003](#), [Ecological Restoration Institute 2008](#)), tidal marshes/estuaries ([Findlay et al. 2002](#), [Merkey 2003](#)), and coral reefs ([Jameson 1998](#)). Reference-based approaches have also been used to evaluate ecosystems in a landscape or watershed context ([Warne et al. 2000](#), [Andreasen et al. 2001](#), [Reinhardt et al. 2007](#), [Wardrop et al. 2007](#), [Whigham et al. 2007](#), [Smith 2008](#)).

#### *Reference Site Selection Strategy*

A one-page handout was provided to the Albuquerque District early-on in the planning process to assist in the selection of reference sites for the bosque model. Here we synopsize the directives given to the team:

#### **A. Definitions**

- 1) **Reference** sites serve several purposes in HEP. First, they function as the physical representation of the communities from the region that can be observed and measured repeatedly. Second, they make it possible to establish the range of variability exhibited by the measures of the model variables, which make it possible for calibration of variables and indices. Third, they serve as a template for restoration by providing design specifications.
- 2) **Reference standard** areas are those optimum conditions in the region that are then used to establish the highest standard of comparison for calibrating assessment model variables and indices. In HEP, the least altered areas in the least altered landscapes are selected as *reference standard* wetlands. This is based on the

assumption that these areas sustain the highest level of function across the suite of habitats within the community that are inherent to the system.

## **B. General Selection Strategy**

- 1) ***Conduct field reconnaissance*** to screen potential candidate reference sites. The objective is to identify sites that represent the range of conditions that exist in the reference area from highly altered sites in highly altered landscapes to unaltered (pristine) sites in unaltered landscapes.
- 2) ***Determine the number*** of reference sites to be included. A variety of factors influence the number of reference sites to be included in the process. Large projects will require more reference sites. Reference areas with a wide variety of alteration scenarios will require more sites. Detail of resolution to detect the types of impacts that typically affect riparian areas in the region is another factor. Lastly, the ideal number of sites dictated by the foregoing considerations must be balanced against the realities of budgets, time and personnel.

## **C. Criteria for Defining Reference Conditions**

- 1) Must be politically palatable and reasonable;
- 2) Must include a large number of sites from the region;
- 3) Must represent important aspects of pre-historical conditions;
- 4) May use minimal disturbance as the surrogate for pre-historical conditions, given the difficulty of establishing pre-historical conditions;
- 5) Must be uniform across political boundaries and bureaucracies (e.g., Federal, State, and local); and

- 6) When the areas have experienced extensive alteration, it may be possible to reconstruct a reference standard area using historical accounts and photography.

*Desired Reference Standard Conditions*

Based on the inventory and reconnaissance efforts completed by the District in early 2005, the reference standard conditions for the Middle Rio Grande bosque community can be characterized by the following in the following manner:

**Hydrology** - Channel characteristics (channel pattern, sinuosity, and width) are not altered by human disturbances that cause changes in hydroregime (flood frequency, duration, or magnitude) or sediment transport. The sediment transport, channel morphology, width, and sinuosity patterns are natural. The river channel should exhibit deposition and erosion of soils creating a wide flood plain characteristic of the area. The flood flow should mimic the climatic/natural regime. Vegetation is present to resist flow downstream, and together with topographic relief and subsurface water flow, they promote surface water storage. The flood prone area is undisturbed by humans. Surface hydraulic connections exist between the bankfull channel and the flood prone area. Surface water ponds for more than one day. Side channels are unmodified and connected to the main reach. If the river system has been altered in the past, the system has attained a stable condition for those characteristics and is no longer undergoing degradation. The depth of saturated sediment is near the surface of the wetland. Groundwater and the managed water supply must be appropriate to establish and maintain a diverse cover type.

**Biogeochemical** - A range of vegetation types and sediment combined with suitable topographic relief support detention of particulates. Sufficient water flow through the riparian zone (surface and subsurface) must be evident as well as substrates with enough silt to adsorb elements, promote propagule recruitment, and supply organic materials. In addition, presence of organic matter indicates nutrient cycling occurring within the bosque.

**Vegetation** - There must be an abundance of native trees, shrubs, and herbaceous vegetation. Invasive plant species are absent. Guild representatives (i.e., indicators) must include a wide variety of growth

forms (trees, shrubs, vines, grasses, forbs, algae, and lichens). Plant vertical configuration and foliage profile (canopy cover) must represent a variety of layers. Vegetation provides vertical and horizontal connectivity the length of the system. All age classes of trees (seedlings, saplings, and trees) must be represented. Biotic legacies from preceding bosque forests, propagules from adjacent cottonwood stands, forest structuring processes and the generation of spatial heterogeneous complexes combined to produce both overall compositional diversity and patch diversity (habitat breadth).

**Spatial Configuration** – Spatially-explicit landscape characteristics within the bosque setting associated with patch geometry and distribution are maximized. Landscape simplification is absent – a mosaic or heterogeneous suite of habitat types are present in sufficient in both size and numbers to promote both core area stability and edge diffusion (a blurring of the edge contrast). Habitat connectivity is evident and supports the persistence of both plant and animal populations. Distances between high quality patches are minimized, and a mixture of age classes are present within a reasonable distance of one another to promote niche diversification and offer escape routes during stochastic disturbances. Land adjacent to the project is undeveloped and unperturbed by human disturbances such as agricultural activities.

### **Reference Site Selection**

Once the inventory and reconnaissance was completed, the E-Team used the strategy outlined above to filter and screen the potential sites down to a manageable number. To assure adequate sampling size, the District was asked to locate at least three sites per cover type spanning the range of reference conditions and representing the relative variation found across the system (described earlier in the reference-based section above). Again, an attempt was made to evenly distribute these sites across the entire watershed. To reduce data collection variability, a single three-person sampling team (a recorder and two data collectors) was used to collect all field data. To the greatest extent possible, underlying stressors in the region were described in the notes section of the field data collection sheets. In particular, land-use activities, physical habitat alterations, and indicator species were described in detail. Their goal was to identify, prioritize, and then select sites across the study area that were considered either “high (**H**),” “medium (**M**),” or “low quality (**L**)” based on expert opinion (Table 5).

Table 5. Middle Rio Grande Reference Sites.

Reach	Reference Site	Site No.	Cover Type	Expected Value (E-Team Estimated)
Reach 1	Corrales	28	TYPE_2U	High
	Corrales	29	TYPE_6W	High
	Corrales	30	TYPE_6W	High
	Corrales	33	TYPE_4U	Low
	Alameda	34	TYPE_4U	Medium
	Alameda NE	36	TYPE_6U	Medium
Reach 2	Paseo NE	1	TYPE_1	High
	Paseo NE	2	TYPE_3	High
	Paseo NE	3	TYPE_6T	Low
	Paseo SE	4	TYPE_4T	Medium
	Paseo SE	5	TYPE_3	Medium
	Paseo SW	6	TYPE_2T	Medium
	La Orilla N	7	TYPE_6T	Medium
	La Orilla S	8	TYPE_6T	Medium
Reach 3	Oxbow N	9	TYPE_5	Low
	Oxbow M	10	TYPE_6W	Medium
	Oxbow S	11	TYPE_2U	Medium
	RGNC N	12	TYPE_2U	Medium
	RGNC S	13	TYPE_4T	Medium
	RGNC W	14	TYPE_1	Low
	Montano SW	15	TYPE_2T	Medium
Reach 4	Bridge SW	16	TYPE_4T	Medium
	AOP	17	TYPE_2U	Medium
	Rio Bravo NE	18	TYPE_4U	Medium
	Tingley Bar	35	TYPE_6U	High
Reach 5	Harrison levee	20	TYPE_1	Medium
	Harrison bar	21	TYPE_6U	High
	SDC North levee	22	TYPE_2T	Low
	SDC North river	23	TYPE_5	High
	SDC South	24	TYPE_5	Low
	Price's Dairy	26	TYPE_3	Medium



These initial rankings were based upon the consensus of the “on-the-ground” resource managers that had actual knowledge of each site’s level of disturbance, species composition, land ownership, and the presence or absence of hydrologic alterations. An attempt was made to evenly distribute the site selection across the study area. All told, **31** sites were considered either reference standard (optimal) or sub-optimal and were chosen to represent the range of conditions existing within the reference domain (Figure 39).



Figure 39. Bosque reference sites in the MRGBER study area used to calibrate the Bosque community index model.

### Sampling Protocol – Site Preparations

A standardized approach was developed to collect all field data. Using a somewhat subjective protocol (taking random numbers of footsteps in a random direction into each reference site) a central sample point in the field was established by the team, and a rebar stake was placed there in the ground. This point served as both a permanent plot marker and as the center point for two, perpendicularly aligned 50-m sampling transects which formed a “cross” configuration (Figure 40).




Figure 40. Illustration of the MRGBER baseline sampling design for the Bosque Riparian HSI model components. Up to three 120-m plots (crosses) were established in a single vegetation polygon.

The orientation of the first 50-m tape in the first “cross” was determined randomly by standing over the central point and making an unobserved spin of a compass dial. The next cross was oriented a random distance away (again through the use of random steps and random compass bearings) at a 90° angle to the previous cross. Three crosses were established per polygon (up to 300-m sampling transect length per

polygon) in this manner when polygon size/shape permitted. As each cross was established, a GPS was used to document the coordinates (northing/easting) of the central sample point and entered into a GIS upon returning to the office.<sup>1</sup>

On a technical note, while the sampling distance along each transect was 50-m, each transect was actually extended to 60-m because the 5-m circumference around the center rebar was avoided to restrict measurement overlap (refer to the green square in Figure 41 below), and because this area was trampled to some extent during plot setup.




Figure 41. Details of the "cross" configuration used to sample the vegetative variables in the MRGBER study.

<sup>1</sup> This procedure will allow researchers and managers to return to these points in the future to facilitate monitoring activities.

### **Vegetative Data Collection**

Table 6 below identifies the sampling techniques used to measure the individual HSI variables in the 2005 field effort. For more details regarding these protocols refer to *Appendix F*.



Table 6. Field sampling protocols summarized for the variables associated with the Bosque Riparian community index model.

Code	Variable Description	Sampling Methodology and Data Management	Cover Type Applicability
CANFORB	Canopy Cover of Forb Species (%)	<p>Point-intercept was used to measure the numerous herbaceous canopy cover parameters (percent grass, sedge, forbs, and overall herbaceous canopy cover). To increase efficiency and considering the project goals, the field team only recorded canopy “hits” according to plant life-form (i.e., grass, forb, sedge, or rush). The only exception to this rule will be if the pin made contact with a highly desirable or undesirable plant species (“indicator species”) (refer to INDICATFB, INDICATGR, INDICATHB, and NATIVESDG below).</p> <p>Canopy “hits” per life-form (for Type 6’s) or for herbaceous canopy in general (for Types 1-5) were converted to a value of 100 and “misses” were converted to zeroes. The average of these values was then calculated per cross (100-m sample point) and the three crosses were averaged to generate a mean score per cover type.</p>	<p>TYPE_6T TYPE_6U TYPE_6W</p>
CANGRASS	Canopy Cover of Grass Species (%)	Same as CANFORB above	<p>TYPE_6T TYPE_6U TYPE_6W</p>
CANHERB	Canopy Cover of Herbaceous Vegetation (%)	Same as CANFORB above	<p>TYPE_1 TYPE_2T TYPE_2U TYPE_3 TYPE_4T TYPE_4U TYPE_5</p>
CANSEDGE	Canopy Cover of Sedge Species (%)	Same as CANFORB above	<p>TYPE_6T TYPE_6U TYPE_6W</p>
CANSHRUB	Canopy Cover of Shrubs (%)	<p>Aerial cover of shrubs was recorded using a line-intercept technique. Canopy cover was measured (cm) along the line intercept transect by noting the point along the tape where the canopy began and point at which it ended based on a technique described by <a href="#">Elzinga et al. (1998)</a>. For this study, a minimum continuous distance along the tape for recording a shrub was set at 0.5-meters.</p> <p>After all line-intercept data was recorded for a plot (plot = two 50-m transects), the intercepts for each shrub species were divided by the total line length sampled (100-m) to get the percent shrub cover for each cross. The three crosses were averaged to generate a mean score per cover type.</p>	<p>ALL TYPES</p>
			(Continued)

Table 6. (Continued).

Code	Variable Description	Sampling Methodology and Data Management	Cover Type Applicability
CANTREE	Canopy Cover of Overstory Trees (%)	<p>Aerial cover of trees was recorded at 2-meter intervals along each transect using a vertical densitometer. A vertical densitometer (a.k.a. "moosehorn") provided a point measure of canopy cover using a crosshairs and a bubble level that allowed the observer to determine whether canopy is present directly over a position along the transect. Species identity was noted, and used to generate the NATIVETREE values as well (see below).</p> <p>Canopy "hits" were converted to a value of 100 and "misses" were converted to zeroes. The average of these values was then calculated per cross (100-m sample point) and the three crosses were averaged to generate a mean score per cover type.</p>	<p>TYPE_1 TYPE_2T TYPE_2U TYPE_3 TYPE_4T TYPE_4U TYPE_5</p>
COVGRND	Ground Cover Present (%)	<p>As with aerial herbaceous plant cover (CANHERB above), ground cover was measured at 2-m intervals along each transect using the point-intercept method. Ground cover was reported as one of six general categories:</p> <ol style="list-style-type: none"> <li>1) bare soil,</li> <li>2) litter (leaves or other non-living plant tissue, except for "woody" plant material)</li> <li>3) mulch (shredded woody debris created by mulching tractors),</li> <li>4) live basal vegetation (the pin rests on the basal portion of a live plant),</li> <li>5) downed woody vegetation &lt;3-in. diameter (shrub or tree stem), or</li> <li>6) downed woody vegetation &gt;3-in. diameter (shrub or tree stem/log).</li> </ol> <p>Ground cover "hits" were converted to a value of 100 and "misses" were converted to zeroes. The average of these values was then calculated per cross (100-m sample point) and the three crosses were averaged to generate a mean score per cover type.</p>	<p>TYPE_1 TYPE_2T TYPE_2U TYPE_3 TYPE_4T TYPE_4U TYPE_5</p>
CTGRNDCOV	Count of Ground Cover Categories Present	<p>Refer to COVGRND above, but in this instance, counts of ground cover categories were recorded.</p> <p>The average of these values was then calculated per cross (100-m sample point) and the three crosses were averaged to generate a mean score per cover type.</p>	<p>TYPE_1 TYPE_2T TYPE_2U TYPE_3 TYPE_4T TYPE_4U TYPE_5</p>
DEPTHOM	Depth of Organic Matter (cm)	<p>Depth of organic matter (O-horizon) will be measured to the nearest 0.25 cm recorded at 2-m intervals along each transect.</p> <p>The average of these values was then calculated per cross (100-m sample point) and the three crosses were averaged to generate a mean score per cover type.</p>	<p>ALL TYPES</p>

(Continued)

Table 6. (Continued).

Code	Variable Description	Sampling Methodology and Data Management	Cover Type Applicability
DISTBIGTR	Distance to Biggest Tree from Sample Point (m)	<p>The point-centered quarter method was known to be a frequently used distance methods to sample forest communities (Bonham 1989; Cottam &amp; Curtis 1956; Elzinga et al. 1998; Krebs 1999). After a sampling point along a transect was located (in this case, at the end of each cross arm), the area around those points was split into four 90° quadrants (quarters) and the distance to the nearest tree and root-sprout in each quarter was estimated with an optical rangefinder.</p> <p>The average distance for all four quadrats (cross-terminus') were calculated per cross (100-m sampling point) and the three crosses were averaged to generate a mean score per cover type.</p>	TYPE_1 TYPE_2T TYPE_2U TYPE_3 TYPE_4T TYPE_4U TYPE_5
INDICATFB	Percent of Forb Canopy that is an Undesirable Indicator Species (%)	<p>The point-intercept approach was used to measure these more particular herbaceous canopy cover parameters, but the sampling team was required to record species identity when undesirable indicators or desirable species were encountered. For a list of undesirable and desirable (native) species per life-form, refer to <i>Appendix F</i>.</p> <p>Canopy "hits" per life-form (for Type 6's) or for herbaceous canopy in general (for Types 1-5) were converted to a value of 100 and "misses" were converted to zeroes. The average of these values was then calculated per cross (100-m sample point) and the three crosses were averaged to generate a mean score per cover type.</p>	TYPE_6T TYPE_6U TYPE_6W
INDICATGR	Percent of Grass Canopy that is an Undesirable Indicator Species (%)	Same as INDICATFB above	TYPE_6T TYPE_6U TYPE_6W
INDICATHB	Percent of Herbaceous Canopy that is an Undesirable Indicator Species (%)	Same as INDICATFB above	TYPE_1 TYPE_2T TYPE_2U TYPE_3 TYPE_4T TYPE_4U TYPE_5
NATIVESDG	Percent of Sedge Canopy that is a Desirable Indicator Species (%)	Same as INDICATFB above	TYPE_6T TYPE_6U TYPE_6W

(Continued)

Table 6. (Concluded).

Code	Variable Description	Sampling Methodology and Data Management	Cover Type Applicability
NATIVETREE	Percent of Tall Overstory Tree Canopy that is a Native Species (%)	The percent of the “hits” recorded as desirable (native) species under the aerial canopy protocol for trees above (CANTREE) was used to generate an average for each of the 100-m sample points (i.e., crosses), and the three crosses were averaged to generate a mean score per cover type.	TYPE_1 TYPE_2T TYPE_2U TYPE_3 TYPE_4T TYPE_4U TYPE_5
SPPCOUNT	Number of Native Tree and Shrub Species (presence/absence)	Same as NATIVETREE	ALL TYPES

### Spatially Explicit Data Collection

Landscape variables were determined based on a combination of onsite reconnaissance, interpretation of maps and aerial photos, and analysis of GIS data layers using ArcGIS 9.2. The GIS information (e.g., vegetative cover, access points along the river, bike trails, kiosks, etc.) was collected by ERDC-EL from various sources including the District itself, Bernalillo County, New Mexico Resource Geographic Information System (<http://rgis.unm.edu/>) and the U.S. Census Bureau (<http://www.census.gov/>) between 2005 and 2008 (JUNE 2008). A personal geodatabase was developed to organize and house the data for quick retrieval.

June, 2005 QuickBird aerial imagery in NAD83, U.S. Survey Feet, New Mexico State Plane Central was used to complete the baseline cover type mapping exercises. The Albuquerque District was responsible for the development of *Hink and Ohmart* classification vegetation mapping (with ground-truthing) from this imagery in 2006. These maps were then digitized and converted into shapefiles with attributes including H&O Codes (C/CW,MH5 , etc.) and acreage. Any questions surrounding this information should be addressed to the Albuquerque District's Ondrea Hummel (refer to *Appendix D* for point of contact information). ERDC-EL developed expression files to crosswalk the H&O codes to the HSI cover type classifications associated with the model (TYPE\_1, TYPE\_2T, etc.) (*Appendix F*). Gaps and overlaps were cleaned, and cover type acreages were generated and exported to spreadsheets at the reach level for the entire study area for use in the HSI model.

The spatially-explicit landscape metrics in the Bosque Riparian HSI model is directly dependent on the cover type mapping results. ERDC-EL developed a series of protocols to calculate these parameters and incorporated their resultant shapefiles into the study's geodatabase (Table 7).<sup>1</sup>

---

<sup>1</sup> Contact Ondrea Hummel in the USACE Albuquerque District Office to obtain copies of the geodatabase.

Table 7. GIS sampling protocols summarized for the variables associated with the Bosque Riparian community index model.

Code	Variable Description	Sampling Methodology	Cover Type Applicability
DISTPATCH	Distance to Nearest Patch (aka Nearest Neighbor of Forest or Meadow) (m)	<p>To calculate the distance between like patches (NEIGHBOR), a tool developed by Jeff Lin at ERDC-EL was employed (<a href="http://el.erd.c.usace.army.mil/emrrp/gis.html">http://el.erd.c.usace.army.mil/emrrp/gis.html</a>).</p> <p>Step 1: Build Base files using the Individual Cover Type (dissolved) <i>PATCHSIZE</i> files developed earlier - merge these to make 1 Cover Type file containing all the like polygons across the 5 reaches. . . these will be used to calculate nearest neighbor for the baseline condition in Step 4 below.</p> <p>Step 2: Create 10 template files (1 per Cover Type) for each reach, by systematically clipping out each reach from the Base files (i.e., Template for Reach 1's Type_1 has all Type_1 polygons for Reach 2-5, but lacks Reach 1's).</p> <p>Step 3: For each alternative, merge the WP Type files from the Dissolved <i>PATCHSIZE</i> files with the Template files (10 files per alternative - 1 for each TYPE will all Reach polygons included).</p> <p>Step 4: Run the NearestNeighbor.py script to on each file.</p> <p>Step 5: Export the data from this analysis into Excel using Xtools Pro (or from the table view).</p> <p>Step 6: Clip out non-applicable reaches (i.e., for Plan 1-A, only use the nearest neighbor calculations for Reach 1 polygons).</p> <p>Step 7: Convert the nearest neighbor values from feet to meters, and average the values across the Reach for each Cover Type.</p> <p>To characterize/quantify changes in WOP and WP conditions based on successional trends, a "factor" was applied to the <i>PATCHSIZE</i> variables over the course of the remaining TYs to show change over time.</p> <p>The variable was calculated at the Landscape scale (i.e., Type 1 and New Type 1 cover types were combined as a single class for this exercise).</p>	ALL TYPES
			(Continued)



Table 7. (Continued).

Code	Variable Description	Sampling Methodology	Cover Type Applicability
PATCHSIZE	Size of Patch (ac)	<p>Step 1: Select by attribute the target cover type and export it as separate shape file for that cover type.</p> <p>Step 2: Using the Dissolve tool, edit the file, and select all target features (this must be done at the Reach level - i.e., dissolve on Reach ID).</p> <p>Step 3: Explode these (using the explode multipart feature tool) to ensure that multiple, separate polygons aren't being misrepresented by what appears as a single feature in the attribute table which is in reality a merged multipart feature.</p> <p>Step 4: Recalculate the acres after this step (using Xtools pro or the VBA code for calculating area while in editor).</p> <p>Step 5: Export the data as a database file from the attribute table view or into Excel using Xtools Pro.</p> <p>Step 6: Patch size for bosque cover types were calculated by reach by dividing the total area of these cover types by the number of patches (polygons) within each reach.</p> <p>To characterize/quantify changes in WOP and WP conditions based on successional trends, a "factor" was applied to the <i>PATCHSIZE</i> variables over the course of the remaining TYs to show change over time.</p> <p>The variable was calculated at the Landscape scale (i.e., Type 1 and New Type 1 covertypes were combined as a single class for this exercise). All polygons smaller than 0.05 acres were merged with the nearest polygon using ArcGIS's "Eliminate" tool.</p>	ALL TYPES
			<i>(Continued)</i>

Table 7. (Concluded).

Code	Variable Description	Sampling Methodology	Cover Type Applicability
TYPDISTURB	Type of Human Disturbance (aka Adjacent Landuse Within 2 km)	<p>Step 1: Open the individual Reach shapefiles and use the ArcGIS Buffer Wizard to draw <b>2-km</b> buffers around each Reach</p> <p>Step 2: Merge these buffer files, and clip the Land Use/Land Cover (LULC) file (to reduce processing)</p> <p>Step 3: Reclassified the Clipped LULC file based on the 5 Disturbance Types (1 Commercial/Industrial, 2 Residential, 3 Right of Ways and Railroads, 4 Agricultural Crops and Pastures, 5 Pristine, uninhabited areas)</p> <p>Step 4: Add 2 fields, 1 for the HEP Code and the HEP Description of these Disturbance types</p> <p>Step 5: X-walk the LULC descriptions and the HEP descriptions/codes (either in *.xls or using expression files and attribute selection)</p> <p>Step 6: Eliminate any "unknown" polygons, and recalculate the area of the shapefile (using XTools)</p> <p>Step 7: Open the 10-1-7 Reach Map, select the area under the reach, use the calculator to reclassify all these areas as "natural" category 5</p> <p>Step 8: Erase file from Step 6 with file from Step 7</p> <p>Step 9: Merge file from Step 8 with file from Step 7, Add a field called "Reach"</p> <p>Step 10: Clip the Step 9 file with the individual reach buffer files in Step 1, and fill in the Reach number with the Calculator</p> <p>Step 11: Recalculate the area and export to excel (using XTools)</p> <p>Step 12: Sum the acres by category and determine the category with the most acres (proportionately)</p> <p>To characterize/quantify changes in WOP and WP conditions, assumed that residential/commercial would remain, and that 10% of the agricultural croplands would be lost to development each target year.</p> <p>The variable was calculated at the Landscape scale at the Reach level (i.e., all types in the reach are assigned the same value).</p>	ALL TYPES

### **Hydrologic Data**

The hydrological information presented in (Table 8) below was generated by the Steve Boberg and Ondrea Hummel in the Albuquerque District and provided to ERDC-EL in response to a request for assessment methodology and documentation. Any questions surrounding this information should be addressed to her (refer to *Appendix D* for point of contact information).

Table 8. Hydrologic data sampling protocols summarized for the variables associated with the Bosque Riparian community index model.

Code	Variable Description	Sampling Methodology	Cover Type Applicability
DEPTHGW	Depth To Groundwater (ft)	Depth to groundwater was taken at each reference site if a well was within that patch. If a well was not within that patch, the nearest known well was used. Data was obtained for the date closest to the field sampling date from wells being monitored by the Corps, U.S. Forest Service, and BEMP (Bosque Ecosystem Monitoring Program).	ALL TYPES
DURATION	Average Duration Of Flooding Events (days)	<p>Flood duration defines the amount of time that a specific flood frequency will meet or exceed a given discharge or flow rate. Flood duration is typically defined in either hours or days. For this study the flood duration is defined as the number of days a specific flood frequency exceeds 3,000 cfs. The flood durations for the three flood frequencies considered for this study are as follows:</p> <p>Discharge Flood Frequency # days &gt; 3,000 cfs 21 day duration flow**</p> <p>3,770 cfs 70% 30 days 3500, cfs                      6,500 cfs 31% 51 days 5460 cfs                      10,000 cfs 4% 65 days 8230 cfs</p>	ALL TYPES
FLOODFREQ	Frequency Of Flooding (#/yr)	<p>Flood Frequency relates the magnitude of discharge to the probability of occurrence or exceedance. Discharge or flow rate is typically given in cubic feet per second (cfs). Probability is given as the likelihood of a particular event occurring in a given year. Therefore, the event commonly called "the 100 year storm" is given a flood frequency of 0.01 or 1% since that is the likelihood that it will occur in any given year. The flood frequencies being considered for this study are as follows:</p> <p>Discharge Flood Frequency Return Period Comment</p> <p>3,770 cfs 70% 1.42 years Average Annual Hydrograph                      6,500 cfs 31% 3.25 years Bank Full Hydrograph                      10,000 cfs 4% 23.6 years Future Target Release</p>	ALL TYPES
WETTEDAREA	Percent Of Polygon That Is Wet (%)	<p>The wetted area is defined as that area in the Bosque located between the active channel bank-line and the levee that is inundated during flooding events. This area is known as the over-bank and is the area where the inventoried sites are located. For any given reach of the Rio Grande there are two over-bank areas, the left over-bank (LOB) and the right over-bank (ROB) defined from looking downstream. For this project the LOB is on east side of the Rio Grande and the ROB is on the west side of the Rio Grande. The wetted area is that area of the over-bank that would be flooded from "over-banking" of active channel flows in the Rio Grande during a given Flood Frequency. The Wetted Area for the individual inventoried sites will be given in percent of area within the site that is inundated or wetted. The wetted areas were determined primarily by the use of the FLO-2D hydraulic model and verified by the HEC-RAS hydraulic model. In some areas of the Corrales reach the HEC-RAS hydraulic model only was used since this area was outside of the FLO-2D analysis limits.</p>	ALL TYPES

## HSI Statistical Analysis and Curve Calibrations

The reference condition described earlier defined the measurement scale and the state toward which the E-Team desired to move the system. In the case of the MRGBER project, the reference-based approach employed “reference standard ecosystems” to establish optimal conditions (HSI = 1.0) that served as benchmarks or standards of comparison for the existing and future conditions. Locating “degraded” reference sites was essential to calibrating the model. These “degraded” reference conditions represented the other end of the measurement scale and represented the ecological systems that were clearly degraded and socially unacceptable (HSI = 0.0). We refer to this process as “calibration,” which we define here loosely as the use of known (reference) data on the observed relationship between a dependent variable and an independent variable to make estimates of other values of the independent variable from new observations of the dependent variable.

To calibrate the models, we used the average values across the watershed and their associated standard deviations to generate a curve for each variable in each model. We calculated these statistics on both a “cover type-by-cover type” basis, as well as at the broader reach and watershed scales. To develop curves for each variable, ERDC used a straightforward assignment process. The watershed mean was assigned a **0.75** SI value in every case. The standard deviation of the mean was added to the average, and this total was assigned a **1.0** SI on the curve (Figure 42).




Figure 42. Example of curve calibration method using the reference mean and its standard deviation.

In most instances, the E-Team made the decision to calibrate the curve on the basis of cover type distinctions. For example, the E-Team reviewed the individual cover type means and made the decision that TYPE 1 and TYPE 3 cover types have significantly lower levels of herbaceous canopy cover than rest of the watershed's cover types. As a result, they chose to create two curves - one for each unique setting (Figure 43).






Figure 43. The model calibration approach was flexible enough to encourage and incorporate professional expertise into the methodology. Here, the reference data support the separation of cover types based on mean data. Type 1 and 3 classes have significantly higher tree canopy cover, shading out the herbaceous layers closer to the ground. As a result, the HSI model was calibrated to capture this unique feature.

Ultimately, the curves developed for the watershed were the result of an iterative process where the E-Team directed ERDC-EL to gradually modify the curves to better reflect reality as they perceived it “in-the-field.” ERDC-EL made a conscious effort to fully document these changes, and curves that have been altered from the means and standard deviations as a result of “expert judgment” are presented as “red” curves in the graphs and supporting text (Figure 44).




Figure 44. Example of curve calibration method using a combination of watershed means, standard deviations and expert opinion.

To review the final curves for the Bosque Riparian HSI model, refer to *Appendix E*.

## Model Results

Because the community-based index model for Middle Rio Grande bosque was developed to operate on a larger, watershed scale, it was important to test their veracity of the tool at the reach level<sup>1</sup> (Figure 45).

<sup>1</sup> Testing here refers to model verification or “the act of reviewing, inspecting, testing, etc. to establish and document that a product, service, or system meets the regulatory, standard, or specification requirements.”




Figure 45. Reaches delineated for the baseline HSI assessment of the MRGBER study

To do this, the individual reference site field data collected between 2005 and 2008 was compiled on a reach-by-reach basis. Data for each variable

per cover type within the community were recorded and the variable means/modes were calculated to generate watershed baseline HSIs at the reach level.<sup>1</sup> Twenty three variables were measured according to the sampling protocols described above at the reference sites for the bosque community. The means for each variable are summarized in Table 9 below.

---

<sup>1</sup> GIS shapefiles and associated datasets are available upon request - contact the District POC (Ondrea Hummel, contact information can be found in [Appendix D](#)).

Table 9. Baseline data for the five reaches used to verify the bosque riparian HSI model.

Reach	Cover Type	BASALAREA	CANFORB	CANGRASS	CANHERB	CANSEDGE	CANSHRUB	CANTREE	COVGRND	CTGRNDCOV	DEPTHGW	DEPTHOM	DISTBIGTR	DISTPATCH	DURATION	FLOODFREQ	INDICATFB	INDICATGR	INDICATHB	NATIVESDG	NATIVETREE	PATCHSIZE	SPPCOUNT	TYPDISTURB	TYPEPATCH	WETTEDAREA
1	1	45			15		10	90	95	1	6.0	4.5	6.5	190	0	0			15		80	20.5	5	6	2	0
	2T	20			25		0	90	95	1	3.5	3.5	8.5	15	0	0			40		95	18.0	7	2	2	0
	2U	20			50		0	90	100	1	6.0	2.5	5.0	0	0	0			20		70	24.5	5	7	2	0
	3	45			20		10	65	100	1	5.5	7.0	11.0	555	0	0			15		35	11.5	3	4	2	0
	4T	20			40		0	65	80	1	7.0	2.0	14.0	75	0	0			10		90	17.0	7	6	2	0
	4U	25			15		10	35	65	1	7.5	1.5	8.5	770	0	0			0		60	5.0	3	6	2	0
	5	35			30		15	30	90	1	4.5	2.5	14.0	25	0	0			40		15	3.5	5	6	2	0
	6T		15	20		0	5				5.0			150	0	0	20	35		0		10.0	5	5	2	0
	6U		0	10		0	30				6.0			105	0	0	0	0		0		8.0	5	4	2	0
	6W		25	15		20	50				6.5			315	20	1	0	0		60		5.0	4	8	2	100
2	1	65			0		35	85	80	1	8.0	3.5	7.5	535	0	0			0		100	6.0	3	4	2	0
	2T	30			55		0	100	95	1	3.5	3.5	8.0	50	0	0			45		95	19.0	12	2	2	0
	2U	35			20		0	90	95	1	4.5	3.5	6.5	115	0	0			5		65	18.0	4	6	2	0
	3	65			10		5	80	95	1	8.5	3.5	8.5	345	0	0			30		40	5.0	3	4	2	0
	4T	20			35		0	50	60	1	9.0	2.0	16.5	60	0	0			5		95	16.0	7	5	2	0
	4U	30			20		5	35	70	1	6.0	1.5	9.0	545	0	0			0		60	10.0	3	6	2	0
	5	35			30		15	30	90	1	4.5	2.5	14.0	25	0	0			40		15	3.5	5	6	2	0
	6T		15	20		0	5				5.0			150	0	0	20	35		0		10.0	5	5	2	0
	6U		5	15		5	45				4.5			135	0	0	0	0		60		5.5	5	5	2	0
	6W		20	10		20	35				6.0			210	15	0	0	0		40		11.5	3	8	2	65

Note: Blank cells indicate the variable was not associated with the particular cover type and therefore were not sampled therein.

(Continued)

Table 9. (Continued).

Reach	Cover Type	BASALAREA	CANFORB	CANGRASS	CANHERB	CANSEDGE	CANSHRUB	CANTREE	COVGRND	CTGRNDCOV	DEPTHGW	DEPTHOM	DISTBIGTR	DISTPATCH	DURATION	FLOODFREQ	INDICATFB	INDICATGR	INDICATHB	NATIVESDG	NATIVETREE	PATCHSIZE	SPPCOUNT	TYPDISTURB	TYPEPATCH	WETTEDAREA
3	1	35			30		0	95	100	1	5.5	3.5	6.0	0	0	0			0		45	30.5	5	8	2	0
	2T	10			0		0	90	100	1	2.0	5.0	8.5	0	0	0			0		85	23.5	5	1	2	0
	2U	35			15		0	85	90	1	3.5	3.5	6.0	235	0	0			0		50	15.0	4	6	2	0
	3	50			10		10	65	100	1	5.5	7.0	11.0	555	0	0			15		35	11.5	3	4	2	0
	4T	15			65		0	75	90	1	5.5	2.0	11.0	165	0	0			10		100	16.5	5	8	2	0
	4U	30			20		5	35	70	1	6.0	1.5	9.0	545	0	0			0		60	10.0	3	6	2	0
	5	25			30		10	10	100	1	2.5	5.0	16.5	0	0	0			65		0	3.0	8	6	2	0
	6T		15	20		0	5				5.0			150	0	0	20	35		0		10.0	5	5	2	0
	6U		5	15		5	45				4.5			135	0	0	0	0		60		5.5	5	5	2	0
	6W		15	5		25	5				5.0			0	0	0	0	0		0		23.5	2	7	2	0
4	1	45			15		10	90	95	1	6.0	4.5	6.5	190	0	0			15		80	20.5	5	6	2	0
	2T	20			25		0	90	95	1	3.5	3.5	8.5	15	0	0			40		95	18.0	7	2	2	0
	2U	50			0		0	100	100	1	4.0	4.0	8.0	0	0	0			0		90	19.5	5	4	2	0
	3	45			10		10	65	100	1	5.5	7.0	11.0	555	0	0			15		35	11.5	3	4	2	0
	4T	25			25		0	65	90	1	7.0	2.0	14.5	0	0	0			15		80	18.5	8	4	2	0
	4U	45			30		0	40	85	1	6.0	1.5	9.0	545	0	0			5		70	18.5	3	7	2	0
	5	35			30		15	30	90	1	4.5	2.5	14.0	25	0	0			40		15	3.5	5	6	2	0
	6T		15	20		0	5				5.0			150	0	0	20	35		0		10.0	5	5	2	0
	6U		15	35		10	70				6.0			105	0	0	0	5		85		4.0	4	4	2	0
	6W		20	10		20	35				6.0			210	15	0	0	0		40		11.5	3	8	2	65

Note: Blank cells indicate the variable was not associated with the particular cover type and therefore were not sampled therein.

(Continued)



Table 9. (Concluded).

Reach	Cover Type	BASALAREA	CANFORB	CANGRASS	CANHERB	CANSEEDGE	CANSHRUB	CANTREE	COVERND	CTGRND	DEPTHGW	DEPTHOM	DISTBIGTR	DISTPATCH	DURATION	FLOODFREQ	INDICATFB	INDICATGR	INDICATHB	NATIVESDG	NATIVEETREE	PATCHSIZE	SPPCOUNT	TYPDISTURB	TYPEPATCH	WETTEDAREA	
5	1	40			10		0	95	100	1	5.0	6.5	5.5	35	0	0			50		90	25.5	8	7	2	0	
	2T	15			20		0	80	95	1	5.5	2.5	9.5	0	0	0			80		100	11.5	3	4	2	0	
	2U	35			20		0	90	95	1	4.5	3.5	6.5	115	0	0			5		65	18.0	4	6	2	0	
	3	30			0		0	100	100	1	5.5	14.5	7.5	1530	0	0			0		60	30.5	3	7	2	0	
	4T	20			40		0	65	80	1	7.0	2.0	14.0	75	0	0			10		90	17.0	7	6	2	0	
	4U	30			20		5	35	70	1	6.0	1.5	9.0	545	0	0			0		60	10.0	3	6	2	0	
	5	40			30		20	45	90	1	5.5	1.5	13.0	40	0	0			25		25	5.0	4	6	2	0	
	6T			15	20		0	5				5.0			150	0	0	20	35		0		10.0	5	5	2	0
	6U			0	0		0	35				1.5			190	0	0	0	0		100		4.5	5	8	2	0
6W			20	10		20	35				6.0			210	15	0	0	0		40		11.5	3	8	2	65	

Note: Blank cells indicate the variable was not associated with the particular cover type and therefore were not sampled therein.

The results of the baseline HEP assessment for the reaches are summarized below. HSIs capture the quality of the acreage within the reach. Units (i.e., HUs) take this quality and apply it to the governing area through multiplication (Quality X Quantity = Units). Both HSIs and HUs are reported for each reach. Interpretations of these findings can be generalized in the following manner (Table 10).

Table 10. Interpretation of HSI scores resulting from HEP assessments.

HSI Score	Interpretation
0.0	Not-suitable - the community does not perform to a measurable level and will not recover through natural processes
Above 0.0 to 0.19	Extremely low or very poor functionality (i.e., habitat suitability) - the community functionality can be measured, but it cannot be recovered through natural processes
0.2 to 0.29	Low or poor functionality
0.3 to 0.39	Fair to moderately low functionality
0.4 to 0.49	Moderate functionality
0.5 to 0.59	Moderately high functionality
0.6 to .79	High or good functionality
0.8 to 0.99	Very high or excellent functionality
1.0	Optimum functionality - the community performs functions at the highest level - the same level as reference standard settings

In most instances, the individual component indices (aka Life Requisite Suitability Indices or LRSIs) and composite HSIs scored in the mid-range of values (<0.5) indicating only a moderate level of functionality in the study area (Table 11 and Figure 46).<sup>1</sup> The highest functioning reach was Reach 1 (HSI = 0.50). This was to be expected – the last vestiges of undisturbed bosque are found in this area. Not surprisingly, Reaches 2 and 3 generated the lowest HSI scores (HSIs ranged from 0.40 to 0.41). Located in the heart of Albuquerque, these areas are highly urbanized and experience extreme levels of disturbance and invasive encroachment. These areas were also targeted for moderate to heavy fire prevention, and as such, their understoreys had incurred significant impacts.

<sup>1</sup> Data are available upon request - contact the District POC (Ondrea Hummel, contact information can be found in [Appendix D](#)).

Table 11. Baseline tabular results for the bosque riparian community.

Reach Name	LRSI Code	LRSI Score	Habitat Suitability Index (HSI)	Applicable Acres	Baseline Habitat Units (HUs)
Reach 1	RIP-BIOINTEG	0.41	0.50	1090	541
	RIP-SPATIAL	0.76			
	RIP-HYDRO	0.32			
Reach 2	RIP-BIOINTEG	0.39	0.40	561	225
	RIP-SPATIAL	0.54			
	RIP-HYDRO	0.28			
Reach 3	RIP-BIOINTEG	0.38	0.41	502	206
	RIP-SPATIAL	0.59			
	RIP-HYDRO	0.26			
Reach 4	RIP-BIOINTEG	0.41	0.42	726	307
	RIP-SPATIAL	0.53			
	RIP-HYDRO	0.33			
Reach 5	RIP-BIOINTEG	0.37	0.48	616	296
	RIP-SPATIAL	0.75			
	RIP-HYDRO	0.33			

If we compare the proposed restoration initiatives to a “virtual” reference conditions (HSI = 1.0), we find that the reaches are functioning at approximately 40 to 50 percent of the maximum potential. Clearly, there are opportunities for improvements – in other words, all the reaches are prime candidates for restoration/rehabilitation activities in terms of the bosque community’s structure and functionality.




Figure 46. Baseline graphical results for the bosque community.

## Model Verification

The first test of the model was to assess the various references sites (both optimal and sub-optimal) with the formulas and curves and determine whether the model “relating to reality” with respect to the E-Team’s expectations. We consider this step to be model verification:

***Verification** (aka Confirmation) is the comparison of the model output to data from well-known, published test cases to confirm that the algorithms and computer code accurately represent system dynamics.<sup>1</sup>*

For purposes of this effort, *verification* asks whether the model is responding as they experts believe it should. Sites deemed to be highly functional wetlands according to experts, should produce high HSI scores. Sites deemed dysfunctional (by the experts) should produce low HSI scores. Again, the model calibration effort described above was an iterative process, and as such, changes to the model’s curves and algorithms were made in an attempt to bring these results as close to the expected outcome as possible. Admittedly, this process was somewhat subjective. But the experts working on the process were the best in the region, and where possible, actual reference conditions and/or historical data sets and literature-based studies were used to refine the model throughout the process. Below, we provide both the E-Team’s expectation of reference site condition (i.e., **High**, **Medium**, or **Low**), and provide the results of the final iteration of model calibration (Table 12 and Table 13).

---

<sup>1</sup> Personal communication regarding American Society of Civil Engineers’ definitions with Dr. John Nestler, ERDC-EL, August 2009

Table 12. Baseline results for the Bosque Riparian HSI assessment of the reference sites.

Reach	Reference Site	Site No.	Cover Type	Model Components			Habitat Suitability Index (HSI)
				RIP-BIOINTEG	RIP-SPATIAL	RIP-HYDRO	
Reach 1	Corrales	28	TYPE_2U	0.32	0.00	0.00	0.11
	Corrales	29	TYPE_6W	0.64	0.68	0.91	0.74
	Corrales	30	TYPE_6W	0.48	0.00	0.75	0.41
	Corrales	33	TYPE_4U	0.34	0.30	0.00	0.21
	Alameda	34	TYPE_4U	0.41	0.29	0.00	0.23
	Alameda NE	36	TYPE_6U	0.24	0.21	0.00	0.15
Reach 2	Paseo NE	1	TYPE_1	0.48	0.23	0.00	0.24
	Paseo NE	2	TYPE_3	0.41	0.23	0.00	0.21
	Paseo NE	3	TYPE_6T	0.19	0.12	0.00	0.10
	Paseo SE	4	TYPE_4T	0.29	0.31	0.00	0.20
	Paseo SE	5	TYPE_3	0.23	0.28	0.00	0.17
	Paseo SW	6	TYPE_2T	0.34	0.19	0.00	0.18
	La Orilla N	7	TYPE_6T	0.34	0.45	0.00	0.26
	La Orilla S	8	TYPE_6T	0.19	0.00	0.00	0.06
Reach 3	Oxbow N	9	TYPE_5	0.43	0.00	0.00	0.14
	Oxbow M	10	TYPE_6W	0.21	0.00	0.00	0.07
	Oxbow S	11	TYPE_2U	0.26	0.16	0.00	0.14
	RGNC N	12	TYPE_2U	0.41	0.00	0.00	0.14
	RGNC S	13	TYPE_4T	0.47	0.75	0.00	0.40
	RGNC W	14	TYPE_1	0.36	0.00	0.00	0.12
	Montano SW	15	TYPE_2T	0.31	0.00	0.00	0.10
Reach 4	Bridge SW	16	TYPE_4T	0.44	0.00	0.00	0.15
	AOP	17	TYPE_2U	0.32	0.00	0.00	0.11
	Rio Bravo NE	18	TYPE_4U	0.45	0.52	0.00	0.32
	Tingley Bar	35	TYPE_6U	0.66	0.15	0.00	0.27
Reach 5	Harrison levee	20	TYPE_1	0.37	0.00	0.00	0.12
	Harrison bar	21	TYPE_6U	0.18	0.47	0.00	0.22
	SDC North levee	22	TYPE_2T	0.23	0.00	0.00	0.08
	SDC North river	23	TYPE_5	0.45	0.00	0.00	0.15
	SDC South	24	TYPE_5	0.35	0.25	0.00	0.20
	Price's Dairy	26	TYPE_3	0.36	0.71	0.00	0.36



Table 13. Comparison of the baseline reference results to the E-Team's expectation of reference conditions.

Reach	Reference Site	Site No.	Cover Type	Model Components			Habitat Suitability Index (HSI)	Expected Value (E-Team Estimated)
				RIP-BIOINTEG	RIP-SPATIAL	RIP-HYDRO		
Reach 1	Corrales	28	TYPE_2U	Low	Low	Low	Low	High
	Corrales	29	TYPE_6W	High	High	High	High	High
	Corrales	30	TYPE_6W	Medium	Low	High	Medium	High
	Corrales	33	TYPE_4U	Medium	Medium	Low	Low	Low
	Alameda	34	TYPE_4U	Medium	Medium	Low	Low	Medium
	Alameda NE	36	TYPE_6U	Low	Medium	Low	Low	Medium
Reach 2	Paseo NE	1	TYPE_1	Medium	Medium	Low	Low	High
	Paseo NE	2	TYPE_3	Medium	Medium	Low	Low	High
	Paseo NE	3	TYPE_6T	Low	Medium	Low	Low	Low
	Paseo SE	4	TYPE_4T	Low	Medium	Low	Low	Medium
	Paseo SE	5	TYPE_3	Low	Medium	Low	Low	Medium
	Paseo SW	6	TYPE_2T	Medium	Medium	Low	Low	Medium
	La Orilla N	7	TYPE_6T	Medium	Medium	Low	Low	Medium
La Orilla S	8	TYPE_6T	Low	Low	Low	Low	Medium	
Reach 3	Oxbow N	9	TYPE_5	Medium	Low	Low	Low	Low
	Oxbow M	10	TYPE_6W	Low	Low	Low	Low	Medium
	Oxbow S	11	TYPE_2U	Low	Medium	Low	Low	Medium
	RGNC N	12	TYPE_2U	Medium	Low	Low	Low	Medium
	RGNC S	13	TYPE_4T	Medium	High	Low	Medium	Medium
	RGNC W	14	TYPE_1	Medium	Low	Low	Low	Low
	Montano SW	15	TYPE_2T	Low	Low	Low	Low	Medium
Reach 4	Bridge SW	16	TYPE_4T	Medium	Low	Low	Low	Medium
	AOP	17	TYPE_2U	Low	Low	Low	Low	Medium
	Rio Bravo NE	18	TYPE_4U	Medium	Medium	Low	Low	Medium
	Tingley Bar	35	TYPE_6U	High	Medium	Low	Low	High
Reach 5	Harrison levee	20	TYPE_1	Medium	Low	Low	Low	Medium
	Harrison bar	21	TYPE_6U	Low	Medium	Low	Low	High
	SDC North levee	22	TYPE_2T	Low	Low	Low	Low	Low
	SDC North river	23	TYPE_5	Medium	Low	Low	Low	High
	SDC South	24	TYPE_5	Medium	Medium	Low	Low	Low
	Price's Dairy	26	TYPE_3	Medium	High	Low	Low	Medium

As a simple test of the veracity of the models and the expert's opinions of the reference site conditions was performed using a correlation analysis. (Figure 47).




Figure 47. A Pearson's correlation of expert team's opinion of site functionality and the HEP results indicate that they are positively related to some degree.

The most common measure of correlation is the Pearson Product Moment Correlation (aka Pearson's correlation).<sup>1</sup> The Pearson correlation values range from +1 to -1. A rule-of-thumb interpretation of the Pearson's correlation is found in the corner of Figure 47 above. Based on this analysis, we can demonstrate that the model is moderately correlated to expert opinion regarding site conditions, and therefore can be said to pass the test of "verification" (Pearson correlation value = 0.31). Because the area is suffering from severe alterations of the natural hydrologic regime, there are no sites within the reference domain functioning at the expected optimal levels, the E-Team felt it was still reasonable to assume that the

<sup>1</sup> Background information was retrieved from [http://en.wikipedia.org/wiki/Pearson\\_product\\_moment\\_correlation\\_coefficient](http://en.wikipedia.org/wiki/Pearson_product_moment_correlation_coefficient) and <http://davidmlane.com/hyperstat/A34739.html> (SEPTEMBER 2008).

model offered a solid, scientifically driven means to characterizing conditions and assessing alternative plans. So for now, the E-Team has agreed that the reference sites were functioning at a reasonable level of expectation and as such the model calibrations were deemed acceptable.

## Model Validation

To date the Bosque (Riparian) community index model has not been validated. We define model validation here as:

***Validation** is accomplished by establishing an objective yet independent line of evidence that the model specifications conform to the user's needs and intended use(s). The validation process questions whether the model is an accurate representation of the system based on independent data not used to develop the model in the first place. Validation can encompass all of the information that can be verified, as well as all of the things that cannot -- i.e., all of the information that the model designers might never have anticipated the user might want or expect the product to do.<sup>1</sup>*

For purposes of this effort, *validation* refers to independent data collections (bird surveys, water quality surveys, etc.) that can be compared to the model outcomes to determine whether the model is capturing the essence of the ecosystem's functionality. As independent measures of function for the model herein, we propose three options or directions to consider as future research opportunities:

1. A few "relevant" HSI Blue Book (species) models could be used to assess the baseline conditions of the area comparing their outputs to the community models' outputs. As these are already "approved" for use under the USACE model certification program, their outputs should provide relevant cross-validation. However, as most of the HSI Blue Books lack validation, this approach may not be appropriate either. And again, as the

---

<sup>1</sup> Personal communication regarding American Society of Civil Engineers' definitions with Dr. John Nestler, ERDC-EL, August 2009

Blue Book models are designed to measure only limiting “life requisites” of these key species, they might not be inclusive enough to capture community function and processes.

2. An extremely expensive and time consuming approach could be undertaken to assess biodiversity (both species richness and diversity) in an attempt to identify an “independent measure of function.” However, to validate the communities modeled herein, a majority of the faunal groups present would need to be surveyed (mammals, birds, fish, reptiles, amphibians, plants, and possibly even insects). This in turn leads to the question, if we had time and funds to do this level of inventory, why use models at all?
3. Alternatively, validation of the models could potentially be accomplished by assessing patch dynamics using transition model at a landscape scale (Acevedo et al. 1995). Again, this would be validating models with models which might not be considered a true validation exercise.



## **5 Summary and Conclusions**

The implications of this report's findings are rather straightforward. First, the results support the conceptual premise surrounding the HSI model and indicate its representative capabilities. In other words, scientific literature characterizing the state of the bosque ecosystems along the middle Rio Grande point to an overall decline in ecosystem integrity (i.e., health, biodiversity, stability, sustainability, naturalness, wildness, and beauty) – a finding the model can now verify and quantify (we found less than optimal HSI scores in all reaches). Furthermore, the results indicate an opportunity to redress ongoing losses. There is great potential to restore sustainable bosque communities therein, offering a significant positive return on investment to both the stakeholders and the federal government.





## References

- Acevedo, M.F., D. L. Urban, and M. Abla. 1995. Transition and gap models of forest dynamics. *Ecol. Appl.* 5 (4), 1040–1055.
- Ahmadi-Nedushan, B., A. St-Hilaire, M. Bérubé, E. Robichaud, N. Thiémonge, and B. Bobée. 2006. A review of statistical methods for the evaluation of aquatic habitat suitability for instream flow assessment. *River Research and Applications* 22:503-523.
- Alvarez-Rogel, J. A., J. J. Martinez-Sanchez, L. C. Blazquez, and C. M. M. Semitiel. 2006. A conceptual model of salt marsh plant distribution in coastal dunes of southeastern Spain. *Wetlands* 26:703-717.
- American Bird Conservancy. 2008. Top 10 Most Threatened Bird Habitats in the U.S. website: <http://www.abcbirds.org/newsandreports/habitatreport.pdf> (MAY 2008).
- Andreasen, J. K., R. V. O'Neill, R. Noss, and N. C. Slosser. 2001. Considerations for the development of a terrestrial index of ecological integrity. *Ecological Indicators* 1:21-35.
- Andreasen, J. K., R. Noss, and N. C. Slosser. 2003. Development of a Terrestrial Index of Ecological Integrity (TIEI), A new tool for ecosystem management. In *Managing for Healthy Ecosystems*. Edited by D. J. Rapport et al., pp. 267-276. Lewis Publishers, Boca Raton, Florida.
- Angradi, T. R. (editor). 2006. *Environmental Monitoring and Assessment Program: Great River Ecosystems, Field Operations Manual*. EPA/620/R-06/002. USEPA, Washington, D.C. <http://www.epa.gov/emap/greatriver/fom.html> (SEPTEMBER 2008).
- Bailey, R. C., R. H. Norris, and T. B. Reynoldson. 2004a. *Bioassessment of Freshwater Ecosystems Using the Reference Condition Approach*. 2<sup>nd</sup> Edition. Springer Science and Business Media, Inc., New York, New York.
- Bailey, R. C., R. H. Norris, and T. B. Reynoldson. 2004b. Bioassessment of freshwater ecosystems using the reference condition approach: Comparing predicted and actual benthic invertebrate communities in Yukon streams. *Freshwater Biology* 39:765-774.
- Barbour, M. T., J. Gerritsen, B. D. Snyder, and J. B. Stribling. 1999. Multimetric approach for establishing biocriteria and measuring biological condition. In *Biological Assessment and Criteria: Tools for Water Resource Planning and Decision Making*. Edited by Davis, W. S., and T. P. Simon, pp. 63-77. CRC Press, Boca Raton, Florida.
- Bedford, B. L. 1996. The need to define hydrologic equivalence at the landscape scale for freshwater wetland mitigation. *Ecological Applications* 6(1):57-68.

- Berry, K. L. and K. Lewis. 1997. Historical Documentation of Middle Rio Grande Flood Protection Projects: Corrales to San Marcial. U.S. Army Corps of Engineers Contract No. DACW47-94-D-0019. Albuquerque, New Mexico.
- Beven, K. J. 1986. Hillslope runoff processes and flood frequency characteristics. In *Hillslope processes*. Edited by A. D. Abrahams, pp. 187-202. Allen and Unwin, Boston, Massachusetts.
- Bonham, C.D. 1989. *Measurements for Terrestrial Vegetation*. John Wiley & Sons.
- Braatne, J. h., R. Jamieson, K. M. Gill, and S. B. Rood. 2007. Instream flows and the decline of riparian cottonwoods along the Yakima River, Washington, USA. *River Research and Applications* 23:247-267.
- Brinson, M.M., B.L. Swift, R.C. Plantico, and J.S. Barclay. 1981. Riparian ecosystems: Their ecology and status. USDI Fish and Wildlife Service, FWS/OBS-81/17.
- Brinson, M. M. and R. Rheinhardt. 1996. The role of reference wetlands in functional assessment and mitigation. *Ecological Applications* 6:69-76.
- Brook, B. W., and D. Bowman. 2006. Postcards from the past: charting the landscape-scale conversion of tropical Australian savanna to closed forest during the 20th century. *Landscape Ecology* 21:1253-1266.
- Bullard, T. F. and S.G. Wells. 1992. Hydrology of the Rio Grande from Velarde to Elephant Butte Reservoir, New Mexico. U.S. Fish and Wildlife Service, Resource Publication 179.
- Burks-Copes, K. A., and A. C. Webb. 2009. Middle Rio Grande Bosque Ecosystem Restoration Feasibility Study Habitat Assessment Using Habitat Evaluation Procedures (HEP): Analyses, Results And Documentation, Draft Report. U. S. Army Engineer Research and Development Center, Environmental Laboratory, Vicksburg, MS.
- Burks-Copes, K. A., A. C. Webb, M. F. Passmore, and S.D. McGee-Rosser. 2008. HEAT - Habitat Evaluation and Assessment Tools for Effective Environmental Evaluations. User's Guide. Final Report. U. S. Army Engineer Research and Development Center, Environmental Laboratory, Vicksburg, MS.
- Center for Watershed Protection. 1994. The importance of imperviousness. *Watershed Protection Techniques* 1:100-111.
- Chambers, J. C. and R. W. Brown. 1983. Methods for vegetation sampling and analysis on revegetated mined lands. Intermountain Forest and Range Experiment Station General Technical Report INT-151. Ogden, UT.
- Chessman, B. C., and M. J. Royal. 2004. Bioassessment without reference sites: Use of environmental filters to predict natural assemblages of river macroinvertebrates. *Journal of the North American Benthological Society* 23:599-615.
- Chicago Region Biodiversity Council. 1999. *Biodiversity Recovery Plan*. Chicago Region Biodiversity Council, Chicago, Illinois, 195 pp.

- Cody, M. L. 1985. An introduction to habitat selection in birds. In *Habitat Selection in Birds*. Edited by Cody, M. L. Academic Press, Orlando, Florida.
- Cottam, G. and J. T. Curtis. 1956. The use of distance measures in phytosociological sampling. *Ecology* 37(3):451-460.
- Cowardin, L. M., V. Carter, F. C. Golet, and E. T. LaRoe. 1979. Classification of wetlands and deepwater habitats of the United States. FWS/OBS-79/31., U.S. Fish and Wildlife Service, US Department of the Interior, Washington, DC, 103 pp.
- Crawford, C. S., A. C. Cully, R. Leutheuser, M. S. Sifuentes, L. H. White, and J. P. Wilber. 1993. Middle Rio Grande Ecosystem: Bosque Biological Management Plan. Bosque Biological Interagency Team, U.S. Fish and Wildlife Service, Albuquerque, New Mexico.
- Crawford, C. S., L. M. Ellis, and M. C. Molles, Jr. 1996. The Middle Rio Grande bosque: An endangered ecosystem. *New Mexico Journal of Science* 36: 276-299.
- Dahl, T. E. 1990. Wetland Losses in the United States 1780's to 1980's. U.S. Department of the Interior Fish and Wildlife Service, Washington, D.C., U.S.A.
- Davis, S. M., E. E. Gaiser, W. F. Loftus, and A. E. Huffman. 2005. Southern marl prairies conceptual ecological model. *Wetlands* 25:821-831.
- de Groot, R.S., Wilson, M.A., Boumans, R.M.J., 2002. A typology for the classification, description and valuation of ecosystem functions, goods and services. *Ecological Economics* 41, 393–408.
- Earth Reflections. 2003. Feasibility Study: San Acacia Diversion Dam to Bosque del Apache NWR North Boundary Socorro County, New Mexico. Prepared for Save Our Bosque Task Force. Revised by Save Our Bosque Task Force April 10, 2003.
- Ecological Restoration Institute. 2008. Establishing Reference Conditions. Northern Arizona University. Flagstaff, Arizona website: <http://www.eri.nau.edu/joomla/content/view/225/148/lang/en/> (SEPTEMBER 2008).
- Ellis, L. M., M. C. Molles, Jr., and C. S. Crawford. *Seasonal Flooding and Riparian Forest Restoration in the Middle Rio Grande Valley. Final Report: Cooperative Agreement 14-16-0003-91-339*. U. S. Fish and Wildlife Service, Ecological Services, Albuquerque, New Mexico. ([http://www.spa.usace.army.mil/urgwops/eis\\_admin\\_record/Ref453.PDF](http://www.spa.usace.army.mil/urgwops/eis_admin_record/Ref453.PDF)). (SEPTEMBER 2008).
- Elzinga, C. L., D. W. Salzer, and J. W. Willoughby. 1998. Measuring and monitoring plant populations. U.S. Department of the Interior, Bureau of Land Management, Technical Reference 1730–1, Denver, Colorado.
- Findlay, S., E. G. Findlay, E. Kiviat, W. C. Nieder, and E. A. Blair. 2002. Functional assessment of a reference wetland set as a tool for science, management and restoration. *Aquatic Science* 64:107-117.

- Flather, C. H., S. J. Brady, and D. B. Inkley. 1992. Regional habitat appraisals of wildlife communities: A landscape-level evaluation of a resource planning model using avian distribution data, *Landscape Ecology* 7:137-147.
- Flotemersch, J. E., J. B. Stribling, and M. J. Paul. 2006. Concepts and Approaches for the Bioassessment of Non-wadeable Streams and Rivers. EPA 600-R-06-127. USEPA, Washington, D. C. (<http://www.epa.gov/eerd/rivers/index.html>) (SEPTEMBER 2008).
- Floyd, D. A. and J. E. Anderson. 1987. A comparison of three methods for estimating plant cover. *Journal of Ecology* 75:221-228.
- Fule, P. S., W. Wallace-Covington, and M. M. Moore. 1997. Determining reference conditions for ecosystem management of southwestern ponderosa pine forests. *Ecological Applications* 7:895-908.
- Giles, R. H., Jr. 1978. *Wildlife Management*. W. H. Freeman and Company, San Francisco, California.
- Gillenwater, D., T. Granata, and U. Zika. 2006. GIS-based modeling of spawning habitat suitability for walleye in the Sandusky River, Ohio, and implications for dam removal and river restoration. *Ecological Engineering* 28:311-323.
- Guisan, A., and N. E. Zimmerman. 2000. Predictive habitat distribution models in ecology. *Ecological Modelling* 135:147-186.
- Graf, W. L. 1988. *Fluvial Processes in Dryland Rivers*. The Blackburn Press, Caldwell, New Jersey.
- Hammer, T. R. 1972. Stream channel enlargement due to urbanization. *Water Resources Research* 8:1530-1540.
- Hansen, S. and C. Gorbach. 1997. *Middle Rio Grande Assessment Final Report*. U. S. Department of the Interior, Albuquerque Office, Albuquerque, New Mexico.
- Hanson, B. 1997. Supplemental Fish and Wildlife Coordination Act Report: Rio Grande and Tributaries Flood Control San Acacia to Bosque del Apache Unit, Socorro County New Mexico.
- Harris, L. D. 1984. *The Fragmented Forest*. University of Chicago Press, Chicago, Illinois.
- Harwell, M. A., V. Myers, T. Younb, A. Bartuska, N. Gassman, J. H. Gentile, C. C. Harwell, S. Appelbaum, J. Barko, B. Causey, C. Johnson, A. McLean, R. Smola, P. Templet, and S. Tosini. 1999. A framework for an ecosystem integrity report card. *BioScience* 49:543-556.
- Henderson, J. E., and L. J. O'Neil. 2004. Conceptual models to support environmental planning operations. ERDC/TN SMART-04-9, U.S. Army Engineer Research and Development Center, Vicksburg, Mississippi. 31 pp.

- Herman, K. D., L. A. Masters, M. R. Penskar, A. A. Reznicek, G. S. Willhem, W. W. Brodovich, and K. P. Gardiner. 2001. *Floristic Quality Assessment with Wetland Categories and Examples of Computer Applications for the State of Michigan*. Revised, 2nd Edition. Michigan Department of Natural Resources, Wildlife, Natural Heritage Program, Lansing, Michigan, 19pp + appendices.
- Hink, V. C., and R. D. Ohmart. 1984. Middle Rio Grande Biological Survey. U.S. Army Corps of Engineers, Albuquerque District, New Mexico. Contract No. DACW47-81-C-0015, Arizona State University. 193 pp.
- Howe, W. H. and F. L. Knopf. 1991. On the imminent decline of Rio Grande cottonwoods in central New Mexico. *The Southwestern Naturalist* 36: 218-224.
- Hughes, R. M. 1994. Defining acceptable biological status by comparing with reference conditions. In *Biological Assessment and Criteria: Tools for Water Resource Planning and Decision Making*. Edited by Davis, W. S., and T. P. Simon, pp. 31-47. CRC Press, Boca Raton, Florida.
- Hunter, M. L., Jr. 1996. *Fundamentals of Conservation Biology*. Blackwell Science, Cambridge, Massachusetts.
- Inglis, G. J., H. Hurren, J. Oldman, and R. Haskew. 2006. Using habitat suitability index and particle dispersion models for early detection of marine invaders. *Ecological Applications* 16:1377-1390.
- Intergovernmental Task Force on Monitoring Water Quality. 2005. Final report of the Intergovernmental Task Force on Monitoring Water Quality. Appendix F: Ecoregions, Reference Conditions, and Index Calibration. U.S. Geological Survey (USGS) Open-File Report 95-742 (<http://www.epa.gov/bioiweb1/html/publications.html>) (SEPTEMBER 2008).
- Jacob, J. S. D. W. Moulton and R. A. López. 2003. Texas Coastal Wetlands Guidebook website (<http://www.texaswetlands.org/>) (APR 2008).
- Jameson, S. C., M. V. Erdmann, G. R. Gibson, Jr., and K. W. Potts. 1998. Development of biological criteria for coral reef ecosystem assessment. U. S. Environmental Protection Agency, Office of Science and Technology, Health and ecological Criteria Division, Washington, D. C. (<http://www.epa.gov/OWOW/oceans/coral/documents/biocrit.pdf>) (SEPTEMBER 2008).
- Johnson, R. R. 1991. Historic changes in vegetation along the Colorado River in the Grand Canyon. In *Colorado River Ecology and Dam Management*. National Research Council, pp. 178-206. National Academy Press, Washington.
- Johnson, R. R. and D. A. Jones (editors). 1977. Importance, Preservation and Management of Riparian Habitat: A Symposium. USDA Forest Service General Technical Report RM-43.
- Johnson, R. R., C. D. Ziebell, D. R. Patton, P. F. Ffolliott, and R. H. Hamre. 1985. Riparian ecosystems and their management: reconciling conflicting uses. *Proceedings of the First North American Riparian Conference*. U.S. Forest Service General Technical Report RM-120, Washington, DC.



- Karr, J. R., and E. W. Chu. 1999. *Restoring Life in Running Waters*. Island Press, Washington, D. C.
- Keddy, P. A., H. T. Lee, and I. C. Wisheu. 1993. Choosing indicators of ecosystem integrity: Wetlands as a model system. In *Ecological Integrity and Management of Ecosystems*. Edited by Woodley, S., J. Kay, and G. Francis, pp. 61-82. St. Lucie Press, Boca Raton, Florida.
- King, D. M., L. A. Wainger, C. C. Bartoldus, and J. S. Wakeley. 2000. Expanding Wetland Assessment Procedures: Linking Indices of Wetland Function with Services and Values. ERDC/EL TR-00-17. U.S. Army Engineer Research and Development Center, Vicksburg, MS.
- Knopf, F. L., R. R. Johnson, T. Rich, F. B. Samson and R. C. Szaro. 1988. Conservation of riparian ecosystems in the United States. *Wilson Bulletin* 100:272-284.
- Krebs, C. J. 1999. *Ecological Methodology*, Second Edition. Addison-Welsey Education Publishers, Inc., Menlo Park, CA.
- Lacey J., P. Husby, and G. Handl. 1990. Observations on spotted and diffuse knapweed invasion into ungrazed bunchgrass communities in western Montana. *Rangelands* 12:30-32.
- Landres, P. B., P. Morgan, and F. J. Swanson. 1999. Overview of the use of natural variability concepts in managing ecological systems. *Ecological Applications* 9:1179-1188.
- Lee, S., A. Klein, and T. Over. 2004. Effects of the El Niño-southern oscillation on temperature, precipitation, snow water equivalent and resulting streamflow in the Upper Rio Grande River Basin. *Hydrologic Processes* 18(6):1053-1071.
- Leopold, L.B., M.G. Wolman, and J.P. Miller. 1964. *Fluvial Processes in Geomorphology*. W.H. Freeman and Co., San Francisco.
- McGarigal, K. and B. J. Marks. 1995. FRAGSTATS: Spatial pattern analysis program for quantifying landscape structure. Forest Science Department, Oregon State University, Corvallis, Oregon.
- Merkey, D. 2003. Selection of reference conditions. In *Science-based Restoration Monitoring of Coastal Habitats*, Volumes 1 and 2: *A Framework for Monitoring Plans Under the Estuaries and Clean Waters Acts of 2000* (Public Law 160-457). Edited by Thayer, G. W., T. A. McTigue, R. J. Bellmer, F. M. Burrows, D. H. Merkey, A. D. Nickens, S. J. Lozano, P. F. Gayaldo, P. J. Polmateer, and P. T. Pinit, Chapter 3. Decision Analysis Series, No. 23. NOAA Coastal Ocean Program. ([http://coastalscience.noaa.gov/ecosystems/estuaries/restoration\\_monitoring.html](http://coastalscience.noaa.gov/ecosystems/estuaries/restoration_monitoring.html)) (SEPTEMBER 2008).
- Millennium Ecosystem Assessment. 2005. *Ecosystems and Human Well-being: Synthesis*. Island Press, Washington, DC. <http://www.millenniumassessment.org/documents/document.358.aspx.pdf> (MAY 2008).

- Minckley, W. L and D. E. Brown. 1994. Wetlands. In *Biotic Communities: Southwestern United States and Northwestern Mexico*. Edited by Brown, D. E., pp. 223-287. University of Utah Press, Salt Lake City.
- Moore, M. M., W. Wallace-Covington, and P. Z. Fule. 1999. Reference conditions and ecological restoration: A southwestern ponderosa pine perspective. *Ecological Applications* 9:1266-1277.
- Morgan, P., G. H. Aplet, J. B. Hafler, H. C. Humphries, M. M. Moore, and W. D. Wilson. 1994. Historical range of variability: A useful tool for evaluating ecological change. *Journal of Sustainable Forestry* 2:87-111.
- Moulton, D. W., T. E. Dahl, and D. M. Dall. 1997. Texas coastal wetlands: Status and trends, mid-1950s to early 1990s. <http://library.fws.gov/Wetlands/TexasWetlands.pdf> (APR 2008).
- Mussetter Engineering, Inc. 2006. FLO-2D Model Development, Albuquerque Reach, Rio Grande, NM. Submitted to U.S. Army Corps of Engineers Albuquerque District, MEI Project 05-03.
- National Oceanic and Atmospheric Administration (NOAA). 2002. *Climatological Data Annual Summary, New Mexico, 2002*. Volume 106, No. 13.
- Nordin, C. F. Jr. and J.P. Beverage. 1965. Sediment transport in the Rio Grande, New Mexico. USGS Professional Paper 462-F.
- Norse, E. A. 1990. *Ancient Forests of the Pacific Northwest*. Island Press, Washington, DC.
- Noss, R. F. 1990. Indicators for monitoring biodiversity: A hierarchical approach. *Conservation Biology* 4(4):355-364.
- Noss, R. F. 1991. Landscape connectivity: Different functions at different scales. In *Landscape Linkages and Biodiversity*. Edited by W. E. Hudson, pp. 27-39. Defenders of Wildlife, Island Press, Washington, DC.
- Noss, R. F., and L. D. Harris. 1986. Nodes, networks, and MUMs: Preserving diversity at all scales. *Environmental Management* 10:299-309.
- Noss, R. F., E. T. LaRoe III, and J. M. Scott. 1995. Endangered Ecosystems of The United States: A Preliminary Assessment of Loss and Degradation. Biological Report 28, National Biological Survey, Washington, D.C.
- Ogden, J. C., S. M. Davis, T. K. Barnes, K. J. Jacobs, and J. H. Gentile. 2005. Total system conceptual ecological model. *Wetlands* 25:955-979.
- Ohmart, R. D., B. W. Anderson, and W. C. Hunter. 1988. The Ecology of the Lower Colorado River from Davis Dam to the Mexico-United States International Border: A Community Profile. USDI Fish and Wildlife Service. Biological Report 85(7.19).

- Olson, B. E. 1999. Impacts of noxious weeds on ecological and economic systems. In *Biology and Management of Noxious Rangeland Weeds*. Edited by Sheley, R. L. and J. K. Petroff, pp. 4-18. Oregon State University Press, Corvallis, Oregon.
- Prestegard, K. L. 1988. Morphological controls on sediment delivery pathways. In *Sediment Budgets*. International Association of Hydrological Sciences Publication No. 174. Edited by Walling, D. E. pp. 533-540. IAHS Press, Wallingford, Connecticut.
- Prober, S. M., I. D. Lunt, and K. R. Thiele. 2002. Determining reference conditions for management and restoration of temperate grassy woodlands: Relationships among trees, topsoils and understorey flora in little-grazed remnants. *Australian Journal of Botany* 50:687-697.
- Reinhardt, R. D., M. M. Brinson, R. R. Christian, K. H. Miller, and G. F. Meyer. 2007. A reference-based framework for evaluating the ecological condition of stream networks in small watersheds. *Wetlands* 27:524-542.
- Robbins, C. S., D. K. Dawson, and B. A. Dowell. 1989. Habitat area requirements of breeding forest birds of Middle Atlantic states. *Wildlife Monographs* 103:1-34.
- Robinson, R. R., W. Hansen, and K. Orth. in collaboration with S. Franco. 1995. Evaluation of environmental investments procedures manual: cost effectiveness and incremental cost analyses, IWR Report 95-R-1. USACE Evaluation of Environmental Investments Research Program, Instate for Water Resources, Alexandria, Virginia, and Waterways Experiment Station, Vicksburg, MS.
- Rood, S. B., J. H. Braatne, and F. M. R. Hughes. 2003. Ecophysiology of riparian cottonwoods: Stream flow dependency, water relations and restoration. *Tree Physiology* 23:1113-1124.
- Ruger, N., M. Schluter, and M. Matthies. 2005. A fuzzy habitat suitability index for *Populus euphratica* in the Northern Amudarya delta (Uzbekistan). *Ecological Modelling* 184:313-328.
- Schluter, M., N. Ruger, A. G. Savitsky, N. M. Novikova, M. Matthies, and H. Lieth. 2006. TUGAI: An integrated simulation tool for ecological assessment of alternative water management strategies in a degraded river delta. *Environmental Management* 38:638-653.
- Scurlock, D. 1998. From the Rio to the Sierra: An Environmental History of the Middle Rio Grande Basin. General Technical Report: RMRS-GTR-5. USDA Forest Service Rocky Mountain Forest and Range Experiment Station, Fort Collins, Colorado.
- Schumm, S. A. 1977. *The Fluvial System*. Wiley Press, New York, New York.
- Scott, M. L., M. A. Wondzell, and G. T. Auble. 1993. Hydrograph characteristics relevant to the establishment and growth of western riparian vegetation. In *Proceedings of the 13th Annual American Geophysical Union Hydrology Days*. Edited by Morel-Seytoax, H. J., pp. 237-246. Hydrology Days Publications, Atherton, CA.

- Smith, R. D. 2001. Hydrogeomorphic approach to assessing wetland functions: Guidelines for developing regional guidebooks. ERDC/EL TR-01-29. U.S. Army Engineer Research and Development Center, Vicksburg, Mississippi. (<http://el.erdc.usace.army.mil/wetlands/pdfs/trel01-29.pdf>) (SEPTEMBER 2008).
- Smith, R. D. 2008. Russian River watershed management plan: Baseline watershed assessment synthesis report. U. S. Engineer Research and Development Center, Vicksburg, Mississippi. (<http://www.russianriverwatershed.net/docs.php?oid=100002720&ogid=10561>) (SEPTEMBER 2008).
- Smith, R. D., A. Ammann, C. Bartoldus, and M. Brinson. 1995. An approach for assessing wetland functions using hydrogeomorphic classification, reference wetlands, and functional indices. Technical Report WRP-DE-9. U.S. Army Engineer Waterways Experiment Station, Vicksburg, Mississippi. (<http://el.erdc.usace.army.mil/wetlands/pdfs/wrpde9.pdf>) (SEPTEMBER 2008).
- Society for Ecological Restoration International. 2004. The Society of Ecological Restoration International Primer on Ecological Restoration, Version 2. ([http://www.ser.org/content/ecological\\_restoration\\_primer.asp](http://www.ser.org/content/ecological_restoration_primer.asp)) (SEPTEMBER 2008).
- Soule, M. E., ed. 1987. *Viable Populations for Conservation*. Cambridge University Press, Cambridge, UK.
- Stamps, J. A. 1991. The effect of conspecifics on habitat selection in territorial species. *Behavioral Ecology and Sociobiology* 28:29-36.
- Stohlgren, T. J., D. Binkley, G. W. Chong, M. A. Kalkhan, L. D. Schell, K. A. Bull, Y. Otsuki, G. Newman, M. Bashkin, and Y. Son. 1999. Exotic plant species invade hot spots of native plant diversity. *Ecological Monograph* 69:25-46.
- Store, R., and J. Kangas. 2001. Integrating spatial multi-criteria evaluation and expert knowledge for GIS-based habitat suitability modelling. *Landscape and Urban Planning* 55:79-93.
- Store, R., and J. Jokimaki. 2003. A GIS-based multi-scale approach to habitat suitability modeling. *Ecological Modelling* 169:1-15. Center for Watershed Protection. 1994. The importance of imperviousness. *Watershed Protection Techniques* 1:100-111.
- Stromberg, J. C., D. T. Patten, and B. D. Richter. 1991. Flood flows and dynamics of Sonoran riparian forests. *Rivers* 2: 221-235.
- Stromberg, J. C., V. B. Beauchamp, M. D. Dixon, S. J. Lite, and C. Paradzick. 2007. Importance of low-flow and high-flow characteristics to restoration of riparian vegetation along rivers in arid south-western United States. *Freshwater Biology* 52:651-679.
- Swanson, F. J., J. A. Jones, D. O. Wallin, and J. H. Cissel. 1993. Natural variability – implications for ecosystem management. In *Eastside Forest Ecosystem Health Assessment. Vol. II. Ecosystem Management: Principles and Applications*. Edited by Jensen, M. E., and P. S. Bourgeron. U.S. Forest Service, Portland, Oregon.

- Tashjian, P. 1999. Geomorphology and Hydrology Data. <http://bhg.fws.gov/geomorph.htm> (AUGUST 2008).
- Texas Parks and Wildlife Department (TPWD). 2007. Oak-Prairie wildlife management website, [http://www.tpwd.state.tx.us/landwater/land/habitats/oak\\_prairie/](http://www.tpwd.state.tx.us/landwater/land/habitats/oak_prairie/) (APR 2008).
- Tinker, D. B., W. H. Romme, and D. G. Despain. 2003. Historic range of variability in landscape structure in subalpine forests of the Greater Yellowstone Areas, USA. *Landscape Ecology* 18:427-439.
- Turner, M. G. 1989. Landscape ecology: The effect of pattern on process. *Annual Review of Ecology and Systematics* 20:171-197.
- Turner, M. G., R. H. Gardener, and R. V. O'Neill. 2001. *Landscape Ecology in Theory and Practice: Pattern and Process*. Springer-Verlag, New York, New York.
- U.S. Army Corps of Engineers (USACE). 2000. Planning guidance notebook, Engineer Regulation 1105-2-100, Washington, DC.
- \_\_\_\_\_. 2002. Bosque Restoration, Middle Rio Grande Reconnaissance Study Section 905(b) Analysis, prepared for the USACE Albuquerque District (New Mexico) by Bohannon Huston Inc and Sites Southwest LLC of Albuquerque under Contract DACW47-00-D-0002, as Delivery Order 017. <http://www.bosquerevive.com/Recon/bosquefinalrpt8-03-LORES.pdf> (MAY 2008).
- \_\_\_\_\_. 2003a. Middle Rio Grande Bosque Restoration Supplemental Planning Document, Albuquerque, NM. <http://www.bosquerevive.com/Recon/bosquefinalrpt8-03-LORES.pdf> (MAY 2008).
- \_\_\_\_\_. 2003b. Planning civil work projects under the environmental operating principles, EC 1105-2-404, Washington, DC.
- \_\_\_\_\_. 2005. Planning models improvement program: Model certification, EC 1105-2-407, Washington, DC. <http://el.erd.usace.army.mil/ecocx/model.html> (JUNE 2008).
- \_\_\_\_\_. 2007a. Final Environmental Impact Statement for the Upper Rio Grade Basin Water Operations Review (URGWOPS), USACE Albuquerque District, Albuquerque, NM (<http://www.spa.usace.army.mil/urgwops/finaleis.asp>) (SEPTEMBER 2008).
- \_\_\_\_\_. 2007b. Middle Rio Grande Bosque Ecosystem Restoration Project: Feasibility Scoping Meeting Documentation, USACE Albuquerque District, Albuquerque, NM.
- \_\_\_\_\_. 2007c. Protocols for Certification of Planning Models, Washington, DC. [http://www.usace.army.mil/cw/cecw-cp/models/protocols\\_cert\\_7-02-07.pdf](http://www.usace.army.mil/cw/cecw-cp/models/protocols_cert_7-02-07.pdf) (APR 2008).
- \_\_\_\_\_. 2008a. Put title here, USACE Albuquerque District, Albuquerque, NM.

- \_\_\_\_\_. 2008b. Environmental Assessment: Put title here, USACE Albuquerque District, Albuquerque, NM.
- U. S. Environmental Protection Agency (USEPA). 1999. Considering ecological processes in environmental impact assessments, Washington, DC.  
<http://www.epa.gov/compliance/resources/policies/nepa/ecological-processes-eia-pg.pdf> (APR 2008).
- \_\_\_\_\_. 2002. Methods for evaluating wetland conditions: #1 Introduction to wetland biological assessment. EPA-822-R-02-014. Office of Water, U. S. Environmental Protection Agency, Washington, D. C.  
(<http://www.epa.gov/waterscience/criteria/wetlands/1Introduction.pdf>) (SEPTEMBER 2008).
- U. S. Fish and Wildlife Service (USFWS). 1980a. Habitat as a Basis for Environmental Assessment, Ecological Services Manual 101. U.S. Fish and Wildlife Service, Department of the Interior, Washington, DC.
- \_\_\_\_\_. 1980b. Habitat Evaluation Procedure (HEP), Ecological Services Manual 102. U.S. Fish and Wildlife Service, Department of the Interior, Washington, DC.
- \_\_\_\_\_. 1980c. Standards for the Development of Habitat Suitability Index models, Ecological Services Manual 103. U.S. Fish and Wildlife Service, Department of the Interior, Washington, DC.
- Wagner, M. 2004. Managing riparian habitats for wildlife in addition to their aesthetic and economic value, riparian areas perform key ecological functions. PWD BR W7000-306. Texas Parks and Wildlife Department, Austin, TX.  
[http://www.tpwd.state.tx.us/publications/pwdpubs/media/pwd\\_br\\_w7000\\_0306.pdf](http://www.tpwd.state.tx.us/publications/pwdpubs/media/pwd_br_w7000_0306.pdf) (APR 2008).
- Waltemeyer, S. D. 1987. Trend in streamflow and reservoir contents in the Rio Grande Basin. New Mexico Proceedings, 31st Annual New Mexico Water Conference. WRRRI Report No. 219.
- Wardrop, D. H., M. E. Kentula, D. L. Stevens, Jr., S. F. Jensen, and R. P Brooks. 2007. Assessment of wetland condition: An example for the Upper Juniata Watershed in Pennsylvania, USA. *Wetlands* 27:416-431.
- Warne, A. G., L. A. Toth, and W. A. White. 2000. Drainage-basin-scale geomorphic analysis to determine reference conditions for ecologic restoration – Kissimmee River, Florida. *Geological Society of America Bulletin* 112:884-899.
- Watzin, M. C., R. L. Smyth, E. A. Cassell, W. C. Hession, R. E. Manning, and D. W. Rubenstein. 2005. Ecosystem indicators and an environmental score card for the Lake Champlain Basin Program. Technical Report No. 46, Rubenstein School of Environment and Natural Resources, University of Vermont, Burlington, Vermont.
- Werner, E. E. 1984. The mechanism of species interactions and community organization in fish. In *Ecological Communities: Conceptual Issues and Evidence*. Edited by Strong, D. R., Jr., D. Simberloff, L. G. Abele, and A. B. Thistle, pp. 360-382. Princeton University Press, Princeton, New Jersey.



- Whigham, D. F., A. D. Jacobs, D. E. Weller, T. E. Jordan, M. E. Kentula, S. F. Jensen, and D. L. Stevens, Jr. 2007. Combining HGM and EMap procedures to assess wetlands at the watershed scale – status of flats and non-tidal riverine wetlands in the Nanticoke River Watershed, Delaware and Maryland (USA). *Wetlands* 27:462-278.
- White, P.S. and J. Walker. 1997. Approximating nature's variation: Selecting and using reference information in restoration ecology. *Restoration Ecology* 5:338-349.
- Winter, T. C. 1988. Conceptual framework for assessment of cumulative impacts on the hydrology of non-tidal wetlands. *Environmental Management* 12:605-620.
- Winter, T. C., and M. R. Llamas. 1993. Introduction to the 28<sup>th</sup> International Geological Congress Symposium on the hydrogeology of wetlands. *Journal of Hydrology* 141:1-3.
- Wolman, M. G., and R. Gerson. 1978. Relative scales of time and effectiveness of climate in watershed geomorphology. *Earth Surface Processes and Landform* 3(2):189-208.
- Woodson, R. C. 1961. Stabilization of the Middle Rio Grande in New Mexico. Proceedings of the American Society of Civil Engineers. Journal of the Waterways and Harbor Division. 81. No. WW4. p 1-15.
- Wozniak, F. E. 1997. *Irrigation in the Rio Grande Valley, New Mexico: A Study and Annotated Bibliography of the Development of Irrigation Systems*. RMRS-P-2. U. D. Department of Agriculture, Rocky Mountain Research Station, Fort Collins, Colorado.
- Yoe, C. E. and K. D. Orth. 1996. Planning Manual, IWR Report 96-R-21. Alexandria, VA: U.S. Army Engineer Institute for Water Resources.

## Appendix A: Notation

<i>AAHU</i>	Average Annual Habitat Unit
<i>AOSD</i>	City of Albuquerque Open Space Division
<i>BOR</i>	Bureau of Reclamation
<i>CT</i>	Cover Type
<i>EA</i>	Environmental Assessment
<i>EC</i>	Engineering Circular
<i>ERDC-EL</i>	Engineer Research and Development Center, Environmental Laboratory
<i>ESM</i>	Ecological Service Manual
<i>E-Team</i>	Ecosystem Assessment Team
<i>EXHEP</i>	EXpert Habitat Evaluation Procedures Module
<i>EXHGM</i>	EXpert Hydrogeomorphic Approach to Wetland Assessments Module
<i>GIS</i>	Geographic Information System
<i>HEAT</i>	Habitat Evaluation and Assessment Tools
<i>HEP</i>	Habitat Evaluation Procedures
<i>HGM</i>	Hydrogeomorphic Wetland Assessment
<i>HSI</i>	Habitat Suitability Index
<i>HU</i>	Habitat Unit
<i>ISC</i>	Interstate Stream Commission
<i>IWR</i>	Institute for Water Resources
<i>LRSI</i>	Life Requisite Suitability Index
<i>LPDT</i>	Laboratory-based Project Delivery Team
<i>LTR</i>	Laboratory-based Technical Review
<i>LTRT</i>	Laboratory-based Technical Review Team
<i>LULC</i>	Land Use/Land Cover
<i>MCDA</i>	Multi Criteria Decision Analysis
<i>MRGBER</i>	Middle Rio Grande Bosque Ecosystem Restoration Feasibility Study
<i>MRGCD</i>	Middle Rio Grande Conservancy District
<i>NER</i>	National Ecosystem Restoration Plan
<i>NEPA</i>	National Environmental Policy Act
<i>NHNM</i>	Natural Heritage New Mexico

---

<i>NMDGF</i>	New Mexico Department of Game and Fish
<i>NMSFD</i>	New Mexico State Forestry Division
<i>NRC</i>	National Research Council
<i>PMIP</i>	USACE Planning Models Improvement Program
<i>RMRS</i>	Rocky Mountain Research Station
<i>RA</i>	Relative Area
<i>SI</i>	Suitability Index
<i>SWCD</i>	Ciudad Soil and Water Conservation District
<i>TY</i>	Target Year
<i>UNM</i>	University of New Mexico
<i>USACE</i>	U.S. Army Corps of Engineers
<i>USEPA</i>	U.S. Environmental Protection Agency
<i>USFS</i>	U.S. Forest Service
<i>USFWS</i>	U.S. Fish and Wildlife Service
<i>USGS</i>	U.S. Geological Survey
<i>WOP</i>	Without-project Condition
<i>WP</i>	With-project Condition

## Appendix B: Glossary

<b>Activity</b>	The smallest component of a management measure that is typically a nonstructural, ongoing (continuing or periodic) action in USACE planning studies ( <a href="#">Robinson, Hansen, and Orth 1995</a> ).
<b>Alternative (aka Alternative Plan, Plan, or Solution)</b>	<p>An alternative can be composed of numerous management measures that in turn are comprised of multiple features or activities. Alternatives are mutually exclusive, but management measures may or may not be combinable with other management measures or alternatives (<a href="#">Robinson, Hansen, and Orth 1995</a>).</p> <p>In HEP analyses, this is the "With-project" condition commonly used in restoration studies. Some examples of Alternatives include:</p> <p><i>Alternative 1: Plant food plots, increase wetland acreage by 10 percent, install 10 goose nest boxes, and build a fence around the entire site.</i></p> <p><i>Alternative 2: Build a dam, inundate 10 acres of riparian corridor, build 50 miles of supporting levee, and remove all wetlands in the levee zone.</i></p>

**Alternative  
(cont)**

*Alternative 3: Reduce the grazing activities on the site by 50 percent, replant grasslands (10 acres), install a passive irrigation system, build 10 escape cover stands, use 5 miles of willow fascines along the stream bank for stabilization purposes.*

**Assessment  
Model**

A simple mathematical tool that defines the relationship between ecosystem/landscape scale variables and either functional capacity of a wetland or suitability of habitat for species and communities. Habitat Suitability Indices are examples of assessment models that the **HEAT** software can be used to assess impacts/benefits of alternatives.

**Average Annual  
Habitat Units  
(AAHUs)**

A quantitative result of annualizing Habitat Unit (HU) gains or losses across all years in the period of analysis.

AAHUs = Cumulative HUs ÷ Number of years in the life of the project (aka period of analysis), where:

Cumulative HUs =

$$\Sigma (T2 - T1) \left[ \left\{ \frac{(A1 H1 + A2 H2)}{3} \right\} + \left\{ \frac{(A2 H1 + A1 H2)}{6} \right\} \right]$$

and where:

T1 = First Target Year time interval

T2 = Second Target Year time interval

A1 = Area of available wetland assessment area at beginning of T1

A2 = Area of available wetland assessment area at end of T2

H1 = HSI at beginning of T1

H2 = HSI at end of T2.

**Baseline  
Condition  
(aka Existing  
Conditions)**

The point in time before proposed changes are implemented in habitat assessment and planning analyses. Baseline is synonymous with Target Year (TY = 0).

<b>Blue Book</b>	<p>In the past, the USFWS was responsible for publishing documents identifying and describing HSI models for numerous species across the nation. Referred to as "Blue Books" in the field, due primarily to the light blue tint of their covers, these references fully illustrate and define habitat relationships and limiting factor criteria for individual species nationwide. Blue Books provide: HSI Models, life history characteristics, SI curves, methods of variable collection, and referential material that can be used in the application of the HSI model in the field. For copies of Blue Books, or a list of available Blue Books, contact your local USFWS office.</p>
<b>Calibration</b>	<p>The use of known (reference) data on the observed relationship between a dependent variable and an independent variable to make estimates of other values of the independent variable from new observations of the dependent variable.</p>
<b>Combined NED/NER Plan (Combined Plan)</b>	<p>Plans that produce both types of benefits such that no alternative plan or scale has a higher excess of NED plus NER benefits over total project costs (<a href="#">USACE 2003</a>).</p>
<b>Cover Type (CT)</b>	<p>Homogenous zones of similar vegetative species, geographic similarities and physical conditions that make the area unique. In general, cover types are defined on the basis of species recognition and dependence.</p>



---

<b>Ecosystem</b>	A biotic community, together with its physical environment, considered as an integrated unit. Implied within this definition is the concept of a structural and functional whole, unified through life processes. Ecosystems are hierarchical, and can be viewed as nested sets of open systems in which physical, chemical and biological processes form interactive subsystems. Some ecosystems are microscopic, and the largest comprises the biosphere. Ecosystem restoration can be directed at different-sized ecosystems within the nested set, and many encompass multi-states, more localized watersheds or a smaller complex of aquatic habitat.
<b>Ecosystem Assessment Team (E-Team)</b>	An interdisciplinary group of regional and local scientists responsible for determining significant resources, identification of reference sites, construction of assessment models, definition of reference standards, and calibration of assessment models. In some instances the E-Team is also referred to as the Environmental Assessment Team or simply the Assessment Team.

**Ecosystem  
Function**

Ecosystem functions are the dynamic attributes of ecosystems, including interactions among organisms and interactions between organisms and their environment (SERI 2001). Some restoration ecologists limit the use of the term "ecosystem functions" to those dynamic attributes which most directly affect metabolism, principally the sequestering and transformation of energy, nutrients, and moisture. Examples are carbon fixation by photosynthesis, trophic interactions, decomposition, and mineral nutrient cycling. When ecosystem functions are strictly defined in this manner, other dynamic attributes are distinguished as "ecosystem processes" such as substrate stabilization, microclimatic control, differentiation of habitat for specialized species, pollination and seed dispersal. Functioning at larger spatial scales is generally conceived in more general terms, such as the long-term retention of nutrients and moisture and overall ecosystem sustainability.

**Ecosystem  
Integrity**

The state or condition of an ecosystem that displays the biodiversity characteristic of the reference, such as species composition and community structure, and is fully capable of sustaining normal ecosystem functioning (SERI 2001). These characteristics are often defined in terms such as health, biodiversity, stability, sustainability, naturalness, wildness, and beauty.

**Ecosystem Services**

The capacity of natural processes and components to provide goods and services that satisfy human needs directly or indirectly ([de Groot et al. 2002](#)).

The benefits people obtain from ecosystems. These include provisioning services such as food and water; regulating services such as regulation of floods, drought, land degradation, and disease; supporting services such as soil formation and nutrient cycling; and cultural services such as recreational, spiritual, religious, and other nonmaterial benefits ([Millennium Ecosystem Assessment 2005](#)).

**Equivalent Optimal Area (EOA)**

The concept of equivalent optimal area (EOA) is used in HEP applications where the composition of the landscape, in relation to providing life requisite habitat, is an important consideration. An EOA is used to weight the value of the LRSI score to compensate for this inter-relationship. For example, for optimal wood duck habitat conditions, at least 20 percent of an area should be composed of cover types providing brood-cover habitat (a life requisite). If an area has less than 20 percent in this habitat, the suitability is adjusted downward.

**Existing Condition**

Also referred to as the baseline condition, the existing condition is the point in time before proposed changes, and is designated as Target Year (TY = 0) in the analysis.

<b>Feature</b>	A feature is the smallest component of a management measure that is typically a structural element requiring construction in USACE planning studies (Robinson, Hansen, and Orth 1995).
<b>Field Data</b>	This information is collected on various parameters (i.e., variables) in the field, and from aerial photos, following defined, well-documented methodology in typical HEP applications. An example is the measurement of percent herbaceous cover, over ten quadrats, within a cover type. The values recorded are each considered “field data.” Means of variables are applied to derive suitability indices and/or functional capacity indices.
<b>Goal</b>	A goal is defined as the end or final purpose. Goals provide the reason for a study rather than a reason to formulate alternative plans in USACE planning studies (Yoe and Orth 1996).
<b>Guild</b>	A group of functionally similar species with comparable habitat requirements whose members interact strongly with one another, but weakly with the remainder of the community. Often a species HSI model is selected to represent changes (impacts) to a guild.
<b>Habitat Assessment</b>	The process by which the suitability of a site to provide habitat for a community or species is measured. This approach measures habitat suitability using an assessment model to determine an HSI.

**Habitat Suitability Index Model (HSI)** A quantitative estimate of suitability habitat for a site. The ideal goal of an HSI model is to quantify and produce an index that reflects functional capacity at the site. The results of an HSI analysis can be quantified on the basis of a standard 0-1.0 scale, where 0.00 represents low functional capacity for the wetland, and 1.0 represents high functional capacity for the wetland. An HSI model can be defined in words, or mathematical equations, that clearly describe the rules and assumptions necessary to combine functional capacity indices in a meaningful manner for the wetland.

**Habitat Suitability Index Model (HSI) (cont)**

For example:

$$HSI = (SI V_1 * SI V_2) / 4,$$

where:

SI V<sub>1</sub> is the Variable Subindex for variable 1;

SI V<sub>2</sub> is the SI for variable 2

<b>Habitat Unit (HU)</b>	<p>A quantitative environmental assessment value, considered the biological currency in HEP. Habitat Units (HUs) are calculated by multiplying the area of available habitat (quantity) by the quality of the habitat for each species or community. Quality is determined by measuring limiting factors for the species (or community), and is represented by values derived from Habitat Suitability Indices (HSIs).</p> <p>HU = AREA (acres) X HSI.</p> <p>Changes in HUs represent potential impacts or improvements of proposed actions.</p>
<b>Life Requisite Suitability Index (LRSI)</b>	<p>A mathematical equation that reflects a species' or community's sensitivity to a change in a limiting life requisite component within the habitat type in HEP applications. LRSIs are depicted using scatter plots and bar charts (i.e., life requisite suitability curves). The LRSI value (Y axis) ranges on a scale from 0.0 to 1.0, where an LRSI = 0.0 means the factor is extremely limiting and an LRSI = 1.0 means the factor is in abundance (not limiting) in most instances.</p>
<b>Limiting Factor</b>	<p>A variable whose presence/absence directly restrains the existence of a species or community in a habitat in HEP applications. A deficiency of the limiting factor can reduce the quality of the habitat for the species or community, while an abundance of the limiting factor can indicate an optimum quality of habitat for the same species or community.</p>

---

<b>Locally Preferred Plan (LPP)</b>	The name frequently given to a plan that is preferred by the non-Federal sponsor over the National Economic Development (NED) plan ( <a href="#">USACE 2000</a> ).
<b>Management Measure</b>	The components of a plan that may or may not be separable actions that can be taken to affect environmental variables and produce environmental outputs. A management measure is typically made up of one or more features or activities at a particular site in USACE Planning studies ( <a href="#">Robinson, Hansen, and Orth 1995</a> ).
<b>Measure</b>	The act of physically sampling variables such as height, distance, percent, etc., and the methodology followed to gather variable information in HEP applications (i.e., see “Sampling Method” below).



**Multiple  
Formula Model  
(MM)  
(aka Life  
Requisite  
Model)**

In HEP applications, there are two types of HSI models, the Single Formula Model (SM) (refer to the definition below) and the Multiple Formula Model (MM). In this case a multiple formula model is, as one would expect, a model that uses more than one formula to assess the suitability of the habitat for a species or a community. If a species/community is limited by the existence of more than one life requisite (food, cover, water, etc.), and the quality of the site is dependent on a minimal level of each life requisite, then the model is considered an MM model. In order to calculate the HSI for any MM, one must derive the value of a Life Requisite Suitability Index (LRSI) (see definition below) for each life requisite in the model – a process requiring the user to calculate multiple LRSI formulas. This Multiple Formula processing has led to the name “Multiple Formula Model” in HEP.

**Multi-Criteria  
Decision  
Analysis  
(MCDA)**

The study of methods and procedures by which concerns about multiple conflicting criteria can be formally incorporated into the management planning process", as defined by the International Society on Multiple Criteria Decision Making (<http://www.terry.uga.edu/mcdm/> MAY 2008).

MCDA is also referred as Multi-Criteria Decision Making (MCDM), Multi-Dimensions Decision-Making (MDDM), and Multi-Attributes Decision Making (MADM)

**National  
Economic  
Development  
(NED) Plan**

For all project purposes except ecosystem restoration, the alternative plan that reasonably maximizes net economics benefits consistent with protecting the Nation's environment, the NED plan, shall be selected. The Assistant Secretary of the Army for Civil Works (ASACW) may grant an exception when there are overriding reasons for selecting another plan based upon other Federal, State, local and international concerns ([USACE 2000](#)).

**National  
Ecosystem  
Restoration  
(NER) Plan**

For ecosystem restoration projects, a plan that reasonably maximizes ecosystem restoration benefits compared to costs, consistent with the Federal objective, shall be selected. The selected plan must be shown to be cost effective and justified to achieve the desired level of output. This plan shall be identified as the National Ecosystem Restoration (NER) Plan. ([USACE 2000](#)).

**No Action Plan  
(aka No Action  
Alternative or  
Without-project  
Condition)**

Also referred to as the Without-project condition, the No Action Plan describes the project area's future if there is no Federal action taken to solve the problem(s) at hand. Every alternative is compared to the same Without-project condition ([Yoe and Orth 1996](#)).

<b>Objective</b>	A statement of the intended purposes of the planning process; it is a statement of what an alternative plan should try to achieve. More specific than goals, a set of objectives will effectively constitute the mission statement of the Federal/non-Federal planning partnership. A planning objective is developed to capture the desired changes between the without- and With-project conditions that when developed correctly identify effect, subject, location, timing, and duration (Yoe and Orth 1996).
<b>Plan (aka Alternative, Alternative Plan, or Solution)</b>	A set of one or more management measures functioning together to address one or more planning objectives (Yoe and Orth 1996). Plans are evaluated at the site level with HEP or other assessment techniques and cost analyses in restoration studies (Robinson, Hansen, and Orth 1995).
<b>Program</b>	Combinations of recommended plans from different sites make up a program. Where the recommended plan at each such site within a program is measured in the same units, a cost analyses can be applied in a programmatic evaluation (Robinson, Hansen, and Orth 1995).
<b>Project Area</b>	The area that encompasses all activities related to an ongoing or proposed project.
<b>Project Manager</b>	Any biologist, economist, hydrologist, engineer, decision- maker, resource project manager, planner, environmental resource specialist, limnologist, etc., who is responsible for managing a study, program, or facility.

<b>Reference Domain</b>	The geographic area from which reference communities or wetland are selected in HEP applications. A reference domain may, or may not, include the entire geographic area in which a community or wetland occurs.
<b>Reference Ecosystems</b>	All the sites that encompass the variability of all conditions within the region in HEP applications. Reference ecosystems are used to establish the range of conditions for construction and calibration of HSIs and establish reference standards.
<b>Reference Standard Ecosystems</b>	The ecosystems that represent the highest level of habitat suitability or function found within the region for a given species or community in HEP applications.
<b>Relative Area (RA)</b>	<p>The relative area is a mathematical process used to “weight” the various applicable cover types on the basis of quantity in HEP applications. To derive the relative area of a model’s CTs, the following equation can be utilized:</p> $\text{Relative Area} = \frac{\text{Acres of Cover Type}}{\text{Total Applicable Area}}$ <p>where:</p> <p>Acres of Cover Type = only those acres assigned to the cover type of interest within the site</p> <p>Total Applicable Area = the sum of the acres associated with the model at the site.</p>

**Relative Preferences**

The rank of ecosystem services in order of importance. Relative preferences for various services are much easier to determine than differences in dollar measures of service values. Although less common than dollar measures of value, individual and community indices of ranked preferences can be used to aggregate service values and compare plans using a single measure ([King et al. 2000](#)).

**Risk**

The volatility of potential outcomes. In the case of ecosystem values, the important risk factors are those that affect the possibility of service flow disruptions and the reversibility of service flow disruptions. These are associated with controllable and uncontrollable on-site risk factors (e.g., invasive plants, overuse, or restoration failure) and landscape risk factors (e.g., changes in adjacent land uses, water diversions) ([King et al. 2000](#)).

**Sampling Method**

The protocol followed to collect and gather field data in HEP and HGM applications. It is important to document the relevant criteria limiting the collection methodology. For example, the time of data collection, the type of techniques used, and the details of gathering this data should be documented as much as possible. An example of a sampling method would be:

*Between March and April, run five random 50-m transects through the relevant cover types. Every 10-m along the transect, place a 10-m<sup>2</sup> quadrat on the right side of the transect tape and record the percent herbaceous cover within the quadrat. Average the results per transect.*

**Scale**

In some geographical methodologies, the scale is the defined size of the image in terms of miles per inch, feet per inch, or pixels per acres. Scale can also refer to different “sizes” of plans (Yoe and Orth 1996) or variations of a management measure in cost analyses. Scales are mutually exclusive, and therefore a plan or alternative may only contain one scale of a given management measure (Robinson, Hansen, and Orth 1995).

<b>Single Formula Model (SM)</b>	In habitat assessments, there are two potential types of models selected to assess change at a site – the Single Formula Model and the Multiple Formula Model (refer to the definition above). In this instance, an HSI model is based on the existence of a single life requisite requirement, and a single formula is used to depict the relationship between quality and carrying capacity for the site.
<b>Site</b>	The location upon which the project manager will take action, evaluate alternatives and focus cost analysis ( <a href="#">Robinson, Hansen, and Orth 1995</a> ).
<b>Solutions (aka Alternative, Alternative Plan, or Plan)</b>	A solution is a way to achieve all or part of one or more planning objectives ( <a href="#">Yoe and Orth 1996</a> ). In cost analysis, this is the alternative (see definition above).
<b>Spreadsheet</b>	A type of computer file or page that allows the organization of data (alpha-numeric information) in a tabular format. Spreadsheets are often used to complete accounting/economic exercises.
<b>Suitability Index (SI)</b>	A mathematical equation that reflects a species' or community's sensitivity to a change in a limiting factor (i.e., variable) within the habitat type in HEP applications. These indices are depicted using scatter plots and bar charts (i.e., suitability curves). The SI value (Y-axis) ranges on a scale from 0.0 to 1.0, where an SI = 0.0 means the factor is extremely limiting, and an SI = 1.0 means the factor is in abundance (not limiting) for the species/community (in most instances).



- Target Year (TY)** A unit of time measurement used in HEP that allows the project manager to anticipate and direct significant changes (in area or quality) within the project (or site). As a rule, the baseline TY is always  $TY = 0$ , where the baseline year is defined as a point in time before proposed changes would be implemented. As a second rule, there must always be a  $TY = 1$ , and a  $TY = X_2$ .  $TY_1$  is the first year land- and water-use conditions are expected to deviate from baseline conditions.  $TY_{X_2}$  designates the ending target year. A new target year must be assigned for each year the project manager intends to develop or evaluate change within the site or project. The habitat conditions (quality and quantity) described for each TY are the expected conditions at the end of that year. It is important to maintain the same target years in both the environmental and economic analyses.
- Trade-Offs(TOs)** Used to adjust the model outputs by considering human values. There are no right or proper answers, only acceptable ones. If trade-offs are used, outputs are no longer directly related to optimum habitat or wetland function ([Robinson, Hansen, and Orth 1995](#)).

**Validation**

Establishing by objective yet independent evidence that the model specifications conform to the user's needs and intended use(s). The validation process questions whether the model is an accurate representation of the system based on independent data not used to develop the model in the first place. Validation can encompass all of the information that can be verified, as well as all of the things that cannot -- i.e., all of the information that the model designers might never have anticipated the user might want or expect the product to do.

For purposes of this effort, *validation* refers to independent data collections (bird surveys, water quality surveys, etc.) that can be compared to the model outcomes to determine whether the model is capturing the essence of the ecosystem's functionality.

**Variable**

A measurable parameter that can be quantitatively described, with some degree of repeatability, using standard field sampling and mapping techniques. Often, the variable is a limiting factor for a wetland's functional capacity used in the development of SI curves and measured in the field (or from aerial photos) by personnel, to fulfill the requirements of field data collection in an HEP application. Some examples of variables include: height of grass, percent canopy cover, distance to water, number of snags, and average annual water temperature.

<b>Verification</b>	<p>Model verification refers to a process by which the development team confirms by examination and/or provision of objective evidence that specified requirements of the model have been fulfilled with the intention of assuring that the model performs (Or behaves) as it was intended.</p> <p>Sites deemed to be highly functional wetlands according to experts, should produce high HSI scores. Sites deemed dysfunctional (by the experts) should produce low HSI scores.</p>
<b>Without-project Condition(WOP) (aka No Action Plan or No Action Alternative)</b>	<p>Often confused with the terms “Baseline Condition” and “Existing Condition,” the Without-Project Condition is the expected condition of the site without implementation of an alternative over the life of the project (aka period of analysis), and is also referred to as the “No Action Plan” in traditional planning studies (Yoe and Orth 1996; USACE 2000).</p>
<b>With-project Condition (WP)</b>	<p>In planning studies, this term is used to characterize the condition of the site after an alternative is implemented (Yoe and Orth 1996; USACE 2000).</p>



## Appendix C: Model Certification Crosswalk

Information necessary to address model certification/one-time-use approval under EC 1105-2-407 is presented in *Table 2* of the *USACE Protocols for Certification of Planning Models* report (USACE 2007c, pages 9-11)<sup>1</sup>. In an effort to streamline the review of the Bosque Riparian community-based (HSI) index model, the authors have provided a table to crosswalk the EC requirements and the information contained in this report (Table C - 1). One-time-use approval was granted by the Eco-PCX in April 2009, and the memo documenting this approval has been included below the table.

Table C - 1. Crosswalk between EC 1105-2-407 model certification requirements and information contained in this report.

Cover Sheet	
a.	<b>Model Name(s):</b> Bosque Riparian Community Index Model for the Middle Rio Grande, Albuquerque, New Mexico
b.	<b>Functional Area:</b> Ecosystem Restoration; Impact Assessment /Mitigation
c.	<b>Model Proponent:</b> Albuquerque District
d.	<b>Model Developers</b> ERDC-EL and Albuquerque District (with support from interagency and stakeholder participants)
1. Background	
a.	<b>Purpose of Model:</b> The model was developed in an effort to quantify the value of diverse biological resources in this study area with the intent of capturing complex biotic patterns of the landscape. Refer to <i>Chapter 1</i> , "Purpose of the Models" for more detail.
b.	<b>Model Description and Depiction:</b> The model was rendered in a HEP-compatible format. Model components were comprised of combinations of relevant parameters to characterize the hydrology, soils, biotic integrity, structure, spatial complexity, and disturbance regimes of the unique bosque riparian ecosystem occurring along the Middle Rio Grande Reach in central New Mexico. Model components (and their underlying variables) were normalized (scaled from 0.0 to 1.0) as required by traditional HEP procedures. Both flow charts ("ecosystem puzzles") and mathematical algorithms were used to depict the model herein. Refer to <i>Chapter 3 (Model Flow Diagram)</i> , <i>Chapter 4 (Model Formulas)</i> , and <i>Chapter 5 (Model Concept and Steps 1-5)</i> for details relating to the individual model components and format.
c.	<b>Contribution to Planning Effort:</b> The model helped to characterize the baseline conditions

<sup>1</sup> [http://www.usace.army.mil/cw/cecw-cp/models/protocols\\_cert\\_7-02-07.pdf](http://www.usace.army.mil/cw/cecw-cp/models/protocols_cert_7-02-07.pdf)

		(in a quantitative manner) of the unique and significant ecological resources along the Middle Rio Grande Reach in central New Mexico. When applied within the HEP assessment paradigm, the study team will be able to evaluate and compare the benefits of proposed ecosystem restoration initiatives. Future applications in the watershed could also use the model to evaluate and compare flood risk management measures and determine the ability of the proposed mitigation measures to offset these losses.
	d.	<b>Description of Input Data:</b> Both field and spatially-explicit (GIS) data are necessary to calculate the outputs. Refer to <a href="#">Chapter 4</a> for a list of variables and appropriate sampling protocols and statistical data management activities.
	e.	<b>Description of Output Data:</b> Habitat Suitability Indices are output on a normalized scale of 0-1 in compliance with the traditional HEP paradigm. Within a standard HEP application, these indices can be multiplied by area to produce Habitat Units (HUs), and can be assessed over time under both With- and Without-project scenarios to generate Average Annual Habitat Units (AAHUs) (Refer to <a href="#">Chapter 2 HEP Overview</a> ).
	f.	<b>Statement on the capabilities and limitations of the model:</b> The model has been tested using reference data and conditions along the Middle Rio Grande Reach. It can be used to assess baseline conditions as well as assess both a No Action condition and proposed alternative designs in either an Impact/Mitigation study or within an Ecosystem Restoration context. The model should not be applied outside of the Rio Grande-Albuquerque watershed without review and recalibration.
	g.	<b>Description of model development process including documentation on testing conducted (Alpha and Beta tests):</b> A series of workshops were convened and experts contributed to the development of both the conceptual framework and the final index model presented here. The model was calibrated using reference data from across the model domain (Middle Rio Grande Reach – refer to Figure 9). Internal (ERDC-EL) peer review has commenced, and the authors are drafting several peer-reviewed journal articles for publication. <a href="#">Appendix G</a> discusses the internal/external peer review process standard for ERDC-EL publications and model building efforts. <a href="#">Chapter 3</a> discusses the model building process. <a href="#">Chapter 4</a> discusses the model calibration process as well as the alpha/beta tests of the model to quantify baseline conditions for the study area.
<b>2. Technical Quality</b>		
	a.	<p><b>Theory:</b> In theory, the quantification of ecosystem function in these communities can be obtained by using indicators of ecosystem integrity and applying these in the well documented, and accepted HEP-based framework.</p> <p>The U.S. Fish and Wildlife Service (USFWS) published quantifiable procedures in 1980 to assess planning initiatives as they relate to change of fish and wildlife habitats (<a href="#">USFWS 1980a,b,and c</a>). These procedures, referred to collectively as Habitat Evaluation Procedures and known widely as HEP, use a habitat-based approach to assess ecosystems and provide a mechanism for quantifying changes in habitat quality and quantity over time under proposed alternative scenarios. Habitat Suitability Indices (HSIs) are simple mathematical algorithms that generate a unitless index derived as a function of one or more environmental variables that characterize or typify the site conditions (i.e., vegetative cover and composition, hydrologic regime, disturbance, etc.) and are deployed in the HEP framework to quantify the outcomes of restoration or impact scenarios. These tools have been applied many times over the course of the last 30 years (<a href="#">Williams 1988</a>, <a href="#">VanHorne and Wiens 1991</a>, <a href="#">Brooks 1997</a>, <a href="#">Brown et al. 2000</a>, <a href="#">Store and Jokimaki 2003</a>, <a href="#">Shifley et al. 2006</a>, <a href="#">Van der Lee et al. 2006</a>).</p> <p>Virtually all attempts to use HSI models have been heavily criticized, and many criticisms are well deserved. In most instances, these criticisms have focused on the lack of: (a) identification of the appropriate context (spatial and temporal) for the model parameters, (b) a conceptual framework for what the model is indicating, (c) integration of science and values, and (d) validation of the models (<a href="#">Kapustka 2005</a>, <a href="#">Barry et al. 2006</a>, <a href="#">Hirzel et al.</a></p>

	<p>2006, Inglis et al. 2006, Ray and Burgman 2006, Van der Lee et al. 2006). A fundamental problem with these approaches continues to be the inability to link species presence or relative abundance with significant aspects of habitat quality (VanHorne and Wiens 1991) such as productivity.</p> <p>Despite such criticisms, HSI models have played an important role in the characterization of ecosystem conditions nationwide. They represent a logical and relatively straightforward process for assessing change to fish and wildlife habitat (Williams 1988, VanHorne and Wiens 1991, Brooks 1997, Brown et al. 2000, Kapustka 2005). The controlled and economical means of accounting for habitat conditions makes HEP a decision-support process that is superior to techniques that rely heavily upon professional judgment and superficial surveys (Williams 1988, Kapustka 2005). They have proven to be invaluable tools in the development and evaluation of restoration alternatives (Williams 1988, Brown et al. 2000, Store and Kangas 2001, Kapustka 2003, Store and Jokimaki 2003, Gillenwater et al. 2006, Schluter et al. 2006, Shifley et al. 2006), managing refuges and nature preserves (Brown et al. 2000, Ortigosa et al. 2000, Store and Kangas 2001, Felix et al. 2004, Ray and Burgman 2006, Van der Lee et al. 2006) and others), and mitigating the effects of human activities on wildlife species (Burgman et al. 2001, NRC 2001, Van Lonkhuyzen et al. 2004). These modeling approaches emphasize usability. Efforts are made during model development to ensure that they are biologically valid and operationally robust. Most HSI models are constructed largely as working versions rather than as final, definitive models (VanHorne and Wiens 1991). Simplicity is implicitly valued over comprehensiveness, perhaps because the models need to be useful to field managers with little training or experience in this arena. The model structure is therefore simple, and the functions incorporated in the models are relatively easy to understand. The functions included in models are often based on published and unpublished information that indicates they are responsive to species density through direct or indirect effects on life requisites. The general approach of HSI modeling is valid, in that the suitability of habitat to a species is likely to exhibit strong thresholds below which the habitat is usually unsuitable and above which further changes in habitat features make little difference. And as such, most HSI models should be seen as quantitative expressions of the best understanding of the relations between easily measured environmental variables and habitat quality. Habitat suitability models then, are a compromise between ecological realism and limited data and time (Radeloff et al. 1999, Vospernik et al. 2007).</p> <p>References</p> <p>Barry, D., R. A. Fischer, K. W. Hoffman, T. Barry, E. G. Zimmerman, and K. L. Dickson. 2006. Assessment of habitat values for indicator species and avian communities in a riparian forest. <i>Southeastern Naturalist</i> 5:295-310.</p> <p>Brooks, R. P. 1997. Improving habitat suitability index models. <i>Wildlife Society Bulletin</i> 25:163-167.</p> <p>Brown, S. K., K. R. Buja, S. H. Jury, M. E. Monaco, and A. Banner. 2000. Habitat suitability index models for eight fish and invertebrate species in Casco and Sheepscot Bays, Maine. <i>North American Journal of Fisheries Management</i> 20:408-435.</p> <p>Burgman, M. A., D. R. Breininger, B. W. Duncan, and S. Ferson. 2001. Setting reliability bounds on habitat suitability indices. <i>Ecological Applications</i> 11:70-78.</p> <p>Felix, A. B., H. Campa, K. F. Millenbah, S. R. Winterstein, and W. E. Moritz. 2004. Development of landscape-scale habitat-potential models for forest wildlife planning and management. <i>Wildlife Society Bulletin</i> 32:795-806.</p> <p>Gillenwater, D., T. Granata, and U. Zika. 2006. GIS-based modeling of spawning habitat suitability for walleye in the Sandusky River, Ohio, and implications for dam removal and river restoration. <i>Ecological Engineering</i> 28:311-323.</p> <p>Hirzel, A. H., G. Le Lay, V. Helfer, C. Randin, and A. Guisan. 2006. Evaluating the ability of habitat suitability models to predict species presences. <i>Ecological Modelling</i> 199:142-152.</p>
--	--



	<p>Inglis, G. J., H. Hurren, J. Oldman, and R. Haskew. 2006. Using habitat suitability index and particle dispersion models for early detection of marine invaders. <i>Ecological Applications</i> 16:1377-1390.</p> <p>Kapustka, L. A. 2003. Rationale for use of wildlife habitat characterization to improve relevance of ecological risk assessments. <i>Human and Ecological Risk Assessment</i> 9:1425-1430.</p> <p>Kapustka, L. A. 2005. Assessing ecological risks at the landscape scale: Opportunities and technical limitations. <i>Ecology and Society</i> 10:Article 11.</p> <p>Ortigosa, G. R., G. A. De Leo, and M. Gatto. 2000. VVF: integrating modelling and GIS in a software tool for habitat suitability assessment. <i>Environmental Modelling &amp; Software</i> 15:1-12.</p> <p>Ray, N., and M. A. Burgman. 2006. Subjective uncertainties in habitat suitability maps. <i>Ecological Modelling</i> 195:172-186.</p> <p>Schluter, M., N. Ruger, A. G. Savitsky, N. M. Novikova, M. Matthies, and H. Lieth. 2006. TUGAI: An integrated simulation tool for ecological assessment of alternative water management strategies in a degraded river delta. <i>Environmental Management</i> 38:638-653.</p> <p>Shifley, S. R., F. R. Thompson, W. D. Dijak, M. A. Larson, and J. J. Millsbaugh. 2006. Simulated effects of forest management alternatives on landscape structure and habitat suitability in the Midwestern United States. <i>Forest Ecology and Management</i> 229:361-377.</p> <p>Store, R., and J. Jokimaki. 2003. A GIS-based multi-scale approach to habitat suitability modeling. <i>Ecological Modelling</i> 169:1-15.</p> <p>Store, R., and J. Kangas. 2001. Integrating spatial multi-criteria evaluation and expert knowledge for GIS-based habitat suitability modelling. <i>Landscape and Urban Planning</i> 55:79-93.</p> <p>U. S. Fish and Wildlife Service (USFWS). 1980a. Habitat as a basis for environmental assessment, <i>Ecological Services Manual 101</i>. U.S. Fish and Wildlife Service, Department of the Interior, Washington, DC.</p> <p>_____. 1980b. Habitat Evaluation Procedure (HEP), <i>Ecological Services Manual 102</i>. U.S. Fish and Wildlife Service, Department of the Interior, Washington, DC.</p> <p>_____. 1980c. Standards for the development of habitat suitability index models, <i>Ecological Services Manual 103</i>. U.S. Fish and Wildlife Service, Department of the Interior, Washington, DC.</p> <p>Van der Lee, G. E. M., D. T. Van der Molen, H. F. P. Van den Boogaard, and H. Van der Klis. 2006. Uncertainty analysis of a spatial habitat suitability model and implications for ecological management of water bodies. <i>Landscape Ecology</i> 21:1019-1032.</p> <p>Van Lonkhuysen, R. A., K. E. Lagory, and J. A. Kuiper. 2004. Modeling the suitability of potential wetland mitigation sites with a geographic information system. <i>Environmental Management</i> 33:368-375.</p> <p>VanHorne, B., and J. A. Wiens. 1991. Forest bird habitat suitability models and the development of general habitat models. Page 31 pp. in D. o. Interior, editor. U.S. Fish and Wildlife Service, Washington, D.C.</p> <p>Williams, G. L. 1988. An assessment of HEP (Habitat Evaluation Procedures) applications to Bureau of Reclamation projects. <i>Wildlife Society Bulletin</i> 16:437-447.</p>
	<p><b>b.</b> <b>Description of system being represented by the model:</b> The Middle Rio Grande bosque riparian ecosystem has been modeled here. <i>Chapter 3</i> offers community (ecosystem) characterization garnered from peer reviewed literature and gray literature generated by federal/local resource management agencies.</p>
	<p><b>c.</b> <b>Analytical requirements and assumptions:</b> Adequate sample sizes (30+ per variable) must be obtained to assure some level of precision (reduction of uncertainty). It is assumed that the user will adopt and follow the suggested sampling protocols detailed herein. Follow-on data management (calculation of means per variable) is straightforward</p>

		and should not be difficult to emulate.
	d.	<b>Conformance with Corps policies and procedures:</b> As indicated in the PMIP, HEP is an accepted and approved approach to quantifying benefits/impacts for these types of studies (Refer to <a href="#">Chapter 1 Planning Model Certification</a> ). The protocol described herein was fully vetted through the ERDC review process, and participants in the workshops, as well as external reviewers have been included in the process (Refer to <a href="#">Chapter 2 – Model Review Process</a> ). Outputs conform to Corps policies and procedures.
	e.	<b>Identification of formulas used in the model and proof that the computations are appropriate and done correctly:</b> Formulas can be found in <a href="#">Chapter 3</a> . All spreadsheets used to organize data and the datafiles used to calculate outputs can be obtained from the District upon request (contact Ondrea Hummel – see <a href="#">Appendix D</a> for contact information). ERDC-EL performed QA/QC on all spreadsheet and datafile operations and can describe these to the reviewers upon request.
<b>3. System Quality</b>		
	a.	<b>Description and rationale for selection of supporting software tool/programming language and hardware platform:</b> The <b>HEAT</b> software is a fully vetted software package currently undergoing model certification. The model described here is not software per se (Refer to <a href="#">Chapter 1 – Planning Model Certification</a> ), and as such do not contain any programming. ArcMap, ArcToolbox, and Spatial Analyst are all commercially developed off-the-shelf software programs readily available to the user base.
	b.	<b>Proof that the programming was done correctly:</b> NA
	c.	<b>Description of process used to test and validate model:</b> Verification of the model can be found in <a href="#">Chapter 4 – Model Verification</a> .
	d.	<b>Discussion of the ability to import data into other software analysis tools (interoperability issue):</b> NA
<b>4. Usability</b>		
	a.	<b>Availability of input data necessary to support the model:</b> All data (presented in spreadsheet and database format) can be obtained from the District upon request (contact Ondrea Hummel – see <a href="#">Appendix D</a> for contact information).
	b.	<b>Formatting of output in an understandable manner:</b> Outputs of the model are standard indices (HSI) - compatible with traditional HEP applications (scaled 0-1).
	c.	<b>Usefulness of results to support project analysis:</b> Model results have been successfully utilized in plan formulation and alternative comparison analyses for the Middle Rio Grande Bosque Ecosystem Restoration (MRGBER) Study.
	d.	<b>Ability to export results into project management documentation:</b> All outputs are MS Office-compatible and easily imported into MS Word and MS PowerPoint for documentation and distribution.
	e.	<b>Training availability:</b> <b>HEAT</b> software training was been provided to the Albuquerque District (and the MRGBER E-Team will receive a 5-day workshop in FY09) in 2006-2007. ERDC-EL also provides model building workshops at the local, regional and national level through PROSPECT and/or on a reimbursable basis.  The District was also required to perform 1/3 of all calculations and 1/3 of all spreadsheet management activities to assure successful technology transfer (“ownership”) of the model and the evaluations thereafter.
	f.	<b>Users documentation availability and whether it is user friendly and complete:</b> This document serves as the model “manual.”  There is a draft manual for the <b>HEAT</b> software currently undergoing certification ( <a href="#">Burks-Copes et al. 2008</a> ). And there are Ecological Service Manuals (ESMs) to support HEP

		applications ( <a href="#">USFWS 1980a-c</a> ).
	<b>g.</b>	<b>Technical support availability:</b> ERDC-EL provides technical support on all products upon request and on a reimbursable basis.
	<b>h.</b>	<b>Software/hardware platform availability to all or most users:</b> The model was provided in both MS Word and MS Excel format and in <b>HEAT</b> datafiles to all study participants (including contractors and stakeholders). All data (presented in spreadsheet and database format) can be obtained from the District upon request (contact Ondrea Hummel – see <a href="#">Appendix D</a> for contact information). The GIS data utilized herein is available upon request from the Albuquerque District.
	<b>i.</b>	<b>Accessibility of the model:</b> The model is accessible now, and will be posted on the System-wide Water Resources Program's (SWWRP) Water Resources Depot website upon completion of ERDC-EL technical review ( <a href="https://swwrp.usace.army.mil/DesktopDefault.aspx">https://swwrp.usace.army.mil/DesktopDefault.aspx</a> ).
	<b>j.</b>	<b>Transparency of model and how it allows for easy verification of calculations and outputs:</b> The mathematical operations in the model have been clearly documented herein and can be easily transferred into any spreadsheet program for verification (a step ERDC-EL uses to QA/QC every model development activity). The outputs are scaled from 0-1 (1 = optimal functionality and 0 = not functioning). An interpretative table has been provided in <a href="#">Chapter 4</a> to assist the user in conclusions.
	<b>k.</b>	<b>Accessibility (where is model physically located?):</b> Both the Albuquerque District and ERDC-EL will maintain separate and relatively permanent copies of all model information (NTE 7 years). The model will also be posted on the SWWRP website.



**DEPARTMENT OF THE ARMY**  
 MISSISSIPPI VALLEY DIVISION, CORPS OF ENGINEERS  
 P.O. BOX 80  
 VICKSBURG, MISSISSIPPI 39181-0080

REPLY TO  
 ATTENTION OF:

CEMVD-RB-T

23 April 2009

MEMORANDUM FOR Commander, South Pacific Division  
 ATTN: (Paul Bowers, CESPDPDC)

SUBJECT: Middle Rio Grande Bosque Feasibility, New Mexico General  
 Investigation Detailed Feasibility Study, Ecosystem Restoration  
 Planning Center of Expertise Endorsement of Review Plan

1. References:

- a. EC 1105-2-410, Review of Decision Documents, 22 August 2008.

2. The enclosed Review Plan (RP) complies with all applicable policy and provides an adequate peer review of the plan formulation, engineering, and environmental analyses, and other aspects of the plan development. The Ecosystem Restoration Planning Center of Expertise (ECO-PCX) has reviewed the RP and documentation of the review is attached.

3. The ECO-PCX concurs with the conclusion that Independent External Peer Review of this project is not necessary. Documentation and review of the Bosque Community Habitat Suitability Index Model is sufficient to demonstrate technical and system quality of the model for single-use on this project. Non-substantive changes to this RP do not require further approval.

3. The ECO-PCX recommends the RP for approval by the MSC Commander. Upon approval of the RP, please provide a copy of the approved RP, a copy of the MSC Commander approval memorandum, and the link to where the RP is posted on the District to Jodi Staebell and Valerie Ringold.

4. Thank you for the opportunity to assist in the preparation of the Review Plan. Please continue to coordinate the Agency Technical Review efforts outlined in the RP with the ECO-PCX.

Enclosure

Jodi Staebell  
 Operational Director,  
 National Ecosystem Planning  
 Center of Expertise

CF:

CEMVD-RB-T (D. Vigh, J. Staebell)  
 CEMVD-PD-N (Smith, Wilbanks)  
 CEPOA-EN-CW-PF (V. Ringold)  
 CESPDPDC (P. Bowers, P. Devitt)  
 CESPDPDS-P (F. Tabatai)  
 CESPA-PM-C (A. Austin-Johnson)  
 CESPA-PM-L (K. Schaeffer, M. Mann)



## Appendix D: E-Team Participants

As described in the main report, a series of workshops were used to facilitate the development of the community-based index model compatible with the HEP application paradigm for the MRGBER feasibility study. Formal minutes were developed for each workshop and can be provided upon request from the Albuquerque District (contact Ondrea Hummel – refer to contact information below). Several federal state and local agencies, as well as local and regional experts from the stakeholder organizations, and private consultants, participated in the model workshops. A complete list of participants can be found in Table D - 1 below. It is important to note that attrition over the course of the study led to many changes in this original roster. We have attempted to include both the names of original participants as well as replacements and additions here as well.

Table D - 1. Model development workshop(s) participants.

E-Team Members	Agency	Phone	Email Address
Abeyta, Cyndie	USFWS	(505) 761-4738	<a href="mailto:cyndie_abeyta@fws.gov">cyndie_abeyta@fws.gov</a>
Anderson, Steve	NMDGF	(505) 841-8881	<a href="mailto:scanderson@state.nm.us">scanderson@state.nm.us</a>
Austin-Johnson, Alicia	USACE	(505) 342-3635	<a href="mailto:Alicia.M.AustinJohnson@usace.army.mil">Alicia.M.AustinJohnson@usace.army.mil</a>
Blake, Fritz	USACE	(505) 342-3202	<a href="mailto:Fritz.J.Blake@usace.army.mil">Fritz.J.Blake@usace.army.mil</a>
Boberg, Steve	USACE	(505) 342-3336	<a href="mailto:Steve.A.Boberg@usace.army.mil">Steve.A.Boberg@usace.army.mil</a>
Branstetter, John	USFWS	(505) 761-4753	<a href="mailto:John_Branstetter@fws.gov">John_Branstetter@fws.gov</a>
Buntjer, Mike	USFWS	(505) 761-4733	<a href="mailto:Mike_Buntjer@fws.gov">Mike_Buntjer@fws.gov</a>
Caplan, Todd	Parametrix	(505) 323-0050	<a href="mailto:tcaplan@parametrix.com">tcaplan@parametrix.com</a>
Coonrod, Julie	UNM	(505) 277-3233	<a href="mailto:jcoonrod@unm.edu">jcoonrod@unm.edu</a>
Crawford, Cliff	UNM	(505) 242-7081	<a href="mailto:ccbosque@juno.com">ccbosque@juno.com</a>
DelloRusso, Gina	USFWS	(505) 835-1828	<a href="mailto:Gina_DelloRusso@fws.gov">Gina_DelloRusso@fws.gov</a>
Doles, Mark	USACE	(505) 342-3364	<a href="mailto:Mark.W.Doles@usace.army.mil">Mark.W.Doles@usace.army.mil</a>
Finch, Debbie	USFS, RMRS	(505) 856-0153	<a href="mailto:dfinch@fs.fed.us">dfinch@fs.fed.us</a>
Giesen, Lynette	USACE	(505) 342-3322	<a href="mailto:Lynette.M.Giesen@usace.army.mil">Lynette.M.Giesen@usace.army.mil</a>
Gonzales, Santiago	USFWS	(505) 761-4720	<a href="mailto:Santiago_Gonzales@fws.gov">Santiago_Gonzales@fws.gov</a>

(Continued)

Table D - 1. (Concluded).

E-Team Members	Agency	Phone	Email Address
Grogan, Sterling	MRGCD	(505) 247-0235	<a href="mailto:grogan@mrgcd.com">grogan@mrgcd.com</a>
Hummel, Ondrea	USACE	(505) 342-3375	Ondrea.C.Linderoth-Hummel@usace.army.mil
Jones, Seth	USACE - Galveston District (Remote Team Member)	(409) 766-3068	Seth.W.Jones@usace.army.mil
Najmi, Yasmeen	MRGCD	(505) 247-0234	yasmeen@mrgcd.dst.nm.us
Pegram, Page	ISC	(505) 764-3890	ppegam@ose.state.nm.us
Schmader, Matt	City of Albuquerque Open Space	(505) 452-5200	Mschmader@cabq.gov
Stretch, Doug	MRGCD	(505) 247-0234	doug@mrgcd.us
Umbreit, Nancy	BOR	(505) 462-3599	numbreit@uc.usbr.gov
Wicklund, Charles	NMSFD	(505) 865-2776	cwicklund@state.nm.us












## Appendix E: HSI Curves for the Bosque Riparian Model



The following curves were developed by the E-Team to measure ecosystem function in the bosque communities found along the Middle Rio Grande Reach running through Albuquerque, New Mexico.<sup>1</sup>





<sup>1</sup> Data are available upon request - contact the District POC (Ondrea Hummel, contact information can be found in [Appendix D](#)).









































## Appendix F

# Useful Field Protocols and Checklists for the Bosque Riparian Model

Several checklists or crosswalks have been included in this appendix to assist the field in the application of the HSI model.

1. For those readers accustomed to the Hink and Omart (1984) vegetative classification system (H&O system), we offer a crosswalk in this appendix between it and the cover typing classification system used in the HSI model (Table F - 2).
2. We provide a list of “desirable” and “undesirable” species that will be needed to record both the indicator and native variables (Table F - 3 and Table F - 4).
3. And finally, we provide direction and diagrams to assist in the measurement of the various vegetative variables for the HSI model (i.e., point-intercept, line-intercept, point-centered quarter).

### H&O Classification System

The “Middle Rio Grande Biological Survey” completed by [Hink and Ohmart](#) in 1984 described the plant communities within the study area’s riparian zone and provided detailed information on species composition and the structure of cover types (Table F - 1.).

Table F - 1. Vegetation structure categories using modified Hink &amp; Ohmart classification.

Structure Type	Dominant Overstory Height (ft)	Overstory Cover (%)	Understory Cover (%)	General Description
1s	>40	>25	25-50	Tall trees with well developed understory
1f	>40	>25	>50	Tall trees with very dense understory
2	>40	>25	<25	Tall trees with little of not understory
3s	20-40	>25	25-50	Intermediate-sized trees with medium understory density
3f	20-40	>25	>50	Intermediate-sized trees with dense understory
4	20-40	>25	<25	Scattered woodlands of intermediate-sized trees
5s	<20	>25	25-50	Shrubs with medium density
5f	<20	>25	>50	Dense shrubby growth
6	<20	<25	<25	Sparse and/or very young shrubs

Six general plant vegetation categories were developed by [Hink and Ohmart \(1984\)](#), based on the height of the vegetation and the make-up of the understory or lower layers:

- Forest Types I & III (untreated only)
- Forest Types II & IV (untreated and treated)
- Shrub Type V (untreated only)
- Dry Meadow Type VI (untreated and treated)
- Wet Meadow Type VI (untreated only)

Armed with this information, Table F - 2 offers a crosswalk between the H&O classification system and the cover type mapping performed for the HSI modeling efforts.

Table F - 2. Crosswalk between the commonly used Hink and Omart vegetative classification system and the Bosque Riparian HSI Model's cover type classification naming conventions

H&O Code	Hink & Omart Description	Scientific Name ( <i>Genus species</i> )	HSI Cover Type
ATX-SS5	Four-wing salt bush-Sand sage, Type 5	<i>Atriplex canescens-Oligosporus filifolius</i>	TYPE 5
ATX-SS6	Four-wing salt bush-Sand sage, Type 6	<i>Atriplex canescens-Oligosporus filifolius</i>	TYPE 6U
B-CW5	Bulrush-Coyoto Willow, Type 5	<i>Scirpus spp.-Salix exigua</i>	TYPE 5
BD6	Broom dalea, Type 6	<i>Dalea scoparia</i>	TYPE 6U
C/A2t	Cottonwood overstory/Atriplex understory, Type 2, treated	<i>Populus fremontii var. wislizenii/Atriplex canescens</i>	TYPE 2T
C/B-A3	Cottonwood/Bulrush-Atriplex, Type 3	<i>Populus fremontii var. wislizenii/Scirpus-Atriplex canescens</i>	TYPE 3
C/C5pt	Cottonwood/Cottonwood, planted and treated	<i>Populus fremontii var. wislizenii</i>	TYPE 5
C/C6bpt	Cottonwood/Cottonwood, burned, planted and treated	<i>Populus fremontii var. wislizenii</i>	TYPE 6T
C/CW1	Cottonwood/Coyote Willow, Type 1	<i>Populus fremontii var. wislizenii/Salix exigua</i>	TYPE 1
C/CW1t	Cottonwood/Coyote Willow, Type 1, treated	<i>Populus fremontii var. wislizenii/Salix exigua</i>	TYPE 2T
C/CW3	Cottonwood/Coyote Willow, Type 3	<i>Populus fremontii var. wislizenii/Salix exigua</i>	TYPE 3
C/CW3S	Cottonwood/Coyote Willow, Type 3, sparse	<i>Populus fremontii var. wislizenii/Salix exigua</i>	TYPE 3
C/CW3t	Cottonwood/Coyote Willow, Type 3, treated	<i>Populus fremontii var. wislizenii/Salix exigua</i>	TYPE 3
C/CW4	Cottonwood/Coyote Willow, Type 4	<i>Populus fremontii var. wislizenii/Salix exigua</i>	TYPE 4U
C/CW-R01	Cottonwood/Coyote Willow-Russian olive, Type 1	<i>Populus fremontii var. wislizenii/Salix exigua-Elaeagnus angustifolia</i>	TYPE 1
C/LC3bpt	Cottonwood overstory/(wolfberry) understory, Type 3	<i>Populus fremontii var. wislizenii/Lycium</i>	TYPE 3
C/MB2t	Cottonwood/Mulberry, Type 2, treated	<i>Populus fremontii var. wislizenii/Morus</i>	TYPE 2T
C/MB2t	Cottonwood/Mulberry, Type 2, treated	<i>Populus fremontii var. wislizenii/Morus</i>	TYPE 2T
C/MB-TW1t	Cottonwood/Mulberry-Tree Willow (Peach-leaf willow or Goodding willow), Type 1, treated	<i>Populus fremontii var. wislizenii/Morus/Salix</i>	TYPE 1
C/NM01	Cottonwood/New Mexico olive, Type 1	<i>Populus fremontii var. wislizenii/Forestiera neomexicana</i>	TYPE 1
C/NM01S	Cottonwood/New Mexico olive, Type 1, sparse	<i>Populus fremontii var. wislizenii/Forestiera neomexicana</i>	TYPE 1
C/NM02t	Cottonwood/New Mexico olive, Type 2, treated	<i>Populus fremontii var. wislizenii/Forestiera neomexicana</i>	TYPE 2T
C/NM03	Cottonwood/New Mexico olive, Type 3,	<i>Populus fremontii var. wislizenii/Forestiera neomexicana</i>	TYPE 3
C/NM03t	Cottonwood/New Mexico olive, Type 3, treated	<i>Populus fremontii var. wislizenii/Forestiera neomexicana</i>	TYPE 3

(Continued)

Table F - 2. (Continued).

H&O Code	Hink & Omart Description	Scientific Name (Genus species)	HSI Cover Type
C/NMO-RO1	Cottonwood/New Mexico olive-Russian olive, Type 1	<i>Populus fremontii</i> var. <i>wislizenii</i> /Forestiera neomexicana-Elaeagnus angustifolia	TYPE 1
C/NMO-SC-RO1	Cottonwood/New Mexico olive-Salt cedar-Russian olive, Type 1	<i>Populus fremontii</i> var. <i>wislizenii</i> /Forestiera neomexicana-Tamarix chinensis-Elaeagnus angustifolia	TYPE 1
C/RO1	Cottonwood/Russian olive, Type 1	<i>Populus fremontii</i> var. <i>wislizenii</i> /Elaeagnus angustifolia	TYPE 1
C/RO15	Cottonwood/Russian olive, Type 15	<i>Populus fremontii</i> var. <i>wislizenii</i> /Elaeagnus angustifolia	TYPE 5
C/RO1F	Cottonwood/Russian olive, Type 1, Flycatcher	<i>Populus fremontii</i> var. <i>wislizenii</i> /Elaeagnus angustifolia	TYPE 1
C/RO1S	Cottonwood/Russian olive, Type 1, sparse	<i>Populus fremontii</i> var. <i>wislizenii</i> /Elaeagnus angustifolia	TYPE 1
C/RO2	Cottonwood/Russian olive, Type 2	<i>Populus fremontii</i> var. <i>wislizenii</i> /Elaeagnus angustifolia	TYPE 2U
C/RO2t	Cottonwood/Russian olive, Type 2, treated	<i>Populus fremontii</i> var. <i>wislizenii</i> /Elaeagnus angustifolia	TYPE 2T
C/RO3	Cottonwood/Russian olive, Type 3	<i>Populus fremontii</i> var. <i>wislizenii</i> /Elaeagnus angustifolia	TYPE 3
C/RO-CW1	Cottonwood/Russian olive-Coyote Willow, Type 1	<i>Populus fremontii</i> var. <i>wislizenii</i> /Elaeagnus angustifolia-Salix exigua	TYPE 1
C/RO-CW3	Cottonwood/Russian olive-Coyote Willow, Type 3	<i>Populus fremontii</i> var. <i>wislizenii</i> /Elaeagnus angustifolia-Salix exigua	TYPE 3
C/RO-NMO-SC1	Cottonwood/Russian olive-New Mexico olive-Salt cedar, Type 1	<i>Populus fremontii</i> var. <i>wislizenii</i> /Elaeagnus angustifolia-Forestiera neomexicana-Tamarix chinensis	TYPE 1
C/RO-SC1	Cottonwood/Russian olive-Salt cedar, Type 1	<i>Populus fremontii</i> var. <i>wislizenii</i> /Elaeagnus angustifolia-Tamarix chinensis	TYPE 1
C/RO-SC3	Cottonwood/Russian olive-Salt cedar, Type 3	<i>Populus fremontii</i> var. <i>wislizenii</i> /Elaeagnus angustifolia-Tamarix chinensis	TYPE 3
C/SC1	Cottonwood/Salt cedar, Type 1	<i>Populus fremontii</i> var. <i>wislizenii</i> /Tamerix chinensis	TYPE 1
C/SC2pt	Cottonwood/Salt cedar, Type 2, planted, treated	<i>Populus fremontii</i> var. <i>wislizenii</i> /Tamerix chinensis	TYPE 2T
C/SC3S	Cottonwood/Salt cedar, Type 3, sparse	<i>Populus fremontii</i> var. <i>wislizenii</i> /Tamerix chinensis	TYPE 3
C/SC4	Cottonwood/Salt cedar, Type 4	<i>Populus fremontii</i> var. <i>wislizenii</i> /Tamerix chinensis	TYPE 4U
C/SC-CW5	Cottonwood/Salt cedar-Coyote Willow, Type 5	<i>Populus fremontii</i> var. <i>wislizenii</i> /Tamerix chinensis-Salix exigua	TYPE 5
C/SC-RO1	Cottonwood/Salt cedar-Russian olive, Type 1	<i>Populus fremontii</i> var. <i>wislizenii</i> /Tamerix chinensis-Elaeagnus angustifolia	TYPE 1
C/SE1	Cottonwood/Siberian elm, Type 1	<i>Populus fremontii</i> var. <i>wislizenii</i> /Ulmus pumila	TYPE 1
C/SE2t	Cottonwood/Siberian elm, Type2, treated	<i>Populus fremontii</i> var. <i>wislizenii</i> /Ulmus pumila	TYPE 2T
C/TH1	Cottonwood/Tree of Heaven, Type 1	<i>Populus fremontii</i> var. <i>wislizenii</i> /Ailanthus altissima	TYPE 1
C/TH-SE2t	Cottonwood/Tree of Heaven-Siberian elm, Type 2, treated	<i>Populus fremontii</i> var. <i>wislizenii</i> /Ailanthus altissima-Ulmus pumila	TYPE 2T

(Continued)

Table F - 2. (Continued).

H&O Code	Hink & Omart Description	Scientific Name (Genus species)	HSI Cover Type
C/TH-SE4t	Cottonwood/Tree of Heaven-Siberian elm, Type 4, treated	<i>Populus fremontii</i> var. <i>wislizenii</i> / <i>Ailanthus altissima</i> - <i>Ulmus pumila</i>	TYPE 4T
C/TW1t	Cottonwood/Peach-leaf willow or Goodding willow, Type 1, treated	<i>Populus fremontii</i> var. <i>wislizenii</i> / <i>Salix gooddingii</i>	TYPE 1
C/TW2t	Cottonwood/Peach-leaf willow or Goodding willow, Type 2, treated	<i>Populus fremontii</i> var. <i>wislizenii</i> / <i>Salix gooddingii</i>	TYPE 2T
C2	Cottonwood, Type 2	<i>Populus fremontii</i> var. <i>wislizenii</i>	TYPE 2U
C2bpt	Cottonwood, Type 2, burned, planted and treated	<i>Populus fremontii</i> var. <i>wislizenii</i>	TYPE 2T
C2p	Cottonwood, Type 2, planted	<i>Populus fremontii</i> var. <i>wislizenii</i>	TYPE 2U
C2pt	Cottonwood, Type 2, planted, treated	<i>Populus fremontii</i> var. <i>wislizenii</i>	TYPE 2T
C2t	Cottonwood, Type 2, treated	<i>Populus fremontii</i> var. <i>wislizenii</i>	TYPE 2T
C4	Cottonwood, Type 4	<i>Populus fremontii</i> var. <i>wislizenii</i>	TYPE 4U
C4bpt	Cottonwood, Type 4, burned, planted and treated	<i>Populus fremontii</i> var. <i>wislizenii</i>	TYPE 4T
C4pt	Cottonwood, Type 4, planted and treated	<i>Populus fremontii</i> var. <i>wislizenii</i>	TYPE 4T
C4t	Cottonwood, Type 4, treated	<i>Populus fremontii</i> var. <i>wislizenii</i>	TYPE 4T
C5Sbpt	Cottonwood, Type 5, sparse, burned, planted and treated	<i>Populus fremontii</i> var. <i>wislizenii</i>	TYPE 5
C5Spt	Cottonwood, Type 5, sparse, planted and treated	<i>Populus fremontii</i> var. <i>wislizenii</i>	TYPE 5
C5St	Cottonwood, Type 5, sparse, treated	<i>Populus fremontii</i> var. <i>wislizenii</i>	TYPE 5
C5t	Cottonwood, Type 5, treated	<i>Populus fremontii</i> var. <i>wislizenii</i>	TYPE 5
C6bpt	Cottonwood, Type 6, burned, planted and treated	<i>Populus fremontii</i> var. <i>wislizenii</i>	TYPE 6T
C-CW5p	Cottonwood-Coyote Willow, Type 5, planted	<i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Salix exigua</i>	TYPE 5
C-MB/MB1t	Cottonwood-Mulberry/Mulberry, type 1, treated	<i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Morus/Morus</i>	TYPE 1
C-R04	Cottonwood-Russian olive, Type 4	<i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Elaeagnus angustifolia</i>	TYPE 4U
C-RO	Cottonwood-Russian olive	<i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Elaeagnus angustifolia</i>	TYPE 5
C-RO/R03	Cottonwood-Russian olive/Russian olive, Type 3	<i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Elaeagnus angustifolia</i> / <i>Elaeagnus angustifolia</i>	TYPE 3
C-R04pt	Cottonwood-Russian olive, Type 4, planted, treated	<i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Elaeagnus angustifolia</i>	TYPE 4T

(Continued)

Table F - 2. (Continued).

H&O Code	Hink & Ormart Description	Scientific Name (Genus species)	HSI Cover Type
C-RO-TW5	Cottonwood-Russian olive-Tree Willow (Peach-leaf willow or Goodding willow), Type 5	<i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Elaeagnus angustifolia</i> / <i>Salix gooddingii</i>	TYPE 5
C-SC/SC1	Cottonwood-Salt cedar/Salt cedar, Type 1	<i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Tamarix L./Tamerix chinensis</i>	TYPE 1
C-SC2	Cottonwood-Salt cedar, Type 2	<i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Tamerix chinensis</i>	TYPE 2U
C-SE/CW3	Cottonwood-Siberian elm/Coyote Willow, Type 3	<i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Ulmus pumila L./Salix exigua</i>	TYPE 3
C-SE/RO1	Cottonwood-Siberian elm/Russian olive, Type 1	<i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Ulmus pumila L./Elaeagnus angustifolia</i>	TYPE 1
C-SE/SC1	Cottonwood-Siberian elm/Salt cedar, Type 1	<i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Ulmus pumila L./Tamerix chinensis</i>	TYPE 1
C-SE/SC2	Cottonwood-Siberian elm/Salt cedar, Type 2	<i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Ulmus pumila L./Tamerix chinensis</i>	TYPE 2U
C-SE/SE2t	Cottonwood-Siberian elm/Siberian elm, Type 2, treated	<i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Ulmus pumila L./Ulmus pumila L.</i>	TYPE 2T
C-SE-TW/SC1	Cottonwood-Siberian elm/Tree Willow (Peach-leaf willow or Goodding willow)/Salt cedar, Type 1	<i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Ulmus pumila L./Salix gooddingii/Tamerix chinensis</i>	TYPE 1
C-TH3	Cottonwood-Tree of Heaven, Type 3	<i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Ailanthus altissima</i>	TYPE 3
C-TW/CW3	Cottonwood-Tree Willow (Peach-leaf willow or Goodding willow)/Coyote Willow, Type 3	<i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Salix gooddingii/Salix exigua</i>	TYPE 3
C-TW/TH2pt	Cottonwood-Tree Willow (Peach-leaf willow or Goodding willow)/Tree of Heaven, Type 2, planted and treated	<i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Salix gooddingii/Ailanthus altissima</i>	TYPE 2T
C-TW4t	Cottonwood-Tree Willow (Peach-leaf willow or Goodding willow), Type 4, treated	<i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Salix gooddingii</i>	TYPE 4T
C-TW5pt	Cottonwood-Tree Willow (Peach-leaf willow or Goodding willow), Type 5, planted and treated	<i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Salix gooddingii</i>	TYPE 5
C-TW6bpt	Cottonwood-Tree Willow (Peach-leaf willow or Goodding willow), Type 6, burned, planted and treated	<i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Salix gooddingii</i>	TYPE 6T
C-TW-SC5bpt	Cottonwood-Tree Willow (Peach-leaf willow or Goodding willow)-Salt cedar, Type 5, burned, planted and treated	<i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Salix gooddingii-Tamerix chinensis</i>	TYPE 5
C-TW-SE2t	Cottonwood-Tree Willow (Peach-leaf willow or Goodding willow)-Siberian elm, Type 2, treated	<i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Salix gooddingii-Populus fremontii</i> var. <i>wislizenii</i>	TYPE 2T
CW5	Coyote Willow, Type 5	<i>Salix exigua</i>	TYPE 5
CW5	Coyote Willow, Type 5	<i>Salix exigua</i>	TYPE 5
CW5bt	Coyote Willow, Type 5, burned, treated	<i>Salix exigua</i>	TYPE 5

(Continued)

Table F - 2. (Continued).

H&O Code	Hink & Ormart Description	Scientific Name ( <i>Genus species</i> )	HSI Cover Type
CW5F	Coyote Willow, Type 5, Flycatcher	<i>Salix exigua</i>	TYPE 5
CW5t	Coyote Willow, Type 5, treated	<i>Salix exigua</i>	TYPE 5
CW6	Coyote Willow, Type 6	<i>Salix exigua</i>	TYPE 6U
CW6C-RO/CW6	Coyote Willow, Type 6, Cottonwood-Russian olive/Coyote Willow, Type 6	<i>Salix exigua</i> , <i>Populus fremontii</i> var. <i>wislizenii</i> - <i>Elaeagnus angustifolia</i> / <i>Salix exigua</i>	TYPE 6U
CW6pt	Coyote Willow, Type 6, planted, treated	<i>Salix exigua</i>	TYPE 6T
CW6S	Coyote Willow, Type 6, sparse	<i>Salix exigua</i>	TYPE 6U
CW6t	Coyote Willow, Type 6, treated	<i>Salix exigua</i>	TYPE 6T
CW-B-CAT6	Coyote Willow-Bulrush-Cattail, Type 6	<i>Salix exigua</i> - <i>Scirpus</i> - <i>Typha</i>	TYPE 6U
CW-C5	Coyote Willow-Cottonwood, Type 5	<i>Salix exigua</i> - <i>Elaeagnus angustifolia</i>	TYPE 5
CW-C6	Coyote Willow-Cottonwood, Type 6	<i>Salix exigua</i> - <i>Elaeagnus angustifolia</i>	TYPE 6U
CW-CAT6	Coyote Willow-Cattail, Type 6	<i>Salix exigua</i> - <i>Typha</i>	TYPE 6U
CW-R05	Coyote Willow-Russian olive, Type 5	<i>Salix exigua</i> - <i>Elaeagnus angustifolia</i>	TYPE 5
CW-R05F	Coyote Willow-Russian olive, Type 5, Flycatcher	<i>Salix exigua</i> - <i>Elaeagnus angustifolia</i>	TYPE 5
CW-R06	Coyote Willow-Russian olive, Type 6	<i>Salix exigua</i> - <i>Elaeagnus angustifolia</i>	TYPE 6U
CW-RO-SC5	Coyote Willow-Russian olive-Salt cedar, Type 5	<i>Salix exigua</i> - <i>Elaeagnus angustifolia</i> - <i>Tamerix chinensis</i>	TYPE 5
CW-SC6	Coyote Willow-Salt cedar, Type 6	<i>Salix exigua</i> - <i>Tamerix chinensis</i>	TYPE 6U
CW-TW5	Coyote Willow-Tree Willow (Peach-leaf willow or Goodding willow), Type 5	<i>Salix exigua</i> - <i>Salix gooddingii</i>	TYPE 5
MB6t	Mulberry, Type 6, treated	<i>Morus</i>	TYPE 6T
MB-SE6t	Mulberry-Siberian elm, Type 6, treated	<i>Morus-Ulmus pumila</i> L	TYPE 6T
MH5	Marsh, Type 5	<i>Morass</i>	TYPE 5
MH5-OW	Marsh, Type 5-Open Water	<i>Morass</i>	TYPE 5
MH6	Marsh, Type 6	<i>Morass</i>	TYPE 6W
NMO-CW5	New Mexico olive-Coyote Willow, Type 5	<i>Forestiera neomexicana</i> - <i>Salix exigua</i>	TYPE 5
NMO-SB5	New Mexico olive-Sandbar, Type 5	<i>Forestiera neomexicana</i> - <i>Salix interior</i>	TYPE 5
OP	Open land		OPENLAND

(Continued)



Table F - 2. (Continued).

H&O Code	Hink & Omart Description	Scientific Name ( <i>Genus species</i> )	HSI Cover Type
OPbpt	Open land, burned, planted and treated		OPENLAND
OPpt	Open land, planted and treated		OPENLAND
OPt	Open land, treated		OPENLAND
OW	Open water		OPENWATER
OWb	Open water, burned		OPENWATER
OW-MH5	Open water-Marsh, Type 5		TYPE 5
RO/CW3	Russian olive/Coyote Willow, Type 3	<i>Elaeagnus angustifolia</i> / <i>Salix exigua</i>	TYPE 3
RO3	Russian olive, Type 3	<i>Elaeagnus angustifolia</i>	TYPE 3
RO5	Russian olive, Type 5	<i>Elaeagnus angustifolia</i>	TYPE 5
RO5b	Russian olive, Type 5, burned	<i>Elaeagnus angustifolia</i>	TYPE 5
RO6	Russian olive, Type 6	<i>Elaeagnus angustifolia</i>	TYPE 6U
RO-C4	Russian olive-Cottonwood, Type 4	<i>Elaeagnus angustifolia</i> - <i>Populus fremontii</i> var. <i>wislizenii</i>	TYPE 4U
RO-C6	Russian olive-Cottonwood, Type 6	<i>Elaeagnus angustifolia</i> - <i>Populus fremontii</i> var. <i>wislizenii</i>	TYPE 6U
RO-CW5	Russian olive-Coyote Willow, Type 5	<i>Elaeagnus angustifolia</i> - <i>Salix exigua</i>	TYPE 5
RO-CW5F	Russian olive-Coyote Willow, Type 5, Flycatcher	<i>Elaeagnus angustifolia</i> - <i>Salix exigua</i>	TYPE 5
RO-CW6	Russian olive-Coyote Willow, Type 6	<i>Elaeagnus angustifolia</i> - <i>Salix exigua</i>	TYPE 6U
RO-SC3	Russian olive-Salt cedar, Type 3	<i>Elaeagnus angustifolia</i> - <i>Tamerix chinensis</i>	TYPE 3
RO-SC5	Russian olive-Salt cedar, Type 5	<i>Elaeagnus angustifolia</i> - <i>Tamerix chinensis</i>	TYPE 5
RO-SE-SC5S	Russian olive-Siberian elm, Salt cedar, Type 5, sparse	<i>Elaeagnus angustifolia</i> - <i>Ulmus pumila</i> - <i>Tamerix chinensis</i>	TYPE 5
SC3	Salt cedar, Type 3	<i>Tamerix chinensis</i>	TYPE 3
SC5	Salt cedar, Type 5	<i>Tamerix chinensis</i>	TYPE 5
SC5F	Salt cedar, Type 5. Flycatcher	<i>Tamerix chinensis</i>	TYPE 5
SC5S	Salt cedar, Type 5, sparse	<i>Tamerix chinensis</i>	TYPE 5
SC5t	Salt cedar, Type 5, treated	<i>Tamerix chinensis</i>	TYPE 5
SC6	Salt cedar, Type 6	<i>Tamerix chinensis</i>	TYPE 6U
SC6S	Salt cedar, Type 6, sparse	<i>Tamerix chinensis</i>	TYPE 6U

(Continued)

Table F - 2. (Continued).

H&O Code	Hink & Omart Description	Scientific Name (Genus species)	HSI Cover Type
SC-C5	Salt cedar-Cottonwood, Type 5	<i>Tamerix chinensis</i> - <i>Populus fremontii</i> var. <i>wislizenii</i>	TYPE 5
SC-C6S	Salt cedar-Cottonwood, Type 6, sparse	<i>Tamerix chinensis</i> - <i>Populus fremontii</i> var. <i>wislizenii</i>	TYPE 6U
SC-CW5	Salt cedar-Coyote Willow, Type 5	<i>Tamerix chinensis</i> - <i>Salix exigua</i>	TYPE 5
SC-CW5pt	Salt cedar-Coyote Willow, Type 5, plant, treated	<i>Tamerix chinensis</i> - <i>Salix exigua</i>	TYPE 5
SC-RO/SC3	Salt cedar-Russian olive/Salt cedar, Type 3	<i>Tamerix chinensis</i> - <i>Elaeagnus angustifolia</i> / <i>Tamerix chinensis</i>	TYPE 3
SC-RO/SC-R03	Salt cedar-Russian olive/Salt cedar-Russian olive, Type 3	<i>Tamerix chinensis</i> - <i>Elaeagnus angustifolia</i> / <i>Tamerix chinensis</i> - <i>Elaeagnus angustifolia</i>	TYPE 3
SC-RO/TW-SE3	Salt cedar/Russian olive-Tree Willow (Peach-leaf willow or Goodding willow)-Siberian elm, Type 3	<i>Tamerix chinensis</i> - <i>Elaeagnus angustifolia</i> / <i>Salix gooddingii</i> - <i>Ulmus pumila</i>	TYPE 3
SC-R05	Salt cedar-Russian olive, Type 5	<i>Tamerix chinensis</i> - <i>Elaeagnus angustifolia</i>	TYPE 5
SC-SE5pt	Salt cedar-Siberian elm, Type 5, plant, treated	<i>Tamerix chinensis</i> - <i>Ulmus pumila</i>	TYPE 5
SE/MB-TH3	Siberian elm/Mulberry-Tree of Heaven, Type 3	<i>Ulmus pumila</i> / <i>Morus</i> - <i>Ailanthus altissima</i>	TYPE 3
SE/SC3	Siberian elm/Salt cedar, Type 3	<i>Ulmus pumila</i> / <i>Tamerix chinensis</i>	TYPE 3
SE1	Siberian elm, Type 1	<i>Ulmus pumila</i>	TYPE 1
SE5bt	Siberian elm, Type 5, burned, treated	<i>Ulmus pumila</i>	TYPE 5
SE-C/SC1	Siberian elm-Cottonwood/Salt cedar, Type 1	<i>Ulmus pumila</i> - <i>Populus fremontii</i> var. <i>wislizenii</i> / <i>Tamerix chinensis</i>	TYPE 1
SE-C1	Siberian elm-Cottonwood, Type 1	<i>Ulmus pumila</i> - <i>Populus fremontii</i> var. <i>wislizenii</i>	TYPE 1
SE-RO/SC-CW5	Siberian elm-Russian olive/Salt cedar-Coyote Willow, Type 5	<i>Ulmus pumila</i> - <i>Elaeagnus angustifolia</i> / <i>Tamerix chinensis</i> - <i>Salix exigua</i>	TYPE 5
SS6t	Sand sage, Type 6, treated	<i>Artemisia filifolia</i>	TYPE 6T
TW5Sbpt	Tree Willow (Peach-leaf willow Goodding willow), Type 5, sparse, burned, planted and treated		TYPE 5
TW-C4	Tree Willow (Peach-leaf willow Goodding willow)-Cottonwood, Type 4		TYPE 4U
TW-SE/CW3	Tree Willow (Peach-leaf willow Goodding willow)-Siberian elm/Coyote Willow, Type 3		TYPE 3
WM	Utility areas not considered "habitat"		UTILITY

## Undesirable vs. Desirable Species Lists

In addition, the E-Team developed a list of “indicator” species to serve as proxies to capture the desired vegetative composition and diversity in a restored bosque ecosystem. Here we offer the list of the undesirable “indicator” species (Table F - 3) as well as the native species of concern (Table F - 4) for Bosque Riparian HSI model applications (variable codes include INDICATFB, INDICATGR, INDICATHB, SPPCOUNT, NATIVETREE, and NATIVESDG).

Table F - 3. List of undesirable indicator species when applying the model.

Life Form	Scientific Name	Common Name	Kartez Symbol	NHNM-ACRO1
Trees	<i>Ailanthus altissima</i>	tree of heaven	AIAL	AIALT
	<i>Elaeagnus angustifolia</i>	Russian olive	ELAN	ELAANG
	<i>Ulmus pumila</i>	Siberian elm	ULPU	ULMPUM
	<i>Tamarix ramosissima</i>	saltcedar	TARA	TAMRAM
Graminoids	<i>Agrostis gigantea</i>	redtop	AGGI2	AGRGIG
	<i>Bromus catharticus</i>	rescuegrass	BRCA6	BROCAT
	<i>Bromus japonicus</i>	Japanese brome	BRJA	BROJAP
	<i>Bromus tectorum</i>	cheatgrass	BRTE	BROTEC
	<i>Cynodon dactylon</i>	bermudagrass	CYDA	CYNDAC
	<i>Hordeum murinum</i>	mouse barley	HOMU	HORMUR
	<i>Saccharum ravennae</i>	ravennagrass	SARA3	SACRAV
	<i>Sorghum halepense</i>	johnsongrass	SOHA	SORHAL
Forbs	<i>Kochia scoparia</i>	common kochia	KOSC	KOCSKO
	<i>Lepidium latifolium</i>	perennial pepperweed	LELA2	LEPLAT
	<i>Salsola tragus</i>	prickly Russian thistle	SATR12	SALTRA
	<i>Aster spp.</i>	dandelion		
	<i>Solidago spp.</i>	Solidago		
	<i>Salsola kalii</i>	tumbleweed	SAKA	SALKAL
	<i>Cardaria draba (L.) Desv.</i>	Hoary cress		
	<i>Alhagi pseudalhagi (Bieb) Desv.</i>	camelthorn		
	<i>Euphorbia esula L.</i>	leafy spurge		
	<i>Peganum harmala L.</i>	African rue		
	<i>Centaurea maculosa Lam.</i>	spotted knapweed		
	<i>Centaurea solstitialis L.</i>	yellow starthistle		
<i>Carduus natuans L.</i>	musk thistle			

Table F - 4. List of native indicator species when applying the model.

Life Form	Scientific Name	Common Name	Kartez Symbol	NHNM-ACRO1
Trees	<i>Populus deltoides ssp. wislizeni</i>	Rio Grande cottonwood	PODEW	POPDELW
	<i>Salix gooddingii</i>	Goodding's willow	SAGO	SALGOO
Shrubs	<i>Amorpha fruticosa</i>	desert indigobush	AMFR	AMOFRU
	<i>Forestiera pubescens</i>	New Mexico olive	FOPU2	FORPUB
	<i>Salix exigua</i>	coyote willow	SAEX	SALEXI
	<i>Baccharis spp</i>	baccharis		
	<i>Ribes aureum</i>	golden currant		
	<i>Rhus sp</i>	sumac		
	<i>Lycium torii</i>	wolfberry		
	<i>Shepherdia argentea</i>	silver buffalo berry		
Graminoids	<i>Carex spp.</i>	sedge	CAREX	CAREX
	<i>Cyperus spp.</i>	flatsedge	CYPER	CYPERU
	<i>Juncus spp.</i>	Rush	JUNCU	JUNCUS
	<i>Muhlenbergia asperifolia</i>	alkali muhly	MUAS	MUHASP
	<i>Oryzopsis hymenoides</i>	Indian ricegrass	ORHY	ORYHYM
	<i>Panicum spp.</i>	panicgrass	PANIC	PANICU
	<i>Sorghastrum nutans</i>	Indiangrass	SONU2	SORNUT
Forbs	<i>Anemopsis californica</i>	yerba mansa	ANCA10	ANECAL

## Field Sampling Protocols and Diagrams

Three specific protocols were used to measure the vegetative conditions on the reference sites for the MRGBER study: 1) point-intercept, 2) line-intercept, and 3) point-centered quarter. Below we illustrate their methodology with the hope that our techniques can be repeated by future users for various reasons (i.e., to perform validation of the model; facilitate a monitoring program using the HSI model; apply the model elsewhere, etc.).

## Point-Intercept

Point-intercept<sup>1</sup> was used to measure the numerous herbaceous canopy cover parameters (CANFORB, CANGRASS, CANHERB, CANSEEDGE), and was calculated by dividing the number of “hits” on a plant by the total number of sample points taken along the transect. Narrow points (e.g. a nail on the bottom of a wooden dowel) were vertically lowered through a frame (e.g. a camera tripod) at pre-determined intervals along the transects (in this case, every 2-meters). As the pin moved towards the ground, every plant that made contact with the pin was recorded as a “canopy hit” (as opposed to a “basal hit”, described below in the ground cover section above). A canopy “hit” included any pin contact with a plant leaf, stem or flower (Figure F - 1).




Figure F - 1. Illustration of the point-intercept method used to record aerial herbaceous plant cover for the MRGBER study.

In the example, the observer would record “grass” as a canopy “hit” and “soil” as a ground cover “hit” (*COVGRND* and *CTGRNDCOV*) at **Sample Point A**. For **Sample Point B**, there would be no aerial “hit” recorded, but the ground cover “hit” would be recorded as “litter.” For **Sample Point C**, both the aerial and the ground cover “hits” would be

<sup>1</sup> While all methods for estimating plant cover have their advantages and disadvantages, points were considered the most objective way to estimate plant cover (Bonham 1989) and for herbaceous plants, is considered more precise and efficient than estimating aerial cover with quadrats (Bonham 1989; Chambers & Brown 1983; Elzinga et. al. 1998; Floyd and Anderson 1987).

recorded as “grass.” To increase efficiency and considering the project goals, the field team only recorded canopy hits according to plant life-form (i.e., grass, forb, sedge, or rush). The only exception to this rule will be if the pin made contact with a highly desirable or undesirable plant species (“indicator species”) (i.e., *INDICATFB*, *INDICATGR*, *INDICATHB*, and *NATIVESDG*). In those instances, the species must be identified along with the “hit”.

### Line-Intercept

The line-intercept method proved to be a fast and efficient way to estimate shrub canopy cover (*CANSHRUB*) over large areas of the study. The line-intercept method run using the existing cross transects. Any shrub crowns that overlapped or intercepted the transect line was recorded (by species) (Figure F - 2).




Figure F - 2. Illustration of the line-intercept method used to record shrub cover for the MRGBER study.

The beginning and end of where the canopy overhung the tape was recorded and later converted to percent cover. A pole with a level/optical sighting device was used, when necessary, to reduce observer bias for

determining if a shrub was “in”, and for determining the starting and ending points along the tape.<sup>1</sup>

### **Point-Centered Quarter**

The point-centered quarter method was known to be a frequently used distance methods to sample forest communities (Bonham 1989; Cottam & Curtis 1956; Elzinga et al. 1998; Krebs 1999). After a sampling point along a transect was located (in this case, at the end of each cross arm), the area around those points was split into four 90° quadrants (quarters) and the distance to the nearest tree and root-sprout in each quarter was estimated with an optical rangefinder (*DISTBIGTR*) (Figure F - 3).

---

<sup>1</sup> Information taken from <http://ag.arizona.edu/AREC/pubs/rmg/1%20orangelandmanagement/5%20monitorangebrowseveg93.pdf> (SEPTEMBER 2008) and diagram taken from <http://en.wikipedia.org/wiki/Image:LiTrSa42008Geelhoed.svg> (SEPTEMBER 2008).






Figure F - 3. Illustration of point-centered quarter method used to record tree and root-sprout density and size.

The tree species was recorded and basal stem diameter of trees (not root-sprouts) was measured with calipers or a dbh tape and recorded on the data sheet as well. Double counting was not allowed. To avoid the potential problem of double counting, the measurements were only recorded at the terminus of each cross arm, and a maximum distance of 20-m was applied for recording a tree in any PCQ quadrant. [Krebs \(1999\)](#) stressed the importance of accurately dividing each sampling point into four even quadrants. We used a compass with the optical rangefinder while standing at the sample point to ensure that a tree or root-sprout was actually in the quadrant of interest before recording it on the data sheet. In those instances where no tree within 20-m in a particular quadrant was found, the team recorded a “>20-m” value on the data sheet. Equations for calculating density and basal area using PCQ are described in [Krebs \(1999\)](#).



## Appendix G: Model Review Forms and Comments

ERDC-EL used technical experts both within the laboratory itself, and outside the facility (but still within the USACE planning community) to perform a review of both the model development process and the model itself. To assure fair and impartial review of the products, members of the Laboratory-based Technical Review Team (LTRT) were chosen on the basis of expertise, seniority in the laboratory chain of command, and USACE planning experience.

The following were members of the LTRT:

1. Dr. Andrew Casper (ERDC-EL) – technical (peer) reviewer,
2. Ms. Kristine Nemeč (Kansas City District) – technical (peer) reviewer,
3. Janean Shirley – editorial review (Technical Editor),
4. Ms. Antisa Webb - management review (Branch Chief),
5. Dr. Edmond J. Russo – management review (Division Chief),
6. Dr. Steve Ashby – program review (System-wide Water Resources Research Program, Program Manager),
7. Dr. Al Cofrancesco – program review (Technical Director), and
8. Dr. Mike Passmore – executive office review (Environmental Laboratory Deputy Director).

No peer review members of the LTRT were directly associated with the development or application of the model(s) for this study, thus assuring independent technical peer review.<sup>1</sup> Referred to as the in-house Laboratory-based Technical Review (LTR), these experts were asked to consider the following issues when reviewing this document:

1. Whether the concepts, assumptions, features, methods, analyses, and details were appropriate and fully coordinated;

---

<sup>1</sup> Resumes for Dr. Casper and Ms. Nemeč (i.e., the technical peer reviewers) can be found immediately following the comment/response tables at the end of this appendix.

2. Whether the analytic methods used were environmentally sound, appropriate, reasonable, fall within policy guidelines, and yielded reliable results;
3. Whether any deviations from USACE policy and guidance were identified, documented, and approved;
4. Whether the products met the Environmental Laboratory's standards based on format and presentation; and
5. Whether the products met the customer's needs and expectations.

Review comments were submitted to the Laboratory-based Project Delivery Team (LPDT) in written format and the LPDT responded in kind (Table G - 1). In the EL Electronic Manuscript Review System (ELEMRS) 2.0, both reviewers indicated that the document was "Acceptable" with grammatical/formatting modifications needed, and when asked to offer their opinion as to the production of the report they stated that it was a, "quality study, well designed and presented [with] important new information."

Table G - 1. Review comments.

Review Comments				
<b>Project:</b>		A Bosque Riparian Community Index Model for the Middle Rio Grande, Albuquerque, New Mexico		
		<b>Review Focus:</b> Model Documentation – Completeness, Scientific Basis (Editorial comments accepted as well)		
Reviewer	Page/ Para	Chapter	Reviewer Comments	Response
Kristine Nemec	Pg. 76 Table 4	4	(Wagner 2004), Jacob, Moulton and Lopez 2004) missing reference	Concur and rectified.
	Pg. 80 Table 4	4	Stamps 1991 missing reference	Concur and rectified
	Pg. 104	Table 10	Explain why some cells are shaded black	Concur and explanation incorporated into table footnote.
		References	Missing or references included that were not cited in text.	Concur and rectified
	Throughout doc	NA	Grammar and spelling suggestions made in track changes format	Concur and incorporated.
	Pg. 6	1	The Middle Rio Grande study documentation identified and recommended effective, affordable and environmentally sensitive ecosystem restoration features throughout the middle reach of the Rio Grande system. Should you add the 905(b) or quote the problem statement?	Do not concur – the reader must turn to the feasibility documentation to investigate study goals and objectives. The purpose of this report is to document the model – not it’s use.
	Pg. 7 Para 1		Do you think a definition of function is necessary	Concur – a definition of function has been incorporated into the text and added to the glossary.
	Pg. 7 Para 2		baseline - Should you use planner speak - inventory or FWOP?	Do not concur – the syntax in the model documentation follows standard USACE planning paradigm. As such, baseline is not the future without-project condition, nor is it wholly equal to the term inventory. An inventory can include more than the baseline condition per the model. The Without project-condition describes changes into the future from the baseline condition under a “No Action” scenario.

(Continued)

Table G - 1. (Continued).

Review Comments				
Project:		A Bosque Riparian Community Index Model for the Middle Rio Grande, Albuquerque, New Mexico		Review Focus: Model Documentation – Completeness, Scientific Basis (Editorial comments accepted as well)
Reviewer	Page/ Para	Chapter	Reviewer Comments	Response
Kristine Nemec	Pg. 8 Para 2		In May of 2005, the PMIP developed Engineering Circular (EC) 1105-2-407, Planning Models Improvement Program: Model Certification (USACE 2005).	No – documents cited in this section are current.
	Pg. 9 Para 4	1	developed - And certified? Or state that certification is not needed	The HEAT software has been recommended for certification, but has not been certified as of December 2009. ERDC-EL is incorporating reviewer changes to the User Guide, and will be submitting the software for certification to USACE-Headquarters soon.
	Pg. 15 # 5	2	Conduct field sampling - Can it also be done with pre-existing GIS files	Although it could be done with pre-existing GIS data to some extent, it was not handled in this manner, and any change from this protocol would necessitate an external peer review (i.e., review via model certification protocols). As such, this issue was not addressed in the document.
	Pg. 21 Figure 1	3	<b>Figure 1</b> I can't tell what the right figure # is this should be 5? (the next is Figure 6	Concur and rectified.
	Pg. 23 Para 1	3	Subsequent iterative refinement of these models led to the identification of contributing ecosystem components, and a description of associated variables (with suggested sampling protocols) that can be used to measure ecosystem restoration benefits. Citation? Is his sentence needed	Do not concur – this sentence if absolutely necessary, and original. Therefore no citations are necessary.

(Continued)

Table G - 1. (Continued).

Review Comments				
Project:		A Bosque Riparian Community Index Model for the Middle Rio Grande, Albuquerque, New Mexico		Review Focus: Model Documentation – Completeness, Scientific Basis (Editorial comments accepted as well)
Reviewer	Page/ Para	Chapter	Reviewer Comments	Response
Andy Casper	Pg. 28 Para 1 (heading)	3	Climatic Characterization - Citations? Maybe 'Dahm, C.M., Edwards, R.J. and F.P. Gelwick. 2005. The Gulf Coast Rivers of the Southwestern United States. Chapter 5. In: The Rivers of North America . Benke, A.C. and C. E. Cushing (eds.). Academic Press, Inc.	Do not concur - Citations unnecessary as this information was taken from the internet and weather citations provided therein.
	Pg. 37 Para 2	3	It should be noted, - It is unclear what the significance is? Does this add/subtract one of the categories? Affect them some other way?	Do not concur – significance is provided at the end of the paragraph.
	Pg. 39 Para 1	3	Clearing activities have greatly reduced the acreage of Type I, III, and V woodlands. Recently-created Type II stands are largely devoid of understory vegetation - Significance to the model is not clear	Do not concur – significance is provided at the end of the paragraph.
<i>(Continued)</i>				

Table G - 1. (Concluded).

Review Comments				
Project:		A Bosque Riparian Community Index Model for the Middle Rio Grande, Albuquerque, New Mexico		Review Focus: Model Documentation – Completeness, Scientific Basis (Editorial comments accepted as well)
Reviewer	Page/ Para	Chapter	Reviewer Comments	Response
Andy Casper	Pg. 39 & 40 Last & first para	3	Because the “treated” habitats were significantly different in terms of vegetative cover, infiltration, etc., from the “untreated” cover types in the region, the E-Team made a decision to capture these differences by dividing several of the Hink and Omart categories (namely Types II, IV, and VI) into “Treated” and “Untreated” classifications (designated by “U’s”) to better capture the degraded habitat conditions in “fire managed” areas within the study boundary . . . “ – Ah here it is! Maybe add an intro sentence to the first paragraph in this section that says something like ‘The prevalence of fire in the riparian community can have a strong impact on the six categories.’ So the reader knows why they are reading about fire in a water project	Do not concur – significance is provided at the end of the paragraph.
	Pg. 40 Para 2	3	Open areas not associated with the model have been mapped, and offer potential areas of restoration and rehabilitation within the study area. I am confused , if it is not part of the accounting the model, it is per force not part of the restoration – why even bring it up if it doesn’t affect the project somehow.	Do not concur - Although this is an application question, the point of this statement is that unassociated habitats CANNOT be assessed with the model, and yet a full accounting of landuse/landcover classifications must be completed in order to balance the books. Unassociated habitat <u>can be</u> enhanced/restored in such a manner that the conversion allows for model assessment.
	Pg. 87 Table 5	4	Need protocol from Ondrea	Concur and rectified.





# US Army Corps of Engineers



## Professional Experience

Research Biologist, Aquatic Ecology and Invasive Species Branch, Engineer Research and Development Center, Environmental Laboratory, Vicksburg, MS., 2006 to present.

- Specializing in large river science, engineering and ecology spanning the continent from Gulf Coast rivers and estuaries to the Ohio and Mississippi River Valley's to the arctic Mackenzie River Delta and Beaufort Sea in Canada
- Development of conceptual, physical habitat, and watershed models
- Modeling climate change and land use impacts/responses
- Assessment of dam removal and ecological restoration
- Food web and community ecology techniques for fish and invertebrates in large navigable rivers and flood plains
- GIS-based, 2-D water quality mapping in tidal creeks/coastal rivers

## Education

- Ph.D. Oceanography, 2005, Université Laval, Québec City, QC.
- M.S. Biological Sciences, 1993 Southern Illinois University Carbondale.
- B.S. Natural Sciences, 1990 Southern Illinois University Carbondale

## Research & Teaching

- A.F. Casper and C. Fischenich. Framework and Integration of Conceptual Models in the CoE Planning Process (System Wide Water Resource Program Environmental Benefits Analysis Program, USACE HQ).
- Brasfield, S., A.F. Casper and B. S. Payne. Potential Contribution of Climate Change to the Bioassessment of Contaminants on Military Installations: Additive, Synergistic or Antagonistic? (USACE ERDC Basic Research Program).
- K. J. Killgore, J. J. Hoover, D. R. Johnson, and A. F. Casper. Envirofish: A HEC compatible floodplain habitat model for evaluating mitigation scenarios (reimbursable project for D. R. Johnson, Mississippi Valley District).

## Other Professional Activities

- Ecosystem restoration/mitigation
- Sensitivity analysis and incorporation of risk/uncertainty
- Forecasting effects of scenarios and plan formulations
- Project/Watershed cumulative impacts assessments
- Coordinate field collections, management, analysis and reporting for river ecology
- SOW proposal and budget writing for multi-year research projects (NSF, EPA, USACE)

## Dr. Andrew F. Casper



Research Biologist - ERDC, Environmental Laboratory  
3909 Halls Ferry Rd., Vicksburg, MS 39180  
601-634-4661

[Andrew.F.Casper@usace.army.mil](mailto:Andrew.F.Casper@usace.army.mil)

## Selected Publications & Conference Presentations

- Casper, R. A. Efoymson, S. M. Davis, G. Steyer, and B. Zettle. 2009. Improving Conceptual Model Development: Avoiding Underperformance Due to Project. U.S. Army Engineer Research and Development Center, Vicksburg, MS.
- Casper A. F., and J. H. Thorp. 2007. Diel and lateral patterns of zooplankton distribution in the St. Lawrence River. *Rivers Research and Application* 23(1):73-85.
- Casper, A. F., J. H. Thorp, S. P. Davies, and D. L. Courtemanch. 2006. Ecological responses of large river benthos to the removal of the Edwards Dam on Kennebec River, Maine (USA). *Archiv für Hydrobiologie* 16(4):541-555 (Large River Supplement 115).
- June 2008 - A surrogate model for future regional climate change: The current affects of the Atlantic Multidecadal Oscillation and its influence on the ecohydrology of Great Lakes and New England rivers. 56th Annual North American Benthological Society International Conference, Salt Lake City, Utah.
- July 2007 - Linking ecological responses to hydrologic characteristics of rivers: Examples from studies of dam removals and PHABSIM modeling for minimum flow standards. US Army Corps of Engineers Waterways Experiment Station, Vicksburg MS.
- A. F. Casper, B. Dixon, E. Steinnle, J. Gore, P. Coble, and R. Conny. Water quality sampling strategies for monitoring coastal rivers & estuaries: Applying technological innovations to Tampa Bay tributaries. Awarded by USEPA (Oct 2006 - Dec 2007).
- Carrabetta, M., A. F. Casper, B. Chernoff, and M. Daniels. The ecological and physical effects of removal of two low-head dams on Eight Mile Creek, a tributary of the Connecticut River. Awarded by TNC/NOAA Community Restoration Program (2005-07).

September 2009



## Missouri River Cottonwood Management Plan

**Professional Experience**  
Environmental Resources Specialist, U.S. Army Corps of Engineers, Omaha District,  
December 2002 to present

- Prepare environmental assessments required under the National Environmental Policy Act for shallow water habitat and emergent sandbar habitat projects along the Missouri River
- Designed planting specifications for riparian forest restorations in South Sioux City, Nebraska; Sioux Falls, South Dakota; and Lower Brule Sioux Reservation, South Dakota
- Served on the South Dakota Bald Eagle Management Team, 2003-05
- Developed environmental sections of water plan updates for Gavins Point and Oahe projects in South Dakota

**Education**

- **Ph.D.**, In progress  
University of Nebraska at Lincoln, Lincoln, NE
- **M.S.**, Biology, 2003  
University of Nebraska at Omaha, Omaha, NE
- **B.S.**, Environmental Studies, 1999  
University of Nebraska at Omaha, Omaha, NE  
*Summa Cum Laude*. University Honors Program

**Research & Teaching**

- Restoration ecology, agroecology, and ecological resilience
- Conducted fieldwork during the summer for research projects in forest, wetland, and grassland ecosystems in Nebraska, 1995 to present
- Taught undergraduate and graduate students in Ecology, Biology I, and Biology II labs at the University of Nebraska at Omaha

**Awards/Honors**

- J. E. Weaver Competitive Grant. The Nature Conservancy, 2009
- Center for Great Plains Studies Grant. Center for Great Plains Studies, 2008
- Contributed two articles to a newspaper series on Platte River water issues which received the Nebraska Wildlife Federation's Conservation Communicator award, 2006 and the Renewable Natural Resources Foundation's national Excellence in Journalism award, 2007

**Kristine T. Nemeč**



USACE - Omaha District  
1616 Capitol Avenue  
Omaha, NE 68102  
402-995-2685  
[Kristine.t.nemec@usace.army.mil](mailto:Kristine.t.nemec@usace.army.mil)

**Selected Publications & Conference Presentations**

Nemeč, K. T., C. R. Allen, A. Alai, G. Clements, A. Kessler, T. Kinsell, A. Major, and B. J. Stephen. Woody invasions of urban parks and trails and the changing face of urban forests in the Great Plains, USA. (Submitted for publication, *Biological Invasions*).

Invited speaker for cottonwood panel discussion sponsored by the Izaak Walton League, Sioux City, Iowa, 2008.

Presented poster entitled "Lower Brule Shoreline Protection and Cottonwood Habitat Enhancement Project, Lake Sharpe, South Dakota" at the Second National Conference on Ecosystem Restoration, Kansas City, Missouri, 2007.

Delivered presentation entitled "Cottonwood Community Delineation" at the Corps of Engineers Wildlife Workshop, Omaha, Nebraska, 2006.

Presented poster entitled "Cottonwood Management and Regeneration along the Missouri River" at the First National Conference on Ecosystem Restoration, Orlando, Florida, 2004.

**Other Professional Activities**

- Society for Ecological Restoration
- Ecological Society of America
- Nebraska Native Plant Society
- Association for Women in Science

September 2009

The documentation is now in senior staff and program management review. Two technology transfer forms will be completed when the document has been reviewed approved by both the senior staff and the program managers (Table G - 2 and Table G - 3).

Table G - 2. Internal ERDC-EL Technology Transfer Review Form.

<b>TECHNOLOGY TRANSFER STATUS SHEET</b>	
<b>INSTRUCTIONS</b> The author(s) of a document based on ERDC-EL research and written for publication or presentation should attach one copy of this sheet to the document when the first draft is prepared. Documents include reports, abstracts, journal articles, and selected proposals and progress reports. The sheet will remain with the most recent draft of the document.	
<b>JOB NUMBERS:</b> a. <b>WORD PROCESSING SECTION</b> _____ b. <b>ENVIRONMENTAL INFORMATION ANALYSIS CENTER</b> _____ c. <b>VISUAL PRODUCTION CENTER</b> _____	
2. TITLE	3. AUTHOR(S)
4. PRESENTATION (Conference Name & Date)	5. PUBLICATION (TR, IR, MP, Journal Name, etc.)
6. SPONSOR OR PROGRAM WORK UNIT	7. DATE REQUIRED BY SPONSOR
8. DATE DRAFT COMPLETED BY AUTHOR(S) AND AREADY FOR SECURITY OR TECHNICAL REVIEW	
9. SECURITY REVIEW (Military Projects)  a. THIS DOCUMENT HAS BEEN REVIEWED FOR SECURITY CLASSIFICATION FOLLOWING GUIDELINES SPECIFIED IN AR 380-5, DEPARTMENT OF THE ARMY INFORMAITON SECURITY PROGRAM, AND FOUND TO BE:  CLASSIFIED _____ CONFIDENTIAL _____ SECRET _____ TOP SECRET _____ UNCLASSIFIED _____ SENSITIVE _____ DISTRIBUTION LIMITED _____  CLASSIFICATION WAS BASED ON THE _____ SECURITY CLASSIFICATION GUIDE DATED _____	
10. AUTHOR	11. DATE
12. GROUP/DIVISION CHIEF	13. DATE
14. IN-HOUSE TECHNICAL REVIEW (To be completed by two or more reviewers who are GS-12 or Above, Expert, or Contractor) a. _____ DATE TO REVIEWER DATE RETURN REQUESTED DATE RETURNED TECHNICAL REVIEWER _____ ACCEPTABLE W/MINOR REVISIONS _____ ACCEPTABLE W/MAJOR REVISIONS _____ UNACCEPTABLE  b. _____ DATE TO REVIEWER DATE RETURN REQUESTED DATE RETURNED TECHNICAL REVIEWER _____ ACCEPTABLE W/MINOR REVISIONS _____ ACCEPTABLE W/MAJOR REVISIONS _____ UNACCEPTABLE  c. _____ DATE TO REVIEWER DATE RETURN REQUESTED DATE RETURNED TECHNICAL REVIEWER _____ ACCEPTABLE W/MINOR REVISIONS _____ ACCEPTABLE W/MAJOR REVISIONS _____ UNACCEPTABLE  NOTE: RETURN TO AUTHOR WHEN TECHNICAL REVIEW IS COMPELTED.	

15. SUPERVISORY REVIEW

THE DOCUMENT IS TECHNICALLY SUITABLE AND REVIEWERS' COMMENTS HAVE BEEN ACKNOWLEDGED. IT IS SUBMITTED FOR EDITORIAL REVIEW AND CLEARANCE FOR PUBLICATION OR PRESENTATION AS INDICATED. THE DOCUMENT CONTAINS NO COPYRIGHTED INFORMATION.\* ENG FORM 4329-R OR 4330-R HAS BEEN COMPLETED, IF REQUIRED, AND IS ATTACHED TO THE DOCUMENT.

a. \_\_\_\_\_  
DATE TO GROUP CHIEF DATE RETURN REQUESTED DATE RETURNED GROUP CHIEF

b. \_\_\_\_\_  
DATE TO DIVISION CHIEF DATE RETURN REQUESTED DATE RETURNED DIVISION CHIEF

16. PROGRAM MANAGER REVIEW (If Appropriate)

\_\_\_\_\_  
DATE TO PROGRAM MANAGER DATE RETURN REQUESTED DATE RETURNED PROGRAM MANAGER

17. COMPLETE THE FOLLOWING FOR ALL REPORTS

a. RECOMMEND TYPE OF REPORTS (TR, IR, MP, Or Other):

\_\_\_\_\_

b. LEVEL OF EDITING (Type 1, 2, 3, Or 4):

\_\_\_\_\_

c. IF TYPE 1 OR 2 EDITING IS INDICATED, ADD A BRIEF JUSTIFICATION:

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_  
SIGNATURE OF DIVISION CHIEF

\*IF COPYRIGHTED MATERIAL IS USED, STRIKE WORD NO. SOURCE OF COPYRIGHTED MEATERIAL SHOULD BE ACKNOWLEDGED IN THE TEXT. IT IS THE AUTHOR'S RESPONSIBILITY TO OBTAIN WRITTEN PERMISSION FROM THE PUBLISHER TO USED COPYRIGHTED MATERIAL (SEE CURRENT INSTRUCTION REPORT ON PREPARING TECHNICAL INFORMATION REPORTS FOR FORM LETTER). CORRESPONDENCE ON RELEASE OF THE MATERIAL MST BE SUBMITTED WITH A REPORT WHEN IT GOES TO THE VISUAL PRODUCTION CENTER FOR PUBLICATION.

Table G - 3. Security Clearance Form for ERDC-EL reports.

REQUEST FOR CLEARANCE OF MATERIAL CONCERNING CIVIL WORKS FUNCTIONS OF THE CORPS (ER 360-1-1)		
THRU	TO CDR, USACE CEPA-ZM WASH, DC 20314-1000	FROM
1. TITLE OF PAPER		
2. AUTHOR (NAME)	3. OFFICIAL TITLE AND/OR MILITARY RANK	
4. THIS PAPER IS SUBMITTED FOR CLEARANCE PRIOR TO PRESENTATION OR PUBLICATION AS IT FALLS INTO THE CATEGORY (OR CATEGORIES) CHECKED BELOW:		
<input type="checkbox"/> MATERIAL THAT AFFECTS THE NATIONAL MISSION OF THE CORPS.  <input type="checkbox"/> RELATES TO CONTROVERSIAL ISSUES.	<input type="checkbox"/> MATERIAL IS SIGNIFICANTLY WITHIN THE PURVIEW OF OTHER AGENCIES OF THE FEDERAL GOVERNMENT.  <input type="checkbox"/> PERTAINS TO MATTERS IN LITIGATION.	
5. CHECK APPLICABLE STATEMENT: <input type="checkbox"/> COPYRIGHTED MATERIAL USED. <span style="float: right;"><input type="checkbox"/> COPYRIGHTED MATERIAL USED HAS BEEN PREVIOUSLY CLEARED IN ACCORDANCE WITH AR 25-30 AND A COPY OF THE CLEARANCE ATTACHED.</span>		
6. FOR PRESENTATION TO:  ORGANIZATION:  CITY AND STATE:		
7. DATE OF FUNCTION	8. DATE CLEARED PAPER IS REQUIRED	
9. FOR PUBLICATION (Name of Publication Media)	10. DATE CLEARED PAPER IS REQUIRED	
THIS PAPER CONTAINS NO CLASSIFIED ORIGINAL OR DERIVATIVE MATERIAL.		
DATE	NAME AND TITLE (Approving Authority)	SIGNATURE (Approving Authority)
THRU	TO	FROM CDR, USACE CEPA-ZM WASH, DC 20314-1000
1. SUBJECT MANUSCRIPT IS CLEARED FOR PRESENTATION AND PUBLICATION:		
<input type="checkbox"/> WITHOUT CHANGE	<input type="checkbox"/> WITH CHANGES ANNOTATED ON THE MANUSCRIPT	<input type="checkbox"/> WITH SUGGESTED CHANGES AND/OR COMMENTS ATTACHED
2. RETURNED WITHOUT CLEARANCE FOR THE FOLLOWING REASON(S):		
DATE	NAME AND TITLE (Approving Authority)	SIGNATURE (Approving Authority)



## INSTRUCTIONS FOR SUBMISSION OF MATERIAL FOR CLEARANCE (ENG Form 4239-R)

1. An original and two copies of papers or material on civil works functions or other non-military matters requiring HQUSACE approval, will be forwarded to reach HQUSACE at least 15 days before clearance is required. Including any maps, pictures and drawings, etc., referred to in the text.
2. Technical papers containing unpublished data and information obtained by the author in connection with his/her official duties will contain the following acknowledgement when released for publication outside the US Army Corps of Engineers. The acknowledgement will identify the research program which provided resources for the paper, the agency directing the program and a statement that publication is by permission of the Chief of Engineers.

The tests described and the resulting data presented herein, unless otherwise noted, were obtained from research conducted under the \_\_\_\_\_ of (Program) the United States Army Corps of Engineers by the \_\_\_\_\_. Permission was granted by (Agency) the Chief of Engineers to publish this information.

3. When manuscripts are submitted for publication in THE MILITARY ENGINEER, a brief biographical sketch (100 to 150 words) of the author is required, indicating his/her background in the subject matter.

## Certificate of Product Check

This certifies that adequate review was provided by all appropriate disciplines to verify the following:

1. Correct application of methods;
2. Adequacy of basic data and assumptions;
3. Completeness of documentation;
4. Compliance with guidance, standards, regulations, and laws; and
5. Correct study approach.

---

Kelly A. Burks-Copes  
Principal Investigator  
Environmental Laboratory  
U.S. Army Engineer Research and Development Center  
Vicksburg, MS

Date