90+ in the United States: 2006-2008

American Community Survey Reports

Issued November 2011

ACS-17

By Wan He and Mark N. Muenchrath



Acknowledgments

This report was prepared by **Wan He** and **Mark N. Muenchrath** under the general direction of **Peter O. Way**, Assistant Division Chief, International Programs Center for Demographic and Economic Studies, Population Division. **Enrique J. Lamas**, Chief, Population Division, provided overall direction. Additional direction was provided by **Loraine A. West**, Acting Chief, Aging Studies Branch (ASB), Population Division.

The authors are grateful to many people both within and outside the Census Bureau who have generously provided insights and assistance to the making of this report. The authors give special thanks to **Mary Beth Kennedy**, ASB, for verifying various materials; **David A. Raglin**, Special Studies Staff, American Community Survey Office, for technical guidance in calculating estimates and margins of error using replicate weighting; Marc J. Perry, Thomas Fischetti, **Geoffrey Hatchard**, and **Steven G. Wilson**, Population Distribution Branch, Population Division, for creating the maps and the scatter plot in this report; Sirius C. Fuller, ACS Variance Estimation and Statistical Support Branch, Decennial Statistics Studies Division, and **Luke J. Larsen**, Foreign-Born Population Branch, Population Division, for data analysis assistance; and J. Gregory Robinson, Estimates and Projections, Population Division, for guidance in evaluating sampling and nonsampling error. Among the many people who provided information on a wide range of topics are **Matthew** W. Brault, Katherine Giefer, and Kirby Posey, Social, Economic and Housing Statistics Division; and Lynn Fisher and Arthur Kahn, Social Security Administration.

Reviewers from Census Bureau's Population Division and National Institute on Aging (NIA) provided valuable comments and suggestions, Dana A. Glei, Karen Humes, Marlene A. Lee, Amy S. Smith, and Victoria A. Velkoff. The authors are particularly thankful to Frank B. Hobbs for his thorough review.

The sampling review was conducted by **Michael J. Roebuck**, ACS Variance Estimation and Statistical Support Branch, Decennial Statistics Studies Division.

Musbaw Alawiye and Christine E. Geter of the Census Bureau's Administrative and Customer Services Division (ACSD), Francis Grailand Hall, Chief, provided publication and printing management, graphics design and composition, and editorial review for print and electronic media. General direction and production management were provided by Claudette E. Bennett, Assistant Division Chief.

Funding for the production of this report was provided by the NIA's Behavioral and Social Research Program, **Richard M. Suzman**, Director.

90+ in the United States: 2006–2008

Issued November 2011

ACS-17





U.S. Department of Commerce John E. Bryson, Secretary

Rebecca M. Blank, Acting Deputy Secretary

Economics and Statistics Administration Rebecca M. Blank,

Under Secretary for Economic Affairs

U.S. CENSUS BUREAU Robert Groves,

Director

Suggested Citation

Wan He and Mark N. Muenchrath,
U.S. Census Bureau,
American Community Survey Reports,
ACS-17, 90+ in the United States:
2006–2008,
U.S. Government Printing Office,
Washington, DC,
2011.



Economics and Statistics Administration Rebecca M. Blank, Under Secretary for Economic Affairs



U.S. CENSUS BUREAU Robert Groves,

Director

Thomas L. Mesenbourg,

Deputy Director and Chief Operating Officer

Howard Hogan,

Acting Associate Director for Demographic Programs

Enrique J. Lamas,

Chief, Population Division

Contents

The 90+ po	tionpulation will continue to grow both in size and of the older population	1
		4
Some states populous The 90+ po	s with the highest share of 90+ are not among the most states in size of the older population	4 7 8
the 90+.	rity represents almost half of total personal income for	9
	y rate for the 90+ is higher than that for those	10
Woman age	d 90+ outnumber 90+ men nearly 3 to 1rcent of the 90+ women are widowed, while more than	11
Asian and H	t of the 90+ men are married	13 14
the two m	oost common types of disability for the 90+ e almost universally covered by health insurance	15 18
Summary	,	18
	f the Data and Accuracy of the Estimates nd Nonsampling Error	20 20
Contact.		21
Referenc	es	22
Figures		
Figure 1. Figure 2.	Population Aged 90 and Over: 1980 to 2050 Percentage Change of Populations Aged 65 to 89 and Aged 90 and Over: 1980 to 2050	3
Figure 3.	Percentage Aged 90 and Over of State Population Aged 65 and Over: 2006–2008	5
Figure 4.	Percentage Aged 65 and Over of Total State Population: 2006–2008	5
Figure 5.	Percentage Aged 90 and Over of 65 and Over, and Percentage Aged 65 and Over of Total Population by State: 2006–2008	6
Figure 6.	Age Distribution of Population Aged 65 and Over by Race and Hispanic Origin: 2006–2008	8
Figure 7.	Income Source of Population Aged 90 and Over: 2006–2008	10
Figure 8.	Percentage in Poverty of Population Aged 90 and Over by Sex, Race, and Hispanic Origin: 2006–2008	11
Figure 9.	Sex Ratio of Population Aged 65 and Over by Age:	12

Figure 11. Living Arrangements of Population Aged 90 and Over by Sex: 2006–2008	. 16
2006–2008	
Type of Disability: 2008	
Figure 14. Percentage With Health Insurance Coverage of Population Aged 90 and Over by Type of	
	. 17
	18
Tables	. 10
Table 1. Ten States With Highest Population Aged 90 and Over, and Percentage Aged 90 and Over of	
Aged 65 and Over: 2006–2008	1
Table 2. Educational Attainment of Population Aged 90 and Over by Sex, Race, and	4
Hispanic Origin: 2006–2008	a
Table 3. Life Expectancy by Age and Sex: 1929–31 and 2006	
Table 4. Ten States With Highest and Lowest Sex Ratios for Population Aged 90 and Over: 2006–2008	
Table 5. Marital Status for Population Aged 15 and Over by Age Group: 2006–2008	
Table 6. Percentage With Disability of Population Aged 85 and Over by Age and Sex: 2008	
Text Boxes	
Why 90+?	1
What Is the American Community Survey (ACS)?	2
Race and Hispanic Origin	7
How Poverty Is Measured	. 10
Group Quarters	. 15
Measurement of Disability in the 2008 American Community Survey (ACS)	. 19
Appendix Tables	
Appendix Table 1-A. Selected Characteristics of Population Aged 90 and Over by Sex: 2006–2008	. 24
Appendix Table 1-B. Margin of Error for Selected Characteristics of Population Aged 90 and Over by Sex: 2006–2008	. 25
Appendix Table 2-A. Marital Status for Population Aged 15 and Over by Age, Sex, and Status: 2006–2008	
Appendix Table 2-B. Marital Status for Population Aged 65 and Over by Age and Sex: 2006–2008	
Appendix Table 3-A. Living Arrangements for Population Aged 65 and Over by Age, Sex, and Type:	
2006–2008	. 27

INTRODUCTION

An increasingly important feature of population aging in the United States is that the older population itself is getting older.1 That is, the proportion of the population aged 90 and over among the older population has been increasing. Thanks to increases in life expectancy at older ages, the oldest segments of the older population are growing the fastest. A nation's oldest-old population consumes resources disproportionately to its overall population size, and its growth has a significant impact on societal and family resources, including pension and retirement income, health care costs, and intergenerational relationships (Kinsella and He, 2009; Zhou, Norton, and Stearns, 2003).

This report presents an overview of the population aged 90 and over in the United States and a comparative analysis of selected characteristics between the 90-and-older and other older age groups. Data for this report primarily come from the 2006-2008 and 2008 American Community Surveys (ACS). Because the 2006-2008 ACS 3-year estimates are based on a larger sample than 1-year estimates and therefore are more reliable, they are used for analysis of the 90-and-over population by age, sex, race, and Hispanic origin at the national level and by age and sex at the state level.2

The 2008 ACS 1-year estimates in this report supplement the 3-year data at the national level with information from the changed questions

Why 90+?

"Oldest old" in the United States is often defined as people aged 85 and over (Suzman and Riley, 1985).* However, the 90-and-older population has been growing more rapidly than those aged 85–89 and other younger age groups among the older population aged 65 and over. Furthermore, not only has the 90-and-older population grown in size, but its proportion within the older population has also expanded.

People aged 90 and over have become an increasingly larger and more important population group that merits a closer look. However, little is known about their characteristics. Where do they live, and which states have the highest concentration? What are their distributions by age, sex, race, and Hispanic origin? Are they different in socioeconomic and health characteristics from their younger counterparts (ages 65–89) in the older population, especially those just a 5-year age group younger (ages 85–89)? These questions have not been addressed before, primarily because the relatively small numbers of people aged 90 and over in survey data do not allow a statistically significant and meaningful analysis.

This report provides answers to these questions, using American Community Survey 3-year (2006–2008) and 1-year (2008) data. It aims at contributing to the research on those 90 and older in order to enhance our understanding of this fast-growing population and to serve as a starting point for future research and trend analyses.

on disability and the newly added question on health insurance coverage.³

The 90+ population will continue to grow both in size and proportion of the older population.

The gains in life expectancy at older ages over the past century are impressive. According to the National Center for Health

Statistics, life expectancy at age 65 in the United States increased from 12.2 years in 1929–1931 to 18.5 years in 2006 (Arias, 2010, Table 11). People at very old ages are also expected to live longer. Today a person 90 years of age is expected to live on average another 4.6 years (versus 3.2 years in 1929–1931), and those who pass the century mark are projected to live another 2.3 years.

The prolonged life expectancy at older ages has led to the growing size of the oldest segments of the population.⁴ Decennial census

¹ In this report, "older population" refers to people aged 65 and over.

² Multiyear estimates should, in general, be used when single-year estimates have large coefficients of variation or when the precision of the estimates is more important than the currency of the data. Multiyear estimates should also be used when analyzing data for smaller geographies and smaller populations in larger geographies. Multiyear estimates are also of value when examining change over nonoverlapping time periods and for smoothing data trends over time.

Suzman and Riley (1985) defined "oldest old" as those aged 85 and over. Pointing to the fast growth of the 85-and-older population and their unique features that were in contrast to other segments of the older population, they called for more valid and reliable information on the oldest-old population. Now, more than 25 years later, the population aged 90 and over is the fastest growing segment among the older population.

³ The single-year and 3-year ACS estimates are period estimates that represent data collected over a period of time. The 2008 estimates used in this report were collected over a 12-month period in 2008 and the 2006–2008 estimates used in this report were collected over a 36-month period during 2006 to 2008. For more information on the methodology of the ACS, see text box "What Is the American Community Survey (ACS)?"

⁴ In this report, the terms "oldest" and "population aged 90 and over" are used interchangeably.

What Is the American Community Survey (ACS)?

The ACS, a nationwide survey sponsored and collected by the U.S. Census Bureau, is designed to provide communities with reliable and timely demographic, social, economic, and housing data every year. It has a total annual sample size of about 3 million addresses across the United States and Puerto Rico, and includes both housing units and group quarters.

The American Community Survey began in 1996 in a sample of counties across the country. Today the survey is conducted in every county throughout the nation and every municipio in Puerto Rico. Beginning in 2006, ACS 1-year estimates for 2005 were released for geographic areas with populations of 65,000 and greater. In 2008, the first set of multiyear estimates was released for data collected between January 2005 and December 2007. These 3-year estimates were published for geographic areas with populations of 20,000 and greater. Single-year and 3-year estimates from the ACS are all "period" estimates that represent data collected over a period of time (as opposed to "point-in-time" estimates, such as the decennial census, that approximate the characteristics of an area on a specific date). While a single-year estimate includes information collected over a 12-month period, a 3-year estimate represents data collected over a 36-month period. The Census Bureau released the first 5-year estimates (2005–2009) in late 2010 for the smallest geographic areas based on data collected during the 60 months between January 2005 and December 2009. These multiyear estimates are updated annually, with data published for the largest areas in 1-, 3-, and 5-year formats, and for those meeting the 3-year threshold in both 3- and 5-year formats.

The 2006–2008 3-year estimates contained in this report are based on the ACS sample interviewed in 2006, 2007, and 2008. The 2008 1-year data and the 2006–2008 3-year data used in this report were released in 2009. This report does not include Puerto Rico in its analysis. For information on the ACS sample design and other topics, visit <www.census.gov/acs/www/>.

data from 1980 to 2010 show that the 90-and-older population has steadily increased and this trend is expected to continue into the middle of the century. The 720,000 people aged 90 and over in 1980 almost tripled to 1.9 million in 2010. The total population aged 90 and over is projected to more than quadruple from 2010 to 2050 (Figure 1), compared to a doubling of the population aged 65 to 89.5


Not only has the 90-and-older population grown in size, it has also increased as a proportion of the older population (aged 65 and over). They accounted for 2.8 percent of the older population in 1980 and in 2010, they represented 4.7 percent. The increase in the proportion 90 and over of the older population is projected to slow down between 2020 and 2030 when the baby boomers join the ranks of the 65 and over population and swell the younger segments of the older population.⁶ However, the percentage of 90 and older is expected to rise again—reaching 7.1 percent in 2040 and 9.9 percent in 2050 when all of the baby boomers become 85 years of age and older. The U.S. population 40 years from now is projected to have 20 percent aged 65 and over, and one-tenth of them aged


90 and over (that is, 2 percent of the total population).

The baby boomers' impact on the growth of the older and oldest populations is also apparent from the percent change over time for ages 65-89 and 90 and older (Figure 2). Between 2020 and 2030, growth of the population aged 65-89 is projected to outpace that of the population aged 90 and over when the 65-89 age group is projected to increase by 32 percent and the 90 and over by 21 percent. However, in the following decade (2030s) the 90-and-older population is projected to experience a 71 percent jump, as opposed to a 10 percent increase for those aged 65-89 years old. The momentum of aging within the older population propelled by the baby boomers will be significant.

⁵ The projections data came from Vincent and Velkoff, 2010, Table A-1. The projections originate with a base population from Census 2000 and are not based on data from the 2010 Census. For more information on projections methodology, see <www.census.gov/population/www/projections/methodstatement.html>. 2010 Census based projections are currently planned for release in 2012.

⁶ Baby boomers are those born between 1946 and 1964.





FINDINGS

Some states with the highest share of 90+ are not among the most populous states in size of the older population.

In 2006–2008, there were an estimated 1.8 million people aged 90 and over in the United States (Appendix Table 1-A).^{7, 8} Ten states

had 50,000 or more people aged 90 and older-California, Florida, Illinois, Massachusetts, Michigan, New Jersey, New York, Ohio, Pennsylvania, and Texas (Table 1).9 However, when using the percentage of the 65-and-older population aged 90 and older as an indicator of being oldest (Figure 3), most of the states, with the exception of Massachusetts, with the largest number of 90 and older were not ranked in the top 10 (Table 1). In contrast, some of the smallest states in terms of population size of 90 and older (North Dakota,

Rhode Island, and South Dakota) were among those which had the highest shares of 90 and older among the older population. This finding is consistent with these states being among the top older states measured by the share of population aged 65 and over of the total state population (Figure 4).

Table 1.

Ten States With Highest Population Aged 90 and Over, and Percentage Aged 90 and Over of Aged 65 and Over: 2006–2008

(Data based on sample. For information on confidentiality protection, sampling error, nonsampling error, and definitions, see www.census.gov/acs/www/)

Rank	Population aged	l 90 and over	Percentage aged 90 and over of aged 65 and over		
	State	Number	State	Percent	
1	California	186,448	North Dakota	6.9	
2	Florida	141,922	Connecticut	6.2	
3	New York	130,549	Iowa	6.1	
4	Texas	96,693	South Dakota	6.0	
5	Pennsylvania	94,444	District of Columbia	6.0	
6	Illinois	78,800	Minnesota	5.9	
7	Ohio	72,077	Nebraska	5.8	
8	Michigan	58,387	Massachusetts	5.8	
9	New Jersey		Kansas	5.5	
10	Massachusetts		Rhode Island	5.4	


Note: Although the American Community Survey (ACS) produces population, demographic, and housing unit estimates, it is the Census Bureau's Population Estimates Program that produces and disseminates the official estimates of the population for the nation, states, counties, cities, and towns.

Source: U.S. Census Bureau, American Community Survey, 2006–2008.

⁷ Although the ACS produces population, demographic, and housing unit estimates, it is the Census Bureau's Population Estimates Program that produces and disseminates the official estimates of the population for the nation by age, sex, race, and Hispanic origin.

⁸ See Appendix Table 1-B for the margin of error for variables included in Appendix Table 1-A.

 $^{^{\}rm 9}$ States in this report include the 50 states and the District of Columbia.







Figure 5 plots the percentage of the older population aged 90 and over, and the percentage of the total population aged 65 and older for each state. The horizontal blue line represents the share aged 90 and older of population aged 65 and over at the national level (4.6 percent), and the vertical orange line represents the national level of the percentage aged 65 and older of total population (12.6 percent). Often, the top older states are also the oldest. Among states with the

largest share of population aged 65 and older of the total population as well as the largest share of 90 and older among the older population, sitting in the upper right quadrant (II), are Connecticut, lowa, Nebraska, North Dakota, and South



Dakota. In the opposite corner, the lower left quadrant (IV), are states that are below the national level on both measures. Alaska is in this category and had among the lowest values for both measures. The other two quadrants include states that are above the national level in one measure but below it in the other measure. Minnesota in the upper left quadrant (I), for example, had a 5.9 percent share aged 90 and older of the older population (higher than the national level) but a percentage aged 65 and older of 12.3 (lower than the national level). West Virginia in the lower right quadrant (III) is an opposite example. Its share aged 65 and older was among the highest in the nation, 15.5 percent, but its percentage aged 90 and older of the older population was among the lowest, 4.1. The top older state, Florida (17.1 percent 65 and older), had a share of the older population aged 90 and older right at the national level, 4.6 percent.

Whether a state with a high percentage of 65 and older of total population is also among the top oldest based on the percentage aged 90 and over of the older population depends on various factors. The age distribution of a state is shaped by decades of fertility and mortality changes. In addition, net interstate migration of the young, older, as well as the oldest populations also plays a role. Even though most older people do not move, past research has shown retirement migration for

Race and Hispanic Origin

The U.S. Census Bureau collects race and ethnicity data in accordance with guidelines provided by the U.S. Office of Management and Budget (OMB). Starting in 1997, OMB required federal agencies to use a minimum of five race categories: White, Black or African American, American Indian or Alaska Native, Asian, and Native Hawaiian or Other Pacific Islander. For respondents unable to identify with any of these five race categories, OMB approved the Census Bureau's inclusion of a sixth category—Some Other Race—on the Census 2000, 2010 Census, and ACS questionnaires.

Race data are based on self-identification. The question on Hispanic origin asks respondents if they are of Hispanic, Latino, or Spanish origin. The question on race asks respondents to report the race or races they consider themselves to be. People who identify their origin as Hispanic, Latino, or Spanish may be of any race.

older people for climate or amenities (such as favorable property tax rates or specialized health care access), and return migration of some of the oldest people to their state of origin to be closer to other family members. He and Schachter (2003) documented that people aged 85 and over were more mobile than the near old (aged 55-64) and the younger old (aged 65-74 and 75-84), and that there were variations in net migration of older people among states. Further analysis and trend data are needed to assess the effects of domestic migration of the older and oldest on the composition of a state's older population.

The 90+ population is overwhelmingly White.

In 2006–2008, Whites represented 88.1 percent of the total 90-andover population (see Appendix Table 1-A).¹¹ This proportion was higher than their share of the 65-and-older population (85.2 percent) and the total population (74.3 percent).¹² Blacks represented 7.6 percent of the 90-and-over population and Asians represented 2.2 percent. About 4 percent of the

¹⁰ For an example of studies on mortality rate differentials at the state level, see Wilmoth, Boe, and Barbieri, 2010.

¹¹ In this report, the terms "White" and "White alone," "Black" and "Black alone," and "Asian" and "Asian alone" are used interchangeably to refer to people who reported one race only.

The terms White alone, Black or African American alone, American Indian and Alaska Native alone, Asian alone, Native Hawaiian and Other Pacific Islander alone, and Some Other Race alone refer to people who reported one race only. The term Two or More Races is used to refer to people who reported more than one race. The use of six single-race populations and one multiple-race population in this report does not imply that this is the preferred method of presenting or analyzing data. The Census Bureau uses a variety of approaches to report race.

In this report, due to the small sample size of the 90-and-over population of some race groups, a group "Other races" is used for analysis which combines all race groups other than White alone, Black alone, or Asian alone, and includes Two or More Races.

¹² The percentages were derived from special tabulations from ACS 2006–2008.

90-and-older population reported themselves to be of Hispanic origin (can be of any race).

The age distribution of the older population also varies by race and Hispanic origin. At 4.8 percent, Whites had the highest percentage aged 90 years and older of the older population (Figure 6). Blacks had the next highest share, with 4.2 percent aged 90 and over. Asians, Other races, and Hispanics were similar at 3 percent. Whites also had the lowest proportion of the youngest-older ages (65–69).

Most 90+ are high school graduates or beyond.


Given that people aged 90 and over included in this report (as of 2008) were born in 1918 or earlier,

a considerable proportion (61.3 percent) of them had completed high school or above (Table 2).¹³ Among the 90-and-older population, about one-third (33.7 percent) stopped after high school graduation. Nearly 28 percent continued their education beyond high school, about half of whom completed a bachelor's degree or higher.

Education is linked to many aspects of a person's well-being, and people with higher education tend

to have lower mortality rates and better overall health than their less-educated counterparts as they are more likely to have better jobs and living conditions and more likely to have healthy behavior and utilize health care (Kinsella and He, 2009). The educational attainment of those aged 65 to 79 in 2006–2008 provides a glimpse of what educational attainment might look like for those aged 90 and older in 10–25 years time. About 77 percent of those aged 65–79 years old in 2006–2008 had com-

¹⁵ The current cohort's educational attainment is only an indication, not a projection, of the educational attainment of the same cohort in the future, as mortality plays an important role in the cohort's survival rate.



¹³ According to the 1940 Census, 39 percent of people aged 20 to 30 had completed high school or above (U.S. Census Bureau, 1943. 1940 Census of Population and Housing, Vol. 4, "Characteristics by age: Marital Status, Relationship, Education, and Citizenship." <www2.census.gov/prod2/decennial/documents/33973538v4p1ch1.pdf>).

¹⁴ For additional research on how education affects health, see Dupre, 2007; Lynch, 2006.

pleted high school, and about 43 percent of them had at least some college education.¹⁶

Educational attainment varies among the 90-and-older population by race and Hispanic origin. In 2006–2008, Whites had a higher proportion (14.9 percent) of having obtained some college education than all other race groups as well as Hispanics (Blacks, Asians, Other races, and Hispanics had similar percentages at around 7 percent). In addition, 14.3 percent of 90-and-older Whites had a bachelor's degree, higher than other race groups and Hispanics except for Asians (17.0 percent).

While a slightly higher proportion of 90-and-older men had at least graduated from high school compared with women (62.9 percent vs. 60.8 percent), a further breakdown of the educational attainment by high school graduate, some college, and bachelor's degree or higher, reveals that the gender difference in educational level is more salient after high school completion. About one in five 90-andolder men had a bachelor's degree or higher, almost twice that of the 90-and-older women, even though the proportions that pursued some college education differed slightly. A possible contributor to this noteworthy difference may be the Servicemen's Readjustment Act of 1944 (the GI Bill of Rights).¹⁷ According to the 2006–2008 ACS, among men aged 90 and over, 42 percent served in the military during World War II (about 1 percent of 90-and-older women did), and another 6 percent were in active duty prior to November 1941. The

Table 2.

Educational Attainment of Population Aged 90 and Over by Sex, Race, and Hispanic Origin: 2006-2008

(In percent. Data based on sample. For information on confidentiality protection, sampling error, nonsampling error, and definitions, see www.census.gov/acs/www/)

Sex, race, and Hispanic origin	Not a high school graduate	High school	Some college	Bachelor's degree or higher
Total	38.7	33.7	14.0	13.6
Male	37.1	29.1	14.6	19.1
Female	39.2	35.3	13.7	11.7
White alone	35.4	35.5	14.9	14.3
	64.8	20.3	7.3	7.6
	52.8	22.3	7.9	17.0
	67.1	20.3	7.0	5.6
Hispanic (any race) Not Hispanic (any race)	69.4	16.6	6.1	7.8
	37.3	34.5	14.3	13.9

Notes:

"Other races" combines all race groups other than White alone, Black alone, or Asian alone, and includes Two or More Races.

Percents shown may not sum to 100.0 due to rounding.

Source: U.S. Census Bureau, American Community Survey, 2006-2008.

GI Bill, designed to help veterans when they returned to civilian life after World War II, provided educational benefits including some tuition waivers and living allowance for the veterans pursuing or continuing their education. "In the peak year of 1947, veterans accounted for 49 percent of college admissions. By the time the original GI Bill ended on July 25, 1956, 7.8 million of 16 million World War II veterans had participated in an education or training program" (Department of Veterans Affairs, $2010).^{18}$

Social Security represents almost half of total personal income for the 90+.

The annual median personal income for people aged 90 and over during 2006–2008 was \$14,760 (in 2008 inflation-adjusted dollars). Men had significantly higher income than women, \$20,133 versus \$13,580.

According to the Social Security Administration (SSA), receipt of Social Security has become nearly universal for people aged 65 and over, and Social Security provides the largest share of their aggregate income (Social Security Administration, 2010). In 2006–2008, 92.3 percent of the 90-and-older population received income from the SSA—86.2 percent received Social Security income only, 3.0 percent collected Supplemental Security Income (SSI) only, and a similar 3.1 percent

¹⁶ The percentages were calculated from special tabulations from ACS 2006–2008.


¹⁷ For information on the Servicemen's Readjustment Act of 1944, visit <www.archives.gov/historical-docs/todays-doc/?dod-date=633>.

¹⁸ Research has documented the major changes in the scope of American higher education institutions, including the emergence of the research universities and great expansion of enrollments in public schools between 1890 and 1940. This expansion facilitated the large influx of WWII veterans into higher education institutions. For an example, see Goldin and Katz, 1999.

Figure 7.

Income Source of Population Aged 90 and Over: 2006-2008

(Data based on sample. For information on confidentiality protection, sampling error, nonsampling error, and definitions, see www.census.gov/acs/www)



Notes:

Income is annual personal income in 2008 inflation-adjusted dollars.

"Other income" includes interest, dividends, or net rental or royalty income or income from estates and trusts; public assistance or welfare payments; and all other income. Percents shown do not sum to 100.0 due to rounding.

Source: U.S. Census Bureau, American Community Survey, 2006-2008.

How Poverty Is Measured

The Office of Management and Budget (OMB) determined the official definition of poverty in Statistical Policy Directive 14. Poverty status is determined by comparing annual income to a set of dollar values called thresholds that vary by family size, number of children, and age of householder. If a family's before-tax money income is less than the dollar value of their threshold, then that family and every individual in it are considered to be in poverty. For people not living in families, poverty status is determined by comparing the individual's income to his or her threshold. The poverty thresholds are updated annually to allow for changes in the cost of living using the Consumer Price Index (CPI-U). They do not vary geographically.

For more information on how poverty is measured, visit <www.census.gov/hhes/www/poverty/about /overviewmeasure.html>.

received both Social Security and SSL^{19, 20}

Social Security income represented almost half (47.9 percent) of personal income for people aged 90 years and over (Figure 7). Retirement pension income was the second largest single source at 18.3 percent. A combined category "Other income" accounted for about 30 percent of income for the 90-and-older population.²¹ Earnings (2.2 percent) and SSI (1.9 percent) comprised the remaining portions of the personal income sources.

The poverty rate for the 90+ is higher than that for those aged 65-89.

In 2006–2008, 14.5 percent of the people aged 90 and over lived in poverty. Among those in poverty, 81.2 percent were women, disproportionately higher than their share of the 90-and-older population (74.1 percent).²² This translates to 16.5 percent of women and 9.6 percent of men aged 90 and older in poverty (Figure 8).

Poverty rates for the 90-and-older population also vary by race and Hispanic origin. Whites had the lowest poverty rate (13.3 percent), followed by Asians (16.0 percent). Blacks had the highest poverty rate, with about a quarter of them

¹⁹ Social Security income includes Social Security pensions and survivor benefits, permanent disability insurance payments made by the SSA prior to deductions for medical insurance, and railroad retirement insurance checks from the U.S. government. Medicare reimbursements are not included.

SSI is a nationwide assistance program administered by the SSA that guarantees a minimum level of income for needy aged, blind, or disabled individuals.

For more information about Social Security income and SSI, visit <www.ssa.gov>.

²⁰ The percentages receiving income from the SSA were derived from special tabulations from ACS 2006–2008.

^{21 &}quot;Other income" includes interest, dividends, or net rental or royalty income, or income from estates and trusts; public assistance or welfare payments; and all other income.

²² The percentages were derived from special tabulations from ACS 2006–2008.

falling below the poverty line during 2006–2008. About 21 percent of Hispanics aged 90 and older were poor.

The 90-and-older population had a higher poverty rate than their younger counterparts within the older population. In 2006–2008. people aged 65 to 89 had a poverty rate of 9.6 percent, 5 percentage points lower than the poverty rate of 14.5 percent for people aged 90 and over (12.4 percent for those aged 85-89).23 The ACS data also showed that in 2006-2008, the poverty rate for children (under 18) was 18.2 percent and for those aged 18 to 64, 11.8 percent. Compared with these younger age groups, the older population (aged 65 and over) had a lower poverty rate (9.8 percent). However, those aged 90 and older are poorer than the rest of the older population.


Women aged 90+ outnumber 90+ men nearly 3 to 1.

Older women not only can expect to live longer than men, but they have experienced more rapid improvements in life expectancy than males during the period from 1929-1931 to 2006. Life expectancy at age 65 in 2006 was 19.7 years for women and 17.0 years for men. In the past 8 decades older women have added almost 7 years to their life expectancy or a 54 percent extension, compared to 5.3 years or 45 percent for men (Table 3).24 This female advantage in life expectancy has resulted in fewer men at older ages relative to the number of women, most prominent in the oldest age groups. As shown

Figure 8.

Percentage in Poverty of Population Aged 90 and Over by Sex, Race, and Hispanic Origin: 2006-2008

(Data based on sample. For information on confidentiality protection, sampling error, nonsampling error, and definitions, see www.census.gov/acs/www)



Note: "Other races" combines all race groups other than White alone, Black alone, or Asian alone, and includes Two or More Races.

Source: U.S. Census Bureau, American Community Survey, 2006-2008.

Table 3. Life Expectancy by Age and Sex: 1929-31 and 2006

Cay and aga	Average number of years of life remaining			
Sex and age	1929–1931	2006		
BOTH SEXES				
0 years	59.2	77.7		
65 years	12.2	18.5		
75 years	7.3	11.6		
85 years	4.2	6.4		
90 years	3.2	4.6		
100 years	1.5	2.3		
MALE				
0 years	57.7	75.1		
65 years	11.7	17.0		
75 years	7.0	10.4		
85 years	4.0	5.7		
90 years	3.1	4.1		
100 years	1.5	2.0		
FEMALE				
0 years	60.9	80.2		
65 years	12.8	19.7		
75 years	7.6	12.3		
85 years	4.3	6.8		
90 years	3.2	4.8		
100 years	1.5	2.3		

Source: Arias, 2010, Table 11.


²³ The poverty rates were derived from special tabulations from ACS 2006-2008.

²⁴ Studies on life expectancy in the United States point to the slowing in gains of life expectancy for women and a narrowing in the mortality gap at birth as well as at older ages between men and women since the 1980s. For examples of the research, see Glei, Mesle, and Vallin, 2010; Preston and Wang, 2006.

Figure 9.

Sex Ratio of Population Aged 65 and Over by Age: 2006–2008

(Data based on sample. For information on confidentiality protection, sampling error, nonsampling error, and definitions, see www.census.gov/acs/www)



Note: Sex ratio is the number of men per 100 women.

Source: U.S. Census Bureau, American Community Survey, 2006-2008.

Table 4.

Ten States With Highest and Lowest Sex Ratios for Population Aged 90 and Over: 2006-2008

(Data based on sample. For information on confidentiality protection, sampling error, nonsampling error, and definitions, see www.census.gov/acs/www/)

Dank	Highes	st	Lowest		
Rank	State	Sex ratio	State	Sex ratio	
1	Hawaii	51	District of Columbia	19	
2	Florida	47	Alaska	23	
3	Arizona	46	Tennessee	26	
4	Utah	46	Georgia	27	
5	Montana	43	North Carolina	27	
6	Idaho	43	Louisiana	29	
7	Oregon	41	Mississippi	29	
8	New Mexico	41	Alabama	29	
9	California	40	Wyoming	30	
10	Nevada		Massachusetts	30	

Notes:

Sex ratio is the number of men per 100 women.

For statistical purposes, the District of Columbia is treated as a state equivalent.

Although the American Community Survey (ACS) produces population, demographic, and housing unit estimates, it is the Census Bureau's Population Estimates Program that produces and disseminates the official estimates of the population for the nation, states, counties, cities, and towns.

Source: U.S. Census Bureau, American Community Survey, 2006-2008.

in Appendix Table 1-A, about threefourths (74.1 percent) of the total population aged 90 and older in 2006–2008 were women.

For the population aged 90 and over, the sex ratio, that is the number of men per 100 women was stunningly low at 35. The sex ratio decreased steadily with age among the older population (Figure 9). The youngest cohort (aged 65 to 69) had a ratio of 87. Even at ages 85 to 89, men were about half the number of women. By the extreme oldest ages of 95–99 and 100 and older, there was about one man for every four women.

Sex ratios of the 90-and-older population varied greatly across states (Table 4). Among the lowest was the District of Columbia (19) and among the highest was Hawaii (51).25 Despite being a relatively "young" state with among the lowest percentage of the older population aged 90 and older as well as the lowest percentage of state total population aged 65 and older, Alaska has one of the lowest sex ratios at 90 and older (less than 30). Other states that ranked lowest in sex ratio included Alabama, the District of Columbia, Georgia, Louisiana, Massachusetts, Mississippi, North Carolina, Tennessee, and Wyoming. At the other end of the spectrum, there were relatively high numbers of 90-and-older men per 100 women (40 or above) in Arizona, California, Florida, Hawaii, Idaho, Montana, Nevada, New Mexico, Oregon, and Utah.

²⁵ For data presentation purposes, the District of Columbia is considered a state equivalent.


Over 80 percent of the 90+ women are widowed, while more than 40 percent of the 90+ men are married.


The impact of the higher male mortality is seen in the considerable differences in marital status between men and women. As illustrated in Figure 10, 90-andolder men differed significantly from their female counterparts in the likelihood of being widowed and of being married. About half of the men aged 90 and over were widowers, while 42.9 percent of them were married. In stark contrast, more than eight in ten (84.2 percent) of women aged 90 and over were widows, and a very low percentage (6.3 percent) were married.

Table 5 shows the marital status by age groups starting with age 15. The likelihood of being married reached over 60 percent by ages 35-44, peaked at ages 55-64, and declined rapidly at the oldest ages. down to 9 percent for people aged 95-99 and 7 percent for those aged 100 and over. On the other hand, the likelihood of widowhood stayed extremely low until ages 65-74, and then rose sharply when people reached the oldest ages. While those aged 85-89 were about twice more likely to be widowed than married, by ages 90-94 they were four times as likely. Note also the significant difference in widowhood by sex between ages 85-89 and ages 90-94, only a 5-year age group gap (Appendix Table 2-A). These findings indicate that people aged 90 and over have different marital characteristics than those aged 85-89.

Figure 10. Marital Status of Population Aged 90 and Over by Sex: 2006-2008

(Data based on sample. For information on confidentiality protection, sampling error, nonsampling error, and definitions, see www.census.gov/acs/www)





Source: U.S. Census Bureau, American Community Survey, 2006-2008.

Table 5.

Marital Status for Population Aged 15 and Over by Age Group: 2006–2008

(In percent. Data based on sample. For information on confidentiality protection, sampling error, nonsampling error, and definitions, see www.census.gov/acs/www/)

Age	Total	Married	Widowed	Divorced	Separated	Never married
15–24	100.0	7.6	0.1	0.6	0.5	91.2
25–34	100.0	48.0	0.3	6.4	2.7	42.7
35–44	100.0	63.6	0.7	13.0	3.4	19.3
45–54	100.0	65.1	2.1	17.2	3.1	12.5
55–64	100.0	66.8	6.0	17.4	2.2	7.5
65–74	100.0	63.5	17.3	12.9	1.5	4.8
75–84	100.0	49.2	38.1	7.5	0.8	4.3
85–89	100.0	30.7	59.7	4.8	0.5	4.3
90–94	100.0	17.9	73.1	3.8	0.4	4.8
95–99	100.0	9.0	82.0	3.3	0.4	5.3
100 years and over	100.0	6.9	80.5	4.0	0.5	8.1

Note: Percentages may not sum to the row totals due to rounding.

Source: U.S. Census Bureau, American Community Survey, 2006-2008.


Asian and Hispanic 90+ are least likely to live alone.

ACS data encompass group quarters, which include institutionalized as well as noninstitutionalized populations. In 2006-2008, half of the men aged 90 and over lived in a household with family members and/or unrelated individuals, less than one-third lived alone, and about 15 percent were institutionalized in facilities such as nursing facilities/skilled-nursing facilities (Figure 11). In contrast, 40 percent of the women aged 90 and over lived alone, and another quarter of them lived in institutional group quarters. Given the large number of women at these ages. this translates into about 520,000

Figure 11.

Living Arrangements of Population Aged 90 and Over by Sex: 2006-2008

(In percent. Data based on sample. For information on confidentiality protection, sampling error, nonsampling error, and definitions, see www.eensus.gov/acs/www)



Note: Percents shown may not sum to 100.0 due to rounding.

Source: U.S. Census Bureau, American Community Survey, 2006-2008.

Group Quarters

A group quarters is a place where people live or stay in a group living arrangement, which is owned or managed by an entity or organization providing housing and/or services for the residents. These services may include custodial or medical care as well as other types of assistance, and residency is commonly restricted to those receiving these services. This is not a typical household-type living arrangement. People living in group quarters usually are not related to each other. Group quarters include places such as college residence halls, residential treatment centers, skilled-nursing facilities, group homes, military barracks, correctional facilities, and workers' dormitories.

Institutional Group Quarters—Includes facilities for people under formally authorized, supervised care or custody at the time of interview, such as correctional facilities, nursing/skilled-nursing facilities, in-patient hospice facilities, mental (psychiatric) hospitals, group homes for juveniles, and residential treatment centers for juveniles.

Noninstitutional Group Quarters—Includes facilities that are not classified as institutional group quarters, such as college/university housing, group homes intended for adults, residential treatment facilities for adults, workers' group living quarters and Job Corps centers, and religious group quarters.

A complete description of the types of group quarters included in the 2008 ACS is located on the U.S. Census Bureau's Internet site at <www.census.gov/acs/www/UseData/GQ/def.htm>.

women aged 90 and over living alone and 330,000 living in institutions. Contrasting the number of 90-and-older women with their male counterparts reveals great sex imbalances for living alone, a sex ratio of only 27, and for living in institutions, an even lower sex ratio of 20.

Special attention is needed when comparing the proportion living alone from this report to results reported in past studies. In this report, percent living alone was calculated as a proportion of the entire population aged 90 and older, including those living in group quarters (e.g., nursing facilities). On the other hand, almost all past studies focused on older people's living arrangements used only the noninstitutionalized population as the base to estimate the proportion living alone. The much larger, but all inclusive, denominator used in this report yields a smaller percentage living alone but provides a more accurate depiction of the living arrangements of the oldest age groups of the population.

For example, in 2006–2008, 39.8 percent of all women aged 90 and older lived alone (Figure 11), compared to 53.4 percent of noninstitutionalized 90-and-older women.

An older person's likelihood of living in a nursing home increases sharply with age. The share institutionalized remained extremely low from ages 65–69 (1.0 percent) and ages 75-79 (3.0 percent), then began to rise markedly, reaching 11.2 percent at ages 85-89, 19.8 percent at ages 90–94, 31.0 percent at ages 95-99, and 38.2 percent at 100 years of age and older (Appendix Table 3-A). Living arrangements vary greatly across race groups and Hispanic origin. Three-quarters of Whites and Blacks aged 90 and older lived in households, while over 85 percent of Asians and Hispanics did. Most notably, almost 40 percent of Whites lived alone, compared with half of that proportion (about 20 percent) for Asians and Hispanics (Figure 12).


Difficulty doing errands alone and mobility-related limitations are the two most common types of disability for the 90+.

Disability is one of the most commonly used indicators for health of the older population. According to the 1990 Americans With Disabilities Act, disability is defined as a substantial limitation in a major life activity. Research shows that age is positively associated with the presence of physical difficulty, and the oldest have the highest levels of physical and cognitive disability (Administration on Aging, 2010; Pleis, Lucas, and Ward, 2009; Wolf, Mendes de Leon, and Glass, 2007).²⁶

The 2008 ACS asked several questions about disabilities, including difficulties in hearing; seeing; concentrating or remembering, or making decisions; walking or climbing stairs; dressing or bathing; and doing errands alone.

U.S. Census Bureau 90+ in the United States: 2006–2008 15

²⁶ Research has documented declines in old-age disability in recent decades in the United States. For examples, see Schoeni, Freedman, and Martin, 2008; Spillman, 2003.



According to the ACS, the vast majority (84.7 percent) of those aged 90 and older reported having one or more types of limitations.²⁷ Difficulty doing errands alone, which represents an instrumental activity of daily living (IADL) such as visiting a doctor's office or shopping, was the most common

type of limitation (67.7 percent). Difficulty in performing the general mobility-related activities of walking or climbing stairs (66.3 percent) was a close second. Difficulty dressing or bathing (45.8 percent) reflects a limitation in activities of daily living (ADL), and about 40 percent had cognitive difficulties. For communication limitations, there were far more aged 90 and older who had difficulty hearing


(43.3 percent) than difficulty seeing (25.5 percent).

Nursing facilities and other healthrelated institutional facilities serve people who cannot fully take care of their own needs because of health and aging (Brault, 2008). People with higher disabilities tend to live in a nursing home. Figure 13 illustrates the differentials in disability rate between the institutionalized population and noninstitutionalized population (including those living in households and noninstitutional group quarters). Almost everyone (98.2) percent) residing in institutional group quarters (e.g., nursing homes) had some type of disability, compared with 80.8 percent of those who lived in households or noninstitutional group quarters. For most measures of disability. rates for those institutionalized were drastically higher than for those not institutionalized.28 The largest differences were in cognitive ability (concentrating, remembering, or making decisions) and limitations in dressing or bathing (indicator for ADL), with the institutionalized population aged 90 and older more than twice as likely to have those limitations than their noninstitutionalized counterparts.

The older a person, the more likely he or she is to have disabilities. When comparing people aged 90–94 with those aged 85–89,

²⁷ The disability rates for the total 90-and-older population were derived from special tabulations from the ACS 2006–2008.

²⁸ The percentage of institutionalized aged 90 and older having difficulty hearing is lower than those noninstitutionalized.



Source: U.S. Census Bureau, American Community Survey, 2008.

the 5-year age group gap again resulted in significant differences (Table 6). The proportion of people aged 90-94 having disabilities is about 13 percentage points higher than that of those aged 85-89 years old, and this difference is seen in both men and women.

Table 6.

Percentage With Disability of Population Aged 85 and Over by Age and Sex: 2008

(In percent. Data based on sample. For information on confidentiality protection, sampling error, nonsampling error, and definitions, see www.census.gov/acs/www/)


Age	Both sexes	Male	Female
85–89	69.4	65.4	71.5
90–94	82.7	77.8	84.6
95 years and over		85.5	92.7

Source: U.S. Census Bureau, American Community Survey, 2006-2008.

Figure 14.

Percentage With Health Insurance Coverage of Population Aged 90 and Over by Type of Insurance: 2008

(Data based on sample. For information on confidentiality protection, sampling error, nonsampling error, and definitions, see www.census.gov/acs/www)



The 90+ are almost universally covered by health insurance.

In 2008, ACS began to collect details on health insurance coverage. Almost everyone (99.5 percent) in the population aged 90 and over was covered by health insurance—98.8 percent had Medicare coverage and 28.0 percent also received Medicaid benefits in 2008 (Figure 14). There was no gender difference in this universality of health insurance coverage (data not shown in figure or table).

Medicare and Medicaid are the two major publicly-funded health insurance programs that assist older, disabled, and poor populations—Medicare provides health care for older people and Medicaid for poor people.²⁹ These public insurance programs' benefits have

enabled people aged 90 and over to be universally covered by health insurance.

In addition to Medicare and/ or Medicaid coverage, about 40 percent of the 90-and-older population also purchased private health insurance coverage from an insurance company. Another one-quarter of them were covered by a previous employer- or unionsponsored health insurance benefit. The 2008 ACS also asked whether the respondent was covered by TRICARE or other military health care, the Department of Veterans Affairs (VA), or Indian Health Service.³⁰

SUMMARY

Little research has been done on one of the fastest growing population segments, those aged 90 and over, due to data limitations.31 The ACS, which contains information similar to the long-form (sample) data previously collected in the decennial censuses, allows a general overview of this population. With the known age reporting difficulty among the oldest population, caution is needed when interpreting the findings in this report. For more information, see "Source of the Data and Accuracy of the Estimates."

²⁹ Medicare is the nation's health insurance program for people aged 65 or older, and certain people younger than age 65 with disabilities or specified health conditions. For more information on Medicare, go to <www.medicare.gov>. Medicaid is the health insurance available only to people with limited income, or other groups of people who meet certain requirements. For more information on Medicaid, go to <www.cms.gov>.

³⁰ TRICARE, the triple option benefit plan available for military families, is the health care program serving active duty service members, National Guard and Reserve members, retirees, their families, survivors, and certain former spouses worldwide. The VA provides a medical benefits package to all enrolled Veterans.

³¹ Interest in the characteristics of the population aged 100 and over also exists; however, because of the small size of this group, data quality thus far limits in-depth analysis of this population.

Measurement of Disability in the 2008 American Community Survey (ACS)

In 2008, the ACS changed the way it asks about disability. There are critical distinctions between the conceptual frameworks encompassing the 2008 questions and prior ACS or Census 2000 questions. The changes were made in an attempt to capture more reliably the population who would be likely to experience restrictions in participation due to physical, social, and other environmental barriers. After versions of proposed initial questions were cognitively tested, the new disability questions were included in the 2006 ACS Content Test. Results showed that the test questions had equal or lower nonresponse rates and performed better than control questions (disability questions in the 2003–2007 ACS).

The 2008 ACS disability questions include the following categories:

Communication domain: hearing difficulty and vision difficulty.

Mental domain: cognitive difficulty (difficulty concentrating, remembering, or making decisions).

Physical domain: ambulatory difficulties (difficulty walking or climbing stairs); self-care difficulty (difficulty dressing or bathing, or ADL/Activities of Daily Living); and independent living difficulty (difficulty doing errands alone such as visiting a doctor's office or shopping, or IADL/Instrumental Activities of Daily Living).

Because of the difference in measurement, the Census Bureau does not encourage data users to make comparisons between the 2008 disability estimates and prior ACS disability estimates. For the definition of disability in the ACS, visit <www.census.gov/acs/www/Downloads/data_documentation/documentation_main/>. For more information on changes to the 2008 ACS disability questions, see Brault, Matthew W., 2009, "Review of Changes to the Measurement of Disability in the 2008 American Community Survey," at <www.census.gov/hhes/www/disability/disability.html>.

A complete description of the types of group quarters included in the 2008 ACS is located on the U.S. Census Bureau's Internet site at <www.census.gov/acs/www/UseData/GQ/def.htm>.

Results from the 2006-2008 ACS 3-year estimates and the 2008 ACS 1-year estimates show that a majority of the 90-and-older population are White, and women who are much more likely than men to be widowed, living alone, or living in institutions. The majority of the 90-and-older population are highschool graduates, a relatively high proportion given that they were born in the early twentieth century. Almost half of their personal income comes from Social Security. The vast majority reported having one or more types of disability, while almost all of them have health insurance coverage thanks to Medicare and Medicaid.

The socioeconomic, demographic, and health characteristics of the population aged 90 and over vary by race and Hispanic origin. Asians and Hispanics are less likely than Whites and Blacks to live alone. However, Hispanics have a much higher poverty rate than Whites and Asians.

The findings in this report also point to important differences in various characteristics between the 90-and-older and the younger-older people, even between those aged 90–94 and 85–89. The 90-and-older population has a much lower sex ratio and much higher widowhood, poverty, and disability rates than those aged 85–89 years old.

This report provides a general cross-sectional examination of the population aged 90 and over. The information may be useful for future discussions among researchers and policy makers on whether the traditional cutoff age of 85 for "oldest old" should be reconsidered, given the rapid growth of the 90-and-over population and their distinct characteristics. Future trend data are needed to assess the changes in their status and needs for their care. Domestic migration data will help decipher the variation among older and oldest states.

SOURCE OF THE DATA AND ACCURACY OF THE ESTIMATES

The findings in this report are primarily based on the American Community Survey (ACS) data collected in 2006, 2007, and 2008. The population universe covered in this report includes the population living in either households or group quarters. The U.S. Census Bureau is both the sponsor and the collector of the ACS. The 2006-2008 3-year ACS is based on a sample of approximately 8.7 million housing unit addresses and a separate sample of just under approximately 560 thousand people living in group quarters. ACS figures are estimates based on this sample and approximate the actual figures that would have been obtained by interviewing the entire household and group quarters populations using the same methodology. The estimates from the 2006–2008 ACS sample may also differ from estimates based on other survey samples of housing units and group quarters, and the people living within those housing units and group quarters. Numbers in Appendix Table 1-A of this

report are rounded and totals may not sum to the column total due to rounding.

The decennial census data from 1980, 1990, 2000, and 2010, and population projections data (vintage 2008) were also used in this report for trend analysis of population growth.

Sampling and Nonsampling Error

Sampling error occurs when the characteristics of a sample are measured instead of those of the entire population (as from a census). Note that sample-based estimates will vary depending on the particular sample selected from the population, but all attempt to approximate the actual figures. Measures of the magnitude of sampling error reflect the variation in the estimates over all possible samples that could have been selected from the population using the same sampling, data collection, and processing methods. Estimates of the magnitude of sampling errors are provided in the form of margins of error for all key ACS estimates included in this report. The Census Bureau recommends

that data users incorporate this information into their analyses, as sampling error in survey estimates could impact the conclusions drawn from the results. All comparative statements in this report have undergone statistical testing, and comparisons are significant at the 90 percent confidence level unless noted otherwise. This means the 90 percent confidence interval for the difference between the estimates being compared does not include zero.

In addition to sampling error, non-sampling errors may be introduced during any phase of data collection or processing. For example, operations such as editing, reviewing, or keying data from questionnaires may introduce error into the estimates. The primary source of nonsampling error and the processes instituted to control error in the 2006–2008 3-year ACS are described in further detail in the 2006–2008 ACS 3-year Accuracy of the Data document (see Web link on the following page).

Nonsampling error also includes bias introduced by undercoverage of the population in the ACS. To minimize this bias, the ACS

20 90+ in the United States: 2006–2008

population estimates are controlled to the population estimates produced independently by the Census Bureau's population estimates program (PEP). The adjustment is done for broad age groups, with a top-end age category of 75 and over. So the population estimates in column 1 of Appendix Table 1-A in this report (ages 90-94, 95-99, and 100+) are not directly controlled to the PEP estimates. Any differential undercoverage (or other types of survey nonsampling error) for specific age groups within the broad 75+ category—including the 90+ group of this report—is not accounted for.

While the PEP population controls are intended to reduce bias in the ACS estimates, the PEP estimates themselves are subject to error. The Census Bureau is currently engaged in an evaluation of the accuracy of the PEP population estimates as compared to the 2010 Census results. The 2010 Census population aged 90 and over (and 100 and over) is lower than implied by the PEP estimates used as controls for the 2008 ACS and 2006-2008 ACS estimates, and we investigate possible reasons for this discrepancy.

Furthermore, nonsampling error specific to the oldest-old populations also stems from age misreporting. This is due to a variety of factors, including a gross ignorance of the true age, lack of birth records which makes it difficult to confirm or disconfirm a reported age, reliance by some oldest people on the knowledge of others for their own age, digital preference (such as those ending in "0" or "5"), and deliberate misreporting out of the desire to share in the esteem generally accorded extreme old age (Hobbs, 2004; Howden and Meyer, 2011; Krach and Velkoff, 1999). Studies on mortality of the "oldest old" in the United States have found overestimation of oldest ages, especially over the age of 100, and particularly in some population subgroups, which biased the mortality rates at oldest ages (Coale and Kisker, 1986; Kestenbaum and Ferguson, 2002, 2005; Preston, et al., 1996; Preston, Elo, and Stewart, 1999). However, age heaping did not appear to be a concern at the national level in Census 2000 or the 2010 Census (Howden and Meyer, 2011).

This report does not focus on population levels but rather provides analysis of the characteristics of the 90-and-older population on the national level. However, because of potential sampling and nonsampling errors discussed above, caution is needed when interpreting the results.

Title 13, U.S. Code, Section 9, prohibits the Census Bureau from publishing results from which the identity of an individual survey respondent could be determined. For more information on how the Census Bureau protects the confidentiality of data, see the 2006–2008 ACS 3-year Accuracy of the Data document, available at <www.census.gov/acs/www/Downloads/data_documentation/Accuracy/accuracy2006-2008ACS3-Year.pdf>.

CONTACT

U.S. Census Bureau Demographic Call Center Staff

For further information, call 1-866-758-1060 (toll-free) or visit <www.census.gov>.

90+ in the United States: 2006-2008 **21**

REFERENCES

- Administration on Aging. 2010.

 A Profile of Older Americans:
 2010. Available at <www.aoa
 .gov/AoARoot/Aging_Statistics
 /Profile/2010/16.aspx>.
 Accessed on February 28, 2011.
- Arias, Elizabeth. 2010. "United States Life Tables, 2006." National Vital Statistics Reports, Volume 58, Number 21, Hyattsville, MD: National Center for Health Statistics.
- Brault, Matthew W. 2009. "Review of Changes to the Measurement of Disability in the 2008

 American Community Survey."

 Available at <www.census.gov
 /hhes/www/disability
 /disability.html>.
- Brault, Matthew W. 2008.

 "Disability Status and the
 Characteristics of People in
 Group Quarters." Available at
 <www.census.gov/hhes/www
 /disability/disability.html>.
- Coale, Ansley J. and Ellen Eliason Kisker. 1986. "Mortality Crossovers: Reality or Bad Data?" *Population Studies*, 40:3, 389–401.
- Department of Veterans Affairs. 2010. "GI Bill History." <www.gibill.va.gov/gi_bill_info /history.htm>. Accessed on August 27, 2010.

- Dupre, Matthew E. 2007.

 "Educational Differences in
 Age-Related Patterns of Disease:
 Reconsidering the Cumulative
 Disadvantage and Age-AsLeveler Hypotheses." Journal
 of Health and Social Behavior,
 Volume 48 (March): 1–15.
- Glei, Dana A., France Mesle, and Jacques Vallin. 2010. "Diverging Trends in Life Expectancy at Age 50: A Look at Causes of Death." In National Research Council. 2010. International Differences in Mortality at Older Ages: Dimensions and Sources. E.M. Crimmins, S.H. Preston, and B. Cohen, Eds. Panel on Understanding Divergent Trends in Longevity in High-Income Countries. Committee on Population, Division of Behavioral and Social Sciences and Education. Washington, DC: The National Academies Press: 17-67.
- Goldin, Claudia and Lawrence F. Katz. 1999. "The Shaping of Higher Education: the Formative Years in the United States, 1890 to 1940." *Journal of Economic Perspectives*, Volume 13, Number 1: 37–62.
- He, Wan and Jason P. Schachter. 2003. Internal Migration of the Older Population: 1995 to 2000. U.S. Census Bureau, Census 2000 Special Reports. CENSR-10, U.S. Government Printing Office, Washington, DC.

- Hobbs, Frank. 2004. Age and Sex Composition. In Siegel, Jacob S. and David A. Swanson, eds. 2004. The Methods and Materials of Demography. San Diego and London, Elsevier Academic Press.
- Howden, Lindsay M. and Julie A. Meyer. 2011. *Age and Sex Composition: 2010*. U.S. Census Bureau, 2010 Census Briefs, C2010BR-03, U.S. Government Printing Office, Washington, DC.
- Kestenbaum, Bertram and B. Renee Ferguson. 2002. "Mortality of the Extreme Aged in the United States in the 1990s, Based on Improved Medicare Data." North American Actuarial Journal, Vol. 6, No. 3: 38–44.
- Kestenbaum, Bertram and B. Renee Ferguson. 2005. "Number of Centenarians in the United States Jan. 1, 1990, Jan. 1, 2000, and Jan. 1, 2010 Based on Improved Medicare Data." Paper presented at The Living to 100 and Beyond Symposium, Orlando, Florida, January 12–14, 2005.
- Kinsella, Kevin and Wan He. 2009. An Aging World: 2008. U.S. Census Bureau, International Population Reports, P95/09-1, U.S. Government Printing Office, Washington, DC.

22 90+ in the United States: 2006–2008 U.S. Census Bureau

- Krach, Constance A. and Victoria A. Velkoff. 1999. *Centenarians* in the United States. U.S. Census Bureau, Current Population Reports Special Studies, P23-199RV, U.S. Government Printing Office, Washington, DC.
- Lynch, Scott M. 2006. "Explaining Life Course and Cohort Variation in the Relationship between Education and Health: The Role of Income." *Journal of Health* and Social Behavior, Volume 47 (December): 324–338.
- Pleis, John R., Jacqueline W. Lucas, and Brian W. Ward. 2009.

 Summary Health Statistics for U.S. Adults: National Health Interview Survey, 2008. National Center for Health Statistics, Vital and Health Statistics 10(242).
- Preston, Samuel H. and Haidong Wang. 2006. "Sex Mortality Differences in the United States: The Role of Cohort Smoking Patterns." *Demography*, Volume 43, Number 4: 631–646.
- Preston, Samuel H., Irma T. Elo, Ira Rosenwaike, and Mark Hill. 1996. "African-American Mortality at Older Ages: Results of a Matching Study." *Demography*, Vol. 33, No. 2: 193–209.
- Preston, Samuel H., Irma T. Elo, and Quincy Stewart. 1999. "Effects of Age Misreporting on Mortality Estimates at Older Ages." Population Studies 53: 165–177.

- Schoeni, Robert F., Vicki A.
 Freedman, and Linda G. Martin.
 2008. "Socioeconomic and
 Demographic Disparities in
 Trends in Old-Age Disability."
 In David M. Cutler and David A.
 Wise, Eds. Health at Older Ages:
 The Causes and Consequences of
 Declining Disability Among the
 Elderly. Chicago: University of
 Chicago Press.
- Social Security Administration. 2010. *Income of the Aged Chartbook, 2008*. U.S. Government Printing Office, Washington, DC.
- Spillman, Brenda C. 2003. "Changes in Elderly Disability Rates and the Implications for Health Care Utilization and Cost." Prepared for Office of the Assistant Secretary for Planning and Evaluation, U.S. Department of Health and Human Services.
- Suzman, Richard and Matilda W. Riley. 1985. "Introducing the 'Oldest Old." *Milbank Memorial Fund Quarterly*, 63 (2): 175–186.
- Vincent, Grayson K. and Victoria A. Velkoff. 2010. THE NEXT FOUR DECADES, The Older Population in the United States: 2010 to 2050. Current Population Reports, P25-1138, U.S. Census Bureau, Washington, DC.

- Wilmoth, John R., Carl Boe, and Magali Barbieri. 2010. "Geographic Differences in Life Expectancy at Age 50 in the United States Compared with Other High-Income Countries." In National Research Council. 2010. International Differences in Mortality at Older Ages: Dimensions and Sources. E.M. Crimmins, S.H. Preston, and B. Cohen, Eds. Panel on **Understanding Divergent** Trends in Longevity in High-Income Countries. Committee on Population, Division of Behavioral and Social Sciences and Education. Washington, DC: The National Academies Press: 333-366.
- Wolf, Douglas A., Carlos F. Mendes de Leon, and Thomas A. Glass. 2007. "Trends in Rates of Onset of and Recovery From Disability at Older Ages: 1982–1994." Journal of Gerontology: Social Sciences 62B/1: S3-10.
- Zhou, Yang, Edward C. Norton, and Sally C. Stearns. 2003.
 "Longevity and Health Care Expenditures: The Real Reasons Older People Spend More."

 Journals of Gerontology Series B: Psychological Sciences and Social Sciences 59B: S2-10.

U.S. Census Bureau 90+ in the United States: 2006–2008 23

Appendix Table 1-A.

Selected Characteristics of Population Aged 90 and Over by Sex: 2006-2008

(Data based on sample. For information on confidentiality protection, sampling error, nonsampling error, and definitions, see www.census.gov/acs/www/)

Observatorialia	Both se	exes	Male		Female	
Characteristic	Number	Percent	Number	Percent	Number	Percent
Total, 90 years and over¹	1,761,770	100.0	457,155	100.0	1,304,615	100.0
AGE¹						
90–94	1,355,390	76.9	374,360	81.9	981,030	75.2
95–99	348,055	19.8	71,625	15.7	276,430	21.2
100 years and over	58,325	3.3	11,170	2.4	47,160	3.6
RACE AND HISPANIC ORIGIN ¹						
Race						
White alone	1,552,725	88.1	404,830	88.6	1,147,895	88.0
Black or African American alone	134,485 5,420	7.6 0.3	29,515 1,265	6.5 0.3	104,970 4,155	8.0 0.3
Asian alone	38.350	2.2	12.980	2.8	25.375	1.9
Native Hawaiian and Other Pacific Islander alone	420		35	2.0	385	-
Some Other Race alone	19,925	1.1	5,875	1.3	14,050	1.1
Two or More Races	10,445	0.6	2,655	0.6	7,790	0.6
Hispanic Origin						
Hispanic	76,370	4.3	22,015	4.8 95.2	54,355	4.2 95.8
Not Hispanic	1,685,405 1,499,100	95.7 85.1	435,140 389,620	85.2 85.2	1,250,265 1,109,480	85.0
MARITAL STATUS						
Married	278,365	15.8	196,285	42.9	82,080	6.3
Widowed	1,323,345 65.095	75.1 3.7	225,365 15.575	49.3 3.4	1,097,985 49.520	84.2 3.8
Divorced	7,135	0.4	2,740	0.6	49,520	0.3
Never married	87,830	5.0	17,195	3.8	70,635	5.4
EDUCATIONAL ATTAINMENT						
Not high school graduate	681,100	38.7	169,705	37.1	511,395	39.2
High school graduate	593,930	33.7	133,215	29.1	460,715	35.3
Some college	246,155 240.585	14.0 13.7	66,820 87,415	14.6 19.1	179,340 153,170	13.7 11.7
	240,303	10.7	07,410	10.1	150,170	11.7
PERSONAL INCOME						
Median annual income ²	\$14,760	(X)	\$20,133	(X)	\$13,580	(X)
POVERTY STATUS						
Below poverty	198,090	14.5	37,335	9.6	160,750	16.5

⁻ Represents or rounds to 0.0.

Note: Numbers and percentages may not sum to the column or row totals due to rounding.

Source: U.S. Census Bureau, American Community Survey, 2006–2008.

⁽X) Not applicable.

¹ Although the American Community Survey (ACS) produces population, demographic, and housing unit estimates, it is the Census Bureau's Population Estimates Program that produces and disseminates the official estimates of the population for the nation by age, sex, race, and Hispanic origin.

² In 2008 inflation-adjusted dollars.

Appendix Table 1-B.

Margin of Error for Selected Characteristics of Population Aged 90 and Over by Sex: 2006-2008

(Data based on sample and are subject to sampling variability. A margin of error is a measure of an estimate's variability. The larger the margin of error in relation to the size of the estimate, the less reliable the estimate. When added to and subtracted from the estimate, the margin of error forms the 90 percent confidence interval. For information on confidentiality protection, sampling error, nonsampling error, and definitions, see www.census.gov/acs/www/)

Ch are at a ristin	Both sexes		Male		Female	
Characteristic	Number	Percent	Number	Percent	Number	Percent
Total, 90 years and over	12,874	(X)	6,118	(X)	10,944	(X)
AGE						
90–94. 95–99. 100 years and over	11,895 4,221 1,915	0.3 0.2 0.1	5,308 2,228 868	0.5 0.4 0.2	9,993 4,026 1,742	0.3 0.3 0.1
RACE AND HISPANIC ORIGIN						
Race White alone Black or African American alone American Indian and Alaska Native alone Asian alone Native Hawaiian and Other Pacific Islander alone Some Other Race alone Two or More Races	12,272 3,090 697 1,850 182 1,369 797	0.2 0.2 - 0.1 - 0.1	6,261 1,472 271 973 40 709 454	0.5 0.3 0.1 0.2 - 0.2 0.1	9,808 2,858 616 1,390 174 1,178 742	0.2 0.2 - 0.1 - 0.1 0.1
Hispanic Origin Hispanic Not Hispanic White alone	2,721 12,624 11,892	0.2 0.2 0.2	1,425 5,838 5,979	0.3 0.3 0.5	2,310 10,824 9,767	0.2 0.2 0.3
MARITAL STATUS						
Married Widowed Divorced Separated Never married	5,420 10,657 2,215 684 3,037	0.3 0.3 0.1 - 0.2	3,929 4,591 1,074 446 1,218	0.7 0.7 0.2 0.1 0.3	2,453 9,871 1,857 584 2,924	0.2 0.3 0.1 - 0.2
EDUCATIONAL ATTAINMENT						
Not high school graduate. High school graduate. Some college. Bachelor's degree or higher.	7,913 6,477 4,734 3,901	0.4 0.3 0.2 0.2	3,571 3,233 2,295 2,715	0.6 0.6 0.5 0.5	6,887 6,201 3,715 3,069	0.4 0.4 0.3 0.2
PERSONAL INCOME						
Median annual income ¹	\$76	(X)	\$236	(X)	\$76	(X)
POVERTY STATUS						
Below poverty	4,202	0.3	1,695	0.4	3,639	0.3

⁻ Represents or Rounds to 0.0.

U.S. Census Bureau

Source: U.S. Census Bureau, American Community Survey, 2006–2008.

90+ in the United States: 2006-2008 **25**

⁽X) Not applicable.

¹ In 2008 inflation-adjusted dollars.

Appendix Table 2-A. Marital Status for Population Aged 15 and Over by Age, Sex, and Status: 2006-2008

(In percent. Data based on sample. For information on confidentiality protection, sampling error, nonsampling error, and definitions, see www.census.gov/acs/www/)

Sex and age	Total	Married	Widowed	Divorced	Separated	Never married
BOTH SEXES						
15–24	100.0	7.6	0.1	0.6	0.5	91.2
25–34	100.0	48.0	0.1	6.4	2.7	42.7
35–44	100.0	63.6	0.3	13.0	3.4	19.3
45–54	100.0	65.1	2.1	17.2	3.1	12.5
55–64	100.0	66.8	6.0	17.4	2.2	7.5
65–74	100.0	63.5	17.3	12.9	1.5	4.8
75–84	100.0	49.2	38.1	7.5	0.8	4.3
85–89.	100.0	30.7	59.7	4.8	0.5	4.3
90–94	100.0	17.9	73.1	3.8	0.4	4.8
95–99	100.0	9.0	82.0	3.3	0.4	5.3
100 years and over	100.0	6.9	80.5	4.0	0.5	8.1
ree years and ever received		0.0	00.0		0.0	0
MALE						
15–24	100.0	5.7	0.1	0.4	0.3	93.5
25–34	100.0	44.7	0.2	5.4	2.0	47.8
35–44	100.0	63.4	0.4	11.6	2.7	21.9
45–54	100.0	66.6	1.0	15.7	2.6	14.1
55–64	100.0	72.2	2.5	15.3	2.0	8.0
65–74	100.0	75.2	7.2	11.1	1.6	4.9
75–84	100.0	70.2	17.9	6.6	1.0	4.2
85–89	100.0	58.5	32.9	4.1	0.7	3.8
90–94	100.0	45.6	46.8	3.4	0.6	3.5
95–99	100.0	31.7	60.9	3.0	0.5	4.0
100 years and over	100.0	24.7	57.3	6.3	1.3	10.4
FEMALE						
15–24	100.0	9.5	0.1	0.8	0.7	88.8
25–34	100.0	51.5	0.4	7.4	3.4	37.3
35–44	100.0	63.8	1.1	14.3	4.1	16.7
45–54	100.0	63.7	3.2	18.6	3.6	11.0
55–64	100.0	61.9	9.2	19.4	2.4	7.1
65–74	100.0	53.5	25.9	14.4	1.5	4.7
75–84	100.0	34.8	52.0	8.2	0.7	4.4
85–89	100.0	16.3	73.6	5.1	0.4	4.6
90–94	100.0	7.4	83.1	3.9	0.3	5.3
95–99	100.0	3.1	87.5	3.4	0.3	5.6
100 years and over	100.0	2.7	86.1	3.4	0.2	7.5

Note: Percentages may not sum to the row totals due to rounding.

Source: U.S. Census Bureau, American Community Survey, 2006–2008.

Appendix Table 2-B. Marital Status for Population Aged 65 and Over by Age and Sex: 2006–2008

(In percent. Data based on sample. For information on confidentiality protection, sampling error, nonsampling error, and definitions, see www.census.gov/acs/www/)

Sex and age	Married	Widowed	Divorced	Separated	Never married
BOTH SEXES					
Total	100.0	100.0	100.0	100.0	100.0
65–74	61.1	28.5	67.1	69.1	53.7
75–84	32.4	43.0	26.8	25.3	32.9
85–89	5.2	17.3	4.4	3.9	8.4
90–94	1.2	8.4	1.4	1.3	3.7
95–99	0.2	2.4	0.3	0.3	1.1
100 years and over	-	0.4	0.1	0.1	0.3
MALE					
Total	100.0	100.0	100.0	100.0	100.0
65–74	58.9	29.0	70.1	67.7	60.4
75–84	33.4	43.6	25.4	26.9	31.2
85–89	6.0	17.3	3.4	4.1	6.0
90–94	1.5	7.9	0.9	1.1	1.8
95–99	0.2	2.0	0.2	0.2	0.4
100 years and over	-	0.3	-	0.1	0.2
FEMALE					
Total	100.0	100.0	100.0	100.0	100.0
65–74	63.9	28.4	65.3	70.5	49.0
75–84	31.0	42.8	27.7	23.8	33.9
85–89	4.2	17.3	4.9	3.8	10.3
90–94	0.8	8.5	1.7	1.5	5.0
95–99	0.1	2.5	0.4	0.4	1.5
100 years and over	-	0.4	0.1	0.1	0.4

⁻ Represents or rounds to 0.0.

Note: Percentages may not sum to the column totals due to rounding.

Source: U.S. Census Bureau, American Community Survey, 2006–2008.

Appendix Table 3-A. Living Arrangements for Population Aged 65 and Over by Age, Sex, and Type: 2006–2008

(In percent. Data based on sample. For information on confidentiality protection, sampling error, nonsampling error, and definitions, see www.census.gov/acs/www/)

Say and age		House	ehold	Group quarters		
Sex and age	Total	Living with others	Living alone	Institutionalized	Noninstitutionalized	
BOTH SEXES						
65–69	100.0	78.2	20.3	1.0	0.4	
70–74	100.0	74.4	23.6	1.6	0.4	
75–79	100.0	67.7	28.7	3.0	0.6	
80–84	100.0	58.4	35.1	5.6	0.9	
85–89	100.0	47.9	39.3	11.2	1.6	
90–94	100.0	38.6	38.9	19.8	2.7	
95–99	100.0	32.3	33.2	31.0	3.5	
100 years and over	100.0	32.6	25.2	38.2	4.0	
MALE						
65–69	100.0	83.4	14.9	1.2	0.5	
70–74	100.0	82.5	15.6	1.5	0.4	
75–79	100.0	79.6	17.3	2.5	0.5	
80–84	100.0	73.9	21.2	4.2	0.7	
85–89	100.0	65.7	25.2	7.9	1.2	
90–94	100.0	54.8	30.1	13.0	2.1	
95–99	100.0	44.5	31.1	22.2	2.2	
100 years and over	100.0	52.7	25.6	18.7	2.9	
FEMALE						
65–69	100.0	73.6	25.1	0.9	0.4	
70–74	100.0	67.7	30.2	1.7	0.4	
75–79	100.0	58.9	37.2	3.3	0.6	
80–84	100.0	48.7	43.8	6.4	1.1	
85–89	100.0	38.6	46.6	12.9	1.9	
90–94	100.0	32.3	42.2	22.4	3.0	
95–99	100.0	29.1	33.7	33.3	3.8	
100 years and over	100.0	27.8	25.1	42.8	4.3	

Note: Percentages may not sum to the row totals due to rounding.

Source: U.S. Census Bureau, American Community Survey, 2006–2008.

Appendix Table 3-B. Living Arrangements for Population Aged 65 and Over by Age and Sex: 2006-2008

(In percent. Data based on sample. For information on confidentiality protection, sampling error, nonsampling error, and definitions, see www.census.gov/acs/www/)

Cov. and and	House	ehold	Group quarters		
Sex and age	Living with others	Living alone	Institutionalized	Noninstitutionalized	
BOTH SEXES					
Total	100.0	100.0	100.0	100.0	
65–69	33.0	21.1	7.1	16.4	
70–74	25.1	19.6	8.9	12.5	
75–79	19.8	20.7	14.2	15.1	
80–84	13.2	19.5	20.5	18.5	
85–89	6.4	12.9	24.2	19.4	
90–94	2.0	5.1	17.0	12.9	
95–99	0.4	1.1	6.8	4.2	
100 years and over	0.1	0.1	1.4	0.8	
MALE					
Total	100.0	100.0	100.0	100.0	
65–69	33.3	26.6	13.3	26.8	
70–74	25.5	21.6	13.2	15.8	
75–79	20.1	19.6	17.7	17.2	
80–84	13.1	16.8	20.9	16.0	
85–89	6.1	10.5	20.3	14.1	
90–94	1.6	4.0	10.7	8.1	
95–99	0.3	0.8	3.5	1.6	
100 years and over	_	0.1	0.5	0.3	
FEMALE					
Total	100.0	100.0	100.0	100.0	
65–69	32.7	19.1	4.6	11.2	
70–74	24.7	18.8	7.1	10.8	
75–79	19.5	21.1	12.8	14.1	
80–84	13.3	20.5	20.3	19.7	
85–89	6.7	13.8	25.7	22.1	
90–94	2.4	5.4	19.5	15.4	
95–99	0.6	1.2	8.2	5.6	
100 years and over	0.1	0.2	1.8	1.1	

Represents or rounds to 0.0.

Note: Percentages may not sum to the column totals due to rounding.

Source: U.S. Census Bureau, American Community Survey, 2006-2008.

90+ in the United States: 2006-2008 27 U.S. Census Bureau