

Guidelines for the Use of Antiretroviral Agents in HIV-1-Infected Adults and Adolescents

Downloaded from http://aidsinfo.nih.gov/guidelines on 3/17/2013

Visit the AIDS*info* website to access the most up-to-date guideline.

Register for e-mail notification of guideline updates at http://aidsinfo.nih.gov/e-news.

HIV and Illicit Drug Users (Last updated March 27, 2012; last reviewed March 27, 2012)

Treatment Challenges of HIV-Infected Illicit Drug Users

Injection drug use is the second most common mode of HIV transmission in the United States. In addition, noninjection illicit drug use may facilitate sexual transmission of HIV. Injection and noninjection illicit drugs include the following: heroin, cocaine, marijuana, and club drugs (i.e., methamphetamine, ketamine, gammahydroxybutyrate [GHB], and amyl nitrate [i.e., poppers]). The most commonly used illicit drugs associated with HIV infection are heroin and stimulants (e.g., cocaine and amphetamines); however, the use of club drugs has increased substantially in the past several years and is common among individuals who have HIV infection or who are at risk of HIV infection. The association between club drugs and high-risk sexual behavior in men who have sex with men (MSM) is strongest for methamphetamine and amyl nitrate; this association is less consistent with the other club drugs.¹

Illicit drug use has been associated with depression and anxiety, either as part of the withdrawal process or as a consequence of repeated use. This is particularly relevant in the treatment of HIV infection because depression is one of the strongest predictors of poor adherence and poor treatment outcomes.² Treatment of HIV disease in illicit drug users can be successful but HIV-infected illicit drug users present special treatment challenges. These challenges may include the following: (1) an array of complicating comorbid medical and mental health conditions; (2) limited access to HIV care; (3) inadequate adherence to therapy; (4) medication side effects and toxicities; (5) the need for substance abuse treatment; and (6) drug interactions that can complicate HIV treatment.³

Underlying health problems in injection and noninjection drug users result in increased morbidity and mortality, either independent of or accentuated by HIV disease. Many of these problems are the consequence of prior exposures to infectious pathogens from nonsterile needle and syringe use. Such problems can include hepatitis B or C virus infection, tuberculosis (TB), skin and soft tissue infections, recurrent bacterial pneumonia, and endocarditis. Other morbidities such as alteration in levels of consciousness and neurologic and renal disease are not uncommon. Furthermore, these comorbidities are associated with a higher risk of drug overdoses in illicit drug users with HIV disease than in HIV-uninfected illicit drug users, due in part to respiratory, hepatic, and neurological impairments associated with HIV infection. Successful HIV therapy for illicit drug users often depends on clinicians becoming familiar with and managing these comorbid conditions and providing overdose prevention support.

Illicit drug users have less access to HIV care and are less likely to receive antiretroviral therapy (ART) than other populations. ⁵⁻⁶ Factors associated with low rates of ART use among illicit drug users include active drug use, younger age, female gender, suboptimal health care, recent incarceration, lack of access to rehabilitation programs, and health care providers' lack of expertise in HIV treatment. ⁵⁻⁶ The typically unstable, chaotic life patterns of many illicit drug users; the powerful pull of addictive substances; and common misperceptions about the dangers, impact, and benefits of ART all contribute to decreased adherence. ⁷ The chronic and relapsing nature of substance abuse as a biologic and medical disease, compounded by the high rate of mental illness that antedates and/or is exacerbated by illicit substance use, additionally complicate the relationship between health care workers and illicit drug users. ⁸⁻⁹ The first step in provision of care and treatment for these individuals is to recognize the existence of a substance abuse problem. It is often obvious that the problem exists, but some patients may hide these problem behaviors from clinicians. Assessment of a patient for substance abuse should be part of routine medical history taking and should be done in a professional, straightforward, and nonjudgmental manner.

Treatment Efficacy in HIV-Infected Illicit Drug Use Populations

Although illicit drug users are underrepresented in HIV therapy clinical trials, available data indicate that efficacy of ART in illicit drug users—when they are not actively using drugs—is similar to that seen in other

populations.¹⁰ Furthermore, therapeutic failure in this population generally correlates with the degree that drug use disrupts daily activities rather than with drug use per se.¹¹ Providers need to remain attentive to the possible impact of disruptions caused by drug use on the patient both before and while receiving ART. Although many illicit drug users can sufficiently control their drug use for long enough time to benefit from care, substance abuse treatment is often necessary for successful HIV management.

Close collaboration with substance abuse treatment programs and proper support and attention to this population's special multidisciplinary needs are critical components of successful HIV treatment. Essential to this end are accommodating, flexible, community-based HIV care sites that are characterized by familiarity with and nonjudgmental expertise in management of drug users' wide array of needs and in development of effective strategies to promote medication adherence. These strategies should include, if available, the use of adherence support mechanisms such as modified directly observed therapy (mDOT), which has shown promise in this population. 12

Antiretroviral Agents and Opioid Substitution Therapy

Compared with noninjection drug users receiving ART, injection drug users (IDUs) receiving ART are more likely to experience an increased frequency of side effects and toxicities of ART. Although not systematically studied, this is likely because underlying hepatic, renal, neurologic, psychiatric, gastrointestinal (GI), and hematologic disorders are highly prevalent among IDUs. These comorbid conditions should be considered when selecting antiretroviral (ARV) agents in this population. Opioid substitution therapies such as methadone and buprenorphine/naloxone and extended-release naltrexone are commonly used for management of opioid dependence in HIV-infected patients.

Methadone and Antiretroviral Therapy. Methadone, an orally administered, long-acting opioid agonist, is the most common pharmacologic treatment for opioid addiction. Its use is associated with decreased heroin use, decreased needle sharing, and improved quality of life. Because of its opioid-induced effects on gastric emptying and the metabolism of cytochrome P (CYP) 450 isoenzymes 2B6, 3A4, and 2D6, pharmacologic effects and interactions with ARV agents may commonly occur. These may diminish the effectiveness of either or both therapies by causing opioid withdrawal or overdose, increased methadone toxicity, and/or decreased ARV efficacy. Efavirenz (EFV), nevirapine (NVP), and lopinavir/ritonavir (LPV/r) have been associated with significant decreases in methadone levels. Patients and substance abuse treatment facilities should be informed of the likelihood of this interaction. The clinical effect is usually seen after 7 days of coadministration and may be managed by increasing the methadone dosage, usually in 5-mg to 10-mg increments daily until the desired effect is achieved.

Buprenorphine and Antiretroviral Therapy. Buprenorphine, a partial μ-opioid agonist, is administrated sublingually and is often coformulated with naloxone. It is increasingly used for opioid dependence treatment. Compared with methadone, buprenorphine has a lower risk of respiratory depression and overdose. This allows physicians in primary care to prescribe buprenorphine for the treatment of opioid dependency. The flexibility of the primary care setting can be of significant value to opioid-addicted HIV-infected patients who require ART because it enables one physician or program to provide both medical and substance abuse services. Limited information is currently available about interactions between buprenorphine and ARV agents. ¹³⁻¹⁴ Findings from available studies show that the drug interaction profile of buprenorphine is more favorable than that of methadone.

Naltrexone and Antiretroviral Therapy. A once-monthly extended-release intramuscular formulation of naltrexone was recently approved for prevention of relapse in patients who have undergone an opioid detoxification program. Naltrexone is also indicated for treatment of alcohol dependency. Naltrexone is not metabolized via the CYP450 enzyme system and is not expected to interact with protease inhibitors (PIs) or non-nucleoside reverse transcriptase inhibitors (NNRTIs).¹⁵

<u>Table 11</u> provides the currently available pharmacokinetic (PK) interaction data that clinicians can use as a guide for managing patients receiving ART and methadone or buprenorphine. Particular attention is needed concerning communication between HIV care providers and drug treatment programs regarding additive drug toxicities and drug interactions resulting in opiate withdrawal or excess.

Methylenedioxymethamphetamine (MDMA), GHB, ketamine, and methamphetamine all have the potential to interact with ARV agents because all are metabolized, at least in part, by the CYP450 system. Overdoses secondary to interactions between the party drugs (i.e., MDMA or GHB) and PI-based ART have been reported.¹⁶

Summary

It is usually possible over time to support most active drug users such that acceptable adherence levels with ARV agents can be achieved. 17-18 Providers must work to combine all available resources to stabilize an active drug user in preparation for ART. This should include identification of concurrent medical and psychiatric illnesses, drug treatment and needle and syringe exchange programs, strategies to reduce high-risk sexual behavior, and harm-reduction strategies. A history of drug use alone is insufficient reason to withhold ART because individuals with a history of prior drug use have adherence rates similar to those who do not abuse drugs.

Important considerations in the selection of successful regimens and the provision of appropriate patient monitoring in this population include need for supportive clinical sites; linkage to substance abuse treatment; and awareness of the interactions between illicit drugs and ARV agents, including the increased risk of side effects and toxicities. Simple regimens should be considered to enhance medication adherence. Preference should be given to ARV agents that have a lower risk of hepatic and neuropsychiatric side effects, simple dosing schedules, and minimal interaction with methadone.

Table 11. Drug Interactions between Antiretroviral Agents and Drugs Used to Treat Opioid Addiction (page 1 of 2)

| Concomitant Drug | Antiretroviral Drug | Pharmacokinetic Interactions Clinical Comments/Recommendations |
|---------------------|-------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Buprenorphine | EFV | buprenorphine AUC ↓ 50%; norbuprenorphine ^a AUC ↓ 71% No withdrawal symptoms reported. No dosage adjustment recommended; however, monitor for withdrawal symptoms. |
| | ETR | buprenorphine AUC ↓ 25% |
| | | No dosage adjustment necessary. |
| | ATV | buprenorphine AUC ↑ 93%; norbuprenorphine AUC ↑ 76%; ↓ ATV levels possible |
| | | Do not co-administer buprenorphine with unboosted ATV. |
| | ATV/r | buprenorphine AUC ↑ 66%; norbuprenorphine AUC ↑ 105% |
| | | Monitor for sedation. Buprenorphine dose reduction may be necessary. |
| | DRV/r | buprenorphine: no significant effect; norbuprenorphine AUC ↑ 46% and C _{min} ↑ 71% |
| | | No dose adjustment necessary. |
| | FPV/r | buprenorphine: no significant effect; norbuprenorphine AUC ↓ 15% |
| | | No dosage adjustment necessary. |
| | TPV/r | buprenorphine: no significant effect; norbuprenorphine AUC, C _{max} , and C _{min} ↓ 80%; TPV C _{min} ↓ 19%–40% |
| | | Consider monitoring TPV level. |
| | 3TC, ddl, TDF, ZDV, NVP, LPV/r, NFV | No significant effect |
| | | No dosage adjustment necessary. |
| | ABC, d4T, FTC, ETR, IDV +/- RTV, SQV/r, RAL, MVC, T20 | No data |
| Methadone | ABC | methadone clearance ↑ 22% |
| | | No dosage adjustment necessary. |
| | d4T | d4T AUC ↓ 23% and C _{max} ↓ 44% |
| | | No dosage adjustment necessary. |
| | ZDV | ZDV AUC ↑ 29%-43% |
| | | Monitor for ZDV-related adverse effects. |
| | EFV | methadone AUC ↓ 52% |
| | | Opioid withdrawal common; increased methadone dose often necessary. |

Table 11. Drug Interactions between Antiretroviral Agents and Drugs Used to Treat Opioid Addiction (page 2 of 2)

| Methadone, cont'd | NVP | methadone AUC ↓ 41% |
|-------------------|-------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | | NVP: no significant effect |
| | | Opioid withdrawal common; increased methadone dose often necessary. |
| | ATV/r, DRV/r, FPV/r, IDV/r, LPV/r, SQV/r, TPV/r | With ATV/r, DRV/r, FPV/r: R-methadone ^b AUC ↓ 16%–18%; With LPV/r: methadone AUC ↓ 26%–53%; With SQV/r 1000/100 mg BID: R-methadone AUC ↓ 19%; With TPV/r: R-methadone AUC ↓ 48% |
| | | Opioid withdrawal unlikely but may occur. Adjustment of methadone dose usually not required; however, monitor for opioid withdrawal and increase methadone dose as clinically indicated. |
| | FPV | No data with FPV (unboosted) With APV: R-methadone C _{min} ↓ 21%, no significant change in AUC |
| | | Monitor and titrate methadone as clinically indicated. The interaction with FPV is presumed to be similar. |
| | NFV | methadone AUC ↓ 40% |
| | | Opioid withdrawal rarely occurs. Monitor and titrate dose as clinically indicated. May require increased methadone dose. |
| | ddl (EC capsule), | No significant effect |
| | 3TC, TDF, ETR, RTV, ATV, IDV, RAL | No dosage adjustment necessary. |
| | FTC, MVC, T20 | No data |

^a Norbuprenorphine is an active metabolite of buprenorphine.

Key to Abbreviations: 3TC = lamivudine, ABC = abacavir, APV = amprenavir, ATV = atazanavir, ATV/r = atazanavir/ ritonavair, AUC = area under the curve, BID = twice daily, C_{max} = maximum plasma concentration, C_{min} = minimum plasma concentration, d4T = stavudine, ddI = didanosine, DRV/r = darunavir/ritonavir, EC = enteric coated, EFV = efavirenz, ETR = etravirine, FPV = fosamprenavir, FPV/r = fosamprenavir/ritonavir, FTC = emtricitabine, IDV = indinavir, IDV/r = indinavir/ritonavir, LPV/r = lopinavir/ritonavir, MVC = maraviroc, NFV = nelfinavir, NVP = nevirapine, RAL = raltegravir, RTV = ritonavir, SQV/r = sacquinavir/ritonavir, T20 = enfuvirtide, TDF = tenofovir, TPV = tipranavir/ritonavir, ZDV = zidovudine

References

- 1. Colfax G, Guzman R. Club drugs and HIV infection: a review. Clin Infect Dis. May 15 2006;42(10):1463-1469.
- Tucker JS, Burnam MA, Sherbourne CD, Kung FY, Gifford AL. Substance use and mental health correlates of nonadherence to antiretroviral medications in a sample of patients with human immunodeficiency virus infection. *Am J Med.* May 2003;114(7):573-580.
- 3. Bruce RD, Altice FL, Gourevitch MN, Friedland GH. Pharmacokinetic drug interactions between opioid agonist therapy and antiretroviral medications: implications and management for clinical practice. *J Acquir Immune Defic Syndr*. Apr 15 2006;41(5):563-572.
- 4. Wang C, Vlahov D, Galai N, et al. The effect of HIV infection on overdose mortality. AIDS. Jun 10 2005;19(9):935-942.
- 5. Strathdee SA, Palepu A, Cornelisse PG, et al. Barriers to use of free antiretroviral therapy in injection drug users. *JAMA*. Aug 12 1998;280(6):547-549.
- 6. Celentano DD, Vlahov D, Cohn S, Shadle VM, Obasanjo O, Moore RD. Self-reported antiretroviral therapy in injection

^b R-methadone is the active form of methadone.

- drug users. JAMA. Aug 12 1998;280(6):544-546.
- 7. Altice FL, Mostashari F, Friedland GH. Trust and the acceptance of and adherence to antiretroviral therapy. *J Acquir Immune Defic Syndr*. Sep 1 2001;28(1):47-58.
- 8. Altice FL, Kamarulzaman A, Soriano VV, Schechter M, Friedland GH. Treatment of medical, psychiatric, and substance-use comorbidities in people infected with HIV who use drugs. *Lancet*. Jul 31 2010;376(9738):367-387.
- 9. Bruce RD, Altice FL, Friedland GH, Volberding P. HIV Disease Among Substance Misusers: Treatment Issues. *Global AIDS/HIV Medicine*. San Diego, CA: Elsevier Inc; 2007:513-526.
- 10. Morris JD, Golub ET, Mehta SH, Jacobson LP, Gange SJ. Injection drug use and patterns of highly active antiretroviral therapy use: an analysis of ALIVE, WIHS, and MACS cohorts. *AIDS Res Ther*. 2007;4:12.
- 11. Bouhnik AD, Chesney M, Carrieri P, et al. Nonadherence among HIV-infected injecting drug users: the impact of social instability. *J Acquir Immune Defic Syndr*. Dec 15 2002;31(Suppl 3):S149-153.
- 12. Altice FL, Maru DS, Bruce RD, Springer SA, Friedland GH. Superiority of directly administered antiretroviral therapy over self-administered therapy among HIV-infected drug users: a prospective, randomized, controlled trial. *Clin Infect Dis.* Sep 15 2007;45(6):770-778.
- 13. Gruber VA, McCance-Katz EF. Methadone, buprenorphine, and street drug interactions with antiretroviral medications. *Curr HIV/AIDS Rep.* Aug 2010;7(3):152-160.
- 14. Bruce RD, McCance-Katz E, Kharasch ED, Moody DE, Morse GD. Pharmacokinetic interactions between buprenorphine and antiretroviral medications. *Clin Infect Dis.* Dec 15 2006;43(Suppl 4):S216-223.
- Food and Drug Administration (FDA). Vivitrol (package insert). October 2010. http://www.accessdata.fda.gov/drugsatfda_docs/label/2010/021897s015lbl.pdf.
- Bruce RD, Altice FL, Gourevitch MN, Friedland GH. A review of pharmacokinetic drug interactions between drugs of abuse and antiretroviral medications: Implications and management for clinical practice. *Exp Rev of Clin Pharmacol*. 2008;1(1):115-127.
- 17. Hicks PL, Mulvey KP, Chander G, et al. The impact of illicit drug use and substance abuse treatment on adherence to HAART. *AIDS Care*. Oct 2007;19(9):1134-1140.
- 18. Cofrancesco J, Jr., Scherzer R, Tien PC, et al. Illicit drug use and HIV treatment outcomes in a US cohort. *AIDS*. Jan 30 2008;22(3):357-365.