Bladder

C670-C679

(Except for M9727, 9733, 9741-9742, 9764-9809, 9832, 9840-9931, 9945-9946, 9950-9967, 9975-9992)

Codes

- 00 None; no surgery of primary site; autopsy ONLY
- 10 Local tumor destruction, NOS
 - 11 Photodynamic therapy (PDT)
 - 12 Electrocautery; fulguration (includes use of hot forceps for tumor destruction)
 - 13 Cryosurgery
 - 14 Laser
 - 15 Intravesical therapy
 - Bacillus Calmette-Guerin (BCG) or other immunotherapy [*SEER Note:* Code BCG as both surgery and immunotherapy]

Also code the introduction of immunotherapy in the immunotherapy items. If immunotherapy is followed by surgery of the type coded 20-80, code that surgery instead and code the immunotherapy only as immunotherapy.

No specimen sent to pathology from surgical events 10-16

- 20 Local tumor excision, NOS
 - 26 Polypectomy
 - 27 Excisional biopsy

[**SEER Note:** Code TURB as 27]

Combination of 20 or 26-27 WITH

- 21 Photodynamic therapy (PDT)
- 22 Electrocautery
- 23 Cryosurgery
- 24 Laser ablation
- 25 Laser excision
- 30 Partial cystectomy
- 50 Simple/total/complete cystectomy
- 60 Complete cystectomy with reconstruction

[**SEER Note:** Use code 71 for cystoprostatectomy.]

- 61 Radical cystectomy PLUS ileal conduit
- 62 Radical cystectomy PLUS continent reservoir or pouch, NOS
- 63 Radical cystectomy PLUS abdominal pouch (cutaneous)
- 64 Radical cystectomy PLUS in situ pouch (orthotopic)

When the procedure is described as a pelvic exenteration for males, but the prostate is not removed, the surgery should be coded as a cystectomy (code 60-64).

- 70 Pelvic exenteration, NOS
 - 71 Radical cystectomy including anterior exenteration

[**SEER Note:** Use code 71 for cystoprostatectomy.]

SEER Program Coding and Staging Manual 2012

For females, includes removal of bladder, uterus, ovaries, entire vaginal wall, and entire urethra. For males, includes removal of the prostate. When a procedure is described as a pelvic exenteration for males, but the prostate is not removed, the surgery should be coded as a cystectomy (code 60-64).

72 Posterior exenteration

For females, also includes removal of vagina, rectum and anus. For males, also includes prostate, rectum and anus.

73 Total exenteration

Includes all tissue and organs removed for an anterior and posterior exenteration.

[**SEER Note:** Includes removal of all pelvic contents and pelvic lymph nodes. The lymph node dissection should also be coded under Scope of Regional Lymph Node Surgery (NAACCR item # 1292).]

74 Extended exenteration

Includes pelvic blood vessels and/or bony pelvis

80 Cystectomy, NOS

Specimen sent to pathology from surgical events 20-80.

- 90 Surgery, NOS
- 99 Unknown if surgery performed; death certificate ONLY