# Bordetella hinzii in Rodents, Southeast Asia

To the Editor: Bacteria of the genus Bordetella are gram-negative, rod-shaped organisms that cause respiratory tract diseases in humans and animals. In 1995, Bordetella hinzii was isolated from poultry and 2 patients in the United States and France (1). This pathogen colonizes the respiratory tract of poultry and is closely related to B. avium, which is a commensal species in poultry. However, information on the etiologic role, hosts, and transmission routes of B. hinzii is incomplete because infections in human who did not have any close contact with poultry have been reported, mainly in immunocompromised patients (1-5). We obtained a single isolate of B. hinzii from blood agar culture during screening for bacterial zoonotic diseases in blood samples of rodents in Southeast Asia during the Ceropath project (www.ceropath.org).

During 2008–2010, we collected rodents along the Mekong River areas of 3 countries in Southeast Asia (Cambodia, Laos, and Thailand). Rodents were trapped in urban areas and in rural areas, which consisted of forests, upland and dry agricultural areas (orchards, cassava fields), unirrigated and irrigated agricultural areas (rice fields), and domestic areas (isolated farms and villages). Each animal was identified at the species level by using morphologic or molecular methods. Two hundred six blood samples were cultured on Columbia agar containing 5% sheep blood and incubated at 37°C for 3-7 days. A single atypical isolate was observed after 2 days of culture. This isolate was identified by using matrixassisted laser desorption ionization time-of-flight mass spectrometry as described by Seng et al. (6). However, this isolate was identified only at

the genus level as a *Bordetella* sp. (score 1.7).

identify То the Bordetella species, DNA from the isolate was extracted by using the QIAamp DNA Kit (OIAGEN, Hilden, Germany). amplification Partial PCR and sequencing of 16S rRNA gene was performed as described (7). Sequence analysis showed that the isolate was closely related to B. hinzii LMG 13501 (99.0% homology), which was isolated from the blood of a patient who died of septicemia in 2000(2). The 16S rRNA sequence of our isolate (B. hinzii L135) has been deposited in GenBank under accession no. JX188059. A phylogenetic analysis of the new sequence and sequences of other bacteria in the genus Bordetella is shown in the Figure.

*B. hinzii* is a causative agent of respiratory tract illnesses in birds and has been described as an emerging and opportunistic pathogen in immunocompromised patients; and in patients with AIDS, cystic fibrosis, and fatal septicemia (1-5). However, the source of transmission is not clear. Although *B. hinzii* is commensal in birds, several cases were reported in persons who did not have any close

contact with birds (2-5), suggesting alternative sources of contamination. Thus, transmission routes and reservoirs of *B. hinzii* infection are ambiguous. *B. hinzii* infection has also been reported in rabbits and laboratory mice in Hungary and Japan (8-10). Rodents were suspected to be potential reservoirs but, to the best of our knowledge, this emerging pathogen has not been reported in wild rodents.

We detected in B. hinzii in a Rattus tanezumi rat that was trapped in upland agricultural area in Laos. R. tanezumi rats are the most common rodent in southeastern Asia and can be found in various habitats, including forests, agricultural areas, and houses. In Southeast Asia, human populations in several countries (Cambodia, Laos, and Thailand) live in close contact with rodents (including R. tanezumi) or share the environment with them. These rodents are known to be a reservoir and possible source of bacterial zoonoses such as leptospirosis, plague, scrub typhus, and murine typhus.

Our findings suggest that *B. hinzii* isolated from wild rodents may serve as reservoir for this bacterial species that could be transmitted to human or pets. *B. hinzii* should be added to




Figure. Maximum-parsimony phylogenetic tree of 16S rRNA gene of *Bordetella hinzii* isolate from this study (L135) and validated *Bordetella* species. Numbers along branches indicate bootstrap values. Scale bar indicates nucleotide substitutions per site.

the list of emerging bacterial zoonotic agents in wild rodents that could be pathogenic for humans. Further studies are warranted to evaluate the prevalence of this bacterium in rodents in other countries and to demonstrate that rodents may be a source of transmission of this bacterium to humans, especially immunocompromised patients.

### Acknowledgments

We thank Annick Bernard and Linda Hadjadj for technical assistance.

This study was supported by the French National Research Agency; CERoPath (Community Ecology of Rodents and their Pathogens in Southeast Asia Project ANR 07 BDIV 012); Infectiopôle Sud; Center for Excellence on Agricultural Biotechnology; the Science and Technology Postgraduate Education and Research Development Office; the Office of Higher Education Commission, Ministry of Education (AG-BIO/PERDO-CHE); and the Center of Advanced Studies for Agriculture and Food, Institute for Advanced Studies, Kasetsart University.

### Tawisa Jiyipong, Serge Morand, Sathaporn Jittapalapong, Didier Raoult, and Jean-Marc Rolain

Author affiliations: Aix-Marseille Université, Marseille, France (T. Jiyipong, D. Raoult, J.-M. Rolain); Université Montpellier 2, Montpellier (S. Morand); Kasetsart University, Bangkok, Thailand (T. Jiyipong, S. Jittapalapong); Kasetsart University, Nakhon Pathom, Thailand (T. Jiyipong); Center of Excellence on Agricultural Biotechnology, Bangkok (T. Jiyipong)

DOI: http://dx.doi.org/10.3201/eid1903.120987

#### References

 Vandamme P, Hommez J, Vancanneyt M, Monsieurs M, Hoste B, Cookson B, et al. *Bordetella hinzii* sp. nov., isolated from poultry and humans. Int J Syst Bacteriol. 1995;45:37–45. http://dx.doi. org/10.1099/00207713-45-1-37

- Kattar MM, Chavez JF, Limaye AP, Rassoulian-Barrett SL, Yarfitz SL, Carlson LC, et al. Application of 16S rRNA gene sequencing to identify *Bordetella hinzii* as the causative agent of fatal septicemia. J Clin Microbiol. 2000;38:789–94.
- Arvand M, Feldhues R, Mieth M, Kraus T, Vandamme P. Chronic cholangitis caused by *Bordetella hinzii* in a liver transplant recipient. J Clin Microbiol. 2004;42:2335– 7. http://dx.doi.org/10.1128/JCM.42.5. 2335-2337.2004
- Fry NK, Duncan J, Edwards MT, Tilley RE, Chitnavis D, Harman R, et al. A UK clinical isolate of *Bordetella hinzii* from a patient with myelodysplastic syndrome. J Med Microbiol. 2007;56:1700–3. http://dx.doi.org/10.1099/jmm.0. 47482-0
- Funke G, Hess T, von Graevenitz A, Vandamme P. Characteristics of *Bordetella hinzii* strains isolated from a cystic fibrosis patient over a 3-year period. J Clin Microbiol. 1996;34:966–9.
- Seng P, Drancourt M, Gouriet F, La Scola B, Fournier PE, Rolain JM, et al. Ongoing revolution in bacteriology: routine identification of bacteria by matrix-assisted laser desorption ionization time-of-flight mass spectrometry. Clin Infect Dis. 2009;49:543–51. http://dx.doi. org/10.1086/600885
- Weisburg WG, Barns SM, Pelletier DA, Lane DJ. 16S ribosomal DNA amplification for phylogenetic study. J Bacteriol. 1991;173:697–703.
- Register KB, Sacco RE, Nordholm GE. Comparison of ribotyping and restriction enzyme analysis for inter- and intraspecies discrimination of *Bordetella avium* and *Bordetella hinzii*. J Clin Microbiol. 2003;41:1512–9. http://dx.doi. org/10.1128/JCM.41.4.1512-1519.2003
- Hayashimoto N, Morita H, Yasuda M, Ishida T, Kameda S, Takakura A, et al. Prevalence of *Bordetella hinzii* in mice in experimental facilities in Japan. Res Vet Sci. 2012. 93:624–6. PubMed
- Hayashimoto N, Yasuda M, Goto K, Takakura A, Itoh T. Study of a *Bordetella hinzii* isolate from a laboratory mouse. Comp Med. 2008;58:440–6.

Address for correspondence: Jean-Marc Rolain, Unité des Rickettsies, Unité de Recherche sur les Maladies Infectieuses et Tropicales Émergentes, Centre National de la Recherche Scientifique–Institut de Recherche pour le Développement, Unités Mixtes de Recherché 6236, Faculté de Médecine et de Pharmacie, Aix-Marseille Université, 27 Bd Jean Moulin 13385 Marseille, France; email: jean-marc. rolain@univmed.fr

# Melioidosis and Hairy Cell Leukemia in 2 Travelers Returning from Thailand

To the Editor: Patients with underlying medical conditions travel more than ever (1), and such travelers may be exposed to uncommon infections (2). We report 2 cases of melioidosis and hairy cell leukemia in travelers returning from Thailand.

Case-patient 1 was a 48-year-old man hospitalized in Paris with fever, asthenia, chills, and pancytopenia after returning from a 1-week visit to Thailand where he had been in flooded regions (Koh Samui and Koh Samet). Clinical examination showed a temperature of 40°C and mucocutaneous pallor. Laboratory tests showed a hemoglobin level of 7.9 g/dL, a platelet count of  $33 \times 10^{9}$ /L, a leukocyte count of  $1.3 \times 10^9$  cells/L, a polymorphonuclear cell count of  $0.77 \times 10^9$  cells/L, a monocyte count of 0, and a C-reactive protein level of 158 mg/L. Results of tests for HIV, dengue, and malaria were negative.

Presumptive antimicrobial drug treatment with piperacillin/tazobactam (12 g/1.5 g/d) was initiated at admission. A blood smear showed 10% hairy cells, and a bone marrow biopsy confirmed a diagnosis of hairy cell leukemia and interstitial infiltration of CD20-positive, monoclonal antibody DBA.44–positive, and tartrate-resistant acid phosphatase–positive cells.

Because of persistent unexplained fever, full-body computed tomography (CT) was performed and showed multiple liver, spleen, and lung abscesses (Figure, panels A and B). Culture of a CT scan–guided liver abscess puncture specimen was positive for *Bukholderia pseudomallei* after 12 days of antimicrobial drug treatment. Treatment was changed to ceftazidime (120 mg/kg/d) trimethoprim/sulfamethoxazole