Appendix C Site-Specific Coding Modules

Appendix C Table of Contents

| Introduction to Apper | ndix C | 1 |
|-----------------------|---|-----|
| Oral Cavity | | |
| | ary and Histology Coding Rules: Head and Neck 1 | |
| Trianspio I Illia | Equivalent Terms, Definitions, Charts, Tables and Illustrations | 3 |
| | Flowchart | |
| | Multiple Primary Rules | 15 |
| | Histology Coding Rules | |
| | Matrix | |
| | Multiple Primary Rules | 25 |
| | Histology Coding Rules | |
| | Text | |
| | Multiple Primary Rules | 33 |
| | Histology Coding Rules | 35 |
| CS Staging Sch | nemas | |
| | Lip, Upper | 39 |
| | Lip, Lower | 48 |
| | Other Lip. | |
| | Base of Tongue, Lingual Tonsil | |
| | Anterior 2/3 of Tongue, Tip, Border, and Tongue, NOS | |
| | Gum, Upper | |
| | Gum, Lower and Retromolar Area Retromolar Gingiva (Trigone) | |
| | Gum, NOS | |
| | Floor of Mouth | |
| | Hard Palate | |
| | Soft Palate, Uvula | |
| | Other Mouth | |
| 0 0 1 | Cheek (Buccal) Mucosa, Vestibule | |
| | : Oral Cavity ⁴ | 155 |
| Parotid, Other and U | nspecified Glands | |
| | Rules: see Head and Neck pg C-3 ¹ | 156 |
| CS Staging Sch | | |
| | Parotid Gland | |
| | Submandibular Gland | |
| 0 0 1 | Other and Unspecified Major Salivary Glands | |
| | : Parotid and Other Unspecified Glands ⁴ | 183 |
| | pharynx, hypopharynx, Pyriform Sinus | |
| | Rules: see Head and Neck pg C-3 1 | 185 |
| CS Staging Sch | | 106 |
| | Tonsil, Oropharynx | |
| | Anterior Surface of Epiglottis | |
| | Nasopharynx | |
| | Pyriform Sinus, Hypopharynx, Laryngopharynx | |
| C C - 1 | Pharynx, NOS, and other Ill-Defined Oral Cavity Sites | 222 |
| Surgery Codes | Dharuny 4 | 220 |
| | Pharynx ⁴ | 221 |
| | All Other Sites | 231 |

| Esophagus | | |
|----------------------------|---|-----|
| Coding Guidelines | | 233 |
| MP/H Coding Rule | es: see Other Sites pg C-1011 ² | 234 |
| CS Staging Scheme | e: Esophagus | 235 |
| Surgery Codes: Esc | ophagus ⁴ | 242 |
| Stomach | | |
| | es: see Other Sites pg C-1011 ² | 243 |
| | e: Stomach | |
| ~ ~ | mach | |
| Small Intestine | | |
| | es: see Other Sites pg C-1011 ² | 253 |
| | e: Small Intestine | |
| | Other Sites ⁴ | |
| 0 , | Culci Sites | |
| Colon Coding Cuidelines | | 260 |
| Multiple Primary of | nd Histology Coding Rules: Colon ¹ | 200 |
| With the Filliary and | uivalent Terms, Definitions and Illustrations | 261 |
| - | owchart | 201 |
| Fic | Multiple Primary Rules | 265 |
| | Histology Coding Rules | |
| Ma | atrix | |
| IVIC | Multiple Primary Rules | 281 |
| | Histology Coding Rules | |
| Te | | 203 |
| 10. | Multiple Primary Rules | 291 |
| | Histology Coding Rules | |
| CS Staging Scheme | e: Colon | |
| | lon ⁴ | |
| Rectosigmoid, Rectum | | |
| | es: see Other Sites pg C-1011 ² | 207 |
| | e: Rectosigmoid, Rectum | |
| Surgery Codes | . Rectosignioid, Rectuin | |
| | ctosigmoid ⁴ | 315 |
| | ctum ⁴ | |
| | Vidili | |
| Anus MD/H Coding Pula | es: see Other Sites pg C-1011 ² | 210 |
| | e: Anus | |
| | us ⁴ | |
| e ; | | |
| Liver, Intrahepatic Bile D | | 225 |
| | es: see Other Sites pg C-1011 ² | |
| | e: Liver and Intrahepatic Bile Ducts | |
| - · | rer and Intrahepatic Bile Ducts ⁴ | 332 |
| | e Bile Ducts, Ampulla of Vater | |
| | es: see Other Sites pg C-1011 ² | 333 |
| CS Staging Schema | | |
| | llbladder | |
| | trahepatic Bile Duct(s) | |
| | npulla of Vater | |
| | her Biliary and Biliary, NOS | |
| Surgery Codes: All | Other Sites ⁴ | 351 |

| Pancreas | | |
|--------------------------|---|------------|
| MP/H Coding Rules: see | Other Sites pg C-1011 ² | 352 |
| CS Staging Schemas | | |
| | Head | 353 |
| | Body and Tail | |
| | Other and Unspecified | |
| | 4 | |
| • • | | |
| Other Digestive | Other Sites pg C-1011 ² | 269 |
| CS Staging Salamas Oth | on and III Defined Dispositive Organia | |
| Cs Staging Scheme: Oth | er and Ill-Defined Digestive Organs | 309 |
| Surgery Codes: see All C | Other Sites pg C-1011 ⁴ | 3/3 |
| Nasal Cavity, Middle Ear | | |
| | Head and Neck pg C-3 ¹ | 375 |
| CS Staging Schemas | 110dd diid 1700k pg C 3 | |
| | ıvity | 376 |
| | Ear | |
| | Sites ⁴ | |
| • • | Sites | 392 |
| Sinuses | | |
| | Head and Neck pg C-3 ¹ | 393 |
| CS Staging Schemas | | |
| | y Sinus | |
| | Sinus | |
| | ry (Paranasal) Sinus | |
| Surgery Codes: All Other | r Sites ⁴ | 419 |
| Larynx | | |
| | Head and Neck pg C-3 ¹ | 420 |
| CS Staging Schemas | | |
| | arynx | 421 |
| | ottic Larynx | |
| | ic Larynx | |
| | Overlapping Lesion or Not Otherwise Specified | |
| | | |
| Trachea | | |
| | Other Sites pg C-1011 ² | 450 |
| CS Storing Schame: Treel | boo | 460 |
| Co Staging Scheme. Track | hea Sites ⁴ | 400 464 |
| | Sites | 404 |
| Lung | | |
| Coding Guidelines | stology Coding Rules: Lung ¹ | 465 |
| Multiple Primary and His | stology Coding Rules: Lung ¹ | |
| | nt Terms, Definitions, Charts, Tables and Illustrations | 467 |
| Flowcha | rt | |
| I | Multiple Primary Rules | 475 |
|] | Histology Coding Rules | 480 |
| Matrix | | |
| I | Multiple Primary Rules | 487 |
| | Histology Coding Rules | |
| Text | - | |
| | Multiple Primary Rules | 495 |
| | Histology Coding Rules | |
| | g | |
| | | |

| Heart, Mediastinum, Pleura | |
|--|-------------|
| MP/H Coding Rules: see Other Sites pg C-1011 ² | 512 |
| CS Staging Schemas | 510 |
| Heart, Mediastinum | |
| Pleura | |
| Other and Ill-Defined Respiratory Sites and Intrathoracic Organs | |
| Bones, Joints, Cartilage | 520 |
| Coding Guidelines | 527 |
| MP/H Coding Rules: see Other Sites pg C-1011 ² | 528 |
| CS Staging Scheme: Bone | |
| Surgery Codes: Bones, Joints, and Articular Cartilage; Peripheral Nerves | |
| and Autonomic Nervous System; Connective, Subcutaneous, and | |
| Other Soft Tissues ⁴ | 533 |
| Skin | |
| MP/H Coding Rules: see Other Sites pg C-1011 ² | 534 |
| CS Staging Schemas | |
| Skin ³ | 535 |
| Skin of Eyelid | |
| Surgery Codes: Skin ⁴ | 544 |
| Melanoma | |
| Multiple Primary and Histology Coding Rules: Cutaneous Melanoma | |
| Equivalent Terms, Definitions and Illustrations | 547 |
| Flowchart | |
| Multiple Primary Rules | |
| Histology Coding Rules | 556 |
| Matrix | 561 |
| Multiple Primary Rules Histology Coding Rules | |
| Text | 303 |
| Multiple Primary Rules | 565 |
| Histology Coding Rules | |
| CS Staging Scheme: Malignant Melanoma of Skin, Vulva, Penis, Scrotum (8720-8790) Surgery Codes | |
| Skin ⁴ | 578 |
| All Other Sites ⁴ | |
| Mycosis Fungoides, Sezary Disease | |
| MP/H Coding Rules: see Other Sites pg C-1011 ² | 581 |
| CS Staging Scheme: Mycosis Fungoides and Sezary disease of Skin, vulva, | |
| Penis, Scrotum (9700-9701) | 582 |
| Surgery Codes | |
| Skin ⁴ | |
| All Other Sites ⁴ | 588 |
| Nerves, Nervous System, Soft Tissues | |
| Coding Guidelines: Bones, Joints, Cartilage | 589 |
| MP/H Coding Rules: see Other Sites pg C-1011 ² | 590 |
| CS Staging Scheme: Peripheral Nerves and Autonomic Nervous System; | |
| Connective, Subcutaneous, and Other Soft Tissues | 591 |
| Surgery Codes: Bones, Joints, and Articular Cartilage; Peripheral Nerves and | |
| Autonomic Nervous System; Connective, Subcutaneous, and | 50 - |
| Other Soft Tissues ⁴ | 597 |

| Retrop | peritoneum, Peritoneum MP/H Coding Rules: see Other Sites pg C-1011 ² | 500 |
|---------|--|--------------|
| | CS Staging Scheme: Retroperitoneum and Peritonuem | |
| | Surgery Codes: All Other Sites ⁴ | |
| _ | Surgery Codes. All Other Sites | 003 |
| Breast | | 60. 7 |
| | Coding Guidelines: Breast | 605 |
| | Multiple Primary and Histology Coding Rules: Breast ¹ | |
| | Equivalent Terms, Definitions, Tables and Illustrations | 609 |
| | Flowchart | 615 |
| | Multiple Primary Rules | |
| | Histology Coding Rules | 621 |
| | Matrix | (22 |
| | Multiple Primary Rules | |
| | Histology Coding Rules | 635 |
| | Text | (12 |
| | Multiple Primary Rules | |
| | Histology Coding Rules | |
| | CS Staging Scheme: Breast | |
| | Surgery Codes: Breast ⁴ | |
| Vulva, | Vagina | |
| | MP/H Coding Rules: see Other Sites pg C-1011 ² | 665 |
| | CS Staging Schemes | |
| | Vulva | |
| | Vagina | 671 |
| | Surgery Codes: All Other Sites ⁴ | 675 |
| Cervix | | |
| | MP/H Coding Rules: see Other Sites pg C-1011 ² | 676 |
| | CS Staging Scheme: Cervix Uteri | 677 |
| | Surgery Codes: Cervix Uteri ⁴ | 684 |
| Corpus | s Uteri, Uterus, NOS | |
| • | MP/H Coding Rules: see Other Sites pg C-1011 ² | 686 |
| | CS Staging Scheme: Corpus Uteri; Uterus, NOS | |
| | Surgery Codes: Corpus Uteri ⁴ | 692 |
| Ovary | G- J F | |
| Ovary | MP/H Coding Rules: see Other Sites pg C-1011 ² | 694 |
| | CS Staging Scheme: Ovary ⁴ | 695 |
| | Surgery Codes: Ovary 4 | 701 |
| Fallon | ian Tube, Ligaments, Adnexa | / 01 |
| ганорі | MP/H Coding Rules: see Other Sites pg C-1011 ² | 703 |
| | CS Staging Schemas | 703 |
| | Fallopian Tube | 704 |
| | Broad and Round Ligaments, Parametrium, Uterine Adnexa | 710 |
| | Surgery Codes: All Other Sites ⁴ | 714 |
| Other : | and Unspecified Female Genital Organs, Placenta | |
| | MP/H Coding Rules: see Other Sites pg C-1011 ² | 715 |
| | CS Staging Schemas | |
| | Other and Unspecified Female Genital Organs | |
| | Placenta | 720 |
| | Surgery Codes: All Other Sites ⁴ | 725 |
| Penis | MD/H C 1' D 1 Od C' C 1011 2 | 50 (|
| | MP/H Coding Rules: see Other Sites pg C-1011 ² | 726 |
| | CS Staging Scheme: Penis ³ | 721 |
| | Surgery Couch. This Office Street | / 3 1 |

| Prostate | |
|--|-------|
| MP/H Coding Rules: see Other Sites pg C-1011 ² | 732 |
| CS Staging Scheme: Prostate (excludes transitional cell carcinoma of the | |
| prostatic ducts and prostatic urethra. See Urethra pg C-925 | 733 |
| Surgery Codes: Prostate ⁴ | 747 |
| Testis | |
| MP/H Coding Rules: see Other Sites pg C-1011 ² | 749 |
| CS Staging Scheme: Testis | |
| Surgery Codes: Testis ⁴ | |
| Other and Unspecified male Genital Organs | |
| MP/H Coding Rules: see Other Sites pg C-1011 ² | 757 |
| CS Staging Schemas | |
| Other and Unspecified Male Genital Organs (excludes Kaposi sarcoma | |
| and lymphoma) | 758 |
| Scrotum ³ | |
| Surgery Codes: All Other Sites ⁴ | |
| Kidney | |
| Coding Guidelines: Kidney, Renal Pelvis, and Ureter | 760 |
| Multiple Primary and Histology Coding Rules: Kidney ¹ | 10) |
| Equivalent Terms, Definitions, Tables and Illustrations | 770 |
| Flowchart | / / 0 |
| Multiple Primary Rules | 775 |
| Histology Coding Rules | |
| Matrix | 700 |
| Multiple Primary Rules | 787 |
| Histology Coding Rules | |
| Text | , , 0 |
| Multiple Primary Rules | 793 |
| Histology Coding Rules | |
| CS Staging Scheme: Kidney (Renal Parenchyma) | |
| Surgery Codes: Kidney, Renal Pelvis, and Ureter 4 | 803 |
| Renal Pelvis, Ureter | 005 |
| Coding Guidelines: Kidney, Renal Pelvis, and Ureter | 905 |
| Multiple Primary and Histology Coding Rules: Renal Pelvis, Ureter, Bladder and | 603 |
| Other Urinary ¹ | |
| Equivalent Terms, Definitions, Tables and Illustrations | 806 |
| Flowchart | 600 |
| Multiple Primary Rules | 813 |
| Histology Coding Rules | |
| Matrix | 017 |
| Multiple Primary Rules | 823 |
| Histology Coding Rules | |
| Text | 0_0 |
| Multiple Primary Rules | 829 |
| Histology Coding Rules | |
| CS Staging Scheme: Renal Pelvis, and Ureter | |
| Surgery Codes: Kidney, Renal Pelvis, and Ureter 4 | 839 |
| Bladder | |
| Coding Guidelines: Bladder | 841 |
| MP/H Coding Rules: see Renal Pelvis, Ureter, Bladder and Other Urinary | 5 11 |
| pg C-871 ¹ | 845 |
| CS Staging Scheme: Bladder | 846 |
| Surgery Codes: Bladder ⁴ | 852 |

| Urethi | ra, Other Urinary | |
|--------|--|-----|
| | MP/H Coding Rules: see Renal Pelvis, Ureter, Bladder and Other Urinary | |
| | pg C-871 ¹ | 854 |
| | CS Staging Schemas | |
| | Urethra | 855 |
| | Paraurethral Gland, Overlapping lesion of Urinary Organs and | |
| | Unspecified Urinary Organs | |
| | Surgery Codes: All Other Sites ⁴ | 863 |
| Eye | | |
| 2,0 | MP/H Coding Rules: see Other Sites pg C-1011 ² | 864 |
| | CS Staging Schemas | |
| | Conjunctiva (excludes retinoblastoma, malignant melanoma, | |
| | Kaposi sarcoma and lymphoma) | 865 |
| | Malignant Melanoma of Conjunctiva (8720-8790) | |
| | Cornea, Retina, Choroid, Ciliary body (Iris, Lens, Sclera, Ureal Tract), | |
| | Eyeball, Overlapping and Other Eye (excludes melanoma and | |
| | retinoblastoma) | 874 |
| | Malignant Melanoma of Iris and Ciliary Body (8720-8790) | 878 |
| | Malignant Melanoma of Choroid (8720-8790) | 884 |
| | Malignant Melanoma of Other Eye (8720-8790) | 889 |
| | Lacrimal Gland | 892 |
| | Orbit | 895 |
| | Retinoblastoma (9510-9514) | |
| | Surgery Codes: All Other Sites ⁴ | 904 |
| Brain, | Central Nervous System, Malignant | |
| , | Coding Guidelines: Brain | 905 |
| | Multiple Primary and Histology Coding Rules: Brain, Spinal Cord, Cranial Nerves, | |
| | Pituitary gland, Craniopharyngeal duct and Pineal gland ¹ | |
| | Equivalent Terms, Definitions, Charts and Illustrations | 906 |
| | Flowchart | |
| | Multiple Primary Rules | 914 |
| | Histology Coding Rules | 918 |
| | Matrix | |
| | Multiple Primary Rules | |
| | Histology Coding Rules | 924 |
| | Text | |
| | Multiple Primary Rules | |
| | Histology Coding Rules | 928 |
| | CS Staging Shemas | |
| | Brain and Cerebral Meninges | |
| | Other Parts of Central Nervous System | |
| | Surgery Codes: Brain ⁴ | 939 |

| Coding Guidelines: Thyroid Gland. 967 MP/H Coding Rules: see Other Sites pg C-1011 2 968 CS Staging Scheme: Thyroid Gland 969 Surgery Codes: Thyroid Gland 4 976 Thymus, Adrenal and Other Endocrine Glands MP/H Coding Rules: For Malignant Pituitary, Craniopharyngeal duct and Pineal Gland (C751-C753) See Malignant Meninges, Brain, Spinal Cord, Cranial Nerves, Pituitary gland, Craniopharyngeal duct and Pineal gland pg C-981 977 For Benign, Borderline Pituitary, Craniopharyngeal duct and Pineal gland Multiple Primary Rules: See Benign and Borderline Primary Intracranial and CNS Tumors pg C-1017 977 For Thymus, Adrenal gland, Carotid body, Aortic body and other paraganglia, Overlapping lesion of endocrine glands and related structures and Endocrine gland NOS (C379, C740-C741, C749, C754-C759) See Other Sites pg C-1011 977 CS Staging Scheme: Thymus, Adrenal (Suprarenal) Gland, and Other Endocrine Glands. 978 Surgery Codes: All Other Sites 4 983 Kaposi Sarcoma Coding Guidelines: Kaposi Sarcoma of All Sites. 984 MP/H Coding Rules: see Other Sites pg C-1011 986 Surgery Codes: see site-specific codes 990 Lymphoma Coding Guidelines: Lymph Nodes. 991 Multiple Primary Rules: Hematopoietic Primaries 993 CS Staging Scheme: Hodgkin and Non-Hodgkin Lymphomas of All Sites (9350-9729) Surgery Codes | Brain, Central Nervous System, Benign and Borderline | |
|---|--|-----------------|
| Intracranial and CNS Tumors Equivalent Terms, Definitions, Charts and Illustrations | | 940 |
| Fquivalent Terms, Definitions, Charts and Illustrations | Multiple Primary and Histology Coding Rules: Benign and Borderline Primary | |
| Flowchart Multiple Primary Rules | Intracranial and CNS Tumors | |
| Multiple Primary Rules | Equivalent Terms, Definitions, Charts and Illustrations | 941 |
| Histology Coding Rules | Flowchart | |
| Histology Coding Rules | Multiple Primary Rules | 947 |
| Matrix Multiple Primary Rules | | |
| Multiple Primary Rules | The state of the s | |
| Histology Coding Rules | | 956 |
| Text Multiple Primary Rules | | |
| Multiple Primary Rules | The state of the s | |
| Histology Coding Rules | | 961 |
| CS Staging Schemas See Brain and Cerebral Meninges pg C-1007 | | |
| See Brain and Cerebral Meninges pg C-1007 | <i>c. c</i> | 703 |
| See Other Parts of Central Nervous System pg C-1011 965 Surgery Codes: Brain 4 966 Thyroid Coding Guidelines: Thyroid Gland. 967 MP/H Coding Rules: see Other Sites pg C-1011 968 CS Staging Scheme: Thyroid Gland 968 Surgery Codes: Thyroid Gland 969 Surgery Codes: Thyroid Gland 976 Thymus, Adrenal and Other Endocrine Glands MP/H Coding Rules: For Malignant Pituitary, Craniopharyngeal duct and Pineal Gland (C751-C753) See Malignant Meninges, Brain, Spinal Cord, Cranial Nerves, Pituitary gland, Craniopharyngeal duct and Pineal gland pg C-981 977 For Benign, Borderline Pituitary, Craniopharyngeal duct and Pineal gland Multiple Primary Rules: See Benign and Borderline Primary Intracranial and CNS Tumors pg C-1017 977 For Thymus, Adrenal gland, Carotid body, Aortic body and other paraganglia, Overlapping lesion of endocrine glands and related structures and Endocrine gland NOS (C379, C740-C741, C749, C754-C759) See Other Sites pg C-1011 977 CS Staging Scheme: Thymus, Adrenal (Suprarenal) Gland, and Other Endocrine Glands. 978 Surgery Codes: All Other Sites 4 983 Kaposi Sarcoma Coding Guidelines: Kaposi Sarcoma of All Sites. 984 MP/H Coding Rules: see Other Sites pg C-1011 985 CS Staging Scheme: Kaposi Sarcoma of All Sites 990 Lymphoma Coding Guidelines: Lymph Nodes. 991 Multiple Primary Rules: Hematopoietic Primaries 993 CS Staging Scheme: Hodgkin and Non-Hodgkin Lymphomas of All Sites (9590-9729) 995 Surgery Codes | | 065 |
| Surgery Codes: Brain 4 | | |
| Thyroid Coding Guidelines: Thyroid Gland. Coding Guidelines: Thyroid Gland. MP/H Coding Rules: see Other Sites pg C-1011 2 | | |
| Coding Guidelines: Thyroid Gland. 967 MP/H Coding Rules: see Other Sites pg C-1011 2 968 CS Staging Scheme: Thyroid Gland 969 Surgery Codes: Thyroid Gland 4 976 Thymus, Adrenal and Other Endocrine Glands MP/H Coding Rules: For Malignant Pituitary, Craniopharyngeal duct and Pineal Gland (C751-C753) See Malignant Meninges, Brain, Spinal Cord, Cranial Nerves, Pituitary gland, Craniopharyngeal duct and Pineal gland pg C-981 977 For Benign, Borderline Pituitary, Craniopharyngeal duct and Pineal gland Multiple Primary Rules: See Benign and Borderline Primary Intracranial and CNS Tumors pg C-1017 977 For Thymus, Adrenal gland, Carotid body, Aortic body and other paraganglia, Overlapping lesion of endocrine glands and related structures and Endocrine gland NOS (C379, C740-C741, C749, C754-C759) See Other Sites pg C-1011 977 CS Staging Scheme: Thymus, Adrenal (Suprarenal) Gland, and Other Endocrine Glands. 978 Surgery Codes: All Other Sites 4 983 Kaposi Sarcoma Coding Guidelines: Kaposi Sarcoma of All Sites. 984 MP/H Coding Rules: see Other Sites pg C-1011 2 985 CS Staging Scheme: Kaposi Sarcoma of All Sites (9140) 986 Surgery Codes: see site-specific codes 990 Lymphoma Coding Guidelines: Lymph Nodes. 991 Multiple Primary Rules: Hematopoietic Primaries 993 CS Staging Scheme: Hodgkin and Non-Hodgkin Lymphomas of All Sites (9350-9729) 995 Surgery Codes | | 966 |
| MP/H Coding Rules: see Other Sites pg C-1011 2 | Thyroid | |
| CS Staging Scheme: Thyroid Gland 4 | Coding Guidelines: Thyroid Gland | 967 |
| CS Staging Scheme: Thyroid Gland 4 | MP/H Coding Rules: see Other Sites pg C-1011 ² | 968 |
| Surgery Codes: Thyroid Gland 4 | | |
| Thymus, Adrenal and Other Endocrine Glands MP/H Coding Rules: For Malignant Pituitary, Craniopharyngeal duct and Pineal Gland (C751-C753) See Malignant Meninges, Brain, Spinal Cord, Cranial Nerves, Pituitary gland, Craniopharyngeal duct and Pineal gland pg C-981 | Surgery Codes: Thyroid Gland ⁴ | 976 |
| MP/H Coding Rules: For Malignant Pituitary, Craniopharyngeal duct and Pineal Gland (C751-C753) See Malignant Meninges, Brain, Spinal Cord, Cranial Nerves, Pituitary gland, Craniopharyngeal duct and Pineal gland pg C-981 | | |
| For Malignant Pituitary, Craniopharyngeal duct and Pineal Gland (C751-C753) See Malignant Meninges, Brain, Spinal Cord, Cranial Nerves, Pituitary gland, Craniopharyngeal duct and Pineal gland pg C-981 | · | |
| See Malignant Meninges, Brain, Spinal Cord, Cranial Nerves, Pituitary gland, Craniopharyngeal duct and Pineal gland pg C-981 | | 2) |
| Pituitary gland, Craniopharyngeal duct and Pineal gland pg C-981 | | ') |
| For Benign, Borderline Pituitary, Craniopharyngeal duct and Pineal gland Multiple Primary Rules: See Benign and Borderline Primary Intracranial and CNS Tumors pg C-1017 | | 077 |
| Multiple Primary Rules: See Benign and Borderline Primary Intracranial and CNS Tumors pg C-1017 | Pitunary giand, Craniopnaryngeai duct and Pineai giand pg C-981 | 9// |
| Multiple Primary Rules: See Benign and Borderline Primary Intracranial and CNS Tumors pg C-1017 | | |
| Intracranial and CNS Tumors pg C-1017 | | |
| For Thymus, Adrenal gland, Carotid body, Aortic body and other paraganglia, Overlapping lesion of endocrine glands and related structures and Endocrine gland NOS (C379, C740-C741, C749, C754-C759) See Other Sites pg C-1011 | | 0== |
| paraganglia, Overlapping lesion of endocrine glands and related structures and Endocrine gland NOS (C379, C740-C741, C749, C754-C759) See Other Sites pg C-1011 | Intracranial and CNS Tumors pg C-1017 | 977 |
| paraganglia, Overlapping lesion of endocrine glands and related structures and Endocrine gland NOS (C379, C740-C741, C749, C754-C759) See Other Sites pg C-1011 | | |
| structures and Endocrine gland NOS (C379, C740-C741, C749, C754-C759) See Other Sites pg C-1011 | | |
| NOS (C379, C740-C741, C749, C754-C759) See Other Sites pg C-1011 | | |
| See Other Sites pg C-1011 | $oldsymbol{arphi}$ | |
| CS Staging Scheme: Thymus, Adrenal (Suprarenal) Gland, and Other Endocrine Glands | NOS (C379, C740-C741, C749, C754-C759) | |
| Other Endocrine Glands | See Other Sites pg C-1011 | 977 |
| Surgery Codes: All Other Sites 4 | CS Staging Scheme: Thymus, Adrenal (Suprarenal) Gland, and | |
| Surgery Codes: All Other Sites 4 | Other Endocrine Glands | 978 |
| Kaposi Sarcoma Coding Guidelines: Kaposi Sarcoma of All Sites | | |
| Coding Guidelines: Kaposi Sarcoma of All Sites | | |
| MP/H Coding Rules: see Other Sites pg C-1011 2 | | 094 |
| CS Staging Scheme: Kaposi Sarcoma of All Sites (9140) | MD/II Coding Dylas: sag Other Sites no C 1011 2 | 20 4 |
| Surgery Codes: see site-specific codes | CC Staning Salama, Vanasi Sanama of All Sites (0.140) | 903 006 |
| Lymphoma Coding Guidelines: Lymph Nodes | | |
| Coding Guidelines: Lymph Nodes | | 990 |
| CS Staging Scheme: Hodgkin and Non-Hodgkin Lymphomas of All Sites (9590-9729) | Lymphoma | 2.5 |
| CS Staging Scheme: Hodgkin and Non-Hodgkin Lymphomas of All Sites (9590-9729) | Coding Guidelines: Lymph Nodes | 991 |
| (9590-9729) | Multiple Primary Kules: Hematopoietic Primaries. | 993 |
| Surgery Codes Lymph Nodes | CS Staging Scheme: Hougkin and Non-Hougkin Lymphomas of All Sites | 005 |
| Lymph Nodes1001 | | 773 |
| | | 1001 |
| DCC 511C-5DCC111C COUES 1002 | See site-specific codes | |

| Hematopoietic, Reticuloendothelial, Immunoproliferative and Myeloproliferative | |
|--|------|
| Multiple Primary Rules: see Hematopoietic Primaries pg C-1003 | 1003 |
| CS Staging Scheme: Hematopoietic, Reticuloendothelial, Immunoproliferative, | |
| and Myeloproliferative Neoplasms (9731-9734, 9740-9742, 9750-9758, | |
| 9760-9762, 9764-9769, 9800-9801, 9805, 9820, 9823, 9826-9827, | |
| 9831-9837, 9840, 9860-9861, 9863, 9866-9867, 9870-9876, 9891, | |
| 9895-9897, 9910, 9920, 9930-9931, 9940, 9945-9946, 9948, 9950, | |
| 9960-9964, 9970, 9975, 9980, 9982-9987, 9989) | 1005 |
| Surgery Codes: | |
| Hematopoietic/Reticuloendothelial/Immunoproliferative/Myeloproliferative | |
| Disease | 1010 |
| Other and Unknown Sites | |
| Multiple Primary and Histology Coding Rules: Other Sites ² | |
| Equivalent Terms, Definitions and Tables | 1012 |
| Flowchart | |
| Multiple Primary Rules | 1017 |
| Histology Coding Rules | 1025 |
| Matrix | |
| Multiple Primary Rules | 1043 |
| Histology Coding Rules | 1047 |
| Text | |
| Multiple Primary Rules | |
| Histology Coding Rules | 1062 |
| CS Staging Scheme: Other and Ill-Defined Sites, Unknown Primary Site | 1069 |
| C42 excludes hematopoietic, reticuloendothelial, immunoproliferative | |
| and myeloproliferative neoplasms, Hodgkin and non-Hodgkin | |
| lymphomas, and Kaposi sarcoma | |
| C77 excludes hematopoietic, reticuloendothelial, immunoproliferative | |
| and myeloproliferative neoplasms, Hodgkin and non-Hodgkin | |
| lymphomas, and Kaposi sarcoma | |
| Surgery Codes | |
| See Hematopoietic, Reticuloendothelial, Immunoproliferative, and | |
| Myeloproliferative Disease pg C-1072 | |
| Spleen ⁴ | 1073 |
| Unknown and Ill-Defined Primary Sites 4 | 1074 |
| CS Staging Schemes | |
| Standard Tables | 1080 |
| | |

Footnotes

- 1. Excludes lymphoma and leukemia (9590 9989) and Kaposi sarcoma (9140)
- 2. Excludes lymphoma and leukemia (9590 9989)
- 3. Excludes malignant melanoma, Kaposi sarcoma, mycosis fungoides, Sezary disease and other lymphomas.
- 4. Excludes 9750, 9760 9764, 9800 9820, 9826, 9831 9920, 9931 9964, 9980 9989. For these histologies, see Surgery Codes Hematopoietic, Reticuloendothelial, Immunoproliferative and Myeloproliferative Disease pg C-1072.

Appendix C

Site-Specific Coding Modules

The site-specific coding modules are stand-alone coding manuals that include SEER Coding Guidelines; Equivalent Terms, Definitions, Tables, Charts and Illustrations; Multiple Primary Rules; Histology Coding Rules; Collaborative Staging Coding Instructions and Surgery of Primary Site codes. In the past, site-specific instructions were scattered throughout the SEER Program Code Manual. Staging rules and codes were in a separate manual from all other coding rules and codes. As part of the SEER commitment to continuing Quality Improvement, this appendix brings together the site-specific instructions needed to abstract a case, facilitating efficiency and accuracy. General instructions in the main manual are applicable in the absence of site-specific instructions. All modules include the collaborative staging and surgery codes, and multiple primary and histology coding rules. In addition, some modules include site-specific coding guidelines. The goal is to have stand-alone modules for major anatomic sites. SEER will continue to work toward this goal by enhancing site-specific guidelines as modules are expanded and revised.

Part II of the Collaborative Staging manual is included in this appendix. For an introduction to Collaborative Staging, see Part I of the Collaborative Staging Manual and Coding Instructions.

The surgery codes are based on the American College of Surgeons Commission on Cancer's *Facility Oncology Registry Data System*, American College of Surgeons, Chicago, IL, 2004 (FORDS), Appendix B: Site-specific Surgery Codes (Revised 2004). The surgery codes in this document are identical to the FORDS manual; only formatting and annotations may vary. The *SEER Notes* that appear in the Surgery Code sections contain information or instructions not found in FORDS or that are different from FORDS.

Oral Cavity C000-C069

Head and Neck Equivalent Terms, Definitions, Charts, Tables and Illustrations C000-C148, C300-C329

(Excludes lymphoma and leukemia – M-9590 – 9989 and Kaposi sarcoma M9140)

Guidelines for Head and Neck

The head and neck rules cover the following sites: Lip C000-C009, Oral Cavity C019-C069, Salivary Gland C079-C089, Tonsil C090-C099, Oropharynx C100-C109, Nasopharynx C110-C119, Pyriform Sinus C129, Hypopharynx C130-C139, Other and Ill-defined Sites in Lip, Oral cavity and Pharynx C140-C148, Nasal Cavity C300, Middle Ear C301, Accessory Sinuses C310-C319, and Larynx C320-C329.

Head and neck tumors frequently extend into adjacent anatomic sites, or overlap multiple contiguous sites. The workup for these tumors often includes physical examinations, imaging, scans, endoscopies, biopsies and surgical observations. Each of these diagnostic tools provides a unique view of the tumor. More than one anatomic location may be involved with tumor and reports may contain conflicting information regarding the primary site.

Coding the Primary Site

Code the site where the tumor **originated**; do not simply code the biopsy site.

When there are multiple biopsies and the primary site is not documented, or when there is discrepant information, code the primary site using the following priority order.

SEER Program Coding and Staging Manual 2007

Priority Order

- 1. Tumor board
 - a. Specialty
 - b. General
- 2. Staging physician's site assignment
 - a. AJCC staging form
 - b. TNM statement in medical record

If neither 1 nor 2 are available, the priority order for using information depends upon whether the patient had a surgical resection of the primary tumor.

- 3. Total (complete) resection of primary tumor
 - Note: The primary tumor is completely removed. The surgical margins may be microscopically positive.
 - a. Surgeon's statement from operative report
 - b. Final diagnosis from pathology report

Head and Neck Equivalent Terms, Definitions, Charts, Tables and Illustrations C000-C148, C300-C329

(Excludes lymphoma and leukemia – M-9590 – 9989 and Kaposi sarcoma M9140)

4. No resection (biopsy only):

Documentation from:

- a. Endoscopy (physical exam with scope)
- b. Radiation oncologist
- c. Diagnosing physician
- d. Primary care physician
- e. Other physician
- f. Radiologist impression from diagnostic imaging
- g. Physician statement based on physical exam (clinical impression)

When the point of origin **cannot be determined**, use a topography code for overlapping sites:

- C02.8 Overlapping lesion of tongue
- C08.8 Overlapping lesion of major salivary glands
- C14.8 Overlapping lesion of lip, oral cavity, and pharynx.

Equivalent or Equal Terms

- In situ, noninvasive, intraepithelial
- Squamous cell carcinoma, squamous cell epithelioma, epidermoid carcinoma
- Tumor, mass, lesion, neoplasm
- Contiguous, continuous

Definitions

In Situ: A tumor that is confined to the epithelium without penetration of the basement membrane

Invasive: A tumor that penetrates the basement membrane and involves at least the lamina propria

Most invasive: The tumor with the greatest continuous extension (see focal and foci definitions in the general instructions). The least to the greatest extension for mouth and oral cavity:

- epithelium
- lamina propria, submucosa (not found in gum and hard palate)
- muscularis propria (not found in gum and hard palate)

Head and Neck Equivalent Terms, Definitions, Charts, Tables and Illustrations C000-C148, C300-C329

(Excludes lymphoma and leukemia – M-9590 – 9989 and Kaposi sarcoma M9140)

Table 1 -Paired Sites

Table Instructions: Use this table to determine multiple primary status for sites listed in Column 1.

| Column 1: | Column 2: | |
|-----------------------|------------------------|--|
| Paired Sites | Code | |
| Parotid Glands | C079 | |
| Major Salivary Glands | C080; C081 | |
| Tonsils | C090; C091; C098, C099 | |
| Nasal Cavity | C300 | |
| Accessory Sinuses | C310; C312 | |
| Middle Ear | C301 | |

Head and Neck Equivalent Terms, Definitions, Charts, Tables and Illustrations C000-C148, C300-C329

(Excludes lymphoma and leukemia – M-9590 – 9989 and Kaposi sarcoma M9140)

Table 2 – Changes to Previous SEER Site Grouping Table

Previous to 2007, tumors in sites on the same row were abstracted as a single primary.

| Code | Site Groupings | |
|------|---|--|
| C01 | Base of tongue | |
| C02 | Other and unspecified parts of tongue | |
| C05 | Palate | |
| C06 | Other and unspecified parts of mouth | |
| C07 | Parotid gland | |
| C08 | Other and unspecified major salivary glands | |
| C09 | Tonsil | |
| C10 | Oropharynx | |
| C12 | Pyriform sinus | |
| C13 | Hypopharynx | |
| C30 | Nasal cavity and middle ear | |
| C31 | Accessory sinuses | |


Head and Neck Equivalent Terms, Definitions, Charts, Tables and Illustrations C000-C148, C300-C329

(Excludes lymphoma and leukemia – M-9590 – 9989 and Kaposi sarcoma M9140)


Chart 1 – Head and Neck Histology Groups and Specific types

Note: Greater than 85% of cancers in the Head and Neck are squamous cell carcinoma

Chart Instructions: Use this chart with the histology rules to code the most specific histologic term. The tree is arranged in descending order. Each branch is a histology group, starting with the NOS or group terms and descending into the specific types for that group. As you follow the branch down, the terms become more specific.




Head and Neck Equivalent Terms, Definitions, Charts, Tables and Illustrations C000-C148, C300-C329
(Excludes lymphoma and leukemia – M-9590 – 9989 and Kaposi sarcoma M9140)




Head and Neck Equivalent Terms, Definitions, Charts, Tables and Illustrations C000-C148, C300-C329

(Excludes lymphoma and leukemia – M-9590 – 9989 and Kaposi sarcoma M9140)




Head and Neck Equivalent Terms, Definitions, Charts, Tables and Illustrations C000-C148, C300-C329 (Excludes lymphoma and leukemia – M-9590 – 9989 and Kaposi sarcoma M9140)




A.D.A.M illustration used with licensed permission. All rights reserved

Head and Neck Equivalent Terms, Definitions, Charts, Tables and Illustrations C000-C148, C300-C329

(Excludes lymphoma and leukemia – M-9590 – 9989 and Kaposi sarcoma M9140)



Head and Neck Equivalent Terms, Definitions, Charts, Tables and Illustrations C000-C148, C300-C329 (Excludes lymphoma and leukemia – M-9590 – 9989 and Kaposi sarcoma M9140)



Illustrations used with permission of Blue Tree Publishing

Head and Neck Equivalent Terms, Definitions, Charts, Tables and Illustrations C000-C148, C300-C329

(Excludes lymphoma and leukemia – M-9590 – 9989 and Kaposi sarcoma M9140)




Image made available by a generous grant from Bristol-Myers Squibb

This page left blank


Head and Neck Multiple Primary Rules-Flowchart

(C000-C148, C300-C329)

(Excludes lymphoma and leukemia M9590-9989 and Kaposi sarcoma M9140)



- * Prepare one abstract. Use the histology coding rules to assign the appropriate histology code.
- ** Prepare two or more abstracts. Use the histology coding rules to assign the appropriate histology code to each case abstracted.



Site-Specific Coding Modules


Head and Neck Multiple Primary Rules-Flowchart

(C000-C148, C300-C329)

(Excludes lymphoma and leukemia M9590-9989 and Kaposi sarcoma M9140)



- * Prepare one abstract. Use the histology coding rules to assign the appropriate histology code.
- ** Prepare two or more abstracts. Use the histology coding rules to assign the appropriate histology code to each case abstracted.




Head and Neck Multiple Primary Rules-Flow chart

(C000-C148, C300-C329)

(Excludes lymphoma and leukemia M9590-9989 and Kaposi sarcoma M9140)




- * Prepare one abstract. Use the histology coding rules to assign the appropriate histology code.
- ** Prepare two or more abstracts. Use the histology coding rules to assign the appropriate histology code to each case abstracted.




Head and Neck Multiple Primary Rules-Flowchart

(C000-C148, C300-C329)

(Excludes lymphoma and leukemia M9590-9989 and Kaposi sarcoma M9140)



- * Prepare one abstract. Use the histology coding rules to assign the appropriate histology code.
- ** Prepare two or more abstracts. Use the histology coding rules to assign the appropriate histology code to each case abstracted.



Head and Neck Multiple Primary Rules

(C000-C148, C300-C329)


(Excludes lymphoma and leukemia M9590-9989 and Kaposisarcoma M9140)

- * Prepare one abstract. Use the histology coding rules to assign the appropriate histology code.
- ** Prepare two or more abstracts. Use the histology coding rules to assign the appropriate histology code to each case abstracted.

Flowchart Key

question

Flow Direction





lowchart Key

Site-Specific Coding Modules

Head and Neck Histology Coding Rules-Flowchart

(C000-C148, C300-C329)






Head and Neck Histology Coding Rules-Flowchart

(C000-C148, C300-C329) (Excludes lymphoma and leukemia M9590-9989 and Kaposi sarcoma M9140)

SINGLE TUMOR



SEER Program Coding and Staging Manual 2007

| Rule | Action | Notes and Examples |
|--|---|---|
| Are there multiple histologies within the same branch such as: • cancer/malignant neoplasm, NOS (8000) and a more specific histology? OR • carcinoma, NOS (8010) and a more specific carcinoma? OR • squamous cell carcinoma, NOS (8070) and a more specific squamous cell carcinoma? OR • ade nocarcinoma, NOS (8140) and a more specific adenocarcinoma? OR • melanoma, NOS (8720) and a more specific melanoma? OR • sarcoma, NOS (8800) and a more specific sarcoma? | Code the most specific hist ologic term using Chart 1 | 1. The specific histology for in situ tumors may be identified as pattern, architecture, type, subtype, predominantly, with features of, major, or with differentiation. 2. The specific histology for invasive tumors may be identified as type, subtype, predominantly, with features of, major, or with differentiation. Example: The final diagnosis is squamous cell carcinoma (8070), papillary (8050). Code the specific type, papillary (8050) |
| H6 | Code the numerically higher ICD-0-3 histology code. | |

This is the end of instructions for Single Tumor. Code the histology according to the rule that fits the case.


Head and Neck Histology Coding Rules-Flowchart

(C000-C148, C300-C329)

(Excludes lymphoma and leukemia M9590-9989 and Kaposi sarcoma M9140)

Flowchart Key Action Notes and Examples FlowDirection

MULTIPLE TUMORS ABSTRACTED AS A SINGLE PRIMARY




Head and Neck Histology Coding Rules-Flowchart

(C000-C148, C300-C329)

(Excludes lymphoma and leukemia M9590-9989 and Kaposi sarcoma M9140)

MULTIPLE TUMORS ABSTRACTED AS A SINGLE PRIMARY






Head and Neck Histology Coding Rules-Flowchart

(C000-C148, C300-C329)

(Excludes lymphoma and leukemia M9590-9989 and Kaposi sarcoma M9140)

MULTIPLE TUMORS ABSTRACTED AS A SINGLE PRIMARY



| Rule | Action | Notes and Examples |
|---|--|---|
| Are there multiple histologies within the same branch such as: cancer/malignant neoplasm, NOS (8000) and a more specific histology? OR carcinoma, NOS (8010) and a more specific carcinoma? OR squamous cell carcinoma, NOS (8070) and a more specific squamous cell carcinoma? OR adenocarcinoma, NOS (8140) and a more specific ade nocarcinoma? OR melanoma, NOS (8720) and a more specific melanoma? OR sarcoma, NOS (8800) and a more specific sarcoma? | Code the most specific histologic term using Chart 1 | 1. The specific histology for in situ tumors may be identified as pattern, architecture, type, subtype, predominantly, with features of, major, or with differentiation. 2. The specific histology for invasive tumors may be identified as type, subtype, predominantly, with features of, major, or with differentiation. Example: The final diagnosis is squamous cell carcinoma (8070), papillary (8050). Code the specific type, papillary (8050) |
| H12 | Code the numerically higher ICD-O-3 histology code. | |

This is the end of instructions for Multiple Tumors Abstracted as a Single Primary. Code the histology according to the rule that fits the case.

Head and Neck Multiple Primary Rules – Matrix C000-C148, C300-C329

(Excludes lymphoma and leukemia – M9590 – 9989 and Kaposi sarcoma M9140)

- Prepare one abstract. Use the histology coding rules to assign the appropriate histology code.
- ** Prepare two or more abstracts. Use the histology coding rules to assign the appropriate histology code to each case abstracted.

| Rule | Site | Histology | Timing | Behavior | Notes/Examples | Primary |
|--------------------------------------|---|-------------------------------|--------|--------------------------------------|---|------------|
| UNKNOWN IF SINGLE OR MULTIPLE TUMORS | | | | Tumor(s) not described as metastasis | | |
| M1 | | | | | Use this rule only after all information sources have been exhausted. Example 1: History and physical exam states large tumor in nasopharynx. Biopsy base of tongue shows squamous cell carcinoma. No further information available. Abstract as a single primary. Example 2: Pathology report states extensive squamous cell carcinoma involving nasopharynx and larynx. Fragments of epiglottis positive for squamous cell carcinoma. No other information available. Abstract as a single primary. | Single* |
| SING | LE TUMOR | | | | 1. Tumor not described as metastasis2: Includes combinations of in situ and invasive | |
| M2 | Single | | | | The tumor may overlap onto or extend into adjacent/contiguous site or subsite. | Single* |
| MUL | TIPLE TUMORS | | | | 1. Tumors not described as metastases | |
| Multip | le tumors may be a sir | gle primary or multiple prima | ries | | 2: Includes combinations of in situ and invasive | |
| М3 | Right side and left side of a paired site | | | | See Table 1 for list of paired sites | Multiple** |
| M4 | Upper lip (C000 or C003) and lower lip (C001 or C004) | | | | | Multiple** |
| M5 | Upper gum (C030) and lower gum (C031) | | | | | Multiple** |
| M6 | Nasal cavity (C300) and middle ear (C301) | | | | | Multiple** |

Head and Neck Multiple Primary Rules – Matrix C000-C148, C300-C329

(Excludes lymphoma and leukemia – M9590 – 9989 and Kaposi sarcoma M9140)

| Rule | Site | Histology | Timing | Behavior | Notes/Examples | Primary |
|------|--|-----------|---|----------------------------------|---|------------|
| M7 | Topography codes that are different at the second (Cxxx) and/or third (Cxxx) character | | | | | Multiple** |
| M8 | | | More than 60 days after diagnosis | An invasive following an in situ | 1: The purpose of this rule is to ensure that the case is counted as an incident (invasive) case when incidence data are analyzed. 2: Abstract as multiple primaries even if the medical record/physician states it is recurrence or progression of disease. | Multiple** |
| M9 | | | Diagnosed more than five (5) years apart | | | Multiple** |

Head and Neck Multiple Primary Rules – Matrix C000-C148, C300-C329

| Rule | Site | Histology | Timing | Behavior | Notes/Examples | Primary |
|------|------|---|--------|----------|----------------|------------|
| M10 | | Cancer/malignant neoplasm, NOS (8000) and another is a specific histology; or Carcinoma, NOS (8010) and another is a specific carcinoma; or Adenocarcinoma, NOS (8140) and another is a specific adenocarcinoma; or Squamous cell carcinoma, NOS (8070) and another is specific squamous cell carcinoma or Melanoma and another is a specific melanoma; or Sarcoma, NOS (8800) and another is a specific melanoma; or | | | | Single* |
| M11 | | Different at the first $(\underline{\mathbf{x}}\mathbf{x}\mathbf{x}\mathbf{x})$, second $(\mathbf{x}\underline{\mathbf{x}}\mathbf{x}\mathbf{x})$, or third $(\mathbf{x}\mathbf{x}\underline{\mathbf{x}}\mathbf{x})$ number | | | | Multiple** |

Site-Specific Coding Modules

Head and Neck Multiple Primary Rules – Matrix C000-C148, C300-C329

| Rule | Site | Histology | Timing | Behavior | Notes/Examples | Primary |
|------|------|-----------------------|--------|----------|--|---------|
| M12 | | of the above criteria | Timing | Behavior | Notes/Examples When an invasive tumor follows an in situ tumor within 60 days, abstract as a single primary. All cases covered by rule M12 have the same first 3 numbers in ICD-O-3 histologic code. Rule M12 Examples: The following are examples of cases that use Rule M12. This is NOT intended to be an exhaustive set of examples; there are other cases that may be classified as a single primary. Warning: Using only these case examples to determine the number of primaries can result in major errors Example 1: Multifocal tumors in floor of mouth Example 2: An in situ and invasive tumor diagnosed within 60 days Example 3: In situ following an invasive | Single* |
| | | | | | tumor more than 60 days apart | |

Head and Neck Histology Coding Rules – Matrix C000-C148, C300-C329

| Rule | Pathology/Cytology Specimen | Histology | Behavior | Notes and Examples | Code |
|------|--|-----------|-------------------------|---|---|
| SING | LE TUMOR | | | | |
| H1 | No pathology/cytology specimen or the pathology/cytology report is not available | | | I: Priority for using documents to code the histology Documentation in the medical record that refers to pathologic or cytologic findings Physician's reference to type of cancer (histology) in the medical record CT, PET or MRI scans Code the specific histology when documented. Code the histology to 8000 (cancer/malignant neoplasm, NOS) or 8010 (carcinoma, NOS) as stated by the physician when nothing more specific is documented | The histology documented by the physician |
| H2 | None from primary site | | | Code the behavior /3 | The histology from metastatic site |
| Н3 | | One type | | Example: Squamous cell carcinoma. Code 8070. Do not code terms that do not appear in the histology description. Example: Do not code 8072 (squamous cell carcinoma non-keratinizing) unless the words "non-keratinizing" actually appear in the diagnosis | The histology |
| H4 | | | Invasive and in situ | <i>Example:</i> The final diagnosis is keratinizing squamous cell carcinoma (8071) with areas of squamous cell carcinoma in situ (8070). Code the invasive histologic type, keratinizing squamous cell carcinoma (8071). | The invasive histologic type |

Site-Specific Coding Modules

Head and Neck Histology Coding Rules – Matrix C000-C148, C300-C329

| Rule | Pathology/Cytology Specimen | Histology | Behavior | Notes and Examples | Code |
|------|--------------------------------|--|----------|---|--|
| Н5 | | Multiple histologies all within the same branch on Chart 1. Examples of histologies within same banch: • Cancer/malignant neoplasm, NOS (8000) and a more specific histology or • Carcinoma, NOS (8010) and a more specific carcinoma or • Squamous cell carcinoma, NOS (8070) and a more specific squamous cell carcinoma or • Adenocarcinoma, NOS (8140) and a more specific adenocarcinoma or • Melanoma, NOS (8720) and a more specific melanoma or • Sarcoma, NOS (8800) and a more specific sarcoma | | The specific histology for in situ tumors may be identified as pattern, architecture, type, subtype, predominantly, with features of, major, or withdifferentiation. The specific histology for invasive tumors may be identified as type, subtype, predominantly, with features of, major, or withdifferentiation. Example: The final diagnosis is squamous cell carcinoma (8070), papillary (8050). Code the specific type, papillary (8050). | The most specific term using Chart 1 |
| Н6 | None of the above conditi | ons are met | | | The histology with the numerically higher ICD-O-3 code |

Head and Neck Histology Coding Rules – Matrix C000-C148, C300-C329

| Rule | Pathology/Cytology | Histology | Behavior | Notes and Examples | Code |
|-------|---|-----------------------------|----------|---|--|
| MITIT | Specimen | TED AS A SINGLE PRIMAR | N/ | | |
| Н7 | No pathology/cytology specimen or the pathology/cytology report is not available | TED AS A SINGLE I KINIAK | | I: Priority for using documents to code the histology Documentation in the medical record that refers to pathologic or cytologic findings Physician's reference to type of cancer (histology) in the medical record CT, PET or MRI scans Code the specific histology when documented 3: Code the histology to 8000 (cancer/malignant neoplasm, NOS) or 8010 (carcinoma, NOS) as stated by the physician when nothing more specific is documented | The histology documented by the physician |
| H8 | None from primary site | | | Code the behavior /3 | The histology from a metastatic site |
| Н9 | | One type | | Example: Squamous cell carcinoma. Code 8070. Do not code terms that do not appear in the histology description. Example: Do not code 8072 (squamous cell carcinoma non-keratinizing) unless the words "non-keratinizing" actually appear in the diagnosis | The histology |
| H10 | | | | 1: See the Head and Neck Equivalent Terms, Definitions, Charts, Tables and Illustrations for the definition of most invasive. One tumor is in situ and one is invasive, code the histology from the invasive tumor Both/all histologies are invasive, code the histology of the more invasive tumor. If tumors are equally invasive, go to the next rule | The histology of the most invasive tumor |

Site-Specific Coding Modules

Head and Neck Histology Coding Rules – Matrix C000-C148, C300-C329

| Rule | Pathology/Cytology Specimen | Histology | Behavior | Notes and Examples | Code |
|------|--------------------------------|--|----------|---|--|
| H11 | | Multiple histologies all within the same branch on Chart 1. Examples of histologies within same banch: • Cancer/malignant neoplasm, NOS (8000) and a more specific histology or • Carcinoma, NOS (8010) and a more specific carcinoma or • Squamous cell carcinoma, NOS (8070) and a more specific squamous cell carcinoma or • Adenocarcinoma, NOS (8140) and a more specific adenocarcinoma or • Melanoma, NOS (8720) and a more specific melanoma or Sarcoma, NOS (8800) and a more specific sarcoma | | The specific histology for in situ tumors may be identified as pattern, architecture, type, subtype, predominantly, with features of, major, or withdifferentiation. The specific histology for invasive tumors may be identified as type, subtype, predominantly, with features of, major, or withdifferentiation. Example: The final diagnosis is squamous cell carcinoma (8070), papillary (8050). Code the specific type, papillary (8050). | The most specific term using Chart 1 |
| H12 | None of the conditions are | met | | | The histology with the numerically higher ICD-O-3 code |

Head and Neck Multiple Primary Rules - Text C000-C148, C300-C329

(Excludes lymphoma and leukemia – M9590 – 9989 and Kaposi sarcoma M9140)

UNKNOWN IF SINGLE OR MULTIPLE TUMORS

Note: Tumor(s) not described as metastasis

Rule M1 When it is not possible to determine if there is a **single** tumor **or multiple** tumors, opt for a single tumor and abstract as a single primary.*

Note: Use this rule only after all information sources have been exhausted.

- *Example 1:* History and physical exam states large tumor in nasopharynx. Biopsy base of tongue shows squamous cell carcinoma. No further information available. Abstract as a single primary.
- *Example 2:* Pathology report states extensive squamous cell carcinoma involving nasopharynx and larynx. Fragments of epiglottis positive for squamous cell carcinoma. No other information available. Abstract as a single primary.

SEER Program Coding and Staging Manual 2007

SINGLE TUMOR

- Note 1: Tumor not described as metastasis
- *Note 2:* Includes combinations of in situ and invasive
- Rule M2 A single tumor is always a single primary. *

Note: The tumor may overlap onto or extend into adjacent/contiguous site or subsite.

This is the end of instructions for Single Tumor.

MULTIPLE TUMORS

Multiple tumors may be a single primary or multiple primaries.

- *Note 1:* Tumors not described as metastases
- *Note 2:* Includes combinations of in situ and invasive
- Rule M3 Tumors on the right side and the left side of a paired site are multiple primaries. **

Note: See Table 1 for list of paired sites.

- Rule M4 Tumors on the upper lip (C000 or C003) and the lower lip (C001 or C004) are multiple primaries. **
- Rule M5 Tumors on the upper gum (C030) and the lower gum (C031) are multiple primaries. **

^{*} Prepare one abstract. Use the histology coding rules to assign the appropriate histology code. This is the end of instructions for Unknown if Single or Multiple Tumors.

^{*} Prepare one abstract. Use the histology coding rules to assign the appropriate histology code.

Site-Specific Coding Modules

Head and Neck Multiple Primary Rules - Text C000-C148, C300-C329 Excludes lymphoma and leukemia – M9590 – 9989 and Kaposi sarcoma M91

| | (Excludes lymphoma and leukemia – M9590 – 9989 and Kaposi sarcoma M9140) |
|----------|--|
| Rule M6 | Tumors in the nasal cavity (C300) and the middle ear (C301) are multiple primaries. ** |
| Rule M7 | Tumors in sites with ICD-O-3 topography codes that are different at the second ($C\underline{\mathbf{x}}xx$) and/or third ($Cx\underline{\mathbf{x}}x$) character are multiple primaries. ** |
| Rule M8 | An invasive tumor following an in situ tumor more than 60 days after diagnosis is a multiple primary. ** Note 1: The purpose of this rule is to ensure that the case is counted as an incident (invasive) case when incidence data are analyzed. Note 2: Abstract as multiple primaries even if the medical record/physician states it is recurrence or progression of disease. |
| Rule M9 | Tumors diagnosed more than five (5) years apart are multiple primaries. ** |
| Rule M10 | Abstract as a single primary* when one tumor is: • Cancer/malignant neoplasm, NOS (8000) and another is a specific histology or • Carcinoma, NOS (8010) and another is a specific carcinoma or • Adenocarcinoma, NOS (8140) and another is a specific adenocarcinoma or |

- Squamous cell carcinoma, NOS (8070) and another is specific squamous cell carcinoma or
- Melanoma, NOS (8720) and another is a specific melanoma
- Sarcoma, NOS (8800) and another is a specific sarcoma
- **Rule M11** Tumors with ICD-O-3 **histology** codes that are **different** at the first ($\underline{\mathbf{x}}$ xxx), second ($x\underline{\mathbf{x}}$ xx) or third ($xx\underline{\mathbf{x}}$ x) number are multiple primaries. **
- **Rule M12** Tumors that **do not meet any** of the above **criteria** are abstracted as a single primary. * *Note 1:* When an invasive tumor follows an in situ tumor within 60 days, abstract as a single primary. *Note 2:* All cases covered by Rule M12 have the same first 3 numbers in ICD-O-3 histology code.

This is the end of instructions for Multiple Tumors.

- * If a single primary, prepare one abstract. Use the histology coding rules to assign the appropriate histology code.
- ** If multiple primaries, prepare two or more abstracts. Use the histology coding rules to assign the appropriate histology code to each case abstracted.

Rule M12 Examples: The following are examples of cases that use Rule M12. This is NOT intended to be an exhaustive set of examples; there are other cases that may be classified as a single primary. Warning: Using only these case examples to determine the number of primaries can result in major errors.

| Example 1: Multifocal tumors in floor of | Example 2: An in situ and invasive tumor | Example 3: In situ following an invasive tumor |
|---|---|---|
| mouth | diagnosed within 60 days | more than 60 days apart |

Head and Neck Histology Coding Rules - Text C000-C148, C300-C329

(Excludes lymphoma and leukemia – M-9590 – 9989 and Kaposi sarcoma M9140)

SINGLE TUMOR

Rule H1 Code the histology documented by the physician when there is **no pathology/cytology specimen** or the **pathology/cytology** report is **not available**.

Note 1: Priority for using documents to code the histology

- Documentation in the medical record that refers to pathologic or cytologic findings
- Physician's reference to type of cancer (histology) in the medical record
- CT, PET, or MRI scans

Note 2: Code the specific histology when documented.

Note 3: Code the histology to 8000 (cancer/malignant neoplasm, NOS) or 8010 (carcinoma, NOS) as stated by the physician when nothing more specific is documented.

Rule H2 Code the histology from a metastatic site when there is **no pathology/cytology specimen from the primary site**.

Note: Code the behavior /3.

Rule H3 Code the histology when only one histologic type is identified.

Example: Squamous cell carcinoma. Code 8070.

Note: Do not code terms that do not appear in the histology description.

Example: Do not code 8072 (squamous cell carcinoma non-keratinizing) unless the words "non-keratinizing" actually appear in the diagnosis.

SEER Program Coding and Staging Manual 2007

Rule H4 Code the **invasive** histologic type when a single tumor has invasive and in situ components.

Example: The final diagnosis is keratinizing squamous cell carcinoma (8071) with areas of squamous cell carcinoma in situ (8070). Code the invasive histologic type, keratinizing squamous cell carcinoma (8071).

Site-Specific Coding Modules

Head and Neck Histology Coding Rules - Text C000-C148, C300-C329

(Excludes lymphoma and leukemia – M-9590 – 9989 and Kaposi sarcoma M9140)

- **Rule H5** Code the most **specific** histologic term using Chart 1 when there are multiple histologies within the same branch. Examples of histologies within the same branch are:
 - Cancer/malignant neoplasm, NOS (8000) and a more specific histology or
 - Carcinoma, NOS (8010) and a more specific carcinoma or
 - Squamous cell carcinoma, NOS (8070) and a more specific squamous carcinoma or
 - Adenocarcinoma, NOS(8140) and a more specific adenocarcinoma or
 - Melanoma, NOS (8720) and a more specific melanoma or
 - Sarcoma, NOS (8800) and a more specific sarcoma

Note 1: The specific histology for **in situ** lesions may be identified as pattern, architecture, type, subtype, predominantly, with features of, major, or with differentiation

Note 2: The specific histology for **invasive** lesions may be identified as type, subtype, predominantly, with features of, major, or with differentiation

Example: The final diagnosis is squamous cell carcinoma (8070), papillary (8050). Code the specific type, papillary (8050).

Rule H6 Code the histology with the numerically higher ICD-O-3 code.

This is the end of instructions for Single Tumor.

Code the histology according to the rule that fits the case.

MULTIPLE TUMORS ABSTRACTED AS A SINGLE PRIMARY

Rule H7 Code the histology documented by the physician when there is **no pathology/cytology specimen** or the **pathology/cytology** report is **not available**.

Note 1: Priority for using documents to code the histology

- Documentation in the medical record that refers to pathologic or cytologic findings
- Physician's reference to type of cancer (histology) in the medical record
- CT, PET, or MRI scans
- *Note 2:* Code the specific histology when documented.
- *Note 3:* Code the histology to 8000 (cancer/malignant neoplasm, NOS), or 8010 (carcinoma, NOS) as stated by the physician when no specific histology is documented.
- Rule H8 Code the histology from the metastatic site when there is **no pathology/cytology specimen from the primary site**. *Note:* Code the behavior /3.

Head and Neck Histology Coding Rules - Text C000-C148, C300-C329

(Excludes lymphoma and leukemia – M-9590 – 9989 and Kaposi sarcoma M9140)

Rule H9 Code the histology when only **one histologic type** is identified.

Example: Squamous cell carcinoma. Code 8070.

Note: Do not code terms that do not appear in the histology description.

Example: Do not code 8072 (squamous cell carcinoma non-keratinizing) unless the words "non-keratinizing" actually appear in the diagnosis

Rule H10 Code the histology of the most invasive tumor.

Note 1: See the Head and Neck Equivalent Terms, Definitions, Charts, Tables and Illustrations for the definition of most invasive.

- One tumor is in situ and one is invasive, code the histology from the invasive tumor.
- Both/all histologies are invasive, code the histology of the more invasive tumor.

Note 2: If tumors are equally invasive, go to the next rule

- **Rule H11** Code the most **specific** histologic term using Chart 1 when there are multiple histologies within the same branch. Examples of histologies within the same branch are:
 - Cancer/malignant neoplasm, NOS (8000) and a more specific histology or
 - Carcinoma, NOS (8010) and a more specific carcinoma or
 - Squamous cell carcinoma, NOS (8070) and a more specific squamous carcinoma or
 - Adenocarcinoma, NOS(8140) and a more specific adenocarcinoma or
 - Melanoma, NOS (8720) and a more specific melanoma or
 - Sarcoma, NOS (8800) and a more specific sarcoma

Note 1: The specific histology for **in situ** lesions may be identified as pattern, architecture, type, subtype, predominantly, with features of, major, or with _____differentiation

SEER Program Coding and Staging Manual 2007

Note 2: The specific histology for **invasive** lesions may be identified as type, subtype, predominantly, with features of, major, or with differentiation

Example: The final diagnosis is squamous cell carcinoma (8070), papillary (8050). Code the specific type, papillary (8050).

Rule H12 Code the histology with the numerically higher ICD-O-3 code.

This is the end of instructions for Multiple Tumors Abstracted as a Single Primary. Code the histology according to the rule that fits the case.

Site-Specific Coding Modules

This page left blank

CS Staging Schemas

Lip, Upper

Lip (Vermilion or Labial Mucosa)

C00.0, C00.3

C00.0 External upper lip C00.3 Mucosa of upper lip

Note: AJCC includes labial mucosa (C00.3) with buccal mucosa (C06.0)

| CS Tumor Size CS Extension CS TS/Ext-Eval CS Lymph Nodes CS Reg Nodes Eval Reg LN Pos Reg LN Exam CS Mets at DX CS Mets Eval | CS Site-Specific Factor 1 - Size of Lymph Nodes CS Site-Specific Factor 2 - Extracapsular Extension, Lymph Nodes for Head and Neck CS Site-Specific Factor 3 - Levels I-III, Lymph Nodes for Head and Neck CS Site-Specific Factor 4 - Levels IV-V and Retropharyngeal Lymph Nodes for Head and Neck CS Site-Specific Factor 5 - Levels VI-VII and Facial Lymph Nodes for Head and Neck CS Site-Specific Factor 6 - Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck | The following tables are available at the collaborative staging website: Histology Exclusion Table AJCC Stage Extension Size Table Lymph Nodes Size Table |
|--|---|---|
|--|---|---|

Lip, Upper CS Tumor Size SEE STANDARD TABLE

Lip, Upper

CS Extension (Revised: 08/22/2006)

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 00 | In situ; noninvasive; intraepithelial | Tis | IS | IS |
| 10 | Invasive tumor confined to: Labial mucosa (inner lip) Lamina propria Multiple foci Submucosa (superficial invasion) Vermilion surface Superficial extension to: Skin of lip Subcutaneous soft tissue of lip | * | L | L |
| 20 | Musculature | * | L | L |
| 30 | Localized, NOS | * | L | L |
| 50 | Buccal mucosa (inner cheek) Commissure Opposite (both) lip(s) | * | RE | RE |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 51 | Gingiva | * | RE | RE |
| 70 | Maxilla | T4 | RE | RE |
| 74 | Upper lip/commissure: Nose | T4 | RE | D |
| 75 | Tongue | T4 | D | D |
| 76 | Skin of face/neck | T4 | D | D |
| 77 | Cortical bone (other than code 70) Floor of mouth Inferior alveolar nerve | T4 | D | D |
| 80 | Further contiguous extension | T4 | D | D |
| 95 | No evidence of primary tumor | Т0 | U | U |
| 99 | Unknown extension Primary tumor cannot be assessed Not documented in patient record | TX | U | U |

^{*} For Extension codes 10, 20, 30, 50, and 51 ONLY, the T category is assigned based on the value of CS Tumor Size, as shown in the Extension Size Table for this site.

Lip, Upper CS TS/Ext-Eval SEE STANDARD TABLE

Lip, Upper

CS Lymph Nodes (Revised: 08/21/2006)

Note 1: For head and neck schemas, this field includes all lymph nodes defined as Levels I-VII and Other by AJCC. The complete definitions are provided in the General Instructions.

Note 2: For head and neck schemas, additional information about lymph nodes (size of involved nodes, extracapsular extension, and levels involved) is coded in Site-Specific Factors 1-6.

Note 3: If laterality of lymph nodes is not specified, assume nodes are ipsilateral. Midline nodes are considered ipsilateral.

Note 4: For head and neck cancers, if lymph nodes are described only as "supraclavicular", try to determine if they are in Level IV (deep to the sternocleidomastoid muscle, in the lower jugular chain) or Level V (in the posterior triangle, inferior to the transverse cervical artery) and code appropriately. If the specific level cannot be determined, consider them as Level V nodes.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | None; no regional lymph node involvement | N0 | NONE | NONE |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 10 | Single positive ipsilateral regional node: Other groups: Facial: Buccinator (buccal) Nasolabial Parotid Infra-auricular Intraparotid Periparotid Preauricular Regional lymph node, NOS | * | RN | RN |
| 11 | Single positive ipsilateral regional node: Level I node Submandibular (submaxillary) Submental Level II node Jugulodigastric (subdigastric) Upper deep cervical Upper jugular Level III node Middle deep cervical Mid jugular Level IV node Jugulo-omohyoid (supraomohyoid) Lower deep cervical Lower jugular Cervical, NOS Deep cervical, NOS Internal jugular, NOS | * | D | RN |
| 12 | Single positive ipsilateral regional node: Level V node Posterior cervical Posterior triangle (spinal accessory and transverse cervical) (upper, middle, and lower corresponding to the levels that define upper, middle, and lower jugular nodes) Level VI node Anterior deep cervical Laterotracheal Paralaryngeal Paratracheal Prelaryngeal Pretracheal Recurrent laryngeal Level VII node Upper mediastinum (for other mediastinal nodes see CS Mets at DX) Other groups Parapharyngeal Retropharyngeal Retropharyngeal Sub-occipital Supraclavicular, NOS (See Note 4) | * | D | D |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-------|------|--------|
| 18 | Stated as N1, no other information | N1 | RN | RN |
| 19 | Stated as N2a, no other information | N2a | RN | RN |
| 20 | Multiple positive ipsilateral nodes listed in code 10 | * | RN | RN |
| 21 | Multiple positive ipsilateral nodes listed in code 11 | * | D | RN |
| 22 | Multiple positive ipsilateral nodes listed in code 12 | * | D | D |
| 29 | Stated as N2b, no other information | N2b | RN | RN |
| 30 | Regional lymph nodes as listed in code 10: Positive ipsilateral node(s), not stated if single or multiple | * | RN | RN |
| 31 | Regional lymph nodes as listed in code 11: Positive ipsilateral node(s), not stated if single or multiple | * | D | RN |
| 32 | Regional lymph nodes as listed in code 12: Positive ipsilateral node(s), not stated if single or multiple | * | D | D |
| 40 | Regional lymph nodes as listed in code 10: Positive bilateral or contralateral nodes | * | RN | RN |
| 41 | Regional lymph nodes as listed in code 11: Positive bilateral or contralateral nodes | * | D | RN |
| 42 | Regional lymph nodes as listed in code 12: Positive bilateral or contralateral nodes | * | D | D |
| 49 | Stated as N2c, no other information | N2c | RN | RN |
| 50 | Regional lymph nodes as listed in code 10: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | RN | RN |
| 51 | Regional lymph nodes as listed in code 11: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | RN |
| 52 | Regional lymph nodes as listed in code 12: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | D |
| 60 | Stated as N2, NOS | N2NOS | RN | RN |
| 70 | Stated as N3, no other information | N3 | RN | RN |
| 80 | Lymph nodes, NOS, no other information | * | RN | RN |
| 99 | Unknown; not stated Regional lymph nodes cannot be assessed Not documented in patient record | NX | U | U |
| | • | | | 0.01 |

^{*} For codes 10-12, 20-22, 30-32, 40-42, 50-52, and 80 ONLY, the N category is assigned based on the value of Site-Specific Factor 1, Size of Lymph Nodes, using the extra table, Lymph Nodes Size Table for this site.

CS Staging Schemas

Lip, Upper CS Reg Nodes Eval SEE STANDARD TABLE

Lip, Upper Reg LN Pos SEE STANDARD TABLE

Lip, Upper Reg LN Exam SEE STANDARD TABLE

Lip, Upper

CS Mets at DX (Revised: 08/14/2006)

Note: Supraclavicular and transverse cervical lymph nodes are now coded in CS Lymph Nodes because they are categorized as N rather than M in AJCC TNM. Any cases coded to 10 or 50 can be reviewed and recoded. The volume of cases affected should be small.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | No; none | M0 | NONE | NONE |
| 10 | Distant lymph node(s) Mediastinal Distant lymph node(s), NOS | M1 | D | D |
| 40 | Distant metastases except distant lymph node(s) (code 10) Distant metastasis, NOS Carcinomatosis | M1 | D | D |
| 50 | (10) + (40) Distant lymph node(s) plus other distant metastases | M1 | D | D |
| 99 | Unknown if distant metastasis Distant metastasis cannot be assessed Not documented in patient record | MX | U | U |

Lip, Upper CS Mets Eval SEE STANDARD TABLE

Lip, Upper

CS Site-Specific Factor 1 Size of Lymph Nodes (Revised: 08/18/2006)

Note: Code the largest diameter, whether measured clinically or pathologically, of any involved regional lymph node(s). Do not code the size of any nodes coded in CS Mets at DX.

| Code | Description |
|------|----------------------------|
| 000 | No involved regional nodes |

CS Staging Schemas

| Code | Description |
|---------|--|
| 001-988 | 001-988 millimeters (code exact size in millimeters) |
| 989 | 989 millimeters or larger |
| 990 | Microscopic focus or foci only, no size of focus given |
| 991 | Described as "less than 1cm" |
| 992 | Described as "less than 2cm" or "greater than 1cm" or "between 1cm and 2cm" |
| 993 | Described as "less than 3cm" or "greater than 2cm" or "between 2cm and 3cm" |
| 994 | Described as "less than 4cm" or "greater than 3cm" or "between 3cm and 4cm" |
| 995 | Described as "less than 5cm" or "greater than 4cm" or "between 4cm and 5cm" |
| 996 | Described as "less than 6cm" or "greater than 5cm" or "between 5cm and 6cm" |
| 997 | Described as "more than 6cm" |
| 999 | Regional lymph node(s) involved, size not stated Unknown if regional lymph node(s) involved Not documented in patient record |

Lip, Upper

CS Site-Specific Factor 2 Extracapsular Extension, Lymph Nodes for Head and Neck (Revised: 08/17/2007)

Note 1: Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. Do not code extracapsular extension in any nodes coded in CS Mets at DX in this field.

Note 2: A statement of the presence or absence of extracapsular extension in a pathology report takes priority over clinical assessment. However, if the pathology report contains no statement about extracapsular extension, either positive or negative, the clinical assessment should be coded. If nodes are involved but there is neither a clinical assessment of extranodal extension nor a statement about it in the pathology report, use code 999.

Note 3: According to AJCC (page 24), "Imaging studies showing amorphous spiculated margins of involved nodes or involvement of internodal fat resulting in loss of normal oval-to-round nodal shape strongly suggest extracapsular (extranodal) tumor spread; however, pathologic examination is necessary for documentation of the extent of such disease."

| Code | Description |
|------|---|
| 000 | No extracapsular extension |
| 001 | Extracapsular extension clinically, not assessed pathologically Nodes described as "fixed", not assessed pathologically |
| 005 | Extracapsular extension present pathologically |
| 888 | Not applicable; no lymph node involvement |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Lip, Upper

CS Site-Specific Factor 3 Levels I-III, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels I, II, or III |
| 100 | Level I lymph node(s) involved |
| 010 | Level II lymph node(s) involved |
| 001 | Level III lymph node(s) involved |
| 110 | Level I and II lymph nodes involved |
| 101 | Level I and III lymph nodes involved |
| 011 | Level II and III lymph nodes involved |
| 111 | Level I, II and III lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Lip, Upper

CS Site-Specific Factor 4 Levels IV-V and Retropharyngeal Lymph Nodes for Head and

Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|--|
| 000 | No lymph node involvement in Levels IV or V or retropharyngeal |
| 100 | Level IV lymph node(s) involved |
| 010 | Level V lymph node(s) involved |
| 001 | Retropharyngeal nodes involved |
| 110 | Level IV and V lymph nodes involved |
| 101 | Level IV and retropharyngeal nodes involved |
| 011 | Level V and retropharyngeal nodes involved |

CS Staging Schemas

| Code | Description |
|------|---|
| 111 | Level IV and V and retropharyngeal lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Lip, Upper

CS Site-Specific Factor 5 Levels VI-VII and Facial Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels VI or VII or facial nodes |
| 100 | Level VI lymph node(s) involved |
| 010 | Level VII lymph node(s) involved |
| 001 | Facial (buccinator, nasolabial) lymph node(s) involved |
| 110 | Level VI and VII lymph nodes involved |
| 101 | Level VI and facial (buccinator, nasolabial) nodes involved |
| 011 | Level VII and facial (buccinator, nasolabial) nodes involved |
| 111 | Level VI and VII and facial (buccinator, nasolabial) lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Lip, Upper

CS Site-Specific Factor 6 Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|--|
| 000 | No parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), or sub-occipital lymph node involvement |

CS Staging Schemas

| Code | Description |
|------|---|
| 100 | Parapharyngeal lymph node(s) involved |
| 010 | Parotid (preauricular, periparotid, and/or intraparotid) lymph node(s) involved |
| 001 | Sub-occipital lymph node(s) involved |
| 110 | Parapharyngeal and parotid (preauricular, periparotid, and/or intraparotid) lymph nodes involved |
| 101 | Parapharyngeal and sub-occipital lymph nodes involved |
| 011 | Parotid (preauricular, periparotid, and/or intraparotid) and sub-occipital lymph nodes involved |
| 111 | Parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), and sub-occipital lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Lip, Lower

Lip (Vermilion or Labial Mucosa)

C00.1, C00.4, C00.6

C00.1 External lower lip

C00.4 Mucosa of lower lip

C00.6 Commissure of lip

Note: AJCC includes labial mucosa (C00.4) with buccal mucosa (C06.0)

| CS Tumor Size CS Extension CS TS/Ext-Eval CS Lymph Nodes CS Reg Nodes Eval Reg LN Pos Reg LN Exam CS Mets at DX CS Mets Eval | CS Site-Specific Factor 1 - Size of Lymph Nodes CS Site-Specific Factor 2 - Extracapsular Extension, Lymph Nodes for Head and Neck CS Site-Specific Factor 3 - Levels I-III, Lymph Nodes for Head and Neck CS Site-Specific Factor 4 - Levels IV-V and Retropharyngeal Lymph Nodes for Head and Neck CS Site-Specific Factor 5 - Levels VI-VII and Facial Lymph Nodes for Head and Neck CS Site-Specific Factor 6 - Parapharyngeal, Parotid, Preauricular, and Sub-Occipital | The following tables are available at the collaborative staging website: Histology Exclusion Table AJCC Stage Extension Size Table Lymph Nodes Size Table |
|--|--|---|
| | Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck | |

Lip, Lower CS Tumor Size SEE STANDARD TABLE

Lip, Lower

CS Extension (Revised: 08/22/2006)

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 00 | In situ; noninvasive; intraepithelial | Tis | IS | IS |
| 10 | Invasive tumor confined to: Labial mucosa (inner lip) Lamina propria Multiple foci Submucosa (superficial invasion) Vermilion surface Superficial extension to: Skin of lip Subcutaneous soft tissue of lip | * | L | L |
| 20 | Musculature | * | L | L |
| 30 | Localized, NOS | * | L | L |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 50 | Buccal mucosa (inner cheek) Commissure Opposite (both) lip(s) | * | RE | RE |
| 51 | Gingiva | * | RE | RE |
| 70 | Mandible | T4 | RE | RE |
| 74 | Nose | T4 | RE | D |
| 75 | Tongue | T4 | D | D |
| 76 | Skin of face/neck | T4 | D | D |
| 77 | Cortical bone (other than code 70) Floor of mouth Inferior alveolar nerve | T4 | D | D |
| 80 | Further contiguous extension | Т4 | D | D |
| 95 | No evidence of primary tumor | ТО | U | U |
| 99 | Unknown extension Primary tumor cannot be assessed Not documented in patient record | TX | U | U |

^{*} For Extension codes 10, 20, 30, 50, and 51 ONLY, the T category is assigned based on the value of CS Tumor Size, as shown in the Extension Size Table for this site.

Lip, Lower CS TS/Ext-Eval SEE STANDARD TABLE

Lip, Lower

CS Lymph Nodes (Revised: 08/21/2006)

Note 1: For head and neck schemas, this field includes all lymph nodes defined as Levels I-VII and Other by AJCC. The complete definitions are provided in the General Instructions.

Note 2: For head and neck schemas, additional information about lymph nodes (size of involved nodes, extracapsular extension, and levels involved) is coded in Site-Specific Factors 1-6.

Note 3: If laterality of lymph nodes is not specified, assume nodes are ipsilateral. Midline nodes are considered ipsilateral.

Note 4: For head and neck cancers, if lymph nodes are described only as "supraclavicular", try to determine if they are in Level IV (deep to the sternocleidomastoid muscle, in the lower jugular chain) or Level V (in the posterior triangle, inferior to the transverse cervical artery) and code appropriately. If the specific level cannot be determined, consider them as Level V nodes.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | None; no regional lymph node involvement | N0 | NONE | NONE |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 10 | Single positive ipsilateral regional node: Level I node Submandibular (submaxillary) Submental Other groups Facial: Mandibular Regional lymph node, NOS | * | RN | RN |
| 11 | Single positive ipsilateral regional node: Level II node Upper deep cervical Upper jugular Level III node Middle deep cervical Mid-jugular Level IV node Jugulo-omohyoid (supraomohyoid) Lower deep cervical Lower jugular Cervical, NOS Deep cervical, NOS Internal jugular, NOS | * | D | RN |
| 12 | Single positive ipsilateral regional node: Level V node Posterior cervical Posterior triangle (spinal accessory and transverse cervical) (upper, middle, and lower corresponding to the levels that define upper, middle, and lower jugular nodes) Level VI node Anterior deep cervical Laterotracheal Paralaryngeal Paratracheal Prelaryngeal Pretracheal Recurrent laryngeal Level VII node Upper mediastinum (for other mediastinal nodes see CS Mets at DX) Other groups Intraparotid Parapharyngeal Periparotid Retropharyngeal Sub-occipital Supraclavicular, NOS (See Note 4) | * | D | D |
| 18 | Stated as N1, no other information | N1 | RN | RN |
| 19 | Stated as N2a, no other information | N2a | RN | RN |
| 20 | Multiple positive ipsilateral nodes listed in code 10 | * | RN | RN |
| 21 | Multiple positive ipsilateral nodes listed in code 11 | * | D | RN |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-------|------|--------|
| 22 | Multiple positive ipsilateral nodes listed in code 12 | * | D | D |
| 29 | Stated as N2b, no other information | N2b | RN | RN |
| 30 | Regional lymph nodes as listed in code 10: Positive ipsilateral node(s), not stated if single or multiple | * | RN | RN |
| 31 | Regional lymph nodes as listed in code 11: Positive ipsilateral node(s), not stated if single or multiple | * | D | RN |
| 32 | Regional lymph nodes as listed in code 12: Positive ipsilateral node(s), not stated if single or multiple | * | D | D |
| 40 | Regional lymph nodes as listed in code 10: Positive bilateral or contralateral nodes | * | RN | RN |
| 41 | Regional lymph nodes as listed in code 11: Positive bilateral or contralateral nodes | * | D | RN |
| 42 | Regional lymph nodes as listed in code 12: Positive bilateral or contralateral nodes | * | D | D |
| 49 | Stated as N2c, no other information | N2c | RN | RN |
| 50 | Regional lymph nodes as listed in code 10: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | RN | RN |
| 51 | Regional lymph nodes as listed in code 11: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | RN |
| 52 | Regional lymph nodes as listed in code 12: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | D |
| 60 | Stated as N2, NOS | N2NOS | RN | RN |
| 70 | Stated as N3, no other information | N3 | RN | RN |
| 80 | Lymph nodes, NOS, no other information | * | RN | RN |
| 99 | Unknown; not stated Regional lymph nodes cannot be assessed Not documented in patient record | NX | U | U |

^{*} For codes 10-12, 20-22, 30-32, 40-42, 50-52, and 80 ONLY, the N category is assigned based on the value of Site Specific Factor 1, Size of Lymph Nodes, using the extra table, Lymph Nodes Size Table for this site.

Lip, Lower CS Reg Nodes Eval SEE STANDARD TABLE

CS Staging Schemas

Lip, Lower Reg LN Pos SEE STANDARD TABLE

Lip, Lower Reg LN Exam SEE STANDARD TABLE

Lip, Lower

CS Mets at DX (Revised: 08/14/2006)

Note: Supraclavicular and transverse cervical lymph nodes are now coded in CS Lymph Nodes because they are categorized as N rather than M in AJCC TNM. Any cases coded to 10 or 50 can be reviewed and recoded. The volume of cases affected should be small.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | No; none | M0 | NONE | NONE |
| 10 | Distant lymph node(s) Mediastinal Distant lymph node(s), NOS | M1 | D | D |
| 40 | Distant metastases except distant lymph node(s) (code 10) Distant metastasis, NOS Carcinomatosis | M1 | D | D |
| 50 | (10) + (40) Distant lymph node(s) plus other distant metastases | M1 | D | D |
| 99 | Unknown if distant metastasis Distant metastasis cannot be assessed Not documented in patient record | MX | U | U |

Lip, Lower CS Mets Eval SEE STANDARD TABLE

Lip, Lower

CS Site-Specific Factor 1 Size of Lymph Nodes (Revised: 08/18/2006)

Note: Code the largest diameter, whether measured clinically or pathologically, of any involved regional lymph node(s). Do not code the size of any nodes coded in CS Mets at DX.

| Code | Description |
|---------|--|
| 000 | No involved regional nodes |
| 001-988 | 001-988 millimeters (code exact size in millimeters) |
| 989 | 989 millimeters or larger |
| 990 | Microscopic focus or foci only, no size of focus given |
| 991 | Described as "less than 1cm" |

CS Staging Schemas

| Code | Description |
|------|--|
| 992 | Described as "less than 2cm" or "greater than 1cm" or "between 1cm and 2cm" |
| 993 | Described as "less than 3cm" or "greater than 2cm" or "between 2cm and 3cm" |
| 994 | Described as "less than 4cm" or "greater than 3cm" or "between 3cm and 4cm" |
| 995 | Described as "less than 5cm" or "greater than 4cm" or "between 4cm and 5cm" |
| 996 | Described as "less than 6cm" or "greater than 5cm" or "between 5cm and 6cm" |
| 997 | Described as "more than 6cm" |
| 999 | Regional lymph node(s) involved, size not stated Unknown if regional lymph node(s) involved Not documented in patient record |

Lip, Lower

CS Site-Specific Factor 2 Extracapsular Extension, Lymph Nodes for Head and Neck (Revised: 08/17/2007)

Note 1: Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. Do not code extracapsular extension in any nodes coded in CS Mets at DX in this field.

Note 2: A statement of the presence or absence of extracapsular extension in a pathology report takes priority over clinical assessment. However, if the pathology report contains no statement about extracapsular extension, either positive or negative, the clinical assessment should be coded. If nodes are involved but there is neither a clinical assessment of extranodal extension nor a statement about it in the pathology report, use code 999.

Note 3: According to AJCC (page 24), "Imaging studies showing amorphous spiculated margins of involved nodes or involvement of internodal fat resulting in loss of normal oval-to-round nodal shape strongly suggest extracapsular (extranodal) tumor spread; however, pathologic examination is necessary for documentation of the extent of such disease."

| Code | Description |
|------|---|
| 000 | No extracapsular extension |
| 001 | Extracapsular extension clinically, not assessed pathologically Nodes described as "fixed", not assessed pathologically |
| 005 | Extracapsular extension present pathologically |
| 888 | Not applicable; no lymph node involvement |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Lip, Lower

CS Site-Specific Factor 3 Levels I-III, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels I, II, or III |
| 100 | Level I lymph node(s) involved |
| 010 | Level II lymph node(s) involved |
| 001 | Level III lymph node(s) involved |
| 110 | Level I and II lymph nodes involved |
| 101 | Level I and III lymph nodes involved |
| 011 | Level II and III lymph nodes involved |
| 111 | Level I, II and III lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Lip, Lower

CS Site-Specific Factor 4 Levels IV-V and Retropharyngeal Lymph Nodes for Head and

Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|--|
| 000 | No lymph node involvement in Levels IV or V or retropharyngeal |
| 100 | Level IV lymph node(s) involved |
| 010 | Level V lymph node(s) involved |
| 001 | Retropharyngeal nodes involved |
| 110 | Level IV and V lymph nodes involved |
| 101 | Level IV and retropharyngeal nodes involved |
| 011 | Level V and retropharyngeal nodes involved |

CS Staging Schemas

| Code | Description |
|------|---|
| 111 | Level IV and V and retropharyngeal lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Lip, Lower

CS Site-Specific Factor 5 Levels VI-VII and Facial Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels VI or VII or facial nodes |
| 100 | Level VI lymph node(s) involved |
| 010 | Level VII lymph node(s) involved |
| 001 | Facial (buccinator, nasolabial) lymph node(s) involved |
| 110 | Level VI and VII lymph nodes involved |
| 101 | Level VI and facial (buccinator, nasolabial) nodes involved |
| 011 | Level VII and facial (buccinator, nasolabial) nodes involved |
| 111 | Level VI and VII and facial (buccinator, nasolabial) lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Lip, Lower

CS Site-Specific Factor 6 Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|--|
| 000 | No parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), or sub-occipital lymph node involvement |

CS Staging Schemas

| Code | Description |
|------|---|
| 100 | Parapharyngeal lymph node(s) involved |
| 010 | Parotid (preauricular, periparotid, and/or intraparotid) lymph node(s) involved |
| 001 | Sub-occipital lymph node(s) involved |
| 110 | Parapharyngeal and parotid (preauricular, periparotid, and/or intraparotid) lymph nodes involved |
| 101 | Parapharyngeal and sub-occipital lymph nodes involved |
| 011 | Parotid (preauricular, periparotid, and/or intraparotid) and sub-occipital lymph nodes involved |
| 111 | Parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), and sub-occipital lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Other Lip

Lip (Vermilion or Labial Mucosa)

C00.2, C00.5, C00.8-C00.9

C00.2 External lip, NOS

C00.5 Mucosa of lip, NOS

C00.8 Overlapping lesion of lip

C00.9 Lip, NOS (excludes skin of lip C44.0)

Note: AJCC includes labial mucosa (C00.5) with buccal mucosa (C06.0)

| CS Tumor Size CS Extension CS TS/Ext-Eval CS Lymph Nodes CS Reg Nodes Eval Reg LN Pos Reg LN Exam CS Mets at DX CS Mets Eval | CS Site-Specific Factor 1 - Size of Lymph Nodes CS Site-Specific Factor 2 - Extracapsular Extension, Lymph Nodes for Head and Neck CS Site-Specific Factor 3 - Levels I-III, Lymph Nodes for Head and Neck CS Site-Specific Factor 4 - Levels IV-V and Retropharyngeal Lymph Nodes for Head and Neck CS Site-Specific Factor 5 - Levels VI-VII and Facial Lymph Nodes for Head and Neck CS Site-Specific Factor 6 - Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck | The following tables are available at the collaborative staging website: Histology Exclusion Table AJCC Stage Extension Size Table Lymph Nodes Size Table |
|--|---|---|
| | ricau anu ineck | |

Other Lip CS Tumor Size SEE STANDARD TABLE

Other Lip

CS Extension (Revised: 08/22/2006)

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 00 | In situ; noninvasive; intraepithelial | Tis | IS | IS |
| 10 | Invasive tumor confined to: Labial mucosa (inner lip) Lamina propria Multiple foci Submucosa (superficial invasion) Vermilion surface Superficial extension to: Skin of lip Subcutaneous soft tissue of lip | * | L | L |
| 20 | Musculature | * | L | L |
| 30 | Localized, NOS | * | L | L |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 50 | Buccal mucosa (inner cheek) Commissure Opposite (both) lip(s) | * | RE | RE |
| 51 | Gingiva | * | RE | RE |
| 75 | Tongue | T4 | D | D |
| 76 | Skin of face/neck | T4 | D | D |
| 77 | Cortical bone Floor of mouth Inferior alveolar nerve | T4 | D | D |
| 80 | Further contiguous extension | T4 | D | D |
| 95 | No evidence of primary tumor | ТО | U | U |
| 99 | Unknown extension Primary tumor cannot be assessed Not documented in patient record | TX | U | U |

^{*} For Extension codes 10, 20, 30, 50, and 51 ONLY, the T category is assigned based on the value of CS Tumor Size, as shown in the Extension Size Table for this site.

Other Lip CS TS/Ext-Eval SEE STANDARD TABLE

Other Lip

CS Lymph Nodes (Revised: 08/21/2006)

Note 1: For head and neck schemas, this field includes all lymph nodes defined as Levels I-VII and Other by AJCC. The complete definitions are provided in the General Instructions.

Note 2: For head and neck schemas, additional information about lymph nodes (size of involved nodes, extracapsular extension, and levels involved) is coded in Site-Specific Factors 1-6.

Note 3: If laterality of lymph nodes is not specified, assume nodes are ipsilateral. Midline nodes are considered ipsilateral.

Note 4: For head and neck cancers, if lymph nodes are described only as "supraclavicular", try to determine if they are in Level IV (deep to the sternocleidomastoid muscle, in the lower jugular chain) or Level V (in the posterior triangle, inferior to the transverse cervical artery) and code appropriately. If the specific level cannot be determined, consider them as Level V nodes.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | None; no regional lymph node involvement | N0 | NONE | NONE |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 10 | Single positive ipsilateral regional node: Level I node: Submandibular (submaxillary) Submental Other groups: Facial: Buccinator (buccal) Mandibular Nasolabial Parotid: Infra-auricular Intraparotid Periparotid Preauricular Regional lymph node, NOS | * | RN | RN |
| 11 | Single positive ipsilateral regional node: Level II node Jugulodigastric (subdigastric) Upper deep cervical Upper jugular Level III node Middle deep cervical Mid jugular Level IV node Jugulo-omohyoid (supraomohyoid) Lower deep cervical Lower jugular Cervical, NOS Deep cervical, NOS Internal jugular, NOS | * | D | RN |
| 12 | Single positive ipsilateral regional node: Level V node Posterior cervical Posterior triangle (spinal accessory and transverse cervical) (upper, middle, and lower corresponding to the levels that define upper, middle, and lower jugular nodes) Level VI node Anterior deep cervical Laterotracheal Paralaryngeal Paratracheal Prelaryngeal Pretracheal Recurrent laryngeal Level VII node Upper mediastinum (for other mediastinal nodes see CS Mets at DX) Other groups Parapharyngeal Retropharyngeal Retropharyngeal Sub-occipital Supraclavicular, NOS (See Note 4) | * | D | D |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-------|------|--------|
| 18 | Stated as N1, no other information | N1 | RN | RN |
| 19 | Stated as N2a, no other information | N2a | RN | RN |
| 20 | Multiple positive ipsilateral nodes listed in code 10 | * | RN | RN |
| 21 | Multiple positive ipsilateral nodes listed in code 11 | * | D | RN |
| 22 | Multiple positive ipsilateral nodes listed in code 12 | * | D | D |
| 29 | Stated as N2b, no other information | N2b | RN | RN |
| 30 | Regional lymph nodes as listed in code 10: Positive ipsilateral node(s), not stated if single or multiple | * | RN | RN |
| 31 | Regional lymph nodes as listed in code 11: Positive ipsilateral node(s), not stated if single or multiple | * | D | RN |
| 32 | Regional lymph nodes as listed in code 12: Positive ipsilateral node(s), not stated if single or multiple | * | D | D |
| 40 | Regional lymph nodes as listed in code 10: Positive bilateral or contralateral nodes | * | RN | RN |
| 41 | Regional lymph nodes as listed in code 11: Positive bilateral or contralateral nodes | * | D | RN |
| 42 | Regional lymph nodes as listed in code 12: Positive bilateral or contralateral nodes | * | D | D |
| 49 | Stated as N2c, no other information | N2c | RN | RN |
| 50 | Regional lymph nodes as listed in code 10: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | RN | RN |
| 51 | Regional lymph nodes as listed in code 11: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | RN |
| 52 | Regional lymph nodes as listed in code 12: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | D |
| 60 | Stated as N2, NOS | N2NOS | RN | RN |
| 70 | Stated as N3, no other information | N3 | RN | RN |
| 80 | Lymph nodes, NOS, no other information | * | RN | RN |
| 99 | Unknown; not stated Regional lymph nodes cannot be assessed Not documented in patient record | NX | U | U |
| | | | | 0.01: |

^{*} For codes 10-12, 20-22, 30-32, 40-42, 50-52, and 80 ONLY, the N category is assigned based on the value of Site-Specific Factor 1, Size of Lymph Nodes, using the extra table, Lymph Nodes Size Table for this site.

CS Staging Schemas

Other Lip CS Reg Nodes Eval SEE STANDARD TABLE

Other Lip Reg LN Pos SEE STANDARD TABLE

Other Lip Reg LN Exam SEE STANDARD TABLE

Other Lip

CS Mets at DX (Revised: 08/14/2006)

Note: Supraclavicular and transverse cervical lymph nodes are now coded in CS Lymph Nodes because they are categorized as N rather than M in AJCC TNM. Any cases coded to 10 or 50 can be reviewed and recoded. The volume of cases affected should be small.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | No; none | M0 | NONE | NONE |
| 10 | Distant lymph node(s) Mediastinal Distant lymph node(s), NOS | M1 | D | D |
| 40 | Distant metastases except distant lymph node(s) (code 10) Distant metastasis, NOS Carcinomatosis | M1 | D | D |
| 50 | (10) + (40) Distant lymph node(s) plus other distant metastases | M1 | D | D |
| 99 | Unknown if distant metastasis Distant metastasis cannot be assessed Not documented in patient record | MX | U | U |

Other Lip CS Mets Eval SEE STANDARD TABLE

Other Lip

CS Site-Specific Factor 1 Size of Lymph Nodes (Revised: 08/18/2006)

Note: Code the largest diameter, whether measured clinically or pathologically, of any involved regional lymph node(s). Do not code the size of any nodes coded in CS Mets at DX.

| Code | Description |
|------|----------------------------|
| 000 | No involved regional nodes |

CS Staging Schemas

| Code | Description |
|---------|--|
| 001-988 | 001-988 millimeters (code exact size in millimeters) |
| 989 | 989 millimeters or larger |
| 990 | Microscopic focus or foci only, no size of focus given |
| 991 | Described as "less than 1cm" |
| 992 | Described as "less than 2cm" or "greater than 1cm" or "between 1cm and 2cm" |
| 993 | Described as "less than 3cm" or "greater than 2cm" or "between 2cm and 3cm" |
| 994 | Described as "less than 4cm" or "greater than 3cm" or "between 3cm and 4cm" |
| 995 | Described as "less than 5cm" or "greater than 4cm" or "between 4cm and 5cm" |
| 996 | Described as "less than 6cm" or "greater than 5cm" or "between 5cm and 6cm" |
| 997 | Described as "more than 6cm" |
| 999 | Regional lymph node(s) involved, size not stated Unknown if regional lymph node(s) involved Not documented in patient record |

Other Lip

CS Site-Specific Factor 2 Extracapsular Extension, Lymph Nodes for Head and Neck (Revised: 08/17/2007)

Note 1: Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. Do not code extracapsular extension in any nodes coded in CS Mets at DX in this field.

Note 2: A statement of the presence or absence of extracapsular extension in a pathology report takes priority over clinical assessment. However, if the pathology report contains no statement about extracapsular extension, either positive or negative, the clinical assessment should be coded. If nodes are involved but there is neither a clinical assessment of extranodal extension nor a statement about it in the pathology report, use code 999.

Note 3: According to AJCC (page 24), "Imaging studies showing amorphous spiculated margins of involved nodes or involvement of internodal fat resulting in loss of normal oval-to-round nodal shape strongly suggest extracapsular (extranodal) tumor spread; however, pathologic examination is necessary for documentation of the extent of such disease."

| Code | Description |
|------|---|
| 000 | No extracapsular extension |
| 001 | Extracapsular extension clinically, not assessed pathologically Nodes described as "fixed", not assessed pathologically |
| 005 | Extracapsular extension present pathologically |
| 888 | Not applicable; no lymph node involvement |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Other Lip

CS Site-Specific Factor 3 Levels I-III, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels I, II, or III |
| 100 | Level I lymph node(s) involved |
| 010 | Level II lymph node(s) involved |
| 001 | Level III lymph node(s) involved |
| 110 | Level I and II lymph nodes involved |
| 101 | Level I and III lymph nodes involved |
| 011 | Level II and III lymph nodes involved |
| 111 | Level I, II and III lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Other Lip

CS Site-Specific Factor 4 Levels IV-V and Retropharyngeal Lymph Nodes for Head and

Neck (Revised: 08/21/2006)

| Code | Description |
|------|--|
| 000 | No lymph node involvement in Levels IV or V or retropharyngeal |
| 100 | Level IV lymph node(s) involved |
| 010 | Level V lymph node(s) involved |
| 001 | Retropharyngeal nodes involved |
| 110 | Level IV and V lymph nodes involved |
| 101 | Level IV and retropharyngeal nodes involved |
| 011 | Level V and retropharyngeal nodes involved |

CS Staging Schemas

| Code | Description |
|------|---|
| 111 | Level IV and V and retropharyngeal lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Other Lip

CS Site-Specific Factor 5 Levels VI-VII and Facial Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels VI or VII or facial nodes |
| 100 | Level VI lymph node(s) involved |
| 010 | Level VII lymph node(s) involved |
| 001 | Facial (buccinator, nasolabial) lymph node(s) involved |
| 110 | Level VI and VII lymph nodes involved |
| 101 | Level VI and facial (buccinator, nasolabial) nodes involved |
| 011 | Level VII and facial (buccinator, nasolabial) nodes involved |
| 111 | Level VI and VII and facial (buccinator, nasolabial) lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Other Lip

CS Site-Specific Factor 6 Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|--|
| 000 | No parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), or sub-occipital lymph node involvement |

CS Staging Schemas

| Code | Description | | | |
|------|---|--|--|--|
| 100 | Parapharyngeal lymph node(s) involved | | | |
| 010 | Parotid (preauricular, periparotid, and/or intraparotid) lymph node(s) involved | | | |
| 001 | Sub-occipital lymph node(s) involved | | | |
| 110 | Parapharyngeal and parotid (preauricular, periparotid, and/or intraparotid) lymph nodes involved | | | |
| 101 | Parapharyngeal and sub-occipital lymph nodes involved | | | |
| 011 | Parotid (preauricular, periparotid, and/or intraparotid) and sub-occipital lymph nodes involved | | | |
| 111 | Parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), and sub-occipital lymph nodes involved | | | |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record | | | |

CS Staging Schemas

Base of Tongue, Lingual Tonsil C01.9, C02.4

C01.9 Base of tongue, NOS C02.4 Lingual tonsil

Note: AJCC includes base of tongue (C01.9) with oropharynx (C10._).

| CS Tumor Size CS Extension | CS Site-Specific Factor 1 - Size of Lymph Nodes | The following tables are available at the collaborative |
|----------------------------|---|---|
| CS TS/Ext-Eval | CS Site-Specific Factor 2 - | staging website: |
| CS Lymph Nodes | Extracapsular Extension, Lymph | Histology Exclusion Table |
| CS Reg Nodes Eval | Nodes for Head and Neck | AJCC Stage |
| Reg LN Pos | CS Site-Specific Factor 3 - | Extension Size Table |
| Reg LN Exam | Levels I-III, Lymph Nodes for | Lymph Nodes Size Table |
| CS Mets at DX | Head and Neck | • • |
| CS Mets Eval | CS Site-Specific Factor 4 - | |
| | Levels IV-V and Retropharyngeal | |
| | Lymph Nodes for Head and Neck | |
| | CS Site-Specific Factor 5 - | |
| | Levels VI-VII and Facial Lymph | |
| | Nodes for Head and Neck | |
| | CS Site-Specific Factor 6 - | |
| | Parapharyngeal, Parotid, | |
| | Preauricular, and Sub-Occipital | |
| | Lymph Nodes, Lymph Nodes for | |
| | Head and Neck | |

Base of Tongue, Lingual Tonsil CS Tumor Size SEE STANDARD TABLE

Base of Tongue, Lingual Tonsil

CS Extension (Revised: 08/22/2006)

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | In situ; noninvasive; intraepithelial | Tis | IS | IS |
| 10 | Invasive tumor on one side confined to posterior 1/3 of tongue: Lamina propria Submucosa | * | L | L |
| 20 | Musculature, intrinsic or NOS | * | L | L |
| 30 | Localized, NOS Midline tumor | * | L | L |
| 40 | Tumor crosses midline | * | L | L |
| 50 | Anterior 2/3 of tongue for base of tongue Base of tongue for lingual tonsil Floor of mouth Lower gingiva | * | RE | RE |
| 53 | Sublingual gland | * | RE | RE |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 60 | Epiglottis, lingual (pharyngeal) surface Glossoepiglottic fold Glossopharyngeal fold Lateral pharyngeal wall Pharyngoepiglottic fold Tonsillar pillars and fossae Tonsils Vallecula | * | RE | RE |
| 62 | Soft palate, inferior surface or NOS | * | D | RE |
| 71 | Mandible for lingual tonsil | T4a | RE | D |
| 72 | Mandible for base of tongue | T4a | D | D |
| 74 | Medial pterygoid Hard palate | T4a | D | D |
| 75 | Musculature, extrinsic: Genioglossus Geniohyoid Hyoglossus Mylohyoid Palatoglossus Styloglossus | T4a | D | D |
| 77 | Larynx | T4a | D | D |
| 78 | Skin | T4b | D | D |
| 80 | Contiguous extension to: Base of skull Carotid artery Hypopharynx Lateral nasopharynx Lateral pterygoid muscle Pterygoid plates Uvula | T4b | D | D |
| 82 | Further contiguous extension | T4b | D | D |
| 95 | No evidence of primary tumor | ТО | U | U |
| 99 | Unknown extension Primary tumor cannot be assessed Not documented in patient record | TX | U | U |

^{*} For Extension codes 10, 20, 30, 40, 50, 53, 60, and 62 ONLY, the T category is assigned based on the value of CS Tumor Size, as shown in the Extension Size Table for this site.

Base of Tongue, Lingual Tonsil CS TS/Ext-Eval SEE STANDARD TABLE

CS Staging Schemas

Base of Tongue, Lingual Tonsil

CS Lymph Nodes (Revised: 08/22/2006)

Note 1: For head and neck schemas, this field includes all lymph nodes defined as Levels I-VII and Other by AJCC. The complete definitions are provided in the General Instructions.

Note 2: For head and neck schemas, additional information about lymph nodes (size of involved nodes, extracapsular extension, and levels involved) is coded in Site-Specific Factors 1-6.

Note 3: If laterality of lymph nodes is not specified, assume nodes are ipsilateral. Midline nodes are considered ipsilateral.

Note 4: For head and neck cancers, if lymph nodes are described only as "supraclavicular", try to determine if they are in Level IV (deep to the sternocleidomastoid muscle, in the lower jugular chain) or Level V (in the posterior triangle, inferior to the transverse cervical artery) and code appropriately. If the specific level cannot be determined, consider them as Level V nodes.

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 00 | None; no regional lymph node involvement | N0 | NONE | NONE |
| 10 | Single positive ipsilateral regional node: Level I node Sublingual Submandibular (submaxillary) Submental Level II node Jugulodigastric (subdigastric) Upper deep cervical Upper jugular Level III node Middle deep cervical Mid jugular Level IV node Jugulo-omohyoid (supraomohyoid) Lower deep cervical Lower jugular Cervical, NOS Deep cervical, NOS Internal jugular, NOS Mandibular, NOS Regional lymph node, NOS | * | RN | RN |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 12 | Single positive ipsilateral regional node: Level V node Posterior cervical Posterior triangle (spinal accessory and transverse cervical) (upper, middle, and lower corresponding to the levels that define upper, middle, and lower jugular nodes) Level VI node Anterior deep cervical Laterotracheal Paralaryngeal Paratracheal Prelaryngeal Pretracheal Recurrent laryngeal Level VII node Upper mediastinum (for other mediastinal nodes see CS Mets at DX) Other groups Intraparotid Parapharyngeal Periparotid Retropharyngeal Sub-occipital Supraclavicular, NOS (See Note 4) | * | D | D |
| 18 | Stated as N1, no other information | N1 | RN | RN |
| 19 | Stated as N2a, no other information | N2a | RN | RN |
| 20 | Multiple positive ipsilateral nodes listed in code 10 | * | RN | RN |
| 22 | Multiple positive ipsilateral nodes listed in code 12 | * | D | D |
| 29 | Stated as N2b, no other information | N2b | RN | RN |
| 30 | Regional lymph nodes as listed in code 10: Positive ipsilateral node(s), not stated if single or multiple | * | RN | RN |
| 32 | Regional lymph nodes as listed in code 12: Positive ipsilateral node(s), not stated if single or multiple | * | D | D |
| 40 | Regional lymph nodes as listed in code 10: Positive bilateral or contralateral nodes | * | RN | RN |
| 42 | Regional lymph nodes as listed in code 12: Positive bilateral or contralateral nodes | * | D | D |
| 49 | Stated as N2c, no other information | N2c | RN | RN |
| 50 | Regional lymph nodes as listed in code 10: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | RN | RN |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-------|------|--------|
| 52 | Regional lymph nodes as listed in code 12: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | D |
| 60 | Stated as N2, NOS | N2NOS | RN | RN |
| 70 | Stated as N3, no other information | N3 | RN | RN |
| 80 | Lymph nodes, NOS | * | RN | RN |
| 99 | Unknown; not stated Regional lymph nodes cannot be assessed Not documented in patient record | NX | U | U |

^{*} For codes 10, 12, 20, 22, 30, 32, 40, 42, 49, 50, 52 and 80 ONLY, the N category is assigned based on the value of Site-Specific Factor 1, Size of Lymph Nodes, using the extra table, Lymph Nodes Size Table for this site.

Base of Tongue, Lingual Tonsil CS Reg Nodes Eval SEE STANDARD TABLE

Base of Tongue, Lingual Tonsil Reg LN Pos SEE STANDARD TABLE

Base of Tongue, Lingual Tonsil Reg LN Exam SEE STANDARD TABLE

Base of Tongue, Lingual Tonsil

CS Mets at DX (Revised: 08/14/2006)

Note: Supraclavicular and transverse cervical lymph nodes are now coded in CS Lymph Nodes because they are categorized as N rather than M in AJCC TNM. Any cases coded to 10 or 50 can be reviewed and recoded. The volume of cases affected should be small.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | No; none | M0 | NONE | NONE |
| 10 | Distant lymph node(s) Mediastinal Distant lymph node(s), NOS | M1 | D | D |
| 40 | Distant metastases except distant lymph node(s) (code 10) Distant metastasis, NOS Carcinomatosis | M1 | D | D |
| 50 | (10) + (40) Distant lymph node(s) plus other distant metastases | M1 | D | D |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 99 | Unknown if distant metastasis Distant metastasis cannot be assessed Not documented in patient record | MX | U | U |

Base of Tongue, Lingual Tonsil CS Mets Eval SEE STANDARD TABLE

Base of Tongue, Lingual Tonsil

CS Site-Specific Factor 1 Size of Lymph Nodes (Revised: 08/18/2006)

Note: Code the largest diameter, whether measured clinically or pathologically, of any involved regional lymph

node(s). Do not code the size of any nodes coded in CS Mets at DX.

| Code | Description |
|---------|--|
| 000 | No involved regional nodes |
| 001-988 | 001-988 millimeters (code exact size in millimeters) |
| 989 | 989 millimeters or larger |
| 990 | Microscopic focus or foci only, no size of focus given |
| 991 | Described as "less than 1cm" |
| 992 | Described as "less than 2cm" or "greater than 1cm" or "between 1cm and 2cm" |
| 993 | Described as "less than 3cm" or "greater than 2cm" or "between 2cm and 3cm" |
| 994 | Described as "less than 4cm" or "greater than 3cm" or "between 3cm and 4cm" |
| 995 | Described as "less than 5cm" or "greater than 4cm" or "between 4cm and 5cm" |
| 996 | Described as "less than 6cm" or "greater than 5cm" or "between 5cm and 6cm" |
| 997 | Described as "more than 6cm" |
| 999 | Regional lymph node(s) involved, size not stated Unknown if regional lymph node(s) involved Not documented in patient record |

CS Staging Schemas

Base of Tongue, Lingual Tonsil

CS Site-Specific Factor 2 Extracapsular Extension, Lymph Nodes for Head and Neck (Revised: 08/17/2007)

Note 1: Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. Do not code extracapsular extension in any nodes coded in CS Mets at DX in this field.

Note 2: A statement of the presence or absence of extracapsular extension in a pathology report takes priority over clinical assessment. However, if the pathology report contains no statement about extracapsular extension, either positive or negative, the clinical assessment should be coded. If nodes are involved but there is neither a clinical assessment of extranodal extension nor a statement about it in the pathology report, use code 999.

Note 3: According to AJCC (page 24), "Imaging studies showing amorphous spiculated margins of involved nodes or involvement of internodal fat resulting in loss of normal oval-to-round nodal shape strongly suggest extracapsular (extranodal) tumor spread; however, pathologic examination is necessary for documentation of the extent of such disease."

| Code | Description |
|------|---|
| 000 | No extracapsular extension |
| 001 | Extracapsular extension clinically, not assessed pathologically Nodes described as "fixed", not assessed pathologically |
| 005 | Extracapsular extension present pathologically |
| 888 | Not applicable; no lymph node involvement |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Base of Tongue, Lingual Tonsil

CS Site-Specific Factor 3 Levels I-III, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels I, II, or III |
| 100 | Level I lymph node(s) involved |
| 010 | Level II lymph node(s) involved |
| 001 | Level III lymph node(s) involved |
| 110 | Level I and II lymph nodes involved |
| 101 | Level I and III lymph nodes involved |
| 011 | Level II and III lymph nodes involved |
| 111 | Level I, II and III lymph nodes involved |

CS Staging Schemas

| Code | Description |
|------|---|
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Base of Tongue, Lingual Tonsil

CS Site-Specific Factor 4 Levels IV-V and Retropharyngeal Lymph Nodes for Head and

Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels IV or V or retropharyngeal |
| 100 | Level IV lymph node(s) involved |
| 010 | Level V lymph node(s) involved |
| 001 | Retropharyngeal nodes involved |
| 110 | Level IV and V lymph nodes involved |
| 101 | Level IV and retropharyngeal nodes involved |
| 011 | Level V and retropharyngeal nodes involved |
| 111 | Level IV and V and retropharyngeal lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Base of Tongue, Lingual Tonsil

CS Site-Specific Factor 5 Levels VI-VII and Facial Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels VI or VII or facial nodes |
| 100 | Level VI lymph node(s) involved |
| 010 | Level VII lymph node(s) involved |

CS Staging Schemas

| Code | Description |
|------|---|
| 001 | Facial (buccinator, nasolabial) lymph node(s) involved |
| 110 | Level VI and VII lymph nodes involved |
| 101 | Level VI and facial (buccinator, nasolabial) nodes involved |
| 011 | Level VII and facial (buccinator, nasolabial) nodes involved |
| 111 | Level VI and VII and facial (buccinator, nasolabial) lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Base of Tongue, Lingual Tonsil

CS Site-Specific Factor 6 Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|---|
| 000 | No parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), or sub-occipital lymph node involvement |
| 100 | Parapharyngeal lymph node(s) involved |
| 010 | Parotid (preauricular, periparotid, and/or intraparotid) lymph node(s) involved |
| 001 | Sub-occipital lymph node(s) involved |
| 110 | Parapharyngeal and parotid (preauricular, periparotid, and/or intraparotid) lymph nodes involved |
| 101 | Parapharyngeal and sub-occipital lymph nodes involved |
| 011 | Parotid (preauricular, periparotid, and/or intraparotid) and sub-occipital lymph nodes involved |
| 111 | Parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), and sub-occipital lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Anterior 2/3 of Tongue, Tip, Border, and Tongue, NOS C02.0-C02.3, C02.8-C02.9

C02.0 Dorsal surface of tongue, NOS

C02.1 Border of tongue

C02.2 Ventral surface of tongue, NOS

C02.3 Anterior 2/3 of tongue, NOS

C02.8 Overlapping lesion of tongue

C02.9 Tongue, NOS

| CS Tumor Size CS Extension CS TS/Ext-Eval CS Lymph Nodes CS Reg Nodes Eval Reg LN Pos Reg LN Exam CS Mets at DX CS Mets Eval | CS Site-Specific Factor 1 - Size of Lymph Nodes CS Site-Specific Factor 2 - Extracapsular Extension, Lymph Nodes for Head and Neck CS Site-Specific Factor 3 - Levels I-III, Lymph Nodes for Head and Neck CS Site-Specific Factor 4 - Levels IV-V and Retropharyngeal Lymph Nodes for Head and Neck CS Site-Specific Factor 5 - Levels VI-VII and Facial Lymph Nodes for Head and Neck CS Site-Specific Factor 6 - Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck | The following tables are available at the collaborative staging website: Histology Exclusion Table AJCC Stage Extension Size Table Lymph Nodes Size Table |
|--|---|---|
|--|---|---|

Anterior 2/3 of Tongue, Tip, Border, and Tongue, NOS CS Tumor Size SEE STANDARD TABLE

Anterior 2/3 of Tongue, Tip, Border, and Tongue, NOS

CS Extension (Revised: 08/22/2006)

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 00 | In situ; noninvasive; intraepithelial | Tis | IS | IS |
| 10 | Invasive tumor on one side confined to: Lamina propria Submucosa | * | L | L |
| 20 | Musculature, intrinsic or NOS | * | L | L |
| 30 | Localized, NOS Midline tumor | * | L | L |
| 40 | Tumor crosses midline | * | L | L |
| 50 | Base of tongue Floor of mouth Gingiva, lower Retromolar trigone | * | RE | RE |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 53 | Sublingual gland | * | RE | RE |
| 60 | Lateral pharyngeal wall Soft palate, inferior surface Tonsillar pillars and fossae Tonsils | * | D | RE |
| 70 | Mandible | T4a | RE | D |
| 72 | (60) + (70) | T4a | D | D |
| 74 | Maxilla Maxillary sinus | T4a | D | D |
| 75 | Musculature, extrinsic: Genioglossus Geniohyoid Hyoglossus Mylohyoid Palatoglossus Styloglossus | T4a | D | D |
| 80 | Further contiguous extension | T4b | D | D |
| 95 | No evidence of primary tumor | ТО | U | U |
| 99 | Unknown extension Primary tumor cannot be assessed Not documented in patient record | TX | U | U |

^{*} For codes 10, 20, 30, 40, 50, 53, and 60 ONLY, the T category is assigned based on the value of CS Tumor Size, as shown in the Extension Size Table for this site.

Anterior 2/3 of Tongue, Tip, Border, and Tongue, NOS CS TS/Ext-Eval SEE STANDARD TABLE

Anterior 2/3 of Tongue, Tip, Border, and Tongue, NOS

CS Lymph Nodes (Revised: 08/22/2006)

Note 1: For head and neck schemas, this field includes all lymph nodes defined as Levels I-VII and Other by AJCC. The complete definitions are provided in the General Instructions.

Note 2: For head and neck schemas, additional information about lymph nodes (size of involved nodes, extracapsular extension, and levels involved) is coded in Site-Specific Factors 1-6.

Note 3: If laterality of lymph nodes is not specified, assume nodes are ipsilateral. Midline nodes are considered ipsilateral.

Note 4: For head and neck cancers, if lymph nodes are described only as "supraclavicular", try to determine if they are Level IV (deep to the sternocleidomastoid muscle, in the lower jugular chain) or Level V (in the posterior triangle, inferior to the transverse cervical artery) and code appropriately. If the specific level cannot be determined, consider them as Level V nodes.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | None; no regional lymph node involvement | N0 | NONE | NONE |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 10 | Single positive ipsilateral regional node: Level I node Sublingual Submandibular (submaxillary) Submental Level II node Jugulodigastric (subdigastric) Upper deep cervical Upper jugular Level III node Middle deep cervical Mid jugular Level IV node Jugulo-omohyoid (supraomohyoid) Lower deep cervical Lower jugular Cervical, NOS Deep cervical, NOS Internal jugular, NOS Mandibular, NOS Regional lymph node, NOS | * | RN | RN |
| 12 | Single positive ipsilateral regional node: Level V node Posterior cervical Posterior triangle (spinal accessory and transverse cervical) (upper, middle, and lower corresponding to the levels that define upper, middle, and lower jugular nodes) Level VI node Anterior deep cervical Laterotracheal Paralaryngeal Paratracheal Prelaryngeal Pretracheal Recurrent laryngeal Level VII node Upper mediastinum (for other mediastinal nodes see CS Mets at DX) Other groups Intraparotid Parapharyngeal Periparotid Retropharyngeal Sub-occipital Supraclavicular, NOS (See Note 4) | * | D | D |
| 18 | Stated as N1, no other information | N1 | RN | RN |
| 19 | Stated as N2a, no other information | N2a | RN | RN |
| 20 | Multiple positive ipsilateral nodes listed in code 10 | * | RN | RN |
| 22 | Multiple positive ipsilateral nodes listed in code 12 | * | D | D |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-------|------|--------|
| 29 | Stated as N2b, no other information | N2b | RN | RN |
| 30 | Regional lymph nodes as listed in code 10: Positive ipsilateral node(s), not stated if single or multiple | * | RN | RN |
| 32 | Regional lymph nodes as listed in code 12: Positive ipsilateral node(s), not stated if single or multiple | * | D | D |
| 40 | Regional lymph nodes as listed in code 10: Positive bilateral or contralateral nodes | * | RN | RN |
| 42 | Regional lymph nodes as listed in code 12: Positive bilateral or contralateral nodes | * | D | D |
| 49 | Stated as N2c, no other information | N2c | RN | RN |
| 50 | Regional lymph nodes as listed in code 10: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | RN | RN |
| 52 | Regional lymph nodes as listed in code 12: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | D |
| 60 | Stated as N2, NOS | N2NOS | RN | RN |
| 70 | Stated as N3, no other information | N3 | RN | RN |
| 80 | Lymph nodes, NOS | * | RN | RN |
| 99 | Unknown; not stated Regional lymph nodes cannot be assessed Not documented in patient record | NX | U | U |

^{*} For codes 10, 12, 20, 22, 30, 32, 40, 42, 49, 50, 52 and 80 ONLY, the N category is assigned based on the value of Site-Specific Factor 1, Size of Lymph Nodes, using the extra table, Lymph Nodes Size Table for this site.

Anterior 2/3 of Tongue, Tip, Border, and Tongue, NOS CS Reg Nodes Eval SEE STANDARD TABLE

Anterior 2/3 of Tongue, Tip, Border, and Tongue, NOS Reg LN Pos SEE STANDARD TABLE

Anterior 2/3 of Tongue, Tip, Border, and Tongue, NOS Reg LN Exam SEE STANDARD TABLE

CS Staging Schemas

Anterior 2/3 of Tongue, Tip, Border, and Tongue, NOS

CS Mets at DX (Revised: 08/15/2006)

Note: Supraclavicular and transverse cervical lymph nodes are now coded in CS Lymph Nodes because they are categorized as N rather than M in AJCC TNM. Any cases coded to 10 or 50 can be reviewed and recoded. The volume of cases affected should be small.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | No; none | M0 | NONE | NONE |
| 10 | Distant lymph node(s), including: Mediastinal Distant lymph nodes, NOS | M1 | D | D |
| 40 | Distant metastases except distant lymph node(s) (code 10) Distant metastasis, NOS Carcinomatosis | M1 | D | D |
| 50 | (10) + (40) | M1 | D | D |
| 99 | Unknown if distant metastasis Distant metastasis cannot be assessed Not documented in patient record | MX | U | U |

Anterior 2/3 of Tongue, Tip, Border, and Tongue, NOS CS Mets Eval SEE STANDARD TABLE

Anterior 2/3 of Tongue, Tip, Border, and Tongue, NOS

CS Site-Specific Factor 1 Size of Lymph Nodes (Revised: 08/18/2006)

Note: Code the largest diameter, whether measured clinically or pathologically, of any involved regional lymph node(s). Do not code the size of any nodes coded in CS Mets at DX.

| Code | Description |
|---------|---|
| 000 | No involved regional nodes |
| 001-988 | 001-988 millimeters (code exact size in millimeters) |
| 989 | 989 millimeters or larger |
| 990 | Microscopic focus or foci only, no size of focus given |
| 991 | Described as "less than 1cm" |
| 992 | Described as "less than 2cm" or "greater than 1cm" or "between 1cm and 2cm" |
| 993 | Described as "less than 3cm" or "greater than 2cm" or "between 2cm and 3cm" |
| 994 | Described as "less than 4cm" or "greater than 3cm" or "between 3cm and 4cm" |
| 995 | Described as "less than 5cm" or "greater than 4cm" or "between 4cm and 5cm" |
| 996 | Described as "less than 6cm" or "greater than 5cm" or "between 5cm and 6cm" |
| 997 | Described as "more than 6cm" |

CS Staging Schemas

| Code | Description |
|------|--|
| 999 | Regional lymph node(s) involved, size not stated Unknown if regional lymph node(s) involved Not documented in patient record |

Anterior 2/3 of Tongue, Tip, Border, and Tongue, NOS

CS Site-Specific Factor 2 Extracapsular Extension, Lymph Nodes for Head and Neck (Revised: 08/17/2007)

- **Note 1:** Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. Do not code extracapsular extension in any nodes coded in CS Mets at DX in this field.
- **Note 2:** A statement of the presence or absence of extracapsular extension in a pathology report takes priority over clinical assessment. However, if the pathology report contains no statement about extracapsular extension, either positive or negative, the clinical assessment should be coded. If nodes are involved but there is neither a clinical assessment of extranodal extension nor a statement about it in the pathology report, use code 999.
- **Note 3:** According to AJCC (page 24), "Imaging studies showing amorphous spiculated margins of involved nodes or involvement of internodal fat resulting in loss of normal oval-to-round nodal shape strongly suggest extracapsular (extranodal) tumor spread; however, pathologic examination is necessary for documentation of the extent of such disease."

| Code | Description |
|------|---|
| 000 | No extracapsular extension |
| 001 | Extracapsular extension clinically, not assessed pathologically Nodes described as "fixed", not assessed pathologically |
| 005 | Extracapsular extension present pathologically |
| 888 | Not applicable; no lymph node involvement |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Anterior 2/3 of Tongue, Tip, Border, and Tongue, NOS

CS Site-Specific Factor 3 Levels I-III, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels I, II, or III |
| 100 | Level I lymph node(s) involved |
| 010 | Level II lymph node(s) involved |
| 001 | Level III lymph node(s) involved |
| 110 | Level I and II lymph nodes involved |

CS Staging Schemas

| Code | Description |
|------|---|
| 101 | Level I and III lymph nodes involved |
| 011 | Level II and III lymph nodes involved |
| 111 | Level I, II and III lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Anterior 2/3 of Tongue, Tip, Border, and Tongue, NOS CS Site-Specific Factor 4 Levels IV-V and Retropharyngeal Lymph Nodes for Head and

Neck (Revised: 08/21/2006)

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels IV or V or retropharyngeal |
| 100 | Level IV lymph node(s) involved |
| 010 | Level V lymph node(s) involved |
| 001 | Retropharyngeal nodes involved |
| 110 | Level IV and V lymph nodes involved |
| 101 | Level IV and retropharyngeal nodes involved |
| 011 | Level V and retropharyngeal nodes involved |
| 111 | Level IV and V and retropharyngeal lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Anterior 2/3 of Tongue, Tip, Border, and Tongue, NOS CS Site-Specific Factor 5 Levels VI-VII and Facial Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels VI or VII or facial nodes |
| 100 | Level VI lymph node(s) involved |
| 010 | Level VII lymph node(s) involved |
| 001 | Facial (buccinator, nasolabial) lymph node(s) involved |
| 110 | Level VI and VII lymph nodes involved |
| 101 | Level VI and facial (buccinator, nasolabial) nodes involved |
| 011 | Level VII and facial (buccinator, nasolabial) nodes involved |
| 111 | Level VI and VII and facial (buccinator, nasolabial) lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Anterior 2/3 of Tongue, Tip, Border, and Tongue, NOS CS Site-Specific Factor 6 Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|--|
| 000 | No parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), or sub-occipital lymph node involvement |
| 100 | Parapharyngeal lymph node(s) involved |
| 010 | Parotid (preauricular, periparotid, and/or intraparotid) lymph node(s) involved |
| 001 | Sub-occipital lymph node(s) involved |
| 110 | Parapharyngeal and parotid (preauricular, periparotid, and/or intraparotid) lymph nodes involved |
| 101 | Parapharyngeal and sub-occipital lymph nodes involved |

CS Staging Schemas

| Code | Description |
|------|---|
| 011 | Parotid (preauricular, periparotid, and/or intraparotid) and sub-occipital lymph nodes involved |
| 111 | Parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), and sub-occipital lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Gum, Upper C03.0

C03.0 Upper gum

| CS Tumor Size CS Extension CS TS/Ext-Eval CS Lymph Nodes CS Reg Nodes Eval Reg LN Pos Reg LN Exam CS Mets at DX CS Mets Eval | CS Site-Specific Factor 1 - Size of Lymph Nodes CS Site-Specific Factor 2 - Extracapsular Extension, Lymph Nodes for Head and Neck CS Site-Specific Factor 3 - Levels I-III, Lymph Nodes for Head and Neck CS Site-Specific Factor 4 - Levels IV-V and Retropharyngeal Lymph Nodes for Head and Neck CS Site-Specific Factor 5 - Levels VI-VII and Facial Lymph Nodes for Head and Neck CS Site-Specific Factor 6 - Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck | The following tables are available at the collaborative staging website: Histology Exclusion Table AJCC Stage Extension Size Table Lymph Nodes Size Table |
|--|---|---|
|--|---|---|

Gum, Upper CS Tumor Size SEE STANDARD TABLE

Gum, Upper

CS Extension (Revised: 08/22/2006)

Note: Superficial erosion alone of bone/tooth socket by gingival primary is not sufficient to code as bone involvement (code 70).

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | In situ; noninvasive; intraepithelial | Tis | IS | IS |
| 10 | Invasive tumor confined to lamina propria (mucoperiosteum) (stroma) | * | L | L |
| 30 | Localized, NOS | * | L | L |
| 50 | Buccal mucosa (inner cheek) Floor of mouth Labial mucosa (inner lip), lip Tongue | * | RE | RE |
| 55 | Facial muscle, NOS Subcutaneous soft tissue of face | * | RE | RE |
| 60 | Lateral pharyngeal wall (tonsillar pillars and fossae, tonsils) | * | RE | RE |
| 70 | Maxilla | T4a | RE | RE |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 72 | Deep muscle of tongue: Genioglossus Hyoglossus Palatoglossus Styloglossus | T4a | RE | RE |
| 74 | Maxillary antrum (sinus) Nasal cavity | T4a | D | D |
| 76 | Skin | T4a | D | D |
| 79 | Skull | T4b | D | D |
| 80 | Further contiguous extension, including: Masticator space Pterygoid plates Skull base Encases internal carotid artery | T4b | D | D |
| 95 | No evidence of primary tumor | Т0 | U | U |
| 99 | Unknown extension Primary tumor cannot be assessed Not documented in patient record | TX | U | U |

^{*} For codes 10, 30, 50, 55, 60, and 65 ONLY, the T category is assigned based on the value of CS Tumor Size, as shown in the Extension Size Table for this site.

Gum, Upper CS TS/Ext-Eval SEE STANDARD TABLE

Gum, Upper

CS Lymph Nodes (Revised: 08/22/2006)

Note 1: For head and neck schemas, this field includes all lymph nodes defined as Levels I-VII and Other by AJCC. The complete definitions are provided in the General Instructions.

Note 2: For head and neck schemas, additional information about lymph nodes (size of involved nodes, extracapsular extension, and levels involved) is coded in Site-Specific Factors 1-6.

Note 3: If laterality of lymph nodes is not specified, assume nodes are ipsilateral. Midline nodes are considered ipsilateral.

Note 4: For head and neck cancers, if lymph nodes are described only as "supraclavicular", try to determine if they are in Level IV (deep to the sternocleidomastoid muscle, in the lower jugular chain) or Level V (in the posterior triangle, inferior to the transverse cervical artery) and code appropriately. If the specific level cannot be determined, consider them as Level V nodes.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | None; no regional lymph node involvement | N0 | NONE | NONE |
| 10 | Single positive ipsilateral regional node: Retropharyngeal, NOS Regional lymph node, NOS | * | RN | RN |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 12 | Single positive ipsilateral regional node: Level V node Posterior cervical Posterior triangle (spinal accessory and transverse cervical) (upper, middle, and lower corresponding to the levels that define upper, middle, and lower jugular nodes) Level VI node Anterior deep cervical Laterotracheal Paralaryngeal Paratracheal Prelaryngeal Pretracheal Recurrent laryngeal Level VII node Upper mediastinum (for other mediastinal nodes see CS Mets at DX) Other groups Intraparotid Parapharyngeal Periparotid Retropharyngeal Sub-occipital Supraclavicular, NOS (See Note 4) | * | D | D |
| 18 | Stated as N1, no other information | N1 | RN | RN |
| 19 | Stated as N2a, no other information | N2a | RN | RN |
| 20 | Multiple positive ipsilateral nodes listed in code 10 | * | RN | RN |
| 22 | Multiple positive ipsilateral nodes listed in code 12 | * | D | D |
| 29 | Stated as N2b, no other information | N2b | RN | RN |
| 30 | Regional lymph nodes as listed in code 10: Positive ipsilateral node(s), not stated if single or multiple | * | RN | RN |
| 32 | Regional lymph nodes as listed in code 12: Positive ipsilateral node(s), not stated if single or multiple | * | D | D |
| 40 | Regional lymph nodes as listed in code 10: Positive bilateral or contralateral nodes | * | RN | RN |
| 42 | Regional lymph nodes as listed in code 12: Positive bilateral or contralateral nodes | * | D | D |
| 49 | Stated as N2c, no other information | N2c | RN | RN |
| 50 | Regional lymph nodes as listed in code 10: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | RN | RN |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-------|------|--------|
| 52 | Regional lymph nodes as listed in code 12: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | D |
| 60 | Stated as N2, NOS | N2NOS | RN | RN |
| 70 | Stated as N3, no other information | N3 | RN | RN |
| 80 | Lymph nodes, NOS | * | RN | RN |
| 99 | Unknown; not stated Regional lymph nodes cannot be assessed Not documented in patient record | NX | U | U |

^{*} For codes 10, 12, 20, 22, 30, 32, 40, 42, 49, 50, 52 and 80 ONLY, the N category is assigned based on the value of Site-Specific Factor 1, Size of Lymph Nodes, using the extra table, Lymph Nodes Size Table for this site.

Gum, Upper CS Reg Nodes Eval SEE STANDARD TABLE

Gum, Upper Reg LN Pos SEE STANDARD TABLE

Gum, Upper Reg LN Exam SEE STANDARD TABLE

Gum, Upper

CS Mets at DX (Revised: 08/14/2006)

Note: Supraclavicular and transverse cervical lymph nodes are now coded in CS Lymph Nodes because they are categorized as N rather than M in AJCC TNM. Any cases coded to 10 or 50 can be reviewed and recoded. The volume of cases affected should be small.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | No; none | M0 | NONE | NONE |
| 10 | Distant lymph node(s) Mediastinal Distant lymph node(s), NOS | M1 | D | D |
| 40 | Distant metastases except distant lymph node(s) (code 10) Distant metastasis, NOS Carcinomatosis | M1 | D | D |
| 50 | (10) + (40) Distant lymph node(s) plus other distant metastases | M1 | D | D |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 99 | Unknown if distant metastasis Distant metastasis cannot be assessed Not documented in patient record | MX | U | U |

Gum, Upper CS Mets Eval SEE STANDARD TABLE

Gum, Upper

CS Site-Specific Factor 1 Size of Lymph Nodes (Revised: 08/18/2006)

Note: Code the largest diameter, whether measured clinically or pathologically, of any involved regional lymph

node(s). Do not code the size of any nodes coded in CS Mets at DX.

| Code | Description |
|---------|--|
| 000 | No involved regional nodes |
| 001-988 | 001-988 millimeters (code exact size in millimeters) |
| 989 | 989 millimeters or larger |
| 990 | Microscopic focus or foci only, no size of focus given |
| 991 | Described as "less than 1cm" |
| 992 | Described as "less than 2cm" or "greater than 1cm" or "between 1cm and 2cm" |
| 993 | Described as "less than 3cm" or "greater than 2cm" or "between 2cm and 3cm" |
| 994 | Described as "less than 4cm" or "greater than 3cm" or "between 3cm and 4cm" |
| 995 | Described as "less than 5cm" or "greater than 4cm" or "between 4cm and 5cm" |
| 996 | Described as "less than 6cm" or "greater than 5cm" or "between 5cm and 6cm" |
| 997 | Described as "more than 6cm" |
| 999 | Regional lymph node(s) involved, size not stated Unknown if regional lymph node(s) involved Not documented in patient record |

CS Staging Schemas

Gum, Upper

CS Site-Specific Factor 2 Extracapsular Extension, Lymph Nodes for Head and Neck (Revised:

Note 1: Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. **Note 1:** Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. Do not code extracapsular extension in any nodes coded in CS Mets at DX in this field.

Note 2: A statement of the presence or absence of extracapsular extension in a pathology report takes priority over clinical assessment. However, if the pathology report contains no statement about extracapsular extension, either positive or negative, the clinical assessment should be coded. If nodes are involved but there is neither a clinical assessment of extranodal extension nor a statement about it in the pathology report, use code 999.

Note 3: According to AJCC (page 24), "Imaging studies showing amorphous spiculated margins of involved nodes or involvement of internodal fat resulting in loss of normal oval-to-round nodal shape strongly suggest extracapsular (extranodal) tumor spread; however, pathologic examination is necessary for documentation of the extent of such disease."

| Code | Description |
|------|---|
| 000 | No extracapsular extension |
| 001 | Extracapsular extension clinically, not assessed pathologically Nodes described as "fixed", not assessed pathologically |
| 005 | Extracapsular extension present pathologically |
| 888 | Not applicable; no lymph node involvement |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Gum, Upper

CS Site-Specific Factor 3 Levels I-III, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels I, II, or III |
| 100 | Level I lymph node(s) involved |
| 010 | Level II lymph node(s) involved |
| 001 | Level III lymph node(s) involved |
| 110 | Level I and II lymph nodes involved |
| 101 | Level I and III lymph nodes involved |
| 011 | Level II and III lymph nodes involved |
| 111 | Level I, II and III lymph nodes involved |

CS Staging Schemas

| Code | Description |
|------|---|
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Gum, Upper

CS Site-Specific Factor 4 Levels IV-V and Retropharyngeal Lymph Nodes for Head and

Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels IV or V or retropharyngeal |
| 100 | Level IV lymph node(s) involved |
| 010 | Level V lymph node(s) involved |
| 001 | Retropharyngeal nodes involved |
| 110 | Level IV and V lymph nodes involved |
| 101 | Level IV and retropharyngeal nodes involved |
| 011 | Level V and retropharyngeal nodes involved |
| 111 | Level IV and V and retropharyngeal lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Gum, Upper

CS Site-Specific Factor 5 Levels VI-VII and Facial Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels VI or VII or facial nodes |
| 100 | Level VI lymph node(s) involved |
| 010 | Level VII lymph node(s) involved |

CS Staging Schemas

| Code | Description | |
|------|---|--|
| 001 | Facial (buccinator, nasolabial) lymph node(s) involved | |
| 110 | Level VI and VII lymph nodes involved | |
| 101 | Level VI and facial (buccinator, nasolabial) nodes involved | |
| 011 | Level VII and facial (buccinator, nasolabial) nodes involved | |
| 111 | Level VI and VII and facial (buccinator, nasolabial) lymph nodes involved | |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record | |

Gum, Upper

CS Site-Specific Factor 6 Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description | | |
|------|---|--|--|
| 000 | No parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), or sub-occipital lymph node involvement | | |
| 100 | Parapharyngeal lymph node(s) involved | | |
| 010 | Parotid (preauricular, periparotid, and/or intraparotid) lymph node(s) involved | | |
| 001 | Sub-occipital lymph node(s) involved | | |
| 110 | Parapharyngeal and parotid (preauricular, periparotid, and/or intraparotid) lymph nodes involved | | |
| 101 | Parapharyngeal and sub-occipital lymph nodes involved | | |
| 011 | Parotid (preauricular, periparotid, and/or intraparotid) and sub-occipital lymph nodes involved | | |
| 111 | Parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), and sub-occipital lymph nodes involved | | |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record | | |

CS Staging Schemas

Gum, Lower and Retromolar Area Retromolar gingiva (trigone) C03.1, C06.2

C03.1 Lower gum

C06.2 Retromolar area

| CS Tumor Size CS Extension CS TS/Ext-Eval CS Lymph Nodes CS Reg Nodes Eval Reg LN Pos Reg LN Exam CS Mets at DX CS Mets Eval | CS Site-Specific Factor 1 - Size of Lymph Nodes CS Site-Specific Factor 2 - Extracapsular Extension, Lymph Nodes for Head and Neck CS Site-Specific Factor 3 - Levels I-III, Lymph Nodes for Head and Neck CS Site-Specific Factor 4 - Levels IV-V and Retropharyngeal Lymph Nodes for Head and Neck CS Site-Specific Factor 5 - Levels VI-VII and Facial Lymph Nodes for Head and Neck CS Site-Specific Factor 6 - Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck | The following tables are available at the collaborative staging website: Histology Exclusion Table AJCC Stage Extension Size Table Lymph Nodes Size Table |
|--|---|---|
|--|---|---|

Gum, Lower and Retromolar Area CS Tumor Size SEE STANDARD TABLE

Gum, Lower and Retromolar Area

CS Extension (Revised: 08/22/2006)

Note: Superficial erosion alone of bone/tooth socket by gingival primary is not sufficient to code as bone

involvement (code 70)

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | In situ; noninvasive; intraepithelial | Tis | IS | IS |
| 10 | Invasive tumor confined to lamina propria (mucoperiosteum) (stroma) | * | L | L |
| 30 | Localized, NOS | * | L | L |
| 50 | Buccal mucosa (inner cheek) Floor of mouth Labial mucosa (inner lip), lip Tongue | * | RE | RE |
| 55 | Facial muscle, NOS Subcutaneous soft tissue of face | * | RE | RE |
| 60 | Lateral pharyngeal wall (tonsillar pillars and fossae, tonsils) | * | RE | RE |
| 65 | Soft palate including uvula | * | RE | RE |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 70 | Mandible | T4a | RE | RE |
| 72 | Deep muscle of tongue: Genioglossus Hyoglossus Palatoglossus Styloglossus | T4a | RE | RE |
| 76 | Skin | T4a | D | D |
| 79 | Skull | T4b | D | D |
| 80 | Further contiguous extension, including: Masticator space Pterygoid plates Skull base Encases internal carotid artery | T4b | D | D |
| 95 | No evidence of primary tumor | ТО | U | U |
| 99 | Unknown extension Primary tumor cannot be assessed Not documented in patient record | TX | U | U |

^{*} For codes 10, 30, 50, 55, 60, and 65 ONLY, the T category is assigned based on the value of CS Tumor Size, as shown in the Extension Size Table for this site.

Gum, Lower and Retromolar Area CS TS/Ext-Eval SEE STANDARD TABLE

Gum, Lower and Retromolar Area

CS Lymph Nodes (Revised: 08/22/2006)

Note 1: For head and neck schemas, this field includes all lymph nodes defined as Levels I-VII and Other by AJCC. The complete definitions are provided in the General Instructions.

Note 2: For head and neck schemas, additional information about lymph nodes (size of involved nodes, extracapsular extension, and levels involved) is coded in Site-Specific Factors 1-6.

Note 3: If laterality of lymph nodes is not specified, assume nodes are ipsilateral. Midline nodes are considered ipsilateral.

Note 4: For head and neck cancers, if lymph nodes are described only as "supraclavicular", try to determine if they are in Level IV (deep to the sternocleidomastoid muscle, in the lower jugular chain) or Level V (in the posterior triangle, inferior to the transverse cervical artery) and code appropriately. If the specific level cannot be determined, consider them as Level V nodes.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | None; no regional lymph node involvement | N0 | NONE | NONE |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 10 | Single positive ipsilateral regional node: Level I node Submandibular (submaxillary) Submental Level II node Jugulodigastric (subdigastric) Upper deep cervical Upper jugular Level III node Middle deep cervical Mid jugular Level IV node Jugulo-omohyoid (supraomohyoid) Lower deep cervical Lower jugular Other groups Facial: Buccinator (buccal) Nasolabial Cervical, NOS Deep cervical, NOS Internal jugular, NOS Mandibular, NOS Regional lymph node, NOS | * | RN | RN |
| 12 | Single positive ipsilateral regional node: Level V node Posterior cervical Posterior triangle (spinal accessory and transverse cervical) (upper, middle, and lower corresponding to the levels that define upper, middle, and lower jugular nodes) Level VI node Anterior deep cervical Laterotracheal Paralaryngeal Paratracheal Prelaryngeal Pretracheal Recurrent laryngeal Level VII node Upper mediastinum (for other mediastinal nodes see CS Mets at DX) Other groups Intraparotid Parapharyngeal Periparotid Retropharyngeal Sub-occipital Supraclavicular, NOS (See Note 4) | * | D | D |
| 18 | Stated as N1, no other information | N1 | RN | RN |
| 19 | Stated as N2a, no other information | N2a | RN | RN |
| 20 | Multiple positive ipsilateral nodes listed in code 10 | * | RN | RN |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-------|------|--------|
| 22 | Multiple positive ipsilateral nodes listed in code 12 | * | D | D |
| 29 | Stated as N2b, no other information | N2b | RN | RN |
| 30 | Regional lymph nodes as listed in code 10: Positive ipsilateral node(s), not stated if single or multiple | * | RN | RN |
| 32 | Regional lymph nodes as listed in code 12: Positive ipsilateral node(s), not stated if single or multiple | * | D | D |
| 40 | Regional lymph nodes as listed in code 10: Positive bilateral or contralateral nodes | * | RN | RN |
| 42 | Regional lymph nodes as listed in code 12: Positive bilateral or contralateral nodes | * | D | D |
| 49 | Stated as N2c, no other information | N2c | RN | RN |
| 50 | Regional lymph nodes as listed in code 10: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | RN | RN |
| 52 | Regional lymph nodes as listed in code 12: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | D |
| 60 | Stated as N2, NOS | N2NOS | RN | RN |
| 70 | Stated as N3, no other information | N3 | RN | RN |
| 80 | Lymph nodes, NOS | * | RN | RN |
| 99 | Unknown; not stated Regional lymph nodes cannot be assessed Not documented in patient record | NX | U | U |

^{*} For codes 10, 12, 20, 22, 30, 32, 40, 42, 49, 50, 52 and 80 ONLY, the N category is assigned based on the value of Site-Specific Factor 1, Size of Lymph Nodes, using the extra table, Lymph Nodes Size Table for this site.

Gum, Lower and Retromolar Area CS Reg Nodes Eval SEE STANDARD TABLE

Gum, Lower and Retromolar Area Reg LN Pos SEE STANDARD TABLE

Gum, Lower and Retromolar Area Reg LN Exam SEE STANDARD TABLE

CS Staging Schemas

Gum, Lower and Retromolar Area

CS Mets at DX (Revised: 08/14/2006)

Note: Supraclavicular and transverse cervical lymph nodes are now coded in CS Lymph Nodes because they are categorized as N rather than M in AJCC TNM. Any cases coded to 10 or 50 can be reviewed and recoded. The volume of cases affected should be small.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | No; none | M0 | NONE | NONE |
| 10 | Distant lymph node(s) Mediastinal Distant lymph node(s), NOS | M1 | D | D |
| 40 | Distant metastases except distant lymph node(s) (code 10) Distant metastasis, NOS Carcinomatosis | M1 | D | D |
| 50 | (10) + (40) Distant lymph node(s) plus other distant metastases | M1 | D | D |
| 99 | Unknown if distant metastasis Distant metastasis cannot be assessed Not documented in patient record | MX | U | U |

Gum, Lower and Retromolar Area CS Mets Eval SEE STANDARD TABLE

Gum, Lower and Retromolar Area

CS Site-Specific Factor 1 Size of Lymph Nodes (Revised: 08/18/2006)

Note: Code the largest diameter, whether measured clinically or pathologically, of any involved regional lymph node(s). Do not code the size of any nodes coded in CS Mets at DX.

| Code | Description |
|---------|---|
| 000 | No involved regional nodes |
| 001-988 | 001-988 millimeters (code exact size in millimeters) |
| 989 | 989 millimeters or larger |
| 990 | Microscopic focus or foci only, no size of focus given |
| 991 | Described as "less than 1cm" |
| 992 | Described as "less than 2cm" or "greater than 1cm" or "between 1cm and 2cm" |
| 993 | Described as "less than 3cm" or "greater than 2cm" or "between 2cm and 3cm" |
| 994 | Described as "less than 4cm" or "greater than 3cm" or "between 3cm and 4cm" |
| 995 | Described as "less than 5cm" or "greater than 4cm" or "between 4cm and 5cm" |
| 996 | Described as "less than 6cm" or "greater than 5cm" or "between 5cm and 6cm" |
| 997 | Described as "more than 6cm" |

CS Staging Schemas

| Code | Description |
|------|--|
| 999 | Regional lymph node(s) involved, size not stated Unknown if regional lymph node(s) involved Not documented in patient record |

Gum, Lower and Retromolar Area

CS Site-Specific Factor 2 Extracapsular Extension, Lymph Nodes for Head and Neck (Revised: 08/17/2007)

Note 1: Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. **Note 1:** Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. Do not code extracapsular extension in any nodes coded in CS Mets at DX in this field.

Note 2: A statement of the presence or absence of extracapsular extension in a pathology report takes priority over clinical assessment. However, if the pathology report contains no statement about extracapsular extension, either positive or negative, the clinical assessment should be coded. If nodes are involved but there is neither a clinical assessment of extranodal extension nor a statement about it in the pathology report, use code 999.

Note 3: According to AJCC (page 24), "Imaging studies showing amorphous spiculated margins of involved nodes or involvement of internodal fat resulting in loss of normal oval-to-round nodal shape strongly suggest extracapsular (extranodal) tumor spread; however, pathologic examination is necessary for documentation of the extent of such disease."

| Code | Description |
|------|---|
| 000 | No extracapsular extension |
| 001 | Extracapsular extension clinically, not assessed pathologically Nodes described as "fixed", not assessed pathologically |
| 005 | Extracapsular extension present pathologically |
| 888 | Not applicable; no lymph node involvement |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Gum, Lower and Retromolar Area

CS Site-Specific Factor 3 Levels I-III, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels I, II, or III |
| 100 | Level I lymph node(s) involved |
| 010 | Level II lymph node(s) involved |
| 001 | Level III lymph node(s) involved |

CS Staging Schemas

| Code | Description |
|------|---|
| 110 | Level I and II lymph nodes involved |
| 101 | Level I and III lymph nodes involved |
| 011 | Level II and III lymph nodes involved |
| 111 | Level I, II and III lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Gum, Lower and Retromolar Area CS Site-Specific Factor 4 Levels IV-V and Retropharyngeal Lymph Nodes for Head and

Neck (Revised: 08/21/2006)

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels IV or V or retropharyngeal |
| 100 | Level IV lymph node(s) involved |
| 010 | Level V lymph node(s) involved |
| 001 | Retropharyngeal nodes involved |
| 110 | Level IV and V lymph nodes involved |
| 101 | Level IV and retropharyngeal nodes involved |
| 011 | Level V and retropharyngeal nodes involved |
| 111 | Level IV and V and retropharyngeal lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Gum, Lower and Retromolar Area

CS Site-Specific Factor 5 Levels VI-VII and Facial Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels VI or VII or facial nodes |
| 100 | Level VI lymph node(s) involved |
| 010 | Level VII lymph node(s) involved |
| 001 | Facial (buccinator, nasolabial) lymph node(s) involved |
| 110 | Level VI and VII lymph nodes involved |
| 101 | Level VI and facial (buccinator, nasolabial) nodes involved |
| 011 | Level VII and facial (buccinator, nasolabial) nodes involved |
| 111 | Level VI and VII and facial (buccinator, nasolabial) lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Gum, Lower and Retromolar Area

CS Site-Specific Factor 6 Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|--|
| 000 | No parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), or sub-occipital lymph node involvement |
| 100 | Parapharyngeal lymph node(s) involved |
| 010 | Parotid (preauricular, periparotid, and/or intraparotid) lymph node(s) involved |
| 001 | Sub-occipital lymph node(s) involved |
| 110 | Parapharyngeal and parotid (preauricular, periparotid, and/or intraparotid) lymph nodes involved |
| 101 | Parapharyngeal and sub-occipital lymph nodes involved |

| Code | Description |
|------|---|
| 011 | Parotid (preauricular, periparotid, and/or intraparotid) and sub-occipital lymph nodes involved |
| 111 | Parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), and sub-occipital lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Gum, NOS C03.9

C03.9 Gum, NOS

| CS Tumor Size CS Extension CS TS/Ext-Eval CS Lymph Nodes CS Reg Nodes Eval Reg LN Pos Reg LN Exam CS Mets at DX CS Mets Eval | CS Site-Specific Factor 1 - Size of Lymph Nodes CS Site-Specific Factor 2 - Extracapsular Extension, Lymph Nodes for Head and Neck CS Site-Specific Factor 3 - Levels I-III, Lymph Nodes for Head and Neck CS Site-Specific Factor 4 - Levels IV-V and Retropharyngeal Lymph Nodes for Head and Neck CS Site-Specific Factor 5 - Levels VI-VII and Facial Lymph Nodes for Head and Neck CS Site-Specific Factor 6 - Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck | The following tables are available at the collaborative staging website: Histology Exclusion Table AJCC Stage Extension Size Table Lymph Nodes Size Table |
|--|---|---|
|--|---|---|

Gum, NOS CS Tumor Size SEE STANDARD TABLE

Gum, NOS

CS Extension (Revised: 08/22/2006)

Note: Superficial erosion alone of bone/tooth socket by gingival primary is not sufficient to code as bone involvement (code 70).

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 00 | In situ; noninvasive; intraepithelial | Tis | IS | IS |
| 10 | Invasive tumor confined to lamina propria (mucoperiosteum) (stroma) | * | L | L |
| 30 | Localized, NOS | * | L | L |
| 50 | Buccal mucosa (inner cheek) Labial mucosa (inner lip), lip | * | RE | RE |
| 55 | Facial muscle, NOS Subcutaneous soft tissue of face | * | RE | RE |
| 60 | Lateral pharyngeal wall (tonsillar pillars and fossae, tonsils) | * | RE | RE |
| 72 | Deep muscle of tongue: Genioglossus Hyoglossus Palatoglossus Styloglossus | T4a | RE | RE |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 76 | Skin | T4a | D | D |
| 79 | Skull | T4b | D | D |
| 80 | Further contiguous extension, including: Masticator space Pterygoid plates Skull base Encases internal carotid artery | T4b | D | D |
| 95 | No evidence of primary tumor | T0 | U | U |
| 99 | Unknown extension Primary tumor cannot be assessed Not documented in patient record | TX | U | U |

^{*} For codes 10, 30, 50, 55, 60, and 65 ONLY, the T category is assigned based on the value of CS Tumor Size, as shown in the Extension Size Table for this site.

Gum, NOS CS TS/Ext-Eval SEE STANDARD TABLE

Gum, NOS

CS Lymph Nodes (Revised: 09/17/2007)

Note 1: For head and neck schemas, this field includes all lymph nodes defined as Levels I-VII and Other by AJCC. The complete definitions are provided in the General Instructions.

Note 2: For head and neck schemas, additional information about lymph nodes (size of involved nodes, extracapsular extension, and levels involved) is coded in Site-Specific Factors 1-6.

Note 3: If laterality of lymph nodes is not specified, assume nodes are ipsilateral. Midline nodes are considered ipsilateral.

Note 4: For head and neck cancer, if lymph nodes are described only as "supraclavicular", try to determine if they are in Level IV (deep to the sternocleidomastoid muscle, in the lower jugular chain) or Level V (in the posterior triangle, inferior to the transverse cervical artery) and code appropriately. If the specific level cannot be determined, consider them as Level V nodes.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | None; no regional lymph node involvement | N0 | NONE | NONE |

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 10 | Single positive ipsilateral regional node: Level I node Submandibular (submaxillary) Submental Level II node Jugulodigastric (subdigastric) Upper deep cervical Upper jugular Level III node Middle deep cervical Mid jugular Level IV node Jugulo-omohyoid (supraomohyoid) Lower deep cervical Lower jugular Other groups Facial: Buccinator (buccal) Nasolabial Cervical, NOS Deep cervical, NOS Internal jugular, NOS Mandibular, NOS Regional lymph node, NOS | * | RN | RN |
| 12 | Single positive ipsilateral regional node: Level V node Posterior cervical Posterior triangle (spinal accessory and transverse cervical) (upper, middle, and lower corresponding to the levels that define upper, middle, and lower jugular nodes) Level VI node Anterior deep cervical Laterotracheal Paralaryngeal Paratracheal Prelaryngeal Pretracheal Recurrent laryngeal Level VII node Upper mediastinum (for other mediastinal nodes see CS Mets at DX) Other groups Intraparotid Parapharyngeal Periparotid Retropharyngeal Sub-occipital Supraclavicular, NOS (See Note 4) | * | D | D |
| 18 | Stated as N1, no other information | N1 | RN | RN |
| 19 | Stated as N2a, no other information | N2a | RN | RN |
| | Multiple positive ipsilateral nodes listed in code 10 | * | RN | RN |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-------|------|--------|
| 22 | Multiple positive ipsilateral nodes listed in code 12 | * | D | D |
| 29 | Stated as N2b, no other information | N2b | RN | RN |
| 30 | Regional lymph nodes as listed in code 10: Positive ipsilateral node(s), not stated if single or multiple | * | RN | RN |
| 32 | Regional lymph nodes as listed in code 12: Positive ipsilateral node(s), not stated if single or multiple | * | D | D |
| 40 | Regional lymph nodes as listed in code 10: Positive bilateral or contralateral nodes | * | RN | RN |
| 42 | Regional lymph nodes as listed in code 12: Positive bilateral or contralateral nodes | * | D | D |
| 49 | Stated as N2c, no other information | N2c | RN | RN |
| 50 | Regional lymph nodes as listed in code 10: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | RN | RN |
| 52 | Regional lymph nodes as listed in code 12: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | D |
| 60 | Stated as N2, NOS | N2NOS | RN | RN |
| 70 | Stated as N3, no other information | N3 | RN | RN |
| 80 | Lymph nodes, NOS | * | RN | RN |
| 99 | Unknown; not stated Regional lymph nodes cannot be assessed Not documented in patient record | NX | U | U |

^{*} For codes 10, 20, 30, 40, 49, 50 and 80 ONLY, the N category is assigned based on the value of Site-Specific Factor 1, Size of Lymph Nodes, using the extra table, Lymph Nodes Size Table for this site.

Gum, NOS CS Reg Nodes Eval SEE STANDARD TABLE

Gum, NOS Reg LN Pos SEE STANDARD TABLE

Gum, NOS Reg LN Exam SEE STANDARD TABLE

CS Staging Schemas

Gum, NOS

CS Mets at DX (Revised: 08/14/2006)

Note: Supraclavicular and transverse cervical lymph nodes are now coded in CS Lymph Nodes because they are categorized as N rather than M in AJCC TNM. Any cases coded to 10 or 50 can be reviewed and recoded. The volume of cases affected should be small.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | No; none | M0 | NONE | NONE |
| 10 | Distant lymph node(s) Mediastinal Distant lymph node(s), NOS | M1 | D | D |
| 40 | Distant metastases except distant lymph node(s) (code 10) Distant metastasis, NOS Carcinomatosis | M1 | D | D |
| 50 | (10) + (40) Distant lymph node(s) plus other distant metastases | M1 | D | D |
| 99 | Unknown if distant metastasis Distant metastasis cannot be assessed Not documented in patient record | MX | U | U |

Gum, NOS CS Mets Eval SEE STANDARD TABLE

Gum, NOS

CS Site-Specific Factor 1 Size of Lymph Nodes (Revised: 08/18/2006)

Note: Code the largest diameter, whether measured clinically or pathologically, of any involved regional lymph node(s). Do not code the size of any nodes coded in CS Mets at DX.

| Code | Description | |
|---------|---|--|
| 000 | No involved regional nodes | |
| 001-988 | 001-988 millimeters (code exact size in millimeters) | |
| 989 | 989 millimeters or larger | |
| 990 | Microscopic focus or foci only, no size of focus given | |
| 991 | Described as "less than 1cm" | |
| 992 | Described as "less than 2cm" or "greater than 1cm" or "between 1cm and 2cm" | |
| 993 | Described as "less than 3cm" or "greater than 2cm" or "between 2cm and 3cm" | |
| 994 | Described as "less than 4cm" or "greater than 3cm" or "between 3cm and 4cm" | |
| 995 | Described as "less than 5cm" or "greater than 4cm" or "between 4cm and 5cm" | |
| 996 | Described as "less than 6cm" or "greater than 5cm" or "between 5cm and 6cm" | |
| 997 | Described as "more than 6cm" | |

CS Staging Schemas

| Code | Description |
|------|--|
| 999 | Regional lymph node(s) involved, size not stated Unknown if regional lymph node(s) involved Not documented in patient record |

Gum, NOS

CS Site-Specific Factor 2 Extracapsular Extension, Lymph Nodes for Head and Neck (Revised: 08/17/2007)

Note 1: Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. **Note 1:** Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. Do not code extracapsular extension in any nodes coded in CS Mets at DX in this field.

Note 2: A statement of the presence or absence of extracapsular extension in a pathology report takes priority over clinical assessment. However, if the pathology report contains no statement about extracapsular extension, either positive or negative, the clinical assessment should be coded. If nodes are involved but there is neither a clinical assessment of extranodal extension nor a statement about it in the pathology report, use code 999.

Note 3: According to AJCC (page 24), "Imaging studies showing amorphous spiculated margins of involved nodes or involvement of internodal fat resulting in loss of normal oval-to-round nodal shape strongly suggest extracapsular (extranodal) tumor spread; however, pathologic examination is necessary for documentation of the extent of such disease."

| Code | Description |
|------|---|
| 000 | No extracapsular extension |
| 001 | Extracapsular extension clinically, not assessed pathologically Nodes described as "fixed", not assessed pathologically |
| 005 | Extracapsular extension present pathologically |
| 888 | Not applicable; no lymph node involvement |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Gum, NOS

CS Site-Specific Factor 3 Levels I-III, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels I, II, or III |
| 100 | Level I lymph node(s) involved |
| 010 | Level II lymph node(s) involved |
| 001 | Level III lymph node(s) involved |

CS Staging Schemas

| Code | Description |
|------|---|
| 110 | Level I and II lymph nodes involved |
| 101 | Level I and III lymph nodes involved |
| 011 | Level II and III lymph nodes involved |
| 111 | Level I, II and III lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Gum, NOS

CS Site-Specific Factor 4 Levels IV-V and Retropharyngeal Lymph Nodes for Head and

Neck (Revised: 08/21/2006)

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels IV or V or retropharyngeal |
| 100 | Level IV lymph node(s) involved |
| 010 | Level V lymph node(s) involved |
| 001 | Retropharyngeal nodes involved |
| 110 | Level IV and V lymph nodes involved |
| 101 | Level IV and retropharyngeal nodes involved |
| 011 | Level V and retropharyngeal nodes involved |
| 111 | Level IV and V and retropharyngeal lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Gum, NOS

CS Site-Specific Factor 5 Levels VI-VII and Facial Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels VI or VII or facial nodes |
| 100 | Level VI lymph node(s) involved |
| 010 | Level VII lymph node(s) involved |
| 001 | Facial (buccinator, nasolabial) lymph node(s) involved |
| 110 | Level VI and VII lymph nodes involved |
| 101 | Level VI and facial (buccinator, nasolabial) nodes involved |
| 011 | Level VII and facial (buccinator, nasolabial) nodes involved |
| 111 | Level VI and VII and facial (buccinator, nasolabial) lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Gum, NOS

CS Site-Specific Factor 6 Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|--|
| 000 | No parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), or sub-occipital lymph node involvement |
| 100 | Parapharyngeal lymph node(s) involved |
| 010 | Parotid (preauricular, periparotid, and/or intraparotid) lymph node(s) involved |
| 001 | Sub-occipital lymph node(s) involved |
| 110 | Parapharyngeal and parotid (preauricular, periparotid, and/or intraparotid) lymph nodes involved |
| 101 | Parapharyngeal and sub-occipital lymph nodes involved |

| Code | Description |
|------|---|
| 011 | Parotid (preauricular, periparotid, and/or intraparotid) and sub-occipital lymph nodes involved |
| 111 | Parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), and sub-occipital lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Floor of Mouth C04.0-C04.1, C04.8-C04.9

C04.0 Anterior floor of mouth

C04.1 Lateral floor of mouth

C04.8 Overlapping lesion of floor of mouth

C04.9 Floor of mouth, NOS

| CS Tumor Size CS Extension CS TS/Ext-Eval CS Lymph Nodes CS Reg Nodes Eval Reg LN Pos Reg LN Exam CS Mets at DX CS Mets Eval | CS Site-Specific Factor 1 - Size of Lymph Nodes CS Site-Specific Factor 2 - Extracapsular Extension, Lymph Nodes for Head and Neck CS Site-Specific Factor 3 - Levels I-III, Lymph Nodes for Head and Neck CS Site-Specific Factor 4 - Levels IV-V and Retropharyngeal Lymph Nodes for Head and Neck CS Site-Specific Factor 5 - Levels VI-VII and Facial Lymph Nodes for Head and Neck CS Site-Specific Factor 6 - Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck | The following tables are available at the collaborative staging website: Histology Exclusion Table AJCC Stage Extension Size Table Lymph Nodes Size Table |
|--|---|---|
|--|---|---|

Floor of Mouth CS Tumor Size SEE STANDARD TABLE

Floor of Mouth

CS Extension (Revised: 08/14/2006)

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | In situ; noninvasive; intraepithelial | Tis | IS | IS |
| 10 | Invasive tumor on one side confined to: Lamina propria Submucosa | * | L | L |
| 30 | Localized, NOS | * | L | L |
| 40 | Tumor crosses midline | * | L | L |
| 50 | Anterior 2/3 of tongue Base of tongue Gingiva (alveolar ridge), lower | * | RE | RE |
| 53 | Sublingual gland, including ducts Submandibular (submaxillary) glands, including ducts | * | RE | RE |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 60 | Epiglottis Glossoepiglottic fold Glossopharyngeal sulcus Lateral pharyngeal wall Pharyngeal (lingual) surface Pharyngoepiglottic fold Tonsillar pillars and fossae Tonsils Vallecula | * | RE | RE |
| 62 | Extension to deep extrinsic muscle of tongue: Genioglossus Geniohyoid Hyoglossus Mylohyoid Palatoglossus Styloglossus | T4a | L | L |
| 63 | (62) + any of (50, 53, or 60) | T4a | RE | RE |
| 64 | Subcutaneous soft tissue of chin/neck | T4a | RE | RE |
| 70 | Mandible | T4a | RE | RE |
| 76 | Skin of undersurface of chin/neck | T4a | RE | RE |
| 77 | Further contiguous extension: Maxillary sinus | T4a | D | D |
| 80 | Further contiguous extension: Base of skull Masticator space Pterygoid plates | T4b | D | D |
| 95 | No evidence of primary tumor | Т0 | U | U |
| 99 | Unknown extension Primary tumor cannot be assessed Not documented in patient record | TX | U | U |

^{*}Note: For Extension codes 10, 20, 30, 40, 50, 53, and 60 ONLY, the T category is assigned based on the value of CS Tumor Size, as shown in the Extension Size Table for this site.

Floor of Mouth CS TS/Ext-Eval SEE STANDARD TABLE

Floor of Mouth

CS Lymph Nodes (Revised: 08/22/2006)

Note 1: For head and neck schemas, this field includes all lymph nodes defined as Levels I-VII and Other by AJCC. The complete definitions are provided in the General Instructions.

Note 2: For head and neck schemes, additional information about lymph nodes (size of involved nodes, extracapsular extension, and levels involved) is coded in Site-Specific Factors 1-6.

Note 3: If laterality of lymph nodes is not specified, assume nodes are ipsilateral. Midline nodes are considered ipsilateral.

Note 4: For head and neck cancers, if lymph nodes are described only as "supraclavicular", try to determine if they are in Level IV (deep to the sternocleidomastoid muscle, in the lower jugular chain) or Level V (in the posterior triangle, inferior to the transverse cervical artery) and code appropriately. If the specific level cannot be determined, consider them as Level V nodes.

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 00 | None; no regional lymph node involvement | N0 | NONE | NONE |
| 10 | Single positive ipsilateral regional node: Level I node Submandibular (submaxillary) Submental Level II node Jugulodigastric (subdigastric) Upper deep cervical Upper jugular Level III node Middle deep cervical Mid jugular Level IV node Jugulo-omohyoid (supraomohyoid) Lower deep cervical Lower jugular Cervical, NOS Deep cervical, NOS Internal jugular, NOS Mandibular, NOS Sublingual Regional lymph node, NOS | * | RN | RN |
| 12 | Single positive ipsilateral regional node: Level V node Posterior cervical Posterior triangle (spinal accessory and transverse cervical) (upper, middle, and lower corresponding to the levels that define upper, middle, and lower jugular nodes) Level VI node Anterior deep cervical Laterotracheal Paralaryngeal Paratracheal Prelaryngeal Pretracheal Recurrent laryngeal Level VII node Upper mediastinum (for other mediastinal nodes see CS Mets at DX) Other groups Intraparotid Parapharyngeal Periparotid Retropharyngeal Sub-occipital Supraclavicular, NOS (See Note 4) | * | D | D |
| 18 | Stated as N1, no other information | N1 | RN | RN |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-------|------|--------|
| 19 | Stated as N2a, no other information | N2a | RN | RN |
| 20 | Multiple positive ipsilateral nodes listed in code 10 | * | RN | RN |
| 22 | Multiple positive ipsilateral nodes listed in code 12 | * | D | D |
| 29 | Stated as N2b, no other information | N2b | RN | RN |
| 30 | Regional lymph nodes as listed in code 10: Positive ipsilateral node(s), not stated if single or multiple | * | RN | RN |
| 32 | Regional lymph nodes as listed in code 12: Positive ipsilateral node(s), not stated if single or multiple | * | D | D |
| 40 | Regional lymph nodes as listed in code 10: Positive bilateral or contralateral nodes | * | RN | RN |
| 42 | Regional lymph nodes as listed in code 12: Positive bilateral or contralateral nodes | * | D | D |
| 49 | Stated as N2c, no other information | N2c | RN | RN |
| 50 | Regional lymph nodes as listed in code 10: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | RN | RN |
| 52 | Regional lymph nodes as listed in code 12: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | D |
| 60 | Stated as N2, NOS | N2NOS | RN | RN |
| 70 | Stated as N3, no other information | N3 | RN | RN |
| 80 | Lymph nodes, NOS | * | RN | RN |
| 99 | Unknown; not stated Regional lymph nodes cannot be assessed Not documented in patient record | NX | U | U |

^{*} For codes 10, 20, 30, 40, 49, 50 and 80 ONLY, the N category is assigned based on the value of Site-Specific Factor 1, Size of Lymph Nodes, using the extra table, Lymph Nodes Size Table for this site.

Floor of Mouth CS Reg Nodes Eval SEE STANDARD TABLE

Floor of Mouth Reg LN Pos SEE STANDARD TABLE

CS Staging Schemas

Floor of Mouth Reg LN Exam SEE STANDARD TABLE

Floor of Mouth

CS Mets at DX (Revised: 08/14/2006)

Note: Supraclavicular and transverse cervical lymph nodes are now coded in CS Lymph Nodes because they are categorized as N rather than M in AJCC TNM. Any cases coded to 10 or 50 can be reviewed and recoded. The volume of cases affected should be small.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | No; none | M0 | NONE | NONE |
| 10 | Distant lymph node(s) Mediastinal Distant lymph node(s), NOS | M1 | D | D |
| 40 | Distant metastases except distant lymph node(s) (code 10) Distant metastasis, NOS Carcinomatosis | M1 | D | D |
| 50 | (10) + (40) Distant lymph node(s) plus other distant metastases | M1 | D | D |
| 99 | Unknown if distant metastasis Distant metastasis cannot be assessed Not documented in patient record | MX | U | U |

Floor of Mouth CS Mets Eval SEE STANDARD TABLE

Floor of Mouth

CS Site-Specific Factor 1 Size of Lymph Nodes (Revised: 08/18/2006)

Note: Code the largest diameter, whether measured clinically or pathologically, of any involved regional lymph node(s). Do not code the size of any nodes coded in CS Mets at DX.

| Code | Description | |
|---------|---|--|
| 000 | No involved regional nodes | |
| 001-988 | 001-988 millimeters (code exact size in millimeters) | |
| 989 | 989 millimeters or larger | |
| 990 | Microscopic focus or foci only, no size of focus given | |
| 991 | Described as "less than 1cm" | |
| 992 | Described as "less than 2cm" or "greater than 1cm" or "between 1cm and 2cm" | |
| 993 | Described as "less than 3cm" or "greater than 2cm" or "between 2cm and 3cm" | |
| 994 | Described as "less than 4cm" or "greater than 3cm" or "between 3cm and 4cm" | |

CS Staging Schemas

| Code | Description |
|------|--|
| 995 | Described as "less than 5cm" or "greater than 4cm" or "between 4cm and 5cm" |
| 996 | Described as "less than 6cm" or "greater than 5cm" or "between 5cm and 6cm" |
| 997 | Described as "more than 6cm" |
| 999 | Regional lymph node(s) involved, size not stated Unknown if regional lymph node(s) involved Not documented in patient record |

Floor of Mouth

CS Site-Specific Factor 2 Extracapsular Extension, Lymph Nodes for Head and Neck (Revised: 08/17/2007)

Note 1: Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. Do not code extracapsular extension in any nodes coded in CS Mets at DX in this field.

Note 2: A statement of the presence or absence of extracapsular extension in a pathology report takes priority over clinical assessment. However, if the pathology report contains no statement about extracapsular extension, either positive or negative, the clinical assessment should be coded. If nodes are involved but there is neither a clinical assessment of extranodal extension nor a statement about it in the pathology report, use code 999.

Note 3: According to AJCC (page 24), "Imaging studies showing amorphous spiculated margins of involved nodes or involvement of internodal fat resulting in loss of normal oval-to-round nodal shape strongly suggest extracapsular (extranodal) tumor spread; however, pathologic examination is necessary for documentation of the extent of such disease."

| Code | Description |
|------|---|
| 000 | No extracapsular extension |
| 001 | Extracapsular extension clinically, not assessed pathologically Nodes described as "fixed", not assessed pathologically |
| 005 | Extracapsular extension present pathologically |
| 888 | Not applicable; no lymph node involvement |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Floor of Mouth

CS Site-Specific Factor 3 Levels I-III, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description | | |
|------|---|--|--|
| 000 | No lymph node involvement in Levels I, II, or III | | |
| 100 | Level I lymph node(s) involved | | |

CS Staging Schemas

| Code | Description | |
|------|---|--|
| 010 | Level II lymph node(s) involved | |
| 001 | Level III lymph node(s) involved | |
| 110 | Level I and II lymph nodes involved | |
| 101 | Level I and III lymph nodes involved | |
| 011 | Level II and III lymph nodes involved | |
| 111 | Level I, II and III lymph nodes involved | |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record | |

Floor of Mouth

CS Site-Specific Factor 4 Levels IV-V and Retropharyngeal Lymph Nodes for Head and

Neck (Revised: 08/21/2006)

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels IV or V or retropharyngeal |
| 100 | Level IV lymph node(s) involved |
| 010 | Level V lymph node(s) involved |
| 001 | Retropharyngeal nodes involved |
| 110 | Level IV and V lymph nodes involved |
| 101 | Level IV and retropharyngeal nodes involved |
| 011 | Level V and retropharyngeal nodes involved |
| 111 | Level IV and V and retropharyngeal lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Floor of Mouth

CS Site-Specific Factor 5 Levels VI-VII and Facial Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels VI or VII or facial nodes |
| 100 | Level VI lymph node(s) involved |
| 010 | Level VII lymph node(s) involved |
| 001 | Facial (buccinator, nasolabial) lymph node(s) involved |
| 110 | Level VI and VII lymph nodes involved |
| 101 | Level VI and facial (buccinator, nasolabial) nodes involved |
| 011 | Level VII and facial (buccinator, nasolabial) nodes involved |
| 111 | Level VI and VII and facial (buccinator, nasolabial) lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Floor of Mouth

CS Site-Specific Factor 6 Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|--|
| 000 | No parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), or sub-occipital lymph node involvement |
| 100 | Parapharyngeal lymph node(s) involved |
| 010 | Parotid (preauricular, periparotid, and/or intraparotid) lymph node(s) involved |
| 001 | Sub-occipital lymph node(s) involved |
| 110 | Parapharyngeal and parotid (preauricular, periparotid, and/or intraparotid) lymph nodes involved |
| 101 | Parapharyngeal and sub-occipital lymph nodes involved |

| Code | Description | | | |
|------|---|--|--|--|
| 011 | Parotid (preauricular, periparotid, and/or intraparotid) and sub-occipital lymph nodes involved | | | |
| 111 | Parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), and sub-occipital lymph nodes involved | | | |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record | | | |

CS Staging Schemas

Hard Palate C05.0

C05.0 Hard palate

| CS Tumor Size CS Extension CS TS/Ext-Eval CS Lymph Nodes CS Reg Nodes Eval Reg LN Pos Reg LN Exam CS Mets at DX CS Mets Eval | CS Site-Specific Factor 1 - Size of Lymph Nodes CS Site-Specific Factor 2 - Extracapsular Extension, Lymph Nodes for Head and Neck CS Site-Specific Factor 3 - Levels I-III, Lymph Nodes for Head and Neck CS Site-Specific Factor 4 - Levels IV-V and Retropharyngeal Lymph Nodes for Head and Neck CS Site-Specific Factor 5 - Levels VI-VII and Facial Lymph Nodes for Head and Neck CS Site-Specific Factor 6 - Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck | The following tables are available at the collaborative staging website: Histology Exclusion Table AJCC Stage Extension Size Table Lymph Nodes Size Table |
|--|---|---|
|--|---|---|

Hard Palate CS Tumor Size SEE STANDARD TABLE

Hard Palate

CS Extension (Revised: 08/22/2006)

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | In situ; noninvasive; intraepithelial | Tis | IS | IS |
| 10 | Invasive tumor on one side confined to mucoperiosteum (stroma) | * | L | L |
| 30 | Localized, NOS | * | L | L |
| 40 | Tumor crosses midline | * | L | L |
| 50 | Buccal mucosa (inner cheek) Gingiva, upper Glossopalatine arch Pharyngopalatine arch Soft palate Uvula | * | RE | RE |
| 70 | Maxillary bone Palatine bone | T4a | RE | RE |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 74 | Deep muscle of tongue Floor of nose Maxillary antrum (sinus) Nasal cavity Nasopharynx Skin of face Sphenoid bone | T4a | D | D |
| 76 | Pterygoid plate | T4b | D | D |
| 80 | Further contiguous extension | T4b | D | D |
| 95 | No evidence of primary tumor | ТО | U | U |
| 99 | Unknown extension Primary tumor cannot be assessed Not documented in patient record | TX | U | U |

^{*} For Extension codes 10, 30, 40, and 50 ONLY, the T category is assigned based on the value of CS Tumor Size, as shown in the Extension Size Table for this site.

Hard Palate CS TS/Ext-Eval SEE STANDARD TABLE

Hard Palate

CS Lymph Nodes (Revised: 08/21/2006)

Note 1: For head and neck schemas, this field includes all lymph nodes defined as Levels I-VII and Other by AJCC. The complete definitions are provided in the General Instructions.

Note 2: For head and neck schemas, additional information about lymph nodes (size of involved nodes, extracapsular extension, and levels involved) is coded in Site-Specific Factors 1-6.

Note 3: If laterality of lymph nodes is not specified, assume nodes are ipsilateral. Midline nodes are considered ipsilateral.

Note 4: For head and neck cancers, if lymph nodes are described only as "supraclavicular", try to determine if they are in Level IV (deep to the sternocleidomastoid muscle, in the lower jugular chain) or Level V (in the posterior triangle, inferior to the transverse cervical artery) and code appropriately. If the specific level cannot be determined, consider them as Level V nodes.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | None; no regional lymph node involvement | N0 | NONE | NONE |

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 10 | Single positive ipsilateral regional node: Level I node Submandibular (submaxillary) Submental Level II node Jugulodigastric (subdigastric) Upper deep cervical Upper jugular Level III node Middle deep cervical Mid jugular Level IV node Jugulo-omohyoid (supraomohyoid) Lower deep cervical Lower jugular Cervical, NOS Deep cervical, NOS Internal jugular, NOS Mandibular, NOS Retropharyngeal Regional lymph node, NOS | * | RN | RN |
| 11 | Single positive ipsilateral regional node: Level I node Submental | * | D | RN |
| 12 | Single positive ipsilateral regional node: Level V node Posterior cervical Posterior triangle (spinal accessory and transverse cervical) (upper, middle, and lower corresponding to the levels that define upper, middle, and lower jugular nodes) Level VI node Anterior deep cervical Laterotracheal Paralaryngeal Prelaryngeal Pretracheal Recurrent laryngeal Level VII node Upper mediastinum (for other mediastinal nodes see CS Mets at DX) Other groups Parapharyngeal Retropharyngeal Retropharyngeal Sub-occipital Supraclavicular, NOS (See Note 4) | * | D | D |
| 18 | Stated as N1, no other information | N1 | RN | RN |
| 19 | Stated as N2a, no other information | N2a | RN | RN |
| 20 | Multiple positive ipsilateral nodes listed in code 10 | * | RN | RN |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-------|------|--------|
| 21 | Multiple positive ipsilateral nodes listed in code 11 | * | D | RN |
| 22 | Multiple positive ipsilateral nodes listed in code 12 | * | D | D |
| 29 | Stated as N2b, no other information | N2b | RN | RN |
| 30 | Regional lymph nodes as listed in code 10: Positive ipsilateral node(s), not stated if single or multiple | * | RN | RN |
| 31 | Regional lymph nodes as listed in code 11: Positive ipsilateral node(s), not stated if single or multiple | * | D | RN |
| 32 | Regional lymph nodes as listed in code 12: Positive ipsilateral node(s), not stated if single or multiple | * | D | D |
| 40 | Regional lymph nodes as listed in code 10: Positive bilateral or contralateral nodes | * | RN | RN |
| 41 | Regional lymph nodes as listed in code 11: Positive bilateral or contralateral nodes | * | D | RN |
| 42 | Regional lymph nodes as listed in code 12: Positive bilateral or contralateral nodes | * | D | D |
| 49 | Stated as N2c, no other information | N2c | RN | RN |
| 50 | Regional lymph nodes as listed in code 10: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | RN | RN |
| 51 | Regional lymph nodes as listed in code 11: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | RN |
| 52 | Regional lymph nodes as listed in code 12: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | D |
| 60 | Stated as N2, NOS | N2NOS | RN | RN |
| 70 | Stated as N3, no other information | N3 | RN | RN |
| 80 | Lymph nodes, NOS, no other information | * | RN | RN |
| 99 | Unknown; not stated Regional lymph nodes cannot be assessed Not documented in patient record | NX | U | U |
| | | • | | • |

^{*} For codes 10-12, 20-22, 30-32, 40-42, 50-52, and 80 ONLY, the N category is assigned based on the value of Site-Specific Factor 1, Size of Lymph Nodes, using the extra table, Lymph Nodes Size Table for this site.

Hard Palate CS Reg Nodes Eval SEE STANDARD TABLE

CS Staging Schemas

Hard Palate Reg LN Pos SEE STANDARD TABLE

Hard Palate Reg LN Exam SEE STANDARD TABLE

Hard Palate

CS Mets at DX (Revised: 08/14/2006)

Note: Supraclavicular and transverse cervical lymph nodes are now coded in CS Lymph Nodes because they are categorized as N rather than M in AJCC TNM. Any cases coded to 10 or 50 can be reviewed and recoded. The volume of cases affected should be small.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | No; none | M0 | NONE | NONE |
| 10 | Distant lymph node(s) Mediastinal Distant lymph node(s), NOS | M1 | D | D |
| 40 | Distant metastases except distant lymph node(s) (code 10) Distant metastasis, NOS Carcinomatosis | M1 | D | D |
| 50 | (10) + (40) Distant lymph node(s) plus other distant metastases | M1 | D | D |
| 99 | Unknown if distant metastasis Distant metastasis cannot be assessed Not documented in patient record | MX | U | U |

Hard Palate CS Mets Eval SEE STANDARD TABLE

Hard Palate

CS Site-Specific Factor 1 Size of Lymph Nodes (Revised: 08/18/2006)

Note: Code the largest diameter, whether measured clinically or pathologically, of any involved regional lymph node(s). Do not code the size of any nodes coded in CS Mets at DX.

| Code | Description |
|---------|--|
| 000 | No involved regional nodes |
| 001-988 | 001-988 millimeters (code exact size in millimeters) |
| 989 | 989 millimeters or larger |
| 990 | Microscopic focus or foci only, no size of focus given |

CS Staging Schemas

| Code | Description |
|------|--|
| 991 | Described as "less than 1cm" |
| 992 | Described as "less than 2cm" or "greater than 1cm" or "between 1cm and 2cm" |
| 993 | Described as "less than 3cm" or "greater than 2cm" or "between 2cm and 3cm" |
| 994 | Described as "less than 4cm" or "greater than 3cm" or "between 3cm and 4cm" |
| 995 | Described as "less than 5cm" or "greater than 4cm" or "between 4cm and 5cm" |
| 996 | Described as "less than 6cm" or "greater than 5cm" or "between 5cm and 6cm" |
| 997 | Described as "more than 6cm" |
| 999 | Regional lymph node(s) involved, size not stated Unknown if regional lymph node(s) involved Not documented in patient record |

Hard Palate

CS Site-Specific Factor 2 Extracapsular Extension, Lymph Nodes for Head and Neck (Revised: 08/17/2007)

Note 1: Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. Do not code extracapsular extension in any nodes coded in CS Mets at DX in this field.

Note 2: A statement of the presence or absence of extracapsular extension in a pathology report takes priority over clinical assessment. However, if the pathology report contains no statement about extracapsular extension, either positive or negative, the clinical assessment should be coded. If nodes are involved but there is neither a clinical assessment of extranodal extension nor a statement about it in the pathology report, use code 999.

Note 3: According to AJCC (page 24), "Imaging studies showing amorphous spiculated margins of involved nodes or involvement of internodal fat resulting in loss of normal oval-to-round nodal shape strongly suggest extracapsular (extranodal) tumor spread; however, pathologic examination is necessary for documentation of the extent of such disease."

| Code | Description |
|------|---|
| 000 | No extracapsular extension |
| 001 | Extracapsular extension clinically, not assessed pathologically Nodes described as "fixed", not assessed pathologically |
| 005 | Extracapsular extension present pathologically |
| 888 | Not applicable; no lymph node involvement |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Hard Palate

CS Site-Specific Factor 3 Levels I-III, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels I, II, or III |
| 100 | Level I lymph node(s) involved |
| 010 | Level II lymph node(s) involved |
| 001 | Level III lymph node(s) involved |
| 110 | Level I and II lymph nodes involved |
| 101 | Level I and III lymph nodes involved |
| 011 | Level II and III lymph nodes involved |
| 111 | Level I, II and III lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Hard Palate

CS Site-Specific Factor 4 Levels IV-V and Retropharyngeal Lymph Nodes for Head and

Neck (Revised: 08/21/2006)

| Code | Description |
|------|--|
| 000 | No lymph node involvement in Levels IV or V or retropharyngeal |
| 100 | Level IV lymph node(s) involved |
| 010 | Level V lymph node(s) involved |
| 001 | Retropharyngeal nodes involved |
| 110 | Level IV and V lymph nodes involved |
| 101 | Level IV and retropharyngeal nodes involved |
| 011 | Level V and retropharyngeal nodes involved |

CS Staging Schemas

| Code | Description |
|------|---|
| 111 | Level IV and V and retropharyngeal lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Hard Palate

CS Site-Specific Factor 5 Levels VI-VII and Facial Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels VI or VII or facial nodes |
| 100 | Level VI lymph node(s) involved |
| 010 | Level VII lymph node(s) involved |
| 001 | Facial (buccinator, nasolabial) lymph node(s) involved |
| 110 | Level VI and VII lymph nodes involved |
| 101 | Level VI and facial (buccinator, nasolabial) nodes involved |
| 011 | Level VII and facial (buccinator, nasolabial) nodes involved |
| 111 | Level VI and VII and facial (buccinator, nasolabial) lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Hard Palate

CS Site-Specific Factor 6 Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|--|
| 000 | No parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), or sub-occipital lymph node involvement |

| Code | Description |
|------|---|
| 100 | Parapharyngeal lymph node(s) involved |
| 010 | Parotid (preauricular, periparotid, and/or intraparotid) lymph node(s) involved |
| 001 | Sub-occipital lymph node(s) involved |
| 110 | Parapharyngeal and parotid (preauricular, periparotid, and/or intraparotid) lymph nodes involved |
| 101 | Parapharyngeal and sub-occipital lymph nodes involved |
| 011 | Parotid (preauricular, periparotid, and/or intraparotid) and sub-occipital lymph nodes involved |
| 111 | Parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), and sub-occipital lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Soft Palate, Uvula C05.1-C05.2

C05.1 Soft Palate, NOS

C05.2 Uvula

Note 1: AJCC includes inferior surface of the soft palate (C05.1) and uvula (C05.2) with oropharynx (C09._,

C10.).

Note 2: Soft palate excludes nasopharyngeal (superior) surface of soft palate (C11.3).

| CS Tumor Size CS Extension CS TS/Ext-Eval CS Lymph Nodes CS Reg Nodes Eval Reg LN Pos Reg LN Exam CS Mets at DX CS Mets Eval | CS Site-Specific Factor 1 - Size of Lymph Nodes CS Site-Specific Factor 2 - Extracapsular Extension, Lymph Nodes for Head and Neck CS Site-Specific Factor 3 - Levels I-III, Lymph Nodes for Head and Neck CS Site-Specific Factor 4 - Levels IV-V and Retropharyngeal Lymph Nodes for Head and Neck CS Site-Specific Factor 5 - Levels VI-VII and Facial Lymph Nodes for Head and Neck CS Site-Specific Factor 6 - Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck | The following tables are available at the collaborative staging website: Histology Exclusion Table AJCC Stage Extension Size Table Lymph Nodes Size Table |
|--|---|---|
|--|---|---|

Soft Palate, Uvula CS Tumor Size SEE STANDARD TABLE

Soft Palate, Uvula

CS Extension (Revised: 08/22/2006)

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 00 | In situ; noninvasive; intraepithelial | Tis | IS | IS |
| 10 | Invasive tumor on one side confined to: Lamina propria Submucosa | * | L | L |
| 20 | Musculature invaded | * | L | L |
| 30 | Localized, NOS | * | L | L |
| 40 | Tumor crosses midline | * | L | L |
| 50 | Buccal mucosa (inner cheek) Gum (gingiva), upper | * | RE | RE |
| 60 | Lateral pharyngeal wall Tonsillar pillars and fossae Tonsils | * | RE | RE |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 65 | Hard palate | T4a | RE | RE |
| 70 | Mandible Maxilla Palatine bone (bone of hard palate) | T4a | D | D |
| 71 | Pterygoid muscle, medial or NOS | T4a | D | D |
| 72 | Tongue Deep extrinsic muscle of tongue | T4a | D | D |
| 73 | Larynx | T4a | D | D |
| 74 | Maxillary antrum (sinus) Nasopharynx, lateral or NOS | T4b | D | D |
| 77 | Nasal cavity | T4a | RE | D |
| 78 | Pterygoid muscle, lateral Pterygoid plates Note: For medial pterygoid muscle or pterygoid muscle, NOS, see code 71 | T4b | RE | D |
| 79 | 77 or 78 with any of 70 to 76 | T4b | D | D |
| 80 | Further contiguous extension Carotid artery Skull base | T4b | D | D |
| 95 | No evidence of primary tumor | ТО | U | U |
| 99 | Unknown extension Primary tumor cannot be assessed Not documented in patient record | TX | U | U |

^{*} For Extension codes 10, 20, 40, 50, and 60 ONLY, the T category is assigned based on the value of CS Tumor Size, as shown in the Extension Size Table for this site.

Soft Palate, Uvula CS TS/Ext-Eval SEE STANDARD TABLE

Soft Palate, Uvula

CS Lymph Nodes (Revised: 08/22/2006)

Note 1: For head and neck schemas, this field includes all lymph nodes defined as Levels I-VII and Other by AJCC. The complete definitions are provided in the General Instructions.

Note 2: For head and neck schemas, additional information about lymph nodes (size of involved nodes, extracapsular extension, and levels involved) is coded in Site-Specific Factors 1-6.

Note 3: If laterality of lymph nodes is not specified, assume nodes are ipsilateral. Midline nodes are considered ipsilateral.

Note 4: For head and neck cancers, if lymph nodes are described only as "supraclavicular", try to determine if they are in Level IV (deep to the sternocleidomastoid muscle, in the lower jugular chain) or Level V (in the posterior triangle, inferior to the transverse cervical artery) and code appropriately. If the specific level cannot be determined, consider them as Level V nodes.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | None; no regional lymph node involvement | N0 | NONE | NONE |
| 10 | Single positive ipsilateral regional node: Level I node Submandibular (submaxillary) Submental Level II node Jugulodigastric (subdigastric) Upper deep cervical Upper jugular Level III node Middle deep cervical Mid jugular Level IV node Jugulo-omohyoid (supraomohyoid) Lower deep cervical Lower jugular Cervical, NOS Deep cervical, NOS Internal jugular, NOS Mandibular, NOS Regional lymph node, NOS | * | RN | RN |
| 11 | Single positive ipsilateral regional node: Other groups Retropharyngeal | * | D | RN |
| 12 | Single positive ipsilateral regional node: Level V node Posterior cervical Posterior triangle (spinal accessory and transverse cervical) (upper, middle, and lower corresponding to the levels that define upper, middle, and lower jugular nodes) Level VI node Anterior deep cervical Laterotracheal Paralaryngeal Paratracheal Prelaryngeal Pretracheal Recurrent laryngeal Level VII node Upper mediastinum (for other mediastinal nodes see CS Mets at DX) Other groups Parapharyngeal Retropharyngeal Sub-occipital Supraclavicular, NOS (See Note 4) | * | D | D |

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-------|------|--------|
| 18 | Stated as N1, no other information | N1 | RN | RN |
| 19 | Stated as N2a, no other information | N2a | RN | RN |
| 20 | Multiple positive ipsilateral nodes listed in code 10 | * | RN | RN |
| 21 | Multiple positive ipsilateral nodes listed in code 11 | * | D | RN |
| 22 | Multiple positive ipsilateral nodes listed in code 12 | * | D | D |
| 29 | Stated as N2b, no other information | N2b | RN | RN |
| 30 | Regional lymph nodes as listed in code 10: Positive ipsilateral node(s), not stated if single or multiple | * | RN | RN |
| 31 | Regional lymph nodes as listed in code 11: Positive ipsilateral node(s), not stated if single or multiple | * | D | RN |
| 32 | Regional lymph nodes as listed in code 12: Positive ipsilateral node(s), not stated if single or multiple | * | D | D |
| 40 | Regional lymph nodes as listed in code 10: Positive bilateral or contralateral nodes | * | RN | RN |
| 41 | Regional lymph nodes as listed in code 11: Positive bilateral or contralateral nodes | * | D | RN |
| 42 | Regional lymph nodes as listed in code 12: Positive bilateral or contralateral nodes | * | D | D |
| 49 | Stated as N2c, no other information | N2c | RN | RN |
| 50 | Regional lymph nodes as listed in code 10: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | RN | RN |
| 51 | Regional lymph nodes as listed in code 11: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | RN |
| 52 | Regional lymph nodes as listed in code 12: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | D |
| 60 | Stated as N2, NOS | N2NOS | RN | RN |
| 70 | Stated as N3, no other information | N3 | RN | RN |
| 80 | Lymph nodes, NOS, no other information | * | RN | RN |
| 99 | Unknown; not stated Regional lymph nodes cannot be assessed Not documented in patient record | NX | U | U |

^{*} For codes 10-12, 20-22, 30-32, 40-42, 50-52, and 80 ONLY, the N category is assigned based on the value of Site-Specific Factor 1, Size of Lymph Nodes, using the extra table, Lymph Nodes Size Table for this site.

CS Staging Schemas

Soft Palate, Uvula CS Reg Nodes Eval SEE STANDARD TABLE

Soft Palate, Uvula Reg LN Pos SEE STANDARD TABLE

Soft Palate, Uvula Reg LN Exam SEE STANDARD TABLE

Soft Palate, Uvula

CS Mets at DX (Revised: 08/14/2006)

Note: Supraclavicular and transverse cervical lymph nodes are now coded in CS Lymph Nodes because they are categorized as N rather than M in AJCC TNM. Any cases coded to 10 or 50 can be reviewed and recoded. The volume of cases affected should be small.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | No; none | M0 | NONE | NONE |
| 10 | Distant lymph node(s) Mediastinal Distant lymph node(s), NOS | M1 | D | D |
| 40 | Distant metastases except distant lymph node(s) (code 10) Distant metastasis, NOS Carcinomatosis | M1 | D | D |
| 50 | (10) + (40) Distant lymph node(s) plus other distant metastases | M1 | D | D |
| 99 | Unknown if distant metastasis Distant metastasis cannot be assessed Not documented in patient record | MX | U | U |

Soft Palate, Uvula CS Mets Eval SEE STANDARD TABLE

Soft Palate, Uvula

CS Site-Specific Factor 1 Size of Lymph Nodes (Revised: 08/18/2006)

Note: Code the largest diameter, whether measured clinically or pathologically, of any involved regional lymph node(s). Do not code the size of any nodes coded in CS Mets at DX.

| Code | Description |
|------|----------------------------|
| 000 | No involved regional nodes |

CS Staging Schemas

| Code | Description |
|---------|--|
| 001-988 | 001-988 millimeters (code exact size in millimeters) |
| 989 | 989 millimeters or larger |
| 990 | Microscopic focus or foci only, no size of focus given |
| 991 | Described as "less than 1cm" |
| 992 | Described as "less than 2cm" or "greater than 1cm" or "between 1cm and 2cm" |
| 993 | Described as "less than 3cm" or "greater than 2cm" or "between 2cm and 3cm" |
| 994 | Described as "less than 4cm" or "greater than 3cm" or "between 3cm and 4cm" |
| 995 | Described as "less than 5cm" or "greater than 4cm" or "between 4cm and 5cm" |
| 996 | Described as "less than 6cm" or "greater than 5cm" or "between 5cm and 6cm" |
| 997 | Described as "more than 6cm" |
| 999 | Regional lymph node(s) involved, size not stated Unknown if regional lymph node(s) involved Not documented in patient record |

Soft Palate, Uvula

CS Site-Specific Factor 2 Extracapsular Extension, Lymph Nodes for Head and Neck (Revised: 08/17/2007)

Note 1: Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. **Note 1:** Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. Do not code extracapsular extension in any nodes coded in CS Mets at DX in this field.

Note 2: A statement of the presence or absence of extracapsular extension in a pathology report takes priority over clinical assessment. However, if the pathology report contains no statement about extracapsular extension, either positive or negative, the clinical assessment should be coded. If nodes are involved but there is neither a clinical assessment of extranodal extension nor a statement about it in the pathology report, use code 999.

Note 3: According to AJCC (page 24), "Imaging studies showing amorphous spiculated margins of involved nodes or involvement of internodal fat resulting in loss of normal oval-to-round nodal shape strongly suggest extracapsular (extranodal) tumor spread; however, pathologic examination is necessary for documentation of the extent of such disease."

| Code | Description |
|------|---|
| 000 | No extracapsular extension |
| 001 | Extracapsular extension clinically, not assessed pathologically Nodes described as "fixed", not assessed pathologically |
| 005 | Extracapsular extension present pathologically |
| 888 | Not applicable; no lymph node involvement |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Soft Palate, Uvula

CS Site-Specific Factor 3 Levels I-III, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels I, II, or III |
| 100 | Level I lymph node(s) involved |
| 010 | Level II lymph node(s) involved |
| 001 | Level III lymph node(s) involved |
| 110 | Level I and II lymph nodes involved |
| 101 | Level I and III lymph nodes involved |
| 011 | Level II and III lymph nodes involved |
| 111 | Level I, II and III lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Soft Palate, Uvula

CS Site-Specific Factor 4 Levels IV-V and Retropharyngeal Lymph Nodes for Head and

Neck (Revised: 08/21/2006)

| Code | Description |
|------|--|
| 000 | No lymph node involvement in Levels IV or V or retropharyngeal |
| 100 | Level IV lymph node(s) involved |
| 010 | Level V lymph node(s) involved |
| 001 | Retropharyngeal nodes involved |
| 110 | Level IV and V lymph nodes involved |
| 101 | Level IV and retropharyngeal nodes involved |
| 011 | Level V and retropharyngeal nodes involved |

CS Staging Schemas

| Code | Description |
|------|---|
| 111 | Level IV and V and retropharyngeal lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Soft Palate, Uvula

CS Site-Specific Factor 5 Levels VI-VII and Facial Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels VI or VII or facial nodes |
| 100 | Level VI lymph node(s) involved |
| 010 | Level VII lymph node(s) involved |
| 001 | Facial (buccinator, nasolabial) lymph node(s) involved |
| 110 | Level VI and VII lymph nodes involved |
| 101 | Level VI and facial (buccinator, nasolabial) nodes involved |
| 011 | Level VII and facial (buccinator, nasolabial) nodes involved |
| 111 | Level VI and VII and facial (buccinator, nasolabial) lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Soft Palate, Uvula

CS Site-Specific Factor 6 Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|--|
| 000 | No parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), or sub-occipital lymph node involvement |

| Code | Description | |
|------|---|--|
| 100 | Parapharyngeal lymph node(s) involved | |
| 010 | Parotid (preauricular, periparotid, and/or intraparotid) lymph node(s) involved | |
| 001 | Sub-occipital lymph node(s) involved | |
| 110 | Parapharyngeal and parotid (preauricular, periparotid, and/or intraparotid) lymph nodes involved | |
| 101 | Parapharyngeal and sub-occipital lymph nodes involved | |
| 011 | Parotid (preauricular, periparotid, and/or intraparotid) and sub-occipital lymph nodes involved | |
| 111 | Parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), and sub-occipital lymph nodes involved | |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record | |

CS Staging Schemas

Other Mouth C05.8-C05.9, C06.8-C06.9

C05.8 Overlapping lesion of palate

C05.9 Palate, NOS

C06.8 Overlapping lesion of other and unspecified parts of mouth

C06.9 Mouth, NOS

CS Site-Specific Factor 1 - Size CS Tumor Size The following tables are CS Extension of Lymph Nodes available at the collaborative CS Site-Specific Factor 2 -CS TS/Ext-Eval staging website: Extracapsular Extension, Lymph CS Lymph Nodes Histology Exclusion Table CS Reg Nodes Eval Nodes for Head and Neck AJCC Stage Reg LN Pos CS Site-Specific Factor 3 -Extension Size Table Reg LN Exam Levels I-III, Lymph Nodes for Lymph Nodes Size Table CS Mets at DX Head and Neck CS Mets Eval CS Site-Specific Factor 4 -Levels IV-V and Retropharyngeal Lymph Nodes for Head and Neck CS Site-Specific Factor 5 -Levels VI-VII and Facial Lymph Nodes for Head and Neck CS Site-Specific Factor 6 -Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck

Other Mouth CS Tumor Size SEE STANDARD TABLE

Other Mouth

CS Extension (Revised: 08/22/2006)

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | In situ; noninvasive; intraepithelial | Tis | IS | IS |
| 10 | Invasive tumor confined to: Lamina propria Submucosa | * | L | L |
| 20 | Musculature invaded | * | L | L |
| 30 | Localized, NOS | * | L | L |
| 50 | Adjacent oral cavity | * | RE | RE |
| 60 | Extension to oropharynx: Inferior surface of soft palate Lateral pharyngeal wall Lingual surface of epiglottis Vallecula | * | RE | RE |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 70 | Extension to adjacent structures: Mandible Maxilla Maxillary antrum (sinus) Nasal cavity Skin of face/neck Tongue | T4a | D | D |
| 71 | Deep extrinsic muscle of tongue | T4a | D | D |
| 72 | Skull | T4b | D | D |
| 75 | Base of skull Encases internal carotid artery Masticator space Pterygoid plates | T4b | D | D |
| 80 | Further contiguous extension | T4b | D | D |
| 95 | No evidence of primary tumor | T0 | U | U |
| 99 | Unknown extension Primary tumor cannot be assessed Not documented in patient record | TX | U | U |

^{*} For Extension codes 10, 20, 30, 50, and 60 ONLY, the T category is assigned based on the value of Tumor Size, as shown in the Extension Size Table for this site.

Other Mouth CS TS/Ext-Eval SEE STANDARD TABLE

Other Mouth

CS Lymph Nodes (Revised: 08/22/2006)

Note 1: For head and neck schemas, this field includes all lymph nodes defined as Levels I-VII and Other by AJCC. The complete definitions are provided in the General Instructions.

Note 2: For head and neck schemas, additional information about lymph nodes (size of involved nodes, extracapsular extension, and levels involved) is coded in Site-Specific Factors 1-6.

Note 3: If laterality of lymph nodes is not specified, assume nodes are ipsilateral. Midline nodes are considered ipsilateral.

Note 4: For head and neck cancers, if lymph nodes are described only as "supraclavicular", try to determine if they are in Level IV (deep to the sternocleidomastoid muscle, in the lower jugular chain) or Level V (in the posterior triangle, inferior to the transverse cervical artery) and code appropriately. If the specific level cannot be determined, consider them as Level V nodes.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | None; no regional lymph node involvement | N0 | NONE | NONE |

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 10 | Single positive ipsilateral regional node: Level I node Submandibular (submaxillary) Submental Level II node Jugulodigastric (subdigastric) Upper deep cervical Upper jugular Level III node Middle deep cervical Mid jugular Level IV node Jugulo-omohyoid (supraomohyoid) Lower deep cervical Lower jugular Cervical, NOS Deep cervical, NOS Internal jugular, NOS Mandibular, NOS Regional lymph node, NOS | * | RN | RN |
| 12 | Single positive ipsilateral regional node: Level V node Posterior cervical Posterior triangle (spinal accessory and transverse cervical) (upper, middle, and lower corresponding to the levels that define upper, middle, and lower jugular nodes) Level VI node Anterior deep cervical Laterotracheal Paralaryngeal Paratracheal Prelaryngeal Pretracheal Recurrent laryngeal Level VII node Upper mediastinum (for other mediastinal nodes see CS Mets at DX) Other groups Intraparotid Parapharyngeal Periparotid Retropharyngeal Sub-occipital Supraclavicular, NOS (See Note 4) | * | D | D |
| 18 | Stated as N1, no other information | N1 | RN | RN |
| 19 | Stated as N2a, no other information | N2a | RN | RN |
| 20 | Multiple positive ipsilateral nodes listed in code 10 | * | RN | RN |
| 22 | Multiple positive ipsilateral nodes listed in code 12 | * | D | D |
| 29 | Stated as N2b, no other information | N2b | RN | RN |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-------|------|--------|
| 30 | Regional lymph nodes as listed in code 10: Positive ipsilateral node(s), not stated if single or multiple | * | RN | RN |
| 32 | Regional lymph nodes as listed in code 12: Positive ipsilateral node(s), not stated if single or multiple | * | D | D |
| 40 | Regional lymph nodes as listed in code 10: Positive bilateral or contralateral nodes | * | RN | RN |
| 42 | Regional lymph nodes as listed in code 12: Positive bilateral or contralateral nodes | * | D | D |
| 49 | Stated as N2c, no other information | N2c | RN | RN |
| 50 | Regional lymph nodes as listed in code 10: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | RN | RN |
| 52 | Regional lymph nodes as listed in code 12: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | D |
| 60 | Stated as N2, NOS | N2NOS | RN | RN |
| 70 | Stated as N3, no other information | N3 | RN | RN |
| 80 | Lymph nodes, NOS | * | RN | RN |
| 99 | Unknown; not stated Regional lymph nodes cannot be assessed Not documented in patient record | NX | U | U |

^{*} For codes 10, 12, 20, 22, 30, 32, 40, 42, 49, 50, 52 and 80 ONLY, the N category is assigned based on the value of Site-Specific Factor 1, Size of Lymph Nodes, using the extra table, Lymph Nodes Size Table for this site.

Other Mouth CS Reg Nodes Eval SEE STANDARD TABLE

Other Mouth Reg LN Pos SEE STANDARD TABLE

Other Mouth Reg LN Exam SEE STANDARD TABLE

CS Staging Schemas

Other Mouth

CS Mets at DX (Revised: 08/14/2006)

Note: Supraclavicular and transverse cervical lymph nodes are now coded in CS Lymph Nodes because they are categorized as N rather than M in AJCC TNM. Any cases coded to 10 or 50 can be reviewed and recoded. The volume of cases affected should be small.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | No; none | M0 | NONE | NONE |
| 10 | Distant lymph node(s) Mediastinal Distant lymph node(s), NOS | M1 | D | D |
| 40 | Distant metastases except distant lymph node(s) (code 10) Distant metastasis, NOS Carcinomatosis | M1 | D | D |
| 50 | (10) + (40) Distant lymph node(s) plus other distant metastases | M1 | D | D |
| 99 | Unknown if distant metastasis Distant metastasis cannot be assessed Not documented in patient record | MX | U | U |

Other Mouth CS Mets Eval SEE STANDARD TABLE

Other Mouth

CS Site-Specific Factor 1 Size of Lymph Nodes (Revised: 08/18/2006)

Note: Code the largest diameter, whether measured clinically or pathologically, of any involved regional lymph node(s). Do not code the size of any nodes coded in CS Mets at DX.

| Code | Description |
|---------|---|
| 000 | No involved regional nodes |
| 001-988 | 001-988 millimeters (code exact size in millimeters) |
| 989 | 989 millimeters or larger |
| 990 | Microscopic focus or foci only, no size of focus given |
| 991 | Described as "less than 1cm" |
| 992 | Described as "less than 2cm" or "greater than 1cm" or "between 1cm and 2cm" |
| 993 | Described as "less than 3cm" or "greater than 2cm" or "between 2cm and 3cm" |
| 994 | Described as "less than 4cm" or "greater than 3cm" or "between 3cm and 4cm" |
| 995 | Described as "less than 5cm" or "greater than 4cm" or "between 4cm and 5cm" |
| 996 | Described as "less than 6cm" or "greater than 5cm" or "between 5cm and 6cm" |
| 997 | Described as "more than 6cm" |

CS Staging Schemas

| Code | Description |
|------|--|
| 999 | Regional lymph node(s) involved, size not stated Unknown if regional lymph node(s) involved Not documented in patient record |

Other Mouth

CS Site-Specific Factor 2 Extracapsular Extension, Lymph Nodes for Head and Neck (Revised: 08/17/2007)

- **Note 1:** Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. Do not code extracapsular extension in any nodes coded in CS Mets at DX in this field.
- **Note 2:** A statement of the presence or absence of extracapsular extension in a pathology report takes priority over clinical assessment. However, if the pathology report contains no statement about extracapsular extension, either positive or negative, the clinical assessment should be coded. If nodes are involved but there is neither a clinical assessment of extranodal extension nor a statement about it in the pathology report, use code 999.
- **Note 3:** According to AJCC (page 24), "Imaging studies showing amorphous spiculated margins of involved nodes or involvement of internodal fat resulting in loss of normal oval-to-round nodal shape strongly suggest extracapsular (extranodal) tumor spread; however, pathologic examination is necessary for documentation of the extent of such disease."

| Code | Description |
|------|---|
| 000 | No extracapsular extension |
| 001 | Extracapsular extension clinically, not assessed pathologically Nodes described as "fixed", not assessed pathologically |
| 005 | Extracapsular extension present pathologically |
| 888 | Not applicable; no lymph node involvement |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Other Mouth

CS Site-Specific Factor 3 Levels I-III, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels I, II, or III |
| 100 | Level I lymph node(s) involved |
| 010 | Level II lymph node(s) involved |
| 001 | Level III lymph node(s) involved |
| 110 | Level I and II lymph nodes involved |

CS Staging Schemas

| Code | Description |
|------|---|
| 101 | Level I and III lymph nodes involved |
| 011 | Level II and III lymph nodes involved |
| 111 | Level I, II and III lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Other Mouth

CS Site-Specific Factor 4 Levels IV-V and Retropharyngeal Lymph Nodes for Head and

Neck (Revised: 08/21/2006)

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels IV or V or retropharyngeal |
| 100 | Level IV lymph node(s) involved |
| 010 | Level V lymph node(s) involved |
| 001 | Retropharyngeal nodes involved |
| 110 | Level IV and V lymph nodes involved |
| 101 | Level IV and retropharyngeal nodes involved |
| 011 | Level V and retropharyngeal nodes involved |
| 111 | Level IV and V and retropharyngeal lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Other Mouth

CS Site-Specific Factor 5 Levels VI-VII and Facial Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description | |
|------|---|--|
| 000 | No lymph node involvement in Levels VI or VII or facial nodes | |
| 100 | Level VI lymph node(s) involved | |
| 010 | Level VII lymph node(s) involved | |
| 001 | Facial (buccinator, nasolabial) lymph node(s) involved | |
| 110 | Level VI and VII lymph nodes involved | |
| 101 | Level VI and facial (buccinator, nasolabial) nodes involved | |
| 011 | Level VII and facial (buccinator, nasolabial) nodes involved | |
| 111 | Level VI and VII and facial (buccinator, nasolabial) lymph nodes involved | |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record | |

Other Mouth

CS Site-Specific Factor 6 Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description | |
|------|--|--|
| 000 | No parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), or sub-occipital lymph node involvement | |
| 100 | apharyngeal lymph node(s) involved | |
| 010 | Parotid (preauricular, periparotid, and/or intraparotid) lymph node(s) involved | |
| 001 | Sub-occipital lymph node(s) involved | |
| 110 | Parapharyngeal and parotid (preauricular, periparotid, and/or intraparotid) lymph nodes involved | |
| 101 | Parapharyngeal and sub-occipital lymph nodes involved | |

| Code | Description | | |
|------|---|--|--|
| 011 | arotid (preauricular, periparotid, and/or intraparotid) and sub-occipital lymph nodes involved | | |
| 111 | Parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), and sub-occipital lymph not involved | | |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record | | |

CS Staging Schemas

Cheek (Buccal) Mucosa, Vestibule C06.0-C06.1

C06.0 Cheek mucosa C06.1 Vestibule of mouth

| CS Tumor Size CS Extension CS TS/Ext-Eval CS Lymph Nodes CS Reg Nodes Eval Reg LN Pos Reg LN Exam CS Mets at DX CS Mets Eval | CS Site-Specific Factor 1 - Size of Lymph Nodes CS Site-Specific Factor 2 - Extracapsular Extension, Lymph Nodes for Head and Neck CS Site-Specific Factor 3 - Levels I-III, Lymph Nodes for Head and Neck CS Site-Specific Factor 4 - Levels IV-V and Retropharyngeal Lymph Nodes for Head and Neck CS Site-Specific Factor 5 - Levels VI-VII and Facial Lymph Nodes for Head and Neck CS Site-Specific Factor 6 - Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes for | The following tables are available at the collaborative staging website: Histology Exclusion Table AJCC Stage Extension Size Table Lymph Nodes Size Table |
|--|--|---|
| | | |

Cheek (Buccal) Mucosa, Vestibule CS Tumor Size SEE STANDARD TABLE

Cheek (Buccal) Mucosa, Vestibule

CS Extension (Revised: 08/22/2006)

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | In situ; noninvasive; intraepithelial | Tis | IS | IS |
| 10 | Invasive tumor confined to: Lamina propria Submucosa | * | L | L |
| 20 | Musculature (buccinator) | * | RE | L |
| 30 | Localized, NOS | * | L | L |
| 50 | Lip(s) including commissure | * | RE | RE |
| 51 | Gingiva | * | RE | RE |
| 60 | Lateral pharyngeal wall Tonsillar pillars and fossae Tonsils | * | RE | RE |
| 65 | Subcutaneous soft tissue of cheek | T4a | RE | RE |
| 66 | Skin of cheek (WITH or WITHOUT ulceration) | T4a | RE | D |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 67 | Maxillary sinus | T4a | D | D |
| 70 | Bone (cortical): Mandible Maxilla | T4a | D | D |
| 73 | Skull | T4b | D | D |
| 75 | Tongue Deep extrinsic muscle of tongue | T4a | D | D |
| 79 | Other contiguous extension: Base of skull Encases internal carotid artery Masticator space Pterygoid plates | T4b | D | D |
| 80 | Further contiguous extension: Hard palate Soft palate | T4b | D | D |
| 95 | No evidence of primary tumor | ТО | U | U |
| 99 | Unknown extension Primary tumor cannot be assessed Not documented in patient record | TX | U | U |

^{*} For Extension codes 10, 20, 30, 50, 51, and 60 ONLY, the T category is assigned based on the value of CS Tumor Size, as shown in the Extension Size Table for this site.

Cheek (Buccal) Mucosa, Vestibule CS TS/Ext-Eval SEE STANDARD TABLE

Cheek (Buccal) Mucosa, Vestibule

CS Lymph Nodes (Revised: 08/22/2006)

Note 1: For head and neck schemas, this field includes all lymph nodes defined as Levels I-VII and Other by AJCC. The complete definitions are provided in the General Instructions.

Note 2: For head and neck schemas, additional information about lymph nodes (size of involved nodes, extracapsular extension, and levels involved) is coded in Site-Specific Factors 1-6.

Note 3: If laterality of lymph nodes is not specified, assume nodes are ipsilateral. Midline nodes are considered ipsilateral.

Note 4: For head and neck cancers, if lymph nodes are described only as "supraclavicular", try to determine if they are in Level IV (deep to the sternocleidomastoid muscle, in the lower jugular chain) or Level V (in the posterior triangle, inferior to the transverse cervical artery) and code appropriately. If the specific level cannot be determined, consider them as Level V nodes.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | None; no regional lymph node involvement | N0 | NONE | NONE |

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 10 | Single positive ipsilateral regional node: Level I node Submandibular (submaxillary) Submental Level II node Jugulodigastric (subdigastric) Upper deep cervical Upper jugular Level III node Middle deep cervical Mid jugular Level IV node Jugulo-omohyoid (supraomohyoid) Lower deep cervical Lower jugular Other groups Facial: Buccinator (buccal) Nasolabial Parotid, NOS Infra-auricular Preauricular Cervical, NOS Deep cervical, NOS Internal jugular, NOS Mandibular, NOS Regional lymph node, NOS | * | RN | RN |
| 12 | Single positive ipsilateral regional node: Level V node Posterior cervical Posterior triangle (spinal accessory and transverse cervical) (upper, middle, and lower corresponding to the levels that define upper, middle, and lower jugular nodes) Level VI node Anterior deep cervical Laterotracheal Paralaryngeal Paratracheal Pretracheal Pretracheal Recurrent laryngeal Level VII node Upper mediastinum (for other mediastinal nodes see CS Mets at DX) Other groups Intraparotid Parapharyngeal Periparotid Retropharyngeal Sub-occipital Supraclavicular, NOS (See Note 4) | * | D | D |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-------|------|--------|
| 18 | Stated as N1, no other information | N1 | RN | RN |
| 19 | Stated as N2a, no other information | N2a | RN | RN |
| 20 | Multiple positive ipsilateral nodes listed in code 10 | * | RN | RN |
| 22 | Multiple positive ipsilateral nodes listed in code 12 | * | D | D |
| 29 | Stated as N2b, no other information | N2b | RN | RN |
| 30 | Regional lymph nodes as listed in code 10: Positive ipsilateral node(s), not stated if single or multiple or regional | * | RN | RN |
| 32 | Regional lymph nodes as listed in code 12: Positive ipsilateral node(s), not stated if single or multiple | * | D | D |
| 40 | Regional lymph nodes as listed in code 10: Positive bilateral or contralateral nodes | * | RN | RN |
| 42 | Regional lymph nodes as listed in code 12: Positive bilateral or contralateral nodes | * | D | D |
| 49 | Stated as N2c, no other information | N2c | RN | RN |
| 50 | Regional lymph nodes as listed in code 10: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | RN | RN |
| 52 | Regional lymph nodes as listed in code 12: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | D |
| 60 | Stated as N2, NOS | N2NOS | RN | RN |
| 70 | Stated as N3, no other information | N3 | RN | RN |
| 80 | Lymph nodes, NOS | * | RN | RN |
| 99 | Unknown; not stated Regional lymph nodes cannot be assessed Not documented in patient record | NX | U | U |

^{*} For codes 10, 12, 20, 22, 30, 32, 40, 42, 49, 50, 52 and 80 ONLY, the N category is assigned based on the value of Site-Specific Factor 1, Size of Lymph Nodes, using the extra table, Lymph Nodes Size Table for this site.

Cheek (Buccal) Mucosa, Vestibule CS Reg Nodes Eval SEE STANDARD TABLE

Cheek (Buccal) Mucosa, Vestibule Reg LN Pos SEE STANDARD TABLE

CS Staging Schemas

Cheek (Buccal) Mucosa, Vestibule Reg LN Exam SEE STANDARD TABLE

Cheek (Buccal) Mucosa, Vestibule

CS Mets at DX (Revised: 08/14/2006)

Note: Supraclavicular and transverse cervical lymph nodes are now coded in CS Lymph Nodes because they are categorized as N rather than M in AJCC TNM. Any cases coded to 10 or 50 can be reviewed and recoded. The volume of cases affected should be small.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | No; none | M0 | NONE | NONE |
| 10 | Distant lymph node(s) Mediastinal Distant lymph node(s), NOS | M1 | D | D |
| 40 | Distant metastases except distant lymph node(s) (code 10) Distant metastasis, NOS Carcinomatosis | M1 | D | D |
| 50 | (10) + (40) Distant lymph node(s) plus other distant metastases | M1 | D | D |
| 99 | Unknown if distant metastasis Distant metastasis cannot be assessed Not documented in patient record | MX | U | U |

Cheek (Buccal) Mucosa, Vestibule CS Mets Eval SEE STANDARD TABLE

Cheek (Buccal) Mucosa, Vestibule

CS Site-Specific Factor 1 Size of Lymph Nodes (Revised: 08/18/2006)

Note: Code the largest diameter, whether measured clinically or pathologically, of any involved regional lymph node(s). Do not code the size of any nodes coded in CS Mets at DX.

| Code | Description |
|---------|---|
| 000 | No involved regional nodes |
| 001-988 | 001-988 millimeters (code exact size in millimeters) |
| 989 | 989 millimeters or larger |
| 990 | Microscopic focus or foci only, no size of focus given |
| 991 | Described as "less than 1cm" |
| 992 | Described as "less than 2cm" or "greater than 1cm" or "between 1cm and 2cm" |
| 993 | Described as "less than 3cm" or "greater than 2cm" or "between 2cm and 3cm" |

CS Staging Schemas

| Code | Description |
|------|--|
| 994 | Described as "less than 4cm" or "greater than 3cm" or "between 3cm and 4cm" |
| 995 | Described as "less than 5cm" or "greater than 4cm" or "between 4cm and 5cm" |
| 996 | Described as "less than 6cm" or "greater than 5cm" or "between 5cm and 6cm" |
| 997 | Described as "more than 6cm" |
| 999 | Regional lymph node(s) involved, size not stated Unknown if regional lymph node(s) involved Not documented in patient record |

Cheek (Buccal) Mucosa, Vestibule

CS Site-Specific Factor 2 Extracapsular Extension, Lymph Nodes for Head and Neck (Revised: 08/17/2007)

Note 1: Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. **Note 1:** Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. Do not code extracapsular extension in any nodes coded in CS Mets at DX in this field.

Note 2: A statement of the presence or absence of extracapsular extension in a pathology report takes priority over clinical assessment. However, if the pathology report contains no statement about extracapsular extension, either positive or negative, the clinical assessment should be coded. If nodes are involved but there is neither a clinical assessment of extranodal extension nor a statement about it in the pathology report, use code 999.

Note 3: According to AJCC (page 24), "Imaging studies showing amorphous spiculated margins of involved nodes or involvement of internodal fat resulting in loss of normal oval-to-round nodal shape strongly suggest extracapsular (extranodal) tumor spread; however, pathologic examination is necessary for documentation of the extent of such disease."

| Code | Description |
|------|---|
| 000 | No extracapsular extension |
| 001 | Extracapsular extension clinically, not assessed pathologically Nodes described as "fixed", not assessed pathologically |
| 005 | Extracapsular extension present pathologically |
| 888 | Not applicable; no lymph node involvement |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Cheek (Buccal) Mucosa, Vestibule

CS Site-Specific Factor 3 Levels I-III, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

CS Staging Schemas

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels I, II, or III |
| 100 | Level I lymph node(s) involved |
| 010 | Level II lymph node(s) involved |
| 001 | Level III lymph node(s) involved |
| 110 | Level I and II lymph nodes involved |
| 101 | Level I and III lymph nodes involved |
| 011 | Level II and III lymph nodes involved |
| 111 | Level I, II and III lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Cheek (Buccal) Mucosa, Vestibule CS Site-Specific Factor 4 Levels IV-V and Retropharyngeal Lymph Nodes for Head and

Neck (Revised: 08/21/2006)

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels IV or V or retropharyngeal |
| 100 | Level IV lymph node(s) involved |
| 010 | Level V lymph node(s) involved |
| 001 | Retropharyngeal nodes involved |
| 110 | Level IV and V lymph nodes involved |
| 101 | Level IV and retropharyngeal nodes involved |
| 011 | Level V and retropharyngeal nodes involved |
| 111 | Level IV and V and retropharyngeal lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Cheek (Buccal) Mucosa, Vestibule

CS Site-Specific Factor 5 Levels VI-VII and Facial Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels VI or VII or facial nodes |
| 100 | Level VI lymph node(s) involved |
| 010 | Level VII lymph node(s) involved |
| 001 | Facial (buccinator, nasolabial) lymph node(s) involved |
| 110 | Level VI and VII lymph nodes involved |
| 101 | Level VI and facial (buccinator, nasolabial) nodes involved |
| 011 | Level VII and facial (buccinator, nasolabial) nodes involved |
| 111 | Level VI and VII and facial (buccinator, nasolabial) lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Cheek (Buccal) Mucosa, Vestibule

CS Site-Specific Factor 6 Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|--|
| 000 | No parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), or sub-occipital lymph node involvement |
| 100 | Parapharyngeal lymph node(s) involved |
| 010 | Parotid (preauricular, periparotid, and/or intraparotid) lymph node(s) involved |
| 001 | Sub-occipital lymph node(s) involved |
| 110 | Parapharyngeal and parotid (preauricular, periparotid, and/or intraparotid) lymph nodes involved |
| 101 | Parapharyngeal and sub-occipital lymph nodes involved |

| Code | Description |
|------|---|
| 011 | Parotid (preauricular, periparotid, and/or intraparotid) and sub-occipital lymph nodes involved |
| 111 | Parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), and sub-occipital lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Surgery Codes

Oral Cavity

Lip C000–C009, Base of Tongue C019, Other Parts of Tongue C020–C029, Gum C030–C039, Floor of Mouth C040–C049, Palate C050–C059, Other Parts of Mouth C060–C069 (Except for M9750, 9760-9764, 9800-9820, 9826, 9831-9920, 9931-9964, 9980-9989)

Codes

- None; no surgery of primary site; autopsy ONLY
- 10 Local tumor destruction, NOS
 - 11 Photodynamic therapy (PDT)
 - 12 Electrocautery; fulguration (includes use of hot forceps for tumor destruction)
 - 13 Cryosurgery
 - 14 Laser

No specimen sent to pathology from surgical events 10–14

- 20 Local tumor excision, NOS
 - 26 Polypectomy
 - 27 Excisional biopsy

Any combination of 20 or 26-27 WITH

- 21 Photodynamic therapy (PDT)
- 22 Electrocautery
- 23 Cryosurgery
- 24 Laser ablation

[**SEER Note:** Codes 21 to 24 above combine 20 Local tumor excision, 26 Polypectomy or 27 Excisional biopsy with 21 PDT, 22 Electrocautery, 23 Cryosurgery, or 24 Laser ablation]

25 Laser excision

Specimen sent to pathology from surgical events 20–27

[SEER Note: Codes 20-27 include shave and wedge resection]

30 Wide excision, NOS

Code 30 includes:

Hemiglossectomy

Partial glossectomy

- 40 Radical excision of tumor, NOS
 - 41 Radical excision of tumor ONLY
 - 42 Combination of 41 WITH resection in continuity with mandible (marginal, segmental, hemi-, or total resection)
 - Combination of 41 WITH resection in continuity with maxilla (partial, subtotal, or total resection)

[**SEER Note:** In continuity with or "en bloc" means that all of the tissues were removed during the same procedure, but not necessarily in a single specimen]

Codes 40–43 include:

Total glossectomy Radical glossectomy

- 90 Surgery, NOS
- 99 Unknown if surgery performed; death certificate ONLY

Parotid, Other and Unspecified Glands C079, C080-C089

Note: For Multiple Primary and Histology Coding Rules: see Head and Neck (pg C-3)

CS Staging Schemas

Parotid Gland

C07.9

C07.9 Parotid gland **Note:** Laterality must be coded for C07.9.

| CS Tumor Size CS Extension CS TS/Ext-Eval CS Lymph Nodes CS Reg Nodes Eval Reg LN Pos Reg LN Exam CS Mets at DX CS Mets Eval | CS Site-Specific Factor 1 - Size of Lymph Nodes CS Site-Specific Factor 2 - Extracapsular Extension, Lymph Nodes for Head and Neck CS Site-Specific Factor 3 - Levels I-III, Lymph Nodes for Head and Neck CS Site-Specific Factor 4 - Levels IV-V and Retropharyngeal Lymph Nodes for Head and Neck CS Site-Specific Factor 5 - Levels VI-VII and Facial Lymph Nodes for Head and Neck CS Site-Specific Factor 6 - Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck | The following tables are available at the collaborative staging website: Histology Exclusion Table AJCC Stage Extension Size Table Lymph Nodes Size Table |
|--|---|---|
|--|---|---|

Parotid Gland CS Tumor Size SEE STANDARD TABLE

Parotid Gland

CS Extension (Revised: 08/14/2006)

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | In situ; non-invasive; intraepithelial | Tis | IS | IS |
| 10 | Invasive tumor confined to gland/duct of origin Multiple foci confined to substance of parotid gland | * | L | L |
| 30 | Localized, NOS | * | L | L |
| 35 | Microscopic extraparenchymal extension ONLY | * | RE | RE |
| 40 | Another major salivary gland (submaxillary, sublingual) Periglandular soft/connective tissue including macroscopic extraparenchymal extension Pharyngeal mucosa Skeletal muscle: Digastric Masseter Pterygoid Sternocleidomastoid Stylohyoid | T3 | RE | RE |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 42 | External auditory meatus Skin overlying gland | T4a | RE | RE |
| 45 | Periosteum of mandible | T4a | RE | RE |
| 50 | Auricular nerve Mandible Mastoid | T4a | RE | RE |
| 70 | Facial (7th) nerve | T4a | RE | D |
| 72 | Spinal accessory nerve | T4a | RE | D |
| 75 | Major blood vessel(s): Carotid artery Facial artery or vein Jugular vein Maxillary artery | T4b | RE | RE |
| 76 | Base of skull Skull, NOS | T4b | RE | D |
| 77 | Pterygoid plates | T4b | D | D |
| 80 | Further contiguous extension | T4b | D | D |
| 95 | No evidence of primary tumor | ТО | U | U |
| 99 | Unknown extension Primary tumor cannot be assessed Not documented in patient record | TX | U | U |

^{*} For Extension codes 10, 30, and 35 ONLY, the T category is assigned based on the value of CS Tumor Size as shown in the Extension by Size Table for this site.

Parotid Gland CS TS/Ext-Eval SEE STANDARD TABLE

Parotid Gland

CS Lymph Nodes (Revised: 09/17/2007)

Note 1: For head and neck schemas, this field includes all lymph nodes defined as Levels I-VII and Other by AJCC. The complete definitions are provided in the General Instructions.

Note 2: For head and neck schemas, additional information about lymph nodes (size of involved nodes, extracapsular extension, and levels involved) is coded in Site-Specific Factors 1-6.

Note 3: If laterality of lymph nodes is not specified, assume nodes are ipsilateral. Midline nodes are considered ipsilateral.

Note 4: For head and neck cancers, if lymph nodes are described only as "supraclavicular", try to determine if they are in Level IV (deep to the sternocleidomastoid muscle, in the lower jugular chain) or Level V (in the posterior triangle, inferior to the transverse cervical artery) and code appropriately. If the specific level cannot be determined, consider them as Level V nodes.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | None; no regional lymph node involvement | N0 | NONE | NONE |

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 10 | Single positive ipsilateral regional node: Level I node Submandibular (submaxillary) Submental Parotid nodes Infra-auricular Intraparotid Periparotid Preauricular Cervical, NOS Deep Cervical, NOS Facial Internal jugular Mandibular, NOS Regional lymph node, NOS | * | RN | RN |
| 11 | Single positive ipsilateral regional node: Level II node Upper deep cervical Upper jugular Level III node Middle deep cervical Mid jugular Level IV node Lower deep cervical Lower jugular | * | D | RN |
| 12 | Single positive ipsilateral regional node: Level V node Posterior cervical Posterior triangle (spinal accessory and transverse cervical) (upper, middle, and lower corresponding to the levels that define upper, middle, and lower jugular nodes) Level VI node Anterior deep cervical Laterotracheal Paralaryngeal Paratracheal Prelaryngeal Pretracheal Recurrent laryngeal Level VII node Upper mediastinum (for other mediastinal nodes see CS Mets at DX) Other groups Parapharyngeal Retropharyngeal Retropharyngeal Sub-occipital Supraclavicular, NOS (See Note 4) | * | D | D |
| 18 | Stated as N1, no other information | N1 | RN | RN |
| 19 | Stated as N2a, no other information | N2a | RN | RN |
| 20 | Multiple positive ipsilateral nodes listed in code 10 | * | RN | RN |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-------|------|--------|
| 21 | Multiple positive ipsilateral nodes listed in code 11 | * | D | RN |
| 22 | Multiple positive ipsilateral nodes listed in code 12 | * | D | D |
| 29 | Stated as N2b, no other information | N2b | RN | RN |
| 30 | Regional lymph nodes as listed in code 10: Positive ipsilateral node(s), not stated if single or multiple | * | RN | RN |
| 31 | Regional lymph nodes as listed in code 11: Positive ipsilateral node(s), not stated if single or multiple | * | D | RN |
| 32 | Regional lymph nodes as listed in code 12: Positive ipsilateral node(s), not stated if single or multiple | * | D | D |
| 40 | Regional lymph nodes as listed in code 10: Positive bilateral or contralateral nodes | * | RN | RN |
| 41 | Regional lymph nodes as listed in code 11: Positive bilateral or contralateral nodes | * | D | RN |
| 42 | Regional lymph nodes as listed in code 12: Positive bilateral or contralateral nodes | * | D | D |
| 49 | Stated as N2c, no other information | N2c | RN | RN |
| 50 | Regional lymph nodes as listed in code 10: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | RN | RN |
| 51 | Regional lymph nodes as listed in code 11: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | RN |
| 52 | Regional lymph nodes as listed in code 12: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | D |
| 60 | Stated as N2, NOS | N2NOS | RN | RN |
| 70 | Stated as N3, no other information | N3 | RN | RN |
| 80 | Lymph nodes, NOS, no other information | * | RN | RN |
| 99 | Unknown; not stated Regional lymph node(s) cannot be assessed Not documented in patient record | NX | U | U |
| | | • | | • |

^{*} For codes 10-12, 20-22, 30-32, 40-42, 50-52, and 80 ONLY, the N category is assigned based on the value of Site-Specific Factor 1, Size of Lymph Nodes, using the extra table, Lymph Nodes Size table, for this site.

Parotid Gland CS Reg Nodes Eval SEE STANDARD TABLE

CS Staging Schemas

Parotid Gland Reg LN Pos SEE STANDARD TABLE

Parotid Gland Reg LN Exam SEE STANDARD TABLE

Parotid Gland

CS Mets at DX (Revised: 02/22/2005)

Note: Supraclavicular and transverse cervical lymph nodes are now coded in CS Lymph Nodes because they are categorized as N rather than M in AJCC TNM. Any cases coded to 10 or 50 can be reviewed and recoded. The volume of cases affected should be small.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | No; none | M0 | NONE | NONE |
| 10 | Distant lymph node(s) | M1 | D | D |
| 40 | Distant metastases except distant lymph node(s) (code 10) Distant metastasis, NOS Carcinomatosis | M1 | D | D |
| 50 | (10) + (40) Distant lymph node(s) plus other distant metastases | M1 | D | D |
| 99 | Unknown if distant metastasis Distant metastasis cannot be assessed Not documented in patient record | MX | U | U |

Parotid Gland CS Mets Eval SEE STANDARD TABLE

Parotid Gland

$CS\ Site-Specific\ Factor\ 1\ Size\ of\ Lymph\ Nodes\ ({\tt Revised:}\ 08/18/2006)$

Note: Code the largest diameter, whether measured clinically or pathologically, of any involved regional lymph node(s). Do not code the size of any nodes coded in CS Mets at DX.

| Code | Description |
|---------|--|
| 000 | No involved regional nodes |
| 001-988 | 001-988 millimeters (code exact size in millimeters) |
| 989 | 989 millimeters or larger |
| 990 | Microscopic focus or foci only, no size of focus given |
| 991 | Described as "less than 1cm" |

CS Staging Schemas

| Code | Description |
|------|--|
| 992 | Described as "less than 2cm" or "greater than 1cm" or "between 1cm and 2cm" |
| 993 | Described as "less than 3cm" or "greater than 2cm" or "between 2cm and 3cm" |
| 994 | Described as "less than 4cm" or "greater than 3cm" or "between 3cm and 4cm" |
| 995 | Described as "less than 5cm" or "greater than 4cm" or "between 4cm and 5cm" |
| 996 | Described as "less than 6cm" or "greater than 5cm" or "between 5cm and 6cm" |
| 997 | Described as "more than 6cm" |
| 999 | Regional lymph node(s) involved, size not stated Unknown if regional lymph node(s) involved Not documented in patient record |

Parotid Gland

CS Site-Specific Factor 2 Extracapsular Extension, Lymph Nodes for Head and Neck (Revised: 08/17/2007)

Note 1: Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. Do not code extracapsular extension in any nodes coded in CS Mets at DX in this field.

Note 2: A statement of the presence or absence of extracapsular extension in a pathology report takes priority over clinical assessment. However, if the pathology report contains no statement about extracapsular extension, either positive or negative, the clinical assessment should be coded. If nodes are involved but there is neither a clinical assessment of extranodal extension nor a statement about it in the pathology report, use code 999.

Note 3: According to AJCC (page 24), "Imaging studies showing amorphous spiculated margins of involved nodes or involvement of internodal fat resulting in loss of normal oval-to-round nodal shape strongly suggest extracapsular (extranodal) tumor spread; however, pathologic examination is necessary for documentation of the extent of such disease."

| Code | Description |
|------|---|
| 000 | No extracapsular extension |
| 001 | Extracapsular extension clinically, not assessed pathologically Nodes described as "fixed", not assessed pathologically |
| 005 | Extracapsular extension present pathologically |
| 888 | Not applicable; no lymph node involvement |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Parotid Gland

CS Site-Specific Factor 3 Levels I-III, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels I, II, or III |
| 100 | Level I lymph node(s) involved |
| 010 | Level II lymph node(s) involved |
| 001 | Level III lymph node(s) involved |
| 110 | Level I and II lymph nodes involved |
| 101 | Level I and III lymph nodes involved |
| 011 | Level II and III lymph nodes involved |
| 111 | Level I, II and III lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Parotid Gland

CS Site-Specific Factor 4 Levels IV-V and Retropharyngeal Lymph Nodes for Head and

Neck (Revised: 08/21/2006)

| Code | Description |
|------|--|
| 000 | No lymph node involvement in Levels IV or V or retropharyngeal |
| 100 | Level IV lymph node(s) involved |
| 010 | Level V lymph node(s) involved |
| 001 | Retropharyngeal nodes involved |
| 110 | Level IV and V lymph nodes involved |
| 101 | Level IV and retropharyngeal nodes involved |
| 011 | Level V and retropharyngeal nodes involved |

CS Staging Schemas

| Code | Description |
|------|---|
| 111 | Level IV and V and retropharyngeal lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Parotid Gland

CS Site-Specific Factor 5 Levels VI-VII and Facial Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels VI or VII or facial nodes |
| 100 | Level VI lymph node(s) involved |
| 010 | Level VII lymph node(s) involved |
| 001 | Facial (buccinator, nasolabial) lymph node(s) involved |
| 110 | Level VI and VII lymph nodes involved |
| 101 | Level VI and facial (buccinator, nasolabial) nodes involved |
| 011 | Level VII and facial (buccinator, nasolabial) nodes involved |
| 111 | Level VI and VII and facial (buccinator, nasolabial) lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Parotid Gland

CS Site-Specific Factor 6 Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description | |
|------|--|--|
| 000 | No parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), or sub-occipital lymph node involvement | |

| Code | Description | |
|------|---|--|
| 100 | Parapharyngeal lymph node(s) involved | |
| 010 | Parotid (preauricular, periparotid, and/or intraparotid) lymph node(s) involved | |
| 001 | Sub-occipital lymph node(s) involved | |
| 110 | Parapharyngeal and parotid (preauricular, periparotid, and/or intraparotid) lymph nodes involved | |
| 101 | Parapharyngeal and sub-occipital lymph nodes involved | |
| 011 | Parotid (preauricular, periparotid, and/or intraparotid) and sub-occipital lymph nodes involved | |
| 111 | Parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), and sub-occipital lymph nodes involved | |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record | |

CS Staging Schemas

Submandibular Gland

C08.0

C08.0 Submandibular gland

Note: Laterality must be coded for C08.0.

| CS Tumor Size CS Extension CS TS/Ext-Eval CS Lymph Nodes CS Reg Nodes Eval Reg LN Pos Reg LN Exam CS Mets at DX CS Mets Eval | CS Site-Specific Factor 1 - Size of Lymph Nodes CS Site-Specific Factor 2 - Extracapsular Extension, Lymph Nodes for Head and Neck CS Site-Specific Factor 3 - Levels I-III, Lymph Nodes for Head and Neck CS Site-Specific Factor 4 - Levels IV-V and Retropharyngeal Lymph Nodes for Head and Neck CS Site-Specific Factor 5 - Levels VI-VII and Facial Lymph Nodes for Head and Neck CS Site-Specific Factor 6 - Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck | The following tables are available at the collaborative staging website: Histology Exclusion Table AJCC Stage Extension Size Table Lymph Nodes Size Table |
|--|---|---|
|--|---|---|

Submandibular Gland CS Tumor Size SEE STANDARD TABLE

Submandibular Gland

CS Extension (Revised: 08/14/2006)

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 00 | In situ; non-invasive; intraepithelial | Tis | IS | IS |
| 10 | Invasive tumor confined to gland/duct of origin | * | L | L |
| 30 | Localized, NOS | * | L | L |
| 35 | Microscopic extraparenchymal extension ONLY | * | RE | RE |
| 40 | Another major salivary gland (parotid, sublingual) Periglandular soft/connective tissue including macroscopic extraparenchymal extension Skeletal muscle: Digastric Genioglossus Geniohyoid Hyoglossus Mylohyoid Palatoglossus Pterygoid Styloglossus Stylohyoid | Т3 | RE | RE |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 45 | Periosteum of mandible | T4a | RE | RE |
| 50 | Mandible Nerves: Facial (7th) Lingual | T4a | RE | RE |
| 51 | External auditory meatus | T4a | D | D |
| 52 | Major blood vessels: Carotid artery Facial artery or vein Maxillary artery | T4b | RE | RE |
| 71 | Base of skull Skull, NOS | T4b | RE | D |
| 72 | Spinal accessory nerve | T4a | RE | D |
| 77 | Pterygoid plates | T4b | D | D |
| 80 | Further contiguous extension | T4b | D | D |
| 95 | No evidence of primary tumor | ТО | U | U |
| 99 | Unknown extension Primary tumor cannot be assessed Not documented in patient record | TX | U | U |

^{*} For Extension codes 10, 30, and 35 ONLY, the T category is assigned based on value of CS Tumor Size as shown in the Extension Size Table for this site.

Submandibular Gland CS TS/Ext-Eval SEE STANDARD TABLE

Submandibular Gland

CS Lymph Nodes (Revised: 09/17/2007)

Note 1: For head and neck schemas, this field includes all lymph nodes defined as Levels I-VII and Other by AJCC. The complete definitions are provided in the General Instructions.

Note 2: For head and neck schemas, additional information about lymph nodes (size of involved nodes, extracapsular extension, and levels involved) is coded in Site-Specific Factors 1-6.

Note 3: If laterality of lymph nodes is not specified, assume nodes are ipsilateral. Midline nodes are considered ipsilateral.

Note 4: For head and neck cancers, if lymph nodes are described only as "supraclavicular", try to determine if they are in Level IV (deep to the sternocleidomastoid muscle, in the lower jugular chain) or Level V (in the posterior triangle, inferior to the transverse cervical artery) and code appropriately. If the specific level cannot be determined, consider them as Level V nodes.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | None; no regional lymph node involvement | N0 | NONE | NONE |

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 10 | Single positive ipsilateral regional node: Level I node Submandibular (submaxillary) Submental Level II node Jugulodigastric (subdigastric) Upper deep cervical Upper jugular Level III node Middle deep cervical Mid jugular Cervical, NOS Deep cervical, NOS Internal jugular, NOS Mandibular, NOS Regional lymph node, NOS | * | RN | RN |
| 12 | Single positive ipsilateral regional node: Level IV node Lower deep cervical Lower jugular Level V node Posterior cervical Posterior triangle (spinal accessory and transverse cervical) (upper, middle, and lower corresponding to the levels that define upper, middle, and lower jugular nodes) Level VI node Anterior deep cervical Laterotracheal Paralaryngeal Paratracheal Prelaryngeal Pretracheal Recurrent laryngeal Level VII node Upper mediastinum (for other mediastinal nodes see CS Mets at DX) Other groups Intraparotid Parapharyngeal Periparotid Retropharyngeal Sub-occipital Supraclavicular, NOS (See Note 4) | * | D | D |
| 18 | Stated as N1, no other information | N1 | RN | RN |
| 19 | Stated as N2a, no other information | N2a | RN | RN |
| 20 | Multiple positive ipsilateral nodes listed in code 10 | * | RN | RN |
| 22 | Multiple positive ipsilateral nodes listed in code 12 | * | D | D |
| 29 | Stated as N2b, no other information | N2b | RN | RN |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-------|------|--------|
| 30 | Regional lymph nodes as listed in code 10: Positive ipsilateral node(s), not stated if single or multiple | * | RN | RN |
| 32 | Regional lymph nodes as listed in code 12: Positive ipsilateral node(s), not stated if single or multiple | * | D | D |
| 40 | Regional lymph nodes as listed in code 10: Positive bilateral or contralateral nodes | * | RN | RN |
| 42 | Regional lymph nodes as listed in code 12: Positive bilateral or contralateral nodes | * | D | D |
| 49 | Stated as N2c, no other information | N2c | RN | RN |
| 50 | Regional lymph nodes as listed in code 10: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | RN | RN |
| 52 | Regional lymph nodes as listed in code 12: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | D |
| 60 | Stated as N2, NOS | N2NOS | RN | RN |
| 70 | Stated as N3, no other information | N3 | RN | RN |
| 80 | Lymph nodes, NOS | * | RN | RN |
| 99 | Unknown; not stated Regional lymph node(s) cannot be assessed Not documented in patient record | NX | U | U |

^{*} For codes 10, 12, 20, 22, 30, 32, 40, 42, 49, 50, 52 and 80 ONLY, the N category is assigned based on the value of Site-Specific Factor 1, Size of Lymph Nodes, using the extra table, Lymph Nodes Size Table for this site.

Submandibular Gland CS Reg Nodes Eval SEE STANDARD TABLE

Submandibular Gland Reg LN Pos SEE STANDARD TABLE

Submandibular Gland Reg LN Exam SEE STANDARD TABLE

CS Staging Schemas

Submandibular Gland

CS Mets at DX (Revised: 02/22/2005)

Note: Supraclavicular and transverse cervical lymph nodes are now coded in the CS Lymph Nodes table because they are categorized as N rather than M in AJCC TNM. Any cases coded to 10 or 50 can be reviewed and recoded. The volume of cases affected should be small.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | No; none | M0 | NONE | NONE |
| 10 | Distant lymph node(s) | M1 | D | D |
| 40 | Distant metastases except distant lymph node(s) (code 10) Distant metastasis, NOS Carcinomatosis | M1 | D | D |
| 50 | (10) + (40) Distant lymph node(s) plus other distant metastases | M1 | D | D |
| 99 | Unknown if distant metastasis Distant metastasis cannot be assessed Not documented in patient record | MX | U | U |

Submandibular Gland CS Mets Eval SEE STANDARD TABLE

Submandibular Gland

CS Site-Specific Factor 1 Size of Lymph Nodes (Revised: 08/18/2006)

Note: Code the largest diameter, whether measured clinically or pathologically, of any involved regional lymph node(s). Do not code the size of any nodes coded in CS Mets at DX.

| Code | Description |
|---------|---|
| 000 | No involved regional nodes |
| 001-988 | 001-988 millimeters (code exact size in millimeters) |
| 989 | 989 millimeters or larger |
| 990 | Microscopic focus or foci only, no size of focus given |
| 991 | Described as "less than 1cm" |
| 992 | Described as "less than 2cm" or "greater than 1cm" or "between 1cm and 2cm" |
| 993 | Described as "less than 3cm" or "greater than 2cm" or "between 2cm and 3cm" |
| 994 | Described as "less than 4cm" or "greater than 3cm" or "between 3cm and 4cm" |
| 995 | Described as "less than 5cm" or "greater than 4cm" or "between 4cm and 5cm" |
| 996 | Described as "less than 6cm" or "greater than 5cm" or "between 5cm and 6cm" |
| 997 | Described as "more than 6cm" |

CS Staging Schemas

| Code | Description | |
|------|--|--|
| 999 | Regional lymph node(s) involved, size not stated Unknown if regional lymph node(s) involved Not documented in patient record | |

Submandibular Gland

CS Site-Specific Factor 2 Extracapsular Extension, Lymph Nodes for Head and Neck (Revised: 08/17/2007)

- **Note 1:** Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. Do not code extracapsular extension in any nodes coded in CS Mets at DX in this field.
- **Note 2:** A statement of the presence or absence of extracapsular extension in a pathology report takes priority over clinical assessment. However, if the pathology report contains no statement about extracapsular extension, either positive or negative, the clinical assessment should be coded. If nodes are involved but there is neither a clinical assessment of extranodal extension nor a statement about it in the pathology report, use code 999.
- **Note 3:** According to AJCC (page 24), "Imaging studies showing amorphous spiculated margins of involved nodes or involvement of internodal fat resulting in loss of normal oval-to-round nodal shape strongly suggest extracapsular (extranodal) tumor spread; however, pathologic examination is necessary for documentation of the extent of such disease."

| Code | Description |
|------|---|
| 000 | No extracapsular extension |
| 001 | Extracapsular extension clinically, not assessed pathologically Nodes described as "fixed", not assessed pathologically |
| 005 | Extracapsular extension present pathologically |
| 888 | Not applicable; no lymph node involvement |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Submandibular Gland

CS Site-Specific Factor 3 Levels I-III, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description | |
|------|---|--|
| 000 | No lymph node involvement in Levels I, II, or III | |
| 100 | Level I lymph node(s) involved | |
| 010 | Level II lymph node(s) involved | |
| 001 | Level III lymph node(s) involved | |
| 110 | Level I and II lymph nodes involved | |

CS Staging Schemas

| Code | Description | |
|------|---|--|
| 101 | Level I and III lymph nodes involved | |
| 011 | Level II and III lymph nodes involved | |
| 111 | Level I, II and III lymph nodes involved | |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record | |

Submandibular Gland

CS Site-Specific Factor 4 Levels IV-V and Retropharyngeal Lymph Nodes for Head and

Neck (Revised: 08/21/2006)

| Code | Description | |
|------|---|--|
| 000 | No lymph node involvement in Levels IV or V or retropharyngeal | |
| 100 | Level IV lymph node(s) involved | |
| 010 | Level V lymph node(s) involved | |
| 001 | Retropharyngeal nodes involved | |
| 110 | Level IV and V lymph nodes involved | |
| 101 | Level IV and retropharyngeal nodes involved | |
| 011 | Level V and retropharyngeal nodes involved | |
| 111 | Level IV and V and retropharyngeal lymph nodes involved | |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record | |

CS Staging Schemas

Submandibular Gland

CS Site-Specific Factor 5 Levels VI-VII and Facial Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels VI or VII or facial nodes |
| 100 | Level VI lymph node(s) involved |
| 010 | Level VII lymph node(s) involved |
| 001 | Facial (buccinator, nasolabial) lymph node(s) involved |
| 110 | Level VI and VII lymph nodes involved |
| 101 | Level VI and facial (buccinator, nasolabial) nodes involved |
| 011 | Level VII and facial (buccinator, nasolabial) nodes involved |
| 111 | Level VI and VII and facial (buccinator, nasolabial) lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Submandibular Gland

CS Site-Specific Factor 6 Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description | |
|------|--|--|
| 000 | No parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), or sub-occipital lymph node involvement | |
| 100 | Parapharyngeal lymph node(s) involved | |
| 010 | Parotid (preauricular, periparotid, and/or intraparotid) lymph node(s) involved | |
| 001 | Sub-occipital lymph node(s) involved | |
| 110 | Parapharyngeal and parotid (preauricular, periparotid, and/or intraparotid) lymph nodes involved | |
| 101 | Parapharyngeal and sub-occipital lymph nodes involved | |

CS Staging Schemas

| Code | Description | |
|---|--|--|
| 011 | Parotid (preauricular, periparotid, and/or intraparotid) and sub-occipital lymph nodes involved | |
| 111 | Parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), and sub-occipital lymph nodes involved | |
| Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record | | |

CS Staging Schemas

Other and Unspecified Major Salivary Glands C08.1, C08.8-C08.9

C08.1 Sublingual gland

C08.8 Overlapping lesion of major salivary glands

C08.9 Major salivary gland, NOS

Note: Laterality must be coded for C08.1.

| CS Tumor Size CS Extension CS TS/Ext-Eval CS Lymph Nodes CS Reg Nodes Eval Reg LN Pos Reg LN Exam CS Mets at DX CS Mets Eval | CS Site-Specific Factor 1 - Size of Lymph Nodes CS Site-Specific Factor 2 - Extracapsular Extension, Lymph Nodes for Head and Neck CS Site-Specific Factor 3 - Levels I-III, Lymph Nodes for Head and Neck CS Site-Specific Factor 4 - Levels IV-V and Retropharyngeal Lymph Nodes for Head and Neck CS Site-Specific Factor 5 - Levels VI-VII and Facial Lymph Nodes for Head and Neck CS Site-Specific Factor 6 - Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck | The following tables are available at the collaborative staging website: Histology Exclusion Table AJCC Stage Extension Size Table Lymph Nodes Size Table |
|--|---|---|
|--|---|---|

Other and Unspecified Major Salivary Glands CS Tumor Size SEE STANDARD TABLE

Other and Unspecified Major Salivary Glands

CS Extension (Revised: 08/14/2006)

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | In situ; non-invasive; intraepithelial | Tis | IS | IS |
| 10 | Invasive tumor confined to gland/duct of origin | * | L | L |
| 30 | Localized, NOS | * | L | L |
| 35 | Microscopic extraparenchymal extension ONLY | * | RE | RE |
| 40 | Extension to: Another major salivary gland (parotid, submandibular) Periglandular soft/connective tissue including extraparenchymal extension Skeletal muscle: Digastric Pterygoid Stylohyoid | Т3 | RE | RE |
| 45 | Periosteum of mandible | T4a | RE | RE |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 51 | Mandible Nerves: Facial (7th) Lingual | T4a | RE | RE |
| 60 | Skin | T4a | D | D |
| 62 | External auditory meatus | T4a | D | D |
| 65 | Blood vessel(s): Carotid artery Facial artery or vein Maxillary artery | T4b | RE | RE |
| 71 | Base of skull Skull, NOS | T4b | RE | D |
| 72 | Spinal accessory nerve | T4a | RE | D |
| 79 | Pterygoid plates | T4b | D | D |
| 80 | Further contiguous extension | T4b | D | D |
| 95 | No evidence of primary tumor | Т0 | U | U |
| 99 | Unknown extension Primary tumor cannot be assessed Not documented in patient record | TX | U | U |

^{*} For Extension codes 10, 30, and 35 ONLY, the T category is assigned based on value of CS Tumor Size as shown in the Extension Size Table for this site.

Other and Unspecified Major Salivary Glands CS TS/Ext-Eval SEE STANDARD TABLE

Other and Unspecified Major Salivary Glands

CS Lymph Nodes (Revised: 08/22/2006)

Note 1: For head and neck schemas, this field includes all lymph nodes defined as Levels I-VII and Other by AJCC. The complete definitions are provided in the General Instructions.

Note 2: For head and neck schemas, additional information about lymph nodes (size of involved nodes, extracapsular extension, and levels involved) is coded in Site-Specific Factors 1-6.

Note 3: If laterality of lymph nodes is not specified, assume nodes are ipsilateral. Midline nodes are considered ipsilateral.

Note 4: For head and neck cancers, if lymph nodes are described only as "supraclavicular", try to determine if they are in Level IV (deep to the sternocleidomastoid muscle, in the lower jugular chain) or Level V (in the posterior triangle, inferior to the transverse cervical artery) and code appropriately. If the specific level cannot be determined, consider them as Level V nodes.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | None; no regional lymph node involvement | N0 | NONE | NONE |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 10 | Single positive ipsilateral regional node: Level I node Submandibular (submaxillary) Submental Cervical, NOS Mandibular, NOS Regional lymph node, NOS | * | RN | RN |
| 12 | Single positive ipsilateral regional node: Level II node Upper deep cervical Upper jugular Level III node Middle deep cervical Mid jugular Level IV node Lower deep cervical Lower jugular Level V node Posterior cervical Posterior triangle (spinal accessory and transverse cervical) (upper, middle, and lower corresponding to the levels that define upper, middle, and lower jugular nodes) Level VI node Anterior deep cervical Laterotracheal Paralaryngeal Paratracheal Prelaryngeal Pretracheal Recurrent laryngeal Level VII node Upper mediastinum (for other mediastinal nodes see CS Mets at DX) Other groups Intraparotid Parapharyngeal Periparotid Retropharyngeal Sub-occipital Supraclavicular, NOS (See Note 4) | * | D | D |
| 18 | Stated as N1, no other information | N1 | RN | RN |
| 19 | Stated as N2a, no other information | N2a | RN | RN |
| 20 | Multiple positive ipsilateral nodes listed in code 10 | * | RN | RN |
| 22 | Multiple positive ipsilateral nodes listed in code 12 | * | D | D |
| 29 | Stated as N2b, no other information | N2b | RN | RN |
| 30 | Regional lymph nodes as listed in code 10: Positive ipsilateral node(s), not stated if single or multiple | * | RN | RN |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-------|------|--------|
| 32 | Regional lymph nodes as listed in code 12: Positive ipsilateral node(s), not stated if single or multiple | * | D | D |
| 40 | Regional lymph nodes as listed in code 10: Positive bilateral or contralateral nodes | * | RN | RN |
| 42 | Regional lymph nodes as listed in code 12: Positive bilateral or contralateral nodes | * | D | D |
| 49 | Stated as N2c, no other information | N2c | RN | RN |
| 50 | Regional lymph nodes as listed in code 10: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | RN | RN |
| 52 | Regional lymph nodes as listed in code 12: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | D |
| 60 | Stated as N2, NOS | N2NOS | RN | RN |
| 70 | Stated as N3, no other information | N3 | RN | RN |
| 80 | Lymph nodes, NOS | * | RN | RN |
| 99 | Unknown; not stated Regional lymph node(s) cannot be assessed Not documented in patient record | NX | U | U |

^{*} For codes 10, 12, 20, 22, 30, 32, 40, 42, 49, 50, 52 and 80 ONLY, the N category is assigned based on the value of Site-Specific Factor 1, Size of Lymph Nodes, using the extra table, Lymph Nodes Size Table for this site.

Other and Unspecified Major Salivary Glands CS Reg Nodes Eval SEE STANDARD TABLE

Other and Unspecified Major Salivary Glands Reg LN Pos SEE STANDARD TABLE

Other and Unspecified Major Salivary Glands Reg LN Exam SEE STANDARD TABLE

Other and Unspecified Major Salivary Glands

CS Mets at DX (Revised: 02/22/2005)

Note: Supraclavicular and transverse cervical lymph nodes are now coded in CS Lymph Nodes because they are categorized as N rather than M in AJCC TNM. Any cases coded to 10 or 50 can be reviewed and recoded. The volume of cases affected should be small.

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | No; none | M0 | NONE | NONE |
| 10 | Distant lymph node(s) | M1 | D | D |
| 40 | Distant metastases except distant lymph node(s) (code 10) Distant metastasis, NOS Carcinomatosis | M1 | D | D |
| 50 | (10) + (40) Distant lymph node(s) plus other distant metastases | M1 | D | D |
| 99 | Unknown if distant metastasis Distant metastasis cannot be assessed Not documented in patient record | MX | U | U |

Other and Unspecified Major Salivary Glands CS Mets Eval SEE STANDARD TABLE

Other and Unspecified Major Salivary Glands

CS Site-Specific Factor 1 Size of Lymph Nodes (Revised: 08/18/2006)

Note: Code the largest diameter, whether measured clinically or pathologically, of any involved regional lymph node(s). Do not code the size of any nodes coded in CS Mets at DX.

| Code | Description | |
|---------|--|--|
| 000 | No involved regional nodes | |
| 001-988 | 001-988 millimeters (code exact size in millimeters) | |
| 989 | 989 millimeters or larger | |
| 990 | Microscopic focus or foci only, no size of focus given | |
| 991 | Described as "less than 1cm" | |
| 992 | Described as "less than 2cm" or "greater than 1cm" or "between 1cm and 2cm" | |
| 993 | Described as "less than 3cm" or "greater than 2cm" or "between 2cm and 3cm" | |
| 994 | Described as "less than 4cm" or "greater than 3cm" or "between 3cm and 4cm" | |
| 995 | Described as "less than 5cm" or "greater than 4cm" or "between 4cm and 5cm" | |
| 996 | Described as "less than 6cm" or "greater than 5cm" or "between 5cm and 6cm" | |
| 997 | Described as "more than 6cm" | |
| 999 | Regional lymph node(s) involved, size not stated Unknown if regional lymph node(s) involved Not documented in patient record | |

CS Staging Schemas

Other and Unspecified Major Salivary Glands

CS Site-Specific Factor 2 Extracapsular Extension, Lymph Nodes for Head and Neck (Revised: 08/17/2007)

Note 1: Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. Do not code extracapsular extension in any nodes coded in CS Mets at DX in this field.

Note 2: A statement of the presence or absence of extracapsular extension in a pathology report takes priority over clinical assessment. However, if the pathology report contains no statement about extracapsular extension, either positive or negative, the clinical assessment should be coded. If nodes are involved but there is neither a clinical assessment of extranodal extension nor a statement about it in the pathology report, use code 999.

Note 3: According to AJCC (page 24), "Imaging studies showing amorphous spiculated margins of involved nodes or involvement of internodal fat resulting in loss of normal oval-to-round nodal shape strongly suggest extracapsular (extranodal) tumor spread; however, pathologic examination is necessary for documentation of the extent of such disease."

| Code | Description | |
|------|---|--|
| 000 | No extracapsular extension | |
| 001 | Extracapsular extension clinically, not assessed pathologically Nodes described as "fixed", not assessed pathologically | |
| 005 | Extracapsular extension present pathologically | |
| 888 | Not applicable; no lymph node involvement | |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record | |

Other and Unspecified Major Salivary Glands

CS Site-Specific Factor 3 Levels I-III, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description | |
|------|---|--|
| 000 | No lymph node involvement in Levels I, II, or III | |
| 100 | Level I lymph node(s) involved | |
| 010 | Level II lymph node(s) involved | |
| 001 | Level III lymph node(s) involved | |
| 110 | Level I and II lymph nodes involved | |
| 101 | Level I and III lymph nodes involved | |
| 011 | Level II and III lymph nodes involved | |
| 111 | Level I, II and III lymph nodes involved | |

CS Staging Schemas

| Code | Description |
|------|---|
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Other and Unspecified Major Salivary Glands CS Site-Specific Factor 4 Levels IV-V and Retropharyngeal Lymph Nodes for Head and

Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description | |
|------|---|--|
| 000 | No lymph node involvement in Levels IV or V or retropharyngeal | |
| 100 | Level IV lymph node(s) involved | |
| 010 | Level V lymph node(s) involved | |
| 001 | Retropharyngeal nodes involved | |
| 110 | Level IV and V lymph nodes involved | |
| 101 | Level IV and retropharyngeal nodes involved | |
| 011 | Level V and retropharyngeal nodes involved | |
| 111 | Level IV and V and retropharyngeal lymph nodes involved | |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record | |

Other and Unspecified Major Salivary Glands CS Site-Specific Factor 5 Levels VI-VII and Facial Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description | |
|------|---|--|
| 000 | No lymph node involvement in Levels VI or VII or facial nodes | |
| 100 | Level VI lymph node(s) involved | |
| 010 | Level VII lymph node(s) involved | |

CS Staging Schemas

| Code | Description | |
|------|---|--|
| 001 | Facial (buccinator, nasolabial) lymph node(s) involved | |
| 110 | Level VI and VII lymph nodes involved | |
| 101 | Level VI and facial (buccinator, nasolabial) nodes involved | |
| 011 | Level VII and facial (buccinator, nasolabial) nodes involved | |
| 111 | Level VI and VII and facial (buccinator, nasolabial) lymph nodes involved | |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record | |

Other and Unspecified Major Salivary Glands CS Site-Specific Factor 6 Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description | |
|------|---|--|
| 000 | No parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), or sub-occipital lymph node involvement | |
| 100 | Parapharyngeal lymph node(s) involved | |
| 010 | Parotid (preauricular, periparotid, and/or intraparotid) lymph node(s) involved | |
| 001 | Sub-occipital lymph node(s) involved | |
| 110 | Parapharyngeal and parotid (preauricular, periparotid, and/or intraparotid) lymph nodes involved | |
| 101 | Parapharyngeal and sub-occipital lymph nodes involved | |
| 011 | Parotid (preauricular, periparotid, and/or intraparotid) and sub-occipital lymph nodes involved | |
| 111 | Parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), and sub-occipital lymph nodes involved | |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record | |

Surgery Codes

Parotid and Other Unspecified Glands Parotid Gland C079, Major Salivary Glands C080–C089 (Except for M9750, 9760-9764, 9800-9820, 9826, 9831-9920, 9931-9964, 9980-9989)

Codes

- None; no surgery of primary site; autopsy ONLY
- 10 Local tumor destruction, NOS
 - 11 Photodynamic therapy (PDT)
 - 12 Electrocautery; fulguration (includes use of hot forceps for tumor destruction)
 - 13 Cryosurgery
 - 14 Laser

No specimen sent to pathology from surgical events 10–14

- 20 Local tumor excision, NOS
 - 26 Polypectomy
 - 27 Excisional biopsy

Any combination of 20 or 26-27 WITH

- 21 Photodynamic therapy (PDT)
- 22 Electrocautery
- 23 Cryosurgery
- 24 Laser ablation

[**SEER Note**: Codes 21 to 24 above combine 20 Local tumor excision, 26 Polypectomy or 27 Excisional biopsy with 21 PDT, 22 Electrocautery, 23 Cryosurgery, or 24 Laser ablation]

25 Laser excision

Specimen sent to pathology from surgical events 20–27

[SEER Note: Codes 30-80 include major salivary gland, NOS]

- 30 Less than total parotidectomy, NOS; less than total removal of major salivary gland, NOS
 - 31 Facial nerve spared
 - 32 Facial nerve sacrificed
 - 33 Superficial lobe ONLY
 - 34 Facial nerve spared
 - 35 Facial nerve sacrificed
 - 36 Deep lobe (Total)

[SEER Note: With or without superficial lobe]

- 37 Facial nerve spared
- 38 Facial nerve sacrificed

[**SEER Note**: Codes 40-80 include submandibulectomy; submaxillectomy]

- 40 Total parotidectomy, NOS; total removal of major salivary gland, NOS
 - 41 Facial nerve spared
 - 42 Facial nerve sacrificed
- Radical parotidectomy, NOS; radical removal of major salivary gland, NOS
 - 51 WITHOUT removal of temporal bone
 - WITH removal of temporal bone
 - WITH removal of overlying skin (requires graft or flap coverage)

Surgery Codes

- 80 Parotidectomy, NOS
- 90 Surgery, NOS
- 99 Unknown if surgery performed; death certificate ONLY

$\begin{array}{c} Pharynx,\,Tonsil,\,Oropharynx,\,Hypopharynx,\,Pyriform\,\,Sinus\\ C090\text{-}C148 \end{array}$

Note: For Multiple Primary and Histology Coding Rules: see Head and Neck (pg C-3)

CS Staging Schemas

Tonsil, Oropharynx C09.0-C09.1, C09.8-C09.9, C10.0, C10.2-C10.4, C10.8-C10.9

C09.0 Tonsillar fossa

C09.1 Tonsillar pillar

C09.8 Overlapping lesion of tonsil

C09.9 Tonsil, NOS (excludes lingual tonsil C02.4)

C10.0 Vallecula

C10.2 Lateral wall of oropharynx

C10.3 Posterior wall of oropharynx

C10.4 Branchial cleft (site of neoplasm)

C10.8 Overlapping lesion of oropharynx

C10.9 Oropharynx, NOS

Note 1: Laterality must be coded for C09.0, C09.1, C09.8, and C09.9.

Note 2: AJCC includes base of tongue (C01.9) with oropharynx (C09._, C10._).

| CS Tumor Size | CS Site-Specific Factor 1 - Size | The following tables are |
|-------------------|----------------------------------|--------------------------------|
| CS Extension | of Lymph Nodes | available at the collaborative |
| CS TS/Ext-Eval | CS Site-Specific Factor 2 - | staging website: |
| CS Lymph Nodes | Extracapsular Extension, Lymph | Histology Exclusion Table |
| CS Reg Nodes Eval | Nodes for Head and Neck | AJCC Stage |
| Reg LN Pos | CS Site-Specific Factor 3 - | Extension Size Table |
| Reg LN Exam | Levels I-III, Lymph Nodes for | Lymph Nodes Size Table |
| CS Mets at DX | Head and Neck | • • |
| CS Mets Eval | CS Site-Specific Factor 4 - | |
| | Levels IV-V and Retropharyngeal | |
| | Lymph Nodes for Head and Neck | |
| | CS Site-Specific Factor 5 - | |
| | Levels VI-VII and Facial Lymph | |
| | Nodes for Head and Neck | |
| | CS Site-Specific Factor 6 - | |
| | Parapharyngeal, Parotid, | |
| | Preauricular, and Sub-Occipital | |
| | Lymph Nodes, Lymph Nodes for | |
| | Head and Neck | |

Tonsil, Oropharynx CS Tumor Size SEE STANDARD TABLE

Tonsil, Oropharynx

CS Extension (Revised: 08/15/2006)

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 00 | In situ; noninvasive; intraepithelial | Tis | IS | IS |
| 10 | Invasive tumor confined to one of the following subsites: Anterior wall (including vallecula and lingual (anterior) surface of epiglottis) One lateral wall Posterior wall | * | L | L |
| 20 | Involvement of two or more subsites: Posterior, anterior or lateral wall(s) | * | L | L |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 30 | Localized, NOS | * | L | L |
| 40 | Soft palate, inferior surface including uvula, or soft palate, NOS | * | RE | RE |
| 41 | Hypopharynx NOS Pyriform sinus | * | RE | RE |
| 42 | Soft palate, superior (nasopharyngeal) surface | * | RE | RE |
| 50 | Base of tongue Buccal mucosa (inner cheek) Floor of mouth Gum (gingiva) | * | RE | RE |
| 55 | Any extension coded in 10-50 WITH fixation | * | RE | RE |
| 60 | Prevertebral fascia or muscle Soft tissue of neck | * | RE | RE |
| 62 | Nasopharynx, lateral, or NOS | T4b | RE | RE |
| 65 | Larynx, NOS Medial pterygoid muscle, or pterygoid muscle, NOS Posterior surface of epiglottis | T4a | RE | RE |
| 70 | Deep extrinsic muscles of tongue: Genioglossus Geniohyoid Hyoglossus Mylohyoid Palatoglossus Styloglossus Hard palate Mandible | T4a | D | D |
| 72 | Lateral pterygoid muscle Pterygoid plates | T4b | D | D |
| 75 | Bone of skull | T4b | D | D |
| 76 | Bone | T4b | D | D |
| 77 | Carotid artery | T4b | D | D |
| 80 | Further contiguous extension: Anterior 2/3 of tongue Parotid gland | T4b | D | D |
| 95 | No evidence of primary tumor | T0 | U | U |
| 99 | Unknown extension Primary tumor cannot be assessed Not documented in patient record | TX | U | U |

^{*} For codes 10, 20, 40, 41, 42, 50, 55, and 60 ONLY, the T category is assigned based on the value of CS Tumor Size as shown in the Extension Size Table for this site.

CS Staging Schemas

Tonsil, Oropharynx CS TS/Ext-Eval SEE STANDARD TABLE

Tonsil, Oropharynx

CS Lymph Nodes (Revised: 08/21/2006)

Note 1: For head and neck schemas, this field includes all lymph nodes defined as Levels I-VII and Other by AJCC. The complete definitions are provided in the General Instructions.

Note 2: For head and neck schemas, additional information about lymph nodes (size of involved nodes, extracapsular extension, and levels involved) is coded in Site-Specific Factors 1-6.

Note 3: If laterality of lymph nodes is not specified, assume nodes are ipsilateral. Midline nodes are considered ipsilateral.

Note 4: For head and neck cancers, if lymph nodes are described only as "supraclavicular", try to determine if they are in Level IV (deep to the sternocleidomastoid muscle, in the lower jugular chain) or Level V (in the posterior triangle, inferior to the transverse cervical artery) and code appropriately. If the specific level cannot be determined, consider them as Level V nodes.

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 00 | None; no regional lymph node involvement | N0 | NONE | NONE |
| 10 | Single positive ipsilateral regional node: Level II node Jugulodigastric (subdigastric) Upper deep cervical Upper jugular Level III node Middle deep cervical Mid jugular Level IV node Lower deep cervical Lower jugular Cervical, NOS Deep cervical, NOS Internal jugular, NOS Mandibular Regional lymph node, NOS | * | RN | RN |
| 11 | Single positive ipsilateral regional node: Level I node Submandibular (submaxillary) Submental | * | D | RN |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 12 | Single positive ipsilateral regional node: Level V node Posterior cervical Posterior triangle (spinal accessory and transverse cervical) (upper, middle, and lower corresponding to the levels that define upper, middle, and lower jugular nodes) Level VI node Anterior deep cervical Laterotracheal Paralaryngeal Paratracheal Prelaryngeal Pretracheal Recurrent laryngeal Level VII node Upper mediastinum (for other mediastinal nodes see CS Mets at DX) Other groups Intraparotid Parapharyngeal Periparotid Retropharyngeal Sub-occipital Supraclavicular, NOS (See Note 4) | * | D | D |
| 18 | Stated as N1, no other information | N1 | RN | RN |
| 19 | Stated as N2a, no other information | N2a | RN | RN |
| 20 | Multiple positive ipsilateral nodes listed in code 10 | * | RN | RN |
| 21 | Multiple positive ipsilateral nodes listed in code 11 | * | D | RN |
| 22 | Multiple positive ipsilateral nodes listed in code 12 | * | D | D |
| 29 | Stated as N2b, no other information | N2b | RN | RN |
| 30 | Regional lymph nodes as listed in code 10: Positive ipsilateral node(s), not stated if single or multiple | * | RN | RN |
| 31 | Regional lymph nodes as listed in code 11: Positive ipsilateral node(s), not stated if single or multiple | * | D | RN |
| 32 | Regional lymph nodes as listed in code 12: Positive ipsilateral node(s), not stated if single or multiple | * | D | D |
| 40 | Regional lymph nodes as listed in code 10: Positive bilateral or contralateral nodes | * | RN | RN |
| 41 | Regional lymph nodes as listed in code 11: Positive bilateral or contralateral nodes | * | D | RN |
| 42 | Regional lymph nodes as listed in code 12: Positive bilateral or contralateral nodes | * | D | D |
| 49 | Stated as N2c, no other information | N2c | RN | RN |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-------|------|--------|
| 50 | Regional lymph nodes as listed in code 10: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | RN | RN |
| 51 | Regional lymph nodes as listed in code 11: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | RN |
| 52 | Regional lymph nodes as listed in code 12: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | D |
| 60 | Stated as N2, NOS | N2NOS | RN | RN |
| 70 | Stated as N3, no other information | N3 | RN | RN |
| 80 | Lymph nodes, NOS, no other information | * | RN | RN |
| 99 | Unknown; not stated Regional lymph node(s) cannot be assessed Not documented in patient record | NX | U | U |

^{*} For codes 10-12, 20-22, 30-32, 40-42, 50-52, and 80 ONLY, the N category is assigned based on the value of Site-Specific Factor 1, Size of Lymph Nodes, using the extra table, Lymph Nodes Size Table for this site.

Tonsil, Oropharynx CS Reg Nodes Eval SEE STANDARD TABLE

Tonsil, Oropharynx Reg LN Pos SEE STANDARD TABLE

Tonsil, Oropharynx Reg LN Exam SEE STANDARD TABLE

Tonsil, Oropharynx

CS Mets at DX (Revised: 08/14/2006)

Note: Supraclavicular and transverse cervical lymph nodes are now coded in CS Lymph Nodes because they are categorized as N rather than M in AJCC TNM. Any cases coded to 10 or 50 can be reviewed and recoded. The volume of cases affected should be small.

| Code | Description | TNM | SS77 | SS2000 |
|------|-------------|-----|-------------|--------|
| 00 | No; none | M0 | NONE | NONE |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 10 | Distant lymph node(s) Mediastinal Distant lymph node(s), NOS | M1 | D | D |
| 40 | Distant metastases except distant lymph node(s) (code 10) Distant metastasis, NOS Carcinomatosis | M1 | D | D |
| 50 | (10) + (40) Distant lymph node(s) plus other distant metastases | M1 | D | D |
| 99 | Unknown if distant metastasis Distant metastasis cannot be assessed Not documented in patient record | MX | U | U |

Tonsil, Oropharynx **CS Mets Eval SEE STANDARD TABLE**

Tonsil, Oropharynx

CS Site-Specific Factor 1 Size of Lymph Nodes (Revised: 08/18/2006)

Note: Code the largest diameter, whether measured clinically or pathologically, of any involved regional lymph

node(s). Do not code the size of any nodes coded in CS Mets at DX.

| Code | Description |
|---------|--|
| 000 | No involved regional nodes |
| 001-988 | 001-988 millimeters (code exact size in millimeters) |
| 989 | 989 millimeters or larger |
| 990 | Microscopic focus or foci only, no size of focus given |
| 991 | Described as "less than 1cm" |
| 992 | Described as "less than 2cm" or "greater than 1cm" or "between 1cm and 2cm" |
| 993 | Described as "less than 3cm" or "greater than 2cm" or "between 2cm and 3cm" |
| 994 | Described as "less than 4cm" or "greater than 3cm" or "between 3cm and 4cm" |
| 995 | Described as "less than 5cm" or "greater than 4cm" or "between 4cm and 5cm" |
| 996 | Described as "less than 6cm" or "greater than 5cm" or "between 5cm and 6cm" |
| 997 | Described as "more than 6cm" |
| 999 | Regional lymph node(s) involved, size not stated Unknown if regional lymph node(s) involved Not documented in patient record |

CS Staging Schemas

Tonsil, Oropharynx

CS Site-Specific Factor 2 Extracapsular Extension, Lymph Nodes for Head and Neck (Revised: 08/17/2007)

Note 1: Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. Do not code extracapsular extension in any nodes coded in CS Mets at DX in this field.

Note 2: A statement of the presence or absence of extracapsular extension in a pathology report takes priority over clinical assessment. However, if the pathology report contains no statement about extracapsular extension, either positive or negative, the clinical assessment should be coded. If nodes are involved but there is neither a clinical assessment of extranodal extension nor a statement about it in the pathology report, use code 999.

Note 3: According to AJCC (page 24), "Imaging studies showing amorphous spiculated margins of involved nodes or involvement of internodal fat resulting in loss of normal oval-to-round nodal shape strongly suggest extracapsular (extranodal) tumor spread; however, pathologic examination is necessary for documentation of the extent of such disease."

| Code | Description |
|------|---|
| 000 | No extracapsular extension |
| 001 | Extracapsular extension clinically, not assessed pathologically Nodes described as "fixed", not assessed pathologically |
| 005 | Extracapsular extension present pathologically |
| 888 | Not applicable; no lymph node involvement |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Tonsil, Oropharynx

CS Site-Specific Factor 3 Levels I-III, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels I, II, or III |
| 100 | Level I lymph node(s) involved |
| 010 | Level II lymph node(s) involved |
| 001 | Level III lymph node(s) involved |
| 110 | Level I and II lymph nodes involved |
| 101 | Level I and III lymph nodes involved |
| 011 | Level II and III lymph nodes involved |
| 111 | Level I, II and III lymph nodes involved |

CS Staging Schemas

| Code | Description |
|------|---|
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Tonsil, Oropharynx

CS Site-Specific Factor 4 Levels IV-V and Retropharyngeal Lymph Nodes for Head and

Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels IV or V or retropharyngeal |
| 100 | Level IV lymph node(s) involved |
| 010 | Level V lymph node(s) involved |
| 001 | Retropharyngeal nodes involved |
| 110 | Level IV and V lymph nodes involved |
| 101 | Level IV and retropharyngeal nodes involved |
| 011 | Level V and retropharyngeal nodes involved |
| 111 | Level IV and V and retropharyngeal lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Tonsil, Oropharynx

CS Site-Specific Factor 5 Levels VI-VII and Facial Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels VI or VII or facial nodes |
| 100 | Level VI lymph node(s) involved |
| 010 | Level VII lymph node(s) involved |

CS Staging Schemas

| Code | Description |
|------|---|
| 001 | Facial (buccinator, nasolabial) lymph node(s) involved |
| 110 | Level VI and VII lymph nodes involved |
| 101 | Level VI and facial (buccinator, nasolabial) nodes involved |
| 011 | Level VII and facial (buccinator, nasolabial) nodes involved |
| 111 | Level VI and VII and facial (buccinator, nasolabial) lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Tonsil, Oropharynx

CS Site-Specific Factor 6 Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|---|
| 000 | No parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), or sub-occipital lymph node involvement |
| 100 | Parapharyngeal lymph node(s) involved |
| 010 | Parotid (preauricular, periparotid, and/or intraparotid) lymph node(s) involved |
| 001 | Sub-occipital lymph node(s) involved |
| 110 | Parapharyngeal and parotid (preauricular, periparotid, and/or intraparotid) lymph nodes involved |
| 101 | Parapharyngeal and sub-occipital lymph nodes involved |
| 011 | Parotid (preauricular, periparotid, and/or intraparotid) and sub-occipital lymph nodes involved |
| 111 | Parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), and sub-occipital lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Anterior Surface of Epiglottis C10.1

C10.1 Anterior surface of epiglottis

Note: AJCC includes lingual (anterior) surface of epiglottis (C10.1) with larynx. SEER Extent of Disease included it

with oropharynx.

| CS Tumor Size | CS Site-Specific Factor 1 - Size | The following tables are |
|-------------------|----------------------------------|--------------------------------|
| CS Extension | of Lymph Nodes | available at the collaborative |
| CS TS/Ext-Eval | CS Site-Specific Factor 2 - | staging website: |
| CS Lymph Nodes | Extracapsular Extension, Lymph | Histology Exclusion Table |
| CS Reg Nodes Eval | Nodes for Head and Neck | AJCC Stage |
| Reg LN Pos | CS Site-Specific Factor 3 - | Lymph Nodes Size Table |
| Reg LN Exam | Levels I-III, Lymph Nodes for | |
| CS Mets at DX | Head and Neck | |
| CS Mets Eval | CS Site-Specific Factor 4 - | |
| | Levels IV-V and Retropharyngeal | |
| | Lymph Nodes for Head and Neck | |
| | CS Site-Specific Factor 5 - | |
| | Levels VI-VII and Facial Lymph | |
| | Nodes for Head and Neck | |
| | CS Site-Specific Factor 6 - | |
| | Parapharyngeal, Parotid, | |
| | Preauricular, and Sub-Occipital | |
| | Lymph Nodes, Lymph Nodes for | |
| | Head and Neck | |

Anterior Surface of Epiglottis CS Tumor Size SEE STANDARD TABLE

Anterior Surface of Epiglottis

CS Extension (Revised: 05/07/2004)

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | In situ; noninvasive; intraepithelial | Tis | IS | IS |
| 10 | Invasive tumor confined to anterior surface of epiglottis with normal vocal cord mobility | Т1 | L | L |
| 20 | Mucosa of adjacent subsite(s) of oropharynx | T2 | L | L |
| 30 | Localized, NOS | T1 | L | L |
| 31 | Vallecula without fixation of larynx | Т2 | L | L |
| 32 | Mucosa of adjacent subsite(s) of supraglottis (including posterior surface of epiglottis) without fixation of larynx | Т2 | RE | RE |
| 33 | Larynx, glottic or NOS, without fixation of larynx | T2 | RE | RE |
| 34 | Pyriform sinus, medial wall or NOS, without fixation of larynx | T2 | RE | RE |
| 35 | Mucosa of base of tongue without fixation of larynx | T2 | RE | RE |
| 36 | Any of (10) to (35) with vocal cord fixation | Т3 | RE | RE |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 37 | Paraglottic space Pre-epiglottic tissues | Т3 | RE | RE |
| 38 | Minor thyroid cartilage erosion (inner cortex) (see also code 67) | Т3 | D | D |
| 39 | Hypopharynx, NOS Postcricoid area Pyriform sinus except medial wall (see code 34) | Т3 | RE | RE |
| 43 | (38) + (39) | Т3 | D | D |
| 45 | Soft palate, inferior surface including uvula, or soft palate, NOS | T4a | RE | RE |
| 47 | Nasopharynx, NOS Soft palate, superior (nasopharyngeal) surface | T4a | RE | RE |
| 50 | Base of tongue, except mucosa (see code 35) Buccal mucosa (inner cheek) Floor of mouth Gum (gingiva) | T4a | RE | RE |
| 62 | Soft tissues of neck | T4a | RE | RE |
| 65 | Pterygoid muscle | T4a | RE | RE |
| 66 | [(38) or (43)] + any of [(45) to (65)] | T4a | D | D |
| 67 | Invasion through thyroid cartilage (see also code 38) Thyroid cartilage, NOS | T4a | D | D |
| 68 | Trachea | T4a | D | D |
| 69 | Esophagus Strap muscles Thyroid | T4a | D | D |
| 70 | Extrinsic muscles of tongue: Genioglossus Geniohyoid Hyoglossus Mylohyoid Palatoglossus Styloglossus | T4a | D | D |
| 75 | Prevertebral fascia or muscle Prevertebral space | T4b | RE | RE |
| 77 | (75) + any of [(66) to (70)] | T4b | D | D |
| 80 | Further contiguous extension, including: Anterior 2/3 of tongue Bone Encases carotid artery Hard palate Mandible Mediastinal structures Parotid gland | T4b | D | D |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 95 | No evidence of primary tumor | Т0 | U | U |
| 99 | Unknown extension Primary tumor cannot be assessed Not documented in patient record | TX | U | U |

Anterior Surface of Epiglottis CS TS/Ext-Eval SEE STANDARD TABLE

Anterior Surface of Epiglottis

CS Lymph Nodes (Revised: 08/21/2006)

Note 1: For head and neck schemas, this field includes all lymph nodes defined as Levels I-VII and Other by AJCC. The complete definitions are provided in the General Instructions.

Note 2: For head and neck schemas, additional information about lymph nodes (size of involved nodes, extracapsular extension, and levels involved) is coded in Site-Specific Factors 1-6.

Note 3: If laterality of lymph nodes is not specified, assume nodes are ipsilateral. Midline nodes are considered ipsilateral.

Note 4: For head and neck cancers, if lymph nodes are described only as "supraclavicular", try to determine if they are in Level IV (deep to the sternocleidomastoid muscle, in the lower jugular chain) or Level V (in the posterior triangle, inferior to the transverse cervical artery) and code appropriately. If the specific level cannot be determined, consider them as Level V nodes.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | None; no regional lymph node involvement | N0 | NONE | NONE |
| 10 | Single positive ipsilateral regional node: Level II node Jugulodigastric (subdigastric) Upper deep cervical Upper jugular Level III node Middle deep cervical Mid jugular Level IV node Lower deep cervical Lower jugular Retropharyngeal Cervical, NOS Deep cervical, NOS Internal jugular, NOS Mandibular Regional lymph node, NOS | * | RN | RN |
| 11 | Single positive ipsilateral regional node: Level I node Submandibular (submaxillary) Submental | * | D | RN |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 12 | Single positive ipsilateral regional node: Level V node Posterior cervical Posterior triangle (spinal accessory and transverse cervical) (upper, middle, and lower corresponding to the levels that define upper, middle, and lower jugular nodes) Level VI node Anterior deep cervical Laterotracheal Paralaryngeal Paratracheal Prelaryngeal Pretracheal Recurrent laryngeal Level VII node Upper mediastinum (for other mediastinal nodes see CS Mets at DX) Other groups Intraparotid Parapharyngeal Periparotid Retropharyngeal Sub-occipital Supraclavicular, NOS (See Note 4) | * | D | D |
| 18 | Stated as N1, no other information | N1 | RN | RN |
| 19 | Stated as N2a, no other information | N2a | RN | RN |
| 20 | Multiple positive ipsilateral nodes listed in code 10 | * | RN | RN |
| 21 | Multiple positive ipsilateral nodes listed in code 11 | * | D | RN |
| 22 | Multiple positive ipsilateral nodes listed in code 12 | * | D | D |
| 29 | Stated as N2b, no other information | N2b | RN | RN |
| 30 | Regional lymph nodes as listed in code 10: Positive ipsilateral node(s), not stated if single or multiple | * | RN | RN |
| 31 | Regional lymph nodes as listed in code 11: Positive ipsilateral node(s), not stated if single or multiple | * | D | RN |
| 32 | Regional lymph nodes as listed in code 12: Positive ipsilateral node(s), not stated if single or multiple | * | D | D |
| 40 | Regional lymph nodes as listed in code 10: Positive bilateral or contralateral nodes | * | RN | RN |
| 41 | Regional lymph nodes as listed in code 11: Positive bilateral or contralateral nodes | * | D | RN |
| 42 | Regional lymph nodes as listed in code 12: Positive bilateral or contralateral nodes | * | D | D |
| 49 | Stated as N2c, no other information | N2c | RN | RN |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-------|------|--------|
| 50 | Regional lymph nodes as listed in code 10: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | RN | RN |
| 51 | Regional lymph nodes as listed in code 11: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | RN |
| 52 | Regional lymph nodes as listed in code 12: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | D |
| 60 | Stated as N2, NOS | N2NOS | RN | RN |
| 70 | Stated as N3, no other information | N3 | RN | RN |
| 80 | Lymph nodes, NOS, no other information | * | RN | RN |
| 99 | Unknown; not stated Regional lymph nodes cannot be assessed Not documented in patient record | NX | U | U |

^{*} For codes 10-12, 20-22, 30-32, 40-42, 50-52, and 80 ONLY, the N category is assigned based on the value of Site-Specific Factor 1, Size of Lymph nodes, using the extra table, Lymph Nodes Size Table for this site.

Anterior Surface of Epiglottis CS Reg Nodes Eval SEE STANDARD TABLE

Anterior Surface of Epiglottis Reg LN Pos SEE STANDARD TABLE

Anterior Surface of Epiglottis Reg LN Exam SEE STANDARD TABLE

Anterior Surface of Epiglottis

CS Mets at DX (Revised: 02/05/2007)

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | No; none | M0 | NONE | NONE |
| 10 | Distant lymph node(s), including mediastinal | M1 | D | D |
| 40 | Distant metastases except distant lymph node(s) (code 10) Distant metastasis, NOS Carcinomatosis | M1 | D | D |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 50 | (10) + (40) (Distant lymph node(s) plus other distant metastases) | M1 | D | D |
| 99 | Unknown if distant metastasis Distant metastasis cannot be assessed Not documented in patient record | MX | U | U |

Anterior Surface of Epiglottis CS Mets Eval SEE STANDARD TABLE

Anterior Surface of Epiglottis

CS Site-Specific Factor 1 Size of Lymph Nodes (Revised: 08/18/2006)

Note: Code the largest diameter, whether measured clinically or pathologically, of any involved regional lymph node(s). Do not code the size of any nodes coded in CS Mets at DX.

| Code | Description |
|---------|--|
| 000 | No involved regional nodes |
| 001-988 | 001-988 millimeters (code exact size in millimeters) |
| 989 | 989 millimeters or larger |
| 990 | Microscopic focus or foci only, no size of focus given |
| 991 | Described as "less than 1cm" |
| 992 | Described as "less than 2cm" or "greater than 1cm" or "between 1cm and 2cm" |
| 993 | Described as "less than 3cm" or "greater than 2cm" or "between 2cm and 3cm" |
| 994 | Described as "less than 4cm" or "greater than 3cm" or "between 3cm and 4cm" |
| 995 | Described as "less than 5cm" or "greater than 4cm" or "between 4cm and 5cm" |
| 996 | Described as "less than 6cm" or "greater than 5cm" or "between 5cm and 6cm" |
| 997 | Described as "more than 6cm" |
| 999 | Regional lymph node(s) involved, size not stated Unknown if regional lymph node(s) involved Not documented in patient record |

Anterior Surface of Epiglottis

CS Site-Specific Factor 2 Extracapsular Extension, Lymph Nodes for Head and Neck (Revised: 08/17/2007)

Note 1: Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. Do not code extracapsular extension in any nodes coded in CS Mets at DX in this field.

Note 2: A statement of the presence or absence of extracapsular extension in a pathology report takes priority over clinical assessment. However, if the pathology report contains no statement about extracapsular extension, either positive or negative, the clinical assessment should be coded. If nodes are involved but there is neither a clinical assessment of extranodal extension nor a statement about it in the pathology report, use code 999.

CS Staging Schemas

Note 3: According to AJCC (page 24), "Imaging studies showing amorphous spiculated margins of involved nodes or involvement of internodal fat resulting in loss of normal oval-to-round nodal shape strongly suggest extracapsular (extranodal) tumor spread; however, pathologic examination is necessary for documentation of the extent of such disease."

| Code | Description | | | |
|------|---|--|--|--|
| 000 | No extracapsular extension | | | |
| 001 | Extracapsular extension clinically, not assessed pathologically Nodes described as "fixed", not assessed pathologically | | | |
| 005 | Extracapsular extension present pathologically | | | |
| 888 | Not applicable; no lymph node involvement | | | |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record | | | |

Anterior Surface of Epiglottis

CS Site-Specific Factor 3 Levels I-III, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels I, II, or III |
| 100 | Level I lymph node(s) involved |
| 010 | Level II lymph node(s) involved |
| 001 | Level III lymph node(s) involved |
| 110 | Level I and II lymph nodes involved |
| 101 | Level I and III lymph nodes involved |
| 011 | Level II and III lymph nodes involved |
| 111 | Level I, II and III lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Anterior Surface of Epiglottis

CS Site-Specific Factor 4 Levels IV-V and Retropharyngeal Lymph Nodes for Head and

Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels IV or V or retropharyngeal |
| 100 | Level IV lymph node(s) involved |
| 010 | Level V lymph node(s) involved |
| 001 | Retropharyngeal nodes involved |
| 110 | Level IV and V lymph nodes involved |
| 101 | Level IV and retropharyngeal nodes involved |
| 011 | Level V and retropharyngeal nodes involved |
| 111 | Level IV and V and retropharyngeal lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Anterior Surface of Epiglottis

CS Site-Specific Factor 5 Levels VI-VII and Facial Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description | | | |
|------|---|--|--|--|
| 000 | No lymph node involvement in Levels VI or VII or facial nodes | | | |
| 100 | Level VI lymph node(s) involved | | | |
| 010 | Level VII lymph node(s) involved | | | |
| 001 | Facial (buccinator, nasolabial) lymph node(s) involved | | | |
| 110 | Level VI and VII lymph nodes involved | | | |
| 101 | Level VI and facial (buccinator, nasolabial) nodes involved | | | |
| 011 | Level VII and facial (buccinator, nasolabial) nodes involved | | | |

CS Staging Schemas

| Code | Description |
|------|---|
| 111 | Level VI and VII and facial (buccinator, nasolabial) lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Anterior Surface of Epiglottis

CS Site-Specific Factor 6 Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description | | | |
|------|---|--|--|--|
| 000 | No parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), or sub-occipital lymph node involvement | | | |
| 100 | Parapharyngeal lymph node(s) involved | | | |
| 010 | Parotid (preauricular, periparotid, and/or intraparotid) lymph node(s) involved | | | |
| 001 | Sub-occipital lymph node(s) involved | | | |
| 110 | Parapharyngeal and parotid (preauricular, periparotid, and/or intraparotid) lymph nodes involved | | | |
| 101 | Parapharyngeal and sub-occipital lymph nodes involved | | | |
| 011 | Parotid (preauricular, periparotid, and/or intraparotid) and sub-occipital lymph nodes involved | | | |
| 111 | Parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), and sub-occipital lymph nodes involved | | | |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record | | | |

CS Staging Schemas

Nasopharynx

C11.0-C11.3, C11.8-C11.9

- C11.0 Superior wall of nasopharynx
- C11.1 Posterior wall of nasopharynx
- C11.2 Lateral wall of nasopharynx
- C11.3 Anterior wall of nasopharynx
- C11.8 Overlapping lesion of nasopharynx
- C11.9 Nasopharynx, NOS

| CS Tumor Size CS Extension CS TS/Ext-Eval CS Lymph Nodes CS Reg Nodes Eval Reg LN Pos Reg LN Exam CS Mets at DX CS Mets Eval | CS Site-Specific Factor 1 - Size of Lymph Nodes CS Site-Specific Factor 2 - Extracapsular Extension, Lymph Nodes for Head and Neck CS Site-Specific Factor 3 - Levels I-III, Lymph Nodes for Head and Neck CS Site-Specific Factor 4 - Levels IV-V and Retropharyngeal Lymph Nodes for Head and Neck CS Site-Specific Factor 5 - Levels VI-VII and Facial Lymph Nodes for Head and Neck CS Site-Specific Factor 6 - Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck | The following tables are available at the collaborative staging website: Histology Exclusion Table AJCC Stage Lymph Nodes Size Table |
|--|---|--|
|--|---|--|

Nasopharynx CS Tumor Size SEE STANDARD TABLE

Nasopharynx

CS Extension (Revised: 03/17/2004)

Note: Parapharyngeal involvement denotes postero-lateral infiltration of tumor beyond the pharyngobasilar fascia. Involvement of the masticator space denotes extension of tumor beyond the anterior surface of the lateral pterygoid muscle, or lateral extension beyond the postero-lateral wall of the maxillary antrum, pterygo-maxillary fissure.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | In situ; noninvasive; intraepithelial | Tis | IS | IS |
| 10 | Invasive tumor confined to one of the following subsites: Inferior wall (superior surface of soft palate) One lateral wall Posterior superior wall (vault) | T1 | L | L |
| 20 | Involvement of two or more subsites: Lateral wall extending into eustachian tube/middle ear Posterior, inferior, or lateral wall(s) | T1 | L | L |
| 30 | Confined to nasopharynx Localized, NOS | T1 | L | L |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 40 | Oropharynx Soft palate, inferior surface | T2a | RE | RE |
| 50 | Nasal cavity | T2a | RE | RE |
| 55 | Any extension coded in 10-50 WITH fixation or tumor Described only as FIXED | Т4 | RE | RE |
| 56 | Any extension coded in 10-50 WITH parapharyngeal extension | T2b | RE | RE |
| 57 | Hard palate | T4 | D | RE |
| 58 | Pterygopalatine fossa | T4 | RE | RE |
| 60 | Bone, including skull | Т3 | RE | RE |
| 62 | Paranasal sinus | Т3 | D | RE |
| 65 | Orbit | T4 | RE | D |
| 70 | Brain Cranial nerves Hypopharynx Infratemporal fossa Orbit Intracranial extension, NOS | T4 | D | D |
| 75 | Masticator space | T4 | D | D |
| 80 | Further contiguous extension Soft tissues of the neck | Т4 | D | D |
| 95 | No evidence of primary tumor | T0 | U | U |
| 99 | Unknown extension Primary tumor cannot be assessed Not documented in patient record | TX | U | U |

Nasopharynx CS TS/Ext-Eval SEE STANDARD TABLE

Nasopharynx

CS Lymph Nodes (Revised: 08/21/2006)

Note 1: For head and neck schemas, this field includes all lymph nodes defined as Levels I-VII and Other by AJCC. The complete definitions are provided in the General Instructions.

Note 2: For head and neck schemas, additional information about lymph nodes (size of involved nodes, extracapsular extension, and levels involved) is coded in Site-Specific Factors 1-6.

Note 3: If laterality of lymph nodes is not specified, assume nodes are ipsilateral. Midline nodes are considered ipsilateral.

CS Staging Schemas

Note 4: For head and neck cancers, if lymph nodes are described only as "supraclavicular", try to determine if they are in Level IV (deep to the sternocleidomastoid muscle, in the lower jugular chain) or Level V (in the posterior triangle, inferior to the transverse cervical artery) and code appropriately. If the specific level cannot be determined, consider them as Level V nodes.

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 00 | None; no regional lymph node involvement | N0 | NONE | NONE |
| 10 | Single positive ipsilateral regional node: Level II node Jugulodigastric (subdigastric) Upper deep cervical Upper jugular Level III node Middle deep cervical Mid jugular Level IV node Lower deep cervical Lower jugular Retropharyngeal Cervical, NOS Deep cervical, NOS Internal jugular, NOS Mandibular Regional lymph node, NOS | * | RN | RN |
| 11 | Single positive ipsilateral regional node: Level I node Submandibular (submaxillary) Submental | * | D | RN |
| 12 | Single positive ipsilateral regional node: Level V node Posterior cervical Posterior triangle (spinal accessory and transverse cervical) (upper, middle, and lower corresponding to the levels that define upper, middle, and lower jugular nodes) Level VI node Anterior deep cervical Laterotracheal Paralaryngeal Paratracheal Prelaryngeal Pretracheal Recurrent laryngeal Level VII node Upper mediastinum (for other mediastinal nodes see CS Mets at DX) Other groups Intraparotid Parapharyngeal Periparotid Retropharyngeal Sub-occipital Supraclavicular fossa | * | D | D |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-------|------|--------|
| 18 | Stated as N1, no other information | N1 | RN | RN |
| 20 | Multiple positive ipsilateral nodes listed in code 10 | * | RN | RN |
| 21 | Multiple positive ipsilateral nodes listed in code 11 | * | D | RN |
| 22 | Multiple positive ipsilateral nodes listed in code 12 | * | D | D |
| 30 | Regional lymph nodes as listed in code 10: Positive ipsilateral node(s), not stated if single or multiple | * | RN | RN |
| 31 | Regional lymph nodes as listed in code 11: Positive ipsilateral node(s), not stated if single or multiple | * | D | RN |
| 32 | Regional lymph nodes as listed in code 12: Positive ipsilateral node(s), not stated if single or multiple | * | D | D |
| 40 | Regional lymph nodes as listed in code 10: Positive bilateral or contralateral nodes | * | RN | RN |
| 41 | Regional lymph nodes as listed in code 11: Positive bilateral or contralateral nodes | * | D | RN |
| 42 | Regional lymph nodes as listed in code 12: Positive bilateral or contralateral nodes | * | D | D |
| 50 | Regional lymph nodes as listed in code 10: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | RN | RN |
| 51 | Regional lymph nodes as listed in code 11: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | RN |
| 52 | Regional lymph nodes as listed in code 12: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | D |
| 60 | Stated as N2, no other information | N2 | RN | RN |
| 70 | Stated as N3, NOS | N3NOS | RN | RN |
| 75 | Regional lymph nodes in the supraclavicular fossa: Inferior deep cervical (scalene) Spinal accessory (posterior cervical) Supraclavicular (transverse cervical) (See Note 4) | N3b | D | D |
| 80 | Lymph nodes, NOS, no other information | * | RN | RN |
| 99 | Unknown; not stated Regional lymph nodes cannot be assessed Not documented in patient record | NX | U | U |
| | | | | |

^{*} For codes 10-12, 20-22, 30-32, 40-42, 50-52, and 80 ONLY, the N category is assigned based on the value of Site-Specific Factor 1, Size of Lymph Nodes, using the extra table, Lymph Nodes Size Table, for this site.

CS Staging Schemas

Nasopharynx CS Reg Nodes Eval SEE STANDARD TABLE

Nasopharynx Reg LN Pos SEE STANDARD TABLE

Nasopharynx Reg LN Exam SEE STANDARD TABLE

Nasopharynx

CS Mets at DX (Revised: 08/15/2006)

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | No; none | M0 | NONE | NONE |
| 10 | Distant lymph node(s) Mediastinal Distant lymph nodes, NOS | M1 | D | D |
| 40 | Distant metastases except distant lymph node(s) (code 10) Distant metastasis, NOS Carcinomatosis | M1 | D | D |
| 50 | (10) + (40) Distant lymph node(s) plus other distant metastases | M1 | D | D |
| 99 | Unknown if distant metastasis Distant metastasis cannot be assessed Not documented in patient record | MX | U | U |

Nasopharynx CS Mets Eval SEE STANDARD TABLE

Nasopharynx

CS Site-Specific Factor 1 Size of Lymph Nodes (Revised: 08/18/2006)

Note: Code the largest diameter, whether measured clinically or pathologically, of any involved regional lymph node(s). Do not code the size of any nodes coded in CS Mets at DX.

| Code | Description |
|---------|--|
| 000 | No involved regional nodes |
| 001-988 | 001-988 millimeters (code exact size in millimeters) |
| 989 | 989 millimeters or larger |
| 990 | Microscopic focus or foci only, no size of focus given |

CS Staging Schemas

| Code | Description |
|------|--|
| 991 | Described as "less than 1cm" |
| 992 | Described as "less than 2cm" or "greater than 1cm" or "between 1cm and 2cm" |
| 993 | Described as "less than 3cm" or "greater than 2cm" or "between 2cm and 3cm" |
| 994 | Described as "less than 4cm" or "greater than 3cm" or "between 3cm and 4cm" |
| 995 | Described as "less than 5cm" or "greater than 4cm" or "between 4cm and 5cm" |
| 996 | Described as "less than 6cm" or "greater than 5cm" or "between 5cm and 6cm" |
| 997 | Described as "more than 6cm" |
| 999 | Regional lymph node(s) involved, size not stated Unknown if regional lymph node(s) involved Not documented in patient record |

Nasopharynx

CS Site-Specific Factor 2 Extracapsular Extension, Lymph Nodes for Head and Neck (Revised: 08/17/2007)

Note 1: Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. Do not code extracapsular extension in any nodes coded in CS Mets at DX in this field.

Note 2: A statement of the presence or absence of extracapsular extension in a pathology report takes priority over clinical assessment. However, if the pathology report contains no statement about extracapsular extension, either positive or negative, the clinical assessment should be coded. If nodes are involved but there is neither a clinical assessment of extranodal extension nor a statement about it in the pathology report, use code 999.

Note 3: According to AJCC (page 24), "Imaging studies showing amorphous spiculated margins of involved nodes or involvement of internodal fat resulting in loss of normal oval-to-round nodal shape strongly suggest extracapsular (extranodal) tumor spread; however, pathologic examination is necessary for documentation of the extent of such disease."

| Code | Description |
|------|---|
| 000 | No extracapsular extension |
| 001 | Extracapsular extension clinically, not assessed pathologically Nodes described as "fixed", not assessed pathologically |
| 005 | Extracapsular extension present pathologically |
| 888 | Not applicable; no lymph node involvement |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Nasopharynx

CS Site-Specific Factor 3 Levels I-III, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels I, II, or III |
| 100 | Level I lymph node(s) involved |
| 010 | Level II lymph node(s) involved |
| 001 | Level III lymph node(s) involved |
| 110 | Level I and II lymph nodes involved |
| 101 | Level I and III lymph nodes involved |
| 011 | Level II and III lymph nodes involved |
| 111 | Level I, II and III lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Nasopharynx

CS Site-Specific Factor 4 Levels IV-V and Retropharyngeal Lymph Nodes for Head and

Neck (Revised: 08/21/2006)

| Code | Description |
|------|--|
| 000 | No lymph node involvement in Levels IV or V or retropharyngeal |
| 100 | Level IV lymph node(s) involved |
| 010 | Level V lymph node(s) involved |
| 001 | Retropharyngeal nodes involved |
| 110 | Level IV and V lymph nodes involved |
| 101 | Level IV and retropharyngeal nodes involved |
| 011 | Level V and retropharyngeal nodes involved |

CS Staging Schemas

| Code | Description |
|------|---|
| 111 | Level IV and V and retropharyngeal lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Nasopharynx

CS Site-Specific Factor 5 Levels VI-VII and Facial Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels VI or VII or facial nodes |
| 100 | Level VI lymph node(s) involved |
| 010 | Level VII lymph node(s) involved |
| 001 | Facial (buccinator, nasolabial) lymph node(s) involved |
| 110 | Level VI and VII lymph nodes involved |
| 101 | Level VI and facial (buccinator, nasolabial) nodes involved |
| 011 | Level VII and facial (buccinator, nasolabial) nodes involved |
| 111 | Level VI and VII and facial (buccinator, nasolabial) lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Nasopharynx

CS Site-Specific Factor 6 Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|--|
| 000 | No parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), or sub-occipital lymph node involvement |

CS Staging Schemas

| Code | Description | |
|------|---|--|
| 100 | Parapharyngeal lymph node(s) involved | |
| 010 | Parotid (preauricular, periparotid, and/or intraparotid) lymph node(s) involved | |
| 001 | Sub-occipital lymph node(s) involved | |
| 110 | Parapharyngeal and parotid (preauricular, periparotid, and/or intraparotid) lymph nodes involved | |
| 101 | Parapharyngeal and sub-occipital lymph nodes involved | |
| 011 | Parotid (preauricular, periparotid, and/or intraparotid) and sub-occipital lymph nodes involved | |
| 111 | Parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), and sub-occipital lymph nodes involved | |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record | |

CS Staging Schemas

Pyriform Sinus, Hypopharynx, Laryngopharynx C12.9, C13.0-C13.2, C13.8-C13.9

C12.9 Pyriform sinus

C13.0 Postcricoid region

C13.1 Hypopharyngeal aspect of aryepiglottic fold

C13.2 Posterior wall of hypopharynx

C13.8 Overlapping lesion of hypopharynx

C13.9 Hypopharynx, NOS

| CS Tumor Size CS Extension CS TS/Ext-Eval CS Lymph Nodes CS Reg Nodes Eval Reg LN Pos Reg LN Exam CS Mets at DX CS Mets Eval | CS Site-Specific Factor 1 - Size of Lymph Nodes CS Site-Specific Factor 2 - Extracapsular Extension, Lymph Nodes for Head and Neck CS Site-Specific Factor 3 - Levels I-III, Lymph Nodes for Head and Neck CS Site-Specific Factor 4 - Levels IV-V and Retropharyngeal Lymph Nodes for Head and Neck CS Site-Specific Factor 5 - Levels VI-VII and Facial Lymph Nodes for Head and Neck CS Site-Specific Factor 6 - Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck | The following tables are available at the collaborative staging website: Histology Exclusion Table AJCC Stage Lymph Nodes Size Table Specific Extension with Size |
|--|---|---|
|--|---|---|

Pyriform Sinus, Hypopharynx, Laryngopharynx CS Tumor Size SEE STANDARD TABLE

Pyriform Sinus, Hypopharynx, Laryngopharynx

CS Extension (Revised: 09/25/2007)

Note: If there is fixation of hemilarynx or larynx, code to 55, not 15 or 45.

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 00 | In situ; noninvasive; intraepithelial | Tis | IS | IS |
| 10 | Invasive tumor confined to one of the following subsites: Laryngopharynx Postcricoid area Posterior pharyngeal wall Pyriform sinus | * | L | L |
| 15 | Code 10 with tumor fixation | * | RE | RE |
| 20 | Tumor invades more than one subsite of hypopharynx (listed in code 10) WITHOUT fixation | * | L | L |
| 30 | Localized, NOS | * | L | L |
| 40 | Oropharynx | * | RE | RE |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 45 | Code 20, 30, or 40 with tumor fixation | * | RE | RE |
| 50 | Larynx | * | RE | RE |
| 51 | OBSOLETE: converted to 45 Any of codes 10-40 WITH fixation of tumor or fixation, NOS | * | RE | RE |
| 55 | Fixation of hemilarynx or larynx | Т3 | RE | RE |
| 60 | Soft tissues of neck including Prelaryngeal strap muscles Subcutaneous fat | T4a | RE | RE |
| 61 | Esophagus | T4a | RE | RE |
| 62 | Thyroid gland | T4a | D | RE |
| 63 | Cricoid cartilage Thyroid cartilage | T4a | D | RE |
| 64 | Prevertebral fascia/muscle(s) | T4b | RE | RE |
| 65 | Carotid artery | T4b | D | RE |
| 66 | Hyoid bone | T4a | D | D |
| 70 | Mediastinal structures | T4b | D | D |
| 80 | Further contiguous extension | T4b | D | D |
| 95 | No evidence of primary tumor | T0 | U | U |
| 99 | Unknown extension Primary tumor cannot be assessed Not documented in patient record | TX | U | U |

^{*} For Extension codes 10, 15, 20, 30, 40, 45, 50, and 51 ONLY, the T category is assigned based on the value of CS Tumor Size and CS Extension as shown in the Specific Extension Codes with Size Table for this site.

Pyriform Sinus, Hypopharynx, Laryngopharynx CS TS/Ext-Eval SEE STANDARD TABLE

Pyriform Sinus, Hypopharynx, Laryngopharynx

CS Lymph Nodes (Revised: 08/21/2006)

Note 1: For head and neck schemas, this field includes all lymph nodes defined as Levels I-VII and Other by AJCC. The complete definitions are provided in the General Instructions.

Note 2: For head and neck schemas, additional information about lymph nodes (size of involved nodes, extracapsular extension, and levels involved) is coded in Site-Specific Factors 1-6.

Note 3: If laterality of lymph nodes is not specified, assume nodes are ipsilateral. Midline nodes are considered ipsilateral.

CS Staging Schemas

Note 4: For head and neck cancers, if lymph nodes are described only as "supraclavicular", try to determine if they are in Level IV (deep to the sternocleidomastoid muscle, in the lower jugular chain) or Level V (in the posterior triangle, inferior to the transverse cervical artery) and code appropriately. If the specific level cannot be determined, consider them as Level V nodes.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | None; no regional lymph node involvement | N0 | NONE | NONE |
| 10 | Single positive ipsilateral regional node: Level II node Jugulodigastric (subdigastric) Upper deep cervical Upper jugular Level III node Middle deep cervical Mid jugular Level IV node Lower deep cervical Lower jugular Retropharyngeal Cervical, NOS Deep cervical, NOS Internal jugular, NOS Mandibular Regional lymph node, NOS | * | RN | RN |
| 11 | Single positive ipsilateral regional node: Level I node Submandibular (submaxillary) Submental Level VI node Anterior deep cervical Laterotracheal Paralaryngeal Paratracheal Prelaryngeal Pretracheal Recurrent laryngeal Other groups Intraparotid Parapharyngeal Periparotid Retropharyngeal Sub-occipital | * | D | RN |
| 12 | Single positive ipsilateral regional node: Level V node Posterior cervical Posterior triangle (spinal accessory and transverse cervical) (upper, middle, and lower corresponding to the levels that define upper, middle, and lower jugular nodes) Level VII node Upper mediastinum (for other mediastinal nodes see CS Mets at DX) Supraclavicular, NOS (See Note 4) | * | D | D |
| 18 | Stated as N1, no other information | N1 | RN | RN |
| | | 1 | 1 | 1 |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-------|------|--------|
| 19 | Stated as N2a, no other information | N2a | RN | RN |
| 20 | Multiple positive ipsilateral nodes listed in code 10 | * | RN | RN |
| 21 | Multiple positive ipsilateral nodes listed in code 11 | * | D | RN |
| 22 | Multiple positive ipsilateral nodes listed in code 12 | * | D | D |
| 29 | Stated as N2b, no other information | N2b | RN | RN |
| 30 | Regional lymph nodes as listed in code 10: Positive ipsilateral node(s), not stated if single or multiple | * | RN | RN |
| 31 | Regional lymph nodes as listed in code 11: Positive ipsilateral node(s), not stated if single or multiple | * | D | RN |
| 32 | Regional lymph nodes as listed in code 12: Positive ipsilateral node(s), not stated if single or multiple | * | D | D |
| 40 | Regional lymph nodes as listed in code 10: Positive bilateral or contralateral nodes | * | RN | RN |
| 41 | Regional lymph nodes as listed in code 11: Positive bilateral or contralateral nodes | * | D | RN |
| 42 | Regional lymph nodes as listed in code 12: Positive bilateral or contralateral nodes | * | D | D |
| 49 | Stated as N2c, no other information | N2c | RN | RN |
| 50 | Regional lymph nodes as listed in code 10: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | RN | RN |
| 51 | Regional lymph nodes as listed in code 11: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | RN |
| 52 | Regional lymph nodes as listed in code 12: Positive node(s), not stated if ipsilateral, or bilateral, or contralateral, AND not stated if single or multiple | * | D | D |
| 60 | Stated as N2, NOS | N2NOS | RN | RN |
| 70 | Stated as N3, no other information | N3 | RN | RN |
| 80 | Lymph nodes, NOS, no other information | * | RN | RN |
| 99 | Unknown; not stated Regional lymph node(s) cannot be assessed Not documented in patient record | NX | U | U |

^{*} For codes 10-12, 20-22, 30-32, 40-42, 50-52, and 80 ONLY, the N category is assigned based on the value of Site-Specific Factor 1, Size of Lymph Nodes, using the extra table, Lymph Nodes Size Table for this site.

CS Staging Schemas

Pyriform Sinus, Hypopharynx, Laryngopharynx CS Reg Nodes Eval SEE STANDARD TABLE

Pyriform Sinus, Hypopharynx, Laryngopharynx Reg LN Pos SEE STANDARD TABLE

Pyriform Sinus, Hypopharynx, Laryngopharynx Reg LN Exam SEE STANDARD TABLE

Pyriform Sinus, Hypopharynx, Laryngopharynx

CS Mets at DX (Revised: 08/14/2006)

Note: Supraclavicular and transverse cervical lymph nodes are now coded in CS Lymph Nodes because they are categorized as N rather than M in AJCC TNM. Any cases coded to 10 or 50 can be reviewed and recoded. The volume of cases affected should be small.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | No; none | M0 | NONE | NONE |
| 10 | Distant lymph node(s) Mediastinal Distant lymph node(s), NOS | M1 | D | D |
| 40 | Distant metastases except distant lymph node(s) (code 10) Distant metastasis, NOS Carcinomatosis | M1 | D | D |
| 50 | (10) + (40) Distant lymph node(s) plus other distant metastases | M1 | D | D |
| 99 | Unknown if distant metastasis Distant metastasis cannot be assessed Not documented in patient record | MX | U | U |

Pyriform Sinus, Hypopharynx, Laryngopharynx CS Mets Eval SEE STANDARD TABLE

Pyriform Sinus, Hypopharynx, Laryngopharynx

CS Site-Specific Factor 1 Size of Lymph Nodes (Revised: 08/18/2006)

Note: Code the largest diameter, whether measured clinically or pathologically, of any involved regional lymph node(s). Do not code the size of any nodes coded in CS Mets at DX.

| Code | Description |
|---------|--|
| 000 | No involved regional nodes |
| 001-988 | 001-988 millimeters (code exact size in millimeters) |

CS Staging Schemas

| Code | Description |
|------|--|
| 989 | 989 millimeters or larger |
| 990 | Microscopic focus or foci only, no size of focus given |
| 991 | Described as "less than 1cm" |
| 992 | Described as "less than 2cm" or "greater than 1cm" or "between 1cm and 2cm" |
| 993 | Described as "less than 3cm" or "greater than 2cm" or "between 2cm and 3cm" |
| 994 | Described as "less than 4cm" or "greater than 3cm" or "between 3cm and 4cm" |
| 995 | Described as "less than 5cm" or "greater than 4cm" or "between 4cm and 5cm" |
| 996 | Described as "less than 6cm" or "greater than 5cm" or "between 5cm and 6cm" |
| 997 | Described as "more than 6cm" |
| 999 | Regional lymph node(s) involved, size not stated Unknown if regional lymph node(s) involved Not documented in patient record |

Pyriform Sinus, Hypopharynx, Laryngopharynx

CS Site-Specific Factor 2 Extracapsular Extension, Lymph Nodes for Head and Neck (Revised: 08/17/2007)

Note 1: Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. Do not code extracapsular extension in any nodes coded in CS Mets at DX in this field.

Note 2: A statement of the presence or absence of extracapsular extension in a pathology report takes priority over clinical assessment. However, if the pathology report contains no statement about extracapsular extension, either positive or negative, the clinical assessment should be coded. If nodes are involved but there is neither a clinical assessment of extranodal extension nor a statement about it in the pathology report, use code 999.

Note 3: According to AJCC (page 24), "Imaging studies showing amorphous spiculated margins of involved nodes or involvement of internodal fat resulting in loss of normal oval-to-round nodal shape strongly suggest extracapsular (extranodal) tumor spread; however, pathologic examination is necessary for documentation of the extent of such disease."

| Code | Description |
|------|---|
| 000 | No extracapsular extension |
| 001 | Extracapsular extension clinically, not assessed pathologically Nodes described as "fixed", not assessed pathologically |
| 005 | Extracapsular extension present pathologically |
| 888 | Not applicable; no lymph node involvement |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Pyriform Sinus, Hypopharynx, Laryngopharynx

CS Site-Specific Factor 3 Levels I-III, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels I, II, or III |
| 100 | Level I lymph node(s) involved |
| 010 | Level II lymph node(s) involved |
| 001 | Level III lymph node(s) involved |
| 110 | Level I and II lymph nodes involved |
| 101 | Level I and III lymph nodes involved |
| 011 | Level II and III lymph nodes involved |
| 111 | Level I, II and III lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Pyriform Sinus, Hypopharynx, Laryngopharynx CS Site-Specific Factor 4 Levels IV-V and Retropharyngeal Lymph Nodes for Head and

Neck (Revised: 08/21/2006)

| Code | Description |
|------|--|
| 000 | No lymph node involvement in Levels IV or V or retropharyngeal |
| 100 | Level IV lymph node(s) involved |
| 010 | Level V lymph node(s) involved |
| 001 | Retropharyngeal nodes involved |
| 110 | Level IV and V lymph nodes involved |
| 101 | Level IV and retropharyngeal nodes involved |
| 011 | Level V and retropharyngeal nodes involved |

CS Staging Schemas

| Code | Description |
|------|---|
| 111 | Level IV and V and retropharyngeal lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Pyriform Sinus, Hypopharynx, Laryngopharynx

CS Site-Specific Factor 5 Levels VI-VII and Facial Lymph Nodes for Head and Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels VI or VII or facial nodes |
| 100 | Level VI lymph node(s) involved |
| 010 | Level VII lymph node(s) involved |
| 001 | Facial (buccinator, nasolabial) lymph node(s) involved |
| 110 | Level VI and VII lymph nodes involved |
| 101 | Level VI and facial (buccinator, nasolabial) nodes involved |
| 011 | Level VII and facial (buccinator, nasolabial) nodes involved |
| 111 | Level VI and VII and facial (buccinator, nasolabial) lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Pyriform Sinus, Hypopharynx, Laryngopharynx CS Site-Specific Factor 6 Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|--|
| 000 | No parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), or sub-occipital lymph node involvement |

CS Staging Schemas

| Code | Description |
|------|---|
| 100 | Parapharyngeal lymph node(s) involved |
| 010 | Parotid (preauricular, periparotid, and/or intraparotid) lymph node(s) involved |
| 001 | Sub-occipital lymph node(s) involved |
| 110 | Parapharyngeal and parotid (preauricular, periparotid, and/or intraparotid) lymph nodes involved |
| 101 | Parapharyngeal and sub-occipital lymph nodes involved |
| 011 | Parotid (preauricular, periparotid, and/or intraparotid) and sub-occipital lymph nodes involved |
| 111 | Parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), and sub-occipital lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Pharynx, NOS, and Other Ill-Defined Oral Cavity Sites C14.0, C14.2, C14.8

C14.0 Pharynx, NOS C14.2 Waldeyer ring

C14.8 Overlapping lesion of lip, oral cavity

Note: AJCC does not define TNM staging for this site.

| CS Tumor Size CS Extension CS TS/Ext-Eval CS Lymph Nodes CS Reg Nodes Eval Reg LN Pos Reg LN Exam CS Mets at DX CS Mets Eval | CS Site-Specific Factor 1 - Size of Lymph Nodes CS Site-Specific Factor 2 - Extracapsular Extension, Lymph Nodes for Head and Neck CS Site-Specific Factor 3 - Levels I-III, Lymph Nodes for Head and Neck CS Site-Specific Factor 4 - Levels IV-V and Retropharyngeal Lymph Nodes for Head and Neck CS Site-Specific Factor 5 - Levels VI-VII and Facial Lymph Nodes for Head and Neck CS Site-Specific Factor 6 - Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck | The following tables are available at the collaborative staging website: Histology Exclusion Table AJCC Stage |
|--|---|---|
|--|---|---|

Pharynx, NOS, and Other Ill-Defined Oral Cavity Sites CS Tumor Size SEE STANDARD TABLE

Pharynx, NOS, and Other Ill-Defined Oral Cavity Sites

CS Extension (Revised: 12/10/2003)

Note: Definition of Adjacent Structures: Connective tissues large enough to be given a specific name would be considered adjacent structures. For example, the brachial artery has a name, as does the broad ligament. Continuous tumor growth from one organ into an adjacent named structure would be coded to less than 60 in the schemes for ill-defined or non-specific sites.

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 00 | In situ; noninvasive; intraepithelial | NA | IS | IS |
| 10 | Invasive tumor confined to site of origin | NA | L | L |
| 30 | Localized, NOS | NA | L | L |
| 40 | More than one region of pharynx involved (oropharynx, nasopharynx, hypopharynx) | NA | RE | RE |
| 50 | Pharynx and oral cavity involved | NA | RE | RE |
| 55 | Any of codes 10-50 WITH fixation | NA | RE | RE |
| 60 | Extension to adjacent structures (See note) | NA | RE | RE |
| 80 | Further contiguous extension | NA | D | D |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 95 | No evidence of primary tumor | NA | U | U |
| 99 | Unknown extension Primary tumor cannot be assessed Not documented in patient record | NA | U | U |

Pharynx, NOS, and Other Ill-Defined Oral Cavity Sites

CS TS/Ext-Eval (Revised: 03/17/2004)

| Code | Description | Staging Basis |
|------|------------------------------|------------------|
| 9 | Not applicable for this site | NA |

Pharynx, NOS, and Other Ill-Defined Oral Cavity Sites

CS Lymph Nodes (Revised: 08/15/2006)

Note 1: For head and neck schemas, this field includes all lymph nodes defined as Levels I-VII and Other by AJCC. The complete definitions are provided in the General Instructions.

Note 2: For head and neck schemas, additional information about lymph nodes (size of involved nodes, extracapsular extension, and levels involved) is coded in Site-Specific Factors 1-6.

Note 3: If laterality of lymph nodes is not specified, assume nodes are ipsilateral. Midline nodes are considered ipsilateral.

Note 4: For head and neck cancers, if lymph nodes are described only as "supraclavicular", try to determine if they are in Level IV (deep to the sternocleidomastoid muscle, in the lower jugular chain) or Level V (in the posterior triangle, inferior to the transverse cervical artery) and code appropriately. If the specific level cannot be determined, consider them as Level V nodes.

| Code | Description | TNM | SS77 | SS2000 |
|------|---|-----|------|--------|
| 00 | None; no regional lymph node involvement | NA | NONE | NONE |
| 10 | Regional lymph node(s) bilateral and/or contralateral: Cervical, NOS Internal jugular, NOS Deep cervical, NOS: Lower, NOS Jugulo-omohyoid (supraomohyoid) Middle Upper, NOS: Jugulodigastric (subdigastric) Mandibular, NOS Submandibular (submaxillary) Submental Paratracheal Recurrent laryngeal nerve chain Prelaryngeal Delphian node Retropharyngeal Regional lymph node(s), NOS | NA | RN | RN |
| 12 | Regional lymph node(s) bilateral and/or contralateral: Supraclavicular, NOS (See Note 4) | NA | D | D |
| 80 | Lymph nodes, NOS | NA | RN | RN |

CS Staging Schemas

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 99 | Unknown; not stated Regional lymph node(s) cannot be assessed Not documented in patient record | NA | U | U |

Pharynx, NOS, and Other Ill-Defined Oral Cavity Sites

CS Reg Nodes Eval (Revised: 03/17/2004)

| Code | Description | Staging Basis |
|------|------------------------------|------------------|
| 9 | Not applicable for this site | NA |

Pharynx, NOS, and Other Ill-Defined Oral Cavity Sites Reg LN Pos SEE STANDARD TABLE

Pharynx, NOS, and Other Ill-Defined Oral Cavity Sites Reg LN Exam SEE STANDARD TABLE

Pharynx, NOS, and Other Ill-Defined Oral Cavity Sites

CS Mets at DX (Revised: 02/22/2005)

Note: Supraclavicular and transverse cervical lymph nodes are now coded in CS Lymph Nodes because they are categorized as N rather than M in AJCC TNM. Any cases coded to 10 or 50 can be reviewed and recoded. The volume of cases affected should be small.

| Code | Description | TNM | SS77 | SS2000 |
|------|--|-----|------|--------|
| 00 | No; none | NA | NONE | NONE |
| 10 | Distant lymph node(s), including: Mediastinal | NA | D | D |
| 40 | Distant metastasis, NOS Distant metastases except distant lymph node(s) (code 10) Carcinomatosis | NA | D | D |
| 50 | (10) + (40) Distant lymph node(s) plus other distant metastases | NA | D | D |
| 99 | Unknown if distant metastasis Distant metastasis cannot be assessed Not documented in patient record | NA | U | U |

CS Staging Schemas

Pharynx, NOS, and Other Ill-Defined Oral Cavity Sites

CS Mets Eval (Revised: 03/17/2004)

| Code | Description | Staging Basis |
|------|------------------------------|------------------|
| 9 | Not applicable for this site | NA |

Pharynx, NOS, and Other Ill-Defined Oral Cavity Sites

CS Site-Specific Factor 1 Size of Lymph Nodes (Revised: 08/18/2006)

Note: Code the largest diameter, whether measured clinically or pathologically, of any involved regional lymph node(s). Do not code the size of any nodes coded in CS Mets at DX.

| Code | Description |
|---------|--|
| 000 | No involved regional nodes |
| 001-988 | 001-988 millimeters (code exact size in millimeters) |
| 989 | 989 millimeters or larger |
| 990 | Microscopic focus or foci only, no size of focus given |
| 991 | Described as "less than 1cm" |
| 992 | Described as "less than 2cm" or "greater than 1cm" or "between 1cm and 2cm" |
| 993 | Described as "less than 3cm" or "greater than 2cm" or "between 2cm and 3cm" |
| 994 | Described as "less than 4cm" or "greater than 3cm" or "between 3cm and 4cm" |
| 995 | Described as "less than 5cm" or "greater than 4cm" or "between 4cm and 5cm" |
| 996 | Described as "less than 6cm" or "greater than 5cm" or "between 5cm and 6cm" |
| 997 | Described as "more than 6cm" |
| 999 | Regional lymph node(s) involved, size not stated Unknown if regional lymph node(s) involved Not documented in patient record |

Pharynx, NOS, and Other Ill-Defined Oral Cavity Sites

CS Site-Specific Factor 2 Extracapsular Extension, Lymph Nodes for Head and Neck (Revised: 08/17/2007)

Note 1: Code the status of extracapsular extension whether assessed clinically or pathologically of any involved regional lymph node(s) coded in the CS Lymph Nodes field. Do not code extracapsular extension in any nodes coded in CS Mets at DX in this field.

Note 2: A statement of the presence or absence of extracapsular extension in a pathology report takes priority over clinical assessment. However, if the pathology report contains no statement about extracapsular extension, either positive or negative, the clinical assessment should be coded. If nodes are involved but there is neither a clinical assessment of extranodal extension nor a statement about it in the pathology report, use code 999.

CS Staging Schemas

Note 3: According to AJCC (page 24), "Imaging studies showing amorphous spiculated margins of involved nodes or involvement of internodal fat resulting in loss of normal oval-to-round nodal shape strongly suggest extracapsular (extranodal) tumor spread; however, pathologic examination is necessary for documentation of the extent of such disease."

| Code | Description |
|------|---|
| 000 | No extracapsular extension |
| 001 | Extracapsular extension clinically, not assessed pathologically Nodes described as "fixed", not assessed pathologically |
| 005 | Extracapsular extension present pathologically |
| 888 | Not applicable; no lymph node involvement |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Pharynx, NOS, and Other Ill-Defined Oral Cavity Sites

CS Site-Specific Factor 3 Levels I-III, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels I, II, or III |
| 100 | Level I lymph node(s) involved |
| 010 | Level II lymph node(s) involved |
| 001 | Level III lymph node(s) involved |
| 110 | Level I and II lymph nodes involved |
| 101 | Level I and III lymph nodes involved |
| 011 | Level II and III lymph nodes involved |
| 111 | Level I, II and III lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

CS Staging Schemas

Pharynx, NOS, and Other Ill-Defined Oral Cavity Sites CS Site-Specific Factor 4 Levels IV-V and Retropharyngeal Lymph Nodes for Head and

Neck (Revised: 08/21/2006)

Note: Site-Specific Factors 3-6 are used to code the presence or absence of lymph node involvement in each of 7 different levels and other groups defined by AJCC. The definitions of the levels are the same for all applicable head and neck sites. One digit is used to represent lymph nodes of a single level, with the three digits of Site-Specific Factor 3 representing lymph nodes of, respectively, Levels I-III; the digits of Site-Specific Factor 4 representing lymph nodes of Levels IV and V and the retropharyngeal nodes; the digits of Site-Specific Factor 5 representing lymph nodes of Levels VI and VII and the facial nodes; and the digits of Site-Specific Factor 6 representing the remaining Other groups as defined by AJCC. In each digit, a code 1 means Yes, the nodes are involved.

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels IV or V or retropharyngeal |
| 100 | Level IV lymph node(s) involved |
| 010 | Level V lymph node(s) involved |
| 001 | Retropharyngeal nodes involved |
| 110 | Level IV and V lymph nodes involved |
| 101 | Level IV and retropharyngeal nodes involved |
| 011 | Level V and retropharyngeal nodes involved |
| 111 | Level IV and V and retropharyngeal lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Pharynx, NOS, and Other Ill-Defined Oral Cavity Sites CS Site-Specific Factor 5 Levels VI-VII and Facial Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|---|
| 000 | No lymph node involvement in Levels VI or VII or facial nodes |
| 100 | Level VI lymph node(s) involved |
| 010 | Level VII lymph node(s) involved |
| 001 | Facial (buccinator, nasolabial) lymph node(s) involved |
| 110 | Level VI and VII lymph nodes involved |
| 101 | Level VI and facial (buccinator, nasolabial) nodes involved |
| 011 | Level VII and facial (buccinator, nasolabial) nodes involved |

CS Staging Schemas

| Code | Description |
|------|---|
| 111 | Level VI and VII and facial (buccinator, nasolabial) lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Pharynx, NOS, and Other Ill-Defined Oral Cavity Sites CS Site-Specific Factor 6 Parapharyngeal, Parotid, Preauricular, and Sub-Occipital Lymph Nodes, Lymph Nodes for Head and Neck (Revised: 08/21/2006)

| Code | Description |
|------|---|
| 000 | No parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), or sub-occipital lymph node involvement |
| 100 | Parapharyngeal lymph node(s) involved |
| 010 | Parotid (preauricular, periparotid, and/or intraparotid) lymph node(s) involved |
| 001 | Sub-occipital lymph node(s) involved |
| 110 | Parapharyngeal and parotid (preauricular, periparotid, and/or intraparotid) lymph nodes involved |
| 101 | Parapharyngeal and sub-occipital lymph nodes involved |
| 011 | Parotid (preauricular, periparotid, and/or intraparotid) and sub-occipital lymph nodes involved |
| 111 | Parapharyngeal, parotid (preauricular, periparotid, and/or intraparotid), and sub-occipital lymph nodes involved |
| 999 | Unknown if regional lymph node(s) involved, not stated Regional lymph nodes cannot be assessed Not documented in patient record |

Surgery Codes

Pharynx

Tonsil C090–C099, Oropharynx C100–C109, Nasopharynx C110–C119 Pyriform Sinus C129, Hypopharynx C130–C139, Pharynx C140 (Except for M9750, 9760-9764, 9800-9820, 9826, 9831-9920, 9931-9964, 9980-9989)

Codes

- None; no surgery of primary site; autopsy ONLY
- 10 Local tumor destruction, NOS
 - 11 Photodynamic therapy (PDT)
 - 12 Electrocautery; fulguration (includes use of hot forceps for tumor destruction)
 - 13 Cryosurgery
 - 14 Laser
 - 15 Stripping

No specimen sent to pathology from surgical events 10–15

- 20 Local tumor excision, NOS
 - 26 Polypectomy
 - 27 Excisional biopsy

Any combination of 20 or 26-27 WITH

- 21 Photodynamic therapy (PDT)
- 22 Electrocautery
- 23 Cryosurgery
- 24 Laser ablation

[**SEER Note:** Codes 21 to 24 above combine 20 Local tumor excision, 26 Polypectomy or 27 Excisional biopsy with 21 PDT, 22 Electrocautery, 23 Cryosurgery, or 24 Laser ablation]

- 25 Laser excision
- 28 Stripping

Specimen sent to pathology from surgical events 20–28

- 30 Pharyngectomy, NOS
 - 31 Limited/partial pharyngectomy; tonsillectomy, bilateral tonsillectomy
 - 32 Total pharyngectomy
- 40 Pharyngectomy WITH laryngectomy OR removal of contiguous bone tissue, NOS (does NOT include total mandibular resection)

[**SEER Notes:** Code 40 includes mandibulectomy (marginal, segmental, hemi-, and/or laryngectomy) NOS Contiguous bone tissue refers to the mandible]

- 41 WITH laryngectomy (laryngopharyngectomy)
- 42 WITH bone [mandibulectomy]
- 43 WITH both 41 and 42

[SEER Notes: Use code 40 when the patient had a pharyngectomy and maybe some sort of mandibulectomy and/or maybe a laryngectomy, but the exact procedures are not clear. Use code 41 when the patient had pharyngectomy and laryngectomy but no mandibulectomy. Use code 42 when the patient had pharyngectomy and mandibulectomy but no laryngectomy. Use code 43 when it is certain that the patient had both a mandibulectomy and laryngectomy in addition to the pharyngectomy]

Surgery Codes

- 50 Radical pharyngectomy (includes total mandibular resection), NOS
 - 51 WITHOUT laryngectomy
 - 52 WITH laryngectomy
- 90 Surgery, NOS
- 99 Unknown if surgery performed; death certificate ONLY

Surgery Codes

All Other Sites

C142–C148, C170–C179, C239, C240–C249, C260–C269, C300–C301, C310–C319, C339, C379, C380–C388, C390–C399, C480–C488, C510–C519, C529, C570–C579, C589, C600–C609, C630–C639, C680–C689, C690–C699, C740–C749, C750–C759 (Except for M9750, 9760-9764, 9800-9820, 9826, 9831-9920, 9931-9964, 9980-9989)

Codes

- None; no surgery of primary site; autopsy ONLY
- 10 Local tumor destruction, NOS
 - 11 Photodynamic therapy (PDT)
 - 12 Electrocautery; fulguration (includes use of hot forceps for tumor destruction)
 - 13 Cryosurgery
 - 14 Laser

No specimen sent to pathology from surgical events 10-14

- 20 Local tumor excision, NOS
 - 26 Polypectomy
 - 27 Excisional biopsy

Any combination of 20 or 26-27 WITH

- 21 Photodynamic therapy (PDT)
- 22 Electrocautery
- 23 Cryosurgery
- 24 Laser ablation

[**SEER Note:** Codes 21 to 24 above combine 20 local tumor excision, 26 Polypectomy or 27 Excisional biopsy with 21 PDT, 22 Electrocautery, 23 Cryosurgery, or 24 Laser ablation]

25 Laser excision

Specimen sent to pathology from surgical events 20-27

- 30 Simple/partial surgical removal of primary site
- 40 Total surgical removal of primary site; enucleation
 - 41 Total enucleation (for eye surgery only)
- 50 Surgery stated to be "debulking"
- 60 Radical surgery

Partial or total removal of the primary site WITH a resection in continuity (partial or total removal) with other organs

[SEER Note: In continuity with or "en bloc" means that all of the tissues were removed during the same procedure, but not necessarily in a single specimen]

- 90 Surgery, NOS
- 99 Unknown if surgery performed; death certificate ONLY

This page left blank