AMIA 2000 Fall Symposium - Tutorial T13

Customizing the UMLS Metathesaurus for Your Applications


William T. Hole, MD
Betsy L. Humphreys, MLS
Suresh Srinivasan, MS
Laura Roth, MLS

National Library of Medicine Saturday, November 4, 2000 - 1:00-4:30 pm

Outline of Tutorial

- Why customize Betsy Humphreys
- How to customize Bill Hole
- A tool to help you customize Laura Roth and Suresh Srinivasan
- Adding "local" terminology Bill Hole


A few Metathesaurus Ingredients...



UMLS Source "Vocabularies"

- Widely varying purposes, structures, properties that do *not* add up to single ontology or view of the world:
 - Thesauri, e.g., MeSH
 - Statistical Classifications, e.g., ICD
 - Billing Codes, e.g., CPT
 - Clinical coding systems, e.g., SNOMED
 - Lists of controlled terms, e.g., HL7 valid values

How to combine them?






Not really


"The Metathesaurus preserves the meanings, hierarchical connections, and other relationships between terms present in its source vocabularies, while adding certain basic information about each of its concepts and establishing new relationships between concepts and terms from different source vocabularies."

It keeps getting bigger....



2000 UMLS Metathesaurus

- **730,000** concepts
- 1,338,650 "terms" (Eye, Eyes, eye = 1)
- 1,593,730 "strings"/concept names (Eye, Eyes, eye = 3)
- >50 source vocabularies



Why Customize? 3 basic reasons


- Because nobody needs or wants all of it for any specific set of purposes
 - extraneous vs. pernicious content
- Because you don't have the licenses required for operational use of all source vocabularies
- Because the default "preferred name" is not best for your applications


Possibly Extraneous, e.g.,

- Terms in languages other than English
- Redundant minor variations
- Procedure codes, when your application is focused on problems


Possibly Pernicious, e.g.,

- Terms that lack face validity
- Abbreviations and short forms
- Other less than beautiful "suppressible synonyms" already identified by NLM
- Unhelpful "views of the world"







Natural Language Processing version of the Metathesaurus, *excluding* "suppressible synonyms", highly structured terms such as those in LOINC, etc.




PubMed's UMLS/MeSH mapping table



■ National Cancer Institute's MetaphraseTM implementation, which changes default "preferred name" precedence





CliniWeb International, which uses MeSH and several of its translations



🖁 Cliniweb International - Netscape

Customization is critical, but it requires a clear understanding of:

- Your functional requirements
- Characteristics of relevant UMLS source vocabularies
- Your license arrangements
- and Technical expertise
- Therefore, it is usually a team sport.

Outline of Tutorial

- Why customize Betsy Humphreys
- How to customize Bill Hole
- A tool to help you customize Laura Roth and Suresh Srinivasan
- Adding "local" terminology Bill Hole

How to Customize your Metathesaurus

- Limit vocabularies
- Limit languages
- Limit Relationships
- Aggregate by Relationships
- Add and Use Suppressibility
- Change Naming Precedence
- Select by attribute e.g. STYs
- Add local terminology

To work with Meta files:

- You will have to select the rows and columns you need, and combine them in ways which best meet your needs.
- You need your own programming and data management tools to work with the files, e.g.:
 - Unix: grep, sed, cut, awk, sort, join ...
 - RDBMS: Mysql, Access, Oracle, Ingres...
 - Other languages and extensions, e.g. Java, C++, , Visual Basic, Perl; interfaces to B-trees, RDBMS ...
- We supply *MetamorphoSys*, a tool to exclude vocabularies and alter naming, described later.
- Some helpful files, such as RDBMS load scripts, are being developed check http://umlsinfo.nlm.nih.gov

Using Unique Identifiers:

Simplified example: Concept Unique Identifier C0002871 links tables:

```
MRCON: Concept names
```

```
C0002871|ENG|P|L0002871|PF|S0013742|Anemia|0|
```

C0002871 ENG|S|L0376533 PF|S0500659 Oligocythemia of red blood cells 3

C0002871|FRE|P|L0162748|PF|<u>S0227229</u>|ANEMIE|2|

MRSO: Sources (vocabulary information)

C0002871|L0002871|S0013742|MSH2000|MH|D000740|0|

C0002871|L0376533|S0500659|SNMI98|SY|DC-10010|3|

C0002871|L0162748|S0227229|INS2000|MH|D000740|3|

C0002871|L0162748|<u>S0227229</u>|WHOFRE|PT|0544|2|

MRSTY: Semantic Types

C0002871 T047 Disease or Syndrome

MRDEF: Definitions

C0002871 | CSP98 | subnormal levels or function of erythrocytes, resulting in symptoms of tissue hypoxia.

C0002871|MSH2000|A reduction in the number of circulating erythrocytes or in the quantity of hemoglobin.

C0002871|PDQ99|A condition in which the number of red blood cells is below normal.

First, Select the data you need:

The 'Big Five' Relational files:

MRCON: Concept Names

MRSO: Source vocabulary information

MRSTY: Semantic Types

MRREL: Most Relationships

MRSAT: Simple Attributes

MRCON: Concept Names

```
CUI
          | LAT|TS|LUI |STT|SUI
                                       /STR
                                                                                |LRL|
C0154009 | ENG | P | L0180842 | PF | S0245368 | Benign neoplasm of prostate | 0 |
C0154009 ENG | S | L0524759 | PF | S0598915 | Benign prostatic tumour | 3 |
C0154009 | ENG | s | L0033572 | PF | S0999020 | Prostate <3> | 0 |
C0154009 ENG | s | L0033572 | VO | S0077252 | Prostate | 3 |
C0154009 GER P L1258213 PF S1500159 Gutartige Neubildung: Prostata 1
   CUI Unique identifier for concept ("The name that never changes";)
         - Links ALL Concept information
    LAT Language of Term
    TS
        Term status
    LUI Unique identifier for term (lexically similar strings, defined by lvg)
    STT String type
    SUI Unique identifier for string
    STR String
    LRL Least Restriction Level (lowest license restriction* for a source of this string)
          - lowest license restriction level for this string; see MRSO Source Restriction level
          * License restriction levels are defined in the UMLS License Agreement.
```

A copy of the License Agreement is provided in the Appendix

Customizing with MRCON - Examples:

- •Select or exclude sets of concepts by CUI identified elsewhere
- •Select or exclude a language by *LAT*
- •Select or exclude by Term Status TS, e.g.:

```
TS="P" Preferred;
TS="S" Synonym
TS="s" Supressible Synonym
```

- •Use Preferred Terms (TS="P") and preferred form (STT="PF")
- •Select or exclude by Least Restriction Level (LRL), e.g.

No additional restrictions LRL = 0

```
CUI | LAT | TS | LUI | STT | SUI | STR | LRL | C0002871 | ENG | P | L0002871 | PF | S0013742 | Anemia | 0 |
```

MRSO: Source vocabulary information

```
TTY SCD
                                                |SRL|
          LUI
                  SUI
                            SAB
CUI
C0002871 L0002871 S0013742 LCH90
                                    PT U000235 0
C0002871 L0002871 S0013742 MSH2000 MH D000740 0
C0002871 L0002871 S0013742 MTH PT
                                   U000161
                                                0
                                    PT | 024503
C0002871 L0002871 S0013742 PSY94
                                                0
...
CUI
        Unique identifier for concept
LUI
        Unique identifier for term
        Unique identifier for string
SUI
        Source abbreviation
SAB
TTY
        Term type in source
SCD
        Unique Identifier or code for string in source
SRL
        Source Restriction Level
```

^{*} on this slide and many which follow, trailing spaces have been added to align columns for readability. They do not exist in the Metathesaurus files.

Source Restriction Level vs. Least Restriction Level

- •Source (Vocabulary) Restriction Level (SRL), in MRSO:
 - O Means there are no additional restrictions
 - 1 3 Means there are additional restrictions as defined in the License Agreement.
- •Least Restriction Level (LRL), in MRCON:

The lowest restriction level (SRL) for all vocabularies providing this string

* All Restrictions are defined and listed for each vocabulary in the UMLS License Agreement

Customizing with MRSO - Examples:

- •Better to use MetamorphoSys to select or exclude sources it removes ALL source information - demo later
- •Select or exclude a TTY, e.g.

TTY="PT": Preferred term in source vocabulary;

TTY="AB": Abbreviation in source vocabulary;

•Select or exclude or order by SCD, e.g.

ICD-9-CM codes with 2 digits before decimal are Procedures

•Select or exclude by *SRL* (Source Restriction Level)

* SABs are listed in Manual Section B.2 and the SABDOC file TTYs are described Manual Section B.4 and the TTYDOC file

MRSTY: Semantic Types

** Don't assume you know what Semantic Types mean!
Use Knowledge Source Server (http://umlsks.nlm.nih.gov)

•Browser display for STY "Finding":

```
Semantic Types

|
Entity
|
Conceptual Entity
|
Finding ...
|
Laboratory or Test Result
Sign or Symptom
```

- •Definitions: ...
- •See a list of Metathesaurus concepts with Semantic type: "Finding".
- •Relations and Related Types for "Finding".
- •View records for Finding in relational format

^{*} hint: Tree numbers in SRDEF can be useful for walking hierarchies

MRSTY: Semantic Types

```
CUI | TUI | STY |
C0002871 | T047 | Disease or Syndrome |
C0004057 | T109 | Organic Chemical |
C0004057 | T121 | Pharmacologic Substance |
```

CUI Unique identifier of concept

TUI Unique identifier of Semantic type

STY Semantic type, defined in the Semantic Network.

Customizing with MRSTY - Examples:

- •Select or exclude by Semantic Type or sets of Types
- •Use Knowledge Source Server to see definitions, hierarchy, examples: http://umlsks.nlm.nih.gov

e.g. select or exclude all Laboratory or Test Result

```
CUI | TUI | STY | C0005798 | T034 | Laboratory or Test Result |
```

MRREL: Most Relationships

CUI1 Unique identifier of first concept

REL Relationship of second to first concept

CUI2 Unique identifier of second concept

RELA Relationship attribute

SAB Abbreviation of the source of relationship

SL Source of relationship labels

MG Machine-generated and unverified indicator (optional)

MRREL: Most Relationships

```
CUI1 | REL | CUI2 | RELA | SAB | SL | MG | C0002871 | CHD | C0002891 | isa | MSH2000 | MTH | | Anemia Anemia, Neonatal
```

"Neonatal Anemia" is child of "Anemia" (REL = CHD)
"Neonatal Anemia" is_a "Anemia" (RELA= isa)

SAB - Source of REL is MeSH;

SL - Source of labels (type of relationship) is MTH

MG - Not Machine generated.

MRREL: Most Relationships

Picking the Relationships you want:

RELDOC file, A bonus file available on http://umlsinfo.nlm.nih.gov

SAB	SL	REL	RELA	Count	
ICD2000	ICD2000	CHD		19579	
ICD2000	ICD2000	PAR		19579	
MSH2000	MSH2000	CHD	connected_to	43	
MTH	MTH	RB	ingredient_of	112	
MTH	MTH	RB		157580	
RAM99	RAM99	RO	clinically_similar	8200	
UWDA99	UWDA99	CHD	isa	16591	
UWDA99	UWDA99	CHD	part_of	7697	

Customizing with MRREL - Examples:

- •Select or exclude RELS, RELAs, and SAB or SL use *RELDOC* or determine suitability empirically
- •Use selected RELS and RELAs to aggregate e.g., all 'clinically_similar'
- •Combine with other criteria e.g., selected RELs to concepts with selected Semantic Types

MRSAT: Simple Attributes

```
CUI | LUI | SUI | SCD | ATN | SAB | ATV | C00002871 | L00002871 | S0013742 | D000740 | MN | MSH2000 | C15.378.71 | C0002871 | L0002871 | S0013742 | D000740 | TH | MSH2000 | POPLINE (1994) | C0002871 | L0002871 | S0414880 | 208/04453 | SOS | PDQ99 | secondary related condition |
```

```
CUI Unique identifier for concept or, for LT element only, LUI for term
```

LUI Unique identifier for term (optional)

SUI Unique identifier for string (optional)

SCD Unique identifier or code for entry in the source of the attribute

ATN Attribute name (see manual, ATNDOC file)

SAB Abbreviation of the source of the attribute

ATV Attribute value (see manual, ATNDOC file)

^{*}note: few attribute values exceed 2,200 characters.

Customizing with MRSAT - Examples:

•Wide variety of Attributes, many very detailed, described in manual or in *ATNDOC file* available on umlsinfo; e.g.:

```
SABATN | Count |MSH2000 | SOS | 88355 | -- Details of scope of concept in MeSHMTHAM | 11056 | -- Ambiguous string indicatorMTHST | 730155 | -- Status - 'R'eviewed or 'U'nreviewed
```

- •Attributes may be attached to CUIs, LUIs, or SUIs
- Choose the attributes you need!

Customizing with MRSAT, continued ...

You may also identify sets of concepts by attribute

- For example, to Select or exclude by Attribute for Reviewed Status
 - ATN "Status" = ST,
 - Attribute Value ATV = 'R' (Values are 'R'eviewed or 'U'nreviewed)
- All Unreviewed Concepts (which are MeSH Supplementary concepts) have ATN 'ST' and ATV 'U'
- To use or exclude these concepts, sselect their CUIs from the MRSAT rows with ATN 'ST' and ATV 'U'

Select Other data you need:

- MRDEF: Definitions
- MRCXT: Contexts
- MRLO: Locator
- MRATX: Mapping one vocabulary to Another
- MRCOC: Co-occurrences
- Indexes:
 - MRXW.ENG, MRXW.FRE, Other languages ...
 - MRXNW.ENG
 - MRXNS.ENG

MRDEF: Definitions

```
CUI | SAB | DEF

C0002871 | MSH2000 | A reduction in the number of circulating erythrocytes or in the quantity of hemoglobin. |
```

CUI Unique identifier for concept

SAB Abbreviation of the source of the definition

DEF Definition

** Note - there are nearly 32,000 definitions. Some definitions are very long, up to 6 kb

MRCXT: Contexts - Examples:

```
MSH2000
  Diseases (MeSH Category) [C]
     Virus Diseases [C2]
      RNA Virus Infections [C2.782]
       Arenaviridae Infections [C2.782.82]
        Lassa Fever [C2.782.82.545]
 MSH2000
    Diseases (MeSH Category) [C]
     Virus Diseases [C2]
      RNA Virus Infections [C2.782]
       Hemorrhagic Fevers, Viral [C2.782.417]
        Lassa Fever [C2.782.417.505]
 ICD10
    Certain infectious and parasitic diseases
     Arthropod-borne viral fevers and viral haemorrhagic fevers
      Arenaviral haemorrhagic fever
       Lassa fever [A96.2]
```

Using MRCXT: Contexts

-- See the documentation!

```
|SCD |CXN|CXL|RNK|CXS|CUI2
                                                        | HCD | REL | XC |
        SUI
                 SAB
CUI
C0002871 | S0013742 | MSH2000 | D000740 | 1 | ANC | 1 | MeSH | C0220876 | | | |
C0002871 | S0013742 | MSH2000 | D000740 | 1 | ANC | 2 | Diseases (MeSH Category) | C0012674 | C | | |
C0002871 | S0013742 | MSH2000 | D000740 | 1 | ANC | 3 | Hemic and Lymphatic Diseases | C0018981 | C15 | | |
C0002871|S0013742|MSH2000|D000740|1|ANC|4|Hematologic Diseases|C0018939|C15.378|isa||
C0002871|S0013742|MSH2000|D000740|1|CCP||Anemia|C0002871|C15.378.71|isa|+|
C0002871|S0013742|MSH2000|D000740|1|CHD||Anemia, Aplastic|C0002874|C15.378.71.85|isa|+|
C0002871|S0013742|MSH2000|D000740|1|SIB||Blood Protein Disorders|C0005830|C15.378.147|isa|+|
C0002871|S0013742|MSH2000|D000740|1|SIB||Bone Marrow Diseases|C0005956|C15.378.190|isa|+|
    CUI
             Unique identifier of concept
     SUI
             Unique identifier for string used in this context
     SAB
             Source abbreviation
     SCD
             Unique Identifier or code for string in that source
     CXN
             The context number (to distinguish multiple contexts, same source, same SUI).
     CXL
             Context member label, e.g., ANC for ancestor of this concept\
     RNK
             For rows with a CXL value of ANC, the rank of the ancestors
     CXS
             String for context member.
     CUI2
             Unique concept identifier of context member (may be empty)
     HCD
             Hierarchical number or code of context member in this source (optional).
     REL
             Relationship of concept to parent, if applicable and known.
     XC
             Plus(+) sign indicating that the concept has children (see manual)
```

MRCXT: Contexts - Caveats:

MRCXT hierarchies are viewable and incomplete.

- MRCXT was created to provide reasonably viewable hierarchies.
- Many vocabularies do not have full, principled hierarchies
- Many hierarchies have too many children or siblings to be viewable

MRREL relationships are authoritative and complete.

MRLO: Locator

CUI	ISN	/ FR	/UN	SUI	SNA SOUI
C0002871				S035278	7
			*CITATIONS		
C0002871	MEDLINE(1996-Fall 1998)	707	*CITATIONS	S001374	2
C0002871	PDQ			S041488	0
C0002871	QMR			S001378	7

- **CUI** Unique identifier of concept
- ISN Name of information source or database in which concept appears
- FR Frequency count of number of occurrences of concept in the information source (optional)
- **UN** Meaning of frequency (optional)
- SUI Unique identifier of string if name used in information source appears in MRCON (optional)
- SNA Actual name that occurs in the information source if not otherwise present in the Metathesaurus (optional)
- SOUI Unique identifier of record in which the concept appears in source (optional)

MRATX: Mapping one vocabulary to another

```
|REL| ATX
          SAB
CUI
C0494958 MSH2000 S < Kidney Failure, Acute > AND < Kidney Papillary
                    Necrosis>
  "Acute renal failure with medullary necrosis"
   in ICD-9-CM and
                       ICD-10
    CUI
           Unique identifier of concept to which the expression is related
    SAB
           Abbreviation of source of terms in expression
          Relationship of meaning of expression to main concept
    REL
           Associated expression (with complex internal syntax )
   ATX
```

Most Metathesaurus concept <u>do not</u> have ATXs Most are *FROM* ICD-9-CM *TO* MeSH Need feedback on usefulness MRCOC: Co-occurrences

Co-occurrence information:

Most are MEDLINE co-occurrences

Also includes:

Patient record co-occurrences from CCPSS, the Canonical Clinical Problem Statement System from Vanderbilt University

Knowledge base co-occurrences from AI Rheum, a Rheumatology expert system

MRCOC: Co-occurrences (see manual)

```
    CUI1
    CUI2
    SOC
    COT | COF | COA |

    C0002871 | C0000727 | MBD
    L | 1 | BL=1,ET=1 |

    C0002871 | C0000737 | MBD
    L | 1 | ET=1 |

    C0002871 | C0000772 | MBD
    L | 2 | CN=2 |

    C0000731 | C0000737 | CCPSS99 | PP | 10 |
```

CUI1 Unique identifier of first concept

CUI2 Unique identifier of second concept

SOC Abbreviation of the Source of co-occurrence information if applicable

COT Type of co-occurrence

COF Frequency of co-occurrence, if applicable

COA Attributes of co-occurrence, if applicable

Indexes:

MRXW.ENG, MRXW.FRE, Other languages ... lowercased words MRXNW.ENG ... lowercased normalized words MRXNS.ENG ... lowercased normalized strings

Example:

MRCON:

C0026927|ENG|P|L0026927|PF|S1396311|Mycobacteria, Atypical|0|

MRXW.ENG:

ENG|atypical|C0026927|L0026927|S1396311|

ENG|mycobacteria|C0026927|L0026927|S1396311|

MRXNW.ENG:

ENG|atypical|C0026927|L0026927|S1396311|

ENG|mycobacterium|C0026927|L0026927|S1396311|

MRXNS.ENG:

ENG|atypical mycobacterium|C0026927|L0026927|S1396311|

Using Indexes: The Specialist Lexical Programs

- Very powerful, standardized tools are available as part of the UMLS Specialist Lexicon and Lexical Programs
- Source code and binary programs for Unix and NT are included
- "norm" will process your terms and queries to match the Meta indexes
- "lvg" does much more ...
- All are included in the UMLS distribution

Recap: How to Customize the Metathesaurus

- Limit vocabularies, languages
 - MetamorphoSys does this best (demo is next!)
- Use Semantic Types
- Limit and aggregate by Relationships
 - MRREL
- Add and Use Suppressibility
 - MRCON "TS"
- Change Naming Precedence -
 - MetamorphoSys GUI or custom configuration
- Select by attribute e.g. ST
 - MRSAT
- Use other MR Files as needed ...
- Adding "local" terminology (after demo)

Outline of Tutorial

- Why customize *Betsy Humphreys*
- How to customize *Bill Hole*
- A tool to help you customize Laura Roth and Suresh Srinivasan
- Adding "local" terminology Bill Hole

MetamorphoSys

- A tool distributed for use with the UMLS Knowledge Sources
 - Already present in UMLS distribution

■ Multi-platform Java software

Creates a customized version of the Metathesaurus

Why Use MetamorphoSys?

- Exclude vocabularies as required by the UMLS License Agreement
 - Default is to select only vocabularies that have no special restrictions (category zero)
 - Example: Remove SNOMED if user does not have an agreement with CAP for use
- Exclude vocabularies not needed for users' specific purposes
 - Example: Nursing vocabularies

Use (cont'd)

- Alter "preferred name" precedence
 - Precedence is determined by MRRANK table supplied by NLM
 - Highest precedence source provides the "preferred name" of the concept name
 - User may want the preferred names of concepts to be other than the default provided
 - Example: User wants Read vocabulary to be highest precedence source

Use (cont'd)

- Add suppressibility to any Source-TTY combination
 - Metathesaurus already marks some combinations as suppressible by setting TS=s in MRCON
 - Suppressibility allows users to program their applications to remove certain groups of terms that may not be suitable
 - Example: Remove LOINC for Natural Language Processing purposes

How does MetamorphoSys work?

- What it does: removes all information from MR* files that is supplied by the excluded vocabularies
 - Allows added source-termgroup suppressibility
 - Allows altered "preferred name" precedence
- What results: A full Metathesaurus of the remaining vocabularies

How to Use MetamorphoSys

■ Machine requirements

Configuration interface

Demo on subset of Metathesaurus

Machine Requirements

- A minimum of 256 MB of physical memory, as well as 8 GB recommended free disk space
 - Full UMLS distribution needs to be present

■ Can be run on: Sun Solaris, Windows NT, Linux and Windows 98

Configuration Interface

- User sees a Java graphical user interface
- Interactively prompts for information
- Started by the MetamorphoSys program once UMLS distribution has been unpacked
 - Found in UMLS2000/META/METAMSYS/ directory
 - MetamorphoSys.sh in the UNIX environment
 - MetamorphoSys.bat in Windows

Configuration

■ Simple to use

- No configuration needed to exclude all nonzero category vocabularies
 - Default is a Metathesaurus of just category zero vocabularies, i.e., to exclude those with category 1, 2 or 3 restrictions (see License Agreement in Appendix for details)

Configuration

- Four tabs present in the MetamorphoSys interface
 - Files/folders
 - Sources
 - Precedence
 - Term Status

Files/Folders

■ Indicate where UMLS distribution is present on user's machine

 Indicate where the customized Metathesaurus should go once MetamorphoSys is finished

■ Default directories are provided

File Help

Files/folders Sources Precedence Term Status

Please choose the folders to use for the following purposes: (Note that folder (2) below will require about 2699918K

bytes of free space.)

(1) The UMLS installation folder/directory, and

Choose UMLS installation folder...

/UMLS2000/META

Choose target folder...

/UMLS2000/METASUBSET

Sources

■ All sources are alphabetically listed

Ones highlighted are the ones to be excluded

Can change to include or exclude any vocabulary

Sources Configuration

Precedence

- MTH source is the default highest precedence source
- Sources are arranged in list alphabetically and not by precedence
- Highlighting a source will select it as the highest precedence source
 - Only one source can be chosen

UMLS MetamorphoSys Configuration

File Help

Files/folders Sources Precedence Term Status

Select a single source whose terms you want to have the highest precedence, overriding the default. This will cause terms from this source to be used to represent the name of concepts in which they occur. For more complex ordering, please refer to the documentation.

Select Highest Precedence Source

MSH2000 - Medical Subject Headings

MTHCH00 - Methathesaurus CPT Hierarchical Terms

MTHHH00 - Metathesaurus HCPCS Hierarchical Terms

MTH - UMLS Metathesaurus

NAN99 - Classification of Nursing Diagnoses

NCI2000 - NCI Thesaurus

NDDF99 - First DataBank National Drug Data File

NEU99 - Neuronames Brain Hierarchy

NIC99 - Nursing Interventions Classification

NOC97 - Nursing Outcomes Classification

OMS94 - Omaha System


PCDS97 - Patient Care Data Set

PDQ99 - Physician Data Query

PPAC98 - Pharmacy Practice Activity Classification


Term Status

- Used to add suppressibility
- All Source-TTY combinations that are suppressible are highlighted
- Cannot change these to be non-suppressible in interface
- New combinations can be highlighted to make them suppressible



Running MetamorphoSys

 Once configuration is defined, a simple file selection starts subsetting of Metathesaurus



Output

- Once started, a message tells user that the program has started and the interface disappears
- Program exits automatically upon completion of data subsetting
- Your customized Metathesaurus will be present in defined directory
 - UMLS2000/METASUBSET by default

Outline of Tutorial

- Why customize *Betsy Humphreys*
- How to customize *Bill Hole*
- A tool to help you customize
 - Laura Roth and Suresh Srinivasan
- Adding "local" terminology *Bill Hole*

MetamorphoSys Output

Distributed 2000 Metathesaurus Data for C0221233

MRCON

Distributed Data for C0221233...

```
C0221233 ENG | P | L0294378 | PF | S0625803 | Cyclic edema | 3 | C0221233 | ENG | P | L0294378 | VW | S0368795 | EDEMA, CYCLIC | 0 | C0221233 | ENG | P | L0294378 | VW | S0369867 | Edema, cyclic | 3 | C0221233 | ENG | S | L0298620 | PF | S0368798 | EDEMA, PERIODIC | 0 | C0221233 | ENG | S | L0298620 | VC | S0369871 | Edema, periodic | 0 | C0221233 | ENG | S | L0298620 | VW | S0395649 | Periodic, edema | 0 | C0221233 | ENG | S | L0803934 | PF | S0852190 | Cyclic oedema | 3 |
```

```
C0221233 | L0294378 | S0368795 | DXP94 | SY | NOCODE | 0 | C0221233 | L0294378 | S0369867 | SNM2 | PT | M-36680 | 3 | C0221233 | L0294378 | S0625803 | SNM198 | PT | M-36480 | 3 | C0221233 | L0298620 | S0368798 | DXP94 | SY | NOCODE | 0 | C0221233 | L0298620 | S0369871 | ICD91 | IT | 995.1 | 0 | C0221233 | L0298620 | S0395649 | ICD91 | IT | 995.1 | 0 | C0221233 | L0803934 | S0852190 | SNM198 | SY | M-36480 | 3 | C0221233 | L0803934 | S0852190 | SNM198 | SY | M-36480 | 3 | C0221233 | L0803934 | S0852190 | SNM198 | SY | M-36480 | 3 | C0221233 | L0803934 | S0852190 | SNM198 | SY | M-36480 | 3 | C0221233 | L0803934 | S0852190 | SNM198 | SY | M-36480 | 3 | C0221233 | L0803934 | S0852190 | SNM198 | SY | M-36480 | 3 | C0221233 | L0803934 | S0852190 | SNM198 | SY | M-36480 | 3 | C0221233 | L0803934 | S0852190 | SNM198 | SY | M-36480 | 3 | C0221233 | L0803934 | S0852190 | SNM198 | SY | M-36480 | 3 | C0221233 | L0803934 | S0852190 | SNM198 | SY | M-36480 | 3 | C0221233 | L0803934 | S0852190 | SNM198 | SY | M-36480 | 3 | C0221233 | L0803934 | S0852190 | SNM198 | SY | M-36480 | 3 | C0221233 | L0803934 | S0852190 | SNM198 | SY | M-36480 | 3 | C0221233 | L0803934 | S0852190 | SNM198 | SY | M-36480 | 3 | C0221233 | L0803934 | S0852190 | SNM198 | SY | M-36480 | 3 | C0221233 | L0803934 | S0852190 | SNM198 | SY | M-36480 | 3 | C0221233 | L0803934 | S0852190 | SNM198 | SY | M-36480 | 3 | C0221233 | L0803934 | S0852190 | SNM198 | SY | M-36480 | 3 | C0221233 | L0803934 | S0852190 | SNM198 | SY | M-36480 | 3 | C0221233 | C0221233 | L0803934 | S0852190 | SNM198 | SY | M-36480 | 3 | C0221233 |
```

Distributed Data for C0221233...

```
C0013604 | CHD | C0221233 | | SNM2 | SNM2 | |
C0013604 | CHD | C0221233 | | SNMI98 | SNMI98 | |
C0221233 | PAR | C0013604 | | SNM2 | SNM2 | |
C0221233 | PAR | C0013604 | | SNMI98 | SNMI98 | |
C0221233 | RB | C0238094 | MTH | MTH | |
C0238094 | RN | C0221233 | | MTH | MTH | |
```

```
C0221233 | | | DA MTH | 19950417 |
C0221233 | | | MR | MTH | 20000101
C0221233 | | | | ST | MTH | R |
```

1. Default Subset for C0221233

Removing all restricted sources

Default Subset for C0221233 (Before)

```
C0221233 ENG | P | L0294378 | PF | S0625803 | Cyclic edema | 3 | C0221233 | ENG | P | L0294378 | VW | S0368795 | EDEMA, CYCLIC | 0 | C0221233 | ENG | P | L0294378 | VW | S0369867 | Edema, cyclic | 3 | C0221233 | ENG | S | L0298620 | PF | S0368798 | EDEMA, PERIODIC | 0 | C0221233 | ENG | S | L0298620 | VC | S0369871 | Edema, periodic | 0 | C0221233 | ENG | S | L0298620 | VW | S0395649 | Periodic, edema | 0 | C0221233 | ENG | S | L0803934 | PF | S0852190 | Cyclic oedema | 3 |
```

Default Subset for C0221233 (After)

```
MIRRE
```

```
C0221233 | ENG | P | L0294378 | PF | S0368795 | EDEMA, CYCLIC | 0 |
C0221233 ENG | S | L0298620 | PF | S0368798 | EDEMA, PERIODIC | 0 |
C0221233 | ENG | S | L0298620 | VC | S0369871 | Edema, periodic | 0 |
C0221233 | ENG | S | L0298620 | VO | S0395649 | Periodic, edema | 0 |
```

```
C0221233 L0294378 S0368795 DXP94 SY NOCODE 0
C0221233 | L0298620 | S0368798 | DXP94 | SY | NOCODE | 0 |
C0221233 | L0298620 | S0369871 | ICD91 | IT | 995.1 | 0 |
C0221233 | L0298620 | S0395649 | ICD91 | IT | 995.1 | 0 |
```

```
C0221233 | RB | C0238094 | MTH | MTH | |
C0238094 | RN | C0221233 | | MTH | MTH | |
```

2. Altering Precedence for C0221233

Making ICD91 the highest precedence source

Changing Precedence for C0221233 (Before)

VIRCON

```
C0221233 ENG P L0294378 PF S0625803 Cyclic edema 3 C0221233 ENG P L0294378 VW S0368795 EDEMA, CYCLIC O C0221233 ENG P L0294378 VW S0369867 Edema, cyclic S C0221233 ENG S L0298620 PF S0368798 EDEMA, PERIODIC O C0221233 ENG S L0298620 VC S0369871 Edema, periodic O C0221233 ENG S L0298620 VW S0395649 Periodic, edema O C0221233 ENG S L0298620 VW S0395649 Periodic, edema O C0221233 ENG S L0803934 PF S0852190 Cyclic oedema 3
```

```
MIRSO
```

```
C0221233 | L0294378 | S0368795 | DXP94 | SY | NOCODE | 0 | C0221233 | L0294378 | S0369867 | SNM2 | PT | M-36680 | 3 | C0221233 | L0294378 | S0625803 | SNMI98 | PT | M-36480 | 3 | C0221233 | L0298620 | S0368798 | DXP94 | SY | NOCODE | 0 | C0221233 | L0298620 | S0369871 | ICD91 | IT | 995.1 | 0 | C0221233 | L0298620 | S0395649 | ICD91 | IT | 995.1 | 0 | C0221233 | L0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0221233 | L0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0221233 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0221233 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0221233 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0221233 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | C0803934 | SNMI98 | SNMI
```

Changing Precedence for C0221233 (After)

MIRCON

```
MRSO
```

```
C0221233 ENG | L0298620 | F | S0369871 | Edema, periodic | 0 | C0221233 | ENG | P | L0298620 | VC | S0368798 | EDEMA, PERIODIC | 0 | C0221233 | ENG | P | L0298620 | VO | S0395649 | Periodic, edema | 0 | C0221233 | ENG | S | L0294378 | PF | S0625803 | Cyclic edema | 3 | C0221233 | ENG | S | L0294378 | VO | S0368795 | EDEMA, CYCLIC | 0 | C0221233 | ENG | S | L0294378 | VO | S0369867 | Edema, cyclic | 3 | C0221233 | ENG | S | L0803934 | PF | S0852190 | Cyclic oedema | 3 |
```

```
C0221233 | L0294378 | S0368795 | DXP94 | SY | NOCODE | 0 | C0221233 | L0294378 | S0369867 | SNM2 | PT | M-36680 | 3 | C0221233 | L0294378 | S0625803 | SNMI98 | PT | M-36480 | 3 | C0221233 | L0298620 | S0368798 | DXP94 | SY | NOCODE | 0 | C0221233 | L0298620 | S0369871 | ICD91 | IT | 995.1 | 0 | C0221233 | L0298620 | S0395649 | ICD91 | IT | 995.1 | 0 | C0221233 | L0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 |
```

3. Adding Suppressibility for C0221233

Suppressing SNOMED synonyms (SNMI98-SY) strings

Adding Suppressibility for C0221233 (Before)

```
MIRCON
```

```
C0221233 ENG | P | L0294378 | PF | S0625803 | Cyclic edema | 3 | C0221233 | ENG | P | L0294378 | VW | S0368795 | EDEMA, CYCLIC | 0 | C0221233 | ENG | P | L0294378 | VW | S0369867 | Edema, cyclic | 3 | C0221233 | ENG | S | L0298620 | PF | S0368798 | EDEMA, PERIODIC | 0 | C0221233 | ENG | S | L0298620 | VC | S0369871 | Edema, periodic | 0 | C0221233 | ENG | S | L0298620 | VW | S0395649 | Periodic, edema | 0 | C0221233 | ENG | S | L0803934 | PF | S0852190 | Cyclic oedema | 3 | Cyclic oedema | 3 | Cyclic oedema | C0221233 | ENG | S | L0803934 | PF | S0852190 | Cyclic oedema | 3 | Cyclic oedema | C0221233 | ENG | S | L0803934 | PF | S0852190 | Cyclic oedema | Cyclic oedema | C0221233 | ENG | S | L0803934 | PF | S0852190 | Cyclic oedema | Cyclic
```

```
MRSO
```

```
C0221233 | L0294378 | S0368795 | DXP94 | SY | NOCODE | 0 | C0221233 | L0294378 | S0369867 | SNM2 | PT | M-36680 | 3 | C0221233 | L0294378 | S0625803 | SNMI98 | PT | M-36480 | 3 | C0221233 | L0298620 | S0368798 | DXP94 | SY | NOCODE | 0 | C0221233 | L0298620 | S0369871 | ICD91 | IT | 995.1 | 0 | C0221233 | L0298620 | S0395649 | ICD91 | IT | 995.1 | 0 | C0221233 | L0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0221233 | L0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0221233 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0221233 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0221233 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0221233 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | M-36480 | 3 | C0803934 | S0852190 | SNMI98 | SY | SNMI98 |
```

Adding Suppressibility for C0221233 (After)

```
C0221233 ENG | P | L0294378 | PF | S0625803 | Cyclic edema | 3 | C0221233 | ENG | P | L0294378 | VO | S0368795 | EDEMA, CYCLIC | 0 | C0221233 | ENG | P | L0294378 | VO | S0369867 | Edema, cyclic | 3 | C0221233 | ENG | S | L0298620 | PF | S0368798 | EDEMA, PERIODIC | 0 | C0221233 | ENG | S | L0298620 | VC | S0369871 | Edema, periodic | 0 | C0221233 | ENG | S | L0298620 | VO | S0395649 | Periodic, edema | 0 | C0221233 | ENG | S | L0803934 | PF | S0852190 | Cyclic oedema | 3 |
```

```
C0221233 | L0294378 | S0368795 | DXP94 | SY | NOCODE | 0 | C0221233 | L0294378 | S0369867 | SNM2 | PT | M-36680 | 3 | C0221233 | L0294378 | S0625803 | SNM198 | PT | M-36480 | 3 | C0221233 | L0298620 | S0368798 | DXP94 | SY | NOCODE | 0 | C0221233 | L0298620 | S0369871 | ICD91 | IT | 995.1 | 0 | C0221233 | L0298620 | S0395649 | ICD91 | IT | 995.1 | 0 | C0221233 | L0803934 | S0852190 | SNM198 | SY | M-36480 | 3 |
```

MetamorphoSys Configuration

- GUI and "Batch" Components
- Data in the "config" Subdirectory,
 e.g., sources.to.remove, prec.order
- GUI creates "Batch" config files
- Or Hand-Edit and Re-run

Why Hand-Edit?

- Better precedence control
- Saving configuration between runs
- Not for novices!
- Details are on http://umlsinfo.nlm.nih.gov

MetamorphoSys Configuration Files

File	Use	Description
Sources.to.remove	Batch	Abbreviations of all sources that will be removed – one per line;
Prec.order	Batch	Source abbreviation and term type in order of precedence; one per line. Leading asterisk implies suppressible combination
Mmsys.properties	both	Properties file; attribute=value format, e.g., begin=true

MetamorphoSys Help Files

File	Use	Description
Source.txt	GUI	Abbreviation and description of all sources
Sources.category <n></n>	n/a	Abbreviations of sources for each restriction level: 0, 1, 2, 3
Prec.txt	GUI	Source and term types in NLM's default order of precedence

sources.to.remove file

- Default is to remove all sources with restriction level>0
- Edit with any text editor add additional source abbreviations (or remove existing ones)
- Ensure that added ones are in source.txt
- Save file prior to re-run

prec.order file

- Order of Source-TTY lines decides precedence (lines in decreasing order of precedence)
- Edit with any text editor to change order
- Make additional ones suppressible by adding a leading '*'
- Save file prior to re-run

Expert(!) Mode Summary

- Edit sources.to.remove, prec.order and mmsys.properties as needed
- Change to installation directory
- Run the "batch" component directly
- Full details on umlsinfo

Post Subset Examples

- Removing Suppressible Synonyms
 - -awk -F'|' '\$3!="s"{print \$1}' MRCON
 - -SELECT CUI FROM MRCON WHERE TS!='s'
- Select concepts by STY
 - -join -F'|' MRSTY MRCON | awk -F'|' '\$2=="Disease or Syndrome" {print \$1}'
 - -SELECT MRCON.CUI FROM MRCON, MRSTY WHERE MRCON.CUI=MRSTY.CUI AND MRSTY.STY='Disease or Syndrome'

Notes

- Resulting STT not always accurate without LVG (see umlsinfo.nlm.nih.gov)
- Sort order By CUI and ASCII within CUI
- Save your configuration files if needed
- Next version will be better!

Outline of Tutorial

- Why customize *Betsy Humphreys*
- How to customize *Bill Hole*
- A tool to help you customize Laura Roth and Suresh Srinivasan
- Adding "local" terminology Bill Hole

Adding Terminology

Create Distinct Unique Identifiers for *your* Terminology...

- e.g., for your concepts, use:
 'CA000001' as CUIs instead
 of Meta's 'C0000001' for CUIs
- Similarly, use 'LA000001 ...' for LUIs and 'SA000001 ...' for SUIs, as needed
- Create a table recording your UIs, and for mapping them to UMLS UIs

Adding Terminology, Continued Which of your terms are Meta Synonyms?

- Normalize them and look for matches in the Normalized String Index (MRXNS).
- Use other sensible approaches to searching:
 - normalized word searches;
 - explore alternate naming styles and conventions
- Use Meta CUIs for Synonyms

* See "Discovering Missed Synonymy in a Large Concept-Oriented Metathesaurus" - AMIA 2000 paper (Session S7)

Adding Terminology, Continued

Bonus - add relationships ...

As you look for Meta Synonyms, add relationships to Meta

Assign a REL and RELA to label the particular kinds of relationships you need and will use,
 e.g. to map or aggregate

Updating to a New Meta Release

- Repeat MetamorphoSys processing scripts from previous release
- Re-use previously found UIs for your terms to map synonyms, etc.
- Check for new synonyms of your terms which were not Meta synonyms before
- Check for any deleted CUIs and map them

Incremental updates are coming!

Same procedures will apply to the changes

- Update consists of deletes and adds only;
- Any changed concept is deleted, then added with the changes
- Any deleted concept is deleted
- Any new Concept is added

Online Resources:

WWW:

http://www.nlm.nih.gov/research/umls/ http:// umlsks.nlm.nih.gov http:// umlsinfo.nlm.nih.gov

E-mail:

umlsmeta@nlm.nih.gov umlslex@nlm.nih.gov umlsnet@nlm.nih.gov umlsks@nlm.nih.gov

umls-users listserv:

To subscribe to the listsery, send a message to

listserv@nlm.nih.gov

which includes the following line:

subscribe umls-users

To post a message to the umls-users listsery AFTER subscribing: send email to: umls-users@nlm.nih.gov