FFIEC 031 and 041 CONTENTS

Instructions for Preparation of Consolidated Reports of Condition and Income (FFIEC 031 and 041)

CONTENTS

GENERAL INSTRUCTIONS

Who Must Report on What Forms	1
Close of Business	1
Frequency of Reporting	2
Differences in Detail of Reports	2
Shifts in Reporting Status	3
Organization of the Instruction Books	4
Preparation of the Reports	5
Internet Web Addresses	5
Signatures	5
Officer Declaration	5
Director Attestation	6
Submission of the Reports	6
Submission Date	7
Amended Reports	7
Scope of the "Consolidated Bank" Required to be Reported in the Submitted Reports	8
Exclusions from the Coverage of the Consolidated Report	8
Rules of Consolidation	9
Reporting by Type of Office	10
Publication Requirements for the Report of Condition	10
Release of Individual Bank Reports	11
Applicability of Generally Accepted Accounting Principles to Regulatory Reporting Requirements	11
Accrual Basis Reporting	12
Miscellaneous General Instructions	12
Rounding	12
Negative Entries	12
Verification	13
Transactions Occurring Near the End of a Reporting Period	13
Separate Branch Reports	14

ı	INE	ITEM	INISTR	LICTIONS	FOR THE	CONSOLIDATED	REPORT OF	INCOM

Schedule RI Income Statement	RI-1
Schedule RI-A Changes in Equity Capital	RI-A-1
Schedule RI-B Charge-offs and Recoveries and Changes in Allowance for Loan and Lease Losses	
Part I. Charge-offs and Recoveries on Loans and Leases	RI-B-1
Part II. Changes in Allowance for Loan and Lease Losses	RI-B-6
Schedule RI-D Income from International Operations (FFIEC 031 only)	RI-D-1
Schedule RI-E Explanations	RI-E-1
LINE ITEM INSTRUCTIONS FOR THE CONSOLIDATED REPORT OF CONDITION	
Schedule RC Balance Sheet	RC-1
Schedule RC-A – Cash and Balances Due from Depository Institutions	RC-A-1
Schedule RC-B Securities	RC-B-1
Schedule RC-C Loans and Lease Financing Receivables	
Part I. Loans and Leases	RC-C-1
Part II. Loans to Small Businesses and Small Farms	RC-C-30
Schedule RC-D Trading Assets and Liabilities	RC-D-1
Schedule RC-E Deposit Liabilities	RC-E-1
Schedule RC-F Other Assets	RC-F-1
Schedule RC-G Other Liabilities	RC-G-1
Schedule RC-H Selected Balance Sheet Items for Domestic Offices (FFIEC 031 only)	RC-H-1
Schedule RC-I Assets and Liabilities of IBFs (FFIEC 031 only)	RC-I-1
Schedule RC-K Quarterly Averages	RC-K-1
Schedule RC-L – Derivatives and Off-Balance Sheet Items	RC-L-1
Schedule RC-M Memoranda	RC-M-1
Schedule RC-N Past Due and Nonaccrual Loans, Leases, and Other Assets	RC-N-1
Schedule RC-O Other Data for Deposit Insurance and FICO Assessments	RC-O-1
Schedule RC-R Regulatory Capital	RC-R-1
Schedule RC-S – Securitization and Asset Sale Activities	RC-S-1
Schedule RC-T – Fiduciary and Related Services	RC-T-1
Optional Narrative Statement Concerning the Amounts Reported in the Reports of Condition and Income	RC-X-1

FFIEC 031 and 041 CONTENTS

GLOSSARY

Accounting Changes	A-1
Acquisition, Development, or Construction (ADC) Arrangements	A-3
Allowance for Loan and Lease Losses	A-3
Bankers Acceptances	A-4
Banks, U.S. and Foreign	A-7
Borrowings and Deposits in Foreign Offices	A-9
Brokered Deposits	A-10
Broker's Security Draft	A-11
Business Combinations	A-11
Capitalization of Interest Costs	A-13
Cash Management Arrangements	A-14
Commercial Paper	A-15
Commodity or Bill-of-Lading Draft	A-15
Coupon Stripping, Treasury Receipts, and STRIPS	A-15
Custody Account	A-16
Dealer Reserve Account	A-16
Depository Institutions in the U.S.	A-16
Deposits	A-17
Derivative Contracts	A-25
Dividends	A-32
Domestic Office	A-32
Domicile	A-32
Due Bills	A-33
Edge and Agreement Corporation	A-33
Equity Method of Accounting	A-33
Extinguishments of Liabilities	A-33
Extraordinary Items	A-34
Fails	A-34
Federal Funds Transactions	A-34
Federally-Sponsored Lending Agency	A-35
Foreclosed Assets	A-35
Foreign Currency Transactions and Translation	A-38
Foreign Debt Exchange Transactions	A-39
Foreign Governments and Official Institutions	A-40
Foreign Office	A-40
Hypothecated Deposit	A-41
Income Taxes	A-41
Internal-Use Computer Software	A-48
International Banking Facility (IBF)	A-49

GLOSSARY (cont.)	
Lease Accounting	A-51
Letter of Credit	A-53
Loan	A-54
Loan Fees	A-55
Loan Impairment	A-57
Loan Secured by Real Estate	A-58
Loss Contingencies	A-58
Mandatory Convertible Debt	A-59
Market Value of Securities	A-59
Nonaccrual of Interest	A-59
Offsetting	A-62
Overdraft	A-63
Pass-through Reserve Balances	A-64
Placements and Takings	A-65
Preferred Stock	A-65
Premiums and Discounts	A-65
Reciprocal Balances	A-66
Repurchase/Resale Agreements	A-66
Sales of Assets for Risk-Based Capital Purposes	A-68
Securities Activities	A-72
Securities Borrowing/Lending Transactions	A-73
Servicing Assets and Liabilities	A-74
Shell Branches	A-75
Short Position	A-75
Start-Up Activities	A-75
Subordinated Notes and Debentures	A-76
Subsidiaries	A-76
Suspense Accounts	A-77
Syndications	A-78
Trade Date and Settlement Date Accounting	A-78
Trading Account	A-78
Transfers of Financial Assets	A-79
Treasury Stock	A-82
Troubled Debt Restructurings	A-83
U.S. Territories and Possessions	A-84
Valuation Allowance	A-84
When-Issued Securities Transactions	A-84

INDEX

GENERAL INSTRUCTIONS

Schedules RC and RC-A through RC-T constitute the Report of Condition and its supporting schedules. Schedules RI, RI-A, RI-B, RI-D, and RI-E constitute the Report of Income and its supporting schedules.

WHO MUST REPORT ON WHAT FORMS

Every national bank, state member bank, and insured state nonmember bank is required to file consolidated Reports of Condition and Income normally as of the close of business on the last calendar day of each calendar quarter, i.e., the report date. The specific reporting requirements depend upon the size of the bank and whether it has any foreign offices. Banks must file the appropriate forms as described below:

- (1) BANKS WITH FOREIGN OFFICES: Banks of any size that have any "foreign" offices (as defined below) must file quarterly the Consolidated Reports of Condition and Income for a Bank with Domestic and Foreign Offices (FFIEC 031). For purposes of these reports, all of the following constitute "foreign" offices:
 - (a) an International Banking Facility (IBF);
 - (b) a branch or consolidated subsidiary in a foreign country, Puerto Rico, or a U.S. territory or possession; and
 - (c) a majority-owned Edge or Agreement subsidiary.

However, for purposes of these reports, a branch at a U.S. military facility located in a foreign country is a "domestic" office.

(2) BANKS WITHOUT FOREIGN OFFICES: Banks of any size that have only domestic offices must file quarterly the Consolidated Reports of Condition and Income for a Bank with Domestic Offices Only (FFIEC 041).

Close of Business

The term "close of business" refers to the time established by the reporting bank as the cut-off time for receipt of work for posting transactions to its general ledger accounts for that day. The time designated as the close of business should be reasonable and applied consistently. The posting of a transaction to the general ledger means that both debit and credit entries are recorded as of the same date. In addition, entries made to general ledger accounts in the period subsequent to the close of business on the report date that are applicable to the period covered by the Reports of Condition and Income (e.g., adjustments of accruals, posting of items held in suspense on the report date to their proper accounts, and other quarter-end adjusting entries) should be reported in the Reports of Condition and Income as if they had actually been posted to the general ledger at or before the cut-off time on the report date.

With respect to deposits received by the reporting bank after the cut-off time for posting them to individual customer accounts for a report date (i.e., so-called "next day deposits" or "late deposits"), but which are nevertheless posted in any manner to the reporting bank's general ledger accounts for that report date (including, but not limited to, through the use of one or more general ledger contra accounts), such deposits must be reported in (1) Schedule RC, Balance Sheet, item 13, "Deposits," and in Schedule RC-E, Deposit Liabilities, or (2) in Schedule RC-O, Other Data for Deposit Insurance and FICO Assessments, item 2, "Unposted credits." The use of memorandum accounts outside the reporting bank's general ledger system for control over "next day" or "late deposits" received on the report date will not cause such deposits to be reportable in Schedules RC and RC-E or Schedule RC-O.

Frequency of Reporting

The reports are required to be submitted quarterly by all banks. However, some schedules are required on a less frequent basis, as follows:

- (1) For all banks, Schedule RC-C, part II, Loans to Small Businesses and Small Farms, is to be filed *only* as of the June 30 report date.
- (2) Effective March 31, 2002, banks with total fiduciary assets greater than \$250 million (as of the preceding December 31) or with gross fiduciary and related services income greater than 10 percent of revenue (net interest income plus noninterest income) for the preceding calendar year must complete the applicable items of Schedule RC-T quarterly. All other banks with fiduciary powers must complete the applicable items of Schedule RC-T annually as of the December 31 report date. In 2001, all banks with fiduciary powers must complete the applicable items of Schedule RC-T as of the December 31 report date only.

In addition, the following items are to be completed annually rather than quarterly:

- (1) Schedule RC, Memorandum item 1, on the level of external auditing work performed for the bank is to be reported as of the March 31 report date;
- (2) Schedule RC-O, Memorandum item 1.a.(2), "Number of deposit accounts of\$100,000 or less" (in domestic offices), is to be reported as of the June 30 report date; and
- (3) Schedule RC-E, Memorandum item 1.e, "Preferred deposits," is to be reported as of the December 31 report date.

Differences in Detail of Reports

The amount of detail required to be reported varies between the two versions of the report forms, with the report forms for banks with foreign offices (FFIEC 031) having more detail than the report forms for banks with domestic offices only (FFIEC 041). Furthermore, as discussed below under Shifts in Reporting Status, the amount of detail varies within the FFIEC 041 report form, primarily based on the size of the bank. In general, the FFIEC 041 report form requires the least amount of detail from banks with less than \$100 million in total assets.

Differences in the level of detail within both the FFIEC 031 and 041 report forms are as follows:

- (1) banks reporting average trading assets of \$2 million or more for any quarter of the preceding calendar year must complete Schedule RC-D, Trading Assets and Liabilities, and provide a breakdown of their trading revenue by risk exposure in Schedule RI, Memorandum item 8, "Trading revenue;"
- (2) banks with financial subsidiaries must complete certain additional items in Schedule RC-R, Regulatory Capital;
- (3) banks servicing more than \$10 million in financial assets other than 1-4 family residential mortgages must report the volume of such servicing in Schedule RC-S, Memorandum item 2.c; and

_

¹ For the March 31, 2001, report date only, if the bank's servicing volume is less than or equal to 10 percent of total assets, Memorandum item 2.c need not be completed.

(4) banks with total fiduciary assets greater than \$100 million (as of the preceding December 31) or with gross fiduciary and related services income greater than 10 percent of revenue (net interest income plus noninterest income) for the preceding calendar year must report information on their fiduciary and related services income and on fiduciary settlements and losses in Schedule RC-T.

In addition, within the FFIEC 031 report form, banks whose international operations account for more than 10 percent of total revenues, total assets, or net income must complete Schedule RI-D, Income from International Operations.

Shifts in Reporting Status

All shifts in reporting status within the FFIEC 041 report form (except as noted below) are to begin with the March Reports of Condition and Income. Such a shift will take place only if the reporting bank's total assets (or, in one case, loans) as reflected in the Report of Condition for June of the previous calendar year equal or exceed the following criteria:

- (1) When total assets exceed \$100 million, a bank must begin to complete:
 - Schedule RI, Memorandum items 9.a through 9.c, which provide detail on the "Impact on income of derivatives held for purposes other than trading;"
 - > Schedule RC-K, items 7 and 13, for the quarterly averages of "Trading assets" and "Other borrowed money;"
 - Schedule RC-L, item 5, "Participations in acceptances conveyed to others by the reporting bank;" and
 - Schedule RC-L, item 14, which provides detail on the fair values of derivative contracts.
- (2) When loans to finance agricultural production and other loans to farmers exceed 5 percent of total loans, net of unearned income, at a bank with less than \$300 million in total assets, the bank must begin to report the following information for these agricultural loans: interest and fee income, quarterly average, past due and nonaccrual loans, and charge-offs and recoveries.
- (3) When total assets exceed \$300 million, a bank must begin to complete:
 - Certain items providing additional detail on the composition of the loan and lease portfolio in Schedule RC-C, part I, Loans and Leases; past due and nonaccrual loans and leases in Schedule RC-N; and loan and lease charge-offs and recoveries in Schedule RI-B, part I;
 - > Schedule RC-A, Cash and Balances Due From Depository Institutions;
 - > Schedule RC-N, Memorandum item 5, on past due derivative contracts; and
 - Schedule RI, Memorandum item 10, "Credit losses on derivatives."

Furthermore, on the FFIEC 041 report form during 2001, banks with less than \$25 million in total assets are not required to report loan income and loan averages by loan category. Effective March 31, 2002, these banks must begin to report this loan information by loan category.

Once a bank surpasses the \$100 million or \$300 million total asset threshold or the agricultural loan percentage threshold and begins to report the additional required information described above, it *must* continue to report the additional information in subsequent years without regard to whether it later falls below the total asset or loan percentage threshold.

-

² In addition, for the March 31, 2001, report date only, banks with less than \$300 million in total assets need not complete Schedule RC-S, Memorandum item 5, on securitized credit cards and related plans. This Memorandum item will not be collected after March 31, 2001.

Other shifts in reporting status occur when:

(1) A bank with domestic offices only establishes or acquires any "foreign" office. The bank must begin filing the FFIEC 031 report form (Consolidated Reports of Condition and Income for a Bank with Domestic and Foreign Offices) for the first quarterly report date following the commencement of operations by the "foreign" office. However, a bank with "foreign" offices that divests itself of all its "foreign" offices must continue filing the FFIEC 031 report form through the end of the calendar year in which the cessation of all operations of its "foreign" offices was completed.

(2) A bank is involved in a business combination (poolings of interests, purchase acquisitions, or reorganizations) or branch acquisition. Beginning with the first quarterly report date following the effective date of a business combination involving a bank and one or more other depository institutions, the resulting bank, regardless of its size prior to the business combination, must (a) file the FFIEC 031 report form if it acquires any "foreign" office, or (b) report the additional required information described above on the FFIEC 041 report form if its total assets or agricultural loans after the consummation of the transaction surpass the \$100 million or \$300 million total asset threshold or the agricultural loan percentage.

In addition, beginning with the first quarterly report date after an operating depository institution that was not previously a member of the FDIC becomes an FDIC-insured bank, it must (a) file the FFIEC 031 report form if it has any "foreign" office, or (b) report the additional required information described above on the FFIEC 041 report form based on its total assets and agricultural loans at the time it becomes an FDIC-insured bank.

ORGANIZATION OF THE INSTRUCTION BOOKS

This instruction book covers both the FFIEC 031 and 041 report forms. It is divided into the following sections:

- (1) The General Instructions describe overall reporting requirements.
- (2) The Line Item Instructions for each schedule of the Report of Income.
- (3) The Line Item Instructions for each schedule of the Report of Condition.
 - The instructions and definitions in sections (2) and (3) are not necessarily self-contained; reference to more detailed treatments in the Glossary may be needed.
- (4) The Glossary presents, in alphabetical order, definitions and discussions of accounting issues and other topics that require more extensive treatment than is practical to include in the line item instructions or that are relevant to several line items or to the overall preparation of these reports. The Glossary is not, and is not intended to be, a comprehensive discussion of the principles of bank accounting or reporting.

In determining the required treatment of particular transactions or portfolio items or in determining the definitions and scope of the various items, the General Instructions, the line item instructions, and the Glossary (all of which are extensively cross-referenced) must be used jointly. A single section does not necessarily give the complete instructions for completing all the items of the reports.

Banks may obtain additional copies of the instruction books from their appropriate federal bank supervisory agency -- the Federal Reserve Banks, the Comptroller of the Currency, or the Federal Deposit Insurance Corporation. The instructions are also available on the Internet at the FFIEC's Web site (www.ffiec.gov) and at the FDIC's Web site (www.fdic.gov).

PREPARATION OF THE REPORTS

Banks are required to prepare and file the Reports of Condition and Income in accordance with these instructions. All reports shall be prepared in a consistent manner.

The bank's financial records shall be maintained in such a manner and scope so as to ensure that the Reports of Condition and Income can be prepared and filed in accordance with these instructions and reflect a fair presentation of the bank's financial condition and results of operations.

Questions and requests for interpretations of matters appearing in any part of these instructions should be addressed to the bank's primary federal bank supervisory agency (i.e., the Federal Reserve Banks, the Comptroller of the Currency, or the Federal Deposit Insurance Corporation). Such inquiries will be referred for resolution to the Reports Task Force of the Federal Financial Institutions Examination Council. Regardless of whether a bank requests an interpretation of a matter appearing in these instructions, when a bank's primary federal bank supervisory agency's interpretation of the instructions differs from the bank's interpretation, the supervisory agency may require the bank to prepare its Reports of Condition and Income in accordance with the agency's interpretation and to amend previously submitted reports.

Internet Web Addresses

Banks with an Internet Web site or home page must report the primary Web address for their site as part of the submission of their Reports of Condition and Income. On the report forms, the location for disclosing this address is on the cover page below the FDIC Certificate Number. Web addresses should not exceed 75 characters in length. Because Web addresses reported on the Reports of Condition and Income are publicly available, each bank should ensure that it accurately reports its Web address, if any. Banks should not provide an e-mail address in the space for the Web address.

The primary Internet Web address is the public Internet site address (also known as the Uniform Resource Locator or URL) that a bank's customer or potential customer enters into Internet browser software in order to find the first page of the bank's Web site. Examples are www.bank.com, www.isp.com/bank/, and bank.isp.com. When entering a Web address on the report form, the Web address should not be prefaced with http:// because this is already included on the form. If a bank does not have its own Web site or home page, but information on or functions of the bank can be accessed through an affiliate's Web address, that affiliate's primary Web address should be reported. A bank that maintains more than one Web site should provide the Web address that best represents the institution.

If a bank has no Web site or home page of its own and the bank cannot be accessed through an affiliate's Web address, the Web address item should be left blank.

SIGNATURES

Either the cover (signature) page of the agency-supplied sample set of report forms, a photocopy of this cover page, or a copy of the cover page printed from the bank's report preparation software or from the FFIEC's or the FDIC's Web site should be used to fulfill the signature and attestation requirement.

Officer Declaration

A duly authorized officer of the bank shall sign a declaration on the cover (signature) page concerning the preparation of the Reports of Condition and Income that the bank has filed with the appropriate supervisory agency.

Director Attestation

National and state member banks -- The correctness of the Report of Condition shall be attested to by at least three directors of the reporting bank, other than the officer signing the officer declaration, as indicated on the cover (signature) page.

State nonmember banks -- The correctness of the Report of Condition shall be attested to by at least two directors of the reporting bank, other than the officer signing the officer declaration, as indicated on the cover (signature) page.

SUBMISSION OF THE REPORTS

Each bank must file its Reports of Condition and Income in one of the following two ways:

- A bank may use computer software to prepare its report and then file the report directly with the banking agencies' electronic collection agent, Electronic Data Systems Corporation (EDS). The bank can send the data file containing its Reports of Condition and Income to EDS electronically by modem or on a computer diskette.
- The institution may complete its reports in paper form and arrange with EDS, a Call Report software vendor, or another party to convert its paper reports to electronic form. If a party other than EDS performs this service, that party must electronically transmit the data file containing the bank's Reports of Condition and Income to EDS.

The filing of Reports of Condition and Income in paper form directly with the FDIC (for national and FDIC-supervised banks) or with the appropriate Federal Reserve District Bank (for state member banks) is not an acceptable method of submission.

Regardless of the method a bank uses to file its Reports of Condition and Income, the bank remains responsible for the accuracy of the data in its Reports of Condition and Income.

In order to file its completed reports with EDS using a computer and modem or to send EDS a computer diskette, banks must use computer software that has been certified for this purpose by EDS. Certified software is available through certain vendors that have completed a certification process. Alternatively, banks may develop their own reporting software and go through the certification process.

Reports submitted in automated form using software that has not been certified will not be accepted by EDS, the banking agencies' collection agent, and resubmission using certified software will be necessary. In addition, reports sent to EDS on computer diskettes that EDS cannot read will not be accepted and resubmission will be necessary. In either case, if such resubmission is received by EDS after the submission date for the report (as defined below), the submitting bank may be subject to the penalties prescribed for late submission.

Each bank is responsible for ensuring that the report form used each quarter is the appropriate form for the bank to use (i.e., FFIEC 031 or 041) for that report date and reflects fully and accurately the item reporting requirements for that report date, including any changes that may be made from time to time. This responsibility cannot be transferred or delegated to servicers or others outside the reporting bank.

A bank filing its Reports of Condition and Income with EDS electronically or under the paper-based alternative must maintain in its files a signed and attested record of its completed report each quarter. This record should be either a computer printout showing at least the caption of each item in the Reports of Condition and Income and the reported amount, a computer-generated facsimile of the report form, or a copy of the printed report form. The signed cover page, as discussed under Signatures above, should be attached to the printout, computer-generated facsimile, or copy of the form that the bank places in its files.

No item on the Reports of Condition and Income is to be left blank unless otherwise indicated in the instructions. Except in those instances, an entry must be made for each item, i.e., an amount, a zero, the word "none," an "X," or an "N/A."

State banks should refer to their appropriate state bank supervisory authority for information concerning state requirements for submitting copies of the Reports of Condition and Income filed with federal bank supervisory authorities.

Submission Date

The term "submission date" is defined as the date by which a bank's completed Reports of Condition and Income must be received in automated form by EDS, the banking agencies' electronic collection agent. EDS must receive the data file for a bank's Reports of Condition and Income no more than 30 calendar days after the report date (subject to the timely filing provisions for computer diskettes set forth in the following paragraph). For example, the March 31 report must be received by April 30 and the June 30 report by July 30. Earlier submission would aid the banking agencies in editing and reviewing the reports and is encouraged. No extensions of time for submitting reports are granted.

Any bank using the paper-based filing alternative must ensure that it delivers its hard-copy reports to the party with whom it has contracted for the conversion of its reports to automated form in sufficient time for that party to electronically transmit the reports to EDS by the submission deadline.

The filing of a bank's completed Reports of Condition and Income on a computer diskette will be considered timely, regardless of when the reports are received by EDS, if the computer diskette is mailed first class and postmarked no later than the third calendar day preceding the submission deadline. In the absence of a postmark, a bank whose computer diskette containing its completed Reports of Condition and Income is received late may be called upon to provide proof of timely mailing. A "Certificate of Mailing" (U.S. Postal Service Form 3817) may be used to provide such proof. If an overnight delivery service is used, the placement of the computer diskette into the delivery system on the day before the submission deadline will constitute timely submission.

15-day extension -- Any bank which has or has had more than one foreign office, other than a "shell" branch or an IBF, may take an additional 15 days to submit its Reports of Condition and Income. Such banks are urged to use the additional time only if absolutely necessary and to make every effort to report as soon as possible, preferably within the 30-day submission period. Any bank that uses any of the additional 15 calendar days allowed for the completion of its Reports of Condition and Income is required to electronically transmit its completed reports to EDS, the banking agencies' collection agent, no more than 45 calendar days after the report date.

Amended Reports

A bank's primary federal bank supervisory authority may require the filing of amended Reports of Condition and Income if reports as previously submitted contain significant errors, as determined by the supervisory authority, in how the reporting bank classified or categorized items in the reports, i.e., on what line of the report an item has been reported.

When dealing with the recognition and measurement of events and transactions in the Reports of Condition and Income, amended reports may be required if a bank's primary federal bank supervisory authority determines that the reports as previously submitted contain errors that are material for the reporting bank. Materiality is a qualitative characteristic of accounting information which is defined in FASB Concepts Statement No. 2 as "the magnitude of an omission or misstatement of accounting information that, in the light of surrounding circumstances, makes it probable that the judgment of a

reasonable person relying on the information would have been changed or influenced by the omission or misstatement."

After a bank begins filing its Reports of Condition and Income in automated form with EDS, it should send any amendments to previously submitted hard-copy (paper) reports directly to the FDIC (for national and FDIC-supervised banks) or the appropriate Federal Reserve District Bank (for state member banks) in hard-copy form.

SCOPE OF THE "CONSOLIDATED BANK" REQUIRED TO BE REPORTED IN THE SUBMITTED REPORTS

In their Reports of Condition and Income submitted to the federal bank supervisory agencies, banks and their subsidiaries shall present their financial condition and results of operations on a consolidated basis in accordance with generally accepted accounting principles. All significant majority-owned subsidiaries shall be consolidated unless the subsidiary is covered by one of the exceptions listed in the "Exclusions from the Coverage of the Consolidated Report" section below. (See the Glossary entry for "subsidiaries" for the definition of "significant subsidiary.") Accordingly, the Consolidated Reports of Condition and Income shall consolidate the operations of:

- (1) the bank's head office;
- (2) all branches of the bank, domestic and foreign;
- (3) any International Banking Facility (IBF) established by the bank;
- (4) all majority-owned Edge and Agreement subsidiaries, including their IBFs, their foreign and domestic branches, and their significant subsidiaries;
- (5) all majority-owned foreign banks held directly by the reporting bank pursuant to Section 25 of the Federal Reserve Act;
- (6) all other majority-owned subsidiaries that are "significant," including domestic subsidiaries that are commercial banks, savings banks, or savings and loan associations that must file separate Reports of Condition and Income (or separate reports of a comparable nature) with any state or federal financial institutions supervisory authority; and
- (7) all nonsignificant majority-owned subsidiaries that the bank has elected to consolidate on a consistent basis in both the Report of Condition and the Report of Income.

Each bank shall account for any investments in unconsolidated subsidiaries, associated companies, and those corporate joint ventures over which the bank exercises significant influence according to the equity method of accounting. The equity method of accounting is described in Schedule RC-M, item 4. (Refer to the Glossary entry for "subsidiaries" for the definitions of the terms subsidiary, associated company, and corporate joint venture.)

Exclusions from the Coverage of the Consolidated Report

Subsidiaries held on a temporary basis -- If control of a majority-owned subsidiary by the parent bank is likely to be temporary or does not rest with the parent bank because of legal or other reasons (e.g., the subsidiary is in bankruptcy), the subsidiary is not to be consolidated for purposes of the report. Thus, the bank's investments in such subsidiaries are not eliminated in consolidation but will be reflected in the reports in the balance sheet item for "Investments in unconsolidated subsidiaries and associated companies" (Schedule RC, item 8) and other transactions of the bank with such subsidiaries will be

reflected in the appropriate items of the reports in the same manner as transactions with unrelated outside parties. Additional guidance on this topic is provided in accounting standards, including Financial Accounting Standards Board Statement No. 94 and SEC Staff Accounting Bulletin No. 92.

Trust accounts -- For purposes of the Reports of Condition and Income, the reporting bank's trust department is not to be consolidated into the reporting bank's balance sheet or income statement. However, information concerning the bank's trust activities must be reported in Schedule RC-T, Fiduciary and Related Services, beginning December 31, 2001. Assets held in or administered by the bank's trust department and the income earned on such assets are excluded from all of the other schedules of the Reports of Condition and Income except when trust funds are deposited by the trust department of the reporting bank in the commercial or some other department of the reporting bank.

When such trust funds are deposited in the bank, they are to be reported as deposit liabilities in Schedule RC-E in the deposit category appropriate to the beneficiary. Interest paid by the bank on such deposits is to be reported as part of the reporting bank's interest expense.

However, there are two exceptions:

- (1) uninvested trust funds (cash) held in the bank's trust department, which are not included on the balance sheet of the reporting bank, must be reported in Schedule RC-O, Other Data for Deposit Insurance and FICO Assessments; and
- (2) the fees earned by the trust department for its fiduciary activities and the operating expenses of the trust department are to be reported in the bank's income statement (Schedule RI) on a gross basis as if part of the consolidated bank.

Custody accounts -- All custody and safekeeping activities (i.e., the holding of securities, jewelry, coin collections, and other valuables in custody or in safekeeping for customers) are not to be reflected on any basis in the balance sheet of the Report of Condition unless cash funds held by the bank in safekeeping for customers are commingled with the general assets of the reporting bank. In such cases, the commingled funds would be reported in the Report of Condition as deposit liabilities of the bank.

RULES OF CONSOLIDATION

For purposes of these reports, all offices (i.e., branches, subsidiaries, and IBFs) that are within the scope of the consolidated bank as defined above are to be reported on a consolidated basis. Unless the report form captions or the line item instructions specifically state otherwise, this consolidation shall be on a line-by-line basis, according to the caption shown. As part of the consolidation process, the results of all transactions and all intercompany balances (e.g., outstanding asset/debt relationships) between offices, subsidiaries, and other entities included in the scope of the consolidated bank are to be eliminated in the consolidation and must be excluded from the Consolidated Reports of Condition and Income. (For example, eliminate in the consolidation (1) loans made by the bank to a consolidated subsidiary and the corresponding liability of the subsidiary to the bank, (2) a consolidated subsidiary's deposits in the bank and the corresponding cash or interest-bearing asset balance of the subsidiary, and (3) the intercompany interest income and expense related to such loans and deposits of the bank and its consolidated subsidiary.)

Subsidiaries of subsidiaries -- For a subsidiary of a bank which is in turn the parent of one or more subsidiaries:

(1) Each subsidiary shall consolidate its majority-owned subsidiaries in accordance with the consolidation requirements set forth above.

(2) Each subsidiary shall account for any investments in unconsolidated subsidiaries, corporate joint ventures over which the bank exercises significant influence, and associated companies according to the equity method of accounting.

Minority interests -- A minority interest arises when the reporting bank owns less than 100 percent of the stock of a consolidated subsidiary. The minority interest consists of the shares of stock not owned by the reporting bank. Report minority interests in the reporting bank's consolidated subsidiaries in Schedule RC, item 22, "Minority interest in consolidated subsidiaries," of the Report of Condition. Report income (or loss) associated with such minority interests in Schedule RI, item 5.I, "Other noninterest income," of the Report of Income.

Intrabank transactions -- (For banks with foreign offices.) While all intrabank transactions are to be excluded from the Consolidated Reports of Condition and Income, one intrabank relationship that is eliminated in consolidation is required to be identified and reported in the Report of Condition. Specifically, Schedule RC-H, Selected Balance Sheet Items for Domestic Offices, requires the reporting of the net amount of "due from" or "due to" balances between the domestic offices and the foreign offices of the consolidated bank.

Deposit insurance and FICO assessments -- For domestic offices of the reporting bank and for insured branches in Puerto Rico and U.S. territories and possessions, all deposits of subsidiaries that are consolidated and, therefore, eliminated from reported deposits (Schedule RC, item 13.a or 13.b, as appropriate) must be reported in Schedule RC-O, item 4.a or 4.b, as appropriate. Similarly, the interest accrued and unpaid on these deposits, which is eliminated in consolidation from reported other liabilities (Schedule RC, item 20), must be reported in Schedule RC-O, item 4.c.

Cutoff dates for consolidation -- All branches must be consolidated as of the report date. For purposes of consolidation, the date of the financial statements of a *subsidiary* should, to the extent practicable, match the report date of the parent bank, but in no case differ by more than 93 days from the report date.

REPORTING BY TYPE OF OFFICE (For banks with foreign offices)

Some information in the Reports of Condition and Income is to be reported by type of office (e.g., for domestic offices, for foreign offices, or for IBFs) as well as for the consolidated bank. Where information is called for by type of office, the information reported shall be the office component of the consolidated item unless otherwise specified in the line item instructions. That is, as a general rule, the office information shall be reported at the same level of consolidation as the fully consolidated statement, shall reflect only transactions with parties outside the scope of the consolidated bank, and shall exclude all transactions between offices of the consolidated bank as defined above.

PUBLICATION REQUIREMENTS FOR THE REPORT OF CONDITION

There are no federal requirements for a bank to publish the balance sheet of the Report of Condition in a newspaper. However, state-chartered banks should consult with their state banking authorities concerning the applicability of any state publication requirements.

FFIEC 031 and 041 10 GENERAL INSTRUCTIONS

RELEASE OF INDIVIDUAL BANK REPORTS

All schedules of the Reports of Condition and Income submitted by each reporting bank, including the optional narrative statement at the end of the Report of Condition, are available to the public from the federal bank supervisory agencies with the exception of the sections of Schedule RC-T, Fiduciary and Related Services, on fiduciary and related services income (items 12 through 23) and fiduciary settlements, surcharges, and losses (Memorandum item 4). In addition, data reported in Schedule RC-N, Past Due and Nonaccrual Loans, Leases, and Other Assets, in column A, "Past due 30 through 89 days and still accruing," and in all of Memorandum item 1, "Restructured loans and leases included in Schedule RC-N above," will not be publicly disclosed on an individual bank basis for periods prior to March 31, 2001.

APPLICABILITY OF GENERALLY ACCEPTED ACCOUNTING PRINCIPLES TO REGULATORY REPORTING REQUIREMENTS

For recognition and measurement purposes, the regulatory reporting requirements applicable to Reports of Condition and Income (Call Report) shall conform to generally accepted accounting principles (GAAP). Nevertheless, because the Call Report is a bank-level report, each bank (together with its consolidated subsidiaries) is considered an "accounting entity" for regulatory reporting purposes and normally must prepare its Call Report on a separate entity basis. Furthermore, when reporting events and transactions not covered in principle by Call Report instructions or authoritative GAAP standards, banks are encouraged to discuss the event or transaction with their primary federal bank supervisory agency.

Regardless of whether a bank discusses a reporting issue with its supervisory agency, when a bank's supervisory agency's interpretation of how GAAP should be applied to a specified event or transaction (or series of related events or transactions) differs from the bank's interpretation, the supervisory agency may require the bank to reflect the event(s) or transaction(s) in its Reports of Condition and Income in accordance with the agency's interpretation and to amend previously submitted reports.

The Call Report instructions contain certain specific reporting guidance that falls within the range of acceptable practice under GAAP. These instructions have been adopted to achieve safety and soundness and other public policy objectives and to ensure comparability. Should the need arise in the future, other specific reporting guidance that falls within the range of GAAP may be issued. Current Call Report instructions providing such specific reporting guidance include the nonaccrual rules in the Glossary entry for "Nonaccrual Status," the treatment of impaired collateral dependent loans in the Glossary entry for "Loan Impairment," the Glossary entry for the "Allowance for Loan and Lease Losses" which references the 1993 Interagency Policy Statement on this subject, the separate entity method of accounting for income taxes of bank subsidiaries of holding companies in the Glossary entry for "Income Taxes," the push down accounting rules in the Glossary entry for "Business Combinations," and the treatment of property dividends in the Glossary entry for "Dividends."

There may be areas in which a bank wishes more technical detail on the application of accounting standards and procedures to the requirements of these instructions. Such information may often be found in the appropriate entries in the Glossary section of these instructions or, in more detail, in the GAAP standards. Selected sections of the GAAP standards are referenced in the instructions where appropriate. The accounting entries in the Glossary are intended to serve as an aid in specific reporting situations rather than as a comprehensive statement on bank accounting.

ACCRUAL BASIS REPORTING

All banks, regardless of size, shall prepare all schedules of the Reports of Condition and Income on an accrual basis. However, banks may report particular accounts on a cash basis, except for the four listed below, if the results would not materially differ from those obtained using an accrual basis.

All banks must report the following on an accrual basis:

- (1) income from installment loans;
- (2) amortization of premiums paid on held-to-maturity and available-for-sale securities (see the Glossary entry for "premiums and discounts");
- (3) income taxes (see the Glossary entry for "income taxes"); and
- (4) depreciation on premises and fixed assets.

All banks shall establish and maintain an adequate allowance for loan and lease losses. Accounting for loan and lease losses is discussed in more detail in the Glossary entry for "allowance for loan and lease losses."

No interest or discount shall be accrued on any asset which must be carried in nonaccrual status. Refer to the Glossary entry for "nonaccrual status" for further information.

MISCELLANEOUS GENERAL INSTRUCTIONS

Rounding

For banks with total assets of less than \$10 billion, all dollar amounts must be reported in thousands, with the figures rounded to the nearest thousand. Items less than \$500 will be reported as zero.

For banks with total assets of \$10 billion or more, all dollar amounts may be reported in thousands, but each bank, at its option, may round the figures reported to the nearest million, with zeros reported in the thousands column. For banks exercising this option, amounts less than \$500,000 will be reported as zero.

Rounding may result in details not adding to their stated totals. The only permissible differences between totals and the sums of their components are those attributable to the mechanics of rounding.

On the Report of Condition, Schedule RC, item 12, "Total assets," and Schedule RC, item 29, "Total liabilities, minority interest, and equity capital," which must be equal, must be derived from unrounded numbers and then rounded in order to ensure that these two items are equal as reported.

Negative Entries

Except for the items listed below, negative entries are not appropriate on the Report of Condition and shall not be reported. Hence, assets with credit balances must be reported in liability items and liabilities with debit balances must be reported in asset items, as appropriate, and in accordance with these instructions. The Report of Condition items for which negative entries may be made, if appropriate, are:

- (1) Schedule RC:
 - > item 8, "Investments in unconsolidated subsidiaries and associated companies,"
 - item 26.a, "Retained earnings,"

- item 26.b, "Accumulated other comprehensive income,"
- item 27, "Other equity capital components," and
- > item 28, "Total equity capital."
- (2) Schedule RC-C, items 10, 10.a, and 10.b, on "Lease financing receivables (net of unearned income)."
- (3)Schedule RC-M, items 4.a, 4.b, and 4.c, on "Investments in unconsolidated subsidiaries and associated companies."
- (4) Schedule RC-R:
 - > item 1, "Total equity capital,"
 - item 2, "Net unrealized gains (losses) on available-for-sale securities,"
 - item 4, "Accumulated net gains (losses) on cash flow hedges,"
 - item 10, "Other additions to (deductions from) Tier 1 capital,"
 - item 11, "Tier 1 capital,"
 - item 21. "Total risk-based capital." and
 - column B, "Items Not Subject to Risk-Weighting," for the asset categories in items 34 through 43.

When negative entries do occur in one or more of these items, they shall be recorded in parentheses rather than with a minus (-) sign.

On the Report of Income, negative entries may appear as appropriate. Income items with a debit balance and expense items with a credit balance must be reported in parentheses.

Verification

All addition and subtraction should be double-checked before reports are submitted. Totals and subtotals in supporting materials should be cross-checked to corresponding items elsewhere in the reports.

Before a report is submitted, all amounts should be compared with the corresponding amounts in the previous report. If there are any unusual changes from the previous report, a brief explanation of the changes should be attached to the submitted reports.

Banks should retain workpapers and other records used in the preparation of these reports.

Transactions Occurring Near the End of a Reporting Period

Transactions between banks occurring near the end of a reporting period may not be reported by the parties to the transaction in such a manner as to cause the asset (or liability) either to disappear entirely from the Reports of Condition submitted for that report date or to appear on both of the submitted reports, regardless of the time zones in which the banks are located, the time zone in which the transaction took place, or the actual zone clock times at the effective moment of the transaction.

In the case of a transaction occurring in different reporting periods for the parties because of time zone differences, the parties may decide between themselves on the reporting period in which they will all, consistently, report the transaction as having occurred, so that in any given reporting period, the asset (or liability) transferred will appear somewhere and without duplication in the reports submitted by the parties to the transaction.

FFIEC 031 and 041 13 **GENERAL INSTRUCTIONS**

If, in such cases, the parties do not agree on the reporting period in which the transaction is to be treated as having occurred on the reports of all parties, i.e., if they do not agree on which party will reflect the asset (or liability) on its reports for these purposes, the transaction will be deemed to have occurred prior to midnight in the time zone of the buyer (or transferee) and must be reported accordingly by all parties to the transaction.

If, in fact, the parties, in their submitted reports, treat the transaction as having occurred in different reporting periods, the parties will be required to amend their submitted reports on the basis of the standard set forth in the preceding paragraph.

SEPARATE BRANCH REPORTS

Each U.S. bank shall submit for each of its branches located in a foreign country, Puerto Rico, or a U.S. territory or possession (including trust territories) a "Foreign Branch Report of Condition" (FFIEC 030) once a year as of the end of December. However, a branch must report quarterly if it has either \$2 billion in total assets or \$5 billion in commitments to purchase foreign currencies and U.S. dollar exchange.

FFIEC 031 and 041 NARRATIVE

OPTIONAL NARRATIVE STATEMENT CONCERNING THE AMOUNTS REPORTED IN THE REPORTS OF CONDITION AND INCOME

The management of the reporting bank may, if it wishes, submit a brief narrative statement on the amounts reported in the Reports of Condition and Income. This optional statement will be made available to the public, along with the publicly available data in the Reports of Condition and Income, in response to any request for individual bank report data. However, the information reported in Schedule RC-T, items 12 through 23 and Memorandum item 4, is regarded as confidential and will not be released to the public. BANKS CHOOSING TO SUBMIT THE NARRATIVE STATEMENT SHOULD ENSURE THAT THE STATEMENT DOES NOT CONTAIN THE NAMES OR OTHER IDENTIFICATIONS OF INDIVIDUAL BANK CUSTOMERS, REFERENCES TO THE AMOUNTS REPORTED IN THE CONFIDENTIAL ITEMS IN SCHEDULE RC-T, OR ANY OTHER INFORMATION THAT THEY ARE NOT WILLING TO HAVE MADE PUBLIC OR THAT WOULD COMPROMISE THE PRIVACY OF THEIR CUSTOMERS. Banks choosing not to make a statement may check the "No comment" box and should make no entries of any kind in the space provided for the narrative statement; i.e., DO NOT enter in this space such phrases as "No statement," "Not applicable," "N/A," "No comment," and "None."

The optional statement must be entered on the sheet provided by the agencies. The statement should not exceed 100 words. Further, regardless of the number of words, the statement must not exceed 750 characters, including punctuation, indentation, and standard spacing between words and sentences. If any submission should exceed 750 characters, as defined, it will be truncated at 750 characters with no notice to the submitting bank and the truncated statement will appear as the bank's statement both on agency computerized records and in computer-file releases to the public.

All information furnished by the bank in the narrative statement must be accurate and not misleading. Appropriate efforts shall be taken by the submitting bank to ensure the statement's accuracy. The statement must be signed, in the space provided, by a senior officer of the bank who thereby attests to its accuracy.

If, subsequent to the original submission, <u>material</u> changes are submitted for the data reported in the Reports of Condition and Income, the existing narrative statement will be deleted from the files, and from disclosure; the bank, at its option, may replace it with a statement, under signature, appropriate to the amended data.

The optional narrative statement will appear in agency records and in release to the public exactly as submitted (or amended as described in the preceding paragraph) by the management of the bank (except for the truncation of statements exceeding the 750-character limit described above). THE STATEMENT WILL NOT BE EDITED OR SCREENED IN ANY WAY BY THE SUPERVISORY AGENCIES FOR ACCURACY OR RELEVANCE. DISCLOSURE OF THE STATEMENT SHALL NOT SIGNIFY THAT ANY FEDERAL SUPERVISORY AGENCY HAS VERIFIED OR CONFIRMED THE ACCURACY OF THE INFORMATION CONTAINED THEREIN. A STATEMENT TO THIS EFFECT WILL APPEAR ON ANY PUBLIC RELEASE OF THE OPTIONAL STATEMENT SUBMITTED BY THE MANAGEMENT OF THE REPORTING BANK.

LINE ITEM INSTRUCTIONS FOR THE CONSOLIDATED REPORT OF **INCOME**

The line item instructions should be read in conjunction with the Glossary and other sections of these instructions. See the discussion of the Organization of the Instruction Books in the General Instructions.

SCHEDULE RI -- INCOME STATEMENT

General Instructions

Report in accordance with these instructions all income and expense of the bank for the calendar year-to-date. Include adjustments of accruals and other accounting estimates made shortly after the end of a reporting period which relate to the income and expense of the reporting period.

A bank that began operating during the year-to-date reporting period should report in the appropriate items of Schedule RI all income earned and expenses incurred since commencing operations. The bank should report pre-opening income earned and expenses incurred from inception until the date operations commenced using one of the two methods described in the Glossary entry for "start-up activities."

Business Combinations and Push Down Accounting Transactions -- If the bank entered into a business combination which became effective during the year-to-date reporting period and which has been accounted for as a pooling of interests, report the income and expense of the combined business for the entire year-to-date. If the bank entered into a business combination which became effective during the reporting period and which has been accounted for as a purchase, report the income and expense of the acquired bank or business only after its acquisition. If the bank was acquired in a transaction which became effective during the reporting period and push down accounting was used to account for the acquisition, Schedule RI should only include amounts from the date of the bank's acquisition through the end of the year-to-date reporting period. For further information on poolings of interests, purchase acquisitions, and push down accounting, see the Glossary entry for "business combinations."

FFIEC 031 and 041 **RI - INCOME STATEMENT** RI-1

Item Instructions

Item No. Caption and Instructions

1 Interest income:

1.a Interest and fee income on loans. Report in the appropriate subitem all interest, fees, and similar charges levied against or associated with all assets reportable as loans in Schedule RC-C, part I, items 1 through 9.

On the FFIEC 041 for report dates during 2001, <u>banks with total assets of less than \$25 million</u> should complete item 1.a.(6) and should report a zero or the word "none" in items 1.a.(1) through 1.a.(5) below. <u>Banks with total assets of \$25 million or more</u> should complete items 1.a.(1) through 1.a.(6). This \$25 million asset size test is generally based on the reporting bank's total assets as reflected in the Report of Condition for June 30, 2000. Beginning March 31, 2002, all banks should complete items 1.a.(1) through 1.a.(6).

Deduct interest rebated to customers on loans paid before maturity from gross interest earned on loans; do *not* report as an expense.

<u>Include</u> as interest and fee income on loans:

- (1) Interest on all assets reportable as loans extended directly, purchased from others, sold under agreements to repurchase, or pledged as collateral for any purpose.
- (2) All yield-related fees on loans held in the bank's portfolio. Report only the bank's proportional share of yield-related fees collected in connection with a loan syndication or participation that are not passed through to another lender.
- (3) Loan commitment fees recognized as described under the Glossary entry for "loan fees."
- (4) Investigation and service charges, fees representing a reimbursement of loan processing costs, renewal and past-due charges, prepayment penalties, and fees charged for the execution of mortgages or agreements securing the bank's loans.
- (5) Accretion of discount on acceptances, loans secured by real estate (including points charged), and other loans. Deduct amortization of premium on loans secured by real estate or other loans from gross interest on loans.
- (6) Charges levied against overdrawn accounts based on the length of time the account has been overdrawn, the magnitude of the overdrawn balance, or which are otherwise equivalent to interest. See exclusion (5) below.

Exclude from interest and fee income on loans:

- (1) Fees for servicing real estate mortgages or other loans that are not assets of the bank (report in item 5.f, "Net servicing fees").
- (2) Charges to merchants for the bank's handling of credit card or charge sales when the bank does not carry the related loan accounts on its books (report as "Other noninterest income" in item 5.l). Banks may report this income net of the expenses (except salaries) related to the handling of these credit card or charge sales.

FFIEC 031 and 041 RI-2 RI - INCOME STATEMENT

Item No. Caption and Instructions

1.a (3) Net gains (losses) from the sale of all assets reportable as loans (report in item 5.i, (cont.)"Net gains (losses) on sales of loans and leases"). Refer to the Glossary entry for "transfers of financial assets."

- (4) Reimbursements for out-of-pocket expenditures (e.g. for the purchase of fire insurance on real estate securing a loan) made by the bank for the account of its customers. If the bank's expense accounts were charged with the amount of such expenditures, the reimbursements should be credited to the same expense accounts.
- (5) Transaction or per item charges levied against deposit accounts for the processing of checks drawn against insufficient funds that the bank assesses regardless of whether it decides to pay, return, or hold the check, so-called "NSF check charges" (report as "Service charges on deposit accounts (in domestic offices)," in item 5.b or, if levied against deposit accounts in foreign offices, as "Other noninterest income" in item 5.l) See inclusion (6) above.
- (6) Interchange fees earned from credit card transactions (report as "Other noninterest income" in item 5.l).

FFIEC 041 FFIEC 031

Item No. Item No. Caption and Instructions

- 1.a.(1) Interest and fee income on loans in domestic offices. Report in the appropriate subitem all interest, fees, and similar charges levied against or associated with all loans in domestic offices reportable in Schedule RC-C, part I, items 1 through 9, column B.
- 1.a.(1)

 1.a.(1)(a)

 Interest and fee income on loans secured by real estate. Report all interest, fees, and similar charges levied against or associated with all loans (in domestic offices) reportable in Schedule RC-C, part I, item 1, "Loans secured by real estate."
 - 1.a.(1)(b) Interest and fee income on loans to finance agricultural production and other loans to farmers. Report all interest, fees, and similar charges levied against or associated with all loans (in domestic offices) reportable in Schedule RC-C, part I, item 3, "Loans to finance agricultural production and other loans to farmers."
- 1.a.(2)

 1.a.(1)(c)

 Interest and fee income on commercial and industrial loans. Report all interest, fees, and similar charges levied against or associated with all loans (in domestic offices) reportable in Schedule RC-C, part I, item 4, "Commercial and industrial loans."
- 1.a.(1)(d)
 Interest and fee income on loans to individuals for household, family, and other personal expenditures. Report in the appropriate subitem all interest, fees, and similar charges levied against or associated with all loans (in domestic offices) reportable in Schedule RC-C, part I, item 6, "Loans to individuals for household, family, and other personal expenditures."

FFIEC 041 FFIEC 031

Item No. Item No. Caption and Instructions

Interest and fee income on credit cards. Report all interest, fees, and 1.a.(3)(a) 1.a.(1)(d)(1) similar charges levied against or associated with all extensions of credit to individuals for household, family, and other personal expenditures arising from credit cards (in domestic offices) reportable in Schedule RC-C, part I, item 6.a, "Credit cards."

> Exclude annual or other periodic fees paid by holders of credit cards issued by the bank (report in item 5.I, "Other noninterest income").

- 1.a.(3)(b) 1.a.(1)(d)(2) Interest and fee income on other loans to individuals for household. family, and other personal expenditures. Report all interest, fees, and similar charges levied against or associated with all other loans to individuals for household, family, and other personal expenditures (in domestic offices) reportable in Schedule RC-C, part I, item 6.b, "Other revolving credit plans," and item 6.c, "Other consumer loans."
- 1.a.(4) 1.a.(1)(e) Interest and fee income on loans to foreign governments and official institutions. Report all interest, fees, and similar charges levied against or associated with all loans (in domestic offices) reportable in Schedule RC-C, part I, item 7, "Loans to foreign governments and official institutions."
- 1.a.(5) 1.a.(1)(f) Interest and fee income on all other loans. On the FFIEC 041, report interest, fees, and similar charges levied against or associated with loans reportable in Schedule RC-C, part I, item 2, "Loans to depository institutions and acceptances of other banks," item 3, "Loans to finance agricultural production and other loans to farmers," item 8, "Obligations (other than securities and leases) of states and political subdivisions in the U.S.," and item 9, "Other loans."

On the FFIEC 031, report interest, fees, and similar charges levied against or associated with loans in domestic offices reportable in Schedule RC-C, part I, item 2, "Loans to depository institutions and acceptances of other banks," item 8, "Obligations (other than securities and leases) of states and political subdivisions in the U.S.," and item 9, "Other loans."

- 1.a.(2) Interest and fee income on loans in foreign offices, Edge and Agreement subsidiaries, and IBFs. Report all interest, fees, and similar charges levied against or associated with all loans in foreign offices, Edge and Agreement subsidiaries, and IBFs reportable in Schedule RC-C, part I, items 1 through 9.
- 1.a.(3) 1.a.(6) Total interest and fee income on loans. On the FFIEC 041 for report dates during 2001, banks with total assets of less than \$25 million should report in item 1.a.(6) the total amount of all interest, fees, and similar charges levied against or associated with all assets reportable as loans in Schedule RC-C, part I, items 1 through 9; banks with total assets of \$25 million or more should report the sum of items 1.a.(1) through 1.a.(5) in item 1.a.(6). On the FFIEC 041 beginning March 31, 2002, all banks should complete items 1.a.(1) through 1.a.(6).

On the FFIEC 031, report the sum of items 1.a.(1)(a) through 1.a.(2) in item 1.a.(3).

FFIEC 031 and 041 RI-4 **RI - INCOME STATEMENT**

FFIEC 031 and 041

Item No. Caption and Instructions

1.b Income from lease financing receivables. Report all income from direct financing and leveraged leases reportable in Schedule RC-C, part I, item 10, "Lease financing receivables (net of unearned income)." (See the Glossary entry for "lease accounting.")

Exclude from income from lease financing receivables:

- (1) Any investment tax credit associated with leased property (include in item 9,"Applicable income taxes (on item 8)").
- (2) Provision for possible losses on leases (report in item 4, "Provision for loan and lease losses").
- (3) Rental fees applicable to operating leases for furniture and equipment rented to others (report as "Other noninterest income" in item 5.l).
- 1.c Interest income on balances due from depository institutions. Report all income on assets reportable in Schedule RC, item 1.b, "Interest-bearing balances due from depository institutions."
- 1.d Interest and dividend income on securities. Report in the appropriate subitem all income on assets that are reportable in Schedule RC-B, Securities. Include accretion of discount and deduct amortization of premium on securities. Refer to the Glossary entry for "premiums and discounts."

Include interest and dividends on securities held in the bank's held-to-maturity and available-for-sale portfolios, even if such securities have been lent, sold under agreements to repurchase that are treated as borrowings, or pledged as collateral for any purpose.

Include interest received at the sale of securities to the extent that such interest had not already been accrued on the bank's books.

Do <u>not</u> deduct accrued interest included in the purchase price of securities from income on securities and do <u>not</u> charge to expense. Record such interest in a separate asset account (to be reported in Schedule RC-F, item 5, "Other assets") to be offset upon collection of the next interest payment.

Report income from detached U.S. Government security coupons and ex-coupon U.S. Government securities not held for trading in item 1.d.(3) as interest and dividend income on "All other securities." Refer to the Glossary entry for "coupon stripping, Treasury receipts, and STRIPS."

Exclude from interest and dividend income on securities:

- (1) Realized gains (losses) on held-to-maturity securities and on available-for-sale securities (report in Schedule RI, items 6.a and 6.b, respectively).
- (2) Net unrealized holding gains (losses) on available-for-sale securities (include the amount of such net unrealized holding gains (losses) in Schedule RC, item 26.b, "Accumulated other comprehensive income," and the calendar year-to-date change in such net unrealized holding gains (losses) in Schedule RI-A, item 10, "Other comprehensive income").

FFIEC 031 and 041 RI-5 RI - INCOME STATEMENT

Item No. **Caption and Instructions**

(3) Income from advances to, or obligations of, majority-owned subsidiaries not 1.d consolidated, associated companies, and those corporate joint ventures over which the (cont.) bank exercises significant influence (report as "Noninterest income" in the appropriate subitem of item 5).

- 1.d.(1) Interest and dividend income on U.S. Treasury securities and U.S. Government agency obligations (excluding mortgage-backed securities). Report income from all securities reportable in Schedule RC-B, item 1, "U.S. Treasury securities," and item 2, "U.S. Government agency obligations." Include accretion of discount on U.S. Treasury bills.
- 1.d.(2) Interest and dividend income on mortgage-backed securities. Report income from all securities reportable in Schedule RC-B, item 4, "Mortgage-backed securities."
- 1.d.(3) Interest and dividend income on all other securities. Report income from all securities reportable in Schedule RC-B, item 3, "Securities issued by states and political subdivisions in the U.S.," item 5, "Asset-backed securities," item 6, "Other debt securities," and item 7, "Investments in mutual funds and other equity securities with readily determinable fair values."

Exclude from interest and dividend income on all other securities:

- (1) Income from equity securities that do not have readily determinable fair values (report as "Other interest income" in item 1.g).
- (2) The bank's proportionate share of the net income or loss from its investments in the stock of unconsolidated subsidiaries, associated companies, and those corporate joint ventures over which the bank exercises significant influence (report income or loss before extraordinary items and other adjustments as "Noninterest income" in the appropriate subitem of item 5 and report extraordinary items and other adjustments in item 11).
- 1.e Interest income on trading assets. Report the interest income earned on assets reportable in Schedule RC, item 5, "Trading assets."

Include accretion of discount on assets held for trading that have been issued on a discount basis, such as U.S. Treasury bills and commercial paper.

Exclude gains (losses) and fees from trading assets, which should be reported in Schedule RI, item 5.c, "Trading revenue."

1.f Interest income on federal funds sold and securities purchased under agreements to resell. Report the gross revenue from assets reportable in Schedule RC, item 3, "Federal funds sold and securities purchased under agreements to resell."

> Report the expense of federal funds purchased and securities sold under agreements to repurchase in Schedule RI, item 2.b; do not deduct from the gross revenue reported in this item. However, if amounts recognized as payables under repurchase agreements have been offset against amounts recognized as receivables under reverse repurchase agreements and reported as a net amount in Schedule RC, Balance Sheet, in accordance with FASB Interpretation No. 41, the income and expense from these agreements may be reported on a net basis in Schedule RI, Income Statement.

FFIEC 031 and 041 RI-6 **RI - INCOME STATEMENT**

Item No. **Caption and Instructions**

Other interest income. Report interest and dividend income on assets other than those 1.g assets properly reported in Schedule RC, items 1 through 5. Include dividend income on "Equity securities that do not have readily determinable fair values" that are reportable in Schedule RC-F, item 4. Also include interest income on interest-only strips receivable (not in the form of a security) that are reportable in Schedule RC-F, item 3. However, exclude interest and dividends on venture capital investments (loans and securities), which should be reported in item 5.e, below.

- 1.h Total interest income. On the FFIEC 041, report the sum of items 1.a.(6) through 1.g. On the FFIEC 031, report the sum of items 1.a.(3) through 1.g.
- 2 Interest expense:
- Interest on deposits. Report in the appropriate subitem all interest expense, including 2.a amortization of the cost of merchandise or property offered in lieu of interest payments, on deposits reportable in Schedule RC, item 13.a.(2), "Interest-bearing deposits in domestic offices," and, for banks filing the FFIEC 031 report forms, Schedule RC, item 13.b.(2), "Interest-bearing deposits in foreign offices, Edge and Agreement subsidiaries, and IBFs."

Exclude the cost of gifts or premiums (whether in the form of merchandise, credit, or cash) given to depositors at the time of the opening of a new account or an addition to, or renewal of, an existing account (report in Schedule RI, item 7.d, "Other noninterest expense").

Include as interest expense on the appropriate category of deposits finders' fees and brokers' fees that represent an adjustment to the interest rate paid on deposits the reporting bank acquires through brokers. If material, such fees should be capitalized and amortized over the term of the related deposits. However, exclude fees levied by brokers that are, in substance, retainer fees or that otherwise do not represent an adjustment to the interest rate paid on brokered deposits (report in Schedule RI, item 7.d, "Other noninterest expense").

Deduct from the gross interest expense of the appropriate category of time deposits penalties for early withdrawals, or portions of such penalties, that represent the forfeiture of interest accrued or paid to the date of withdrawal. If material, portions of penalties for early withdrawals that exceed the interest accrued or paid to the date of withdrawal should not be treated as a reduction of interest expense but should be included in "Other noninterest income" in Schedule RI, item 5.I.

FFIEC 041 FFIEC 031

Item No. Item No. Caption and Instructions

- Interest on deposits in domestic offices: 2.a.(1)
- 2.a.(1) Interest on transaction accounts (NOW, ATS accounts, and telephone 2.a.(1)(a) and preauthorized transfer accounts). Report interest expense on the three interest-bearing categories of transaction accounts (NOW accounts, ATS accounts, and telephone and preauthorized transfer accounts) reportable in Schedule RC-E, (part I,) items 1 through 6, column A, "Total transaction accounts." Exclude all costs incurred by the bank in connection with demand deposits which are noninterest-bearing transaction accounts. See the Glossary entry for "deposits" for the definitions of "NOW accounts," "ATS accounts," and

"telephone or preauthorized transfer accounts."

FFIEC 031 and 041 RI-7 **RI - INCOME STATEMENT**

FFIEC 041 FFIEC 031 Item No. Item No. **Caption and Instructions**

- 2.a.(2) Interest on nontransaction accounts. Report in the appropriate subitem 2.a.(1)(b) interest expense on all deposits reportable in Schedule RC-E, (part I,) items 1 through 6, column C, "Total nontransaction accounts."
- 2.a.(2)(a) 2.a.(2)(b)(1) Interest on savings deposits. Report interest expense on all deposits reportable in Schedule RC-E, (part I,) Memorandum item 2.a.(1), "Money market deposit accounts (MMDAs)," and Memorandum item 2.a.(2), "Other savings deposits."
- 2.a.(2)(b) 2.a.(1)(b)(2) Interest on time deposits of \$100.000 or more. Report interest expense on all deposits reportable in Schedule RC-E, (part I,) Memorandum item 2.c, "Total time deposits of \$100,000 or more."
- 2.a.(2)(c) 2.a.(1)(b)(3) Interest on time deposits of less than \$100,000. Report interest expense on all deposits reportable in Schedule RC-E, (part I,) Memorandum item 2.b, "Total time deposits of less than \$100,000."
 - 2.a.(2) Interest on deposits in foreign offices. Edge and Agreement subsidiaries. and IBFs. Report interest expense on all deposits in foreign offices reportable in Schedule RC, item 13.b.(2), "Interest-bearing deposits in foreign offices, Edge and Agreement subsidiaries, and IBFs."

FFIEC 031 and 041 Item No. Caption and Instructions

2.b Expense of federal funds purchased and securities sold under agreements to repurchase. Report the gross expense of all liabilities reportable in Schedule RC, item 14, "Federal funds purchased and securities sold under agreements to repurchase."

> Report the income of federal funds sold and securities purchased under agreements to resell in Schedule RI, item 1.f; do not deduct from the gross expense reported in this item. However, if amounts recognized as payables under repurchase agreements have been offset against amounts recognized as receivables under reverse repurchase agreements and reported as a net amount in Schedule RC, Balance Sheet, in accordance with FASB Interpretation No. 41, the income and expense from these agreements may be reported on a net basis in Schedule RI, Income Statement.

- 2.c Interest on trading liabilities and other borrowed money. Report the interest expense on all liabilities reportable in Schedule RC, item 15, "Trading liabilities," and item 16, "Other borrowed money."
- 2.d Interest on subordinated notes and debentures. Report the interest expense on all liabilities reportable in Schedule RC, item 19, "Subordinated notes and debentures."

Include amortization of expenses incurred in the issuance of subordinated notes and debentures. Capitalize such expenses, if material, and amortize them over the life of the related notes and debentures.

Exclude dividends declared or paid on limited-life preferred stock (report dividends declared in Schedule RI-A, item 8).

FFIEC 031 and 041 RI-8 **RI - INCOME STATEMENT**

Item No. **Caption and Instructions**

- **Total interest expense.** Report the sum items 2.a through 2.d. 2.e
- 3 Net interest income. Report the difference between Schedule RI, item 2.e, "Total interest expense," and Schedule RI, item 1.h, "Total interest income." If the amount is negative, enclose it in parentheses.
- Provision for loan and lease losses. Report the amount needed to make the allowance for 4 loan and lease losses, as reported in Schedule RC, item 4.c, adequate to absorb estimated loan and lease losses, based upon management's evaluation of the bank's current loan and lease portfolio. The amount reported in this item must equal Schedule RI-B, part II, item 4, "Provision for loan and lease losses." Enclose negative amounts in parentheses.

Exclude provision for credit losses on off-balance sheet credit exposures and provision for allocated transfer risk, both of which should be reported in item 7.d, "Other noninterest expense."

The amount reported here may differ from the bad debt expense deduction taken for federal income tax purposes.

Refer to the Glossary entries for "allowance for loan and lease losses" and "loan impairment" for additional information.

5 Noninterest income:

5.a Income from fiduciary activities. Report gross income from services rendered by the bank's trust department or by any of its consolidated subsidiaries acting in any fiduciary capacity. Include commissions and fees on sales of annuities by the bank's trust department (or by a consolidated trust company subsidiary) that are executed in a fiduciary capacity. For banks required to complete Schedule RC-T, items 12 through 19, this item must equal the amount reported in Schedule RC-T, item 19.

> Exclude commissions and fees received for the accumulation or disbursement of funds deposited to Individual Retirement Accounts (IRAs) or Keogh Plan accounts when they are not handled by the bank's trust department (report in Schedule RI, item 5.b, "Service charges on deposit accounts (in domestic offices)").

Report a zero or the word "none" if the bank has no trust department and no consolidated subsidiaries that render services in any fiduciary capacity.

- 5.b Service charges on deposit accounts (in domestic offices). Report in this item amounts charged depositors (in domestic offices):
 - (1) For the maintenance of their deposit accounts with the bank, so-called "maintenance charges."
 - (2) For their failure to maintain specified minimum deposit balances.
 - (3) Based on the number of checks drawn on and deposits made in their deposit accounts.
 - (4) For checks drawn on so-called "no minimum balance" deposit accounts.
 - (5) For withdrawals from nontransaction deposit accounts.

FFIEC 031 and 041 RI-9 **RI - INCOME STATEMENT**

Item No. Caption and Instructions

5.b (6) For the closing of savings accounts before a specified minimum period of time has (cont.) elapsed.

- (7) For accounts which have remained inactive for extended periods of time or which have become dormant.
- (8) For deposits to or withdrawals from deposit accounts through the use of automated teller machines or remote service units.
- (9) For the processing of checks drawn against insufficient funds, so-called "NSF check charges," that the bank assesses regardless of whether it decides to pay, return, or hold the check. Exclude subsequent charges levied against overdrawn accounts based on the length of time the account has been overdrawn, the magnitude of the overdrawn balance, or which are otherwise equivalent to interest (report in the appropriate subitem of Schedule RI, item 1.a, "Interest and fee income on loans (in domestic offices)").
- (10) For issuing stop payment orders.
- (11) For certifying checks.
- (12) For the accumulation or disbursement of funds deposited to Individual Retirement Accounts (IRAs) or Keogh Plan accounts when not handled by the bank's trust department. Report such commissions and fees received for accounts handled by the bank's trust department in Schedule RI, item 5.a, "Income from fiduciary activities."

Exclude penalties paid by depositors for the early withdrawal of time deposits (report as "Other noninterest income" in Schedule RI, item 5.I, or deduct from the interest expense of the related category of time deposits, as appropriate).

5.c Trading revenue. Report the net gain or loss from trading cash instruments and derivative contracts (including commodity contracts) that has been recognized during the calendar year-to-date. For banks required to complete Schedule RI, Memorandum item 8, the amount reported in this item must equal the sum of Schedule RI, Memorandum items 8.a through 8.d.

Include as trading revenue:

- (1) Revaluation adjustments to the carrying value of cash instruments reportable in Schedule RC, item 5, "Trading assets," and Schedule RC, item 15, "Trading liabilities," resulting from the periodic marking to market of such instruments.
- (2) Revaluation adjustments from the periodic marking to market of interest rate, foreign exchange, equity derivative, and commodity and other contracts reportable in Schedule RC-L, item 12, "Total gross notional amount of derivative contracts held for trading."
- (3) Incidental income and expense related to the purchase and sale of cash instruments reportable in Schedule RC, item 5, "Trading assets," and Schedule RC, item 15, "Trading liabilities," and derivative contracts reportable in Schedule RC-L, item 12, "Total gross notional amount of derivative contracts held for trading."

If the amount to be reported in this item is a net loss, enclose it in parentheses.

FFIEC 031 and 041 RI-10 RI - INCOME STATEMENT

Item No. Caption and Instructions

5.d Investment banking, advisory, brokerage, and underwriting fees and commissions.

Report fees and commissions from underwriting (or participating in the underwriting of) securities, private placements of securities, investment advisory and management services, merger and acquisition services, and other related consulting fees. Include fees and commissions from securities brokerage activities, from the sale and servicing of mutual funds, from the sale of annuities to bank customers by securities brokerage firms, from the purchase and sale of securities and money market instruments where the bank is acting as agent for other banks or customers, and from the lending of securities owned by the bank or by bank customers (if these fees and commissions are not included in Schedule RI, item 5.a, "Income from fiduciary activities," or item 5.c, "Trading revenue").

Also include the bank's proportionate share of the income or loss before extraordinary items and other adjustments from its investments in:

- unconsolidated subsidiaries,
- associated companies, and
- corporate joint ventures, unincorporated joint ventures, general partnerships, and limited partnerships over which the bank exercises significant influence

that are principally engaged in investment banking, advisory, brokerage, or securities underwriting activities.

Venture capital revenue. In general, venture capital activities involve the providing of funds, whether in the form of loans or equity, and technical and management assistance, when needed and requested, to start-up or high-risk companies specializing in new technologies, ideas, products, or processes. The primary objective of these investments is capital growth.

Report as venture capital revenue market value adjustments, interest, dividends, gains, and losses (including impairment losses) on venture capital investments (loans and securities). Include any fee income from venture capital activities that is not reported in one of the preceding items of Schedule RI, Income Statement.

Also include the bank's proportionate share of the income or loss before extraordinary items and other adjustments from its investments in:

- unconsolidated subsidiaries,
- associated companies, and
- corporate joint ventures, unincorporated joint ventures, general partnerships, and limited partnerships over which the bank exercises significant influence

that are principally engaged in venture capital activities.

- 5.f Net servicing fees. Report income from servicing real estate mortgages, credit cards, and other financial assets held by others. Report any premiums received in lieu of regular servicing fees on such loans only as earned over the life of the loans. Banks should report servicing income net of the related servicing assets' amortization expense. Include impairments recognized on servicing assets. Also include increases in servicing liabilities recognized when subsequent events have increased the fair value of the liability above its carrying amount. For further information on servicing, see the Glossary entry for "servicing assets and liabilities."
- 5.g Net securitization income. Report net gains (losses) on assets sold in securitization transactions, i.e., net of transaction costs. Include fees (other than servicing fees) earned from the bank's securitization transactions and unrealized losses (and recoveries of unrealized losses) on loans and leases held for sale in securitization transactions. Exclude income from servicing securitized assets (report in Schedule RI, item 5.f, above) and income

Item No. Caption and Instructions

5.g from seller's interests and residual interests retained by the bank (report in the appropriate cont.) subitem of Schedule RI, item 1, "Interest income)."

5.h Insurance commissions and fees. Report all income from insurance and reinsurance underwriting, including the amount of premiums earned by property-casualty insurers and the amount of premiums written by life and health insurers. Report income from agency and brokerage operations (includes sales of annuities and supplemental contracts); service charges, commissions, and fees from the sale of insurance (including credit life insurance), reinsurance, and annuities; and management fees from separate accounts, deferred annuities, and universal life products.

Also include the bank's proportionate share of the income or loss before extraordinary items and other adjustments from its investments in:

- unconsolidated subsidiaries,
- associated companies, and
- corporate joint ventures, unincorporated joint ventures, general partnerships, and limited partnerships over which the bank exercises significant influence

that are principally engaged in insurance underwriting, reinsurance, or insurance sales activities.

Exclude commissions and fees on sales of annuities by the bank's trust department (or by a consolidated trust company subsidiary) that are executed in a fiduciary capacity (report in Schedule RI, item 5.a, "Income from fiduciary activities"). Also exclude commissions and fees that the bank earns from the sale of annuities to bank customers by securities brokerage firms (report in Schedule RI, item 5.d, "Investment banking, advisory, brokerage, and underwriting fees and commissions").

- 5.i Net gains (losses) on sales of loans and leases. Report the amount of net gains (losses) on sales and other disposals of loans and leases (reportable in Schedule RC-C), including unrealized losses (and subsequent recoveries of such net unrealized losses) on loans and leases held for sale. Exclude net gains (losses) on loans and leases sold in securitization transactions and unrealized losses (and recoveries of unrealized losses) on loans and leases held for sale in securitization transactions (report these gains (losses) in Schedule RI, item 5.g, "Net securitization income").
- 5.j Net gains (losses) on sales of other real estate owned. Report the amount of net gains (losses) on sales and other disposals of other real estate owned (reportable in Schedule RC, item 7), increases and decreases in the valuation allowance for foreclosed real estate, and write-downs of other real estate owned subsequent to acquisition (or physical possession) charged to expense. Do not include as a loss on other real estate owned any amount charged to the allowance for loan and lease losses at the time of foreclosure (actual or physical possession) for the difference between the carrying value of a loan and the fair value less cost to sell of the foreclosed real estate.
- 5.k Net gains (losses) on sales of other assets (excluding securities). Report the amount of net gains (losses) on sales and other disposals of assets not required to be reported elsewhere in the income statement (Schedule RI). Include net gains (losses) on sales and other disposals of premises and fixed assets; personal property acquired for debts previously contracted (such as automobiles, boats, equipment, and appliances); and coins, art, and other similar assets. Do not include net gains (losses) on sales and other disposals of loans and leases (either directly or through securitization), other real estate owned, securities, and trading assets (report these net gains (losses) in the appropriate items of Schedule RI).

FFIEC 031 and 041 RI-12 RI - INCOME STATEMENT

Item No. Caption and Instructions

5.I Other noninterest income. Report all operating income of the bank for the calendar year to date not required to be reported elsewhere in Schedule RI. Disclose in Schedule RI-E, items 1.a through 1.h, each component of other noninterest income, and the dollar amount of such component, that exceeds 1 percent of the sum of the bank's total interest income (from Schedule RI, item 1.h) and its total noninterest income (from Schedule RI, item 5.m). For each component of other noninterest income that exceeds this disclosure threshold for which a preprinted caption has not been provided in Schedule RI-E, items 1.a through 1.e, describe the component with a clear but concise caption in Schedule RI-E, items 1.f though 1.h. These descriptions should not exceed 50 characters in length (including spacing between words).

<u>Include</u> as other noninterest income:

- (1) Service charges, commissions, and fees for such services as:
 - (a) The rental of safe deposit boxes. (Report the amount of safe deposit box rent in Schedule RI-E, item 1.e, if this amount exceeds 1 percent of the sum of the bank's total interest income from Schedule RI, item 1.h, and its total noninterest income from Schedule RI, item 5.m.)
 - (b) The safekeeping of securities for other depository institutions (if the income for such safekeeping services is not included in Schedule RI, item 5.a, "Income from fiduciary activities").
 - (c) The sale of bank drafts, money orders, cashiers' checks, and travelers' checks.
 - (d) The collection of utility bills, checks, notes, bond coupons, and bills of exchange.
 - (e) The redemption of U.S. savings bonds.
 - (f) The handling of food stamps and the U.S. Treasury Tax and Loan Account, including fees received in connection with the bank's issuance of interest-bearing demand notes.
 - (g) The execution of acceptances and the issuance of commercial letters of credit, standby letters of credit, deferred payment letters of credit, and letters of credit issued for cash or its equivalent. <u>Exclude</u> income on bankers acceptances and trade acceptances (report such income in the appropriate subitem of Schedule RI, item 1.a, "Interest and fee income on loans," or in Schedule RI, item 1.e, "Interest income from trading assets," as appropriate).
 - (h) The notarizing of forms and documents.
 - The negotiation or management of loans from other lenders for customers or correspondents.
 - (j) The providing of consulting and advisory services to others. <u>Exclude</u> income from investment advisory services, which is to be reported in Schedule RI, item 5.d.
 - (k) The use of the bank's automated teller machines or remote service units by depositors of other depository institutions. (Report the amount of this income in Schedule RI-E, item 1.c, if this amount exceeds 1 percent of the sum of the bank's total interest income from Schedule RI, item 1.h, and its total noninterest income from Schedule RI, item 5.m.)

Item No. **Caption and Instructions**

5.I (cont.)

- (2) Income and fees from the sale and printing of checks. (Report the amount of this income in Schedule RI-E, item 1.a, if this amount exceeds 1 percent of the sum of the bank's total interest income from Schedule RI, item 1.h, and its total noninterest income from Schedule RI, item 5.m.)
- (3) Gross rentals and other income from all real estate reportable in Schedule RC, item 7, "Other real estate owned." (Report the amount of this income in Schedule RI-E, item 1.d, if this amount exceeds 1 percent of the sum of the bank's total interest income from Schedule RI, item 1.h, and its total noninterest income from Schedule RI, item 5.m.)
- (4) Earnings on or other increases in the value of the cash surrender value of bank-owned life insurance policies. (Report the amount of this income in Schedule RI-E, item 1.b, if this amount exceeds 1 percent of the sum of the bank's total interest income from Schedule RI, item 1.h, and its total noninterest income from Schedule RI, item 5.m.)
- (5) Annual or other periodic fees paid by holders of credit cards issued by the bank. Fees that are periodically charged to cardholders shall be deferred and recognized on a straight-line basis over the period the fee entitles the cardholder to use the card.
- (6) Charges to merchants for the bank's handling of credit card or charge sales when the bank does not carry the related loan accounts on its books. Banks may report this income net of the expenses (except salaries) related to the handling of these credit card or charge sales.
- (7) Interchange fees earned from credit card transactions.
- (8) Gross income received for performing data processing services for others. Do not deduct the expense of performing such services for others (report in the appropriate items of noninterest expense).
- (9) Loan commitment fees that are recognized during the commitment period (i.e., fees retrospectively determined and fees for commitments where exercise is remote) or included in income when the commitment expires and loan syndication fees that are not required to be deferred. Refer to the Glossary entry for "loan fees" for further information.
- (10) On the FFIEC 031 only, service charges on deposit accounts in foreign offices.
- (11) Net tellers' overages (shortages), net recoveries (losses) on forged checks, net recoveries (losses) on payment of checks over stop payment orders, and similar recurring operating gains (losses) of this type. Banks should consistently report these gains (losses) either in this item or in Schedule RI, item 7.d.
- (12) Net gains (losses) from the sale or other disposal of branches (i.e., where the reporting bank sells a branch's assets to another depository institution, which assumes the deposit liabilities of the branch). Banks should consistently report these net gains (losses) either in this item or in Schedule RI, item 7.d.
- (13) Net gains (losses) from all transactions involving foreign currency or foreign exchange other than trading transactions. Banks should consistently report these net gains (losses) either in this item or in Schedule RI, item 7.d.

FFIEC 031 and 041 **RI-14 RI - INCOME STATEMENT**

Item No. **Caption and Instructions**

- **5.I** (14) Rental fees applicable to operating leases for furniture and equipment rented to others. (cont.)
 - (15) Interest received on tax refunds.
 - (16) Life insurance proceeds on policies for which the bank is the beneficiary.
 - (17) Credits resulting from litigation or other claims.
 - (18) Portions of penalties for early withdrawals of time deposits that exceed the interest accrued or paid on the deposit to the date of withdrawal, if material. Penalties for early withdrawals, or portions of such penalties, that represent the forfeiture of interest accrued or paid to the date of withdrawal are a reduction of interest expense and should be deducted from the gross interest expense of the appropriate category of time deposits in Schedule RI, item 2.a, "Interest on deposits."
 - (19) Interest income from advances to, or obligations of, and the bank's proportionate share of the income or loss before extraordinary items and other adjustments from its investments in:
 - unconsolidated subsidiaries,
 - associated companies, and
 - corporate joint ventures, unincorporated joint ventures, general partnerships, and limited partnerships over which the bank exercises significant influence, other than those that are principally engaged in investment banking, advisory, brokerage, or securities underwriting activities; venture capital activities; or insurance underwriting, reinsurance, or insurance sales activities (the income from which should be reported in Schedule RI, items 5.d, 5.e, and 5.h, respectively). Exclude the bank's proportionate share of material extraordinary items and other adjustments of these entities (report in Schedule RI, item 11, "Extraordinary items and other adjustments, net of income taxes").
 - (20) Net gains (losses) on nonhedging derivative instruments held for purposes other than trading. Banks should consistently report these net gains (losses) either in this item or in Schedule RI, item 7.d. For further information, see the Glossary entry for "derivative contracts."
 - (21) Gross income generated by securities contributed to charitable contribution Clifford Trusts.
 - (22) Income from ground rents and air rights.
- 5.m **Total noninterest income.** Report the sum of items 5.a through 5.l.

FFIEC 031 and 041 **RI-15 RI - INCOME STATEMENT** (3-01)

Item No. Caption and Instructions

Realized gains (losses) on held-to-maturity securities. Report the net gain or loss realized during the calendar year to date from the sale, exchange, redemption, or retirement of all securities reportable in Schedule RC, item 2.a, "Held-to-maturity securities." The realized gain or loss on a security is the difference between the sales price (excluding interest at the coupon rate accrued since the last interest payment date, if any) and its amortized cost. Also include in this item write-downs of the cost basis of individual held-to-maturity securities for other than temporary impairments. If the amount to be reported in this item is a net loss, enclose it in parentheses.

<u>Exclude</u> from this item realized gains (losses) on available-for-sale securities (report in Schedule RI, item 6.b, below) and on trading securities (report in Schedule RI, item 5.c, "Trading revenue").

Realized gains (losses) on available-for-sale securities. Report the net gain or loss realized during the calendar year to date from the sale, exchange, redemption, or retirement of all securities reportable in Schedule RC, item 2.b, "Available-for-sale securities." The realized gain or loss on a security is the difference between the sales price (excluding interest at the coupon rate accrued since the last interest payment date, if any) and its amortized cost. Also include in this item write-downs of the cost basis of individual available-for-sale securities for other than temporary impairments. If the amount to be reported in this item is a net loss, enclose it in parentheses.

Exclude from this item:

- (1) The change in net unrealized holding gains (losses) on available-for-sale securities during the calendar year to date (report in Schedule RI-A, item 10, "Other comprehensive income").
- (2) Realized gains (losses) on held-to-maturity securities (report in Schedule RI, item 6.a, above) and on trading securities (report in Schedule RI, item 5.c, "Trading revenue").

7 Noninterest expense:

7.a Salaries and employee benefits. Report salaries and benefits of all officers and employees of the bank and its consolidated subsidiaries including guards and contracted guards, temporary office help, dining room and cafeteria employees, and building department officers and employees (including maintenance personnel). Include as employees individuals who, in form, are employed by an affiliate but who, in substance, do substantially all of their work for the reporting bank. However, banking organizations should not segregate the compensation component of other intercompany cost allocations arising from arrangements other than that described in the preceding sentence for purposes of this item.

Include as salaries and employee benefits:

- (1) Gross salaries, wages, overtime, bonuses, incentive compensation, and extra compensation.
- (2) Social security taxes and state and federal unemployment taxes paid by the bank.
- (3) Contributions to the bank's retirement plan, pension fund, profit-sharing plan, employee stock ownership plan, employee stock purchase plan, and employee savings plan.

FFIEC 031 and 041 RI-16 RI - INCOME STATEMENT

Item No. **Caption and Instructions**

7.a (cont.)

- (4) Premiums (net of dividends received) on health and accident, hospitalization, dental, disability, and life insurance policies for which the bank is not the beneficiary.
- (5) Cost of office temporaries whether hired directly by the bank or through an outside agency.
- (6) Workmen's compensation insurance premiums.
- (7) The net cost to the bank for employee dining rooms, restaurants, and cafeterias.
- (8) Accrued vacation pay earned by employees during the calendar year-to-date.
- (9) The cost of medical or health services, relocation programs and reimbursements of moving expenses, tuition reimbursement programs, and other so-called fringe benefits for officers and employees.

Exclude from salaries and employee benefits (report in Schedule RI, item 7.d, "Other noninterest expense"):

- (1) Amounts paid to attorneys, accountants, management consultants, investment counselors, and other professionals who are not salaried officers or employees of the bank (except if these professionals, in form, are employed by an affiliate of the reporting bank but, in substance, do substantially all of their work for the reporting bank).
- (2) Expenses related to the testing and training of officers and employees.
- (3) The cost of bank newspapers and magazines prepared for distribution to bank officers and employees.
- (4) Expenses of life insurance policies for which the bank is the beneficiary. (However, when these expenses relate to bank-owned life insurance policies with cash surrender values, banks may report the net earnings on or the net increases in the value of these cash surrender values in Schedule RI, item 5.I, above.)
- (5) The cost of athletic activities in which officers and employees participate when the purpose may be construed to be for marketing or public relations, and employee benefits are only incidental to the activities.
- (6) Dues, fees and other expenses associated with memberships in country clubs, social or private clubs, civic organizations, and similar clubs and organizations.

FFIEC 031 and 041 **RI-17 RI - INCOME STATEMENT**

Item No. **Caption and Instructions**

7.b Expenses of premises and fixed assets. Report all noninterest expenses related to the use of premises, equipment, furniture, and fixtures reportable in Schedule RC, item 6, "Premises and fixed assets," net of rental income. If this net amount is a credit balance, enclose it in parentheses.

> Deduct rental income from gross premises and fixed asset expense. Rental income includes all rentals charged for the use of buildings not incident to their use by the reporting bank and its consolidated subsidiaries, including rentals by regular tenants of the bank's buildings, income received from short-term rentals of other bank facilities, and income from subleases. Also deduct income from stocks and bonds issued by nonmajority-owned corporations that indirectly represent premises, equipment, furniture, or fixtures and are reportable in Schedule RC, item 6, "Premises and fixed assets."

Include as expenses of premises and fixed assets:

- (1) Normal and recurring depreciation and amortization charges against assets reportable in Schedule RC, item 6, "Premises and fixed assets," including capital lease assets, which are applicable to the calendar year-to-date, whether they represent direct reductions in the carrying value of the assets or additions to accumulated depreciation or amortization accounts. Any method of depreciation or amortization conforming to accounting principles that are generally acceptable for financial reporting purposes may be used. However, depreciation for premises and fixed assets may be based on a method used for federal income tax purposes if the results would not be materially different from depreciation based on the asset's estimated useful life.
- All operating lease payments made by the bank on premises (including parking lots), equipment (including data processing equipment), furniture, and fixtures.
- (3) Cost of ordinary repairs to premises (including leasehold improvements), equipment, furniture, and fixtures.
- (4) Cost of service or maintenance contracts for equipment, furniture, and fixtures.
- Cost of leasehold improvements, equipment, furniture, and fixtures charged directly to expense and not placed on the bank's books as assets.
- Insurance expense related to the use of premises, equipment, furniture, and fixtures including such coverages as fire, multi-peril, boiler, plate glass, flood, and public liability.
- All property tax and other tax expense related to premises (including leasehold improvements), equipment, furniture, and fixtures, including deficiency payments, net of all rebates, refunds, or credit.
- (8) Any portion of capital lease payments representing executory costs such as insurance, maintenance, and taxes.
- (9) Cost of heat, electricity, water, and other utilities connected with the use of premises and fixed assets.
- (10) Cost of janitorial supplies and outside janitorial services.
- (11) Fuel, maintenance, and other expenses related to the use of the bank-owned automobiles, airplanes, and other vehicles for bank business.

FFIEC 031 and 041 **RI-18 RI - INCOME STATEMENT**

Item No. **Caption and Instructions**

7.b Exclude from expenses of premises and fixed assets: (cont.)

- (1) Salaries and employee benefits (report such expenses for all officers and employees of the bank and its consolidated subsidiaries in Schedule RI, item 7.a, "Salaries and employee benefits").
- (2) Interest on mortgages, liens, or other encumbrances on premises or equipment owned, including the portion of capital lease payments representing interest expense (report in Schedule RI, item 2.c, "Interest on trading liabilities and other borrowed money").
- (3) All expenses associated with other real estate owned (report in Schedule RI, item 7.d, "Other noninterest expense").
- (4) Gross rentals from other real estate owned and fees charged for the use of parking lots properly reported as other real estate owned, as well as safe deposit box rentals and rental fees applicable to operating leases for furniture and equipment rented to others (report in Schedule RI, item 5.l).
- 7.c.(1) Goodwill impairment losses. Report any impairment losses recognized during the period on goodwill (as defined for Schedule RC, item 10.a). Exclude the amortization expense of and any impairment losses on any unidentifiable intangible assets recorded in accordance with FASB Statement No. 72 (report such amortization expense and impairment losses in Schedule RI, item 7.c.(2)). Also exclude goodwill impairment losses associated with discontinued operations (report such losses on a net-of-tax basis in Schedule RI, item 11, "Extraordinary items and other adjustments, net of income taxes").

If the reporting bank is not a subsidiary of a bank holding company or other company, goodwill must be tested for impairment at the reporting unit level as determined by the bank in accordance with FASB Statement No. 142. If the reporting bank is a subsidiary of a bank holding company or other company, all goodwill recognized by the bank in its Reports of Condition and Income, which are financial statements prepared in accordance with generally accepted accounting principles, should be accounted for in accordance with FASB Statement No. 142 and these instructions. In this situation, the bank's goodwill must be tested for impairment at the bank level using the bank's reporting units. For impairment testing purposes, the bank itself may be a reporting unit.

Goodwill is considered impaired when the amount of goodwill exceeds its implied fair value at the reporting unit level. If the carrying amount of reporting unit goodwill exceeds its implied fair value, an impairment loss must be recognized in earnings in an amount equal to that excess and reported in this item. The loss recognized cannot exceed the carrying amount of the reporting unit's goodwill. After a goodwill impairment loss is recognized, the adjusted carrying amount of goodwill shall be its new accounting basis. Subsequent reversal of a previously recognized goodwill impairment loss is prohibited once the measurement of that loss is completed.

Goodwill of a reporting unit must be tested for impairment annually and between annual tests if an event occurs or circumstances change that would more likely than not reduce the fair value of a reporting unit below its carrying amount. Examples of such events or circumstances include a significant adverse change in the business climate, unanticipated competition, a loss of key personnel, and an expectation that a reporting unit or a significant portion of a reporting unit will be sold or otherwise disposed of. In addition, goodwill must be tested for impairment after a portion of goodwill has been allocated to a business to be disposed of.

FFIEC 031 and 041 **RI-19 RI - INCOME STATEMENT** (3-02)

Item No. **Caption and Instructions**

When a reporting unit is to be disposed of in its entirety, goodwill of that reporting unit must be 7.c.(1) included in the carrying amount of the reporting unit in determining the gain or loss on (cont.) disposal. When a portion of a reporting unit that constitutes a business is to be disposed of, goodwill associated with that business must be included in the carrying amount of the business in determining the gain or loss on disposal. Otherwise, a bank may not remove goodwill from its balance sheet, for example, by "selling" or "dividending" this asset to its parent holding company or another affiliate.

> Until interpretive guidance concerning the application of the purchase method of accounting for business combinations between two or more mutual institutions is issued by the FASB and takes effect, mutual institutions must continue to amortize goodwill over its estimated useful life, generally not to exceed 25 years, and test goodwill for impairment in accordance with APB Opinion No. 17. Mutual institutions should report goodwill amortization expense and any goodwill impairment losses in this item.

7.c.(2) Amortization expense and impairment losses for other intangible assets. Report the amortization expense of and any impairment losses on "Other intangible assets" (as defined for Schedule RC, item 10.b). Under FASB Statement No. 142, intangible assets that have indefinite useful lives should not be amortized but must be tested at least annually for impairment. Intangible assets that have finite useful lives must be amortized over their useful lives and must be reviewed for impairment in accordance with FASB Statement No. 144.

> Include in this item the amortization expense of and any impairment losses on any unidentifiable intangible assets recorded in accordance with FASB Statement No. 72. However, exclude the amortization expense of and any impairment losses on servicing assets, which should be netted against the servicing income reported in Schedule RI, item 5.f, "Net servicing fees," above.

7.d Other noninterest expense. Report all operating expenses of the bank for the calendar year-to-date not required to be reported elsewhere in Schedule RI. Disclose in Schedule RI-E, items 2.a through 2.j, each component of other noninterest expense, and the dollar amount of such component, that exceeds 1 percent of the sum of the bank's total interest income (from Schedule RI, item 1.h) and its total noninterest income (from Schedule RI, item 5.m). For each component of other noninterest expense that exceeds this disclosure threshold for which a preprinted caption has not been provided in Schedule RI-E, items 2.a through 2.g, describe the component with a clear but concise caption in Schedule RI-E, items 2.h though 2.j. These descriptions should not exceed 50 characters in length (including spacing between words).

<u>Include</u> as other noninterest expense:

- (1) Fees paid to directors and advisory directors for attendance at board of directors' or committee meetings (including travel and expense allowances). (Report the amount of these fees in Schedule RI-E, item 2.c, if this amount exceeds 1 percent of the sum of the bank's total interest income from Schedule RI, item 1.h, and its total noninterest income from Schedule RI, item 5.m.)
- (2) Cost of data processing services performed for the bank by others. (Report the amount of these expenses in Schedule RI-E, item 2.a, if this amount exceeds 1 percent of the sum of the bank's total interest income from Schedule RI, item 1.h, and its total noninterest income from Schedule RI, item 5.m.)

FFIEC 031 and 041 **RI-20 RI - INCOME STATEMENT**

Item No. **Caption and Instructions**

7.d (cont.)

- (3) Advertising, promotional, public relations, marketing, and business development expenses. Such expenses include the cost of athletic activities in which officers and employees participate when the purpose may be construed to be for marketing or public relations, and employee benefits are only incidental to the activities. (Report the amount of advertising and marketing expenses in Schedule RI-E, item 2.b, if this amount exceeds 1 percent of the sum of the bank's total interest income from Schedule RI, item 1.h, and its total noninterest income from Schedule RI, item 5.m.)
- (4) Cost of gifts or premiums (whether in the form of merchandise, credit, or cash) given to depositors at the time of the opening of a new account or an addition to, or renewal of, an existing account, if not included in advertising and marketing expenses above.
- (5) Retainer fees, legal fees, and other fees and expenses paid to attorneys who are not bank officers or employees and to outside law firms. (Report the amount of legal fees and expenses in Schedule RI-E, item 2.f, if this amount exceeds 1 percent of the sum of the bank's total interest income from Schedule RI, item 1.h, and its total noninterest income from Schedule RI, item 5.m.)
- (6) Cost of printing, stationery, and office supplies. (Report the amount of these expenses in Schedule RI-E, item 2.d, if this amount exceeds 1 percent of the sum of the bank's total interest income from Schedule RI, item 1.h, and its total noninterest income from Schedule RI, item 5.m.)
- (7) Postage and mailing expenses. (Report the amount of these expenses in Schedule RI-E, item 2.e, if this amount exceeds 1 percent of the sum of the bank's total interest income from Schedule RI, item 1.h, and its total noninterest income from Schedule RI, item 5.m.)
- (8) Telephone and telegraph expenses.
- (9) Federal deposit insurance assessments, including Financing Corporation (FICO) assessments. (Report the amount of these assessments in Schedule RI-E, item 2.g, if this amount exceeds 1 percent of the sum of the bank's total interest income from Schedule RI, item 1.h, and its total noninterest income from Schedule RI, item 5.m.)
- (10) Premiums on fidelity insurance (blanket bond, excess employee dishonesty bond), directors' and officers' liability insurance, and life insurance policies for which the bank is the beneficiary.
- (11) Assessment expense, examination expense, and other fees levied by the Comptroller of the Currency or a state chartering authority, net of any assessment credits during the period.
- (12) Legal fees and other direct costs incurred to effect foreclosures on real estate and subsequent noninterest expenses related to holdings of real estate owned other than bank premises (including depreciation charges, if appropriate).
- (13) Net losses (gains) from the sale or other disposal of branches (i.e., where the reporting bank sells a branch's assets to another depository institution, which assumes the deposit liabilities of the branch). Banks should consistently report these net losses (gains) either in this item or in Schedule RI, item 5.I.

FFIEC 031 and 041 RI-20a **RI - INCOME STATEMENT**

Item No. Caption and Instructions

7.d (cont.)

- (14) Net losses (gains) from all transactions involving foreign currency or foreign exchange other than trading transactions. Banks should consistently report these net losses (gains) either in this item or in Schedule RI, item 5.I.
- (15) Management fees assessed by the bank's parent holding company, whether for specific services rendered or of a general (prorated) nature.
- (16) Sales taxes, taxes based on the number of shares of bank stock outstanding, taxes based on the bank's total assets or total deposits, taxes based on the bank's gross revenues or gross receipts, capital stock taxes, and other taxes not included in other categories of expense. <u>Exclude</u> any foreign, state, and local taxes based on a net amount of revenues less expenses (report as applicable income taxes in Schedule RI, items 9).
- (17) Fees levied by deposit brokers that are, in substance, retainer fees or that otherwise do not represent an adjustment to the interest rate paid on deposits the reporting bank acquires through brokers. However, report as interest expense on the appropriate category of deposits those finders' fees and brokers' fees that do represent an adjustment to the interest rate paid on brokered deposits.
- (18) Research and development costs and costs incurred in the internal development of computer software.
- (19) Charges resulting from litigation or other claims.
- (20) Charitable contributions including donations by Clifford Trusts.
- (21) Fees for auditing and attestation services, retainer fees, and other fees and expenses paid to accountants, management consultants, investment counselors, and other professionals (other than attorneys providing legal services) who are not bank officers or employees.
- (22) Net losses (gains) on nonhedging derivative instruments held for purposes other than trading. Banks should consistently report these net losses (gains) either in this item or in Schedule RI, item 5.I. For further information, see the Glossary entry for "derivative contracts."
- (23) Net tellers' shortages (overages), net losses (recoveries) on forged checks, net losses (recoveries) on payment of checks over stop payment orders, and similar recurring operating losses (gains) of this type. Banks should consistently report these losses (gains) either in this item or in Schedule RI, item 5.I.
- (24) Minority interests in the net income or loss of the reporting bank's consolidated subsidiaries.
- (25) Losses from robberies, defalcations, and other criminal acts not covered by the bank's blanket bond.
- (26) Travel and entertainment expenses, including costs incurred by bank officers and employees for attending meetings and conventions.

FFIEC 031 and 041 RI-21 RI - INCOME STATEMENT (3-01)

Item No. Caption and Instructions

7.d (27) Dues, fees, and other expenses associated with memberships in country clubs, social or (cont.) private clubs, civic organizations, and similar clubs and organizations.

- (28) Civil money penalties and fines.
- (29) All service charges, commissions, and fees levied by others for the repossession of assets and the collection of the bank's loans or other assets, including charged-off loans or other charged-off assets.
- (30) Expenses (except salaries) related to handling credit card or charge sales received from merchants when the bank does not carry the related loan accounts on its books. Banks are also permitted to net these expenses against their charges to merchants for the bank's handling of these sales in Schedule RI, item 5.I.
- (31) Expenses related to the testing and training of officers and employees.
- (32) The cost of bank newspapers and magazines prepared for distribution to bank officers and employees or to others.
- (33) Depreciation expense of furniture and equipment rented to others under operating leases.
- (34) Cost of checks provided to depositors.
- (35) Amortization expense of purchased computer software and of the costs of computer software to be sold, leased, or otherwise marketed capitalized in accordance with the provisions of FASB Statement No. 86.
- (36) Provision for credit losses on off-balance sheet credit exposures.
- (37) Provision for allocated transfer risk.

Exclude from other noninterest expense:

- (1) Material expenses incurred in the issuance of subordinated notes and debentures (capitalize such expenses and amortize them over the life of the related notes and debentures and report the expense in Schedule RI, item 2.d, "Interest on subordinated notes and debentures").
- (2) Expenses incurred in the sale of preferred and common stock (deduct such expenses from the sale proceeds and credit the net amount to the appropriate stock account. For perpetual preferred and common stock only, report the net sales proceeds in Schedule RI-A, item 5, "Sale, conversion, acquisition, or retirement of capital stock, net").
- (3) Depreciation and other expenses related to the use of bank-owned automobiles, airplanes, and other vehicles for bank business (report in Schedule RI, item 7.b, "Expenses of premises and fixed assets").
- (4) Write-downs of the cost basis of individual held-to-maturity and available-for-sale securities for other than temporary impairments (report in Schedule RI, item 6.a, "Realized gains (losses) on held-to-maturity securities," and item 6.b, "Realized gains (losses) on available-for-sale securities," respectively).

FFIEC 031 and 041 RI-22 RI - INCOME STATEMENT

Item No. Caption and Instructions

Total noninterest expense. Report the sum of items 7.a through 7.d.

Report the bank's pretax operating income. This amount will generally be determined by taking item 3, "Net interest income," minus item 4, "Provision for loan and lease losses," plus item 5.m, "Total noninterest income," plus or minus item 6.a, "Realized gains (losses) on held-to-maturity securities," plus or minus item 6.b, "Realized gains (losses) on available-for-sale securities," minus item 7.e, "Total noninterest expense." If the result is negative, enclose it in parentheses.

Applicable income taxes on item 8. Report the total estimated federal, state and local, and foreign income tax expense applicable to item 8, "Income (loss) before income taxes and extraordinary items and other adjustments." Include both the current and deferred portions of these income taxes. If the amount is a tax benefit rather than tax expense, enclose it in parentheses.

<u>Include</u> as applicable income taxes all taxes based on a net amount of taxable revenues less deductible expenses. <u>Exclude</u> from applicable income taxes all taxes based on gross revenues or gross receipts (report such taxes in Schedule RI, item 7.d, "Other noninterest expense").

Include income tax effects of changes in tax laws or rates. Also include the effect of changes in the valuation allowance related to deferred tax assets resulting from a change in estimate of the realizability of deferred tax assets, excluding the effect of any valuation allowance changes related to unrealized holding gains (losses) on available-for-sale securities that are charged or credited directly to the separate component of equity capital for "Accumulated other comprehensive income" (Schedule RC, item 26.b).

<u>Include</u> the tax benefit of an operating loss carryforward or carryback for which the source of the income or loss in the current year is reported in Schedule RI, item 8, "Income (loss) before income taxes and extraordinary items and other adjustments."

Also <u>include</u> the dollar amount of any material adjustments or settlements reached with a taxing authority (whether negotiated or adjudicated) relating to disputed income taxes of prior years.

Exclude the estimated federal, state and local, and foreign income taxes applicable to:

- Schedule RI, item 11, "Extraordinary items and other adjustments, net of income taxes."
- (2) Schedule RI-A, item 2, "Restatements due to corrections of material accounting errors and changes in accounting principles."
- (3) Schedule RI-A, item 10, "Other comprehensive income."

Refer to the Glossary entry for "income taxes" for additional information.

FFIEC 031 and 041 RI-23 RI - INCOME STATEMENT

Item No. Caption and Instructions

Income (loss) before extraordinary items and other adjustments. Report the difference between item 9, "Applicable income taxes (on item 8)," and item 8, "Income (loss) before income taxes and extraordinary items and other adjustments." If the amount is negative, enclose it in parentheses.

11 Extraordinary items and other adjustments, net of income taxes. Report the total of the transactions listed below, if any, net of any applicable income tax effect. If the amount reported in this item is a net loss, enclose it in parentheses. State the dollar amount and provide a description of each transaction included in this item and any applicable income tax effect of the transaction in Schedule RI-E, item 3.

Include as extraordinary items and other adjustments:

- (1) The material effects of any extraordinary items. Extraordinary items are very rare and the criteria which must be satisfied in order for an event or transaction to be reported as an extraordinary item are discussed in the Glossary entry for "extraordinary items."
- (2) Material aggregate gains or losses from extinguishments of the reporting bank's own debt unrelated to sinking fund requirements, as determined in accordance with the provisions of FASB Statement No. 4, as amended.
- (3) Material aggregate gains on troubled debt restructurings of the reporting bank's own debt, as determined in accordance with the provisions of FASB Statement No. 15.
- (4) The cumulative effect of all changes in accounting principles except for those required to be reported in Schedule RI-A, item 2, "Restatements due to corrections of material accounting errors and changes in accounting principles." Refer to the Glossary entry for "accounting changes" for further discussion of changes in accounting principles.
- (5) Material aggregate gains or losses from disposals of segments of the bank's business, as determined in accordance with the provisions of APB Opinion No. 30.
- (6) Material net gains or losses from disposals of significant assets within two years after a pooling of interests business combination.

Exclude from extraordinary items and other adjustments:

- (1) Net gains (losses) from the sale or other disposal of:
 - (a) All assets reportable as loans and leases in Schedule RC-C.
 - (b) Premises and fixed assets.
 - (c) Other real estate owned.
 - (d) Personal property acquired for debts previously contracted (such as automobiles, boats, equipment, and appliances).
 - (e) Coins, art, and other similar assets.
 - (f) Branches (i.e., where the reporting bank sells a branch's assets to another depository institution which assumes the deposit liabilities of the branch).

For the first five categories above, banks should report net gains (losses) in the appropriate category of "Noninterest income" in Schedule RI, item 5. For the final category above, banks should consistently report net gains (losses) from branch sales as "Other noninterest income" in Schedule RI, item 5.I, or as "Other noninterest expense" in Schedule RI, item 7.d.

Item No. **Caption and Instructions**

(2) Write-downs of the cost basis of individual held-to-maturity and available-for-sale 11 (cont.) securities for other than temporary impairments (report in Schedule RI, item 6.a, "Realized gains (losses) on held-to-maturity securities," and item 6.b, "Realized gains (losses) on available-for-sale securities," respectively).

12 Net income (loss). Report the sum of items 10 and 11. This item must equal Schedule RI-A, item 4, "Net income (loss)." If this amount is a net loss, enclose it in parentheses.

FFIEC 031 and 041 **RI-25 RI - INCOME STATEMENT**


Memoranda

Item No. **Caption and Instructions**

1 Interest expense incurred to carry tax-exempt securities, loans, and leases acquired after August 7, 1986, that is not deductible for federal income tax purposes. Report the bank's best estimate of the amount of the year-to-date interest expense included in Schedule RI, item 2.e, "Total interest expense," that is subject to a 100 percent loss of deductibility for federal income tax purposes because it is deemed to have been incurred to carry tax-exempt securities, loans, and leases of states and political subdivisions in the U.S. acquired after August 7, 1986. Tax-exempt securities, loans, and leases are those securities, loans, and leases of states and political subdivisions in the U.S. whose interest is excludable from gross income under the regular tax system for federal income tax purposes, regardless of whether the income must be included in the bank's alternative minimum taxable income.

Exclude from this item interest expense incurred to carry (1) tax-exempt securities, loans, and leases of states and political subdivisions in the U.S. acquired after December 31, 1982, but before August 8, 1986, and (2) so-called "Qualified tax-exempt obligations" acquired after August 7, 1986, 20 percent of which is not deductible for federal income tax purposes.

The general formula that may be used for computing the amount of interest expense that is subject to a 100 percent loss of deductibility is as follows:



For the March 31, June 30, and September 30 Call Reports, the amount reported in Memorandum item 1 should not be an estimate of the amount of interest expense that will not be deductible for the entire calendar year.

2 Income from the sale and servicing of mutual funds and annuities (in domestic offices). Report the amount of income earned by the reporting bank during the calendar year-to-date from the sale and servicing of mutual funds and annuities (in domestic offices).

Include in this item:

(1) Income earned in connection with mutual funds and annuities that are sold on bank premises or are otherwise sold by the reporting bank, through a bank subsidiary, or by affiliated or unaffiliated entities from whom the bank receives income. This income may be in the form of fees or sales commissions at the time of the sale or fees, including a share of another entity's fees, that are earned over the duration of the account (e.g., annual fees, Rule 12b-1 fees or "trailer fees," and redemption fees). Commissions should be reported as income as earned at the time of the sale (i.e., on an accrual basis), but may be reported as income when payment is received if the results would not differ materially from those obtained using an accrual basis.

FFIEC 031 and 041 **RI-26 RI - INCOME STATEMENT**

Memoranda

Item No. Caption and Instructions

2 (cont.)

- (2) Income from leasing arrangements with affiliated and unaffiliated entities who lease space in bank offices for use in selling mutual funds and annuities. Income from leasing arrangements should be reported as income as earned (i.e., on an accrual basis), but may be reported as income when payment is received if the results would not differ materially from those obtained using an accrual basis.
- (3) Fees for providing investment advisory services for proprietary mutual funds and annuities.
- (4) Fees for providing securities custody, transfer agent, and other operational and ancillary services to mutual funds and annuities that are sold on bank premises or are otherwise sold by the reporting bank, through a bank subsidiary, or by affiliated or unaffiliated entities from whom the bank receives income at the time of the sale or over the duration of the account.

Also include income from sales conducted through the reporting bank's trust department that are <u>not</u> executed in a fiduciary capacity (e.g., trustee, executor, administrator, conservator), but exclude income from sales conducted by the trust department that are executed in a fiduciary capacity.

In general, this income will have been included in Schedule RI, item 5.d, "Investment banking, advisory, brokerage, and underwriting fees and commissions" (for mutual funds) and item 5.h, "Insurance commissions and fees" (for annuities). However, income from leasing arrangements, or the portion thereof, that is fixed in amount and does not vary based on sales volume may have been reported as a deduction from Schedule RI, item 7.b, "Expenses of premises and fixed assets." Thus, the income to be included in this item should be reported gross rather than net of expenses incurred by the reporting bank or a consolidated subsidiary.

Exclude fees earned for providing securities custody, transfer agent, and other operational and ancillary services to third party mutual funds and annuities that are <u>not</u> sold on bank premises and are <u>not</u> otherwise sold by the reporting bank, through a bank subsidiary, or by affiliated or unaffiliated entities from whom the bank receives income at the time of the sale or over the duration of the account.

- 3 Income on tax-exempt loans and leases to states and political subdivisions in the U.S. Report the bank's best estimate of the income earned on:
 - (1) Tax-exempt loans to states and political subdivisions in the U.S. reportable in Schedule RC-C, part I, item 8. On the FFIEC 041, this income will have been included in Schedule RI, item 1.a.(5), Interest and fee income on "All other loans" (except that, for banks with total assets of less than \$25 million for report dates during 2001, this income will have been included in Schedule RI, item 1.a.(6), "Total interest and fee income on loans"). On the FFIEC 031, this income will have been included in Schedule RI, item 1.a.(1)(f), Interest and fee income on "All other loans in domestic offices."
 - (2) Tax-exempt leases to states and political subdivisions in the U.S. reportable in Schedule RC-C, part I, item 10. This income will have been included in Schedule RI, item 1.b, "Income from lease financing receivables," above.

FFIEC 031 and 041 RI-27 RI - INCOME STATEMENT (3-01)

Memoranda

Item No. **Caption and Instructions**

3 Tax-exempt loans and leases are those loans and leases to states and political subdivisions (cont.) in the U.S. whose income is excludable from gross income for federal income tax purposes, regardless of whether the income from the loan or lease must be included in the bank's alternative minimum taxable income and regardless of the federal income tax treatment of the interest expense incurred to carry the loan or lease.

- 4 Income on tax-exempt securities issued by states and political subdivisions in the U.S. Report the bank's best estimate of the income earned on those securities issued by states and political subdivisions in the U.S. reportable in Schedule RC-B, item 3, the income from which is excludable from gross income for federal income tax purposes, regardless of whether the income from the securities must be included in the bank's alternative minimum taxable income and regardless of the federal income tax treatment of the interest expense incurred to carry the securities.
- 5 Number of full-time equivalent employees at end of current period. Report the number of full-time equivalent employees of the bank and its consolidated subsidiaries as of the report date (round to the nearest whole number). For purposes of this Memorandum item, a bank should include as employees individuals who, in form, are employed by an affiliate but who, in substance, do substantially all of their work for the reporting bank. However, banking organizations should not segregate the compensation component of other intercompany cost allocations arising from arrangements other than that described in the preceding sentence nor calculate the related pro rata number of full-time equivalent employees for purposes of this Memorandum item.

To convert the number of part-time employees to full-time equivalent employees, add the total number of hours all part-time and temporary employees worked during the quarter ending on the report date and divide this amount by the number of hours a full-time employee would have been expected to work during the quarter. Round the result to the nearest whole number and add it to the number of full-time employees. (A full-time employee may be expected to work more or less than 40 hours each week, depending on the policies of the reporting bank.)

NOTE: Memorandum item 6 is applicable only to banks filing the FFIEC 041 report form.

6 Interest and fee income on loans to finance agricultural production and other loans to farmers.

For report dates during 2001, Memorandum items 6 is to be completed by:

- banks with \$300 million or more in total assets, and
- banks with total assets of \$25 million or more but less than \$300 million and with loans to finance agricultural production and other loans to farmers (as reported in Schedule RC-C. part I, item 3, column B) exceeding five percent of total loans, net of unearned income.

FFIEC 031 and 041 **RI - INCOME STATEMENT RI-28**

Memoranda

Item No. Caption and Instructions

6 Beginning March 31, 2002, Memorandum item 6 is to be completed by: (cont.)

- banks with \$300 million or more in total assets, and
- banks with less than \$300 million in total assets and with loans to finance agricultural production and other loans to farmers (as reported in Schedule RC-C, part I, item 3, column B) exceeding five percent of total loans, net of unearned income.

All other banks should report a zero or the word "none" in this item.

Report in this item all interest, fees, and similar charges levied against or associated with all loans reportable in Schedule RC-C, part I, item 3, column B, "Loans to finance agricultural production and other loans to farmers."

If the reporting bank has restated its balance sheet as a result of applying push down accounting this calendar year, report the date of the bank's acquisition. If the reporting bank was acquired during the calendar year-to-date reporting period and applied push down accounting to its balance sheet in accordance with the "push down accounting" section of the Glossary entry for "business combinations," report the date (year, month, and day) as of which the acquisition took place. For example, a bank that was acquired as of the close of business June 1, 2001, and applied push down accounting to its balance sheet would report 20010601 in this Memorandum item in the Reports of Condition and Income for June 30, September 30, and December 31, 2001.

Push down accounting is the establishment of a new accounting basis for a bank in its separate financial statements (including its Call Report) as a result of a substantive change in control. When push down accounting is used to account for the acquisition of a bank that retains its separate corporate existence, the acquired bank's assets and liabilities (Schedule RC) are restated to their fair values as of the acquisition date. The bank's post-acquisition income statements (Schedule RI) only include amounts from the date of its acquisition through the end of the calendar year-to-date reporting period.

If the reporting bank has not been acquired during this calendar year or if the reporting bank has been acquired during this calendar year but push down accounting was not applied, the bank should report zeros (i.e., 00000000) in the year, month, and day columns of this Memorandum item.

8 Trading revenue (from cash instruments and derivative instruments).

Memorandum items 8.a through 8.d are to be completed by banks that reported average trading assets (in Schedule RC-K, item 7) of \$2 million or more for any quarter of the preceding calendar year.

Report, in the appropriate item below, a breakdown of trading revenue that has been included in the body of the income statement in Schedule RI, item 5.c. For each of the four types of underlying risk exposure, report the combined revenue (net gains and losses) from trading cash instruments and derivative instruments. For purposes of Memorandum item 8, the reporting bank should determine the underlying risk exposure category in which to report the trading revenue from cash instruments and derivative instruments in the same manner that the bank makes this determination for other financial reporting purposes. The sum of Memorandum items 8.a through 8.d must equal Schedule RI, item 5.c.

FFIEC 031 and 041 RI-29 RI - INCOME STATEMENT

Memoranda

Item No. **Caption and Instructions**

Interest rate exposures. Report in this item net gains (losses) from trading cash instruments 8.a and derivative contracts that the reporting bank manages as interest rate exposures. Interest rate exposures may arise from cash debt instruments (e.g., U.S. Treasury securities) and interest rate contracts. Interest rate contracts are those contracts related to an interestbearing financial instrument or whose cash flows are determined by referencing interest rates or another interest rate contract (e.g., an option on a futures contract to purchase a Treasury bill). Interest rate contracts include interest rate futures, single currency interest rate swaps, basis swaps, forward rate agreements, and interest rate options, including caps, floors, collars, and corridors.

> Exclude trading revenue on contracts involving the exchange of foreign currencies (e.g., cross-currency swaps and currency options) that the reporting bank manages as foreign exchange exposures. Report such trading revenue in Memorandum item 8.b.

- 8.b Foreign exchange exposures. Report in this item net gains (losses) from trading cash instruments and derivative contracts that the reporting bank manages as foreign exchange exposures. Foreign exchange exposures may arise from cash instruments (e.g., debt securities) denominated in non-U.S. currencies and foreign exchange rate contracts. Foreign exchange rate contracts are those contracts to purchase foreign (non-U.S.) currencies and U.S. dollar exchange in the forward market, i.e., on an organized exchange or in an over-the-counter market. A purchase of U.S. dollar exchange is equivalent to a sale of foreign currency. Foreign exchange rate contracts include cross-currency interest rate swaps where there is an exchange of principal, forward and spot foreign exchange contracts, and currency futures and currency options.
- 8.c Equity security and index exposures. Report in this item net gains (losses) from trading cash instruments and derivative contracts that the reporting bank manages as equity security or index exposures. Equity security or index exposures may arise from equity securities and equity security or index (i.e., equity derivative) contracts. Equity derivative contracts are contracts that have a return, or a portion of their return, linked to the price of a particular equity or to an index of equity prices, such as the Standard and Poor's 500.
- 8.d Commodity and other exposures. Report in this item net gains (losses) from trading cash instruments and derivative contracts that the reporting bank manages as commodity or other exposures. Commodity or other exposures may arise from commodities and commodity and other derivative contracts not reported as interest rate, foreign exchange, or equity derivative contracts. Commodity and other contracts are contracts that have a return, or a portion of their return, linked to the price or to an index of precious metals, petroleum, lumber, agricultural products, etc. Commodity and other contracts also include any other contracts that are not reportable as interest rate, foreign exchange, or equity derivative contracts.

FFIEC 031 and 041 **RI-30 RI - INCOME STATEMENT**

Memoranda

Item No. Caption and Instructions

9 Impact on income of derivatives held for purposes other than trading.

Memorandum items 9.a through 9.c are applicable to all banks filing the FFIEC 031 report forms and to those banks filing the FFIEC 041 report forms that have \$100 million or more in total assets.

For derivatives held for purposes other than trading, report in the appropriate subitem the impact that these contracts had on the bank's income as reported in Schedule RI.

- 9.a Net increase (decrease) to interest income. Report the net sum of all amounts reported in the interest income items of Schedule RI, i.e., items 1.a through 1.g, resulting from the bank's use of derivatives held for purposes other than trading. If the net sum is a net reduction in interest income, enclose this amount in parentheses.
- 9.b Net (increase) decrease to interest expense. Report the net sum of all amounts reported in the interest expense items of Schedule RI, i.e., items 2.a through 2.d, resulting from the bank's use of derivatives held for purposes other than trading. If the net sum is a net increase to interest expense, enclose this amount in parentheses.
- 9.c Other (noninterest) allocations. Report the net sum of all amounts reported in the noninterest items of Schedule RI, i.e., items 5 and 7, resulting from the bank's use of derivatives held for purposes other than trading. If the net sum is a net expense or loss, enclose this amount in parentheses.

Include gains (losses) on nonhedging derivative instruments held for purposes other than trading. Banks should consistently report these nonhedging derivative gains (losses) in either "Other noninterest income" (Schedule RI, item 5.1) or "Other noninterest expense" (Schedule RI, item 7.d).

10 Credit losses on derivatives.

Memorandum item 10 is applicable to all banks filing the FFIEC 031 report forms and to those banks filing the FFIEC 041 report forms that have \$300 million or more in total assets.

Report the bank's year-to-date credit losses (e.g., charge-offs) incurred on derivative contracts (as defined for Schedule RC-L, items 7 and 11). The amount reported in this item should include all credit losses recognized in the bank's income statement in any manner, e.g., as a charge against trading revenue.

FFIEC 031 and 041 **RI-31 RI - INCOME STATEMENT**

Memoranda

Item No. **Caption and Instructions**

Does the reporting bank have a Subchapter S election in effect for federal income tax 11 purposes for the current tax year? Indicate in the boxes marked "YES" and "NO" whether the bank is, for federal income tax purposes, either an "S corporation" or a "qualifying subchapter S subsidiary," as defined in Internal Revenue Code Section 1361, as of the report date. In order to be an S corporation, the bank must have filed a valid election with the Internal Revenue Service and obtained the consent of <u>all</u> of its shareholders. An election for a bank to be a qualifying subchapter S subsidiary must have been made by a bank's parent holding company, which must also have made a valid election to be an S corporation. In addition, the bank (and its parent holding company, if applicable) must meet specific criteria for federal income tax purposes at all times during which the election remains in effect. These specific criteria include, for example, having no more than 75 qualifying shareholders and having only one class of stock outstanding.

FFIEC 031 and 041 **RI - INCOME STATEMENT RI-32**

FFIEC 031 and 041 RI-A - EQUITY CAPITAL

SCHEDULE RI-A -- CHANGES IN EQUITY CAPITAL

General Instructions

This schedule is to be completed quarterly by all banks.

Total equity capital includes perpetual preferred stock, common stock, surplus, retained earnings, and accumulated other comprehensive income. All amounts in Schedule RI-A, other than those reported in items 1, 3, and 12, should represent net aggregate changes for the calendar year-to-date. Enclose all net decreases and losses (net reductions in equity capital) in parentheses.

Item No. Caption and Instructions

Total equity capital most recently reported for the December 31, 20xx, Reports of Condition and Income. Report the bank's total equity capital balance as reported in the Reports of Condition and Income for the previous calendar year-end after the effect of all corrections and adjustments to total equity capital that were made in any amended report(s) for the previous calendar year-end.

For banks opened since January 1 of the current calendar year, report a zero or the word "none" in this item. Report the bank's opening (original) total equity capital in Schedule RI-A, item 5, "Sale, conversion, acquisition, or retirement of capital stock, net."

Restatements due to corrections of material accounting errors and changes in accounting principles. Report the sum of all corrections, net of applicable income taxes, resulting from material accounting errors which were made in prior years' Reports of Condition and Income and not corrected by the filling of an amended report for the period in which the error was made and the cumulative effect, net of applicable income taxes, of those changes in accounting principles adopted during the calendar year-to-date reporting period that were applied retroactively and for which prior years' financial statements were restated.

Include only those corrections that result from:

- (1) Mathematical mistakes.
- (2) Mistakes in applying accounting principles.
- (3) Improper use of information which existed when the prior Reports of Condition and Income were prepared.
- (4) A change from an accounting principle that is neither accepted nor sanctioned by bank supervisors to one that is acceptable to supervisors.

The effect of accounting errors differs from the effect of changes in accounting estimates. Changes in accounting estimates are an inherent part of the accrual accounting process. Report the effect of any changes in accounting estimates in the appropriate line items of Schedule RI, Income Statement.

FFIEC 031 and 041 RI-A-1 RI-A - EQUITY CAPITAL

FFIEC 031 and 041 **RI-A - EQUITY CAPITAL**

Item No. **Caption and Instructions**

The cumulative effect of a change in accounting principle is the difference between (1) the balance in the retained earnings account at the beginning of the year in which the (cont.) change is made and (2) the balance in the retained earnings account that would have been reported at the beginning of the year had the newly adopted accounting principle been applied in all prior periods.

> The cumulative effect, if any, of all other changes in accounting principles adopted during the calendar year-to-date reporting period must be reported in Schedule RI, item 11, "Extraordinary items and other adjustments, net of income taxes."

State the dollar amount of and describe each accounting error correction and cumulative effect included in this item in Schedule RI-E, item 4.

Refer to the Glossary entry for "accounting changes" for additional information on how to report the effects of changes in accounting principles, corrections of errors, and changes in estimates.

- 3 Balance end of previous calendar year as restated. Report the sum of items 1 and 2.
- 4 Net income (loss). Report the net income (loss) for the calendar year-to-date as reported in Schedule RI, item 12, "Net income (loss)."
- 5 Sale, conversion, acquisition, or retirement of capital stock, net (excluding treasury stock transactions). Report the changes in the bank's total equity capital resulting from:
 - (1) Sale of the bank's perpetual preferred stock or common stock. Limited-life preferred stock is <u>not</u> included in equity capital; any proceeds from the sale of limited-life preferred stock during the calendar year-to-date is not to be reported in this schedule.
 - (2) Exercise of stock options, including:
 - (a) Any income tax benefits to the bank resulting from the sale of the bank's own stock acquired under a qualified stock option within three years of its purchase by the employee who had been granted the option.
 - (b) Any tax benefits to the bank resulting from the exercise (or granting) of nonqualified stock options (on the bank's stock) based on the difference between the option price and the fair market value of the stock at the date of exercise (or grant).
 - (3) Conversion of convertible debt, limited-life preferred stock, or perpetual preferred stock into perpetual preferred or common stock.
 - (4) Redemption of perpetual preferred stock or common stock.
 - (5) Retirement of perpetual preferred stock or common stock.
 - (6) Capital-related transactions involving the bank's Employee Stock Ownership Plan.

RI-A - EQUITY CAPITAL FFIEC 031 and 041 RI-A-2

FFIEC 031 and 041 RI-A - EQUITY CAPITAL

Item No. Caption and Instructions

5 <u>Include</u> in this item: (cont.)

(1) The net decrease in equity capital that occurs when cash is distributed in lieu of fractional shares in a stock dividend.

(2) The net increase in equity capital when a stockholder who receives a fractional share from a stock dividend purchases the additional fraction necessary to make a whole share.

<u>Exclude</u> treasury stock transactions from this item (report such transactions in Schedule RI-A, item 6, below).

For banks opened since January 1 of the year-to-date reporting period, report opening (original) equity capital in this item. Pre-opening income earned and expenses incurred from the bank's inception until the date the bank commenced operations should be reported in the Report of Income using one of the two following methods, consistent with the manner in which the bank reports pre-opening income and expenses for other financial reporting purposes:

- (1) Pre-opening income and expenses for the entire period from the bank's inception until the date the bank commenced operations should be reported in the appropriate items of Schedule RI, Income Statement, each quarter during the calendar year in which operations commenced; or
- (2) Pre-opening income and expenses for the period from the bank's inception until the beginning of the calendar year in which the bank commenced operations should be included, along with the bank's opening (original) equity capital, in this item. The net amount of these pre-opening income and expenses should be identified and described in Schedule RI-E, item 7. Pre-opening income earned and expenses incurred during the calendar year in which the bank commenced operations should be reported in the appropriate items of Schedule RI, Income Statement, each quarter during the calendar year in which operations commenced.
- Treasury stock transactions, net. Report the change in the bank's total equity capital during the calendar year to date from the acquisition (without retirement) and resale or other disposal of the bank's own perpetual preferred stock or common stock, i.e., treasury stock transactions (see the Glossary entry for "treasury stock").
- Changes incident to business combinations, net. If the bank has entered into a business combination which became effective during the year-to-date reporting period and which has been accounted for as a pooling of interests, report the historical equity capital balances of the bank or other business acquired as of the end of the previous calendar year. For further information on poolings of interests, refer to the Glossary entry for "business combinations."

If the bank purchased another bank or business during the year-to-date reporting period, report the fair value of any perpetual preferred or common shares issued (less the direct cost of issuing the shares). Exclude the fair value of limited-life preferred stock issued in connection with purchase acquisitions. Refer to the Glossary entry for "business combinations" for further information on purchase acquisitions.

FFIEC 031 and 041 RI-A-3 RI-A - EQUITY CAPITAL

FFIEC 031 and 041 **RI-A - EQUITY CAPITAL**

Caption and Instructions Item No.

7 If the bank has been acquired in a transaction accounted for using push down (cont.) accounting, report in this item the initial increase or decrease in equity capital that results from the application of push down accounting, i.e., the difference between the bank's total equity capital as of the end of the previous calendar year and its restated equity capital after the push down adjusting entries have been recorded as of the acquisition date. For further information on push down accounting, refer to the Glossary entry for "business combinations."

8 LESS: Cash dividends declared on preferred stock. Report all cash dividends declared on limited-life preferred and perpetual preferred stock during the calendar year-to-date, including dividends not payable until after the report date.

> Do not include dividends declared during the previous calendar year but paid in the current period.

Refer to the Glossary entry for "dividends" for further information on cash dividends.

9 LESS: Cash dividends declared on common stock. Report all cash dividends declared on common stock during the calendar year-to-date, including dividends not payable until after the report date.

> Do <u>not</u> include dividends <u>declared</u> during the previous calendar year but paid in the current period.

For further information on cash dividends, see the Glossary entry for "dividends."

10 Other comprehensive income. Report the bank's other comprehensive income for the calendar year-to-date. If the amount to be reported represents a reduction in the bank's equity capital, enclose it in parentheses.

Other comprehensive income includes:

- (1) The change during the calendar year-to-date in net unrealized holding gains (losses) on the bank's available-for-sale securities.
- (2) The change during the calendar year-to-date in the bank's accumulated net gains (losses) on cash flow hedges.
- (3) On the FFIEC 031 only, the increase or decrease during the calendar year-to-date in the bank's cumulative foreign currency translation adjustments and qualifying foreign currency transaction gains and losses, net of applicable income taxes, if any. Refer to the Glossary entry for "foreign currency transactions and translation" for further information on accounting for foreign currency translation.
- (4) The change during the calendar year-to-date in any minimum pension liability adjustment recognized in accordance with FASB Statement No. 87, Employers' Accounting for Pensions.

FFIEC 031 and 041 **RI-A - EQUITY CAPITAL** RI-A-4

FFIEC 031 and 041 **RI-A - EQUITY CAPITAL**

Item No. **Caption and Instructions**

11 Other transactions with parent holding company. Report the net aggregate amount of transactions with the bank's parent holding company which affect equity capital directly, other than those reported in Schedule RI-A, items 5, 6, 8, and 9, above, such as:

- (1) Capital contributions other than those for which stock has been issued to the parent holding company (report issuances of perpetual preferred and common stock and sales of treasury stock in Schedule RI-A, items 5 and 6, respectively; issuances of limited-life preferred stock are not reported in this schedule).
- (2) Dividends to the holding company in the form of property rather than cash (report cash dividends in Schedule RI-A, items 8 or 9, as appropriate). Record such property dividends at the fair value of the transferred asset. Include any gain or loss recognized on the disposition of the asset in the determination of net income for the calendar year-to-date in Schedule RI, Income Statement. Refer to the Glossary entry for "dividends" for additional information on property dividends.

State the dollar amount of and describe each transaction included in this item in Schedule RI-E, item 5.

12 Total equity capital end of current period. Report the sum of items 3 through 12. This item must equal Schedule RC, item 28, "Total equity capital."

FFIEC 031 and 041 **RI-A - EQUITY CAPITAL** RI-A-5

SCHEDULE RI-B -- CHARGE-OFFS AND RECOVERIES ON LOANS AND LEASES AND CHANGES IN ALLOWANCE FOR LOAN AND LEASE LOSSES

For those banks required to establish and maintain an allocated transfer risk reserve as specified in Section 905(a) of the International Lending Supervision Act of 1983, in the agency regulations implementing the Act (Subpart D of Federal Reserve Regulation K, Part 347 of the FDIC's Rules and Regulations, and Part 20 of the Comptroller of the Currency's Regulations), and in any guidelines, letters, or instructions issued by the agencies, this schedule excludes charge-offs and recoveries of loans and leases through such an allocated transfer risk reserve and excludes a reconcilement of this reserve.

Part I. Charge-offs and Recoveries on Loans and Leases

General Instructions

This part has two columns. In column A report loans and leases charged off against the allowance for loan and lease losses during the current calendar year-to-date. Also include in column A write-downs to fair value on loans (and leases) transferred to the held-for-sale account during the calendar year-to-date that occurred when (1) the reporting bank decided to sell loans that were not originated or otherwise acquired with the intent to sell and (2) the fair value of those loans had declined for any reason other than a change in the general market level of interest or foreign exchange rates. In column B report amounts recovered through the allowance for loan and lease losses during the calendar year-to-date on loans and leases previously charged off.

These instructions should be read in conjunction with the Glossary entries for "allowance for loan and lease losses" and "domicile."

Item Instructions

Item No. Caption and Instructions

- 1 <u>Loans secured by real estate</u>. Report in the appropriate subitem and column loans secured by real estate (as defined for Schedule RC-C, part I, item 1) charged off and recovered.
- **1.a** Construction, land development, and other land loans (in domestic offices). Report in columns A and B, as appropriate, construction, land development, and other land loans (as defined for Schedule RC-C, part I, item 1.a, column B) charged off and recovered.
- **1.b** Secured by farmland (in domestic offices). Report in columns A and B, as appropriate, loans secured by farmland (as defined for Schedule RC-C, part I, item 1.b, column B) charged off and recovered.
- 1.c Secured by 1-4 family residential properties (in domestic offices). Report in the appropriate subitem and column loans secured by 1-4 family residential properties (as defined for Schedule RC-C, part I, item 1.c, column B) charged off and recovered.
- 1.c.(1) Revolving, open-end loans secured 1-4 family residential properties and extended under lines of credit. Report in columns A and B, as appropriate, loans secured by revolving, open-end loans secured by 1-4 family residential properties and extended under line of credit (as defined for Schedule RC-C, part I, item 1.c.(1), column B) charged-off and recovered.

Part I. (cont.)

Item No. Caption and Instructions

1.c.(2) Closed-end loans secured by 1-4 family residential properties. Report in the appropriate subitem and column closed-end loans secured by 1-4 family residential properties (as defined for Schedule RC-C, part I, item 1.c.(2), column B) charged-off and recovered.

- **1.c.(2)(a)** Secured by first liens. Report in columns A and B, as appropriate, closed-end loans secured by first liens on 1-4 family residential properties (as defined for Schedule RC-C, part I, item 1.c.(2)(a), column B) charged-off and recovered.
- **1.c.(2)(b)** Secured by junior liens. Report in columns A and B, as appropriate, closed-end loans secured by junior liens on 1-4 family residential properties (as defined for Schedule RC-C, part I, item 1.c.(2)(b), column B) charged-off and recovered. Include loans secured by junior liens in this item even if the bank also holds a loan secured by a first lien on the same 1-4 family residential property and there are no intervening junior liens.
- **Secured by multifamily (5 or more) residential properties (in domestic offices)**. Report in columns A and B, as appropriate, loans secured by multifamily (5 or more) residential properties (as defined for Schedule RC-C, part I, item 1.d, column B) charged-off and recovered.
- **Secured by nonfarm nonresidential properties (in domestic offices).** Report in columns A and B, as appropriate, loans secured by nonfarm nonresidential properties (as defined for Schedule RC-C, part I, item 1.e, column B) charged-off and recovered.

NOTE: Item 1.f is applicable only to banks filing the FFIEC 031 report form.

- **1.f** In foreign offices. Report in columns A and B, as appropriate, loans secured by real estate (as defined for Schedule RC-C, part I, item 1) in foreign offices charged-off and recovered.
- 2 Loans to depository institutions and acceptances of other banks. Report in columns A and B, as appropriate, loans to depository institutions and acceptances of other banks (as defined for Schedule RC-C, part I, item 2) charged-off and recovered.

NOTE: Items 2.a, 2.b, and 3 are applicable only to banks filing the FFIEC 031 report form.

- **To U.S. banks and other U.S. depository institutions.** Report in columns A and B, as appropriate, loans to and acceptances of U.S. banks and other U.S. depository institutions (as defined for Schedule RC-C, part 1, items 2.a.(2), 2.b, and 2.c.(1), column A) charged-off and recovered.
- **To foreign banks.** Report in columns A and B, as appropriate, loans to and acceptances of foreign banks (as defined for Schedule RC-C, part I, items 2.a.(1) and 2.c.(2), column A) charged-off and recovered.
- 3 Loans to finance agricultural production and other loans to farmers. Report in columns A and B, as appropriate, loans to finance agricultural production and other loans to farmers (as defined for Schedule RC-C, part I, item 3, column A) charged-off and recovered.
- **Commercial and industrial loans.** Report in columns A and B, as appropriate, commercial and industrial loans (as defined for Schedule RC-C, part I, item 4) charged-off and recovered.

Part I. (cont.)

Item No. Caption and Instructions

NOTE: Items 4.a and 4.b are applicable only to banks filing the FFIEC 031 report form.

To U.S. addressees (domicile). Report in columns A and B, as appropriate, commercial and industrial loans to U.S. addressees (as defined for Schedule RC-C, part I, item 4.a, column A) charged-off and recovered.

- **To non-U.S. addressees.** Report in columns A and B, as appropriate, commercial and industrial loans to U.S. addressees (as defined for Schedule RC-C, part I, item 4.b, column A) charged-off and recovered.
- Loans to individuals for household, family, and other personal expenditures. Report in the appropriate subitem and column loans to individuals for household, family, and other personal expenditures (as defined for Schedule RC-C, part I, item 6) charged-off and recovered.
- **5.a Credit cards.** Report in columns A and B, as appropriate, all extensions of credit under credit cards (as defined for Schedule RC-C, part I, items 6.a) charged-off and recovered.
- 5.b Other (includes single payment, installment, all student loans, and revolving credit plans other than credit cards). Report in columns A and B, as appropriate, all extensions of credit to individuals for household, family, and other personal expenditures other than credit cards (as defined for Schedule RC-C, part I, items 6.b and 6.c) charged-off and recovered.
- **Loans to foreign governments and official institutions.** Report in columns A and B, as appropriate, loans to foreign governments and official institutions (as defined for Schedule RC-C, part I, item 7) charged-off and recovered.
- All other loans. On the FFIEC 041, report in columns A and B, as appropriate, loans to finance agricultural production and other loans to farmers, obligations (other than securities and leases) of states and political subdivisions in the U.S., and other loans (as defined for Schedule RC-C, part I, items 3, 8, and 9) charged-off and recovered. On the FFIEC 031, report in columns A and B, as appropriate, obligations (other than securities and leases) of states and political subdivisions in the U.S. and other loans (as defined for Schedule RC-C, part I, items 8 and 9) charged-off and recovered.
- **Lease financing receivables.** Report in columns A and B, as appropriate, all lease financing receivables (as defined for Schedule RC-C, part I, item 10) charged-off and recovered.

NOTE: Items 8.a and 8.b are applicable only to banks filing the FFIEC 031 report form.

- **To U.S. addressees (domicile).** Report in columns A and B, as appropriate, all lease financing receivables to U.S. addressees (as defined for Schedule RC-C, part I, item 10.a, column A) charged-off and recovered.
- **To non-U.S. addressees (domicile).** Report in columns A and B, as appropriate, all lease financing receivables to non-U.S. addressees (as defined for Schedule RC-C, part I, item 10.b, column A) charged-off and recovered.
- **Total.** Report in columns A and B the sum of item 1 through 8. The amount reported in column A must equal Schedule RI-B, part II, item 3, "Charge-offs," below. The amount reported in column B must equal Schedule RI-B, part II, item 2, "Recoveries," below.

Part I. (cont.)

Memoranda

Item No. Caption and Instructions

1 Loans to finance commercial real estate, construction, and land development activities (not secured by real estate) included in Schedule RI-B, part I, items 4 and 7, above. Report in columns A and B, as appropriate, loans to finance commercial real estate, construction, and land development activities not secured by real estate (as defined for Schedule RC-C, part I, Memorandum item 3) charged off and recovered. Such loans will have been included in items 4 and 7 of Schedule RI-B, part I, above. Exclude from this item all loans secured by real estate included in item 1 of Schedule RI-B, part I, above.

FFIEC 031 FFIEC 041

Item No. Item No. Caption and Instructions

NOTE: On the FFIEC 041, Memorandum items 2.a through 2.d are to be completed by banks that have \$300 million or more in total assets.

2 Loans secured by real estate to non-U.S. addressees (domicile). Report in 2.a columns A and B, as appropriate, loans secured by real estate to non-U.S. addressees (as defined for Schedule RC-C, part 1, Memorandum item 5) charged off and recovered. Such loans will have been included in Schedule RI-B, part I, item 1, above.

FFIEC 041

Item No. **Caption and Instructions**

NOTE: On the FFIEC 041, Memorandum items 2.b through 2.d are to be completed by banks that have \$300 million or more in total assets.

- 2.b Loans to and acceptances of foreign banks. Report in columns A and B, as appropriate, loans to and acceptances of foreign banks (as defined for Schedule RC-C, part I, items 2.a.(1) and 2.c.(2), column A) charged off and recovered. Such loans and acceptances will have been included in Schedule RI-B, part I, item 2, above.
- 2.c Commercial and industrial loans to non-U.S. addressees (domicile). Report in columns A and B, as appropriate, commercial and industrial loans to non-U.S. addressees (as defined for Schedule RC-C, part I, item 4.b, column A) charged off and recovered. Such loans will have been included in Schedule RI-B, part I, item 4, above.
- 2.d Lease financing receivables of non-U.S. addressees (domicile). Report in columns A and B, as appropriate, lease financing receivables of non-U.S. addressees (as defined for Schedule RC-C, part I, item 10.b, column A) charged off and recovered. Such leases will have been included in Schedule RI-B, part I, item 8, above.

Part I. (cont.)

Memoranda

FFIEC 041

Item No. Caption and Instructions

3 Loans to finance agricultural production and other loans to farmers.

Memorandum item 3 is to be completed by:

- banks with \$300 million or more in total assets, and
- banks with less than \$300 million in total assets and with loans to finance agricultural production and other loans to farmers (as reported in Schedule RC-C, part I, item 3, column B) exceeding five percent of total loans, net of unearned income.

Report in columns A and B, as appropriate, loans to finance agricultural production and other loans to farmers (as defined for Schedule RC-C, part I, item 3, column B) charged off and recovered. Such loans will have been included in Schedule RI-B, part I, item 7, above.

FFIEC 031 and 041 RI-B-5 RI-B - ALLOWANCE

Part II. Changes In Allowance for Loan and Lease Losses

General Instructions

Report the reconcilement of the allowance for loan and lease losses on a calendar year-to-date basis. This schedule is to be completed quarterly by all banks.

Exclude the balances of the allowance for credit losses on off-balance sheet credit exposures reported in Schedule RC-G, item 3, and any capital reserves included in Schedule RC, item 26.a, "Retained earnings," and the effects of any transactions therein.

Refer to the Glossary entry for "allowance for loan and lease losses" for further information.

Business Combinations and Push Down Accounting Transactions -- If the bank has entered into a business combination that became effective during the reporting period which has been accounted for as a pooling of interests, include the recoveries, charge-offs, and provisions of the combined bank or other business for the calendar year-to-date. Report the balance as of the end of the previous calendar year of the allowance for loan and lease losses of the bank or other business acquired in the pooling in item 6, "Adjustments."

If the bank purchased another bank or business during the reporting period, include the recoveries, charge-offs, and provisions of the acquired bank or other business <u>only</u> after its acquisition. Report the amount of the allowance for loan and lease losses of the acquired bank or other business as of the effective date of the business combination in item 6, "Adjustments."

If the bank was acquired in a transaction which became effective during the reporting period and push down accounting was used to account for the acquisition, include only the recoveries, charge-offs, and provisions from the effective date of the bank's acquisition through the end of the year-to-date reporting period. Report the change in the balance of the allowance for loan and lease losses from the end of the previous calendar year through the effective date of the bank's acquisition in item 6, "Adjustments."

For further information on poolings of interests, purchase acquisitions, and push down accounting, see the Glossary entry for "business combinations."

Item Instructions

Item No. Caption and Instructions

Balance most recently reported in the December 31, 20xx, Reports of Condition and Income. Report the balance of the bank's allowance for loan and lease losses as reported in the Reports of Condition and Income for the previous calendar year-end after the effect of all corrections and adjustments to the allowance for loan and lease losses that were made in any amended report(s) for the previous calendar year-end.

FFIEC 031 and 041 RI-B-6 RI-B - ALLOWANCE

Part II. (cont.)

Item No. Caption and Instructions

Recoveries. Report the amount credited to the allowance for loan and lease losses for recoveries during the calendar year-to-date on amounts previously charged against the allowance for loan and lease losses. The amount reported in this item must equal Schedule RI-B, part I, item 9, column B.

- 3 LESS: Charge-offs. Report the amount of all loans and leases charged against the allowance for loan and lease losses during the calendar year-to-date. The amount reported in this item must equal Schedule RI-B, part I, item 9, column A, "Total" charge-offs, less Schedule RI-B, part II, item 4, "LESS: Write-downs arising from transfers of loans to a held-for-sale account."
- 4 LESS: Write-downs arising from transfers of loans to a held-for-sale account. Report the amount of write-downs to fair value charged against the allowance for loan and lease losses resulting from transfers of loans and leases to a held-for-sale account during the calendar year-to-date that occurred when:
 - the reporting bank decided to sell loans and leases that were not originated or otherwise acquired with the intent to sell, and
 - the fair value of those loans and leases had declined for any reason other than a change in the general market level of interest or foreign exchange rates.
- Provision for loan and lease losses. Report the amount expensed as the provision for loan and losses during the calendar year-to-date. The provision for loan and lease losses represents the amount needed to make the allowance for loan and lease losses adequate to absorb estimated loan and lease losses, based upon management's evaluation of the bank's current loan and lease exposures. The amount reported in this item must equal Schedule RI, item 4. If the amount reported in this item is negative, enclose it in parentheses.
- Adjustments. Report the allowance for loan and lease losses of a bank or other business acquired in a business combination during the calendar year-to-date reporting period. Determine the amount to be reported in this item in accordance with the General Instructions at the beginning of part II.

If the bank was acquired in a transaction which became effective during the reporting period and push down accounting was used to account for the acquisition, report the change in the balance of the allowance for loan and lease losses from the end of the previous calendar year through the effective date of the bank's acquisition in this item.

For those banks required to establish and maintain an allocated transfer risk reserve, report all allowable adjustments made during the reporting period between the regular allowance for loan and lease losses and the allocated transfer risk reserve as specified in Section 905(a) of the International Lending Supervision Act of 1983, in the agency regulations implementing the Act (Federal Reserve Regulation K, Part 347 of the FDIC Rules and Regulations, and Part 20 of the Comptroller of the Currency's Regulations), and in any guidelines, letters, or instructions issued by the agencies.

FFIEC 031 and 041 RI-B-7 RI-B - ALLOWANCE

Part II. (cont.)

Item No. Caption and Instructions

For banks with foreign offices that file the FFIEC 031 report forms, report any increases or decreases resulting from the translation into dollars of any portions of the allowance for loan and lease losses which are denominated in a foreign currency.

If the amount reported in this item is negative, enclose it in parentheses.

State the dollar amount of and describe each transaction included in this item in Schedule RI-E, Explanations, item 6.

Report the sum of items 1, 2, 5, and 6, less items 3 and 4. The amount reported in this item must equal Schedule RC, item 4.c, "Allowance for loan and lease losses."

(3-02)

SCHEDULE RI-D -- INCOME FROM INTERNATIONAL OPERATIONS

General Instructions

Schedule RI-D is applicable only to certain banks that file the FFIEC 031 report forms.

Banks with foreign offices, Edge or Agreement subsidiaries, or IBFs are required to complete this schedule if their international operations account for more than 10 percent of their total revenues, total assets, or net income; otherwise, banks need not complete this schedule.

Banks that are required to complete this schedule should report estimates of the amounts of their income and expense attributable to international operations after eliminating intracompany accounts. These estimates should reflect all appropriate internal allocations of income and expense, whether or not "booked" that way in the bank's formal accounting records. To the extent feasible, banks should attempt to maintain consistency over time in their procedures for making such allocations.

Item Instructions

Item No. Caption and Instructions

- 1 Interest income and expense attributable to international operations:
- **Gross interest income**. Report the bank's best estimate of that portion of total interest income, including fees and other interest associated charges, (reported in Schedule RI, item 1.h) that is allocable to international operations.
- **1.b Gross interest expense.** Report the bank's best estimate of that portion of total interest expense (reported in Schedule RI, item 2.e) that is allocable to international operations.
- 2 Net interest income attributable to international operations. Report the difference between items 1.a and 1.b. If the result is negative, enclose it in parentheses.
- 3 Noninterest income and expense attributable to international operations:
- 3.a Noninterest income attributable to international operations. Report the bank's best estimate of that portion of Schedule RI, item 5.m, "Total noninterest income," item 6.a, "Realized gains (losses) on held-to-maturity securities," item 6.b, "Realized gains (losses) on available-for-sale securities," and item 11, "Extraordinary items and other adjustments, net of income taxes," that is allocable to international operations.
- 3.b <u>Provision for loan and lease losses attributable to international operations</u>. Report the bank's best estimate of that portion of the provision for loan and lease losses (reported in Schedule RI, item 4) that is allocable to loans and leases to non-U.S. addressees.
- **3.c** Other noninterest expense attributable to international operations. Report the bank's best estimate of that portion of Schedule RI, item 7.e, "Total noninterest expense," that is allocable to international operations.
- **3.d** Net noninterest income (expense) attributable to international operations. Report the total of item 3.a less items 3.b and 3.c. If the result is negative, enclose it in parentheses.

Item No. Caption and Instructions

- Estimated pretax income attributable to international operations before capital allocation adjustment. Report the sum of items 2 and 3.d. If the amount is negative, enclose it in parentheses. This amount represents the bank's best estimate of income before a capital allocation adjustment and income taxes that is attributable to international operations. The estimate should reflect all appropriate internal allocations of income and expense.
- Adjustment to pretax income for internal allocations to international operations to reflect the effects of equity capital on overall bank funding costs. Report any amount credited to estimated pretax income attributable to international operations that reflects management's estimate of the effect of equity capital allocable to international operations. Equity capital, which is interest-free, helps to reduce a bank's overall funding costs and increase net interest income.
- **Estimated pretax income attributable to international operations after capital allocation adjustment**. Report the sum of items 4 and 5. If the result is negative, enclose it in parentheses.
- 7 Income taxes attributable to income from international operations as estimated in item 6. Report the bank's best estimate of income taxes, both U.S. and foreign, that are applicable to estimated pretax income attributable to international operations.
- **Estimated net income attributable to international operations**. Report the difference between item 6 and item 7. If the result is negative, enclose it in parentheses. This amount represents the bank's best estimate of net income attributable to international operations.

FFIEC 031

FFIEC 031 and 041 RI-E - EXPLANATIONS

SCHEDULE RI-E -- EXPLANATIONS

General Instructions

Schedule RI-E is to be completed each quarter on a calendar year-to-date basis. On those lines for which your bank must provide a description of the amount being reported, the description should not exceed 50 characters (including punctuation and spacing between words). If additional space is needed to complete a description, item 7 of this schedule may be used.

Item No. Caption and Instructions

Other noninterest income. Disclose in items 1.a through 1.h each component of Schedule RI, item 5.l, "Other noninterest income," and the dollar amount of such component, that exceeds 1 percent of the sum of "Total interest income" and "Total noninterest income" (Schedule RI, item 1.h plus item 5.m).

Preprinted captions have been provided for the following categories of "Other noninterest income":

- Item 1.a, "Income and fees from the printing and sale of checks,"
- Item 1.b, "Earnings on/increase in value of cash surrender value of life insurance,"
- Item 1.c, "Income and fees from automated teller machines (ATMs),"
- Item 1.d, "Rent and other income from other real estate owned," and
- Item 1.e, "Safe deposit box rent."

For other components of "Other noninterest income" that exceed the disclosure threshold, list and briefly describe these components in items 1.f through 1.h and, if necessary, in Schedule RI-E, item 7, below.

2 Other noninterest expense. Disclose in items 2.a through 2.j each component of Schedule RI, item 7.d, "Other noninterest expense," and the dollar amount of such component, that exceeds 1 percent of the sum of "Total interest income" and "Total noninterest income" (Schedule RI, item 1.h plus item 5.m).

Preprinted captions have been provided for the following categories of "Other noninterest expense":

- Item 2.a, "Data processing expenses,"
- Item 2.b, "Advertising and marketing expenses,"
- Item 2.c, "Directors' fees,"
- Item 2.d, "Printing, stationery, and supplies,"
- Item 2.e, "Postage,"
- Item 2.f, "Legal fees and expenses," and
- Item 2.g, "FDIC deposit insurance assessments."

For other components of "Other noninterest expense" that exceed the disclosure threshold, list and briefly describe these components in items 2.h through 2.j and, if necessary, in Schedule RI-E, item 7, below.

Extraordinary items and other adjustments and applicable income tax effect. List and briefly describe in items 3.a, 3.b, and 3.c the gross dollar amount of each item included in Schedule RI, item 11, "Extraordinary items and other adjustments, net of income taxes," and its related income tax effect, if any. If Schedule RI, item 11, includes more than three items, report the additional items and their related tax effects in Schedule RI-E, item 7, below.

FFIEC 031 and 041 RI-E - EXPLANATIONS

Item No. Caption and Instructions

If an extraordinary item or other adjustment is a loss or otherwise reduces the bank's (cont.) income, enclose the dollar amount reported in parentheses. If an applicable income tax effect is a tax benefit (rather than a tax expense), enclose the dollar amount reported in parentheses.

Restatements due to corrections of material accounting errors and changes in accounting principles. List and briefly describe in items 4.a and 4.b the dollar amount of each correction of a material accounting error and cumulative effect of a change in accounting principles, net of applicable income taxes, that is included in Schedule RI-A, item 2. If Schedule RI-A, item 2, includes more than two accounting error corrections and accounting principle changes, report the additional corrections and cumulative effects in Schedule RI-E, item 7, below.

If an accounting error correction or a cumulative effect of an accounting principle change represents a reduction of the bank's equity capital, enclose the dollar amount reported in parentheses.

Other transactions with parent holding company. List and briefly describe in items 5.a and 5.b the dollar amount of each type of other transaction with the bank's parent holding company that is included in Schedule RI-A, item 11. If Schedule RI-A, item 11, includes more than two types of other transactions, report the additional types of other transactions in Schedule RI-E, item 7, below.

If the effect of a type of other transaction with the bank's parent holding company is to reduce the bank's equity capital, enclose the dollar amount reported in parentheses.

Adjustments to allowance for loan and lease losses. List and briefly describe in items 6.a and 6.b the dollar amount of each type of adjustment to the allowance for loan and lease losses that is included in Schedule RI-B, part II, item 6. If Schedule RI-B, part II, item 6, includes more than two types of adjustments, report the additional adjustments in Schedule RI-E, item 7, below.

If the effect of an adjustment is to reduce the bank's allowance for loan and lease losses, enclose the dollar amount reported in parentheses.

Other explanations. In the space provided on the report form, the bank may, at its option, list and briefly describe any other significant items relating to the Report of Income. The bank's other explanations must not exceed 750 characters, including punctuation and standard spacing between words and sentences.

FFIEC 031 and 041 RI-E-2 RI-E - EXPLANATIONS

FFIEC 031 and 041 **RC - BALANCE SHEET**

LINE ITEM INSTRUCTIONS FOR THE CONSOLIDATED REPORT OF CONDITION

The line item instructions should be read in conjunction with the Glossary and other sections of these instructions. See the discussion of the Organization of the Instruction Books in the General Instructions.

SCHEDULE RC -- BALANCE SHEET

ASSETS

Item No. Caption and Instructions

1 Cash and balances due from depository institutions. On the FFIEC 031, the sum of Schedule RC, items 1.a and 1.b, must equal Schedule RC-A, item 5, column A, "Total." On the FFIEC 041. Schedule RC-A is not applicable to banks with less than \$300 million in total assets; for banks with \$300 million or more in total assets, the sum of Schedule RC, items 1.a and 1.b, must equal Schedule RC-A, item 5, "Total."

Treatment of reciprocal balances with depository institutions -- Reciprocal balances arise when two depository institutions maintain deposit accounts with each other, i.e., when a reporting bank has both a "due from" and a "due to" balance with another depository institution. Reciprocal balances between the reporting bank and other depository institutions may be reported on a net basis when a right of setoff exists. Net "due from" balances should be reported in items 1.a and 1.b below, as appropriate. Net "due to" balances should be reported as deposit liabilities in Schedule RC, item 13 below. See the Glossary entry for "offsetting" for the conditions that must be met for a right of setoff to exist. See also the Glossary entry for "reciprocal balances."

Noninterest-bearing balances and currency and coin. Report the total of all 1.a noninterest-bearing balances due from depository institutions, currency and coin, cash items in process of collection, and unposted debits. On the FFIEC 031, the components of this item will also be included in the appropriate items of Schedule RC-A, column A. On the FFIEC 041, for banks with \$300 million or more in total assets, the components of this item will also be included in the appropriate items of Schedule RC-A.

> For purposes of these reports, deposit accounts "due from" other depository institutions that are overdrawn are to be reported as borrowings in Schedule RC, item 16, and in Schedule RC-M, item 5.b, except overdrawn "due from" accounts arising in connection with checks or drafts drawn by the reporting bank and drawn on, or payable at or through, another depository institution either on a zero-balance account or on an account that is not routinely maintained with sufficient balances to cover checks or drafts drawn in the normal course of business during the period until the amount of the checks or drafts is remitted to the other depository institution (in which case, report the funds received or held in connection with such checks or drafts as deposits in Schedule RC-E until the funds are remitted). For further information, refer to the Glossary entry for "overdraft."

FFIEC 031 and 041 **RC - BALANCE SHEET** RC-1

FFIEC 031 and 041 RC - BALANCE SHEET

Item No. Caption and Instructions

1.a Cash items in process of collection include: (cont.)

(1) Checks or drafts in process of collection that are drawn on another depository institution (or on a Federal Reserve Bank) and that are payable immediately upon presentation in the United States. This includes:

- (a) Checks or drafts drawn on other institutions that have already been forwarded for collection but for which the reporting bank has not yet been given credit ("cash letters").
- (b) Checks or drafts on hand that will be presented for payment or forwarded for collection on the following business day.
- (c) Checks or drafts that have been deposited with the reporting bank's correspondent and for which the reporting bank has already been given credit, but for which the amount credited is <u>not</u> subject to immediate withdrawal ("ledger credit" items).

However, if the reporting bank has been given immediate credit by its correspondent for checks or drafts presented for payment or forwarded for collection <u>and</u> if the funds on deposit are subject to immediate withdrawal, the amount of such checks or drafts is considered part of the reporting bank's balances due from depository institutions.

- (2) Government checks drawn on the Treasurer of the United States or any other government agency that are payable immediately upon presentation and that are in process of collection.
- (3) Such other items in process of collection that are payable immediately upon presentation and that are customarily cleared or collected as cash items by depository institutions in the United States, such as:
 - (a) Redeemed United States savings bonds and food stamps.
 - (b) Amounts associated with automated payment arrangements in connection with payroll deposits, federal recurring payments, and other items that are credited to a depositor's account prior to the payment date to ensure that the funds are available on the payment date.
 - (c) Federal Reserve deferred account balances until credit has been received in accordance with the appropriate time schedules established by the Federal Reserve Banks. At that time, such balances are considered part of the reporting bank's balances due from depository institutions.
 - (d) Checks or drafts drawn on another depository institution that have been deposited in one office of the reporting bank and forwarded for collection to another office of the reporting bank.
 - (e) Brokers' security drafts and commodity or bill-of-lading rafts payable immediately upon presentation in the U.S. (See the Glossary entries for "broker's security draft" and "commodity or bill-of-lading draft" for the definitions of these terms.)

FFIEC 031 and 041 RC - BALANCE SHEET

Item No. Caption and Instructions

1.a Exclude from cash items in process of collection: (cont.)

(1) Cash items for which the reporting bank has already received credit, provided that the funds on deposit are subject to immediate withdrawal. The amount of such cash items is considered part of the reporting bank's balances due from depository institutions.

- (2) Credit or debit card sales slips in process of collection (report as noncash items in Schedule RC-F, item 5, "Other" assets). However, when the reporting bank has been notified that it has been given credit, the amount of such sales slips is considered part of the reporting bank's balances due from depository institutions.
- (3) Cash items not conforming to the definition of in process of collection, whether or not cleared through Federal Reserve Banks (report in Schedule RC-F, item 5, "Other" assets).
- (4) Commodity or bill-of-lading drafts (including arrival drafts) not yet payable (because the merchandise against which the draft was drawn has not yet arrived), whether or not deposit credit has been given. (If deposit credit has been given, report as loans in the appropriate item of Schedule RC-C, part I; if the drafts were received on a collection basis, they should be excluded entirely from the bank's balance sheet, Schedule RC, until the funds have actually been collected.)

<u>Unposted debits</u> are cash items in the bank's possession, drawn on itself, that are immediately chargeable, but that have not been charged to the general ledger deposit control account at the close of business on the report date. All banks including an amount for unposted debits in this item should also see Schedule RC-O, item 1.a or 1.b, "Unposted debits."

<u>Currency and coin</u> include both U.S. and foreign currency and coin owned and held in all offices of the reporting bank, currency and coin in transit to a Federal Reserve Bank or to any other depository institution for which the reporting bank has not yet received credit, and currency and coin in transit from a Federal Reserve Bank or from any other depository institution for which the reporting bank's account has already been charged. Foreign currency and coin should be converted into U.S. dollar equivalents as of the report date.

Noninterest-bearing balances due from depository institutions include balances due from Federal Reserve Banks (including reserve and other balances), commercial banks in the U.S., other depository institutions in the U.S. (e.g., credit unions, mutual and stock savings banks, savings or building and loan associations, and cooperative banks), Federal Home Loan Banks, banks in foreign countries, and foreign central banks. Noninterest-bearing balances include those noninterest-bearing funds on deposit at other depository institutions for which the reporting bank has already received credit and which are subject to immediate withdrawal. Balances for which the bank has not yet received credit and balances representing checks or drafts for which immediate credit has been given but which are not subject to immediate withdrawal are considered "cash items in process of collection."

Item No. Caption and Instructions

1.a <u>Include</u> as noninterest-bearing balances due from depository institutions: (cont.)

(1) Noninterest-bearing balances due from the reporting bank's correspondents, including amounts that its correspondent is to pass through or already has passed through to a Federal Reserve Bank on behalf of the reporting bank (see the Glossary entry for "pass-through reserve balances" for further discussion).

- (2) Noninterest-bearing balances that reflect deposit credit received by the reporting bank because of credit or debit card sales slips that had been forwarded for collection. (Until credit has been received, report as noncash items in process of collection in Schedule RC-F, item 5, "Other" assets.)
- (3) Amounts that the reporting bank has <u>actually</u> passed through to a Federal Reserve Bank on behalf of its respondent depository institutions (see the Glossary entry for "pass-through reserve balances" for further discussion).

Exclude from noninterest-bearing balances due from depository institutions:

- (1) Deposit accounts "due to" other depository institutions that are overdrawn (report in Schedule RC-C, part I, item 2, "Loans to depository institutions and acceptances of other banks").
- (2) All noninterest-bearing balances that the reporting bank's trust department maintains with other depository institutions.
- 1.b Interest-bearing balances. Report all interest-bearing balances due from depository institutions whether in the form of savings or time balances, including certificates of deposit, but excluding certificates of deposit held for trading. Include balances due from commercial banks in the U.S., other depository institutions in the U.S., Federal Home Loan Banks, banks in foreign countries, and foreign central banks.

On the FFIEC 031, the components of this item will also be included in the appropriate items of Schedule RC-A, column A. On the FFIEC 041, for banks with \$300 million or more in total assets, the components of this item will also be included in the appropriate items of Schedule RC-A.

Exclude from interest-bearing balances:

- (1) Loans to depository institutions and acceptances of other banks (report in Schedule RC-C, part I, item 2).
- (2) All interest-bearing balances that the reporting bank's trust department maintains with other depository institutions.
- (3) Certificates of deposit held for trading (report in Schedule RC, item 5).

Item No. **Caption and Instructions**

- 2 Securities:
- Held-to-maturity securities. Report the amount from Schedule RC-B, item 8, column A, 2.a "Total amortized cost."
- Available-for-sale securities. Report the amount from Schedule RC-B, item 8, column D, 2.b "Total fair value."
- 3 Federal funds sold and securities purchased under agreements to resell:
- 3.a **Federal funds sold (in domestic offices).** Report the outstanding amount of federal funds sold, i.e., immediately available funds lent (in domestic offices) under agreements or contracts that have an original maturity of one business day or roll over under a continuing contract, excluding such funds lent in the form of securities purchased under agreements to resell (which should be reported in Schedule RC, item 3.b) and overnight lending for commercial and industrial purposes (which generally should be reported in Schedule RC, item 4.b). Transactions that are to be reported as federal funds sold may be secured or unsecured or may involve an agreement to resell loans or other instruments that are not securities.

Immediately available funds are funds that the purchasing bank can either use or dispose of on the same business day that the transaction giving rise to the receipt or disposal of the funds is executed. A continuing contract, regardless of the terminology used, is an agreement that remains in effect for more than one business day, but has no specified maturity and does not require advance notice of the lender or the borrower to terminate.

Report federal funds sold on a gross basis; i.e., do not net them against federal funds purchased, except to the extent permitted under FASB Interpretation No. 39.

Also exclude from federal funds sold:

- (1) Sales of so-called "term federal funds" (as defined in the Glossary entry for "federal funds" transactions") (report in Schedule RC, item 4.b, "Loans and leases, net of unearned income").
- (2) Securities resale agreements that have an original maturity of one business day or roll over under a continuing contract, if the agreement requires the bank to resell the identical security purchased or a security that meets the definition of substantially the same in the case of a dollar roll (report in Schedule RC, item 3.b, "Securities purchased under agreements to resell").
- (3) Deposit balances due from a Federal Home Loan Bank (report as balances due from depository institutions in Schedule RC, item 1.a or 1.b, as appropriate).
- (4) Lending transactions in foreign offices involving immediately available funds with an original maturity of one business day or under a continuing contract that are not securities resale agreements (report in Schedule RC, item 4.b, "Loans and leases, net of unearned income").

For further information, see the Glossary entry for "federal funds transactions."

Item No. **Caption and Instructions**

3.b Securities purchased under agreements to resell. Report the outstanding amount of:

- (1) Securities resale agreements, regardless of maturity, if the agreement requires the bank to resell the identical security purchased or a security that meets the definition of substantially the same in the case of a dollar roll.
- Purchases of participations in pools of securities, regardless of maturity.

Report securities purchased under agreements to resell on a gross basis, i.e., do not net them against securities sold under agreements to repurchase, except to the extent permitted under FASB Interpretation No. 41.

Exclude from this item:

- (1) Resale agreements involving assets other than securities (report in Schedule RC, item 3.a, "Federal funds sold," or item 4.b, "Loans and leases, net of unearned income," as appropriate, depending on the maturity and office location of the transaction).
- (2) Due bills representing purchases of securities or other assets by the reporting bank that have not yet been delivered and similar instruments, whether collateralized or uncollateralized (report in Schedule RC, item 4.b). See the Glossary entry for "due bills."
- (3) So-called yield maintenance dollar repurchase agreements (see the Glossary entry for "repurchase/resale agreements").

For further information, see the Glossary entry for "repurchase/resale agreements."

- 4 Loans and lease financing receivables. Report in the appropriate subitem loans and leases (not held for trading) net of any allocated transfer risk reserve. The sum of Schedule RC, items 4.a and 4.b, must equal Schedule RC-C, part I, item 12, (column A on the FFIEC 031).
- 4.a Loans and leases held for sale. Report the amount of loans and leases held for sale at the lower of cost or fair value. The amount by which cost exceeds fair value, if any, shall be accounted for as a valuation allowance. These loans and leases are included by loan category in Schedule RC-C, part I.
- 4.b Loans and leases, net of unearned income. Report the amount of loans and leases that the reporting bank has the intent and ability to hold for the foreseeable future or until maturity or payoff. These loans and leases are included by loan category in Schedule RC-C part I
- 4.c Less: Allowance for loan and lease losses. Report the allowance for loan and lease losses as determined in accordance with the instructions in the Glossary entry for "allowance for loan and lease losses." This item must equal Report of Income Schedule RI-B, part II, item 7, "Balance end of current period."
- 4.d Loans and leases, net of unearned income and allowance. Report the amount derived by subtracting Schedule RC, item 4.c, from Schedule RC, item 4.b.

FFIEC 031 and 041 RC-6 **RC - BALANCE SHEET**

Caption and Instructions Item No.

5 **Trading assets.** Banks that (a) regularly underwrite or deal in securities; interest rate, foreign exchange rate, equity, and commodity and other derivative contracts; other financial instruments; and other assets for resale; (b) acquire or take positions in such items principally for the purpose of selling in the near term or otherwise with the intent to resell in order to profit from short-term price movements; or (c) acquire or take positions in such items as an accommodation to customers or for other trading purposes shall report in this item the value of such assets or positions on the report date. Assets and other financial instruments held for trading shall be consistently valued at fair value.

> Do not include in this item the carrying value of any available-for-sale securities or of any loans or leases that are held for sale. Available-for-sale securities are reported in Schedule RC, item 2.b, and in Schedule RC-B, columns C and D. Loans and leases held for sale should be reported in Schedule RC, item 4.a, "Loans and leases held for sale," and in Schedule RC-C.

Trading assets include but are not limited to U.S. Treasury securities, U.S. Government agency obligations, securities issued by states and political subdivisions in the U.S., other bonds, notes, and debentures, certificates of deposit, commercial paper, and bankers acceptances. Trading assets also include the amount of revaluation gains (i.e., assets) from the "marking to market" of interest rate, foreign exchange rate, and other off-balance sheet commodity and equity contracts held for trading purposes. Revaluation gains and losses (i.e., assets and liabilities) from the "marking to market" of the reporting bank's interest rate, foreign exchange rate, and other off-balance sheet commodity and equity contracts with the same counterparty that meet the criteria for a valid right of setoff contained in FASB Interpretation No. 39 (e.g., those contracts subject to a qualifying master netting agreement) may be reported on a net basis using this item and Schedule RC, item 15, "Trading liabilities," as appropriate. (See the Glossary entry for "offsetting.")

For those banks that must complete Schedule RC-D, this item must equal Schedule RC-D, item 12, "Total trading assets."

6 Premises and fixed assets. Report the book value, less accumulated depreciation or amortization, of all premises, equipment, furniture and fixtures purchased directly or acquired by means of a capital lease. Any method of depreciation or amortization conforming to accounting principles that are generally acceptable for financial reporting purposes may be used. However, depreciation for premises and fixed assets may be based on a method used for federal income tax purposes if the results would not be materially different from depreciation based on the asset's estimated useful life.

> Do not deduct mortgages or other liens on such property (report in Schedule RC, item 16, "Other borrowed money").

Include as premises and fixed assets:

- (1) Premises that are actually owned and occupied (or to be occupied, if under construction) by the bank, its branches, or its consolidated subsidiaries.
- (2) Leasehold improvements, vaults, and fixed machinery and equipment.
- (3) Remodeling costs to existing premises.
- (4) Real estate acquired and intended to be used for future expansion.

Item No. Caption and Instructions

6 (5) Parking lots that are used by customers or employees of the bank, its branches, and its consolidated subsidiaries.

- (6) Furniture, fixtures, and movable equipment of the bank, its branches, and its consolidated subsidiaries.
- (7) Automobiles, airplanes, and other vehicles owned by the bank and used in the conduct of its business.
- (8) The amount of capital lease property (with the bank as lessee): premises, furniture, fixtures, and equipment. See the discussion of accounting with bank as lessee in the Glossary entry for "lease accounting."
- (9) Stocks and bonds issued by nonmajority-owned corporations whose principal activity is the ownership of land, buildings, equipment, furniture, or fixtures occupied or used (or to be occupied or used) by the bank, its branches, or its consolidated subsidiaries.

Exclude from premises and fixed assets:

- (1) Original paintings, antiques, and similar valuable objects (report in Schedule RC-F, item 5, "Other" assets).
- (2) Favorable leasehold rights (report in Schedule RC, item 10.b, "Other intangible assets").

Property formerly but no longer used for banking may be reported either in this item as "Premises and fixed assets" or in Schedule RC-M, item 3.b, as "All other real estate owned."

- **Other real estate owned.** Report the total amount of other real estate owned from Schedule RC-M, item 3.c. For further information on other real estate owned, see the instruction to Schedule RC-M, item 3, and the Glossary entry for "foreclosed assets."
- 8 Investments in unconsolidated subsidiaries and associated companies. Report the total amount of the bank's investments in unconsolidated subsidiaries and associated companies from Schedule RC-M, item 4.c. For further information on unconsolidated subsidiaries and associated companies, see the instruction to Schedule RC-M, item 4.
- **Customers' liability to this bank on acceptances outstanding.** Report the *full* amount (with the exceptions noted below) of customers' liability to the reporting bank on drafts and bills of exchange that have been accepted by the reporting bank, or by others for its account, and are outstanding.

The amount of customers' liability to the reporting bank on its acceptances that have not yet matured should be reduced *only* when: (1) the customer anticipates its liability to the reporting bank on an outstanding acceptance by making a payment to the bank in advance of the acceptance's maturity that immediately reduces the customer's indebtedness to the bank on such an acceptance; or (2) the reporting bank acquires and holds its own acceptance. See the Glossary entry for "bankers acceptances" for further information.

Item No. **Caption and Instructions**

10 Intangible assets:

10.a Goodwill. Report the carrying amount of goodwill. Goodwill represents the excess of the cost of a company over the sum of the fair values of the tangible and identifiable intangible assets acquired less the fair value of liabilities assumed in a business combination accounted for as a purchase.

> Goodwill should not be amortized, but must be tested for impairment as described in the instructions to Schedule RI, item 7.c.(1), "Goodwill impairment losses." However, until interpretive guidance concerning the application of the purchase method of accounting for business combinations between two or more mutual institutions is issued by the FASB and takes effect, goodwill acquired in a combination between two or more mutual enterprises must continue to be amortized over its estimated useful life, generally not to exceed 25 years, and tested for impairment in accordance with APB Opinion No. 17.

Exclude unidentifiable intangible assets recorded in accordance with FASB Statement No. 72 (report such intangible assets in Schedule RC, item 10.b, "Other intangible assets.")

- 10.b Other intangible assets. Report the total amount of intangible assets other than goodwill from Schedule RC-M, item 2.d. For further information on intangible assets, see the instruction to Schedule RC-M, item 2.
- 11 Other assets. Report the amount from Schedule RC-F, item 6, "Total."
- Total assets. Report the sum of items 1 through 11. This item must equal Schedule RC, 12 item 29, "Total liabilities, minority interest, and equity capital."

FFIEC 031 and 041 **RC - BALANCE SHEET** RC-9

LIABILITIES

Item No. Caption and Instructions

Deposits. (For a discussion of noninterest-bearing and interest-bearing deposits, see the Glossary entry for "deposits.")

13.a In domestic offices. Report the total of all deposits in domestic offices of the reporting bank. This item must equal the sum of Schedule RC-E, (part I), item 7, columns A and C.

This item must also equal the sum of items 13.a.(1) and 13.a.(2) below.

- **Noninterest-bearing**. On the FFIEC, 041, report the total of all noninterest-bearing deposits included in Schedule RC-E, Deposit Liabilities. On the FFIEC 031, report the total of all noninterest-bearing deposits in domestic offices included in Schedule RC-E, part I, Deposits in Domestic Offices. Noninterest-bearing deposits include total demand deposits and noninterest-bearing time and savings deposits.
- **13.a.(2)** Interest-bearing. On the FFIEC 041, report the total of all interest-bearing deposits included in Schedule RC-E, Deposit Liabilities. On the FFIEC 031, report the total of all interest-bearing deposits in domestic offices included in Schedule RC-E, part I, Deposits in Domestic Offices.

NOTE: Items 13.b, 13.b.(1), and 13.b.(2) are applicable only to banks filing the FFIEC 031 report form.

13.b In foreign offices, Edge and Agreement subsidiaries, and IBFs. Report the total of all deposits in foreign offices, Edge and Agreement subsidiaries, and IBFs. This item must equal the amount reported in Schedule RC-E, part II, item 6, "Total."

This item must also equal the sum of items 13.b.(1) and 13.b.(2) below.

- **13.b.(1) Noninterest-bearing.** Report the total of all noninterest-bearing deposits in foreign offices reported in Schedule RC-E, part II, Deposits in Foreign Offices.
- **13.b.(2)** Interest-bearing. Report the total of all interest-bearing deposits in foreign offices reported in Schedule RC-E, part II, Deposits in Foreign Offices.
- 14 Federal funds purchased and securities sold under agreements to repurchase:
- 14.a Federal funds purchased (in domestic offices). Report the outstanding amount of federal funds purchased, i.e., immediately available funds borrowed (in domestic offices) under agreements or contracts that have an original maturity of one business day or roll over under a continuing contract, excluding such funds borrowed in the form of securities sold under agreements to repurchase (which should be reported in Schedule RC, item 14.b) and Federal Home Loan Bank advances (which should be reported in Schedule RC, item 16). Transactions that are to be reported as federal funds purchased may be secured or unsecured or may involve an agreement to repurchase loans or other instruments that are not securities.

Immediately available funds are funds that the purchasing bank can either use or dispose of on the same business day that the transaction giving rise to the receipt or disposal of the funds is executed. A continuing contract, regardless of the terminology used, is an agreement that remains in effect for more than one business day, but has no specified maturity and does not require advance notice of the lender or the borrower to terminate.

FFIEC 031 and 041 RC - BALANCE SHEET

Item No. Caption and Instructions

14.a Report federal funds purchased on a gross basis; i.e., do <u>not</u> net them against federal funds sold, except to the extent permitted under FASB Interpretation No. 39.

Also exclude from federal funds purchased:

- (1) Purchases of so-called "term federal funds" (as defined in the Glossary entry for "federal funds transactions") (report in Schedule RC, item 16, "Other borrowed money").
- (2) Security repurchase agreements that have an original maturity of one business day or roll over under a continuing contract, if the agreement requires the bank to repurchase the identical security sold or a security that meets the definition of substantially the same in the case of a dollar roll (report in Schedule RC, item 14.b, "Securities sold under agreements to repurchase").
- (3) Borrowings from a Federal Home Loan Bank or a Federal Reserve Bank (report those in the form of securities repurchase agreements in Schedule RC, item 14.b, and all other borrowings in Schedule RC, item 16).
- (4) Borrowing transactions in foreign offices involving immediately available funds with an original maturity of one business day or under a continuing contract that are not securities repurchase agreements (report in Schedule RC, item 16).

For further information, see the Glossary entry for "federal funds transactions."

14.b Securities sold under agreements to repurchase. Report the outstanding amount of:

- (1) Securities repurchase agreements, regardless of maturity, if the agreement requires the bank to repurchase the identical security sold or a security that meets the definition of substantially the same in the case of a dollar roll.
- (2) Sales of participations in pools of securities, regardless of maturity.

Report securities sold under agreements to repurchase on a gross basis, i.e., do <u>not</u> net them against securities purchased under agreements to resell, except to the extent permitted under FASB Interpretation No. 41.

Exclude from this item:

- (1) Repurchase agreements involving assets other than securities (report in Schedule RC, item 14.a, "Federal funds purchased," or item 16, "Other borrowed money," as appropriate, depending on the maturity and office location of the transaction).
- (2) Borrowings from a Federal Home Loan Bank or a Federal Reserve Bank other than in the form of securities repurchase agreements (report in Schedule RC, item 16).
- (3) Obligations under due bills that resulted when the bank sold securities or other assets and received payment, but has not yet delivered the assets, and similar obligations, whether collateralized or uncollateralized (report in Schedule RC, item 16). See the Glossary entry for "due bills."
- (4) So-called yield maintenance dollar repurchase agreements (see the Glossary entry for "repurchase/resale agreements").

FFIEC 031 and 041 RC-10a RC - BALANCE SHEET

Item No. Caption and Instructions

14.b For further information, <u>see</u> the Glossary entry for "repurchase/resale agreements." (cont.)

- Trading liabilities. Report the amount of liabilities from the reporting bank's trading activities. Include liabilities resulting from sales of assets that the reporting bank does not own (see the Glossary entry for "short position") and revaluation losses from the "marking to market" of interest rate, foreign exchange rate, equity, and commodity and other derivative contracts into which the reporting bank has entered for trading, dealer, customer accommodation, and similar purposes. For those banks that must complete Schedule RC-D, Trading Assets and Liabilities, the amount reported in this item must equal Schedule RC-D, item 15.
- **Other borrowed money.** Report the amount from Schedule RC-M, item 5.c.
- 17 Not applicable.
- 18 Bank's liability on acceptances executed and outstanding. Report the <u>full</u> amount (except as noted below) of the liability represented by drafts and bills of exchange that have been accepted by the reporting bank, or by others for its account, and that are outstanding.

The bank's liability on acceptances executed and outstanding should be reduced prior to the maturity of such acceptances <u>only</u> when the reporting bank acquires and holds its own acceptances, i.e., only when the acceptances are not outstanding. See the Glossary entry for "bankers acceptances" for further information.

Subordinated notes and debentures. Report the amount of subordinated notes and debentures (including mandatory convertible debt) (see the Glossary entry for "subordinated notes and debentures"). Also include the amount of outstanding limited-life preferred stock including any amounts received in excess of its par or stated value. (See the Glossary entry for "preferred stock" for the definition of limited-life preferred stock.)

FFIEC 031 and 041 RC-10b RC - BALANCE SHEET

Caption and Instructions Other liabilities. Report the amount from Schedule RC-G, item 5, "Total." Total liabilities. Report the sum of items 13 through 20. Minority interest in consolidated subsidiaries. Report the portion of the equity capital accounts of all consolidated subsidiaries of the reporting bank that must be allocated to minority shareholders of such subsidiaries.

FFIEC 031 and 041 RC - BALANCE SHEET

EQUITY CAPITAL

Item No. Caption and Instructions

23 <u>Perpetual preferred stock and related surplus</u>. Report the amount of perpetual preferred stock issued, including any amounts received in excess of its par or stated value. (See the Glossary entry for "preferred stock" for the definition of perpetual preferred stock.)

- **Common stock**. Report the aggregate par or stated value of common stock issued.
- **Surplus.** Report the net amount formally transferred to the surplus account, including capital contributions, adjustments arising from treasury stock transactions, and any amount received for common stock in excess of its par or stated value on or before the report date.

Do <u>not</u> include any portion of the proceeds received from the sale of preferred stock in excess of its par or stated value (report in Schedule RC, item 19 or 23, as appropriate).

Retained earnings. Report the amount of retained earnings (undivided profits) and capital reserves. The amount of the retained earnings and capital reserves should reflect transfers of net income, declarations of dividends, transfers to surplus, and any other appropriate entries.

Adjustments of accruals and other accounting estimates made shortly after the report date which relate to the income and expenses of the year-to-date period ended as of the report date must be reported in the appropriate items of Schedule RI, Income Statement, for that year-to-date period.

Capital reserves are segregations of retained earnings and are <u>not</u> to be reported as liability accounts or as reductions of asset balances. Capital reserves may be established for such purposes as:

- (1) Reserve for undeclared stock dividends -- includes amounts set aside to provide for stock dividends (not cash dividends) not yet declared.
- (2) Reserve for undeclared cash dividends -- includes amounts set aside for cash dividends on common and preferred stock not yet declared. (Cash dividends declared but not yet payable should be included in Schedule RC-G, item 5, "Other" liabilities.)
- (3) Retirement account (for limited-life preferred stock or subordinated notes and debentures) -- includes amounts allocated under the plan for retirement of limited-life preferred stock or subordinated notes and debentures contained in the bank's articles of association or in the agreement under which such stock or notes and debentures were issued.
- (4) Reserve for contingencies -- includes amounts set aside for possible unforeseen or indeterminate liabilities not otherwise reflected on the bank's books and not covered by insurance. This reserve may include, for example, reserves set up to provide for possible losses which the bank may sustain because of lawsuits, the deductible amount under the bank's blanket bond, defaults on obligations for which the bank is contingently liable, or other claims against the bank. A reserve for contingencies represents a segregation of retained earnings. It should not include any element of known losses or of any probable incurred losses the amount of which can be estimated with reasonable accuracy (see the Glossary entry for "loss contingencies" for additional information).

Item No. Caption and Instructions

26.a Exclude from retained earnings: (cont.)

(1) Any portion of the proceeds received from the sale of common stock in excess of its par or stated value (report in Schedule RC, item 25).

- (2) Any portion of the proceeds received from the sale of preferred stock in excess of its par or stated value (report in Schedule RC, item 19 or 23, as appropriate).
- (3) "Reserves" that reduce the related asset balances such as valuation allowances (e.g., the allowance for loan and lease losses), reserves for depreciation, and reserves for bond premiums.
- 26.b Accumulated other comprehensive income. Report the accumulated balance of other comprehensive income in accordance with FASB Statement No. 130, Reporting Comprehensive Income. "Other comprehensive income" refers to revenues, expenses, gains, and losses that under generally accepted accounting principles are included in comprehensive income but excluded from net income. Include in this item:
 - (1) Net unrealized holding gains (losses) on available-for-sale securities. Report the difference between the amortized cost and the fair value of the reporting bank's available-for-sale securities, net of tax effects, as of the report date. For most banks, all "securities," as that term is defined in FASB Statement No. 115, that are designated as "available-for-sale" will be reported as "Available-for-sale securities" in Schedule RC, item 2.b, and in Schedule RC-B, columns C and D. However, a bank may have certain assets that fall within the definition of "securities" in FASB Statement No. 115 (e.g., nonrated industrial development obligations) that the bank has designated as "available-for-sale" which are reported for purposes of the Report of Condition in a balance sheet category other than "Securities" (e.g., "Loans and lease financing receivables"). These "available-for-sale" assets must be carried on the Report of Condition balance sheet at fair value rather than amortized cost and the difference between these two amounts, net of tax effects, also must be included in this item.

Also include the unamortized amount of the unrealized holding gain or loss at the date of transfer of any debt security transferred into the held-to-maturity category from the available-for-sale category. When a debt security is transferred from available-for-sale to held-to-maturity, the unrealized holding gain or loss at the date of transfer continues to be reported in this equity capital account, but must be amortized over the remaining life of the security as an adjustment of yield in a manner consistent with the amortization of any premium or discount.

1 For example, if the fair value of the reporting bank's available-for-sale securities exceeds the amortized cost of its

FFIEC 031 and 041 RC-13 RC - BALANCE SHEET

assets or liabilities to report in Schedule RC-F, item 2, or Schedule RC-G, item 2.

available-for-sale securities by \$100,000 (and the bank has had no other transactions affecting the "net unrealized holding gains (losses)" account), the amount to be included in Schedule RC, item 26.b, must be reduced by the estimated amount of taxes using the bank's applicable tax rate (federal, state and local). (See the Glossary entry for "income taxes" for a discussion of "applicable tax rate.") If the bank's applicable tax rate (federal, state and local) is 40% and the tax basis of its available-for-sale securities approximates their amortized cost, the bank would include "net unrealized holding gains" of \$60,000 [\$100,000 - (40% x \$100,000)] in Schedule RC, item 26.b. The bank would also have a deferred tax liability of \$40,000 which would enter into the determination of the amount of net deferred tax

Item No. Caption and Instructions

26.b (cont.)

(2) <u>Accumulated net gains (losses) on cash flow hedges.</u> Report the effective portion² of the accumulated change in fair value (gain or loss) on derivatives designated and qualifying as cash flow hedges in accordance with FASB Statement No. 133, *Accounting for Derivative Instruments and Hedging Activities*.

Under Statement No. 133, a bank that elects to apply hedge accounting must exclude from net income the effective portion of the change in fair value of a derivative designated as a cash flow hedge and record it on the balance sheet in a separate component of equity capital (referred to as "accumulated other comprehensive income" in the accounting standard). The ineffective portion of the cash flow hedge must be reported in earnings. The equity capital component (i.e., the accumulated other comprehensive income) associated with a hedged transaction should be adjusted each reporting period to a balance that reflects the lesser (in absolute amounts) of:

- (a) The cumulative gain or loss on the derivative from inception of the hedge, less (i) amounts excluded consistent with the bank's defined risk management strategy and (ii) the derivative's gains or losses previously reclassified from accumulated other comprehensive income into earnings to offset the hedged transaction, or
- (b) The portion of the cumulative gain or loss on the derivative necessary to offset the cumulative change in expected future cash flows on the hedged transaction from inception of the hedge less the derivative's gains or losses previously reclassified from accumulated other comprehensive income into earnings

Accordingly, the amount reported in this item should reflect the sum of the adjusted balance (as described above) of the cumulative gain or loss for each derivative designated and qualifying as a cash flow hedge. These amounts will be reclassified into earnings in the same period or periods during which the hedged transaction affects earnings (for example, when a hedged variable-rate interest receipt on a loan is accrued or when a forecasted sale occurs).

- (3) <u>Cumulative foreign currency translation adjustments</u>. Report the sum of the bank's foreign currency translation adjustments accumulated in accordance with FASB Statement No. 52. See the Glossary entry for "foreign currency transactions and translation" for further information.
- (4) Minimum pension liability adjustment. Report any minimum pension liability adjustment recognized in accordance with FASB Statement No.87, Employers' Accounting for Pensions. Under Statement No. 87, an employer must report in a separate component of equity capital, net of any applicable tax benefits, the excess of additional pension liability over unrecognized prior service cost.

FFIEC 031 and 041 RC-14 RC - BALANCE SHEET

¹ Generally, the objective of a cash flow hedge is to link a derivative to an existing recognized asset or liability or a forecasted transaction with exposure to variability in expected future cash flows, e.g., the future interest payments (receipts) on a variable-rate liability (asset) or a forecasted purchase (sale). The changes in cash flows of the derivative are expected to offset changes in cash flows of the hedged item or transaction. To achieve the matching of cash flows, FASB Statement No. 133 requires that changes in the fair value of properly designated and qualifying derivatives initially be reported in a separate component of equity (accumulated other comprehensive income) and reclassified into earnings in the same future period that the hedged transaction affects earnings.

² The effective portion of a cash flow hedge can be described as the change in fair value of the derivative that offsets the change in expected future cash flows being hedged. Refer to FASB Statement No. 133, Appendix A, Section 2, for further information.

Item No. Caption and Instructions

Other equity capital components. Report the carrying value of any treasury stock and of any unearned Employee Stock Ownership Plan (ESOP) shares, which under generally accepted accounting principles are reported in a contra-equity account on the balance sheet. Also include any unearned or deferred compensation expense that must be shown as a separate reduction of equity capital pursuant to Accounting Principles Board Opinion No. 25, Accounting for Stock Issued to Employees. For further information, see the Glossary entry for "treasury stock," AICPA Statement of Position 93-6, Employers' Accounting for Employee Stock Ownership Plans, and APB Opinion No. 25.

- **Total equity capital.** Report the sum of items 23 through 27. This item must equal Report of Income Schedule RI-A, item 12, "Total equity capital end of current period."
- **Total liabilities, minority interest, and equity capital.** Report the sum of items 21, 22, and 28. This item must equal Schedule RC, item 12, "Total assets."

(3-01)

Memorandum

Item No. Caption and Instructions

Indicate in the box at the right the number of the statement below that best describes 1 the most comprehensive level of auditing work performed for the bank by independent external auditors as of any date during the preceding calendar year. (To be reported only with the March Report of Condition.) Report the number of the statement listed on the report form that, in the bank's judgment, best describes the most comprehensive level of auditing work performed by any independent external auditors during the preceding calendar vear.

The term "any date during the preceding calendar year" refers to the date of the balance sheet and income statement reported on by the auditor (or the date as of which certain agreed-upon procedures were applied to selected records and transactions by the auditor) regardless of the actual date of the commencement of the auditing work (audit, internal control attestation, directors' examination, review, compilation, or specific procedures) and regardless of the date of the report submitted by the auditor.

Exclude from "auditing work performed" any tax or consulting work regardless of whether it was performed by an independent certified public accounting firm or others.

The list of possible external auditing work is structured with the "most comprehensive level," an audit of the bank, as number 1 and the other levels of auditing work in descending order so that "no external audit work" is number 9.

Banks may be assisted in determining the level of auditing work performed by reviewing the type of report received from the auditor:

(a) If the bank or parent holding company has external auditing work performed by a certified public accounting firm and the report of the auditor:

Begins "We have examined . . . " or "We have audited ..."

and

The final paragraph begins "In our opinion, the financial statements referred to

above . . . "_or

"In our opinion, the balance sheet referred to

above . . . "

the bank would respond to this item with a "1" if the first sentence of the first paragraph of the report describes the financial statements or the balance sheet of the bank or with a "2" if the first sentence of the first paragraph of the report describes the financial statements or the balance sheet of the parent holding company.

Memorandum

Item No. Caption and Instructions

1 (b) If the report submitted by the auditor:

(cont.)

Begins "We have examined management's assertion . . .

maintained effective internal control over financial

reporting . . .,"

and

The final paragraph states "In our opinion . . ."

the bank would respond to this item with a "3."

(c) If the report submitted by the auditor:

Begins "We have applied certain procedures to selected

records and transactions . . .,"

The second paragraph includes "We do not express an opinion, . . ."

and

The next to last paragraph states "Had we performed additional procedures . . .

other matters may have come to our attention . . .

"

the bank would respond with:

- a "4" if this auditing work was performed by a certified public accounting firm for the Board of Directors as a directors' examination;
- (ii) a "5" if this auditing work was performed by any other firm (e.g., a consulting firm, another banking organization) for the Board of Directors as a directors' examination; or
- (iii) a "8" if management otherwise engaged the auditor to perform specified auditing work (excluding tax or consulting work) but this auditing work did not constitute a directors' examination.
- (d) If the report submitted by the auditor:

Begins "We have reviewed . . . , "

The second paragraph states "A review consists principally of inquiries . . . ,"

and

The final paragraph begins "Based on our review . . ."

the bank would respond to this item with a "6."

Memorandum

Item No. Caption and Instructions

1 (e) If the report submitted by the auditor: (cont.)

Begins "We have compiled . . ."

and

The second paragraph begins "A compilation is limited to presenting . . . "

the bank would respond to this item with a "7."

An "independent external auditor" is an auditor who at no time during the year:

- (1) was an employee of the bank;
- (2) performed the bank's bookkeeping or maintained the bank's accounting records;
- (3) was dependent on the bank for his livelihood nor was the bank such a significant client that the loss of that client would jeopardize his livelihood; nor
- (4) held the bank's securities or was indebted to the bank beyond those types of loans permitted under applicable professional standards.

SCHEDULE RC-A -- CASH AND BALANCES DUE FROM DEPOSITORY INSTITUTIONS

General Instructions

Schedule RC-A is to be completed by banks with foreign offices or with \$300 million or more in total assets.

On the FFIEC 031, this schedule has two columns for banks with foreign offices to report detail on "Cash and balances due from depository institutions." In column A report amounts for the fully consolidated bank, and in column B report amounts for domestic offices only. See the Glossary entry for "domestic office" for the definition of this term. Refer to the General Instructions section of this book for a detailed discussion of consolidation.

On the FFIEC 041, this schedule has a single column for banks with \$300 million or more in total assets to report detail on "Cash and balances due from depository institutions."

For purposes of these reports, deposit accounts "due from" other depository institutions that are overdrawn are to be reported as other borrowings with a remaining maturity of one year or less in Schedule RC-M, item 5.b.(1), except overdrawn "due from" accounts arising in connection with checks or drafts drawn by the reporting bank and drawn on, or payable at or through, another depository institution either on a zero-balance account or on an account that is <u>not</u> routinely maintained with sufficient balances to cover checks or drafts drawn in the normal course of business during the period until the amount of the checks or drafts is remitted to the other depository institution (in which case, report the funds received or held in connection with such checks or drafts as deposits in Schedule RC-E until the funds are remitted). For further information, refer to the Glossary entry for "overdraft."

<u>Treatment of reciprocal balances with depository institutions</u> -- Reciprocal balances arise when two depository institutions maintain deposit accounts with each other, i.e., when a reporting bank has both a "due from" and a "due to" balance with another depository institution. Reciprocal balances between the reporting bank and other depository institutions may be reported on a net basis when a right of setoff exists. Net "due from" balances should be reported in this schedule. Net "due to" balances should be reported as deposit liabilities in Schedule RC-E. <u>See</u> the Glossary entry for "offsetting" for the conditions that must be met for a right of setoff to exist. See also the Glossary entry for "reciprocal balances."

Exclude from this schedule:

- (1) All intrabank transactions, i.e., all transactions between any offices of the consolidated bank.
- (2) Claims on banks or other depository institutions that the reporting bank holds for trading purposes (report in Schedule RC, item 5, "Trading assets").
- (3) Deposit accounts "due to" other depository institutions that are overdrawn (report in Schedule RC-C, part I, item 2, "Loans to depository institutions and acceptances of other banks").
- (4) Loans to depository institutions (report in Schedule RC-C, part I, item 2).

FFIEC 031 and 041 RC-A-1 RC-A - CASH AND DUE FROM (3-01)

Item Instructions

Item No. Caption and Instructions

Cash items in process of collection, unposted debits, and currency and coin. On the FFIEC 031, report this item as a single total for the fully consolidated bank in column A, but with a breakdown between cash items in process of collection and unposted debits (item 1.a) and currency and coin (item 1.b) for domestic offices of the bank in column B. On the FFIEC 041, report cash items in process of collection and unposted debits in item 1.a and currency and coin in item 1.b.

Cash items in process of collection include:

- (1) Checks or drafts in process of collection that are drawn on another depository institution (or on a Federal Reserve Bank) and that are payable immediately upon presentation in the United States (or, for purposes of the FFIEC 031, in the country where the reporting bank's office which is clearing or collecting the check or draft is located). This includes:
 - (a) Checks or drafts drawn on other institutions that have already been forwarded for collection but for which the reporting bank has not yet been given credit ("cash letters").
 - (b) Checks or drafts on hand that will be presented for payment or forwarded for collection on the following business day.
 - (c) Checks or drafts that have been deposited with the reporting bank's correspondent and for which the reporting bank has already been given credit, but for which the amount credited is <u>not</u> subject to immediate withdrawal ("ledger credit" items).

However, if the reporting bank has been given immediate credit by its correspondent for checks or drafts presented for payment or forwarded for collection <u>and</u> if the funds on deposit are subject to immediate withdrawal, report the amount of such checks or drafts in Schedule RC-A, item 2, "Balances due from depository institutions in the U.S.," or item 3, "Balances due from banks in foreign countries and foreign central banks."

- (2) Government checks drawn on the Treasurer of the United States or any other government agency that are payable immediately upon presentation and that are in process of collection.
- (3) Such other items in process of collection that are payable immediately upon presentation and that are customarily cleared or collected as cash items by depository institutions in the United States or in such other country where the reporting bank's office which is clearing or collecting the item is located, such as:
 - (a) Redeemed United States savings bonds and food stamps.
 - (b) Amounts associated with automated payment arrangements in connection with payroll deposits, federal recurring payments, and other items that are credited to a depositor's account prior to the payment date to ensure that the funds are available on the payment date.

FFIEC 031 and 041 RC-A-2 RC-A - CASH AND DUE FROM (3-01)

Item No. Caption and Instructions

1 (cont.)

- (c) Federal Reserve deferred account balances until credit has been received in accordance with the appropriate time schedules established by the Federal Reserve Banks. At that time, such balances should be reported in Schedule RC-A, item 4, "Balances due from Federal Reserve Banks."
- (d) Checks or drafts drawn on another depository institution that have been deposited in one office of the reporting bank and forwarded for collection to another office of the reporting bank.
- (e) Brokers' security drafts and commodity or bill-of-lading drafts payable immediately upon presentation in the U.S. (See the Glossary entries for "broker's security draft" and "commodity or bill-of-lading draft" for the definitions of these terms.)

Exclude from cash items in process of collection:

- (1) Cash items for which the reporting bank has already received credit, provided that the funds on deposit are subject to immediate withdrawal (report in Schedule RC-A, item 2, 3, or 4, below, as appropriate).
- (2) Credit or debit card sales slips in process of collection (report as noncash items in Schedule RC-F, item 5, "Other" assets). However, when the reporting bank has been notified that it has been given credit, the amount of such sales slips should be reported in Schedule RC-A, item 2, "Balances due from depository institutions in the U.S.," or item 3, "Balances due from banks in foreign countries and foreign central banks," as appropriate.
- (3) Cash items not conforming to the definition of in process of collection, whether or not cleared through Federal Reserve Banks (report in Schedule RC-F, item 5, "Other" assets).
- (4) Commodity or bill-of-lading drafts (including arrival drafts) not yet payable (because the merchandise against which the draft was drawn has not yet arrived), whether or not deposit credit has been given. (If deposit credit has been given, report as loans in the appropriate item of Schedule RC-C, part I; if the drafts were received on a collection basis, they should be excluded entirely from the bank's balance sheet, Schedule RC, until the funds have actually been collected.)

<u>Unposted debits</u> are cash items in the bank's possession, drawn on itself, that are immediately chargeable, but that have not been charged to the general ledger deposit control account at the close of business on the report date. All banks including an amount for unposted debits in this item should also see Schedule RC-O, item 1.a or 1.b, "Unposted debits."

<u>Currency and coin</u> include both U.S. and foreign currency and coin owned and held in all offices of the reporting bank, currency and coin in transit to a Federal Reserve Bank or to any other depository institution for which the reporting bank has not yet received credit, and currency and coin in transit from a Federal Reserve Bank or from any other depository institution for which the reporting bank's account has already been charged. Foreign currency and coin should be converted into U.S. dollar equivalents as of the report date.

FFIEC 031 and 041 RC-A-3 RC-A - CASH AND DUE FROM (3-01)

Item No. Caption and Instructions

1.a Cash items in process of collection and unposted debits. Report (on the FFIEC 031, in column B) the total amount outstanding (at domestic offices) of cash items in process of collection and unposted debits that are immediately payable upon presentation in the United States.

- **1.b** Currency and coin. Report (on the FFIEC 031, in column B) all currency and coin owned and held (in domestic offices) by the reporting bank.
- Balances due from depository institutions in the U.S. On the FFIEC 031, report this item as a single total for the domestic offices of the bank in column B, but with a breakdown between balances due from U.S. branches and agencies of foreign banks, including their IBFs, (item 2.a) and balances due from other commercial banks in the U.S. and other depository institutions in the U.S., including their IBFs, (item 2.b) for the fully consolidated bank in column A. On the FFIEC 041, report balances due from U.S. branches and agencies of foreign banks in item 2.a and balances due from other commercial banks in the U.S. and other depository institutions in the U.S. in item 2.b.

Depository institutions in the U.S. cover:

- (1) U.S. branches and agencies of foreign banks (refer to the Glossary entry for "banks, U.S. and foreign" for the definition of this term); and
- (2) All other depository institutions in the U.S., i.e.,
 - (a) U.S. branches of U.S. banks (refer to the Glossary entry for "banks, U.S. and foreign");
 - (b) savings or building and loan associations, homestead associations, and cooperative banks;
 - (c) mutual and stock savings banks; and
 - (d) credit unions.

For purposes of this schedule, also include Federal Home Loan Banks in "all other depository institutions in the U.S."

Balances due from such institutions cover all interest-bearing and noninterest-bearing balances whether in the form of demand, savings, or time balances, including certificates of deposit, but excluding certificates of deposit held for trading. Balances, as reported in these items, should reflect funds on deposit at other depository institutions in the U.S. for which the reporting bank has already received credit and which are subject to immediate withdrawal. Balances for which the bank has not yet received credit and balances representing checks or drafts for which immediate credit has been given but which are not subject to immediate withdrawal are to be reported as "cash items in process of collection."

Included in the amounts to be reported as balances due from depository institutions in the U.S. are:

(1) Balances due from the reporting bank's correspondents, including amounts that its correspondent is to pass through or already has passed through to a Federal Reserve Bank on behalf of the reporting bank (see the Glossary entry for "pass-through reserve balances" for further discussion).

FFIEC 031 and 041 RC-A-4 RC-A - CASH AND DUE FROM (3-01)

Item No. Caption and Instructions

2 (2) Balances that reflect deposit credit received by the reporting bank because of credit or (cont.) debit card sales slips that had been forwarded for collection. (Until credit has been received, report as noncash items in process of collection in Schedule RC-F, item 5, "Other" assets.)

Exclude from Schedule RC-A, items 2, 2.a, and 2.b:

- (1) Cash items in process of collection (including cash letters and "ledger credit" items) and unposted debits (report in Schedule RC-A, item 1, above).
- (2) All balances that the reporting bank's trust department maintains with other depository institutions.
- (3) Loans to depository institutions (report in Schedule RC-C, part I, item 2).
- (4) Certificates of deposit held for trading (report in Schedule RC, item 5).
- **2.a** U.S. branches and agencies of foreign banks (including their IBFs). Report (on the FFIEC 031, in column A) all balances due from U.S. branches and agencies of foreign banks (including their IBFs).
- **2.b** Other depository institutions in the U.S. (including their IBFs). Report (on the FFIEC 031, in column A) all balances due from depository institutions in the U.S., other than U.S. branches and agencies of foreign banks.
- Balances due from banks in foreign countries and foreign central banks. On the FFIEC 031, report this item as a single total for the domestic offices of the bank in column B, but with a breakdown between balances due from foreign branches of other U.S. banks (item 3.a) and balances due from other banks in foreign countries and foreign central banks (item 3.b) for the fully consolidated bank in column A. On the FFIEC 041, report balances due from foreign branches of other U.S. banks in item 3.a and balances due from other banks in foreign countries and foreign central banks in item 3.b.

Banks in foreign countries cover:

- (1) foreign-domiciled branches of other U.S. banks; and
- (2) foreign-domiciled branches of foreign banks.

See the Glossary entry for "banks, U.S. and foreign" for a description of banks in foreign countries.

For purposes of this item, foreign central banks cover:

- (1) Central banks in foreign countries;
- (2) Departments of foreign central governments that have, as an important part of their functions, activities similar to those of a central bank;

FFIEC 031 and 041 RC-A-5 RC-A - CASH AND DUE FROM (3-01)

Item No. Caption and Instructions

3 (3) Nationalized banks and banking institutions owned by central governments that have, (cont.) as an important part of their functions, activities similar to those of a central bank; and

(4) The Bank for International Settlements (BIS).

Balances due from banks in foreign countries and foreign central banks cover all interest-bearing and noninterest-bearing balances <u>excluding</u> any balances that the reporting bank holds for trading. Balances, as reported in this item, should reflect funds on deposit at other banks in foreign countries and at foreign central banks for which the reporting bank has already received credit. Balances with foreign central banks should include all balances with such entities, including reserve, operating, and investment balances. On the FFIEC 031, balances reported in column A should include "placements and redeposits" between foreign offices of the reporting bank and foreign offices of other banks.

Exclude from Schedule RC-A, items 3, 3.a, and 3.b:

- (1) Balances with U.S. branches and agencies of foreign banks (report in Schedule RC-A, item 2 above).
- (2) Loans to foreign central banks (report in Schedule RC-C, part I, item 7).
- (3) Loans to banks in foreign countries (report in Schedule RC-C, part I, item 2.c).
- (4) Cash items in process of collection and unposted debits (report in Schedule RC-A, item 1 above).
- (5) Any balances held for trading (report in Schedule RC, item 5).
- **3.a** Foreign branches of other U.S. banks. Report (on the FFIEC 031, in column A) all balances due from foreign-domiciled branches of other U.S. banks.
- 3.b Other banks in foreign countries and foreign central banks. Report (on the FFIEC 031, in column A) all balances due from banks in foreign countries, other than foreign-domiciled branches of other U.S. banks, and foreign central banks.
- Balances due from Federal Reserve Banks. Report (on the FFIEC 031, in columns A and B, as appropriate) the total balances due from Federal Reserve Banks as shown by the reporting bank's books. This amount includes reserves and other balances. Include the amount of reserve balances actually passed through to a Federal Reserve Bank by the reporting bank on behalf of its respondent depository institutions. On the FFIEC 031, include in column A balances of the bank's Edge and Agreement subsidiaries with a Federal Reserve Bank.
- Total. On the FFIEC 041, report the sum of items 1 through 4. On the FFIEC 031, report the sum of items 1 through 4 in column A for the fully consolidated bank and in column B for its domestic offices. On the FFIEC 041, this item must equal Schedule RC, sum of items 1.a and 1.b. On the FFIEC 031, the total of column A must equal Schedule RC, sum of items 1.a and 1.b.

FFIEC 031 and 041 RC-A-6 RC-A - CASH AND DUE FROM (3-01)

SCHEDULE RC-B -- SECURITIES

General Instructions

This schedule has four columns for information on securities, two columns for held-to-maturity securities and two columns for available-for-sale securities. Report the amortized cost and the current fair (market) value of held-to-maturity securities in columns A and B, respectively. Report the amortized cost and the current fair (market) value of available-for-sale debt securities in columns C and D, respectively. Information on equity securities with readily determinable fair values is reported in the columns for available-for-sale securities only (columns C and D). For these equity securities, historical cost (not amortized cost) is reported in column C and fair (market) value is reported in column D. See the Glossary entry for "market value of securities" for a discussion of acceptable valuation methods.

<u>Exclude</u> from this schedule all securities held for trading. Securities held for trading are to be reported in Schedule RC, item 5, "Trading assets," and, for certain banks that file the FFIEC 031 and 041 report forms, in Schedule RC-D -- Trading Assets and Liabilities.

In general, <u>amortized cost</u> is the purchase price of a debt security adjusted for amortization of premium or accretion of discount if the debt security was purchased at other than par or face value. (See the Glossary entry for "premiums and discounts.")

The preferred method for reporting purchases and sales of securities is as of trade date. However, settlement date accounting is acceptable if the reported amounts would not be materially different. (See the Glossary entry for "trade date and settlement date accounting.")

For purposes of this schedule, the following events and transactions involving securities should be reported in the manner indicated below:

- (1) Purchases of securities under agreements to resell and sales of securities under agreements to repurchase -- These transactions are not to be treated as purchases or sales of securities but as lending or borrowing (i.e., financing) transactions collateralized by these securities if the agreements meet the criteria for a borrowing set forth in FASB Statement No. 140, Accounting for Transfers and Servicing of Financial Assets and Extinguishments of Liabilities. For further information, see the Glossary entries for "transfers of financial assets" and "repurchase/resale agreements."
- (2) Purchases and sales of participations in pools of securities -- Similarly, these transactions are not to be treated as purchases or sales of the securities in the pool but as lending or borrowing (i.e., financing) transactions collateralized by the pooled securities if the participation agreements meet the criteria for a borrowing set forth in FASB Statement No. 140. For further information, see the Glossary entries for "transfers of financial assets" and "repurchase/resale agreements."
- (3) <u>Pledged securities</u> -- Pledged securities that have not been transferred to the secured party should continue to be included in the pledging bank's holdings of securities that are reported in Schedule RC-B. If the bank has transferred pledged securities to the secured party, the bank should account for the pledged securities in accordance with FASB Statement No. 140.

Available-for-sale securities are generally reported in Schedule RC-B, columns C and D. However, a bank may have certain assets that fall within the definition of "securities" in FASB Statement No. 115 (e.g., certain industrial development obligations) that the bank has designated as "available-for-sale" which are reported for purposes of the Report of Condition in a balance sheet category other than "Securities" (e.g., "Loans and lease financing receivables").

General Instructions (cont.)

(4) <u>Securities borrowed and lent</u> -- Securities borrowed and lent shall be reported on the balance sheet of either the borrowing or lending bank in accordance with FASB Statement No. 140. For further information, see the Glossary entries for "transfers of financial assets" and "securities borrowing/lending transactions."

- (5) <u>Short sales of securities</u> -- Such transactions are to be reported as described in the Glossary entry for "short position."
- (6) <u>Futures, forward, and option contracts</u> Such open contracts to buy or sell securities in the future are to be reported as derivatives in Schedule RC-L, item 11.

Item Instructions

Item No. Caption and Instructions

U.S. Treasury securities. Report in the appropriate columns the amortized cost and fair value of all U.S. Treasury securities not held in trading accounts. <u>Include</u> all bills, certificates of indebtedness, notes, and bonds, including those issued under the Separate Trading of Registered Interest and Principal of Securities (STRIPS) program and those that are "inflation-indexed."

Exclude all obligations of U.S. Government agencies. Also exclude detached Treasury security coupons and ex-coupon Treasury securities held as the result of either their purchase or the bank's stripping of such securities and Treasury receipts such as CATS, TIGRs, COUGARs, LIONs, and ETRs (report in Schedule RC-B, item 6.a below). Refer to the Glossary entry for "coupon stripping, Treasury receipts, and STRIPS" for additional information.

2 <u>U.S. Government agency obligations.</u> Report in the appropriate columns of the appropriate subitems the amortized cost and fair value of all U.S. Government agency obligations (excluding mortgage-backed securities) not held for trading.

Exclude from U.S. Government agency obligations:

- (1) <u>Loans</u> to the Export-Import Bank and to federally-sponsored lending agencies (report in "Other loans," Schedule RC-C, part I, item 9). Refer to the Glossary entry for "federally-sponsored lending agency" for the definition of this term.
- (2) All holdings of U.S. Government-issued or -guaranteed mortgage pass-through securities (report in Schedule RC-B, item 4.a, below).
- (3) Collateralized mortgage obligations (CMOs), real estate mortgage investments conduits (REMICs), CMO and REMIC residuals, and stripped mortgage-backed securities (such as interest-only strips (IOs), principal-only strips (POs), and similar instruments) issued by U.S. Government agencies and corporations (report in Schedule RC-B, item 4.b, below).
- (4) Participations in pools of Federal Housing Administration (FHA) Title I loans, which generally consist of junior lien home improvement loans (report as loans in Schedule RC-C, generally in item 1.c.(2)(b), Loans "secured by junior liens" on 1-to-4 family residential properties).

Item No. Caption and Instructions

2.a <u>Issued by U.S. Government agencies</u>. Report in the appropriate columns the amortized cost and fair value of all obligations (excluding mortgage-backed securities) not held for trading that have been issued by U.S. Government agencies. For purposes of these reports, a U.S. Government agency is defined as an instrumentality of the U.S. Government whose debt obligations are fully and explicitly guaranteed as to the timely payment of principal and interest by the full faith and credit of the U.S. Government.

<u>Include</u>, among others, debt securities (but not mortgage-backed securities) of the following U.S. Government agencies:

- (1) Export-Import Bank (Ex-Im Bank)
- (2) Federal Housing Administration (FHA)
- (3) Government National Mortgage Association (GNMA)
- (4) Maritime Administration
- (5) Small Business Administration (SBA)

Include such obligations as:

- (1) Small Business Administration (SBA) "Guaranteed Loan Pool Certificates," which represent an undivided interest in a pool of SBA-guaranteed portions of loans for which the SBA has further guaranteed the timely payment of scheduled principal and interest payments.
- (2) Participation certificates issued by the Export-Import Bank and the General Services Administration.
- 2.b Issued by U.S. Government-sponsored agencies. Report in the appropriate columns the amortized cost and fair value of all obligations (excluding mortgage-backed securities) not held for trading that have been issued by U.S. Government-sponsored agencies. For purposes of these reports, U.S. Government-sponsored agencies are defined as agencies originally established or chartered by the U.S. Government to serve public purposes specified by the U.S. Congress but whose debt obligations are not explicitly guaranteed by the full faith and credit of the U.S. Government.

<u>Include</u>, among others, debt securities and mortgage-backed bonds (i.e., bonds that are collateralized by mortgages) of the following government-sponsored agencies:

- (1) Federal Agricultural Mortgage Corporation (Farmer Mac)
- (2) Federal Farm Credit Banks
- (3) Federal Home Loan Banks (FHLBs)
- (4) Federal Home Loan Mortgage Corporation (FHLMC or Freddie Mac)
- (5) Federal Land Banks (FLBs)
- (6) Federal National Mortgage Association (FNMA or Fannie Mae)
- (7) Financing Corporation (FICO)
- (8) Resolution Funding Corporation (REFCORP)
- (9) Student Loan Marketing Association (SLMA or Sallie Mae)
- (10) Tennessee Valley Authority (TVA)
- (11) U.S. Postal Service

Item No. Caption and Instructions

3 Securities issued by states and political subdivisions in the U.S. Report in the appropriate columns the amortized cost and fair value of all securities issued by states and political subdivisions in the United States not held for trading.

States and political subdivisions in the U.S., for purposes of this report, include:

- (1) the fifty States of the United States and the District of Columbia and their counties, municipalities, school districts, irrigation districts, and drainage and sewer districts; and
- (2) the governments of Puerto Rico and of the U.S. territories and possessions and their political subdivisions.

Securities issued by states and political subdivisions in the U.S. include:

- (1) General obligations, which are securities whose principal and interest will be paid from the general tax receipts of the state or political subdivision.
- (2) Revenue obligations, which are securities whose debt service is paid solely from the revenues of the projects financed by the securities rather than from general tax funds.
- (3) Industrial development and similar obligations, which are discussed below.

Treatment of industrial development bonds (IDBs) and similar obligations. Industrial development bonds (IDBs), sometimes referred to as "industrial revenue bonds," and similar obligations are issued under the auspices of states or political subdivisions for the benefit of a private party or enterprise where that party or enterprise, rather than the government entity, is obligated to pay the principal and interest on the obligation. For purposes of these reports, all IDBs and similar obligations should be reported as securities in this item (Schedule RC-B, item 3) or as loans in Schedule RC-C, part I, item 8, consistent with the asset category in which the bank reports IDBs and similar obligations on its balance sheet for other financial reporting purposes. Regardless of whether they are reported as securities in Schedule RC-B or as loans in Schedule RC-C, part I, all IDBs and similar obligations that meet the definition of a "security" in FASB Statement No. 115 must be measured in accordance with Statement No. 115.

Treatment of other obligations of states and political subdivisions in the U.S. In addition to those IDBs and similar obligations that are reported as securities in accordance with the preceding paragraph, also <u>include</u> in this item as securities issued by states and political subdivisions in the U.S. all obligations other than IDBs that meet <u>any</u> of the following criteria:

- (1) Nonrated obligations of states and political subdivisions in the U.S., other than those specifically excluded below, that the bank considers securities for other financial reporting purposes.
- (2) Notes, bonds, and debentures (including tax warrants and tax-anticipation notes) that are rated by a nationally-recognized rating service.
- (3) Obligations of state and local governments that are guaranteed by the United States Government (excluding mortgage-backed securities).

Item No. Caption and Instructions

3 Exclude from item 3: (cont.)

(1) All overdrafts of states and political subdivisions in the U.S. (report as loans in Schedule RC-C, part I, item 8).

- (2) All lease financing receivables of states and political subdivisions in the U.S. (report as leases in Schedule RC-C, part I, item 10).
- (3) All IDBs that are reported as loans in accordance with the reporting treatment described above (report as loans in Schedule RC-C, part I, item 8).
- (4) All other nonrated obligations of states and political subdivisions in the U.S. that the bank considers loans for other financial reporting purposes (report as loans in Schedule RC-C, part I, item 8).
- (5) All mortgage-backed securities issued by state and local housing authorities in the U.S. (report in Schedule RC-B, item 4, below).
- (6) Collateralized mortgage obligations (CMOs), real estate mortgage investments conduits (REMICs), CMO and REMIC residuals, and stripped mortgage-backed securities (such as interest-only strips (IOs), principal-only strips (POs), and similar instruments) issued by state and local housing authorities in the U.S. (report in Schedule RC-B, item 4.b, below).
- (7) All obligations of states and political subdivisions in the U.S. held by the reporting bank for trading (report in Schedule RC, item 5).
- Mortgage-backed securities. Report in the appropriate columns of the appropriate subitems the amortized cost and fair value of all mortgage-backed securities, including mortgage pass-through securities, collateralized mortgage obligations (CMOs), real estate mortgage investment conduits (REMICs), CMO and REMIC residuals, and stripped mortgage-backed securities (such as interest-only strips (IOs), principal-only strips (POs), and similar instruments).

Exclude from mortgage-backed securities:

- (1) Securities backed by loans extended under home equity lines, i.e., revolving open-end lines of credit secured by 1-4 family residential properties (report as asset-backed securities backed by "Home equity lines" in Schedule RC-B, item 5.b).
- (2) Bonds issued by the Federal National Mortgage Association (FNMA) and the Federal Home Loan Mortgage Corporation (FHLMC) that are collateralized by mortgages, i.e., mortgage-backed bonds, (report in Schedule RC-B, item 2.b, Obligations "Issued by U.S. Government-sponsored agencies") and mortgage-backed bonds issued by non-U.S. Government issuers (report in Schedule RC-B, item 6, "Other debt securities," below).
- (3) Participation certificates issued by the Export-Import Bank and the General Services Administration (report in Schedule RC-B, item 2.a, Obligations "Issued by U.S. Government agencies").
- (4) Participation certificates issued by a Federal Intermediate Credit Bank (report in Schedule RC-F, item 4, "Equity securities that do not have readily determinable fair values").

Item No. Caption and Instructions

4.a Pass-through securities. Report in the appropriate columns of the appropriate subitems the amortized cost and fair value of all holdings of mortgage pass-through securities. In general, a mortgage pass-through security represents an undivided interest in a pool that provides the holder with a pro rata share of all principal and interest payments on the residential mortgages in the pool, and includes certificates of participation in pools of residential mortgages.

Include certificates of participation in pools of residential mortgages even though the reporting bank was the original holder of the mortgages underlying the pool and holds the instruments covering that pool, as may be the case with GNMA certificates issued by the bank and swaps with FNMA and FHLMC. Also include U.S. Government-issued participation certificates (PCs) that represent a pro rata share of all principal and interest payments on a pool of resecuritized participation certificates that, in turn, are backed by residential mortgages, e.g., FHLMC Giant PCs.

<u>Exclude</u> all collateralized mortgage obligations (CMOs), real estate mortgage investment conduits (REMICs), CMO and REMIC residuals, and stripped mortgage-backed securities (such as interest-only strips (IOs), principal-only strips (POs), and similar instruments) (report in Schedule RC-B, item 4.b, below).

- **Guaranteed by GNMA**. Report in the appropriate columns the amortized cost and fair value of all holdings of mortgage pass-through securities guaranteed by the Government National Mortgage Association (GNMA) that are not held for trading. Exclude mortgage pass-through securities issued by FNMA and FHLMC (report in Schedule RC-B, item 4.a.(2), below).
- **4.a.(2) Issued by FNMA and FHLMC**. Report in the appropriate columns the amortized cost and fair value of all holdings of mortgage pass-through securities issued by the Federal National Mortgage Association (FNMA) and the Federal Home Loan Mortgage Corporation (FHLMC) that are not held for trading. Exclude mortgage pass-through securities that are guaranteed by the Government National Mortgage Association (GNMA) (report in Schedule RC-B, item 4.a.(1), above).
- **Other pass-through securities.** Report in the appropriate columns the amortized cost and fair value of all holdings of mortgage pass-through securities issued by others (e.g., other depository institutions, insurance companies, state and local housing authorities in the U.S.) that are <u>not</u> guaranteed by the U.S. Government and are not held for trading.

If the bank has issued pass-through securities backed by a pool of its own residential mortgages and the certificates are not guaranteed by the U.S. Government, any holdings of these pass-through securities (not held for trading) are to be reported in this item.

4.b Other mortgage-backed securities. Report in the appropriate columns of the appropriate subitems the amortized cost and fair value of all mortgage-backed securities other than pass-through securities that are not held for trading.

Other mortgage-backed securities include:

- (1) All classes of collateralized mortgage obligations (CMOs) and real estate mortgage investments conduits (REMICs).
- (2) CMO and REMIC residuals and similar interests.
- (3) Stripped mortgage-backed securities (such as interest-only strips (IOs), principal-only strips (POs), and similar instruments).

Caption and Instructions Item No.

Issued or guaranteed by FNMA, FHLMC, or GNMA. Report in the appropriate columns the 4.b.(1) amortized cost and fair value of all classes of CMOs and REMICs, CMO and REMIC residuals, and stripped mortgage-backed securities issued by the Federal National Mortgage Association (FNMA) or the Federal Home Loan Mortgage Corporation (FHLMC) or guaranteed by the Government National Mortgage Association (GNMA). For purposes of these reports, also include REMICs issued by the U.S. Department of Veterans Affairs (VA) in this item.

- 4.b.(2) Other mortgage-backed securities collateralized by MBS issued or guaranteed by **FNMA. FHLMC. or GNMA.** Report in the appropriate columns the amortized cost and fair value of all classes of CMOs, REMICs, CMO and REMIC residuals, and stripped mortgagebacked securities issued by non-U.S. Government issuers (e.g., other depository institutions, insurance companies, state and local housing authorities in the U.S.) for which the collateral consists of GNMA (Ginnie Mae) pass-throughs, FNMA (Fannie Mae) pass-throughs, FHLMC (Freddie Mac) participation certificates, or other mortgage-backed securities (i.e., classes of CMOs or REMICs, CMO or REMIC residuals, and stripped mortgage-backed securities) issued or guaranteed by FNMA, FHLMC, GNMA, or VA.
- All other mortgage-backed securities. Report in the appropriate columns the amortized 4.b.(3) cost and fair value of all CMOs, REMICs, CMO and REMIC residuals, and stripped mortgage-backed securities issued by non-U.S. Government issuers (e.g., other depository institutions, insurance companies, state and local housing authorities in the U.S.) for which the collateral does not consist of GNMA (Ginnie Mae) pass-throughs, FNMA (Fannie Mae) pass-throughs, FHLMC (Freddie Mac) participation certificates, or other mortgage-backed securities (i.e., classes of CMOs or REMICs, CMO or REMIC residuals, and stripped mortgage-backed securities) issued or guaranteed by FNMA, FHLMC, GNMA, or VA.
 - 5 Asset-backed securities. Report in the appropriate columns of the appropriate subitems the amortized cost and fair value of all asset-backed securities (other than mortgage-backed securities), including asset-backed commercial paper, not held for trading. For purposes of categorizing asset-backed securities in Schedule RC-B, items 5.a through 5.f, below, each individual asset-backed security should be included in the item that most closely describes the predominant type of asset that collateralizes the security and this categorization should be used consistently over time. For example, an asset-backed security may be collateralized by automobile loans to both individuals and business enterprises. If the prospectus for this asset-backed security or other available information indicates that these automobile loans are predominantly loans to individuals, the security should be reported in Schedule RC-B, item 5.c, as being collateralized by automobile loans.
- Credit card receivables. Report in the appropriate columns the amortized cost and fair 5.a value of all asset-backed securities collateralized by credit card receivables, i.e., extensions of credit to individuals for household, family, and other personal expenditures arising from credit cards as defined for Schedule RC-C, part I, item 6.a.
- 5.b Home equity lines. Report in the appropriate columns the amortized cost and fair value of all asset-backed securities collateralized by home equity lines of credit, i.e., revolving, open-end lines of credit secured by 1-to-4 family residential properties as defined for Schedule RC-C, part I, item 1.c.(1).

Item No. Caption and Instructions

Automobile loans. Report in the appropriate columns the amortized cost and fair value of all asset-backed securities collateralized by automobile loans, i.e., loans to individuals for the purpose of purchasing private passenger vehicles, including minivans, vans, sport-utility vehicles, pickup trucks, and similar light trucks for personal use. Such loans are a subset of "Other consumer loans," as defined for Schedule RC-C, part I, item 6.c.

- **Other consumer loans.** Report in the appropriate columns the amortized cost and fair value of all asset-backed securities collateralized by other consumer loans, i.e., loans to individuals for household, family, and other personal expenditures as defined for Schedule RC-C, part I, items 6.b and 6.c, excluding automobile loans as described in Schedule RC-B, item 5.c, above.
- **Commercial and industrial loans**. Report in the appropriate columns the amortized cost and fair value of all asset-backed securities collateralized by commercial and industrial loans, i.e., loans for commercial and industrial purposes to sole proprietorships, partnerships, corporations, and other business enterprises, whether secured (other than by real estate) or unsecured, single-payment or installment, as defined for Schedule RC-C, part I, item 4.
- **Other.** Report in the appropriate columns the amortized cost and fair value of all asset-backed securities collateralized by non-mortgage loans other than those described in Schedule RC-B, items 5.a through 5.e, above, i.e., loans as defined for Schedule RC-C, part I, items 2, 3, and 7 through 9; lease financing receivables as defined for Schedule RC-C, part I, item 10; and all other assets.
- Other debt securities. Report in the appropriate columns of the appropriate subitems the amortized cost and fair value of all debt securities not held for trading that cannot properly be reported in Schedule RC-B, items 1 through 5, above.

Exclude from other debt securities:

- (1) All holdings of certificates of participation in pools of residential mortgages, collateralized mortgage obligations (CMOs), real estate mortgage investment conduits (REMICs), CMO and REMIC residuals, and stripped mortgage-backed securities (such as interest-only strips (IOs), principal-only strips (POs), and similar instruments) (report in Schedule RC-B, item 4, above).
- (2) Holdings of bankers acceptances and certificates of deposit, which are not categorized as securities for purposes of this report.
- **6.a** Other domestic debt securities. Report in the appropriate columns the amortized cost and fair value of all other domestic debt securities not held for trading.

Other domestic debt securities include:

- (1) Bonds, notes, debentures, equipment trust certificates, and commercial paper (except asset-backed commercial paper) issued by U.S.-chartered corporations and other U.S. issuers and not reportable elsewhere in Schedule RC-B.
- (2) Preferred stock of U.S.-chartered corporations that by its terms either must be redeemed by the issuing enterprise or is redeemable at the option of the investor.

Item No. Caption and Instructions

6.a (cont.)

(3) Detached U.S. Government security coupons and ex-coupon U.S. Government securities held as the result of either their purchase or the bank's stripping of such securities and Treasury receipts such as CATS, TIGRs, COUGARs, LIONs, and ETRs. Refer to the Glossary entry for "coupon stripping, Treasury receipts, and STRIPS" for additional information.

6.b Foreign debt securities. Report in the appropriate columns the amortized cost and fair value of all foreign debt securities not held for trading.

Foreign debt securities include:

- (1) Bonds, notes, debentures, equipment trust certificates, and commercial paper (except asset-backed commercial paper) issued by non-U.S.-chartered corporations.
- (2) Debt securities issued by foreign governmental units.
- (3) Debt securities issued by international organizations such as the International Bank for Reconstruction and Development (World Bank), Inter-American Development Bank, and Asian Development Bank.
- (4) Preferred stock of non-U.S.-chartered corporations that by its terms either must be redeemed by the issuing enterprise or is redeemable at the option of the investor.
- Investments in mutual funds and other equity securities with readily determinable fair values. Report in columns C and D the historical cost and fair value, respectively, of all investments in mutual funds and other equity securities with readily determinable fair values. Such securities include, but are not limited to, money market mutual funds, mutual funds that invest solely in U.S. Government securities, common stock of the Federal National Mortgage Association (Fannie Mae), preferred stock and unrestricted voting common stock of the Student Loan Marketing Association (Sallie Mae), and common stock of the Federal Home Loan Mortgage Corporation (Freddie Mac).

The fair value of an equity security is readily determinable if sales or bid-and-asked quotations are currently available on a securities exchange registered with the Securities and Exchange Commission (SEC) or in the over-the-counter market, provided that those prices or quotations for the over-the-counter market are publicly reported by the National Association of Securities Dealers Automated Quotations systems or by the National Quotation Bureau. The fair value of an equity security traded only in a foreign market is readily determinable if that foreign market is of a breadth and scope comparable to one of the U.S. markets referred to above.

Investments in mutual funds and other equity securities with readily determinable fair values may have been purchased by the reporting bank or acquired for debts previously contracted.

Exclude from investments in mutual funds and other equity securities with readily determinable fair values:

- (1) Paid-in stock of a Federal Reserve Bank (report as an equity security that does not have a readily determinable fair value in Schedule RC-F, item 4).
- (2) Stock of a Federal Home Loan Bank (report as an equity security that does not have a readily determinable fair value in Schedule RC-F, item 4).

Item No. Caption and Instructions

7 (cont.)

- (3) Common and preferred stocks that do not have readily determinable fair values, such as stock of bankers' banks and voting common stock of the Federal Agricultural Mortgage Corporation (Farmer Mac) (report in Schedule RC-F, item 4).
- (4) Preferred stock that by its terms either must be redeemed by the issuing enterprise or is redeemable at the option of the investor (report such preferred stock as an other debt security in Schedule RC-B, item 6, above).
- (5) "Restricted stock," as defined in FASB Statement No. 115, i.e., equity securities for which sale is restricted by governmental or contractual requirement (other than in connection with being pledged as collateral), except if that requirement terminates within one year or if the holder has the power by contract or otherwise to cause the requirement to be met within one year (report "restricted stock" as an equity security that does not have a readily determinable fair value in Schedule RC-F, item 4).
- (6) Participation certificates issued by a Federal Intermediate Credit Bank, which represent nonvoting stock in the bank (report as an equity security that does not have a readily determinable fair value in Schedule RC-F, item 4).
- (7) Minority interests held by the reporting bank in any companies not meeting the definition of associated company (report as equity securities that do not have a readily determinable fair value in Schedule RC-F, item 4), except minority holdings that indirectly represent bank premises (report in Schedule RC, item 6) or other real estate owned (report in Schedule RC, item 7), provided that the fair value of any capital stock representing the minority interest is not readily determinable. (See the Glossary entry for "subsidiaries" for the definition of associated company.)
- (8) Equity holdings in those corporate joint ventures over which the reporting bank does not exercise significant influence (report as equity securities that do not have a readily determinable fair value in Schedule RC-F, item 4), except equity holdings that indirectly represent bank premises (report in Schedule RC, item 6) or other real estate owned (report in Schedule RC, item 7). (See the Glossary entry for "subsidiaries" for the definition of corporate joint venture.)
- (9) Holdings of capital stock of and investments in unconsolidated subsidiaries, associated companies, and those corporate joint ventures over which the reporting bank exercises significant influence (report in Schedule RC, item 8, "Investments in unconsolidated subsidiaries and associated companies").
- **Total**. Report the sum of items 1 through 7. The total of column A for this item must equal Schedule RC, item 2.a, "Held-to-maturity securities." The total of column D for this item must equal Schedule RC, item 2.b, "Available-for-sale securities."

Memoranda

Item No. **Caption and Instructions**

Pledged securities. Report the amortized cost of all held-to-maturity securities and the 1 fair value of all available-for-sale securities included in Schedule RC-B above that are pledged to secure deposits, repurchase transactions, or other borrowings (regardless of the balance of the deposits or other liabilities against which the securities are pledged), as performance bonds under futures or forward contracts, or for any other purpose.

2 Maturity and repricing data for debt securities. Report in the appropriate subitem maturity and repricing data for the bank's holdings of debt securities (reported in Schedule RC-B, items 1 through 6 above). Report the amortized cost of held-to-maturity debt securities and the fair value of available-for-sale debt securities in the appropriate maturity and repricing subitems. Exclude from Memorandum item 2 the bank's holdings of equity securities with readily determinable fair values (reported in Schedule RC-B, item 7, above) (e.g., investments in mutual funds, common stock, preferred stock). Also exclude those debt securities that are reported as "nonaccrual" in Schedule RC-N, item 9, column C.

> The sum of Memorandum items 2.a.(1) through 2.c.(2) plus the amount of any nonaccrual debt securities included in Schedule RC-N, item 9, column C, must equal Schedule RC-B, sum of items 1 through 6, columns A and D.

On the FFIEC 031, banks that have more than one office in foreign countries (including offices of consolidated foreign subsidiaries but excluding "shell" branches, offices in Puerto Rico or U.S. territories and possessions, and IBFs) have the option of excluding the smallest of such non-U.S. offices from Memorandum item 2. Such banks may omit the smallest of their offices in foreign countries (other than "shell" branches) when arrayed by total assets provided that the assets of the excluded offices do not exceed 50 percent of the total assets of the bank's offices (excluding "shells") in foreign countries and do not exceed 10 percent of the total consolidated assets of the reporting bank as of the report date. (Note: In determining the total assets of offices in foreign countries eligible for exclusion from these memorandum items, banks should exclude not only "shell" branches but also offices in Puerto Rico and U.S. territories and possessions, domestic offices of Edge and Agreement subsidiaries, and IBFs even though these are sometimes referred to as "foreign" offices. Also, the asset totals for all offices in foreign countries should be the component of the total consolidated assets, i.e., should exclude all intrabank transactions.)

For purposes of this memorandum item, the following definitions apply:

A fixed interest rate is a rate that is specified at the origination of the transaction, is fixed and invariable during the term of the debt security, and is known to both the borrower and the lender. Also treated as a fixed interest rate is a predetermined interest rate which is a rate that changes during the term of the debt security on a predetermined basis, with the exact rate of interest over the life of the debt security known with certainty to both the borrower and the lender when the debt security is acquired.

A floating rate is a rate that varies, or can vary, in relation to an index, to some other interest rate such as the rate on certain U.S. Government securities or the "prime rate," or to some other variable criterion the exact value of which cannot be known in advance. Therefore, the exact rate the debt security carries at any subsequent time cannot be known at the time of origination.

FFIEC 031 and 041 **RC-B-11 RC-B - SECURITIES**

Memoranda

Item No. Caption and Instructions

When the rate on a debt security with a floating rate has reached a contractual floor or ceiling level, the debt security is to be treated as "fixed rate" rather than as "floating rate" until the rate is again free to float.

<u>Remaining maturity</u> is the amount of time remaining from the report date until the final contractual maturity of a debt security without regard to the security's repayment schedule, if any.

<u>Next repricing date</u> is the date the interest rate on a floating rate debt security can next change in accordance with the terms of the contract (without regard to the security's repayment schedule, if any, or expected prepayments) or the contractual maturity date of the security, whichever is earlier.

Banks whose records or information systems provide data on the final contractual maturities, next repricing dates, and expected average lives of their debt securities for time periods that closely approximate the maturity and repricing periods specified in Memorandum items 2.a through 2.d (e.g., 89 or 90 days rather than three months, 359 or 360 days rather than 12 months) may use these date to complete Memorandum items 2.a through 2.d.

For debt securities with scheduled contractual payments, banks whose records or information systems provide repricing data that take into account these scheduled contractual payments, with or without the effect of anticipated prepayments, may adjust these data in an appropriate manner to derive reasonable estimates for the final contractual maturities of fixed rate debt securities (and floating rate debt securities for purposes of Memorandum item 2.c) and the next repricing dates of floating rate debt securities.

Callable fixed rate debt securities should be reported in Memorandum items 2.a, 2.b, and 2.d without regard to their next call date <u>unless</u> the security has actually been called. When fixed rate debt securities have been called, they should be reported on the basis of the time remaining until the call date. Callable floating rate debt securities should be reported in Memorandum items 2.a and 2.b on the basis of their next repricing date without regard to their next call date if the security has not been called. Those that have been called should be reported based on the earlier of their next repricing date or their actual call date.

Fixed rate mortgage pass-through securities (such as those guaranteed by the Government National Mortgage Association (GNMA) or issued by the Federal Home Loan Mortgage Corporation (FHLMC), the Federal National Mortgage Association (FNMA), and certain banks, savings associations, and securities dealers) and fixed rate Small Business Administration (SBA) "Guaranteed Loan Pool Certificates" should be reported on the basis of the time remaining until their final contractual maturity without regard to either expected prepayments or scheduled contractual payments. Floating rate mortgage pass-through securities and SBA "Guaranteed Loan Pool Certificates" should be reported in Memorandum items 2.a and 2.b on the basis of their next repricing date.

FFIEC 031 and 041 RC-B-12 RC-B - SECURITIES

Memoranda

Item No. Caption and Instructions

Fixed rate debt securities that provide the reporting bank with the option to redeem them at one or more specified dates prior to their contractual maturity date, so-called "put bonds," should be reported on the basis of the time remaining until the next "put" date. Floating rate "put bonds" should be reported in Memorandum items 2.a and 2.b on the basis of their next repricing date without regard to "put" dates if the bank has not exercised the put. If a "put" has been exercised but the security has not yet been repaid, the "put" bond should be reported based on the earlier of its next repricing date or its scheduled repayment date.

Zero coupon debt securities, including U.S. Treasury bills, should be treated as fixed rate debt securities for purposes of this Memorandum item.

2.a Securities issued by the U.S. Treasury, U.S. Government agencies, and states and political subdivisions in the U.S.; other non-mortgage debt securities; and mortgage pass-through securities other than those backed by closed-end first lien 1-4 family residential mortgages with a remaining maturity or next repricing date of. Report the bank's holdings of fixed rate debt securities -- other than mortgage pass-through securities backed by closed-end first lien 1-4 family residential mortgages -- in the appropriate subitems according to the amount of time remaining to their final contractual maturities (without regard to repayment schedules, if any). Report the bank's holdings of floating rate debt securities -- other than mortgage pass-through securities backed by closed-end first lien 1-4 family residential mortgages -- in the appropriate subitems according to the amount of time remaining until their next repricing date. Exclude debt securities that are in nonaccrual status.

For held-to-maturity debt securities, report amortized cost. For available-for-sale debt securities, report fair value.

2.a.(1) Three months or less. Report the amount of:

- the bank's fixed rate debt securities -- other than mortgage pass-through securities backed by closed-end first lien 1-4 family residential mortgages -- with remaining maturities of three months or less, and
- the bank's floating rate debt securities -- other than mortgage pass-through securities backed by closed-end first lien 1-4 family residential mortgages – with next repricing dates occurring in three months or less.

2.a.(2) Over three months through 12 months. Report the amount of:

- the bank's fixed rate debt securities -- other than mortgage pass-through securities backed by closed-end first lien 1-4 family residential mortgages -- with remaining maturities (without regard to repayment schedules, if any) of over three months through 12 months, and
- the bank's floating rate debt securities -- other than mortgage pass-through securities backed by closed-end first lien 1-4 family residential mortgages – with next repricing dates occurring in over three months through 12 months.

FFIEC 031 and 041 RC-B-13 RC-B - SECURITIES

Memoranda

Item No. Caption and Instructions

2.a.(3) Over one year through three years. Report the amount of:

 the bank's fixed rate debt securities -- other than mortgage pass-through securities backed by closed-end first lien 1-4 family residential mortgages -- with remaining maturities (without regard to repayment schedules, if any) of over one year through three years, and

 the bank's floating rate debt securities -- other than mortgage pass-through securities backed by closed-end first lien 1-4 family residential mortgages – with next repricing dates occurring in over one year through three years.

2.a.(4) Over three years through five years. Report the amount of:

- the bank's fixed rate debt securities -- other than mortgage pass-through securities backed by closed-end first lien 1-4 family residential mortgages -- with remaining maturities (without regard to repayment schedules, if any) of over three years through five years, and
- the bank's floating rate debt securities -- other than mortgage pass-through securities backed by closed-end first lien 1-4 family residential mortgages with next repricing dates occurring in over three years through five years.

2.a.(5) Over five years through 15 years. Report the amount of:

- the bank's fixed rate debt securities -- other than mortgage pass-through securities backed by closed-end first lien 1-4 family residential mortgages -- with remaining maturities (without regard to repayment schedules, if any) of over five years through 15 years, and
- the bank's floating rate debt securities -- other than mortgage pass-through securities backed by closed-end first lien 1-4 family residential mortgages with next repricing dates occurring in over five years through 15 years.

2.a.(6) Over 15 years. Report the amount of:

- the bank's fixed rate debt securities -- other than mortgage pass-through securities backed by closed-end first lien 1-4 family residential mortgages -- with remaining maturities (without regard to repayment schedules, if any) of over 15 years, and
- the bank's floating rate debt securities -- other than mortgage pass-through securities backed by closed-end first lien 1-4 family residential mortgages – with next repricing dates occurring in over 15 years.
- 2.b Mortgage pass-through securities backed by closed-end first lien 1-4 family residential mortgages with a remaining maturity or next repricing date of. Report the bank's holdings of fixed rate mortgage pass-through securities backed by closed-end first lien 1-4 family residential mortgages in the appropriate subitems according to the amount of time remaining to their final contractual maturities (without regard to repayment schedules, if any). Report the bank's holdings of floating rate mortgage pass-through securities backed by

FFIEC 031 and 041 RC-B-14 RC-B - SECURITIES

Memoranda

Item No. Caption and Instructions

2.b closed-end first lien 1-4 family residential mortgages in the appropriate subitems according to the amount of time remaining until their next repricing date. Exclude mortgage pass-through securities that are in nonaccrual status.

For held-to-maturity mortgage pass-through securities, report amortized cost. For available-for-sale mortgage pass-through securities, report fair value.

2.b.(1) Three months or less. Report the amount of:

- the bank's fixed rate mortgage pass-through securities backed by closed-end first lien 1-4 family residential mortgages with remaining maturities of three months or less, and
- the bank's floating rate mortgage pass-through securities backed by closed-end first lien
 1-4 family residential mortgages with next repricing dates occurring in three months or less.

2.b.(2) Over three months through 12 months. Report the amount of:

- the bank's fixed rate mortgage pass-through securities backed by closed-end first lien 1-4 family residential mortgages with remaining maturities (without regard to repayment schedules, if any) of over three months through 12 months, and
- the bank's floating rate mortgage pass-through securities backed by closed-end first lien
 1-4 family residential mortgages with next repricing dates occurring in over three months through 12 months.

2.b.(3) Over one year through three years. Report the amount of:

- the bank's fixed rate mortgage pass-through securities backed by closed-end first lien 1-4
 family residential mortgages with remaining maturities (without regard to repayment
 schedules, if any) of over one year through three years, and
- the bank's floating rate mortgage pass-through securities backed by closed-end first lien
 1-4 family residential mortgages with next repricing dates occurring in over one year
 through three years.

2.b.(4) Over three years through five years. Report the amount of:

- the bank's fixed rate mortgage pass-through securities backed by closed-end first lien 1-4
 family residential mortgages with remaining maturities (without regard to repayment
 schedules, if any) of over three years through five years, and
- the bank's floating rate mortgage pass-through securities backed by closed-end first lien
 1-4 family residential mortgages with next repricing dates occurring in over three years through five years.

FFIEC 031 and 041 RC-B-15 RC-B - SECURITIES

Memoranda

Item No. Caption and Instructions

2.b.(5) Over five years through 15 years. Report the amount of:

the bank's fixed rate mortgage pass-through securities backed by closed-end first lien 1-4
family residential mortgages with remaining maturities (without regard to repayment
schedules, if any) of over five years through 15 years, and

the bank's floating rate mortgage pass-through securities backed by closed-end first lien
 1-4 family residential mortgages with next repricing dates occurring in over five years
 through 15 years.

2.b.(6) Over 15 years. Report the amount of:

- the bank's fixed rate mortgage pass-through securities backed by closed-end first lien 1-4 family residential mortgages with remaining maturities (without regard to repayment schedules, if any) of over 15 years, and
- the bank's floating rate mortgage pass-through securities backed by closed-end first lien
 1-4 family residential mortgages with next repricing dates occurring in over fifteen years.
- 2.c Other mortgage-backed securities (include CMOs, REMICs, and stripped MBS) with an expected average life of. Report the bank's holdings of other mortgage-backed securities (including collateralized mortgage obligations (CMOs), real estate mortgage investment conduits (REMICs), and stripped mortgage-backed securities (MBS)) in the appropriate subitems by their expected weighted average life as of the report date. Include both fixed rate and floating rate securities. For held-to-maturity securities, report amortized cost. For available-for-sale securities, report fair value. Exclude all mortgage pass-through securities. Also exclude securities that are in nonaccrual status.

Banks should report based on the most recent average life information obtained within the twelve months preceding the report date. Weighted average life is the dollar-weighted average time in which principal is repaid. For a mortgage-backed security, weighted average life should be based on the prepayment assumptions associated with the pool of loans underlying the security as well as scheduled repayments. Weighted average life is computed by (a) multiplying the amount of each principal reduction by the number of years or months from the date of issuance or the testing date to the date of the principal reduction, (b) summing the results, and (c) dividing the sum by the remaining principal balance as of the date of issuance or the testing date. Because weighted average life should consider expected prepayments, it is not equivalent to contractual maturity. Because it is dollar- and time-weighted, it also is not equivalent to expected final maturity.

- **Three years or less.** Report the bank's holdings of other mortgage-backed securities with an expected weighted average life of three years or less as of the report date. Include both fixed rate and floating rate securities.
- **2.c.(2)** Over three years. Report the bank's holdings of other mortgage-backed securities with an expected weighted average life of over three years as of the report date. Include both fixed rate and floating rate securities.

FFIEC 031 and 041 RC-B-16 RC-B - SECURITIES

Memoranda

Item No. Caption and Instructions

2.d <u>Debt securities with a remaining maturity of one year or less.</u> Report all debt securities with a remaining maturity of one year or less. Include both fixed rate and floating rate debt securities. Exclude debt securities that are in nonaccrual status.

For held-to-maturity debt securities, report amortized cost. For available-for-sale debt securities, report fair value.

The fixed rate debt securities (excluding "Other mortgage-backed securities") that should be included in this item will also have been reported by remaining maturity in Schedule RC-B, Memorandum items 2.a.(1), 2.a.(2), 2.b.(1), and 2.b.(2), above. The floating rate debt securities (excluding "Other mortgage-backed securities") that should be included in this item will have been reported by next repricing date in Memorandum items 2.a.(1), 2.a.(2), 2.b.(1), and 2.b.(2), above. However, these four Memorandum items may include floating rate debt securities with a remaining maturity of more than one year, but on which the interest rate can next change in one year or less; those debt securities should not be included in this Memorandum item 2.d. The "Other mortgage-backed securities" included in this item will have been reported by expected weighted average life in Memorandum items 2.c.(1) and 2.c.(2) above.

Amortized cost of held-to-maturity securities sold or transferred to available-for-sale or trading securities during the calendar year-to-date. If the reporting bank has sold any held-to-maturity debt securities or has transferred any held-to-maturity debt securities to the available-for-sale or to trading securities during the calendar year-to-date, report the total amortized cost of these held-to-maturity debt securities as of their date of sale or transfer.

Exclude the amortized cost of any held-to-maturity debt security that has been sold near enough to (e.g., within three months of) its maturity date (or call date if exercise of the call is probable) that interest rate risk is substantially eliminated as a pricing factor. Also exclude the amortized cost of any held-to-maturity debt security that has been sold after the collection of a substantial portion (i.e., at least 85 percent) of the principal outstanding at acquisition due to prepayments on the debt security or, if the debt security is a fixed rate security, due to scheduled payments payable in equal installments (both principal and interest) over its term.

Structured notes. Report in this item all structured notes included in the held-to-maturity and available-for-sale accounts and reported in Schedule RC-B, items 2, 3, 5, and 6. In general, structured notes are debt securities whose cash flow characteristics (coupon rate, redemption amount, or stated maturity) depend upon one or more indices and/or that have embedded forwards or options or are otherwise commonly known as "structured notes." Include as structured notes any asset-backed securities (other than mortgage-backed securities) which possess the aforementioned characteristics. **Exclude** from structured notes all "inflation-indexed" securities issued by the U.S. Treasury.

Structured notes include, but are not limited to, the following common structures:

(1) Floating rate debt securities whose payment of interest is based upon a single index of a Constant Maturity Treasury (CMT) rate or a Cost of Funds Index (COFI).

FFIEC 031 and 041 RC-B-17 RC-B - SECURITIES

Memoranda

Item No. **Caption and Instructions**

4 (cont.)

- (2) Step-up Bonds. Step-up securities initially pay the investor an above-market yield for a short noncall period and then, if not called, "step up" to a higher coupon rate (which will be below current market rates). The investor initially receives a higher yield because of having implicitly sold one or more call options. A step-up bond may continue to contain call options even after the bond has stepped up to the higher coupon rate. A multistep bond has a series of fixed and successively higher coupons over its life. At each call date, if the bond is not called, the coupon rate increases.
- (3) Index Amortizing Notes (IANs). IANs repay principal according to a predetermined amortization schedule that is linked to the level of a specific index (usually the London Interbank Offered Rate - LIBOR - or a specified prepayment rate). As market interest rates increase (or prepayment rates decrease), the maturity of an IAN extends, similar to that of a collateralized mortgage obligation.
- (4) **Dual Index Notes.** These bonds have coupon rates that are determined by the difference between two market indices, typically the CMT rate and LIBOR. These bonds often have a fixed coupon rate for a brief period, followed by a longer period of variable rates, e.g., 8 percent fixed for two years, then the 10-year CMT rate plus 300 basis points minus three-month LIBOR.
- (5) **De-leveraged Bonds.** These bonds pay investors according to a formula that is based upon a fraction of the increase or decrease in a specified index, such as the CMT rate or the prime rate. For example, the coupon might be the 10-year CMT rate multiplied by 0.5, plus 150 basis points. The de-leveraging multiplier (0.5) causes the coupon to lag overall movements in market yields. A leveraged bond would involve a multiplier greater than 1.
- (6) Range Bonds. Range bonds (or accrual bonds) pay the investor an above-market coupon rate as long as the reference rate is between levels established at issue. For each day that the reference rate is outside this range, the bonds earn no interest. For example, if LIBOR is the reference rate, a bond might pay LIBOR plus 75 basis points for each day that LIBOR is between 3.5 and 5.0 percent. When LIBOR is less than 3.5 percent or more than 5 percent, the bond would accrue no interest.
- (7) Inverse Floaters. These bonds have coupons that increase as rates decline and decrease as rates rise. The coupon is based upon a formula, such as 12 percent minus three-month LIBOR.

Exclude from structured notes floating rate debt securities denominated in U.S. dollars whose payment of interest is based upon a single index of a Treasury bill rate, the prime rate, or LIBOR and which do not contain adjusting caps, adjusting floors, leverage, or variable principal redemption. Furthermore, debt securities that do not possess the aforementioned characteristics of a structured note need not be reported as structured notes solely because they are callable as of a specified date at a specified price. In addition, debt securities that in the past possessed the characteristics of a structured note, but which have "fallen through" their structures (e.g., all of the issuer's call options have expired and there are no more adjustments to the interest rate on the security), need not be reported as structured notes.

FFIEC 031 and 041 **RC-B-18 RC-B - SECURITIES**

Memoranda

Item No. Caption and Instructions

Generally, municipal and corporate securities that have periodic call options should **not** be reported as structured notes. Although many of these securities have features similar to those found in some structured notes (e.g., step-ups, which generally remain callable after a step-up date), they are **not commonly known** as structured notes. Examples of such callable securities that should **not** be reported as structured notes include:

- (1) Callable municipal and corporate bonds which have single (or multiple) explicit call dates and then can be called on any interest payment date after the last explicit call date (i.e., they are continuously callable).
- (2) Callable federal agency securities that have continuous call features after an explicit call date, except step-up bonds (which are structured notes).

The mere existence of simple caps and floors does not necessarily make a security a structured note. Securities with **adjusting** caps or floors (i.e., caps or floors that change over time), however, are structured notes. Therefore, the following types of securities should **not** be reported as structured notes:

- (1) Variable rate securities, including Small Business Administration "Guaranteed Loan Pool Certificates," unless they have features of securities which are commonly known as structured notes (i.e., they are inverse, range, or de-leveraged floaters, index amortizing notes, dual index or variable principal redemption or step-up bonds), or have adjusting caps or floors.
- Mortgage-backed securities.
- **4.a Amortized cost (of structured notes).** Report the amortized cost of all structured notes included in the held-to-maturity and available-for-sale accounts. The amortized cost of these securities will have been reported in columns A and C of the body of Schedule RC-B.
- 4.b Fair value (of structured notes). Report the fair (market) value of structured notes reported in Memorandum item 4.a above. The fair value of these securities will have been reported in columns B and D of the body of Schedule RC-B. Do not combine or otherwise net the fair value of any structured note with the fair or book value of any related asset, liability, or off-balance sheet derivative instrument.

FFIEC 031 and 041 RC-B-19 RC-B - SECURITIES

SCHEDULE RC-C -- LOANS AND LEASE FINANCING RECEIVABLES

Part I. Loans and Leases

General Instructions for Part I

Loans and lease financing receivables are extensions of credit resulting from either direct negotiation between the bank and its customers or the purchase of such assets from others. See the Glossary entries for "loan" and for "lease accounting" for further information.

Report all loans and leases that the bank has the intent and ability to hold for the foreseeable future or until maturity or payoff in Schedule RC-C, part I. Also report all loans and leases held for sale as part of the consolidated bank's mortgage banking activities or activities of a similar nature involving other types of loans. Loans held for sale shall be reported at the lower of cost or fair value as of the report date. The amount by which cost exceeds fair value, if any, shall be accounted for as a valuation allowance. For further information, see FASB Statement No. 65, Accounting for Certain Mortgage Banking Activities.

On the FFIEC 041, Schedule RC-C, part I, has two columns for information on loans and leases: column B is to be completed by all banks and column A is to be completed by banks with \$300 million or more in total assets. On the FFIEC 031, this schedule has two columns: column A provides loan and lease detail for the fully consolidated bank and column B provides detail on loans and leases held by the domestic offices of the reporting bank. (See the Glossary entry for "domestic office" for the definition of this term.)

Report loans and leases in this schedule without any deduction for the "Allowance for loan and lease losses," which is to be reported in Schedule RC, item 4.c. Each item in this schedule should be reported net of (1) unearned income (to the extent possible), (2) any applicable allocated transfer risk reserve, and (3) deposits accumulated for the payment of personal loans (hypothecated deposits). Net unamortized loan fees represent an adjustment of the loan yield, and shall be reported in this schedule in the same manner as unearned income on loans, i.e., deducted from the related loan balances (to the extent possible) or deducted from total loans in item 11, "LESS: Any unearned income on loans reflected in items 1-9 above." Net unamortized direct loan origination costs shall be added to the related loan balances in each item in this schedule. (See the Glossary entry for "loan fees" for further information.)

<u>Exclude</u> all loans and leases held for trading purposes (report in Schedule RC, item 5, "Trading assets," and, in the appropriate items of Schedule RC-D, Trading Assets and Liabilities, if applicable).

All loans should be categorized in Schedule RC-C, part I, according to security, borrower, or purpose. Loans covering two or more categories are sometimes difficult to categorize. In such instances, categorize the entire loan according to the major criterion.

Report in Schedule RC-C, part I, all loans and leases on the books of the reporting bank even if on the report date they are past due and collection is doubtful. Exclude any loans or leases the bank has sold or charged off. Also exclude assets received in full or partial satisfaction of a loan or lease (unless the asset received is itself reportable as a loan or lease) and any loans for which the bank has obtained physical possession of the underlying collateral, regardless of whether formal foreclosure or repossession proceedings have been instituted against the borrower. Refer to the Glossary entries for "troubled debt restructurings" and "foreclosed assets" for further discussion of these topics.

FFIEC 031 and 041 RC-C-1 RC-C - LOANS AND LEASES (3-01)

General Instructions for Part I (cont.)

Exclude, for purposes of this schedule, the following:

(1) All loans of immediately available funds that mature in one business day or roll over under a continuing contract, i.e., federal funds sold (report in Schedule RC, item 3, "Federal funds sold and securities purchased under agreements to resell"). However, report overnight lending for commercial and industrial purposes as loans in this schedule.

- (2) All holdings of commercial paper (report in Schedule RC, item 5, if held for trading; report in Schedule RC-B, item 5, "Asset-backed securities," or item 6, "Other debt securities," as appropriate, if held for purposes other than trading).
- (3) Contracts of sale or other loans indirectly representing other real estate (report in Schedule RC, item 7, "Other real estate owned").
- (4) Undisbursed loan funds, sometimes referred to as incomplete loans or loans in process, unless the borrower is liable for and pays the interest thereon. If interest is being paid by the borrower on the undisbursed proceeds, the amount of such undisbursed funds should be included in both loans and deposits. (Do not include loan commitments that have not yet been taken down, even if fees have been paid; see Schedule RC-L, item 1.)

Item Instructions for Part I

Item No. Caption and Instructions

Loans secured by real estate. Report all loans secured by real estate. On the FFIEC 041, all banks should report in the appropriate subitems of column B a breakdown of these loans into seven categories. On the FFIEC 031, all banks should report the total amount of these loans for the fully consolidated bank in column A, but with a breakdown of these loans into seven categories for domestic offices in column B.

Include all loans (other than those to states and political subdivisions in the U.S.), regardless of purpose and regardless of whether originated by the bank or purchased from others, that are secured by real estate as evidenced by mortgages, deeds of trust, land contracts, or other instruments, whether first or junior liens (e.g., equity loans, second mortgages) on real estate. See the Glossary entry for "loan secured by real estate" for the definition of this term.

Include as loans secured by real estate:

- (1) Loans secured by residential properties that are guaranteed by the Farmers Home Administration (FmHA) and extended, collected, and serviced by a party other than the FmHA.
- (2) Loans secured by properties and guaranteed by governmental entities in foreign countries.
- (3) Participations in pools of Federal Housing Administration (FHA) Title I home improvement loans that are secured by liens (generally, junior liens) on residential properties.

FFIEC 031 and 041 RC-C-2 RC-C - LOANS AND LEASES (3-01)

Part I. (cont.)

Item No. **Caption and Instructions**

Exclude from loans secured by real estate: 1 (cont.)

- (1) Obligations (other than securities and leases) of states and political subdivisions in the U.S. that are secured by real estate (report in Schedule RC-C, part I, item 8).
- (2) All loans and sales contracts indirectly representing other real estate (report in Schedule RC, item 7, "Other real estate owned").
- (3) Loans to real estate companies, real estate investment trusts, mortgage lenders, and foreign non-governmental entities that specialize in mortgage loan originations and that service mortgages for other lending institutions when the real estate mortgages or similar liens on real estate are not sold to the bank but are merely pledged as collateral (report in Schedule RC-C, part I, item 2, "Loans to depository institutions and acceptances of other banks," or as all other loans in Schedule RC-C, part I, item 9).
- (4) Bonds issued by the Federal National Mortgage Association or by the Federal Home Loan Mortgage Corporation that are collateralized by residential mortgages (report in Schedule RC-B, item 2.b, Securities "Issued by U.S. Government-sponsored agencies").
- (5) Pooled residential mortgages for which participation certificates have been issued or guaranteed by the Government National Mortgage Association, the Federal National Mortgage Association, or the Federal Home Loan Mortgage Corporation (report in Schedule RC-B, item 4.a).
- Construction, land development, and other land loans. Report in column B loans secured 1.a by real estate made to finance land development (i.e., the process of improving land -- laying sewers, water pipes, etc.) preparatory to erecting new structures or the on-site construction of industrial, commercial, residential, or farm buildings. For this item, "construction" includes not only construction of new structures, but also additions or alterations to existing structures and the demolition of existing structures to make way for new structures.

Also include in this item:

- (1) Loans secured by vacant land, except land known to be used or usable for agricultural purposes, such as crop and livestock production (which should be reported in Schedule RC-C, part I, item 1.b, below, as loans secured by farmland).
- (2) Loans secured by real estate the proceeds of which are to be used to acquire and improve developed and undeveloped property.
- (3) Loans made under Title I or Title X of the National Housing Act that conform to the definition of construction stated above and that are secured by real estate.

Exclude loans to finance construction and land development that are not secured by real estate (report in other items of Schedule RC-C, part I, as appropriate).

FFIEC 031 and 041 RC-C-3 **RC-C - LOANS AND LEASES**

Part I. (cont.)

Item No. Caption and Instructions

Secured by farmland. Report in column B loans secured by farmland and improvements thereon, as evidenced by mortgages or other liens. Farmland includes all land known to be used or usable for agricultural purposes, such as crop and livestock production. Farmland includes grazing or pasture land, whether tillable or not and whether wooded or not.

<u>Include</u> loans secured by farmland that are guaranteed by the Farmers Home Administration (FmHA) or by the Small Business Administration (SBA) and that are extended, serviced, and collected by any party other than FmHA or SBA.

<u>Exclude</u> loans for farm property construction and land development purposes (report in Schedule RC-C, part I, item 1.a).

- **Secured by 1-4 family residential properties**. Report in the appropriate subitem of column B open-end and closed-end loans secured by real estate as evidenced by mortgages (FHA, FmHA, VA, or conventional) or other liens on:
 - (1) Nonfarm property containing 1-to-4 dwelling units (including vacation homes) or more than four dwelling units if each is separated from other units by dividing walls that extend from ground to roof (e.g., row houses, townhouses, or the like).
 - (2) Mobile homes where (a) state laws define the purchase or holding of a mobile home as the purchase or holding of real property and where (b) the loan to purchase the mobile home is secured by that mobile home as evidenced by a mortgage or other instrument on real property.
 - (3) Individual condominium dwelling units and loans secured by an interest in individual cooperative housing units, even if in a building with five or more dwelling units.
 - (4) Housekeeping dwellings with commercial units combined where use is primarily residential and where only 1-to-4 family dwelling units are involved.

Exclude loans for 1-to-4 family residential property construction and land development purposes (report in Schedule RC-C, part I, item 1.a). Also exclude loans secured by vacant lots in established single-family residential sections or in areas set aside primarily for 1-to-4 family homes (report in Schedule RC-C, part I, item 1.a).

- 1.c.(1) Revolving, open-end loans secured by 1-4 family residential properties and extended under lines of credit. Report in column B the amount outstanding under revolving, open-end lines of credit secured by 1-to-4 family residential properties. These lines of credit, commonly known as home equity lines, are typically secured by a junior lien and are usually accessible by check or credit card.
- **1.c.(2)** Closed-end loans secured by 1-4 family residential properties. Report in the appropriate subitem of column B the amount of all closed-end loans secured by 1-to-4 family residential properties (i.e., closed-end first mortgages and junior liens).

FFIEC 031 and 041 RC-C-4 RC-C - LOANS AND LEASES (6-01)

Part I. (cont.)

Item No. **Caption and Instructions**

Secured by first liens. Report in column B the amount of all closed-end loans secured by 1.c.(2)(a) first liens on 1-to-4 family residential properties.

- Secured by iunior liens. Report in column B the amount of all closed-end loans secured by 1.c.(2)(b) junior (i.e., other than first) liens on 1-to-4 family residential properties. Include loans secured by junior liens in this item even if the bank also holds a loan secured by a first lien on the same 1-to-4 family residential property and there are no intervening junior liens.
- 1.d Secured by multifamily (5 or more) residential properties. Report in column B all other nonfarm residential loans secured by real estate as evidenced by mortgages (FHA and conventional) or other liens that are not reportable in Schedule RC-C, part I, item 1.c. Specifically, include loans on:
 - (1) Nonfarm properties with 5 or more dwelling units in structures (including apartment buildings and apartment hotels) used primarily to accommodate households on a more or less permanent basis.
 - (2) 5 or more unit housekeeping dwellings with commercial units combined where use is primarily residential.
 - (3) Cooperative-type apartment buildings containing 5 or more dwelling units.

Exclude loans for multifamily residential property construction and land development purposes (report in Schedule RC-C, part I, item 1.a). Also exclude loans secured by nonfarm nonresidential properties (report in Schedule RC-C, part I, item 1.e).

1.e Secured by nonfarm nonresidential properties. Report in column B loans secured by real estate as evidenced by mortgages or other liens on business and industrial properties, hotels, motels, churches, hospitals, educational and charitable institutions, dormitories, clubs, lodges, association buildings, "homes" for aged persons and orphans, golf courses, recreational facilities, and similar properties.

> Exclude loans for nonfarm nonresidential property construction and land development purposes (report in Schedule RC-C, part I, item 1.a).

2 Loans to depository institutions and acceptances of other banks. Report all loans (other than those secured by real estate), including overdrafts, to banks, other depository institutions, and other associations, companies, and financial intermediaries whose primary business is to accept deposits and to extend credit for business or for personal expenditure purposes and the bank's holdings of all bankers acceptances accepted by other banks that are not held for trading. Acceptances accepted by other banks may be purchased in the open market or discounted by the reporting bank. For further information, see the Glossary entry for "bankers acceptances."

> On the FFIEC 041, all banks should report the total amount of these loans and acceptances in column B, and banks with \$300 million or more in total assets should also report in the appropriate subitems of column A a breakdown of these loans among five categories of depository institutions. On the FFIEC 031, all banks should report a breakdown of loans to

FFIEC 031 and 041 RC-C-5 **RC-C - LOANS AND LEASES**

Part I. (cont.)

Item No. Caption and Instructions

depository institutions and acceptances of other banks among five categories of depository (cont.) institutions for the fully consolidated bank in column A and a breakdown of these loans and acceptances among three categories of depository institutions for domestic offices in column B.

Depository institutions cover:

- (1) commercial banks in the U.S., including:
 - (a) U.S. branches and agencies of foreign banks, U.S. branches and agencies of foreign official banking institutions, and investment companies that are chartered under Article XII of the New York State banking law and are majority-owned by one or more foreign banks; and
 - (b) all other commercial banks in the U.S., i.e., U.S. branches of U.S. banks;
- (2) depository institutions in the U.S., other than commercial banks, including:
 - (a) credit unions:
 - (b) mutual or stock savings banks;
 - (c) savings or building and loan associations;
 - (d) cooperative banks; and
 - (e) other similar depository institutions; and
- (3) banks in foreign countries, including:
 - (a) foreign-domiciled branches of other U.S. banks; and
 - (b) <u>foreign</u>-domiciled branches of foreign banks.

See the Glossary entry for "banks, U.S. and foreign" and "depository institutions in the U.S." for further discussion of these terms.

<u>Include</u> as loans to depository institutions and acceptances of other banks:

- (1) Loans to depository institutions for the purpose of purchasing or carrying securities.
- (2) Loans to depository institutions for which the collateral is a mortgage instrument and not the underlying real property. Report loans to depository institutions where the collateral is the real estate itself, as evidenced by mortgages or similar liens, in Schedule RC-C, part I, item 1.
- (3) Purchases of mortgages and other loans under agreements to resell that do not involve the lending of immediately available funds <u>or</u> that mature in more than one business day, if acquired from depository institutions.
- (4) Loan participations acquired from depository institutions that must be treated as secured borrowings rather than sales in accordance with generally accepted accounting principles. (See the Glossary entry for "transfers of financial assets" for further information.)
- (5) The reporting bank's own acceptances discounted and held in its portfolio when the account party is another depository institution.

FFIEC 031 and 041 RC-C-6 RC-C - LOANS AND LEASES (3-01)

Item No. Caption and Instructions

2 Exclude from loans to depository institutions: (cont.)

(1) All transactions reportable in Schedule RC, item 3, "Federal funds sold and securities purchased under agreements to resell."

- (2) Loans secured by real estate, even if extended to depository institutions (report in Schedule RC-C, part I, item 1).
- (3) Loans to holding companies of depository institutions (report as all other loans in Schedule RC-C, part I, item 9).
- (4) Loans to real estate investment trusts and to mortgage companies that specialize in mortgage loan originations and warehousing or in mortgage loan servicing (report as all other loans in Schedule RC-C, part I, item 9).
- (5) Loans to finance companies and insurance companies (report as all other loans in Schedule RC-C, part I, item 9).
- (6) Loans to brokers and dealers in securities, investment companies, and mutual funds (report as loans for purchasing or carrying securities in Schedule RC-C, part I, item 9).
- (7) Loans to Small Business Investment Companies (report as all other loans in Schedule RC-C, part I, part I, item 9).
- (8) Loans to lenders other than brokers, dealers, and banks whose principal business is to extend credit for the purpose of purchasing or carrying securities (as described in Federal Reserve Regulation U) and loans to "plan lenders" (as defined in Federal Reserve Regulation G) (report as loans for purchasing or carrying securities in Schedule RC-C, part I, item 9).
- (9) Loans to federally-sponsored lending agencies (report as all other loans in Schedule RC-C, part I, item 9). Refer to the Glossary entry for "federally-sponsored lending agency" for the definition of this term.
- (10) Dollar exchange acceptances created by foreign governments and official institutions (report in Schedule RC-C, part I, item 7).
- (11) Loans to foreign governments and official institutions, including foreign central banks (report in Schedule RC-C, part I, item 7). See the Glossary entry for "foreign governments and official institutions" for the definition of this term.
- (12) Acceptances accepted by the reporting bank, discounted, and held in its portfolio, when the account party is not another depository institution. Report such acceptances are reported in other items of Schedule RC-C, part I, according to the account party.

FFIEC 031 and 041 RC-C-7 RC-C - LOANS AND LEASES (3-01)

Part I. (cont.)

Item No. Caption and Instructions

NOTE: Items 2.a through 2.c are <u>not</u> applicable to banks filing the FFIEC 041 report forms that have less than \$300 million in total assets.

2.a To commercial banks in the U.S. Report all loans to and acceptances of other commercial banks in the U.S. On the FFIEC 041, banks with \$300 million or more in total assets should report in the appropriate subitems of column A a breakdown of these loans and acceptances between those to U.S. branches and agencies of foreign banks and those to other commercial banks in the U.S. On the FFIEC 031, all banks should report the total amount of these loans and acceptances in domestic offices in column B, and a breakdown of these loans and acceptances for the fully consolidated bank between those to U.S. branches and agencies of foreign banks and those to other commercial banks in the U.S. in the appropriate subitems of column A.

Refer to the instruction to Schedule RC-C, part I, item 2, above, and to the Glossary entry for "banks, U.S. and foreign" for further discussion of the term "commercial banks in the U.S."

Exclude from Schedule RC-C, part I, items 2.a, 2.a.(1), and 2.a.(2), loans to other domestic depository institutions such as savings banks, savings and loan associations, and credit unions (report in Schedule RC-C, part I, item 2.b, below).

2.a.(1) To U.S. branches and agencies of foreign banks. Report in column A all loans to and acceptances of U.S. branches and agencies of foreign banks.

<u>Exclude</u> loans to U.S. offices of U.S.-chartered banks that are owned by foreign banks or by foreign official banking institutions (report in Schedule RC-C, part I, item 2.a.(2), below).

- **2.a.(2)** To other commercial banks in the U.S. Report in column A all loans to and acceptances of commercial banks in the U.S., other than U.S. branches and agencies of foreign banks.
- **To other depository institutions in the U.S.** Report (on the FFIEC 041, in column A; on the FFIEC 031, in columns A and B, as appropriate) loans to and acceptances of depository institutions, other than commercial banks, domiciled in the U.S. Refer to the instruction to Schedule RC-C, part I, item 2, above, and to the Glossary entry for "depository institutions in the U.S."

<u>Exclude</u> loans to and acceptances of commercial banks in the U.S. (report in Schedule RC-C, part I, item 2.a, above).

2.c To banks in foreign countries. Report all loans to and acceptances of banks and their branches domiciled outside the U.S. On the FFIEC 041, banks with \$300 million or more in total assets should report in the appropriate subitems of column A a breakdown of these loans and acceptances between those to foreign branches of other U.S. banks and those to other banks in foreign countries. On the FFIEC 031, all banks should report the total amount of these loans and acceptances in domestic offices in column B and a breakdown of these loans and acceptances for the fully consolidated bank between those to foreign branches of other U.S. banks and those to other banks in foreign countries in the appropriate subitems of column A.

FFIEC 031 and 041 RC-C-8 RC-C - LOANS AND LEASES (3-01)

Part I. (cont.)

Item No. **Caption and Instructions**

NOTE: Items 2.c, 2.c.(1), and 2.c.(2) are not applicable to banks filing the FFIEC 041 report forms that have less than \$300 million in total assets.

2.c See the instruction to Schedule RC-C, part I, item 2, above, and to the Glossary entry for (cont.) "banks, U.S. and foreign" for further discussion of the term "banks in foreign countries."

> Exclude loans to U.S. branches and agencies of foreign banks (report in Schedule RC-C, part I, item 2.a, above).

- 2.c.(1) To foreign branches of other U.S. banks. Report in column A all loans to and acceptances of foreign branches of other U.S. banks.
- To other banks in foreign countries. Report in column A all loans to and acceptances of 2.c.(2) banks in foreign countries, other than foreign-domiciled branches of other U.S. banks.
 - 3 Loans to finance agricultural production and other loans to farmers. On the FFIEC 041, report in column B and, on the FFIEC 031, report in columns A and B, as appropriate, loans for the purpose of financing agricultural production. Include such loans whether secured (other than by real estate) or unsecured and whether made to farm and ranch owners and operators (including tenants) or to nonfarmers. All other loans to farmers, other than those excluded below, should also be reported in this item.

<u>Include</u> as loans to finance agricultural production and other loans to farmers:

- (1) Loans and advances made for the purpose of financing agricultural production, including the growing and storing of crops, the marketing or carrying of agricultural products by the growers thereof, and the breeding, raising, fattening, or marketing of livestock.
- (2) Loans and advances made for the purpose of financing fisheries and forestries, including loans to commercial fishermen.
- (3) Agricultural notes and other notes of farmers that the bank has discounted for, or purchased from, merchants and dealers, either with or without recourse to the seller.
- (4) Loans to farmers that are guaranteed by the Farmers Home Administration (FmHA) or by the Small Business Administration (SBA) and that are extended, serviced, and collected by a party other than the FmHA or SBA.
- (5) Loans and advances to farmers for purchases of farm machinery, equipment, and implements.
- (6) Loans and advances to farmers for all other purposes associated with the maintenance or operations of the farm, including purchases of private passenger automobiles and other retail consumer goods and provisions for the living expenses of farmers or ranchers and their families.

Loans to farmers for household, family, and other personal expenditures (including credit cards) that are not readily identifiable as being made to farmers need not be broken out of Schedule RC-C, part I, item 6, for inclusion in this item.

FFIEC 031 and 041 **RC-C - LOANS AND LEASES** RC-C-9

Part I. (cont.)

Item No. Caption and Instructions

- **3** Exclude from loans to finance agricultural production and other loans to farmers: (cont.)
 - (1) Loans secured by real estate (report in Schedule RC-C, part I, item 1).
 - (2) Loans to farmers for commercial and industrial purposes, e.g., when a farmer is operating a business enterprise as well as a farm (report in Schedule RC-C, part I, item 4).
 - (3) Loans to farmers for the purpose of purchasing or carrying securities (report in Schedule RC-C, part I, item 9).
 - (4) Loans to farmers secured by oil or mining production payments (report in Schedule RC-C, part I, item 4).
 - Commercial and industrial loans. Report loans for commercial and industrial purposes to sole proprietorships, partnerships, corporations, and other business enterprises, whether secured (other than by real estate) or unsecured, single-payment or installment. On the FFIEC 041, all banks should report the total of these loans in column B, and banks with \$300 million or more in total assets should also report in the appropriate subitems of column A a breakdown of these loans between those loans to U.S. and non-U.S. addressees. On the FFIEC 031, all banks should report a breakdown of these loans between those to U.S. and non-U.S. addressees for the fully consolidated bank in the appropriate subitems of column A and for domestic offices in the appropriate subitems of column B.

Commercial and industrial loans may take the form of direct or purchased loans. Include loans to individuals for commercial, industrial, and professional purposes but not for investment or personal expenditure purposes. Also include the reporting bank's own acceptances that it holds in its portfolio when the account party is a commercial or industrial enterprise. Exclude all commercial and industrial loans held for trading.

<u>Include</u> loans of the types listed below as commercial and industrial loans. These descriptions may overlap and are not all inclusive.

- (1) Loans for commercial, industrial, and professional purposes to:
 - (a) mining, oil- and gas-producing, and quarrying companies;
 - (b) manufacturing companies of all kinds, including those which process agricultural commodities;
 - (c) construction companies;
 - (d) transportation and communications companies and public utilities;
 - (e) wholesale and retail trade enterprises and other dealers in commodities:
 - (f) cooperative associations including farmers' cooperatives;
 - (g) service enterprises such as hotels, motels, laundries, automotive service stations, and nursing homes and hospitals operated for profit;
 - (h) insurance agents; and
 - (i) practitioners of law, medicine, and public accounting.
- (2) Loans for the purpose of financing capital expenditures and current operations.
- (3) Loans to business enterprises guaranteed by the Small Business Administration.

FFIEC 031 and 041 RC-C-10 RC-C - LOANS AND LEASES (3-01)

Part I. (cont.)

Item No. Caption and Instructions

4 (4) Loans to farmers for commercial and industrial purposes (when farmers operate a business enterprise as well as a farm).

- (5) Loans supported by letters of commitment from the Agency for International Development.
- (6) Loans made to finance construction that are not secured by real estate.
- (7) Loans to merchants or dealers on their own promissory notes secured by the pledge of their own installment paper.
- (8) Loans extended under credit cards and related plans that are readily identifiable as being issued in the name of a commercial or industrial enterprise.
- (9) Dealer flooring or floor-plan loans.
- (10) Loans collateralized by production payments (e.g., oil or mining production payments). Treat as a loan to the original seller of the production payment rather than to the holder of the production payment. For example, report in this item, as a loan to an oil company, a loan made to a nonprofit organization collateralized by an oil production payment; do not include in Schedule RC-C, part I, item 9, as a loan to the nonprofit organization.
- (11) Loans and participations in loans secured by conditional sales contracts made to finance the purchase of commercial transportation equipment.
- (12) Commercial and industrial loans guaranteed by foreign governmental institutions.
- (13) Overnight lending for commercial and industrial purposes.

Exclude from commercial and industrial loans:

- (1) Loans secured by real estate, even if for commercial and industrial purposes (report in Schedule RC-C, part I, item 1).
- (2) Loans to depository institutions (report in Schedule RC-C, part I, item 2).
- (3) Loans to nondepository financial institutions such as real estate investment trusts, mortgage companies, and insurance companies (report as all other loans in Schedule RC-C, part I, item 9).
- (4) Loans for the purpose of purchasing or carrying securities (report in Schedule RC-C, part I, item 9).
- (5) Loans for the purpose of financing agricultural production, whether made to farmers or to nonagricultural businesses (report in Schedule RC-C, part I, item 3).
- (6) Loans to nonprofit organizations, such as hospitals or educational institutions (report as all other loans in Schedule RC-C, part I, item 9), except those for which oil or mining production payments serve as collateral which are to be reported in this item.

FFIEC 031 and 041 RC-C-11 RC-C - LOANS AND LEASES (3-01)

Part I. (cont.)

Item No. **Caption and Instructions**

4 Holdings of acceptances accepted by other banks (report in Schedule RC-C, part I, (cont.) item 2).

- Holdings of the bank's own acceptances when the account party is another bank (report in Schedule RC-C, part I, item 2) or a foreign government or official institution (report in Schedule RC-C, part I, item 7).
- Equipment trust certificates (report in Schedule RC-B, item 6, "Other debt securities").
- (10) Any commercial or industrial loans held by the reporting bank for trading purposes (report in Schedule RC, item 5, "Trading assets").
- (11) Commercial paper (report in Schedule RC-B, item 5, "Asset-backed securities," or item 6, "Other debt securities," or in Schedule RC, item 5, "Trading assets," as appropriate).

NOTE: Items 4.a and 4.b are not applicable to banks filing the FFIEC 041 report forms that have less than \$300 million in total assets.

- To U.S. addressees (domicile). Report (on the FFIEC 041, in column A; on the FFIEC 031, 4.a in columns A and B, as appropriate) all commercial and industrial loans to U.S. addressees. For a detailed discussion of U.S. and non-U.S. addressees, see the Glossary entry for "domicile."
- 4.b To non-U.S. addressees (domicile). Report (on the FFIEC 041, in column A; on the FFIEC 031, in columns A and B, as appropriate) all commercial and industrial loans to non-U.S. addressees. For a detailed discussion of U.S. and non-U.S. addressees, see the Glossary entry for "domicile."
- Not applicable. 5
- 6 Loans to individuals for household, family, and other personal expenditures. Report in the appropriate subitem all credit extended to individuals for household, family, and other personal expenditures that are not secured by real estate, whether direct loans or purchased paper. Exclude loans to individuals for the purpose of purchasing or carrying securities (report in Schedule RC-C, part I, item 9).

Deposits accumulated by borrowers for the payment of personal loans (i.e., hypothecated deposits) should be netted against the related loans.

Credit cards. Report (on the FFIEC 041, in column B; on the FFIEC 031, in columns A 6.a and B, as appropriate) all extensions of credit to individuals for household, family, and other personal expenditures arising from credit cards. Report the total amount outstanding of all funds advanced under these credit cards regardless of whether there is a period before interest charges are made. Report only amounts carried on the books of the reporting bank as loans that are outstanding on the report date, even if the plan is shared with other banks or organizations and even if accounting and billing are done by a correspondent bank or the accounting center of a plan administered by others.

FFIEC 031 and 041 RC-C-12 **RC-C - LOANS AND LEASES**

Part I. (cont.)

Item No. **Caption and Instructions**

If the reporting bank has securitized credit cards and has retained a seller's interest that is not 6.a in the form of a security, the carrying value of the seller's interest should be reported as credit (cont.) card loans in this item. For purposes of these reports, the term "seller's interest" means the reporting bank's ownership interest in loans that have been securitized, except an interest that is a form of recourse or other seller-provided credit enhancement. Seller's interests differ from the securities issued to investors by the securitization structure. The principal amount of a seller's interest is generally equal to the total principal amount of the pool of assets included in the securitization structure less the principal amount of those assets attributable to investors, i.e., in the form of securities issued to investors.

> Do not net credit balances resulting from overpayments of account balances on credit card accounts against the debit balances of other credit card accounts. Report credit balances (in domestic offices) in Schedule RC-E, (part I,) item 1, column A, and item 7, column B. On the FFIEC 031, report credit balances in foreign offices in Schedule RC-E, part II, item 1.

Exclude from credit cards:

- (1) Credit extended under credit card plans to business enterprises (report in Schedule RC-C, part I, item 4, "Commercial and industrial loans").
- (2) All credit extended to individuals through credit cards secured by real estate (report in Schedule RC-C, part I, item 1).
- (3) All credit extended to individuals for household, family, and other personal expenditures under prearranged overdraft plans (report in Schedule RC-C, part I, item 6.b).

If the bank acts only as agent or correspondent for other banks or nonbank corporations and carries no credit card plan assets on its books, enter a "zero" or the word "none." Banks that do not participate in any credit card plan should also enter a zero or the word "none."

Other revolving credit plans. Report (on the FFIEC 041, in column B; on the FFIEC 031, in 6.b columns A and B, as appropriate) all extensions of credit to individuals for household, family, and other personal expenditures arising from prearranged overdraft plans and other revolving credit plans not accessed by credit cards. Report the total amount outstanding of all funds advanced under these revolving credit plans regardless of whether there is a period before interest charges are made.

> Do not net credit balances resulting from overpayments of account balances on other revolving credit plan accounts against the debit balances of other revolving credit plan accounts. Report credit balances (in domestic offices) in Schedule RC-E, (part I,) item 1, column A, and item 7, column B. On the FFIEC 031, report credit balances in foreign offices in Schedule RC-E, part II, item 1.

Exclude from other revolving credit plans:

- (1) All ordinary (unplanned) overdrafts on transaction accounts not associated with revolving credit plans (report in other items of Schedule RC-C, part I, as appropriate).
- (2) Credit extended to individuals for household, family, and other personal expenditures arising from credit cards (report in Schedule RC-C, part I, item 6.a).

FFIEC 031 and 041 **RC-C-13 RC-C - LOANS AND LEASES**

Part I. (cont.)

Item No. Caption and Instructions

Other consumer loans. Report (on the FFIEC 041, in column B; on the FFIEC 031, in columns A and B, as appropriate) all other loans to individuals for household, family, and other personal expenditures (other than those secured by real estate and other than those for purchasing or carrying securities). Include loans for such purposes as:

- (1) purchases of private passenger automobiles, pickup trucks, household appliances, furniture, trailers, and boats;
- (2) repairs or improvements to the borrower's residence (not secured by real estate);
- (3) educational expenses, including student loans;
- (4) medical expenses;
- (5) personal taxes;
- (6) vacations:
- (7) consolidation of personal (nonbusiness) debts;
- (8) purchases of real estate or mobile homes (not secured by real estate) to be used as a residence by the borrower's family; and
- (9) other personal expenditures.

Other consumer loans may take the form of:

- (1) Installment loans, demand loans, single payment time loans, and hire purchase contracts, and should be reported as loans to individuals for household, family, and other personal expenditures regardless of size or maturity and regardless of whether the loans are made by the consumer loan department or by any other department of the bank.
- (2) Retail installment sales paper purchased by the bank from merchants or dealers, finance companies, and others.

Exclude from other consumer loans:

- (1) All direct and purchased loans, regardless of purpose, secured by real estate as evidenced by mortgages, deeds of trust, land contracts, or other instruments, whether first or junior liens (e.g., equity loans, second mortgages), on real estate (report in Schedule RC-C, part I, item 1).
- (2) Loans to individuals not secured by real estate for the purpose of investing in real estate when the real estate is not to be used as a residence or vacation home by the borrower or by members of the borrower's family (report as all other loans in Schedule RC-C, part I, item 9).
- (3) Loans to individuals for commercial, industrial, and professional purposes and for "floor plan" or other wholesale financing (report in Schedule RC-C, part I, item 4).
- (4) Loans to individuals for the purpose of purchasing or carrying securities (report in Schedule RC-C, part I, item 9).
- (5) Loans to individuals for investment (as distinct from commercial, industrial, or professional) purposes other than those for purchasing or carrying securities (report as all other loans in Schedule RC-C, part I, item 9).

FFIEC 031 and 041 RC-C-14 RC-C - LOANS AND LEASES (3-01)

Part I. (cont.)

Item No. **Caption and Instructions**

6.c (cont.)

- (6) Loans to merchants, automobile dealers, and finance companies on their own promissory notes, secured by the pledge of installment paper or similar instruments (report in Schedule RC-C, part I, item 4, or as all other loans in Schedule RC-C, part I, item 9, as appropriate).
- (7) Loans to farmers, regardless of purpose, to the extent that can be readily identified as such loans (report in Schedule RC-C, part I, item 3).
- (8) All credit extended to individuals for household, family, and other personal expenditures arising from:
 - (a) Credit cards (report in Schedule RC-C, part I, item 6.a), and
 - (b) Prearranged overdraft plans (report in Schedule RC-C, part I, item 6.b).
- 7 Loans to foreign governments and official institutions. Report (on the FFIEC 041, in column B; on the FFIEC 031, in columns A and B, as appropriate) all loans (other than those secured by real estate), including planned and unplanned overdrafts, to governments in foreign countries, to their official institutions, and to international and regional institutions. See the Glossary entry for "foreign governments and official institutions" for the definition of this term.

Include:

- (1) Bankers acceptances accepted by the reporting bank and held in its portfolio when the account party is a foreign government or official institution, including such acceptances for the purpose of financing dollar exchange. Exclude acceptances that are held for trading.
- (2) Loans to foreign governments, their official institutions, and international and regional institutions (other than those secured by real estate), including planned and unplanned overdrafts.

Exclude from loans to foreign governments and official institutions:

- (1) Loans to nationalized banks and other banking institutions owned by foreign governments and not functioning as central banks, banks of issue, or development banks (report in Schedule RC-C, part I, item 2, "Loans to depository institutions and acceptances of other banks").
- (2) Loans to U.S. branches and agencies of foreign official banking institutions (report in Schedule RC-C, part I, item 2).
- (3) Loans to foreign-government-owned nonbank corporations and enterprises (report in Schedule RC-C, part I, item 4 or 9, as appropriate).

FFIEC 031 and 041 RC-C-15 **RC-C - LOANS AND LEASES**

Part I. (cont.)

Item No. Caption and Instructions

Obligations (other than securities and leases) of states and political subdivisions in the U.S. Report (on the FFIEC 041, in column B; on the FFIEC 031, in columns A and B, as appropriate) all obligations of states and political subdivisions in the United States (including overdrafts and obligations secured by real estate), other than leases and obligations reported as securities. (Report leases to states and political subdivisions in the U.S. in Schedule RC-C, part I, item 10, and securities issued by such entities in Schedule RC-B, item 3, "Securities issued by states and political subdivisions in the U.S.," or item 4, "Mortgage-backed securities," as appropriate.) Exclude all such obligations held for trading.

States and political subdivisions in the U.S. include:

- (1) the fifty States of the United States and the District of Columbia and their counties, municipalities, school districts, irrigation districts, and drainage and sewer districts; and
- (2) the governments of Puerto Rico and of the U.S. territories and possessions and their political subdivisions.

Treatment of industrial development bonds (IDBs). Industrial development bonds (IDBs), sometimes referred to as "industrial revenue bonds," are issued under the auspices of states or political subdivisions for the benefit of a private party or enterprise where that party or enterprise, rather than the government entity, is obligated to pay the principal and interest on the obligation. For purposes of these reports, all IDBs should be reported as securities in Schedule RC-B, item 3, or as loans in this item (Schedule RC-C, part I, item 8), consistent with the asset category in which the bank reports IDBs on its balance sheet for other financial reporting purposes. Regardless of whether they are reported as securities in Schedule RC-B or as loans in Schedule RC-C, part I, all IDBs that meet the definition of a "security" in FASB Statement No. 115 must be measured in accordance with Statement No. 115.

Treatment of other obligations of states and political subdivisions in the U.S. In addition to those IDBs that are reported in this item in accordance with the preceding paragraph, also include in this item all obligations (other than securities) of states and political subdivisions in the U.S. except those that meet any of the following criteria:

- (1) Industrial development bonds (IDBs) that are reported as securities in accordance with the reporting treatment described above (report as securities in Schedule RC, item 2, and Schedule RC-B, item 3).
- (2) Notes, bonds, and debentures (including tax warrants and tax-anticipation notes) which are rated by a nationally-recognized rating service (report as securities in Schedule RC, item 2, and Schedule RC-B, item 3).
- (3) Mortgage-backed securities issued by state and local housing authorities (report as securities in Schedule RC, item 2, and Schedule RC-B, item 4).
- (4) Obligations of state and local governments that are guaranteed by the United States Government (report as securities in Schedule RC, item 2, and Schedule RC-B, item 3).

FFIEC 031 and 041 RC-C-16 RC-C - LOANS AND LEASES (3-01)

Part I. (cont.)

Item No. Caption and Instructions

8 (5) Nonrated obligations of states and political subdivisions in the U.S. that the bank (cont.) considers securities for other financial reporting purposes (report as securities in Schedule RC, item 2, and Schedule RC-B, item 3).

- (6) Lease financing receivables of states and political subdivisions in the U.S. (report as leases in Schedule RC-C, part I, item 10).
- (7) Obligations of states and political subdivisions in the U.S. held by the reporting bank for trading purposes (report in Schedule RC, item 5).
- Other loans. Report all loans for purchasing or carrying securities and all other loans that cannot properly be reported in one of the preceding items in this schedule. On the FFIEC 041, all banks should report the total amount of these loans in column B, and banks with \$300 million or more in total assets should also report in the appropriate subitem of column A loans for purchasing or carrying securities (item 9.a) and all other loans (item 9.b). On the FFIEC 031, all banks should report the total amount of these loans for the fully consolidated bank in column A, but with a breakdown between loans for purchasing or carrying securities (item 9.a) and all other loans (item 9.b) for domestic offices in column B.

Loans for purchasing or carrying securities include:

- (1) <u>All</u> loans to brokers and dealers in securities (other than those secured by real estate and those to depository institutions).
- (2) All loans, whether secured (other than by real estate) or unsecured, to any other borrower for the purpose of purchasing or carrying securities, such as:
 - (a) Loans made to provide funds to pay for the purchase of securities at settlement date.
 - (b) Loans made to provide funds to repay indebtedness incurred in purchasing securities.
 - (c) Loans that represent the renewal of loans to purchase or carry securities.
 - (d) Loans to investment companies and mutual funds, but <u>excluding</u> loans to Small Business Investment Companies.
 - (e) Loans to "plan lenders" as defined in Section 221.4(a) of Federal Reserve Regulation U .
 - (f) Loans to lenders other than brokers, dealers, and banks whose principal business is to extend credit for the purpose of purchasing or carrying securities as described in Section 221.3(q) of Federal Reserve Regulation U, unless the loan is excepted by that section.
 - (g) Loans to Employee Stock Ownership Plans (ESOPs).

FFIEC 031 and 041 RC-C-17 RC-C - LOANS AND LEASES (3-01)

Part I. (cont.)

Item No. Caption and Instructions

9 For purposes of the Report of Condition, the purpose of a loan collateralized by "stock" is determined as follows:

- (1) For loans that are collateralized in whole or in part by "margin stock," as defined by Federal Reserve Regulation U, the purpose of the loan is determined by the latest Statement of Purpose (Form FR U-1) on file.
- (2) For loans that are collateralized by "stock" other than "margin stock," the bank may determine the purpose of the loan according to the most current information available.

Exclude from loans for purchasing or carrying securities:

- (1) Loans to banks in foreign countries that act as brokers and dealers in securities (report in Schedule RC-C, part I, item 2).
- (2) Loans to depository institutions for the purpose of purchasing or carrying securities (report Schedule RC-C, part I, item 2).
- (3) Transactions reportable in Schedule RC, item 3, "Federal funds sold and securities purchased under agreements to resell."
- (4) Loans secured by real estate (report in Schedule RC-C, part I, item 1).

<u>All other loans</u> include all loans and discounts (other than loans for purchasing or carrying securities) that cannot properly be reported in one of the preceding items in Schedule RC-C, part I, such as:

- (1) Unplanned overdrafts to deposit accounts (except overdrafts of depository institutions, which are to be reported in Schedule RC-C, part I, item 2; overdrafts of foreign governments and official institutions, which are to be reported in Schedule RC-C, part I, item 7; and overdrafts of states and political subdivisions in the U.S., which are to be reported in Schedule RC-C, part I, item 8).
- (2) Loans (other than those secured by real estate) to nonprofit organizations (e.g., churches, hospitals, educational and charitable institutions, clubs, and similar associations) except those collateralized by production payments where the proceeds ultimately go to a commercial or industrial organization (which are to be reported in Schedule RC-C, part I, item 4).
- (3) Loans to individuals for investment purposes (as distinct from commercial, industrial, or professional purposes), other than those secured by real estate.
- (4) Loans (other than those secured by real estate) to real estate investment trusts and to mortgage companies that specialize in mortgage loan originations and warehousing or in mortgage loan servicing. (Exclude outright purchases of mortgages or similar instruments by the bank from such companies, which are to be reported in Schedule RC-C, part I, item 1.)

FFIEC 031 and 041 RC-C-18 RC-C - LOANS AND LEASES (3-01)

Part I. (cont.)

Item No. Caption and Instructions

9 (5) Loans to holding companies of other depository institutions. (cont.)

- (6) Loans to insurance companies.
- (7) Loans to finance companies, mortgage finance companies, factors and other financial intermediaries, short-term business credit institutions that extend credit to finance inventories or carry accounts receivable, and institutions whose functions are predominantly to finance personal expenditures (exclude loans to financial corporations whose sole function is to borrow money and relend it to its affiliated companies or a corporate joint venture in which an affiliated company is a joint venturer).
- (8) Loans to federally-sponsored lending agencies (see the Glossary entry for "federally-sponsored lending agency" for the definition of this term).
- (9) Loans to investment banks.
- (10) Loans and advances made to the bank's own trust department.
- (11) Loans to other domestic and foreign financial intermediaries whose functions are predominantly the extending of credit for business purposes, such as investment companies that hold stock of operating companies for management or development purposes.
- (12) Loans to Small Business Investment Companies.

Exclude from all other loans extensions of credit initially made in the form of planned or "advance agreement" overdrafts other than those made to borrowers of the types whose obligations are specifically reportable in this item (report such planned overdrafts in other items of Schedule RC-C, part I, as appropriate). For example, report advances to banks in foreign countries in the form of "advance agreement" overdrafts as loans to depository institutions in Schedule RC-C, part I, item 2, and overdrafts under consumer check-credit plans as "Other revolving credit plans" to individuals in Schedule RC-C, part I, item 6.b. Report both planned and unplanned overdrafts on "due to" deposit accounts of depository institutions in Schedule RC-C, part I, item 2.

NOTE: Items 9.a and 9.b are not applicable to banks filing the FFIEC 041 report forms that have less than \$300 million in total assets.

- **9.a** Loans for purchasing or carrying securities. Report (on the FFIEC 041, in column A; on the FFIEC 031, in column B) all loans for purchasing or carrying securities (on the FFIEC 031, in domestic offices) as described above.
- **9.b** All other loans. Report (on the FFIEC 041, in column A; on the FFIEC 031, in column B) all other loans (on the FFIEC 031, in domestic offices) as described above.

FFIEC 031 and 041 RC-C-19 RC-C - LOANS AND LEASES (3-01)

Part I. (cont.)

Item No. **Caption and Instructions**

10 Lease financing receivables (net of unearned income). Report all outstanding receivable balances relating to direct financing and leveraged leases on property acquired by the bank for leasing purposes. On the FFIEC 041, all banks should report the total amount of these balances in column B, and banks with \$300 million or more in total assets should also report in the appropriate subitems of column A a breakdown of these balances between those of U.S. and non-U.S. addressees. On the FFIEC 031, all banks should report the total amount of these balances in domestic offices in column B and a breakdown of these balances for the fully consolidated bank between those of U.S. and non-U.S. addressees in column A. These balances should include the estimated residual value of leased property and must be net of unearned income. For further discussion of leases where the bank is the lessor, refer to the Glossary entry for "lease accounting."

<u>Include</u> all leases to states and political subdivisions in the U.S. in this item.

NOTE: Items 10.a and 10.b are not applicable to banks filing the FFIEC 041 report forms that have less than \$300 million total assets.

- 10.a Of U.S. addressees (domicile). Report in column A all outstanding receivable balances relating to direct financing and leveraged leases on property acquired by the fully consolidated bank for leasing to U.S. addressees (see the Glossary entry for "domicile").
- 10.b Of non-U.S. addressees (domicile). Report in column A all outstanding receivable balances relating to direct financing and leveraged leases on property acquired by the fully consolidated bank for leasing to non-U.S. addressees (see the Glossary entry for "domicile").
- 11 LESS: Any unearned income on loans reflected in items 1-9 above. To the extent possible, the preferred treatment is to report the specific loan categories net of unearned income. A reporting bank should enter (on the FFIEC 041, in column B; on the FFIEC 031, in columns A and B, as appropriate) unearned income only to the extent that it is included in (i.e., not deducted from) the various loan items of this schedule (Schedule RC-C, part I, items 1 through 9). If a bank reports each loan item of this schedule net of unearned income, enter a zero or the word "none" in this item.

Do not include unearned income on lease financing receivables in this item. Leases should be reported net of unearned income in Schedule RC-C, part I, item 10.

Total loans and leases, net of unearned income. Report (on the FFIEC 041, in column B; 12 on the FFIEC 031, in columns A and B, as appropriate) the sum of items 1 through 10 less the amount reported in item 11. The amount reported for this item (on the FFIEC 041, in column B; on the FFIEC 031, in column A) must equal Schedule RC, item 4.a plus item 4.b.

FFIEC 031 and 041 **RC-C-20 RC-C - LOANS AND LEASES**

Part I. (cont.)

Memoranda

Item No. **Caption and Instructions**

1 Loans and leases restructured and in compliance with modified terms. Report loans and leases that have been restructured and are in compliance with their modified terms. However, exclude from this item all restructured loans secured by 1-to-4 family residential properties and all restructured loans to individuals for household, family, and other personal expenditures.

For purposes of this item, restructured loans and leases are those loans and leases whose terms have been modified, because of a deterioration in the financial condition of the borrower, to provide for a reduction of either interest or principal, regardless of whether such loans and leases are secured or unsecured, regardless of whether such credits are quaranteed by the government or by others, and (except as noted in the following paragraph) regardless of the effective interest rate on such credits.

Once an obligation has been restructured because of such credit problems, it continues to be considered restructured until paid in full. However, a restructured obligation that is in compliance with its modified terms and yields a market rate (i.e., the recorded amount of the obligation bears an effective interest rate that at the time of the restructuring is greater than or equal to the rate that the bank is willing to accept for a new extension of credit with comparable risk) need not continue to be reported as a troubled debt restructuring in this Memorandum item in calendar years after the year in which the restructuring took place. A loan extended or renewed at a stated interest rate equal to the current interest rate for new debt with similar risk is not considered a restructured loan. Also, a loan to a purchaser of "other real estate owned" by the reporting bank for the purpose of facilitating the disposal of such real estate is not considered a restructured loan. For further information, see the Glossary entry for "troubled debt restructurings."

Include in this item all restructured loans and leases as defined above that are in compliance with their modified terms, that is, restructured loans and leases (1) on which no contractual payments of principal or interest scheduled under the modified repayment terms are due and unpaid or (2) on which contractual payments of both principal and interest scheduled under the modified repayment terms are less than 30 days past due.

Exclude from this item (1) those restructured loans and leases on which under the modified repayment terms either principal or interest is 30 days or more past due (report in Schedule RC-N, column A or B, as appropriate) and (2) those restructured loans and leases that are in nonaccrual status under the modified repayment terms (report in Schedule RC-N, column C).

Loan amounts should be reported net of unearned income to the extent that they are reported net of unearned income in Schedule RC-C, part I. All lease amounts must be reported net of unearned income.

FFIEC 031 and 041 RC-C-21 **RC-C - LOANS AND LEASES**

Part I. (cont.)

Memoranda

Item No. **Caption and Instructions**

2 Maturity and repricing data for loans and leases (excluding those in nonaccrual status). Report in the appropriate subitem maturity and repricing data for the bank's loans and leases. Loans and leases are to be reported in this Memorandum item regardless of whether they are current or are reported as "past due and still accruing" in Schedule RC-N, columns A and B. However, exclude those loans and leases that are reported as "nonaccrual" in Schedule RC-N. column C.

> The sum of Memorandum items 2.a.(1) through 2.b.(6) plus total nonaccrual loans and leases from Schedule RC-N, sum of items 1 through 8, column C, must equal Schedule RC-C, sum of items 1 through 10.

> On the FFIEC 031, banks that have more than one office in foreign countries (including offices of consolidated foreign subsidiaries but excluding "shell" branches, excluding offices in Puerto Rico or U.S. territories and possessions, and excluding IBFs) have the option of excluding the smallest of such non-U.S. offices from Memorandum item 2. Such banks may omit the smallest of their offices in foreign countries (other than "shell" branches) when arrayed by total assets provided that the assets of the excluded offices do not exceed 50 percent of the total assets of the bank's offices (excluding "shells") in foreign countries and do not exceed 10 percent of the total consolidated assets of the reporting bank as of the report date. (Note: In determining the total assets of offices in foreign countries eligible for exclusion from these memorandum items, banks should exclude not only "shell" branches but also offices in Puerto Rico and U.S. territories and possessions, domestic offices of Edge and Agreement subsidiaries, and IBFs even though these are sometimes referred to as "foreign" offices. Also, the asset totals for all offices in foreign countries should be the component of the total consolidated assets, i.e., should exclude all intrabank transactions.)

For purposes of this memorandum item, the following definitions apply:

A fixed interest rate is a rate that is specified at the origination of the transaction, is fixed and invariable during the term of the loan or lease, and is known to both the borrower and the lender. Also treated as a fixed interest rate is a predetermined interest rate which is a rate that changes during the term of the loan on a predetermined basis, with the exact rate of interest over the life of the loan known with certainty to both the borrower and the lender when the loan is acquired. Examples of predetermined-rate transactions are: (1) Loans that carry a specified interest rate, for, say, six months and thereafter carry a rate equal to a specific percentage over the initial rate. (2) Loans that carry a specified interest rate while the loan amount is below a certain threshold amount but carry a different specified rate above that threshold (e.g., a line of credit where the interest rate is 10% when the unpaid balance of amounts advanced is \$100,000 or less, and 8% when the unpaid balance is more than \$100,000).

A floating rate is a rate that varies, or can vary, in relation to an index, to some other interest rate such as the rate on certain U.S. Government securities or the bank's "prime rate." or to some other variable criterion the exact value of which cannot be known in advance. Therefore, the exact rate the loan carries at any subsequent time cannot be known at the time of origination.

FFIEC 031 and 041 **RC-C-22 RC-C - LOANS AND LEASES**

Part I. (cont.)

Memoranda

Item No. **Caption and Instructions**

2 When the rate on a loan with a floating rate has reached a contractual floor or ceiling level, the loan is to be treated as "fixed rate" rather than as "floating rate" until the rate is again (cont.) free to float.

> Remaining maturity is the amount of time remaining from the report date until the final contractual maturity of a loan or lease without regard to the loan's or lease's repayment schedule, if any.

Next repricing date is the date the interest the rate on a floating rate loan can next change in accordance with the terms of the contract (without regard to the loan's repayment schedule, if any, or expected prepayments) or the contractual maturity date of the loan, whichever is earlier.

Banks whose records or information systems provide data on the final contractual maturities and next repricing dates of their loans and leases for time periods that closely approximate the maturity and repricing periods specified in Memorandum items 2.a through 2.c (e.g., 89 or 90 days rather than three months, 359 or 360 days rather than 12 months) may use these data to complete Memorandum items 2.a through 2.c.

For loans and leases with scheduled contractual payments, banks whose records or information systems provide repricing data that take into account these scheduled contractual payments, with or without the effect of anticipated prepayments, may adjust these data in an appropriate manner to derive reasonable estimates for the final contractual maturities of fixed rate loans and leases (and floating rate loans for purposes of Memorandum item 2.c) and the next repricing dates of floating rate loans.

Loan amounts should be reported net of unearned income to the extent that they have been reported net of unearned income in Schedule RC-C, part I, items 1 through 9. Leases must be reported net of unearned income.

Fixed rate loans and leases that are past due (with respect to principal or interest) and still accruing should be reported according to the time remaining to final contractual maturity without regard to delinquency status. Floating rate loans that are past due (with respect to principal or interest) and still accruing should be reported according to their next repricing date without regard to delinquency status.

Report all unplanned overdrafts as fixed rate loans with a remaining maturity of three months or less in Memorandum item 2.b.(1).

Report all leases, net of unearned income, as fixed rate instruments in Memorandum item 2.b according to the amount of time remaining to final contractual maturity without regard to repayment schedules.

FFIEC 031 and 041 **RC-C - LOANS AND LEASES RC-C-23**

Part I. (cont.)

Memoranda

Item No. **Caption and Instructions**

2 Report fixed rate and floating rate loans made solely on a demand basis (i.e., without an (cont.) alternate maturity date or without repayment terms) as having a remaining maturity or next repricing date of three months or less in Memorandum items 2.a.(1) and 2.b.(1), as appropriate. In addition, report all fixed rate and floating rate loans made solely on a

> Fixed rate demand loans that have an alternate maturity date or repayment terms are to be reported in this Memorandum item according to the amount of time remaining to the alternate maturity date or final payment due date. Floating rate demand loans that have an alternate maturity date or repayment terms are to be reported according to their next repricing date in Memorandum items 2.a and 2.b, as appropriate. In addition, fixed rate and floating rate demand loans for which the amount of time remaining to the alternate maturity date or final payment due date is one year or less are to be reported in Memorandum item 2.c.

demand basis as having a remaining maturity of one year or less in Memorandum item 2.c.

Fixed rate "Credit cards" and "Other revolving credit plans" are considered to have a remaining maturity of over one year through three years and should be reported in Memorandum item 2.b.(3), regardless of the actual maturity experience or expectation. Floating rate "Credit cards" and "Other revolving credit plans" (e.g., where the rate varies, or can be varied, periodically) are to be reported in Memorandum item 2.b according to their next repricing date. Where the bank in its contract with the borrower simply reserves the right to change the interest rate on the "Credit card" or "Other revolving credit," the plan should be considered to have a fixed rate.

Student loans whose interest rate is adjusted periodically by the U.S. Government by means of interest payments that include an amount of "additional interest" should be treated as floating rate loans and should be reported in Memorandum item 2.b according to their next repricing date.

Fixed rate loans that are held by the bank for sale and delivery in the secondary market under the terms of a binding commitment should be reported in Memorandum item 2.a or 2.b. as appropriate, on the basis of the time remaining until the delivery date specified in the commitment. Floating rate loans that are held by the bank for sale and delivery in the secondary market under the terms of a binding commitment should be reported in Memorandum item 2.a or 2.b, as appropriate, based on the date the interest rates on the loans can next change or the delivery date specified in the commitment, whichever is earlier.

2.a Closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) with a remaining maturity or next repricing date of. Report the dollar amount of the bank's fixed rate closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) in the appropriate subitems according to the amount of time remaining to their final contractual maturities (without regard to repayment schedules, if any). Report the dollar amount of the bank's floating rate closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) in the appropriate subitems according to their next repricing date. Exclude loans that are in nonaccrual status.

FFIEC 031 and 041 RC-C-24 **RC-C - LOANS AND LEASES**

Part I. (cont.)

Memoranda

Item No. **Caption and Instructions**

2.a.(1) **Three months or less.** Report the amount of:

- the bank's fixed rate closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) with remaining maturities of three months or less, and
- the bank's floating rate closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) with next repricing dates occurring in three months or less.

2.a.(2) Over three months through 12 months. Report the amount of:

- the bank's fixed rate closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) with remaining maturities (without regard to repayment schedules, if any) of over three months through 12 months, and
- the bank's floating rate closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) with next repricing dates occurring in over three months through 12 months.

2.a.(3) Over one year through three years. Report the amount of:

- the bank's fixed rate closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) with remaining maturities (without regard to repayment schedules, if any) of over one year through three years, and
- the bank's floating rate closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) with next repricing dates occurring in over one year through three years.

Over three years through five years. Report the amount of: 2.a.(4)

- the bank's fixed rate closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) with remaining maturities (without regard to repayment schedules, if any) of over three years through five years, and
- the bank's floating rate closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) with next repricing dates occurring in over three years through five years.

Over five years through 15 years. Report the amount of: 2.a.(5)

- the bank's fixed rate closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) with remaining maturities (without regard to repayment schedules, if any) of over five years through 15 years, and
- the bank's floating rate closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) with next repricing dates occurring in over five years through 15 years.

FFIEC 031 and 041 RC-C-25 **RC-C - LOANS AND LEASES**

Part I. (cont.)

Memoranda

Item No. **Caption and Instructions**

2.a.(6) **Over 15 years.** Report the amount of:

- the bank's fixed rate closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) with remaining maturities (without regard to repayment schedules, if any) of over 15 years, and
- the bank's floating rate closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) with next repricing dates occurring in over 15 years.
- 2.b All loans and leases other than closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) with a remaining maturity or next repricing date of. Report the dollar amount of the bank's fixed rate loans and leases - other than closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) -- in the appropriate subitems according to the amount of time remaining to their final contractual maturities (without regard to repayment schedules, if any). Report the dollar amount of the bank's floating rate loans -- other than closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) -- in the appropriate subitems according to their next repricing date. Exclude loans that are in nonaccrual status.

2.b.(1) Three months or less. Report the amount of:

- the bank's fixed rate loans and leases -- other than closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) -- with remaining maturities of three months or less, and
- the bank's floating rate loans -- other than closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) - with next repricing dates occurring in three months or less.

2.b.(2) Over three months through 12 months. Report the amount of:

- the bank's fixed rate loans and leases -- other than closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) -- with remaining maturities (without regard to repayment schedules, if any) of over three months through 12 months, and
- the bank's floating rate loans -- other than closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) - with next repricing dates occurring in over three months through 12 months.

FFIEC 031 and 041 **RC-C-26 RC-C - LOANS AND LEASES**

Part I. (cont.)

Memoranda

Item No. **Caption and Instructions**

2.b.(3)Over one vear through three vears. Report the amount of:

- the bank's fixed rate loans and leases -- other than closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) -- with remaining maturities (without regard to repayment schedules, if any) of over one year through three years, and
- the bank's floating rate loans -- other than closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) - with next repricing dates occurring in over one year through three years.

2.b.(4) Over three years through five years. Report the amount of:

- the bank's fixed rate loans and leases -- other than closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) -- with remaining maturities (without regard to repayment schedules, if any) of over three years through five years, and
- the bank's floating rate loans -- other than closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) – with next repricing dates occurring in over three years through five years.

2.b.(5) Over five years through 15 years. Report the amount of:

- the bank's fixed rate loans and leases -- other than closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) -- with remaining maturities (without regard to repayment schedules, if any) of over five years through 15 years, and
- the bank's floating rate loans -- other than closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) – with next repricing dates occurring in over five years through 15 years.

2.b.(6) **Over 15 years.** Report the amount of:

- the bank's fixed rate loans and leases -- other than closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) -- with remaining maturities (without regard to repayment schedules, if any) of over 15 years, and
- the bank's floating rate loans -- other than closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) – with next repricing dates occurring in over 15 years.

FFIEC 031 and 041 **RC-C-27 RC-C - LOANS AND LEASES**

Part I. (cont.)

Memoranda

Item No. **Caption and Instructions**

2.c Loans and leases with a remaining maturity of one year or less. Report all loans and leases with a remaining maturity of one year or less. Include both fixed rate and floating rate loans and leases.

> The fixed rate loans and leases that should be included in this item will also have been reported by remaining maturity in Schedule RC-C, part I, Memorandum items 2.a.(1), 2.a.(2), 2.b.(1), and 2.b.(2), above. The floating rate loans that should be included in this item will have been reported by next repricing date in Memorandum items 2.a.(1), 2.a.(2), 2.b.(1), and 2.b.(2), above. However, these four Memorandum items may include floating rate loans with a remaining maturity of more than one year, but on which the interest rate can next change in one year or less; those loans should not be included in this Memorandum item 2.c.

3 Loans to finance commercial real estate, construction, and land development activities (not secured by real estate) included in Schedule RC-C, part I, items 4 and 9. Report in this item loans to finance commercial and residential real estate activities, e.g., acquiring, developing, and renovating commercial and residential real estate, that are reported in Schedule RC-C, part I, items 4, "Commercial and industrial loans," and 9, "Other loans" (column B on the FFIEC 041; column A on the FFIEC 031).

Such loans generally may include:

- (1) loans made for the express purpose of financing real estate ventures as evidenced by loan documentation or other circumstances connected with the loan; or
- (2) loans made to organizations or individuals 80 percent of whose revenue or assets are derived from or consist of real estate ventures or holdings.

Exclude from this item all loans secured by real estate that are reported in Schedule RC-C, part I, item 1. Also exclude loans to commercial and industrial firms where the sole purpose for the loan is to construct a factory or office building to house the company's operations or employees.

Adjustable rate closed-end loans secured by first liens on 1-4 family residential 4 properties. Report the amount of closed-end loans secured by first liens on 1-4 family residential properties (in domestic offices) included in Schedule RC-C, part I, item 1.c.(2)(a), column B, that have a floating or adjustable interest rate.

> A floating or adjustable rate is a rate that varies, or can vary, in relation to an index, to some other interest rate such as the rate on certain U.S. Government securities, or to some other variable criterion the exact value of which cannot be known in advance. Therefore, the exact rate the loan carries at any subsequent time cannot be known at the time of origination. For purposes of this item, even if the rate on a loan with a floating or adjustable rate can no longer float because it has reached a floor or ceiling level, the loan is to be reported in this item as an adjustable rate loan.

Also include in this item amortizing fixed rate loans secured by first liens on 1-4 family residential properties that have original maturities of one year or less and require a balloon payment at maturity.

FFIEC 031 and 041 **RC-C-28 RC-C - LOANS AND LEASES**

Part I. (cont.)

Memoranda

Item No. Caption and Instructions

NOTE: Memorandum item 5 is <u>not</u> applicable to banks filing the FFIEC 041 report forms that have less than 300 million in total assets.

Loans secured by real estate to non-U.S. addressees (domicile). Report the amount of loans secured by real estate to non-U.S. addressees that are included in Schedule RC-C, part I, items 1.a through 1.e, column B, on the FFIEC 041; item 1, column A, on the FFIEC 031. For a detailed discussion of U.S. and non-U.S. addressees, see the Glossary entry for "domicile."

FFIEC 031 and 041 RC-C-29 RC-C - LOANS AND LEASES

Schedule RC-C. Part II. Loans to Small Businesses and Small Farms

General Instructions

Schedule RC-C, part II, is to be completed only with the June 30 Report of Condition.

Schedule RC-C, part II, requests information on the number and amount currently outstanding of "loans to small businesses" and "loans to small farms," as defined below. This information is being collected pursuant to Section 122 of the Federal Deposit Insurance Corporation Improvement Act of 1991.

For purposes of this schedule, "loans to small businesses" consist of the following:

- (1) Loans with original amounts of \$1 million or less that have been reported in Schedule RC-C, part I, item 1.e, column B, "Loans secured by nonfarm nonresidential properties" (in domestic offices), and
- (2) Loans with original amounts of \$1 million or less that have been reported in Schedule RC-C, part I:
 - On the FFIEC 041 for banks with less than \$300 million in total assets, item 4, column B,
 "Commercial and industrial loans;"
 - On the FFIEC 041 for banks with \$300 million or more in total assets, item 4.a, "Commercial and industrial loans to U.S. addressees;" and
 - On the FFIEC 031, item 4.a, column B, "Commercial and industrial loans to U.S. addressees" in domestic offices.

For purposes of this schedule, "loans to small farms" consist of the following:

- (1) Loans with original amounts of \$500,000 or less that have been reported in Schedule RC-C, part I, item 1.b, column B, "Loans secured by farmland (including farm residential and other improvements)" (in domestic offices), and
- (2) Loans with original amounts of \$500,000 or less that have been reported in Schedule RC-C, part I, item 3, column B, "Loans to finance agricultural production and other loans to farmers" (in domestic offices).

The following guidelines should be used to determine the "original amount" of a loan:

- (1) For loans drawn down under lines of credit or loan commitments, the "original amount" of the loan is the size of the line of credit or loan commitment when the line of credit or loan commitment was most recently approved, extended, or renewed prior to the report date. However, if the amount currently outstanding as of the report date exceeds this size, the "original amount" is the amount currently outstanding on the report date.
- (2) For loan participations and syndications, the "original amount" of the loan participation or syndication is the entire amount of the credit originated by the lead lender.
- (3) For all other loans, the "original amount" is the total amount of the loan at origination or the amount currently outstanding as of the report date, whichever is larger.

The "amount currently outstanding" for a loan is its carrying value, i.e., the amount at which the loan is reported in Schedule RC-C, part I, item 1.b, 1.e, 3, 4, or 4.a.

General Instructions (cont.)

Except as noted below for "corporate" or "business" credit card programs, when determining "original amounts" and reporting the number and amount currently outstanding for a category of loans in this part II, multiple loans to one borrower should be combined and reported on an aggregate basis rather than as separate individual loans to the extent that the loan systems in which the bank's business and/or farm loan data are maintained can provide aggregate individual borrower data without undue cost to the reporting institution. However, if the burden of such aggregation would be excessive, the institution may report multiple loans to one borrower as separate individual loans.

A bank that offers "corporate" or "business" credit card programs under which credit cards are issued to one or more of a company's employees for business-related use should treat each company's program as a single extension of credit to that company. The credit limits for all of the individual credit cards issued to the company's employees should be totaled and this total should be treated as the "original amount" of the "corporate" or "business" credit card program established for this company. The company's program should be reported as one loan and the amount currently outstanding would be the sum of the credit card balances as of the June 30 report date on each of the individual credit cards issued to the company's employees. However, when aggregated data for each individual company in a "corporate" or "business" credit card program are not readily determinable from the bank's credit card records, the bank should develop reasonable estimates of the number of "corporate" or "business" credit card programs in existence as of the June 30 report date, the "original amounts" of these programs, and the "amounts currently outstanding" for these programs and should then report information about these programs on the basis of its reasonable estimates. In no case should the individual credit cards issued to a company's employees under a "corporate" or "business" credit card program be reported as separate individual loans to small businesses.

Item Instructions

Loans to Small Businesses

Item No. Caption and Instructions

- Indicate in the appropriate box at the right whether all or substantially all of the dollar volume of your bank's "Loans secured by nonfarm nonresidential properties" (in domestic offices) reported in Schedule RC-C, part I, item 1.e, and all or substantially all of the dollar volume of your bank's "Commercial and industrial loans (to U.S. addressees)" (in domestic offices) reported in Schedule RC-C, part I, item 4 (or 4.a), have original amounts of \$100,000 or less.
 - If: (a) the average size of the amount currently outstanding for your bank's "Loans secured by nonfarm nonresidential properties" (in domestic offices) as reported in Schedule RC-C, part I, above, is \$100,000 or less, and
 - (b) the average size of the amount currently outstanding for your bank's "Commercial and industrial loans (to U.S. addressees)" (in domestic offices) as reported in Schedule RC-C, part I, above, is \$100,000 or less, and

Item No. Caption and Instructions

1 (cont.) (c) your lending officers' knowledge of your bank's loans or other relevant information pertaining to "Loans secured by nonfarm nonresidential properties" (in domestic offices) and "Commercial and industrial loans (to U.S. addressees)" (in domestic offices) indicates that all or substantially all of the dollar volume of your bank's loans in each of these two categories has "original amounts" (as described above in the General Instructions to this part II) of \$100,000 or less,

place an "X" in the box marked "YES," complete items 2.a and 2.b below, skip items 3 and 4, and go to item 5.

If your bank has <u>no</u> loans outstanding in <u>both</u> of these two loan categories, place an "X" in the box marked "NO," skip items 2 through 4, and go to item 5.

Otherwise, place an "X" in the box marked "NO," skip items 2.a and 2.b, complete items 3 and 4 below, and go to item 5.

- Report the total number of loans currently outstanding for each of the following Schedule RC-C, part I, loan categories. Multiple loans to one borrower should be combined and reported on an aggregate basis rather than as separate individual loans to the extent that the loan systems in which the bank's business and/or farm loan data are maintained can provide aggregate individual borrower data without undue cost to the reporting institution. However, if the burden of such aggregation would be excessive, the institution may report multiple loans to one borrower as separate individual loans.
- 2.a Number of "Loans secured by nonfarm nonresidential properties" (in domestic offices) reported in Schedule RC-C, part I, item 1.e. Count the number of individual loans currently outstanding whose carrying values add up to the amount reported in Schedule RC-C, part I, item 1.e, column B, "Loans secured by nonfarm nonresidential properties" (in domestic offices). The amount reported in Schedule RC-C, part I, item 1.e, column B, divided by the number of loans reported in this item should not exceed \$100,000.
- 2.b Number of "Commercial and industrial loans (to U.S. addressees)" (in domestic offices) reported in Schedule RC-C, part I, item 4 (or 4.a). Count the number of individual loans currently outstanding whose carrying values add up to the amount reported in Schedule RC-C, part I:
 - On the FFIEC 041 for banks with less than \$300 million in total assets, item 4, column B, "Commercial and industrial loans:"
 - On the FFIEC 041 for banks with \$300 million or more in total assets, item 4.a, "Commercial and industrial loans to U.S. addressees;" and
 - On the FFIEC 031, item 4.a, column B, "Commercial and industrial loans to U.S. addressees" in domestic offices.

The amount reported in Schedule RC-C, part I, item 4 or 4.a, as appropriate, divided by the number of loans reported in this item should not exceed \$100,000.

Item No. Caption and Instructions

Number and amount currently outstanding of "Loans secured by nonfarm nonresidential properties" (in domestic offices) reported in Schedule RC-C, part I, item 1.e, column B. See the General Instructions to this part II for the guidelines for determining the "original amount" of a loan. Multiple loans to one borrower should be combined and reported on an aggregate basis rather than as separate individual loans to the extent that the loan systems in which the bank's business and/or farm loan data are maintained can provide aggregate individual borrower data without undue cost to the reporting institution. However, if the burden of such aggregation would be excessive, the institution may report multiple loans to one borrower as separate individual loans.

The sum of the amounts currently outstanding reported in items 3.a through 3.c, column B, must be less than or equal to the amount reported in Schedule RC-C, part I, item 1.e, column B.

3.a With original amounts of \$100,000 or less. Add up the total carrying value of all currently outstanding "Loans secured by nonfarm nonresidential properties" (in domestic offices) with "original amounts" of \$100,000 or less and report this total amount in column B. Do not add up the "original amounts" of each of these loans and report the total original amount in column B.

Count the number of individual "Loans secured by nonfarm nonresidential properties" (in domestic offices) whose carrying values were included in the amount reported in column B for this item (i.e., those "Loans secured by nonfarm nonresidential properties" (in domestic offices) with "original amounts" of \$100,000 or less). Report this number in column A.

3.b With original amounts of more than \$100,000 through \$250,000. Add up the total carrying value of all currently outstanding "Loans secured by nonfarm nonresidential properties" (in domestic offices) with "original amounts" of more than \$100,000 through \$250,000 and report this total amount in column B. Do not add up the "original amounts" of each of these loans and report the total original amount in column B.

Count the number of individual "Loans secured by nonfarm nonresidential properties" (in domestic offices) whose carrying values were included in the amount reported in column B for this item (i.e., those "Loans secured by nonfarm nonresidential properties" (in domestic offices) with "original amounts" of more than \$100,000 through \$250,000). Report this number in column A.

3.c With original amounts of more than \$250,000 through \$1,000,000. Add up the total carrying value of all currently outstanding "Loans secured by nonfarm nonresidential properties" (in domestic offices) with "original amounts" of more than \$250,000 through \$1,000,000 and report this total amount in column B. Do not add up the "original amounts" of each of these loans and report the total original amount in column B.

Count the number of individual "Loans secured by nonfarm nonresidential properties" (in domestic offices) whose carrying values were included in the amount reported in column B for this item (i.e., those "Loans secured by nonfarm nonresidential properties" (in domestic offices) with "original amounts" of more than \$250,000 through \$1,000,000). Report this number in column A.

Item No. Caption and Instructions

Number and amount currently outstanding of "Commercial and industrial loans (to U.S. addressees)" (in domestic offices) reported in Schedule RC-C, part I, item 4 (or 4.a). See the General Instructions to this part II for the guidelines for determining the "original amount" of a loan and for the treatment of "corporate" or "business" credit card programs. Multiple loans to one borrower should be combined and reported on an aggregate basis rather than as separate individual loans to the extent that the loan systems in which the bank's business and/or farm loan data are maintained can provide aggregate individual borrower data without undue cost to the reporting institution. However, if the burden of such aggregation would be excessive, the institution may report multiple loans to one borrower as separate individual loans.

The sum of the amounts currently outstanding reported in items 4.a through 4.c, column B, must be less than or equal to the amount reported in Schedule RC-C, part I:

- On the FFIEC 041 for banks with less than \$300 million in total assets, item 4, column B,
 "Commercial and industrial loans:"
- On the FFIEC 041 for banks with \$300 million or more in total assets, item 4.a,
 "Commercial and industrial loans to U.S. addressees;" and
- On the FFIEC 031, item 4.a, column B, "Commercial and industrial loans to U.S. addressees" in domestic offices.
- **4.a** With original amounts of \$100,000 or less. Add up the total carrying value of all currently outstanding "Commercial and industrial loans (to U.S. addressees)" (in domestic offices) with "original amounts" of \$100,000 or less and report this total amount in column B. Do <u>not</u> add up the "original amounts" of each of these loans and report the total original amount in column B.

Count the number of individual "Commercial and industrial loans (to U.S. addressees)" (in domestic offices) whose carrying values were included in the amount reported in column B for this item (i.e., those "Commercial and industrial loans (to U.S. addressees)" (in domestic offices) with "original amounts" of \$100,000 or less). Report this number in column A.

4.b With original amounts of more than \$100,000 through \$250,000. Add up the total carrying value of all currently outstanding "Commercial and industrial loans (to U.S. addressees)" (in domestic offices) with "original amounts" of more than \$100,000 through \$250,000 and report this total amount in column B. Do not add up the "original amounts" of each of these loans and report the total original amount in column B.

Count the number of individual "Commercial and industrial loans (to U.S. addressees)" (in domestic offices) whose carrying values were included in the amount reported in column B for this item (i.e., those "Commercial and industrial loans (to U.S. addressees)" (in domestic offices) with "original amounts" of more than \$100,000 through \$250,000). Report this number in column A.

Item No. Caption and Instructions

4.c With original amounts of more than \$250,000 through \$1,000,000. Add up the total carrying value of all currently outstanding "Commercial and industrial loans (to U.S. addressees)" (in domestic offices) with "original amounts" of more than \$250,000 through \$1,000,000 and report this total amount in column B. Do not add up the "original amounts" of each of these loans and report the total original amount in column B.

Count the number of individual "Commercial and industrial loans (to U.S. addressees)" (in domestic offices) whose carrying values were included in the amount reported in column B for this item (i.e., those "Commercial and industrial loans (to U.S. addressees)" (in domestic offices) with "original amounts" of more than \$250,000 through \$1,000,000). Report this number in column A.

Agricultural Loans to Small Farms

Item No. Caption and Instructions

- Indicate in the appropriate box at the right whether all or substantially all of the dollar volume of your bank's "Loans secured by farmland (including farm residential and other improvements)" (in domestic offices) reported in Schedule RC-C, part I, item 1.b, column B, and all or substantially all of the dollar volume of your bank's "Loans to finance agricultural production and other loans to farmers" (in domestic offices) reported in Schedule RC-C, part I, item 3, column B, have original amounts of \$100,000 or less.
 - If: (a) the average size of the amount currently outstanding for your bank's "Loans secured by farmland (including farm residential and other improvements)" (in domestic offices) as reported in Schedule RC-C, part I, above, is \$100,000 or less, and
 - (b) the average size of the amount currently outstanding for your bank's "Loans to finance agricultural production and other loans to farmers" (in domestic offices) as reported in Schedule RC-C, part I, above, is \$100,000 or less, and
 - (c) your lending officers' knowledge of your bank's loans or other relevant information pertaining to "Loans secured by farmland (including farm residential and other improvements" (in domestic offices) and your "Loans to finance agricultural production and other loans to farmers" (in domestic offices) indicates that all or substantially all of the dollar volume of your bank's loans in <u>each</u> of these two categories has "original amounts" (as described above in the General Instructions to this part II) of \$100,000 or less,

place an "X" in the box marked "YES," complete items 6.a and 6.b below, and do not complete items 7 and 8 below.

If your bank has <u>no</u> loans outstanding in <u>both</u> of these two loan categories, place an "X" in the box marked "NO," and do not complete items 6 through 8.

Otherwise, place an "X" in the box marked "NO," skip items 6.a and 6.b, and complete items 7 and 8 below.

Item No. Caption and Instructions

- Report the total number of loans currently outstanding for each of the following Schedule RC-C, part I, loan categories. Multiple loans to one borrower should be combined and reported on an aggregate basis rather than as separate individual loans to the extent that the loan systems in which the bank's business and/or farm loan data are maintained can provide aggregate individual borrower data without undue cost to the reporting institution. However, if the burden of such aggregation would be excessive, the institution may report multiple loans to one borrower as separate individual loans.
- Number of "Loans secured by farmland (including farm residential and other improvements)" (in domestic offices) reported in Schedule RC-C, part I, item 1.b, column B. Count the number of individual loans currently outstanding whose carrying values add up to the amount reported in Schedule RC-C, part I, item 1.b, column B, "Loans secured by farmland (including farm residential and other improvements)" (in domestic offices). The amount reported in Schedule RC-C, part I, item 1.b, column B, divided by the number of loans reported in this item should not exceed \$100,000.
- 6.b Number of "Loans to finance agricultural production and other loans to farmers" (in domestic offices) reported in Schedule RC-C, part I, item 3, column B. Count the number of individual loans currently outstanding whose carrying values add up to the amount reported in Schedule RC-C, part I, item 3, column B, "Loans to finance agricultural production and other loans to farmers" (in domestic offices). The amount reported in Schedule RC-C, part I, item 3, column B, divided by the number of loans reported in this item should not exceed \$100,000.
- Number and amount currently outstanding of "Loans secured by farmland (including farm residential and other improvements)" (in domestic offices) reported in Schedule RC-C, part I, item 1.b, column B. See the General Instructions to this part II for the guidelines for determining the "original amount" of a loan. Multiple loans to one borrower should be combined and reported on an aggregate basis rather than as separate individual loans to the extent that the loan systems in which the bank's business and/or farm loan data are maintained can provide aggregate individual borrower data without undue cost to the reporting institution. However, if the burden of such aggregation would be excessive, the institution may report multiple loans to one borrower as separate individual loans.

The sum of the amounts currently outstanding reported in items 7.a through 7.c, column B, must be less than or equal to the amount reported Schedule RC-C, part I, item 1.b, column B.

7.a With original amounts of \$100,000 or less. Add up the total carrying value of all currently outstanding "Loans secured by farmland (including farm residential and other improvements)" (in domestic offices) with "original amounts" of \$100,000 or less and report this total amount in column B. Do not add up the "original amounts" of each of these loans and report the total original amount in column B.

Count the number of individual "Loans secured by farmland (including farm residential and other improvements" (in domestic offices) whose carrying values were included in the amount reported in column B for this item (i.e., those "Loans secured by farmland (including farm residential and other improvements)" (in domestic offices) with "original amounts" of \$100,000 or less). Report this number in column A.

Item No. Caption and Instructions

7.b With original amounts of more than \$100,000 through \$250,000. Add up the total carrying value of all currently outstanding "Loans secured by farmland (including farm residential and other improvements" (in domestic offices) with "original amounts" of more than \$100,000 through \$250,000 and report this total amount in column B. Do not add up the "original amounts" of each of these loans and report the total original amount in column B.

Count the number of individual "Loans secured by farmland (including farm residential and other improvements)" (in domestic offices) whose carrying values were included in the amount reported in column B for this item (i.e., those "Loans secured by farmland (including farm residential and other improvements)" (in domestic offices) with "original amounts" of more than \$100,000 through \$250,000). Report this number in column A.

7.c With original amounts of more than \$250,000 through \$500,000. Add up the total carrying value of all currently outstanding "Loans secured by farmland (including farm residential and other improvements)" (in domestic offices) with "original amounts" of more than \$250,000 through \$500,000 and report this total amount in column B. Do not add up the "original amounts" of each of these loans and report the total original amount in column B.

Count the number of individual "Loans secured by farmland (including farm residential and other improvements)" (in domestic offices) whose carrying values were included in the amount reported in column B for this item (i.e., those "Loans secured by farmland (including farm residential and other improvements)" (in domestic offices) with "original amounts" of more than \$250,000 through \$500,000). Report this number in column A.

Number and amount currently outstanding of "Loans to finance agricultural production and other loans to farmers" (in domestic offices) reported in Schedule RC-C, part I, item 3, column B. See the General Instructions to this part II for the guidelines for determining the "original amount" of a loan. Multiple loans to one borrower should be combined and reported on an aggregate basis rather than as separate individual loans to the extent that the loan systems in which the bank's business and/or farm loan data are maintained can provide aggregate individual borrower data without undue cost to the reporting institution. However, if the burden of such aggregation would be excessive, the institution may report multiple loans to one borrower as separate individual loans.

The sum of the amounts currently outstanding reported in items 8.a through 8.c, column B, must be less than or equal to the amount reported in Schedule RC-C, part I, item 3, column B.

8.aWith original amounts of \$100,000 or less. Add up the total carrying value of all currently outstanding "Loans to finance agricultural production and other loans to farmers" (in domestic offices) with "original amounts" of \$100,000 or less and report this total amount in column B. Do not add up the "original amounts" of each of these loans and report the total original amount in column B.

Count the number of individual "Loans to finance agricultural production and other loans to farmers" (in domestic offices) whose carrying values were included in the amount reported in column B for this item (i.e., those "Loans to finance agricultural production and other loans to farmers" (in domestic offices) with "original amounts" of \$100,000 or less). Report this number in column A.

Item No. Caption and Instructions

8.b With original amounts of more than \$100,000 through \$250,000. Add up the total carrying value of all currently outstanding "Loans to finance agricultural production and other loans to farmers" (in domestic offices) with "original amounts" of more than \$100,000 through \$250,000 and report this total amount in column B. Do not add up the "original amounts" of each of these loans and report the total original amount in column B.

Count the number of individual "Loans to finance agricultural production and other loans to farmers" (in domestic offices) whose carrying values were included in the amount reported in column B for this item (i.e., those "Loans to finance agricultural production and other loans to farmers" (in domestic offices) with "original amounts" of more than \$100,000 through \$250,000). Report this number in column A.

8.c With original amounts of more than \$250,000 through \$500,000. Add up the total carrying value of all currently outstanding "Loans to finance agricultural production and other loans to farmers" (in domestic offices) with "original amounts" of more than \$250,000 through \$500,000 and report this total amount in column B. Do not add up the "original amounts" of each of these loans and report the total original amount in column B.

Count the number of individual "Loans to finance agricultural production and other loans to farmers" (in domestic offices) whose carrying values were included in the amount reported in column B for this item (i.e., those "Loans to finance agricultural production and other loans to farmers" (in domestic offices) with "original amounts" of more than \$250,000 through \$500,000). Report this number in column A.

Examples of Reporting in Schedule RC-C, Part II

- (1) A bank has a "Loan secured by nonfarm nonresidential property" which has a carrying value on the June 30 report date of \$70,000 and this amount is included in Schedule RC-C, part I, item 1.e, column B. The bank made this loan to the borrower in the original amount of \$75,000, so it would be considered a "loan to a small business" and would be reported in Schedule RC-C, part II. Because the original amount of the loan is \$100,000 or less, the bank would report the \$70,000 amount currently outstanding in part II, item 3.a, column B.
- (2) The bank has a second "Loan secured by nonfarm nonresidential property" which has a carrying value on the June 30 report date of \$60,000 and this amount is included in Schedule RC-C, part I, item 1.e, column B. The bank made this loan to the borrower in the original amount of \$125,000, so it would be considered a "loan to a small business" and would be reported in Schedule RC-C, part II. Because the original amount of the loan falls within the more than \$100,000 through \$250,000 range, the bank would report the \$60,000 amount currently outstanding in part II, item 3.b, column B.
- (3) The bank has a "Commercial and industrial loan" (to a U.S. addressee in a domestic office) which has a carrying value on the June 30 report date of \$200,000 and this amount is included in Schedule RC-C, part I, item 4 or 4.a, as appropriate. The bank made this loan to the borrower in the original amount of \$250,000, so it would be considered a "loan to a small business" and would be reported in Schedule RC-C, part II. Because the original amount of the loan is exactly \$250,000 which is the upper end of the more than \$100,000 through \$250,000 range, the bank would report the \$200,000 amount currently outstanding in part II, item 4.b, column B.

Examples of Reporting in Schedule RC-C, Part II (cont.)

- (4) The bank has a second "Commercial and industrial loan" (to a U.S. addressee in a domestic office) which has a carrying value on the June 30 report date of \$90,000 and this amount is included in Schedule RC-C, part I, item 4 or 4.a, as appropriate. The bank made this loan to the borrower in the original amount of \$500,000 and sold loan participations for \$400,000 while retaining \$100,000. Nevertheless, based on the entire amount of the credit that was originated by the bank, the loan would be considered a "loan to a small business" and would be reported in Schedule RC-C, part II. Because the original amount of the entire loan is \$500,000 which falls within the more than \$250,000 through \$1,000,000 range, the bank would report the \$90,000 amount currently outstanding in part II, item 4.c, column B.
- (5) The bank has a third "Commercial and industrial loan" (to a U.S. addressee in a domestic office) which has a carrying value on the June 30 report date of \$55,000 and this amount is included in Schedule RC-C, part I, item 4 or 4.a, as appropriate. This loan represents a participation purchased by the bank from another lender. The original amount of the entire credit is \$750,000 and the bank's original share of this credit was \$75,000. Based on the entire amount of the credit that was originated by the other lender, the loan would be considered a "loan to a small business" and would be reported in Schedule RC-C, part II. Because the original amount of the entire credit is \$750,000 which falls within the more than \$250,000 through \$1,000,000 range, the bank would report the \$55,000 amount currently outstanding in part II, item 4.c, column B.
- (6) The bank has another "Commercial and industrial loan" (to a U.S. addressee in a domestic office) and it has a carrying value on the June 30 report date of \$120,000. This amount is included in Schedule RC-C, part I, item 4 or 4.a, as appropriate. This loan represents a participation purchased by the bank from another lender. The original amount of the entire credit is \$1,250,000 and the bank's original share of this credit was \$250,000. Because the original amount of the entire credit exceeds \$1,000,000, the loan would not be considered a "loan to a small business" and would not be reported in Schedule RC-C, part II.
- (7) The bank has a "Loan secured by nonfarm nonresidential property" and a "Commercial and industrial loan" to the same (U.S. addressee) borrower (in its domestic offices). The first loan has a carrying value on the June 30 report date of \$375,000 and this amount is included in Schedule RC-C, part I, item 1.e, column B. This "Loan secured by nonfarm nonresidential property" was made in the original amount of \$400,000. The second loan has a carrying value on the June 30 report date of \$650,000 and this amount is included in Schedule RC-C, part I, item 4 or 4.a, as appropriate. This "Commercial and industrial loan" was made in the original amount of \$750,000.

Case I: The bank's loan system <u>can provide</u> aggregate individual borrower data without undue cost to the reporting institution. The loan system indicates that this borrower's two loans have a combined original amount of \$1,150,000 and therefore the loans would <u>not</u> be considered "loans to a small business" and would <u>not</u> be reported in Schedule RC-C, part II.

Case II: The bank's loan system <u>cannot provide</u> aggregate individual borrower data without undue cost to the reporting institution. Therefore, the borrower's two loans would be treated as separate loans for purposes of Schedule RC-C, part II. Based on its \$400,000 original amount, the "Loan secured by nonfarm nonresidential property" would be considered a "loan to a small business" and would be reported in Schedule RC-C, part II. Because the original amount of the loan falls within the more than \$250,000 through \$1,000,000 range, the bank would report the \$375,000 amount currently outstanding in part II, item 3.c, column B, and count this loan as <u>one</u> loan for purposes of part II, item 3.c, column A. Since the "Commercial and industrial loan" is being handled separately and its original amount is \$750,000, it would also be considered a "loan to a small business" and

Examples of Reporting in Schedule RC-C, Part II (cont.)

would be reported in Schedule RC-C, part II. Because the original amount of this loan falls within the more than \$250,000 through \$1,000,000 range, the bank would report the \$650,000 amount currently outstanding in part II, item 4.c, column B, and count this loan as <u>one</u> loan for purposes of part II, item 4.c, column A.

(8) The bank has a "Loan secured by farmland (including farm residential and other improvements)" which has a carrying value on the June 30 report date of \$225,000. The bank made this loan to the borrower in the original amount of \$260,000 and the loan is secured by a first lien on the borrower's farmland. The bank has a second "Loan secured by farmland" to this same borrower and it is secured by a second lien on the borrower's property. This second lien loan has a carrying value of \$50,000 and the original amount of the loan is the same as its carrying value. The carrying values of both loans (the \$225,000 first lien loan and the \$50,000 second lien loan) are included in Schedule RC-C, part I, item 1.b, column B.

Case I: The bank's loan system <u>can provide</u> aggregate individual borrower data without undue cost to the reporting institution. The loan system indicates that this borrower's two loans have a combined original amount of \$310,000 and therefore the two loans together would be considered a single "loan to a small farm" and would be reported in Schedule RC-C, part II. Because the original amount of the two combined loans falls within the more than \$250,000 through \$500,000 range, the bank would report the \$275,000 combined total of the amounts currently outstanding for the two loans in part II, item 7.c, column B, and count these two loans to the same borrower as <u>one</u> loan for purposes of part II, item 7.c, column A.

Case II: The bank's loan system <u>cannot provide</u> aggregate individual borrower data without undue cost to the reporting institution. Therefore, the borrower's two loans would be treated as separate loans for purposes of Schedule RC-C, part II. Based on its \$260,000 original amount, the first lien loan would be considered a "loan to a small farm" and would be reported in Schedule RC-C, part II. Because the original amount of the loan falls within the more than \$250,000 through \$500,000 range, the bank would report the \$225,000 amount currently outstanding in part II, item 7.c, column B, and count this loan as <u>one</u> loan for purposes of part II, item 7.c, column A. Since the second lien loan is being handled separately and its original amount is \$50,000, it would also be considered a "loan to a small farm" and would be reported in Schedule RC-C, part II. Because the original amount of this loan is less than \$100,000, the bank would report the \$50,000 amount currently outstanding in part II, item 7.a, column B, and count this loan as <u>one</u> loan for purposes of part II, item 7.a, column A.

- (9) The bank has one final "Loan secured by farmland" which has a carrying value on the June 30 report date of \$5,000 and this amount is included in Schedule RC-C, part I, item 1.b, column B. The bank made this loan to the borrower in the original amount of \$300,000, so it would be considered a "loan to a small farm" and would be reported in Schedule RC-C, part II. Because the original amount of the loan falls within the more than \$250,000 through \$500,000 range, the bank would report the \$5,000 amount currently outstanding in part II, item 7.c, column B.
- (10) The bank has granted a \$150,000 line of credit to a farmer that is not secured by real estate. The farmer has received advances twice under this line of credit and, rather than having signed a single note for the entire \$150,000 amount of the line of credit, has signed separate notes for each advance. One note is in the original amount of \$30,000 and the other is in the original amount of \$50,000. The carrying values of the two notes on the June 30 report date are the same as their original amounts and these amounts are included in Schedule RC-C, part I, item 3, column B. For loans drawn down under lines of credit, the original amount of the loan is the size of the line of credit when it was most recently approved, extended, or renewed prior to the report date. In this case, the line of credit was most recently approved for \$150,000.

Examples of Reporting in Schedule RC-C, Part II (cont.)

Case I: The bank's loan system <u>can provide</u> aggregate individual borrower data for multiple advances under lines of credit without undue cost to the reporting institution. Thus, even though a separate note was signed each time the farmer borrowed under the line of credit, the loan system combines all information about the farmer's separate borrowings under the line of credit. Therefore, the loan system indicates that the farmer has a line of credit for \$150,000 and that the amount currently outstanding under the line of credit for the combined carrying values of the two borrowings under the line of credit is \$80,000. Because the line of credit was most recently approved for \$150,000, this \$150,000 original amount for the line of credit would be considered a "loan to a small farm" that would be reported in Schedule RC-C, part II. Therefore, the original amount of the line of credit falls within the more than \$100,000 through \$250,000 range and the bank would report the \$80,000 combined total of the amounts currently outstanding for the two notes in part II, item 8.b, column B, and count these two notes to the farmer under the line of credit as <u>one</u> loan for purposes of part II, item 8.b, column A.

Case II: The bank's loan system <u>cannot provide</u> aggregate individual borrower data for lines of credit without undue cost to the reporting institution. Therefore, the farmer's two notes under the line of credit would be treated as separate loans for purposes of Schedule RC-C, part II. The original amount of the line of credit is \$150,000 and each of the two notes would be considered a "loan to a small farm" that would be reported in Schedule RC-C, part II. Because each of the two notes indicates that it is part of a \$150,000 line of credit and the \$150,000 original amount of the line of credit falls within the more than \$100,000 through \$250,000 range, the bank would report both the \$30,000 and \$50,000 amounts currently outstanding in part II, item 8.b, column B, and count these as two loans for purposes of part II, item 8.b, column A.

(11) The bank has one other "Loan to finance agricultural production and other loans to a farmer" which has a carrying value on the June 30 report date of \$75,000 and this amount is included in Schedule RC-C, part I, item 3, column B. The bank made this loan to the borrower in the original amount of \$100,000, so it would be considered a "loan to a small farm" and would be reported in Schedule RC-C, part II. Because the original amount of the loan is exactly \$100,000 which is the upper end of the \$100,000 or less range, the bank would report the \$75,000 amount currently outstanding in part II, item 8.a, column B.

FFIEC 031 and 041 RC-D - TRADING

SCHEDULE RC-D - TRADING ASSETS AND LIABILITIES

General Instructions

Schedule RC-D is to be completed by banks that reported a quarterly average for trading assets of \$2 million or more in Schedule RC-K, item 7, for any quarter of the preceding calendar year. However, because banks with domestic offices only and with less than \$100 million in total assets do not report a quarterly average for trading assets in Schedule RC-K, item 7, on the FFIEC 041, Schedule RC-D is not applicable to such banks.

Banks that (a) regularly underwrite or deal in securities, interest rate contracts, foreign exchange rate contracts, other off-balance sheet commodity and equity contracts, other financial instruments, and other assets for resale (or repurchase), (b) acquire or take positions in such items principally for the purpose of selling in the near term or otherwise with the intent to resell (or repurchase) in order to profit from short-term price movements, or (c) acquire or take positions in such items as an accommodation to customers or for other trading purposes shall report in this schedule the value of such items or positions on the report date. Assets, liabilities, and other financial instruments held for trading shall be consistently valued at fair value.

Exclude from this schedule all available-for-sale securities and all loans and leases that are held for sale. Available-for-sale securities are generally reported in Schedule RC, item 2.b, and in Schedule RC-B, columns C and D. However, a bank may have certain assets that fall within the definition of "securities" in FASB Statement No. 115 (e.g., nonrated industrial development obligations) that the bank has designated as "available-for-sale" which are reported for purposes of the Report of Condition in a balance sheet category other than "Securities" (e.g., "Loans and lease financing receivables"). Loans and leases held for sale should be reported in Schedule RC, item 4.a, "Loans and leases held for sale," and in Schedule RC-C.

Item Instructions

Item No. Caption and Instructions

ASSETS

- 1 <u>U.S. Treasury securities (in domestic offices)</u>. Report the total fair value of securities issued by the U.S. Treasury (as defined for Schedule RC-B, item 1, "U.S. Treasury securities") held for trading (in domestic offices).
- 2 U.S. Government agency obligations (in domestic offices). Report the total fair value of all obligations of U.S. Government agencies (as defined for Schedule RC-B, item 2, "U.S. Government agency obligations") held for trading (in domestic offices). Exclude mortgage-backed securities.
- 3 Securities issued by states and political subdivisions in the U.S. (in domestic offices). Report the total fair value of all securities issued by states and political subdivisions in the United States (as defined for Schedule RC-B, item 3, "Securities issued by states and political subdivisions in the U.S.") held for trading (in domestic offices).
- 4 Mortgage-backed securities (in domestic offices). Report in the appropriate subitem the total fair value of all mortgage-backed securities held for trading (in domestic offices).

FFIEC 031 and 041 RC-D - TRADING

Item No. Caption and Instructions

4.a Pass-through securities issued or guaranteed by FNMA, FHLMC, or GNMA. Report the total fair value of all pass-through securities issued or guaranteed by FNMA, FHLMC, or GNMA (as defined for Schedule RC-B, item 4.a.(1), Pass-through securities "Guaranteed by GNMA," and item 4.a.(2), Pass-through securities "Issued by FNMA and FHLMC") held for trading (in domestic offices).

- 4.b Other mortgage-backed securities issued or guaranteed by FNMA, FHLMC, or GNMA. Report the total fair value of all other mortgage-backed securities issued by FNMA, FHLMC, or GNMA (as defined for Schedule RC-B, item 4.b.(1), Other mortgage-backed securities "Issued or guaranteed by FNMA, FHLMC, or GNMA") held for trading (in domestic offices).
- **All other mortgage-backed securities**. Report the total fair value of all other mortgage-backed securities (as defined for Schedule RC-B, item 4.a.(3), "Other pass-through securities," item 4.b.(2), Other mortgage-backed securities "Collateralized by MBS issued or guaranteed by FNMA, FHLMC, or GNMA," and item 4.b.(3) "All other mortgage-backed securities") held for trading (in domestic offices).
- 5 Other debt securities (in domestic offices). Report the total fair value of all other debt securities (as defined for Schedule RC-B, item 5, "Asset-backed securities," and item 6, "Other debt securities") held for trading (in domestic offices).
- **6-8** Not applicable.
- Other trading assets (in domestic offices). Report the total fair value of all trading assets (in domestic offices) that cannot properly be reported in items 1 through 5. Exclude revaluation gains on interest rate, foreign exchange rate, and other commodity and equity derivative contracts (in domestic offices) (report in item 11 below).

NOTE: Item 10 is applicable only to banks filing the FFIEC 031 report form.

- **Trading assets in foreign offices**. On the FFIEC 031 only, report the total fair value of all assets held for trading in foreign offices. Exclude revaluation gains on interest rate, foreign exchange rate, and other commodity and equity derivative contracts in foreign offices (report in item 11.b below).
- Revaluation gains on interest rate, foreign exchange rate, and other commodity and equity contracts. Report (on the FFIEC 031, in the appropriate subitem) the amount of revaluation gains (i.e., assets) from the "marking to market" of interest rate, foreign exchange rate, and other commodity and equity derivative contracts held for trading purposes. Revaluation gains and losses (i.e., assets and liabilities) from the "marking to market" of the reporting bank's interest rate, foreign exchange rate, and other commodity and equity derivative contracts executed with the same counterparty that meet the criteria for a valid right of setoff contained in FASB Interpretation No. 39 (e.g., those contracts subject to a qualifying master netting arrangement) may be reported on a net basis using this item and item 14 below, as appropriate. (For further information, see the Glossary entry for "offsetting.")

FFIEC 031 and 041 RC-D - TRADING

Item No. Caption and Instructions

NOTE: Items 11.a and 11.b are applicable only to banks filing the FFIEC 031 report form.

11.a In domestic offices. On the FFIEC 031 only, report the amount of revaluation gains (i.e., assets) from the "marking to market" of interest rate, foreign exchange rate, and other commodity and equity derivative contracts held for trading purposes in domestic offices. To the extent that the bank performs its "marking to market" of these contracts on a consolidated basis and nets the resulting revaluation gains and losses (i.e., assets and liabilities) for other financial reporting purposes as described in the instruction to item 11 above, but cannot readily determine separate asset amounts for its domestic offices and for its foreign offices, the asset amounts reported in this item may include revaluation gains and losses on derivative contracts with the same counterparty in both domestic and foreign offices.

- **11.b** In foreign offices. On the FFIEC 031 only, report the amount of revaluation gains (i.e., assets) from the "marking to market" of interest rate, foreign exchange rate, and other commodity and equity derivative contracts held for trading purposes in foreign offices.
- **Total trading assets**. Report the sum of items 1 through 11. This amount must equal Schedule RC, item 5, "Trading assets."

LIABILITIES

- Liability for short positions. Report the total fair value of the reporting bank's liabilities resulting from sales of assets that the reporting bank does not own (see the Glossary entry for "short position").
- Revaluation losses on interest rate, foreign exchange rate, and other commodity and equity contracts. Report the amount of revaluation losses (i.e., liabilities) from the "marking to market" of interest rate, foreign exchange rate, and other commodity and equity derivative contracts held for trading purposes. Revaluation gains and losses (i.e., assets and liabilities) from the "marking to market" of the reporting bank's interest rate, foreign exchange rate, and other commodity and equity derivative contracts executed with the same counterparty that meet the criteria for a valid right of setoff contained in FASB Interpretation No. 39 (e.g., those contracts subject to a qualifying master netting arrangement) may be reported on a net basis using this item and item 11 above, as appropriate. (For further information, see the Glossary entry for "offsetting.")
- **Total trading liabilities**. Report the sum of items 13 and 14. This amount must equal Schedule RC, item 15, "Trading liabilities."

SCHEDULE RC-E -- DEPOSIT LIABILITIES

General Instructions

A complete discussion of deposits is included in the Glossary entry entitled "deposits." That discussion addresses the following topics and types of deposits in detail:

- (1) Federal Deposit Insurance Act definition of deposits;
- (2) transaction accounts;
- (3) demand deposits;
- (4) NOW accounts;
- (5) ATS accounts;
- (6) telephone or preauthorized transfer accounts;
- (7) nontransaction accounts;
- (8) savings deposits;
- (9) money market deposit accounts;
- (10) other savings deposits;
- (11) time deposits;
- (12) time certificates of deposit;
- (13) time deposits, open account;
- (14) interest-bearing deposit accounts; and
- (15) noninterest-bearing deposit accounts.

Additional discussions pertaining to deposits will also be found under separate Glossary entries for:

- (1) borrowings and deposits in foreign offices;
- (2) brokered deposits;
- (3) cash management arrangements;
- (4) dealer reserve accounts;
- (5) hypothecated deposits;
- (6) letter of credit (for letters of credit sold for cash and travelers letters of credit);
- (7) overdraft;
- (8) pass-through reserve balances;
- (9) placements and takings; and
- (10) reciprocal balances.

On the FFIEC 031 only, Schedule RC-E consists of two parts. Part I covers the deposit liabilities of the domestic offices of the consolidated bank. Part II covers the deposit liabilities of the foreign offices (including Edge and Agreement subsidiaries and IBFs) of the consolidated bank. (See the Glossary entries for "domestic office" and "foreign office" for the definitions of these terms.)

NOTE: For information about the reporting of deposits for deposit insurance and FICO assessment purposes, refer to Schedule RC-O.

NOTE: For the appropriate treatment of deposits of depository institutions for which the reporting bank is serving as a pass-through agent for federal required reserves, see the Glossary entry for "pass-through reserve balances."

(Part I. Deposits in Domestic Offices)

Definitions

The term "deposits" is defined in the Glossary and generally follows the definitions of deposits used in the Federal Deposit Insurance Act and in Federal Reserve Regulation D.

Reciprocal balances between the reporting bank and other depository institutions may be reported on a net basis when a right of setoff exists. See the Glossary entry for "offsetting" for the conditions that must be met for a right of setoff to exist.

The following are not reported as deposits:

- (1) Deposits received in one office of the bank for deposit in another office of the bank.
- (2) Outstanding drafts (including advices or authorizations to charge the bank's balance in another depository institution) drawn in the regular course of business by the reporting bank on other depository institutions.
- (3) Trust funds held in the bank's own trust department that the bank keeps segregated and apart from its general assets and does not use in the conduct of its business (report separately in Schedule RC-O, item 3, "Uninvested trust funds (cash) held in the bank's own trust department").
- (4) Deposits accumulated for the payment of personal loans (i.e., hypothecated deposits), which should be netted against loans in Schedule RC-C, Loans and Lease Financing Receivables.
- (5) All obligations arising from assets sold under agreements to repurchase.
- (6) Overdrafts in deposit accounts. Overdrafts are to be reported as loans in Schedule RC-C and not as negative deposits. Overdrafts in one or more transaction accounts within a group of related transaction accounts of a single type (i.e., demand deposit accounts or NOW accounts, but not a combination thereof) maintained in the same right and capacity by a customer (a single legal entity) that are established under a bona fide cash management arrangement by this customer are not to be classified as loans unless there is a net overdraft position in the group of related transaction accounts taken as a whole. For reporting and deposit insurance assessment purposes, such accounts function as, and are regarded as, one account rather than multiple separate accounts. (NOTE: Affiliates and subsidiaries are considered separate legal entities.) See the Glossary entry for "cash management arrangements" for information on bona fide cash management arrangements.
- (7) Time deposits sold (issued) by the reporting bank that it has subsequently purchased in the secondary market (typically as a result of the bank's trading activities) and has not resold as of the report date. For purposes of these reports, a bank that purchases a time deposit it has issued is regarded as having paid the time deposit prior to maturity. The effect of the transaction is that the bank has cancelled a liability as opposed to having acquired an asset for its portfolio.

The following are reported as deposits:

- (1) Deposits of trust funds standing to the credit of other banks and all trust funds held or deposited in any department of the reporting bank other than the trust department.
- (2) Credit items that could not be posted to the individual deposit accounts but that have been credited to the control accounts of the various deposit categories on the general ledger.

Definitions (cont.)

(3) Credit items not yet posted to deposit accounts that are carried in suspense or similar nondeposit accounts and are material in amount. As described in the Glossary entry for "suspense accounts," the items included in such accounts should be reviewed and material amounts reported in the appropriate balance sheet accounts. NOTE: Deposits carried in suspense accounts that have not been reclassified as deposits and reported in Schedule RC-E must be reported as unposted credits in Schedule RC-O, item 2.

- (4) Escrow funds.
- (5) Payments collected by the bank on loans secured by real estate and other loans serviced for others that have not yet been remitted to the owners of the loans.
- (6) Credit balances resulting from customers' overpayments of account balances on credit cards and other revolving credit plans.
- (7) Funds received or held in connection with checks or drafts drawn by the reporting bank and drawn on, or payable at or through, another depository institution either on a zero-balance account or on an account that is <u>not</u> routinely maintained with sufficient balances to cover checks drawn in the normal course of business (including accounts where funds are remitted by the reporting bank only when it has been advised that the checks or drafts have been presented).
- (8) Funds received or held in connection with traveler's checks and money orders sold (but not drawn) by the reporting bank, until the proceeds of the sale are remitted to another party, and funds received or held in connection with other such checks used (but not drawn) by the reporting bank, until the amount of the checks is remitted to another party.
- (9) Checks drawn by the reporting bank on, or payable at or through, a Federal Reserve Bank or a Federal Home Loan Bank.
- (10) Refundable loan commitment fees received or held by the reporting bank prior to loan closing.
- (11) Refundable stock subscription payments received or held by the reporting bank prior to the issuance of the stock. (Report nonrefundable stock subscription payments in Schedule RC-G, item 4, "Other" liabilities.)

In addition, the gross amount of debit items ("throw-outs," "bookkeepers' cutbacks," or "rejects") that cannot be posted to the individual deposit accounts without creating overdrafts or for some other reason (e.g., stop payment, missing endorsement, post or stale date, or account closed), but which have been charged to the control accounts of the various deposit categories on the general ledger, should be credited to (added back to) the appropriate deposit control totals and reported in Schedule RC-F, item 5, "Other" assets.

The Monetary Control Act of 1980 and the resulting revision to Federal Reserve Regulation D, "Reserve Requirements of Depository Institutions," established, for purposes of federal reserve requirements on deposit liabilities, a category of deposits designated as "transaction accounts." The distinction between transaction and nontransaction accounts is discussed in detail in the Glossary entry for "deposits." NOTE: Money market deposit accounts (MMDAs) are regarded as savings deposits and are specifically excluded from the "transaction account" classification.

<u>Summary of Transaction Account Classifications</u> (See the Glossary entry for "deposits" for detailed definitions and further information.)

- A. Always regarded as transaction accounts:
 - 1. Demand deposits.
 - 2. NOW accounts.
 - ATS accounts.
 - 4. Accounts (other than savings deposits) from which payments may be made to third parties by means of an automated teller machine (ATM), a remote service unit (RSU), or another electronic device, including by debit card.
 - 5. Accounts (other than savings deposits) that permit third party payments through use of checks, drafts, negotiable instruments, or other similar instruments.
- B. Deposits or accounts that are regarded as transaction accounts if the following specified conditions exist:
 - 1. Accounts that otherwise meet the definition of savings deposits but that authorize or permit the depositor to <u>exceed</u> the transfer and withdrawal rules for a savings deposit.
 - 2. Any deposit or account that otherwise meets the definition of a time deposit but that allows withdrawals within the first six days after the date of deposit and that does <u>not</u> require an early withdrawal penalty of at least seven days' simple interest on amounts withdrawn within those first six days, <u>unless</u> the deposit or account meets the definition of a savings deposit. Any such deposit or account that meets the definition of a savings deposit shall be reported as a savings deposit, otherwise it shall be reported as a demand deposit, which is a transaction account.
 - 3. The <u>remaining balance</u> of a time deposit from which a partial early withdrawal is made, <u>unless</u> the remaining balance <u>either</u> (a) is subject to additional early withdrawal penalties of at least seven days' simple interest on amounts withdrawn within six days after each partial withdrawal (in which case the deposit or account continues to be reported as a time deposit) <u>or</u> (b) is placed in an account that meets the definition of a savings deposit (in which case the deposit or account shall be reported as a savings deposit). Otherwise, the deposit or account shall be reported as a demand deposit, which is a transaction account.
- C. Not regarded as transaction accounts (unless specified above):
 - Savings deposits (including accounts commonly known as money market deposit accounts (MMDAs)).
 - 2. Accounts that permit telephone or preauthorized transfers or transfers by ATMs or RSUs to repay loans made or serviced by the same depository institution.
 - 3. Accounts that permit telephone or preauthorized withdrawals where the proceeds are to be mailed to or picked up by the depositor.
 - Accounts that permit transfers to other accounts of the depositor at the same institution through ATMs or RSUs.

Column Instructions

Deposits as summarized above are divided into two general categories, "Transaction Accounts" (columns A and B) and "Nontransaction Accounts (including MMDAs)" (column C).

Column A - Total transaction accounts. Report in column A the total of all transaction accounts as summarized above and fully defined in the Glossary entry for "deposits." With the exceptions noted in the item instructions and the Glossary entry, the term "transaction account" is defined as a deposit or account from which the depositor or account holder is permitted to make transfers or withdrawals by negotiable or transferable instruments, payment orders of withdrawal, telephone transfers, or other similar devices for the purpose of making third party payments or transfers to third persons or others, or from which the depositor may make third party payments at an automated teller machine (ATM), a remote service unit (RSU), or another electronic device, including by debit card.

<u>Column B - Memo: Total demand deposits</u>. Report in item 7, column B, the total of all demand deposits, including any matured time or savings deposits without automatic renewal provisions, unless the deposit agreement specifically provides for the funds to be transferred at maturity to another type of account (i.e., other than a demand deposit) (see the Glossary entry for "deposits").

NOTE: Demand deposits are, of course, one type of transaction account. Therefore, the amount reported in item 7, column B, should be included by category of depositor in the breakdown of transaction accounts by category of depositor that is reported in column A.

Column C - Total nontransaction accounts (including MMDAs). Report in column C all deposits other than transaction accounts as summarized above and defined in the Glossary entry for "deposits." Include in column C all interest-bearing and noninterest-bearing savings deposits and time deposits together with all interest paid by crediting savings and time deposit accounts.

Item Instructions

In items 1 through 6 of Schedule RC-E, banks report separate breakdowns of their transaction and nontransaction accounts by category of depositor. When reporting brokered deposits in these items, the funds should be categorized based on the beneficial owners of the funds that the broker has placed in the bank. The business structure of the deposit broker (i.e., whether the broker is, for example, a bank, an individual, a partnership, or a nonbank corporation) has no bearing on the categorization of the deposit. Thus, deposits placed in a bank by a deposit broker that is a nonbank corporation should not be reported in their entirety as deposits of "individuals, partnerships, and corporations" when in fact the beneficial owners of the deposits are, for example, individuals, local governments, and other commercial banks. Instead, the bank should report these deposits in items 1 through 6 of Schedule RC-E according to the appropriate beneficial owner categories as deposits of "Individuals, partnerships, and corporations," "States and political subdivisions in the U.S.," and "Commercial banks and other depository institutions in the U.S." based on the proportionate amount of funds from each category of depositor included in the brokered deposits the bank has received. For further information, see the Glossary entry for "brokered deposits."

Item No. Caption and Instructions

Deposits of individuals, partnerships, and corporations (include all certified and official checks). Report in the appropriate column all deposits of individuals, partnerships, and corporations, wherever located, and all certified and official checks.

Item No. Caption and Instructions

1 <u>Include</u> in this item: (cont.)

(1) Deposits related to the personal, household, or family activities of both farm and nonfarm individuals and to the business activities of sole proprietorships.

- (2) Deposits of corporations and organizations (other than depository institutions), regardless of whether they are operated for profit, including but not limited to:
 - (a) mutual funds and other nondepository financial institutions;
 - (b) foreign government-owned nonbank commercial and industrial enterprises; and
 - (c) quasi-governmental organizations such as post exchanges on military posts and deposits of a company, battery, or similar organization (unless the reporting bank has been designated by the U.S. Treasury as a depository for such funds and appropriate security for the deposits has been pledged, in which case, report in Schedule RC-E, item 2).
- (3) Dealer reserve accounts (see the Glossary entry for "dealer reserve accounts" for the definition of this term).
- (4) Deposits of U.S. Government agencies and instrumentalities such as the:
 - (a) Banks for Cooperatives,
 - (b) Export-Import Bank of the U.S.,
 - (c) Federal Deposit Insurance Corporation,
 - (d) Federal Financing Bank,
 - (e) Federal Home Loan Banks.
 - (f) Federal Home Loan Mortgage Corporation,
 - (g) Federal Intermediate Credit Banks,
 - (h) Federal Land Banks,
 - (i) Federal National Mortgage Association,
 - (j) National Credit Union Administration Central Liquidity Facility,
 - (k) National Credit Union Share Insurance Fund,
 - (I) Office of Thrift Supervision, and
 - (m) Student Loan Marketing Association.
- (5) Deposits of trust funds standing to the credit of other banks and all trust funds held or deposited in any department (except the trust department) of the reporting bank if the beneficiary is an individual, partnership, or corporation.
- (6) Credit balances on credit cards and other revolving credit plans as a result of customer overpayments.
- (7) Deposits of a federal or state court held for the benefit of individuals, partnerships, or corporations, such as bankruptcy funds and escrow funds.

Item No. Caption and Instructions

1 (8) Certified and official checks, which include the following: (cont.)

- (a) Unpaid depositors' checks that have been certified.
- (b) Cashiers' checks, money orders, and other officers' checks issued for any purpose including those issued in payment for services, dividends, or purchases that are drawn on the reporting bank by any of its duly authorized officers and that are outstanding on the report date.
- (c) Funds received or held in connection with checks or drafts drawn by the reporting bank and drawn on, or payable at or through, another depository institution either on a zero-balance account or on an account that is <u>not</u> routinely maintained with sufficient balances to cover checks drawn in the normal course of business (including accounts where funds are remitted by the reporting bank only when it has been advised that the checks or drafts have been presented).
- (d) Funds received or held in connection with traveler's checks and money orders sold (but not drawn) by the reporting bank, until the proceeds of the sale are remitted to another party, and funds received or held in connection with other such checks used (but not drawn) by the reporting bank, until the amount of the checks is remitted to another party.

Item No. Caption and Instructions

1 (e) Checks drawn by the reporting bank on, or payable at or through, a Federal Reserve (cont.) Bank or a Federal Home Loan Bank.

- (f) Outstanding travelers' checks, travelers' letters of credit and other letters of credit (less any outstanding drafts accepted thereunder) sold for cash or its equivalent by the reporting bank or its agents.
- (g) Outstanding drafts and bills of exchange accepted by the reporting bank or its agents for money or its equivalent, including drafts accepted against a letter of credit issued for money or its equivalent.
- (h) On the FFIEC 031, checks or drafts drawn by, or on behalf of, a non-U.S. office of the reporting bank on an account maintained at a U.S. office of the reporting bank. Such drafts are, for Report of Condition and federal deposit insurance assessment purposes, the same as officers' checks. This would include "London checks," "Eurodollar bills payable checks," and any other credit items that the domestic bank issues in connection with such transactions.

Exclude from this item deposits of:

- (1) The U.S. Government (report in Schedule RC-E, item 2).
- States and political subdivisions in the U.S. (report in Schedule RC-E, item 3).
- (3) Commercial banks in the U.S. (report in Schedule RC-E, item 4).
- (4) Other depository institutions in the U.S. (report in Schedule RC-E, item 4).
- (5) Banks in foreign countries (report in Schedule RC-E, item 5).
- 2 <u>Deposits of U.S. Government</u>. Report in the appropriate column all deposits of federal public funds made by or for the account of the United States or some department, bureau, or official thereof.

Include in this item:

- (1) U.S. Treasury Tax and Loan Accounts, including deposits of federal income tax withheld from employee salaries, from interest and dividend payments, and from distributions or payments from pensions, annuities, and other deferred income including IRAs; social security tax deposits and other federal tax payments; and the proceeds from sales of U.S. Savings Bonds.
 - NOTE: Only deposits credited to the U.S. Treasury Tax and Loan demand deposit accounts that represent funds received as of the close of business of the "current" day should be reported as Treasury Tax and Loan Demand Deposits. (The "current" day's deposits should reflect those deposits on the bank's books standing to the credit of the U.S. Treasury's Tax and Loan Account as of the report date.) Funds credited to Tax and Loan Demand Deposit Accounts as of the close of business on previous days should already have been remitted to the Federal Reserve Bank (and thus excluded from this report) or automatically converted into open-ended interest-bearing notes (to be reported in Schedule RC-M, item 5.b.(1), "Other borrowings with a remaining maturity of one year or less"), depending on the option selected by the reporting institution.

Item No. Caption and Instructions

1 (2) Deposits standing to the credit of certain quasi-governmental institutions when the reporting bank has been designated by the U.S. Treasury as a depository for such funds.

(3) Deposits of the U.S. Postal Service and local post offices.

<u>Exclude</u> from this item deposits of U.S. Government agencies and instrumentalities. (Such deposits are to be reported in Schedule RC-E, item 1, above.)

Deposits of states and political subdivisions in the U.S. Report in the appropriate column all deposits standing to the credit of states, counties, municipalities, and local housing authorities; school, irrigation, drainage, and reclamation districts; or other instrumentalities of one or more states of the United States, the District of Columbia, Puerto Rico, and U.S. territories and possessions.

Also <u>include</u> deposits of funds advanced to states and political subdivisions by U.S. Government agencies and corporations and deposits of withheld income taxes of states and political subdivisions.

4 <u>Deposits of commercial banks and other depository institutions in the U.S.</u> Report in the appropriate column all deposits of commercial banks and other depository institutions located in the U.S.

Commercial banks in the U.S. cover:

- (1) U.S. branches and agencies of foreign banks; and
- (2) all other commercial banks in the U.S., i.e., U.S. branches of U.S. banks.

Other depository institutions in the U.S. cover:

- (1) Building or savings and loan associations, homestead associations, and cooperative banks;
- (2) credit unions; and
- (3) mutual and stock savings banks.

For purposes of these reports, U.S. branches and agencies of foreign banks include U.S. branches and agencies of foreign official banking institutions and investment companies that are chartered under Article XII of the New York State banking law and that are majority-owned by one or more foreign banks.

For the appropriate treatment of deposits of depository institutions for which the reporting bank is serving as a pass-through agent for federal required reserves, see the Glossary entry for "pass-through reserve balances."

Refer to the Glossary entries for "banks, U.S. and foreign" and "depository institutions in the U.S." for further discussion of these terms.

Item No. Caption and Instructions

- **4** Exclude from this item deposits of the following depository institutions:
 - (1) Banks in foreign countries (report in Schedule RC-E, item 5, below). (See the Glossary entry for "banks, U.S. and foreign" for the definition of this term.)
 - (2) On the FFIEC 031, IBFs (report in part II of Schedule RC-E).
- Deposits of banks in foreign countries. Report in the appropriate column all deposits of banks located in foreign countries.

Banks in foreign countries cover:

- (1) foreign-domiciled branches of other U.S. banks; and
- (2) <u>foreign</u>-domiciled branches of foreign banks.

See the Glossary entry for "banks, U.S. and foreign" for further discussion of these terms.

<u>Exclude</u> from this item deposits of foreign official institutions and foreign central banks (to be reported in Schedule RC-E, item 6 below) and deposits of U.S. branches and agencies of foreign banks and New York State investment companies (to be reported in Schedule RC-E, item 4 above).

For the appropriate treatment of deposits of depository institutions for which the reporting bank is serving as a pass-through agent for federal required reserves, see the Glossary entry for "pass-through reserve balances."

6 <u>Deposits of foreign governments and official institutions</u>. Report in the appropriate column all deposits of foreign governments and official institutions. (See the Glossary entry for "foreign governments and official institutions" for the definition of this term.)

Exclude from this item deposits of:

- (1) U.S. branches and agencies of foreign official banking institutions (report in Schedule RC-E, item 4, above).
- (2) Nationalized banks and other banking institutions that are owned by foreign governments and that do <u>not</u> function as central banks, banks of issue, or development banks (report in Schedule RC-E, item 5, above).
- (3) Foreign government-owned nonbank commercial and industrial enterprises (report in Schedule RC-E, item 1, above).
- **Total**. Report in column B the total of all demand deposits. Report in columns A and C the sum of items 1 through 6. The sum of columns A and C of this item must equal Schedule RC, item 13.a, "Deposits in domestic offices."

Memoranda

Item No. Caption and Instructions

Selected components of total deposits. The amounts to be reported in Memorandum items 1.a through 1.e below are included as components of total deposits (in domestic offices) (Schedule RC-E, sum of item 7, columns A and C).

- **1.a** Total Individual Retirement Accounts (IRAs) and Keogh Plan accounts. Report in this Memorandum item the total of <u>all</u> IRA and Keogh Plan deposits included in total deposits (in domestic offices) (Schedule RC-E, sum of item 7, columns A and C).
- **1.b** Total brokered deposits. Report in this Memorandum item the total of <u>all</u> brokered deposits included in total deposits (in domestic offices) (Schedule RC-E, sum of item 7, columns A and C), regardless of size or type of deposit instrument. (See the Glossary entry for "brokered deposits" for the definition of this term.)
- **1.c Fully insured brokered deposits**. Report in the appropriate subitem all fully insured brokered deposits (as defined in the Glossary entry for "brokered deposits") included in Schedule RC-E. Memorandum item 1.b above.
- **1.c.(1) Issued in denominations of less than \$100,000**. Report in this item those brokered deposits issued by the bank in denominations of less than \$100,000.
- 1.c.(2) <u>Issued either in denominations of \$100,000 or in denominations greater than \$100,000 and participated out by the broker in shares of \$100,000 or less</u>. Report in this item:
 - (1) those brokered deposits issued by the bank in denominations of exactly \$100,000; and
 - (2) those brokered deposits issued by the bank in denominations greater than \$100,000 that have been participated out by the broker in shares of \$100,000 or less.
- **1.d Maturity data for brokered deposits.** Report in the appropriate subitem the indicated maturity data for brokered deposits (as defined in the Glossary entry for "brokered deposits").
- 1.d.(1) Brokered deposits issued in denominations of less than \$100,000 with a remaining maturity of one year or less. Report in this item those brokered deposits issued by the bank in denominations of less than \$100,000 with a remaining maturity of one year or less. Remaining maturity is the amount of time remaining from the report date until the final contractual maturity of a brokered deposit. The brokered deposits included in this item will have been reported in Schedule RC-E, Memorandum item 1.c.(1) above.
- 1.d.(2) Brokered deposits issued in denominations of \$100,000 or more with a remaining maturity of one year or less. Report in this item those brokered deposits issued by the bank in denominations of \$100,000 or more with a remaining maturity of one year or less.

 Remaining maturity is the amount of time remaining from the report date until the final contractual maturity of a brokered deposit. The brokered deposits included in this item will have been reported in Schedule RC-E, Memorandum item 1.b above.

Memoranda

Item No. Caption and Instructions

1.e Preferred deposits. (This item is to be reported for the December 31 report only.)
Report in this item all deposits of states and political subdivisions in the U.S. included in Schedule RC-E, item 3, columns A and C above, which are secured or collateralized as required under state law. Exclude deposits of the U.S. Government which are secured or collateralized as required under federal law. Also exclude deposits of trust funds which are secured or collateralized as required under state law unless the beneficiary is a state or political subdivision in the U.S. The amount reported in this memorandum item must be less than the sum of Schedule RC-E, item 3, column A, and item 3, column C, above.

State law may require a bank to pledge securities (or other readily marketable assets) to cover the uninsured portion of the deposits of a state or political subdivision. If the bank has pledged securities with a value that exceeds the amount of the uninsured portion of the state or political subdivision's deposits, only the uninsured amount (and none of the insured portion of the deposits) should be reported as a "preferred deposit." For example, a political subdivision has \$350,000 in deposits at a bank which, under state law, is required to pledge securities to cover only the uninsured portion of such deposits (\$250,000 in this example). The bank has pledged securities with a value of \$300,000 to secure these deposits. Only \$250,000 of the political subdivision's \$350,000 in deposits (the uninsured amount) would be considered "preferred deposits."

In other states, banks must participate in a state public deposits program in order to receive deposits from the state or from political subdivisions within the state in amounts that would not be covered by federal deposit insurance. Under state law in such states, the value of the securities a bank must pledge to the state is calculated annually, but represents only a percentage of the uninsured portion of its public deposits. Institutions participating in the state program may potentially be required to share in any loss to public depositors incurred in the failure of another participating institution. As long as the value of the securities pledged to the state exceeds the calculated requirement, all of the bank's uninsured public deposits are protected from loss under the operation of the state program if the bank fails and, therefore, all of the uninsured public deposits are considered "preferred deposits." For example, a bank participating in a state public deposits program has \$1,000,000 in public deposits under the program and \$700,000 of this amount is uninsured. The bank's most recent calculation indicates that it must pledge securities with a value of at least \$77,000 to the state in order to participate in the state program. The bank has pledged securities with an actual value of \$80,000. The bank should report the \$700,000 in uninsured public deposits as "preferred deposits."

Components of total nontransaction accounts. Memorandum item 2 divides total nontransaction accounts into two major categories: savings deposits (Memorandum items 2.a.(1) and 2.a.(2)) and time deposits (Memorandum items 2.b and 2.c). The sum of Memorandum items 2.a.(1) and 2.a.(2) equals total savings deposits. The sum of Memorandum items 2.b and 2.c equals total time deposits. The sum of Memorandum items 2.a.(1) and 2.a.(2) (savings deposits) and Memorandum items 2.b and 2.c (time deposits) equals total nontransaction deposits reported in item 7, column C, above.

Memoranda

Item No. Caption and Instructions

2 <u>Include</u> as time deposits in Memorandum items 2.b and 2.c: (cont.)

- (1) All time deposits (as defined in the Glossary entry for "deposits") with original maturities of seven days or more that are not classified as transaction accounts.
- (2) Interest paid by crediting time deposit accounts.
- **2.a Savings deposits**. Report in the appropriate subitem all savings deposits included in column C above. See the Glossary entry for "deposits" for the definition of savings deposits.

<u>Include</u> as savings deposits in Memorandum items 2.a.(1) and 2.a.(2) interest paid by crediting savings deposit accounts.

Exclude from Memorandum items 2.a.(1) and 2.a.(2):

- (1) NOW accounts, ATS accounts, and telephone or preauthorized transfer accounts that meet the definition of a transaction account (report in Schedule RC-E, column A, as transaction accounts).
- (2) Special passbook or statement accounts, such as "90-day notice accounts," "golden passbook accounts," or deposits labeled as "savings certificates," that have a specified original maturity of seven days or more (report as time deposits in Schedule RC-E, Memorandum item 2.b or 2.c, below).
- (3) Interest accrued on savings deposits but not yet paid or credited to a deposit account (exclude from this schedule and report in Schedule RC-G, item 1.a, "Interest accrued and unpaid on deposits (in domestic offices)").
- 2.a.(1) Money market deposit accounts (MMDAs). Report in this item the total amount of all money market deposit accounts (MMDAs) that are included in Schedule RC-E, column C, above. See the Glossary entry for "deposits" for the definition of money market deposit accounts.
- **Other savings deposits.** Report in this item the total amount of all other savings deposits that are included in Schedule RC-E, column C, above. This item includes those accounts commonly known as passbook savings and statement savings. See the Glossary entry for "deposits" for the definition of other savings deposits.
- 2.b Total time deposits of less than \$100,000. Report in this item all time deposits included in Schedule RC-E, column C, above with balances of less than \$100,000. This item includes both time certificates of deposit and open-account time deposits with balances of less than \$100,000, regardless of negotiability or transferability. Exclude from this item all time deposits with balances of \$100,000 or more (report in Schedule RC-E, Memorandum item 2.c, below).

Memoranda

Item No. Caption and Instructions

2.c Total time deposits of \$100,000 or more. Report in this item all time deposits included in Schedule RC-E, column C, above with balances of \$100,000 or more. This item includes both time certificates of deposit and open-account time deposits with balances of \$100,000 or more, regardless of negotiability or transferability. Include in this item brokered deposits issued to brokers or dealers in the form of large (\$100,000 or more) certificates of deposit, regardless of whether the underlying depositors' shares are in denominations of less than \$100,000. Exclude from this item time deposits with balances of less than \$100,000 (report in Schedule RC-E, Memorandum item 2.b, above).

NOTE: Banks should include as time deposits of \$100,000 or more those time deposits originally issued in denominations of less than \$100,000 but that, because of interest paid or credited, or because of additional deposits, now have a balance of \$100,000 or more.

Maturity and repricing data for time deposits of less than \$100,000. Report in the appropriate subitem maturity and repricing data for the bank's time deposits of less than \$100,000, i.e., the bank's time certificates of deposit of less than \$100,000 and the bank's open-account time deposits of less than \$100,000. The time deposits included in this item will have been reported in Schedule RC-E, Memorandum item 2.b, above. Therefore, the sum of the amounts reported in Schedule RC-E, Memorandum items 3.a.(1) through 3.a.(4) must equal Schedule RC-E, Memorandum item 2.b, above.

For purposes of this memorandum item and Schedule RC-E, Memorandum item 4, the following definitions apply:

A <u>fixed interest rate</u> is a rate that is specified at the origination of the transaction, is fixed and invariable during the term of the time deposit, and is known to both the bank and the depositor. Also treated as a fixed interest rate is a predetermined interest rate which is a rate that changes during the term of the time deposit on a predetermined basis, with the exact rate of interest over the life of the time deposit known with certainty to both the bank and the depositor when the time deposit is acquired.

A <u>floating rate</u> is a rate that varies, or can vary, in relation to an index, to some other interest rate such as the rate on certain U.S. Government securities or the bank's "prime rate," or to some other variable criterion the exact value of which cannot be known in advance. Therefore, the exact rate the time deposit carries at any subsequent time cannot be known at the time the time deposit is received by the bank or subsequently renewed.

When the rate on a time deposit with a floating rate has reached a contractual floor or ceiling level, the time deposit is to be treated as "fixed rate" rather than as "floating rate" until the rate is again free to float.

<u>Remaining maturity</u> is the amount of time remaining from the report date until the final contractual maturity of a time deposit.

Next <u>repricing date</u> is the date the interest rate on a floating rate time deposit can next change in accordance with the terms of the contract or the contractual maturity date of the deposit, whichever is earlier.

Memoranda

Item No. Caption and Instructions

Banks whose records or information systems provide data on the final contractual maturities (cont.)

and next repricing dates of their time deposits for time periods that closely approximate the maturity and repricing periods specified in this Memorandum item and Schedule RC-E, Memorandum item 4 (e.g., 89 or 90 days rather than three months, 359 or 360 days rather 12 months) may use these data to complete this Memorandum item and Schedule RC-E, Memorandum item 4.

Time deposits held in Individual Retirement Accounts (IRAs) and Keogh Plan accounts should be reported without regard to distribution schedules that may be in effect for funds held in certain depositors' accounts. Such time deposits should be reported in this Memorandum item and in Schedule RC-E, Memorandum item 4, in the same manner as time deposits not held in IRAs and Keogh Plan accounts.

Noninterest-bearing time deposits should be treated as fixed rate time deposits and reported according to the amount of time remaining until the final contractual maturity in this Memorandum item and in Schedule RC-E, Memorandum item 4.

Fixed rate time deposits that are callable at the option of the issuing bank should be reported according to their remaining maturity without regard to their next call date unless the time deposit has actually been called. When fixed rate time deposits have been called, they should be reported on the basis of the time remaining until the call date. Callable floating rate time deposits should be reported on the basis of their next repricing date, without regard to their next call date unless the time deposit has actually been called. Floating rate time deposits that have been called should be reported on the basis of their next repricing date or their actual call date, whichever is earlier.

Fixed rate time deposits that provide depositors with the option to redeem them at one or more specified dates prior to their contractual maturity date without penalty should be reported according to their remaining maturity without regard to "put" dates if the depositor has not exercised the "put." If a redemption option has been exercised, however, such deposits should be reported on the basis of the time remaining until the date on which the time deposit will be redeemed. Floating rate time deposits that provide depositors with redemption options without penalty should be reported on the basis of their next repricing date without regard to the "put" dates if the depositor has not exercised the "put." If a redemption option has been exercised but the time deposit has not yet been redeemed, the deposit should be reported on the basis of its next repricing date or its scheduled redemption date, whichever is earlier.

Time deposits of less than \$100,000 with a remaining maturity or next repricing date of.

Report the dollar amount of the bank's <u>fixed rate</u> time deposits of less than \$100,000 in the appropriate subitems according to the amount of time remaining to their final contractual maturities. Report the dollar amount of the bank's <u>floating rate</u> time deposits of less than \$100,000 in the appropriate subitems according to their next repricing dates.

3.a.(1) Three months or less. Report the dollar amount of:

- the bank's fixed rate time deposits of less than \$100,000 with remaining maturities of three months or less, and
- the bank's floating rate time deposits of less than \$100,000 with the next repricing date occurring in three months or less.

Memoranda

Item No. Caption and Instructions

3.a.(2) Over three months through 12 months. Report the dollar amount of:

- the bank's fixed rate time deposits of less than \$100,000 with remaining maturities of over three months through 12 months, and
- the bank's floating rate time deposits of less than \$100,000 with the next repricing date occurring in over three months through 12 months.

3.a.(3) Over one year through three years. Report the dollar amount of:

- the bank's fixed rate time deposits of less than \$100,000 with remaining maturities of over one year through three years, and
- the bank's floating rate time deposits of less than \$100,000 with the next repricing date occurring in over one year through three years.

3.a.(4) Over three years. Report the dollar amount of:

- the bank's fixed rate time deposits of less than \$100,000 with remaining maturities of over three years, and
- the bank's floating rate time deposits of less than \$100,000 with the next repricing date occurring in over three years.
- 3.b Time deposits of less than \$100,000 with a remaining maturity of one year or less.

 Report all time deposits of less than \$100,000 with a remaining maturity of one year or less.

 Include both fixed rate and floating rate time deposits of less than \$100,000.

The fixed rate time deposits that should be included in this item will also have been reported by remaining maturity in Schedule RC-E, Memorandum items 3.a.(1) and 3.a.(2), above. The floating rate time deposits that should be included in this item will have been reported by next repricing date in Memorandum items 3.a.(1) and 3.a.(2), above. However, these two Memorandum items may include floating rate time deposits with a remaining maturity of more than one year, but on which the interest rate can next change in one year or less; those time deposits should not be included in this Memorandum item 3.b.

Maturity and repricing data for time deposits of \$100,000 or more. Report in the appropriate subitem maturity and repricing data for the bank's time deposits of \$100,000 or more, i.e., the bank's time certificates of deposit of \$100,000 or more and the bank's open-account time deposits of \$100,000 or more. The time deposits included in this item will have been reported in Schedule RC-E, Memorandum item 2.c, above. Therefore, the sum of the amounts reported in Schedule RC-E, Memorandum items 4.a.(1) through 4.a.(4) must equal Schedule RC-E, Memorandum item 2.c, above. Refer to the definitions and other instructions about time deposits in Schedule RC-E, Memorandum item 3, above.

Memoranda

Item No. Caption and Instructions

4.a Time deposits of \$100,000 or more with a remaining maturity or next repricing date of.

Report the dollar amount of the bank's <u>fixed rate</u> time deposits of \$100,000 or more in the appropriate subitems according to the amount of time remaining to their final contractual maturities. Report the dollar amount of the bank's <u>floating rate</u> time deposits of \$100,000 or more in the appropriate subitems according to their next repricing dates.

4.a.(1) Three months or less. Report the dollar amount of:

- the bank's fixed rate time deposits of \$100,000 or more with remaining maturities of three months or less, and
- the bank's floating rate time deposits of \$100,000 or more with the next repricing date occurring in three months or less.

4.a.(2) Over three months through 12 months. Report the dollar amount of:

- the bank's fixed rate time deposits of \$100,000 or more with remaining maturities of over three months through 12 months, and
- the bank's floating rate time deposits of \$100,000 or more with the next repricing date occurring in over three months through 12 months.

4.a.(3) Over one year through three years. Report the dollar amount of:

- the bank's fixed rate time deposits of \$100,000 or more with remaining maturities of over one year through three years, and
- the bank's floating rate time deposits of \$100,000 or more with the next repricing date occurring in over one year through three years.

4.a.(4) Over three years. Report the dollar amount of:

- the bank's fixed rate time deposits of \$100,000 or more with remaining maturities of over three years, and
- the bank's floating rate time deposits of \$100,000 or more with the next repricing date occurring in over three years.
- 4.b Time deposits of \$100,000 or more with a remaining maturity of one year or less.

 Report all time deposits of \$100,000 or more with a remaining maturity of one year or less.

 Include both fixed rate and floating rate time deposits of \$100,000 or more.

The fixed rate time deposits that should be included in this item will also have been reported by remaining maturity in Schedule RC-E, Memorandum items 4.a.(1) and 4.a.(2), above. The floating rate time deposits that should be included in this item will have been reported by next repricing date in Memorandum items 4.a.(1) and 4.a.(2), above. However, these two Memorandum items may include floating rate time deposits with a remaining maturity of more than one year, but on which the interest rate can next change in one year or less; those time deposits should not be included in this Memorandum item 4.b.

Schedule RC-E, Part II. Deposits in Foreign Offices (FFIEC 031 only)

General Instructions

Part II of Schedule RC-E is not applicable to banks filing the FFIEC 041 report forms.

For purposes of this report, IBFs are to be treated as foreign offices and their deposit liabilities should be reported <u>only</u> in Schedule RC-E, part II. Also included in this part are deposits of all offices of Edge and Agreement subsidiaries and deposits of offices in foreign countries.

The definition of deposits in Schedule RC-E, part I, will apply directly to deposits of branches in Puerto Rico and U.S. territories and possessions and to the domestic offices of Edge and Agreement subsidiaries. However, for all other "foreign offices," the definition of deposits in Schedule RC-E, part I, must be adjusted for any differences in statutory and regulatory requirements and in institutional practices in foreign countries.

For these other foreign offices include as deposits:

- (1) Liabilities readily identifiable as deposits because of name or definition.
- (2) All foreign office liabilities identical to those described for domestic offices that have different names in different countries.
- (3) Liabilities that, owing to law, custom, or banking practice in foreign countries, have characteristics similar to those defined for Schedule RC-E, part I.
- (4) Any other foreign office liability that is treated as a deposit by the laws, local custom, or banking practice of the country in which it is booked.

Report any nondeposit borrowing of an office in a foreign country as a borrowing in Schedule RC-M, item 5.b, "Other borrowings," or in other items, as appropriate.

When it is not clear whether a liability in a foreign office should be treated as a deposit or as a borrowing, treat it as a deposit. Report <u>all</u> deposits in IBFs in Schedule RC-E, part II, whether in the form of deposits, borrowings, placements, or similar instruments. <u>Exclude</u> IBF liabilities in the form of federal funds purchased and securities sold under agreements to repurchase (report in Schedule RC, item 14) and in the form of accrued liabilities, such as interest accrued but unpaid (report in Schedule RC-G, item 1.b).

For a discussion of deposits in foreign offices, see the Glossary entry for "borrowings and deposits in foreign offices."

Reciprocal balances between foreign offices of the reporting bank and other depository institutions may be reported on a net basis when a right of setoff exists. See the Glossary entry for "offsetting" for the conditions that must be met for a right of setoff to exist.

Part II. Deposits in Foreign Offices (cont.)

Item Instructions

Item No. Caption and Instructions

Deposits of individuals, partnerships, and corporations (include all certified and official checks). Report all balances in foreign offices standing to the credit of individuals, partnerships, and corporations (as defined for Schedule RC-E, part I, item 1). Report all certified and official checks issued by foreign offices of the reporting bank (as defined for Schedule RC-E, part I, item 1). Also report all other liabilities that, owing to law, custom, or banking practice in foreign countries, have characteristics similar to those specified for domestic offices.

- Deposits of U.S. banks (including IBFs and foreign branches of U.S. banks) and other U.S. depository institutions. Report all deposit balances in foreign offices of the reporting bank standing to the credit of banks and other depository institutions headquartered and chartered in the United States. Include both U.S. and non-U.S. branches of U.S. commercial banks and other depository institutions as well as IBFs established by U.S. commercial banks. Exclude U.S. branches and agencies of foreign banks and IBFs established by such branches and agencies. (See the Glossary entry for "banks, U.S. and foreign" for the definition of U.S. banks and the Glossary entry for "depository institutions in the U.S." for further discussion of this term).
- Deposits of foreign banks (including U.S. branches and agencies of foreign banks, including their IBFs). Report all balances in foreign offices of the reporting bank standing to the credit of banks headquartered and chartered in foreign countries. Include both U.S. and non-U.S. branches of foreign banks and IBFs established by U.S. branches and agencies of foreign banks. Exclude foreign offices of U.S. banks. (See the Glossary entry for "banks, U.S. and foreign" for the definition of foreign banks.)
- **Deposits of foreign governments and official institutions**. Report all balances in foreign offices standing to the credit of foreign governments and official institutions, including foreign central banks. (See the Glossary entry for "foreign governments and official institutions" for the definition of this term.)
- 5 <u>Deposits of U.S. Government and states and political subdivisions in the U.S.</u> Report all balances in foreign offices standing to the credit of the U.S. Government and states and political subdivisions in the U.S. (as defined for Schedule RC-E, part I, items 2 and 3).
- **Total**. Report the sum of items 1 through 5. This item must equal Schedule RC, item 13.b, "Deposits in foreign offices, Edge and Agreement subsidiaries, and IBFs."

Memorandum

Item No. Caption and Instructions

Time deposits with a remaining maturity of one year or less. Report all time deposits in foreign offices with remaining maturities of one year or less. Remaining maturity is the amount of time remaining from the report date until the final contractual maturity of a time deposit. The time deposits included in this item will also have been reported in Schedule RC-E, part II, item 6, above.

FFIEC 031 and 041 RC-F - OTHER ASSETS

SCHEDULE RC-F -- OTHER ASSETS

General Instructions

Complete this schedule for the fully consolidated bank. Eliminate all intrabank transactions between offices of the consolidated bank.

Item Instructions

Item No. Caption and Instructions

- **Accrued interest receivable.** Report the amount of interest earned or accrued on earning assets and applicable to current or prior periods that has not yet been collected.
- Net deferred tax assets. Report the net amount after offsetting deferred tax assets (net of valuation allowance) and deferred tax liabilities measured at the report date for a particular tax jurisdiction if the net result is a debit balance. If the result for a particular tax jurisdiction is a net credit balance, report the amount in Schedule RC-G, item 2, "Net deferred tax liabilities." If the result for each tax jurisdiction is a net credit balance, enter a zero or the word "none" in this item. (A bank may report a net deferred tax debit, or asset, for one tax jurisdiction, such as for federal income tax purposes, and also report at the same time a net deferred tax credit, or liability, for another tax jurisdiction, such as for state or local income tax purposes.)

For further information on calculating deferred taxes for different tax jurisdictions, see the Glossary entry for "income taxes."

Interest-only strips receivable (not in the form of a security) on. As defined in FASB Statement No. 140, Accounting for Transfers and Servicing of Financial Assets and Extinguishments of Liabilities, an interest-only strip receivable is the contractual right to receive some or all of the interest due on a bond, mortgage loan, collateralized mortgage obligation, or other interest-bearing financial asset. This includes, for example, contractual rights to future interest cash flows that exceed contractually specified servicing fees on financial assets that have been sold. Report in the appropriate subitem interest-only strips receivable not in the form of a security that are measured at fair value like available-for-sale securities. Report unrealized gains (losses) on these interest-only strips receivable in Schedule RC, item 26.b, "Accumulated other comprehensive income."

Exclude from this item interest-only strips receivable in the form of a security, which should be reported as available-for-sale securities in Schedule RC, item 2.b, or as trading assets in Schedule RC, item 5, as appropriate. Also exclude interest-only strips not in the form of a security that are held for trading, which should be reported in Schedule RC, item 5.

- **3.a** Mortgage loans. Report the fair value of interest-only strips receivable (not in the form of a security) on mortgage loans.
- **Other financial assets.** Report the fair value of interest-only strips receivable (not in the form of a security) on financial assets other than mortgage loans.

FFIEC 031 and 041 RC-F-1 RC-F - OTHER ASSETS (3-01)

FFIEC 031 and 041 RC-F - OTHER ASSETS

Item No. Caption and Instructions

4 Equity securities that do not have readily determinable fair values. Report the historical cost of equity securities without readily determinable fair values. These equity securities are outside the scope of FASB Statement No. 115, Accounting for Certain Investments in Debt and Equity Securities. An equity security does not have a readily determinable fair value if sales or bid-and-asked quotations are not currently available on a securities exchange registered with the Securities and Exchange Commission (SEC) and are not publicly reported by the National Association of Securities Dealers Automated Quotations systems or the National Quotation Bureau. The fair value of an equity security traded only in a foreign market is not readily determinable if that foreign market is not one of the U.S. markets referenced above.

Equity securities that do not have readily determinable fair values may have been purchased by the reporting bank or acquired for debts previously contracted.

<u>Include</u> in this item:

- (1) Paid-in stock of a Federal Reserve Bank.
- (2) Stock of a Federal Home Loan Bank.
- (3) Common and preferred stocks that do not have readily determinable fair values, such as stock of bankers' banks and voting common stock of the Federal Agricultural Mortgage Corporation (Farmer Mac).
- (4) "Restricted stock," as defined in FASB Statement No. 115, i.e., equity securities for which sale is restricted by governmental or contractual requirement (other than in connection with being pledged as collateral), except if that requirement terminates within one year or if the holder has the power by contract or otherwise to cause the requirement to be met within one year.
- (5) Participation certificates issued by a Federal Intermediate Credit Bank, which represent nonvoting stock of the bank.
- (6) Minority interests held by the reporting bank in any company not meeting the definition of associated company, except minority holdings that indirectly represent bank premises (report in Schedule RC, item 6) or other real estate owned (report in Schedule RC, item 7), provided that the fair value of any capital stock representing the minority interest is not readily determinable. (See the Glossary entry for "subsidiaries" for the definition of associated company.)
- (7) Equity holdings in those corporate ventures over which the reporting bank does not exercise significant influence, except equity holdings that indirectly represent bank premises (report in Schedule RC, item 6) or other real estate owned (report in Schedule RC, item 7). (See the Glossary entry for "subsidiaries" for the definition of corporate joint venture.)

Exclude from this item:

(1) Holdings of capital stock of and investments in unconsolidated subsidiaries, associated companies, and those corporate joint ventures over which the reporting bank exercises significant influence (report in Schedule RC, item 8, "Investments in unconsolidated subsidiaries and associated companies"). FFIEC 031 and 041 RC-F - OTHER ASSETS

Item No. Caption and Instructions

4 (2) Preferred stock that by its terms either must be redeemed by the issuing enterprise or (cont.) is redeemable at the option of the investor (report in Schedule RC-B, item 6, "Other debt securities").

Other. Report the amount of all other assets (other than those reported in Schedule RC-F, items 1, 2, 3, and 4, above) that cannot properly be reported in Schedule RC, items 1 through 10.

Disclose in items 5.a through 5.g each component of all other assets, and the dollar amount of such component, that is greater than \$25,000 and exceeds 25 percent of the amount reported for this item. For each component of all other assets that exceeds this disclosure threshold for which a preprinted caption has not been provided in items 5.a through 5.d, describe the component with a clear but concise caption in items 5.e through 5.g. These descriptions should not exceed 50 characters in length (including spacing between words).

Include as all other assets:

- (1) Prepaid expenses, i.e., those applicable as a charge against operations in future periods. (Report the amount of prepaid expenses in Schedule RC-F, item 5.a, if this amount is greater than \$25,000 and exceeds 25 percent of the amount reported in Schedule RC-F, item 5.)
- (2) Cash surrender value of life insurance policies for which the bank is the beneficiary. (Policies acquired after November 14, 1985, should be reported at the amount that could be realized under the insurance contracts as of the report date. For further information, see FASB Technical Bulletin No. 85-4.) (Report the amount of cash surrender value in Schedule RC-F, item 5.b, if this amount is greater than \$25,000 and exceeds 25 percent of the amount reported in Schedule RC-F, item 5.)
- (3) Automobiles, boats, equipment, appliances, and similar personal property repossessed or otherwise acquired for debts previously contracted. (Report the amount of repossessed personal property in Schedule RC-F, item 5.c, if this amount is greater than \$25,000 and exceeds 25 percent of the amount reported in Schedule RC-F, item 5.)
- (4) Derivative instruments that have a positive fair value that the bank holds for purposes other than trading. For further information, see Glossary entry for "derivative contracts." (Report this positive fair value in Schedule RC-F, item 5.d, if this amount is greater than \$25,000 and exceeds 25 percent of the amount reported in Schedule RC-F, item 5.)
- (5) Accrued interest on securities purchased (if accounted for separately from "accrued interest receivable" in the bank's records).
- (6) Cash items not conforming to the definition of "Cash items in process of collection" found in the instruction to Schedule RC, item 1.a.
- (7) Credit or debit card sales slips in process of collection until the reporting bank has been notified that it has been given credit (report thereafter in Schedule RC, item 1.a, "Noninterest-bearing balances and currency and coin," and, if applicable, in Schedule RC-A, item 2, "Balances due from depository institutions in the U.S.," or item 3, "Balances due from banks in foreign countries and foreign central banks," as appropriate).

FFIEC 031 and 041 RC-F - OTHER ASSETS

Item No. Caption and Instructions

5 (8) Purchased computer software, net of accumulated amortization, and unamortized costs (cont.) of computer software to be sold, leased, or otherwise marketed capitalized in accordance with the provisions of FASB Statement No. 86.

- (9) Bullion (e.g., gold or silver) not held for trading purposes.
- (10) Original art objects, including paintings, antique objects, and similar valuable decorative articles (report at cost unless there has been a decline in value, judged to be other than temporary, in which case the object should be written down to its fair value).
- (11) Securities or other assets held in charitable trusts (e.g., Clifford Trusts).
- (12) Cost of issuing subordinated notes and debentures, net of accumulated amortization.
- (13) Furniture and equipment rented to others under operating leases, net of accumulated depreciation.
- (14) Ground rents.
- (15) Customers' liability for deferred payment letters of credit.

Exclude from all other assets:

- (1) Redeemed U.S. savings bonds and food stamps (report in Schedule RC, item 1.a, "Noninterest-bearing balances and currency and coin," and, if applicable, in Schedule RC-A, item 1, "Cash items in process of collection, unposted debits, and currency and coin").
- (2) Real estate owned or leasehold improvements to property intended for future use as banking premises (report in Schedule RC, item 6, "Premises and fixed assets").
- (3) Accounts identified as "building accounts," "construction accounts," or "remodeling accounts" (report in Schedule RC, item 6, "Premises and fixed assets").
- (4) Real estate acquired in any manner for debts previously contracted (including, but not limited to, real estate acquired through foreclosure and real estate acquired by deed in lieu of foreclosure), even if the bank has not yet received title to the property, and real estate collateral underlying a loan when the bank has obtained physical possession of the collateral, regardless of whether formal foreclosure proceedings have been instituted against the borrower (report as "All other real estate owned" in Schedule RC-M, item 3.b).
- (5) Due bills representing purchases of securities or other assets by the reporting bank that have not yet been delivered (report as loans in Schedule RC-C).
- (6) Factored accounts receivable (report as loans in Schedule RC-C).
- **Total.** Report the sum of items 1 through 5. This amount must equal Schedule RC, item 11, "Other assets."

FFIEC 031 and 041 RC-F-4 RC-F - OTHER ASSETS (6-01)

FFIEC 031 and 041 **RC-G - OTHER LIABILITIES**

SCHEDULE RC-G -- OTHER LIABILITIES

General Instructions

Complete this schedule for the fully consolidated bank. Eliminate all intrabank transactions between offices of the consolidated bank.

Item Instructions

Item No. **Caption and Instructions**

- 1.a Interest accrued and unpaid on deposits (in domestic offices). Report the amount of interest on deposits (in domestic offices) accrued through charges to expense during the current or prior periods, but not yet paid or credited to a deposit account. For savings banks, include in this item "dividends" accrued and unpaid on deposits. On the FFIEC 031, exclude from this item interest accrued and unpaid on deposits in foreign offices (report such accrued interest in Schedule RC-G, item 1.b below).
- 1.b Other expenses accrued and unpaid. Report the amount of income taxes, interest on nondeposit liabilities (and, on the FFIEC 031, deposits in foreign offices), and other expenses accrued through charges to expense during the current or prior periods, but not yet paid. Exclude interest accrued and unpaid on deposits in domestic offices (report such accrued interest in Schedule RC-G, item 1.a above).
- 2 Net deferred tax liabilities. Report the net amount after offsetting deferred tax assets (net of valuation allowance) and deferred tax liabilities measured at the report date for a particular tax jurisdiction if the net result is a credit balance. If the result for a particular tax jurisdiction is a net debit balance, report the amount in Schedule RC-F, item 2, "Net deferred tax assets." If the result for each tax jurisdiction is a net debit balance, enter a zero or the word "none" in this item. (A bank may report a net deferred tax debit, or asset, for one tax jurisdiction, such as for federal income tax purposes, and also report at the same time a net deferred tax credit, or liability, for another tax jurisdiction, such as for state or local income tax purposes.)

For further information on calculating deferred taxes for different tax jurisdictions, see the Glossary entry for "income taxes."

- 3 Allowance for credit losses on off-balance sheet credit exposures. Report the amount of any allowance for credit losses on off-balance sheet exposures established in accordance with generally accepted accounting principles.
- Other. Report the amount of all other liabilities (other than those reported in Schedule RC-G, 4 items 1, 2, and 3, above) that cannot properly be reported in Schedule RC, items 13 through

Disclose in items 4.a through 4.g each component of all other liabilities, and the dollar amount of such component, that is greater than \$25,000 and exceeds 25 percent of the amount reported for this item.

For each component of all other liabilities that exceeds this disclosure threshold for which a preprinted caption has not been provided in items 4.a through 4.d, describe the component with a clear but concise caption in items 4.e through 4.g. These descriptions should not exceed 50 characters in length (including spacing between words).

FFIEC 031 and 041 RC-G-1 **RC-G - OTHER LIABILITIES** FFIEC 031 and 041 RC-G - OTHER LIABILITIES

Item No. Caption and Instructions

4 <u>Include</u> as all other liabilities: (cont.)

(1) Accounts payable (other than expenses accrued and unpaid). (Report the amount of accounts payable in Schedule RC-G, item 4.a, if this amount is greater than \$25,000 and exceeds 25 percent of the amount reported in Schedule RC-G, item 4.)

- (2) Deferred compensation liabilities. (Report the amount of such liabilities in Schedule RC-G, item 4.b, if this amount is greater than \$25,000 and exceeds 25 percent of the amount reported in Schedule RC-G, item 4.)
- (3) Dividends declared but not yet payable, i.e., the amount of cash dividends declared on limited-life preferred, perpetual preferred, and common stock on or before the report date but not payable until after the report date. (Report the amount of such dividends in Schedule RC-G, item 4.c, if this amount is greater than \$25,000 and exceeds 25 percent of the amount reported in Schedule RC-G, item 4.) (Report dividend checks outstanding as deposit liabilities in Schedule RC-E, item 1, column A, and item 7, column B.)
- (4) Derivative instruments that have a negative fair value that the reporting bank holds for purposes other than trading. For further information, see the Glossary entry for "derivative contracts." (Report this negative fair value in Schedule RC-G, item 4.d, if this amount is greater than \$25,000 and exceeds 25 percent of the amount reported in Schedule RC-G, item 4.)
- (5) Deferred gains from sale-leaseback transactions.
- (6) Unamortized loan fees, other than those that represent an adjustment of the interest yield, if material (refer to the Glossary entry for "loan fees" for further information).
- (7) Bank's liability for deferred payment letters of credit.
- (8) Unamortized negative goodwill (refer to the "purchase acquisition" section of the Glossary entry for "business combinations" for further information).
- (9) Recourse liability accounts arising from asset transfers with recourse that are reported as sales.

<u>Exclude</u> from all other liabilities (report in appropriate items of Schedule RC-E, Deposit Liabilities):

- (1) Proceeds from sales of U.S. savings bonds.
- (2) Withheld taxes, social security taxes, sales taxes, and similar items.
- (3) Mortgage and other escrow funds (e.g., funds received for payment of taxes or insurance), sometimes described as mortgagors' deposits or mortgage credit balances.
- (4) Undisbursed loan funds for which borrowers are liable and on which they pay interest. The amounts of such undisbursed funds should be included in both loans and deposits.
- (5) Funds held as dealer reserves (see the Glossary entry for "dealer reserve accounts" for the definition of this term).

FFIEC 031 and 041 RC-G-2 RC-G - OTHER LIABILITIES (3-01)

FFIEC 031 and 041 RC-G - OTHER LIABILITIES

Item No. Caption and Instructions

4 (cont.)

- (6) Payments collected by the bank on loans secured by real estate and other loans serviced for others that have not yet been remitted to the owners of the loans.
- (7) Credit balances on credit cards and other revolving credit plans as a result of customers' overpayments.

Also exclude from all other liabilities due bills or similar instruments representing the bank's receipt of payment and the bank's liability on capital lease obligations (report in Schedule RC, item 16, "Other borrowed money").

Total. Report the sum of items 1 through 4. This amount must equal Schedule RC, item 20, "Other liabilities."

FFIEC 031 and 041 RC-G-3 RC-G - OTHER LIABILITIES (3-01)

SCHEDULE RC-H -- SELECTED BALANCE SHEET ITEMS FOR DOMESTIC OFFICES

General Instructions

Schedule RC-H is applicable only to banks filing the FFIEC 031 report forms.

For the following items, report balances outstanding in the bank's domestic offices only.

Item Instructions

Item No. Caption and Instructions

- Customers' liability to this bank on acceptances outstanding. Report the amount in domestic offices of the reporting bank of customers' liability on drafts and bills of exchange that have been accepted by the reporting bank, or by others for its account, and are outstanding. See the Glossary entry for "bankers acceptances" for further information.
- **Bank's liability on acceptances executed and outstanding.** Report the amount of liability represented by drafts and bills of exchange that have been accepted by domestic offices of the reporting bank, or by others for the account of such offices, and are outstanding. See the Glossary entry for "bankers acceptances" for further information.
- **Securities purchased under agreements to resell**. Report the amount of securities purchased under agreements to resell (as defined for Schedule RC, item 3.b) held in domestic offices of the reporting bank. See the Glossary entry for "repurchase/resale agreements" for further information.
- **Securities sold under agreements to repurchase.** Report the amount of securities sold under agreements to repurchase (as defined for Schedule RC, item 14.b) held in domestic offices of the reporting bank. See the Glossary entry for "repurchase/resale agreements" for further information.
- 5 Other borrowed money. Report the amount of other borrowed money (as defined for Schedule RC, item 16, "Other borrowed money") held in domestic offices of the reporting bank.
- 6 Net due from own foreign offices, Edge and Agreement subsidiaries, and IBFs. (See the instructions following item 7 of this schedule.)

OR

7 Net due to own foreign offices, Edge and Agreement subsidiaries, and IBFs. Report in the appropriate item *either* the "net due from" (item 6) or the "net due to" (item 7) position of

the domestic offices of the bank relative to all the bank's Edge and Agreement subsidiaries, (cont.)
foreign branches, IBFs, consolidated foreign subsidiaries, and branches in Puerto Rico and U.S. territories and possessions. These items must reflect all intrabank transactions of domestic offices with such other offices of the reporting bank, including investments (both equity and debt) in consolidated foreign subsidiaries. All other items in the Report of Condition (except for the memorandum item below) must exclude intrabank transactions.

Calculate a *single* net amount for all the intrabank due to and due from positions of the domestic offices and enter it *either* in item 6 *or* in item 7 of this schedule, depending on the nature of the single net amount.

- **Total assets**. Report the amount of total assets (as defined for Schedule RC, item 12, "Total assets") held in domestic offices of the reporting bank. For purposes of this report, "Net due from own foreign offices, Edge and Agreement subsidiaries, and IBFs" should be excluded from total assets in domestic offices.
- **Total liabilities.** Report the amount of total liabilities (as defined for Schedule RC, item 21, "Total liabilities") held in domestic offices of the reporting bank. For purposes of this report, "Net due to own foreign offices, Edge and Agreement subsidiaries, and IBFs" should be excluded from total liabilities in domestic offices.

NOTE: Items 10 through 17 include held-to-maturity and available-for-sale securities in domestic offices. Report the amortized cost of both held-to-maturity and available-for-sale debt securities in these items. Report the historical cost of investments in mutual funds and other equity securities with readily determinable fair values in these items. These amounts will have been included in the amounts reported in Schedule RC-B, columns A and C.

- 10 <u>U.S. Treasury securities</u>. Report the amortized cost of both held-to-maturity and available-for-sale U.S. Treasury securities (as defined for Schedule RC-B, item 1) held in domestic offices of the reporting bank.
- 11 <u>U.S. Government agency obligations</u>. Report the amortized cost of both held-to-maturity and available-for-sale U.S. Government agency obligations (as defined for Schedule RC-B, items 2.a and 2.b) held in domestic offices of the reporting bank. Exclude mortgage-backed securities (report in Schedule RC-H, item 13 below).
- Securities issued by states and political subdivisions in the U.S. Report the amortized cost of both held-to-maturity and available-for-sale securities issued by states and political subdivisions in the U.S. (as defined for Schedule RC-B, item 3) held in domestic offices of the reporting bank.
- 13 Mortgage-backed securities:
- **Pass-through securities.** Report in the appropriate subitem the amortized cost of both held-to-maturity and available-for-sale mortgage pass-through securities (as defined for Schedule RC-B, item 4.a) held in domestic offices of the reporting bank.

- **Issued or guaranteed by FNMA, FHLMC, or GNMA**. Report the amortized cost of both held-to-maturity and available-for-sale mortgage pass-through securities issued or guaranteed by the Federal National Mortgage Association (FNMA), the Federal Home Loan Mortgage Corporation (FHLMC), or the Government National Mortgage Association (GNMA) (as defined for Schedule RC-B, items 4.a.(1) and 4.a.(2)) held in domestic offices of the reporting bank.
- **13.a.(2)** Other pass-through securities. Report the amortized cost of both held-to-maturity and available-for-sale mortgage pass-through securities issued by non-U.S. Government issuers (as defined for Schedule RC-B, item 4.a.(3)) held in domestic offices of the reporting bank.
- 13.b Other mortgage-backed securities. Report in the appropriate subitem the amortized cost of both held-to-maturity and available-for-sale mortgage-backed securities other than pass-through securities (as defined for Schedule RC-B, item 4.b) held in domestic offices of the reporting bank.
- 13.b.(1) Issued or guaranteed by FNMA, FHLMC, or GNMA. Report the amortized cost of both held-to-maturity and available-for-sale collateralized mortgage obligations (CMOs), real estate mortgage investment conduits (REMICs), CMO and REMIC residuals, and stripped mortgage-backed securities issued by the Federal National Mortgage Association (FNMA) or the Federal Home Loan Mortgage Corporation (FHLMC) or guaranteed by the Government National Mortgage Association (GNMA) (as defined for Schedule RC-B, item 4.b.(1)) held in domestic offices of the reporting bank. Also include REMICs issued by the U.S. Department of Veterans Affairs (VA) held in domestic offices of the reporting bank.
- All other mortgage-backed securities. Report the amortized cost of both held-to-maturity and available-for-sale collateralized mortgage obligations (CMOs), real estate mortgage investment conduits (REMICs), CMO and REMIC residuals, and stripped mortgage-backed securities issued by non-U.S. Government issuers (as defined for Schedule RC-B, items 4.b.(2) and 4.b.(3)) held in domestic offices of the reporting bank.
- Other domestic debt securities (include domestic asset-backed securities). Report the amortized cost of both held-to-maturity and available-for-sale asset-backed securities (as defined for Schedule RC-B, item 5) issued by issuers in the U.S. and "Other domestic debt securities" (as defined for Schedule RC-B, item 6.a) held in domestic offices of the reporting bank.
- Foreign debt securities (include foreign assets-backed securities). Report the amortized cost of both held-to-maturity and available-for-sale asset-backed securities (as defined for Schedule RC-B, item 5) issued by non-U.S. issuers and foreign debt securities (as defined for Schedule RC-B, item 6.b) held in domestic offices of the reporting bank.
- Investments in mutual funds and other equity securities with readily determinable fair values. Report the historical cost of all investments in mutual funds and other equity securities with readily determinable fair values (as defined for Schedule RC-B, item 7) held in domestic offices of the reporting bank.
- 17 Total amortized (historical) cost of both held-to-maturity and available-for-sale securities. Report the sum of items 10 through 16. This amount must be less than or equal to Schedule RC-B, item 8, the sum of columns A and C.

18 Equity securities that do not have readily determinable fair values. Report the historical cost of equity securities without readily determinable fair values (as defined for Schedule RC-F, item 4) held in domestic offices of the reporting bank.

FFIEC 031 RC-I - IBFs

SCHEDULE RC-I -- ASSETS AND LIABILITIES OF IBFs

General Instructions

Schedule RC-I is to be completed only by banks filing the FFIEC 031 report forms that have IBFs and other "foreign" offices.

This schedule requires the reporting, on a fully consolidated basis, of the total assets and liabilities of all IBFs established by the reporting bank, i.e., including any IBFs established by the parent bank or by its Edge or Agreement subsidiaries. Both items represent components of the consolidated items reported for the consolidated bank and thus include only claims on, or liabilities to, third parties. That is, all intrabank transactions are excluded. All of the asset and debt relationships, except for those between the consolidated bank's IBFs and the IBFs of other depository institutions, are with foreign-domiciled customers or customers domiciled in Puerto Rico and U.S. territories and possessions.

Item Instructions

Item No. Caption and Instructions

- 1 <u>Total IBF assets of the consolidated bank</u>. Report the total amount outstanding of assets of the consolidated bank's IBFs that are included in Schedule RC, item 12, "Total assets."
- **Total IBF liabilities**. Report the total amount outstanding of all liabilities of the consolidated bank's IBFs that are included in Schedule RC, item 21, "Total liabilities."

FFIEC 031 and 041 RC-K - AVERAGES

SCHEDULE RC-K -- QUARTERLY AVERAGES

General Instructions

Report for the items on this schedule the average of the balances as of the close of business for each day for the calendar quarter or an average of the balances as of the close of business on each Wednesday during the calendar quarter. For days that an office of the bank (or any of its consolidated subsidiaries or branches) is closed (e.g., Saturdays, Sundays, or holidays), use the amount outstanding from the previous business day. An office is considered closed if there are no transactions posted to the general ledger as of that date.

If the bank entered into a business combination which became effective during the calendar quarter and was properly accounted for as a pooling of interests, the quarterly averages should include amounts for the acquired bank or business from the beginning of the calendar quarter. If the bank entered into a business combination which became effective during the calendar quarter and was properly accounted for as a purchase, the quarterly averages should include amounts for the acquired bank or business from the date of its acquisition through the end of the quarter only. If the bank was acquired in a transaction which became effective during the calendar quarter and push down accounting was used to account for the acquisition, the quarterly averages for the bank should include only the dollar amounts for the days (or Wednesdays) since the bank's acquisition in the numerator and the number of days (or Wednesdays) since the acquisition in the denominator. For further information on poolings of interests, purchase acquisitions, and push down accounting, see the Glossary entry for "business combinations."

If the bank began operating during the calendar quarter, the quarterly averages for the bank should include only the dollar amounts for the days (or Wednesdays) since the bank began operating in the numerator and the number of days (or Wednesdays) since the bank began operating in the denominator.

For all banks, the loan categories specified in item 6 of this schedule correspond to the loan category definitions for Schedule RC-C, part I, Loans and Leases.

Item Instructions

Item No. Caption and Instructions

ASSETS

- 1 <u>Interest-bearing balances due from depository institutions</u>. Report the quarterly average for the fully consolidated bank's interest-bearing balances due from depository institutions (as defined for Schedule RC, item 1.b, "Interest-bearing balances").
- 2 U.S. Treasury securities and U.S. Government agency obligations (excluding mortgage-backed securities). Report the quarterly average of the amortized cost of the bank's held-to-maturity and available-for-sale U.S. Treasury and Government agency obligations (as defined for Schedule RC-B, items 1 and 2, columns A and C).
- Mortgage-backed securities. Report the quarterly average of the <u>amortized cost</u> of the bank's held-to-maturity and available-for-sale mortgage-backed securities (as defined for Schedule RC-B, item 4, columns A and C).

FFIEC 031 and 041 RC-K - AVERAGES

Item No. Caption and Instructions

All other securities. Report the quarterly average of the amortized cost of the bank's held-to-maturity and available-for-sale securities issued by states and political subdivisions in the U.S., asset-backed securities, and other debt securities (as defined for Schedule RC-B, items 3, 5, and 6, columns A and C) plus the quarterly average of the historical cost of investments in mutual funds and other equity securities with readily determinable fair values (as defined for Schedule RC-B, item 7, column C).

5 <u>Federal funds sold and securities purchased under agreements to resell</u>. Report the quarterly average for federal funds sold and securities purchased under agreements to resell (as defined for Schedule RC, item 3).

6 Loans.

On the FFIEC 041 for report dates during 2001, <u>banks with total assets of less than \$25 million</u> should complete item 6.a and should report a zero or the word "none" in items 6.b through 6.d.(2) below. <u>Banks with total assets of \$25 million or more</u> should complete items 6.a through 6.d.(2) below. This \$25 million asset size test is based on the reporting bank's total assets as reflected in the Report of Condition for June 30, 2000. Beginning March 31, 2002, all banks should complete items 6.a through 6.d.(2) below.

FFIEC 041 Item No.	FFIEC 031 Item No.	Caption and Instructions
-	6.a	Loans in domestic offices:
6.a	6.a.(1)	Total loans (in domestic offices) . Report the quarterly average for total loans, net of unearned income (as defined for Schedule RC-C, part I, items 1 through 9, less item 11, column B).
6.b	6.a.(2)	Loans secured by real estate . Report the quarterly average for loans secured by real estate (in domestic offices) as defined for (Schedule RC-C, part I, item 1, column B).
-	6.a.(3)	Loans to finance agricultural production and other loans to farmers. Report the quarterly average for loans to finance agricultural production and other loans to farmers in domestic offices (as defined for Schedule RC-C, part I, item 3, column B).
6.c	6.a.(4)	Commercial and industrial loans . Report the quarterly average for commercial and industrial loans (in domestic offices) (as defined for Schedule RC-C, part I, item 4, column B).
6.d	6.a.(5)	Loans to individuals for household, family, and other personal expenditures:
6.d.(1)	6.a.(5)(a)	<u>Credit cards</u> . Report the quarterly average for credit cards. For purposes of this schedule, credit cards (in domestic offices) (as defined for Schedule RC-C, part I, item 6.a, column B).

FFIEC 031 and 041 **RC-K - AVERAGES**

FFIEC 041 Item No.	FFIEC 031 Item No.	Caption and Instructions
6.d.(2)	6.a.(5)(b)	Other. Report the quarterly average for loans (in domestic offices) to individuals for household, family, and other personal expenditures other than credit cards (as defined for Schedule RC-C, part I, items 6.b and 6.c, column B).
-	6.b	Total loans in foreign offices, Edge and Agreement subsidiaries, and IBFs. Report the quarterly average for total loans, net of unearned income (as defined for Schedule RC-C, part I, items 1 through 9, less item 11), held in the reporting bank's foreign offices, Edge and Agreement subsidiaries, and IBFs.

FFIEC 031 and 041

Item No. **Caption and Instructions**

NOTE: On the FFIEC 041, item 7 is to be completed by banks that have \$100 million or more in total assets.

- 7 **Trading assets**. Report the guarterly average for the fully consolidated bank for assets held for trading (as defined for Schedule RC, item 5).
- Lease financing receivables (net of unearned income). Report the quarterly average for 8 the fully consolidated bank's lease financing receivables, net of unearned income (as defined for Schedule RC-C, part I, item 10, column B, on the FFIEC 041; column A on the FFIEC 031).
- 9 Total assets. Report the quarterly average for the bank's total assets, as defined for "Total assets," on Schedule RC, item 12, except that this quarterly average should reflect all debt securities (not held for trading) at amortized cost and available-for-sale equity securities with readily determinable fair values at the lower of cost or fair value, and equity securities without readily determinable fair values at historical cost. In addition, to the extent that net deferred tax assets included in the bank's total assets, if any, include the deferred tax effects of any unrealized holding gains and losses on available-for-sale debt securities, these deferred tax effects may be excluded from the determination of the quarterly average for total assets. If these deferred tax effects are excluded, this treatment must be followed consistently over time.

This item is <u>not</u> the sum of items 1 through 8 above.

LIABILITIES

10 Interest-bearing transaction accounts (in domestic offices) (NOW accounts, ATS accounts, and telephone and preauthorized transfer accounts). Report the quarterly average for the three interest-bearing categories of transaction accounts (in domestic offices): NOW accounts, ATS accounts, and telephone and preauthorized transfer accounts (as defined for Schedule RC-E, (part I,) column A, "Total transaction accounts"). Exclude demand deposits which are noninterest-bearing transaction accounts. See the Glossary entry for "deposits" for the definitions of "NOW accounts," "ATS accounts," and "telephone or preauthorized transfer accounts."

FFIEC 031 and 041 RC-K - AVERAGES

Item No. Caption and Instructions

- 11 Nontransaction accounts (in domestic offices):
- **Savings deposits**. Report the quarterly average for savings deposits (as defined for Schedule RC-E, (part I), Memorandum items 2.a.(1) and 2.a.(2)). Savings deposits include money market deposit accounts (MMDAs) and other savings deposits.
- **Time deposits of \$100,000 or more**. Report the quarterly average for time deposits of \$100,000 or more (as defined for Schedule RC-E, (part I), Memorandum item 2.c).
- **Time deposits of less than \$100,000**. Report the quarterly average for time deposits of less than \$100,000 (as defined for Schedule RC-E, (part I,) Memorandum item 2.b).

FFIEC 041 FFIEC 031 Item No. Item No. Caption and Instructions - 12 Interest-bearing deposits in foreign offices, Edge and Agreement subsidiaries, and IBFs. Report the quarterly average for interest-bearing deposits in foreign offices, Edge and Agreement subsidiaries, and IBFs (as defined for Schedule RC, item 13.b.(2), "Interest-bearing"). 12 13 Federal funds purchased and securities sold under agreements to repurchase. Report the quarterly average for federal funds purchased and securities sold under agreements to repurchase (as defined for Schedule RC, item 14).

NOTE: On the FFIEC 041, item 13 is to be completed by banks that have \$100 million or more in total assets.

13 Other borrowed money. Report the quarterly average for the fully consolidated bank's other borrowed money (as defined for Schedule RC, item 16).

FFIEC 031 and 041 RC-K - AVERAGES

Memorandum

FFIEC 041

Item No. Caption and Instructions

NOTE: Memorandum item 1 is applicable only to banks filing the FFIEC 041 report. There are no Schedule RC-K memorandum items on the FFIEC 031.

1 Loans to finance agricultural production and other loans to farmers.

For report dates during 2001, Memorandum item 1 is to be completed by:

- banks with \$300 million or more in total assets, and
- banks with total assets of \$25 million or more, but less than \$300 million in total assets, and with loans to finance agricultural production and other loans to farmers (as reported in Schedule RC-C, part I, item 3, column B) exceeding five percent of total loans, net of unearned income.

Beginning March 31, 2002, Memorandum 1 is to be completed by:

- banks with \$300 million or more in total assets, and
- banks with less than \$300 million in total assets and with loans to finance agricultural production and other loans to farmers (as reported in Schedule RC-C, part I, item 3, column B) exceeding five percent of total loans, net of unearned income.

All other banks should report a zero or the word "none" in this item.

Report in this item the quarterly average for loans to finance agricultural production and other loans to farmers (as defined for Schedule RC-C, part I, item 3, column B).

SCHEDULE RC-L - DERIVATIVES AND OFF-BALANCE SHEET ITEMS

General Instructions

Schedule RC-L should be completed on a fully consolidated basis. In addition to information about derivatives, Schedule RC-L includes the following selected commitments, contingencies, and other off-balance sheet items that are <u>not</u> reportable as part of the balance sheet of the Report of Condition. Among the items <u>not</u> to be reported in this schedule are contingencies arising in connection with litigation.

Item Instructions

Item No. Caption and Instructions

Unused commitments. Report in the appropriate subitem the unused portions of commitments to make or purchase extensions of credit in the form of loans or participations in loans, lease financing receivables, or similar transactions. Exclude commitments that meet the definition of a derivative and must be accounted for in accordance with FASB Statement No. 133, which should be reported in Schedule RC-L, item 12.

Report the unused portions of all credit card lines in item 1.b. Report in items 1.a and 1.c through 1.e the unused portions of commitments for which the bank has charged a commitment fee or other consideration, or otherwise has a legally binding commitment. Such commitments are to be reported in the appropriate subitem regardless of whether they contain "material adverse change" clauses or other provisions that are intended to relieve the issuer of its funding obligations under certain conditions and regardless of whether they are unconditionally cancelable at any time. In the case of commitments for syndicated loans, report only the bank's proportional share of the commitment. Unused commitments are to be reported gross, i.e., include in this item the amounts of commitments acquired from and conveyed to others.

<u>Include</u> loan proceeds that the bank is obligated to advance, such as loan draws, construction progress payments, seasonal or living advances to farmers under prearranged lines of credit, rotating or revolving credit arrangements, including retail credit cards, or similar transactions. Forward agreements and commitments to issue a commitment at some point in the future are to be reported in this item.

In addition, include revolving underwriting facilities (RUFs), note issuance facilities (NIFs), and other similar arrangements. These are facilities under which a borrower can issue on a revolving basis short-term paper in its own name, but for which the underwriting banks have a legally binding commitment either to purchase any notes the borrower is unable to sell by the rollover date or to advance funds to the borrower.

1.a Revolving, open-end lines secured by 1-4 family residential properties. Report the unused portions of commitments to extend credit under revolving, open-end lines of credit secured by 1-4 family residential properties. These lines, commonly known as home equity lines, are typically secured by a junior lien and are usually accessible by check or credit card.

- 1.b <u>Credit card lines</u>. Report the unused portions of all commitments to extend credit both to individuals for household, family, and other personal expenditures and to commercial or industrial enterprises through credit cards. Exclude home equity lines accessible through credit cards. Banks may report unused credit card lines as of the end of their customers' last monthly billing cycle prior to the report date or as of the report date.
- **1.c Commercial real estate, construction and land development**. Report in the appropriate subitem the unused portions of commitments to extend credit for commercial real estate, construction, and land development activities.
- 1.c.(1) Commitments to fund loans secured by real estate. Report the unused portions of commitments to extend credit for the specific purpose of financing commercial and multifamily residential properties (e.g., business and industrial properties, hotels, motels, churches, hospitals, and apartment buildings), provided that such commitments, when funded, would be reportable as either loans secured by multifamily residential properties in Schedule RC-C, part I, item 1.d, or loans secured by nonfarm nonresidential properties in Schedule RC-C, part I, item 1.e.

Also include the unused portions of commitments to extend credit for the specific purpose of financing land development (i.e., the process of improving land - laying sewers, water pipes, etc.) preparatory to erecting new structures or the on-site construction of industrial, commercial, residential, or farm buildings, provided that such commitments, when funded, would be reportable as loans secured by real estate in Schedule RC-C, part I, item 1.a, "Construction, land development, and other land loans." For this item, "construction" includes not only construction of new structures, but also additions or alterations to existing structures and the demolition of existing structures to make way for new structures. Also include in this item loan proceeds the bank is obligated to advance as construction progress payments.

Do <u>not</u> include general lines of credit that a borrower, at its option, may draw down to finance construction and land development (report in Schedule RC-L, item 1.c.(2) or item 1.e, below, as appropriate).

1.c.(2) Commitments to fund loans not secured by real estate. Report the unused portions of all commitments to extend credit for the specific purpose of financing commercial and residential real estate activities, e.g., acquiring, developing, and renovating commercial and residential real estate, provided that such commitments, when funded, would be reportable as "Commercial and industrial loans" in Schedule RC-C, part I, item 4, or as "Other loans" in Schedule RC-C, part I, item 9. Include in this item loan proceeds the bank is obligated to advance as construction progresses.

Such commitments generally may include:

- (1) commitments to extend credit for the express purpose of financing real estate ventures as evidenced by loan documentation or other circumstances connected with the loan; or
- (2) commitments made to organizations or individuals 80 percent of whose revenue or assets are derived from or consist of real estate ventures or holdings.

- 1.c.(2) Exclude from this item all commitments that, when funded, would be reportable as
 (cont.) "Loans secured by real estate" in Schedule RC-C, part I, item 1. Also exclude commitments
 made to commercial and industrial firms where the sole purpose for the financing is to
 construct a factory or office building to house the company's operations or employees.
 - **1.d Securities underwriting.** Report the unsold portion of the reporting bank's own takedown in securities underwriting transactions. Include NIFs and RUFs in this item.
 - **1.e** Other unused commitments. Report the unused portion of all other commitments not reportable above. Include commitments to extend credit through overdraft facilities or commercial lines of credit and retail check credit and related plans.

Also include commitments to extend credit secured by 1-4 family residential properties, except (a) revolving, open-end lines of credit secured by 1-4 family residential properties (e.g., home equity lines) which should be reported in Schedule RC-L, item 1.a, above, (b) commitments for 1-4 family residential construction and land development loans (that are secured by such properties) which should be reported in Schedule RC-L, item 1.c.(1), above, and (c) commitments that meet the definition of a derivative and must be accounted for in accordance with FASB Statement No. 133, which should be reported in Schedule RC-L, item 12.

2 and 3 General Instructions for Standby Letters of Credit -- Originating banks must report in items 2 and 3 the full amount outstanding and unused of financial and performance standby letters of credit, respectively. Include those standby letters of credit that are collateralized by cash on deposit, that have been acquired from others, and in which participations have been conveyed to others where (a) the originating and issuing bank is obligated to pay the full amount of any draft drawn under the terms of the standby letter of credit and (b) the participating banks have an obligation to partially or wholly reimburse the originating bank, either directly in cash or through a participation in a loan to the account party.

For syndicated standby letters of credit where each bank has a direct obligation to the beneficiary, each bank must report only its share in the syndication. Similarly, if several banks participate in the issuance of a standby letter of credit under a <u>bona fide</u> binding agreement which provides that (a) regardless of any event, each participant shall be liable only up to a certain percentage or to a certain amount and (b) the beneficiary is advised and has agreed that each participating bank is only liable for a certain portion of the entire amount, each bank shall report only its proportional share of the total standby letter of credit.

For a financial or performance standby letter of credit that is in turn backed by a financial standby letter of credit issued by another bank, each bank must report the entire amount of the standby letter of credit it has issued in either item 2 or item 3 below, as appropriate. The amount of the reporting bank's financial or performance standby letter of credit that is backed by the other bank's financial standby letter of credit must also be reported in either item 2.a or 3.a, as appropriate, since the backing of standby letters of credit has substantially the same effect as the conveying of participations in standby letters of credit.

On the FFIEC 031, also include all financial and performance guarantees issued by foreign offices of the reporting bank pursuant to Federal Reserve Regulation K or Section 347.103(a)(1) of the FDIC Rules and Regulations.

Einancial standby letters of credit (and foreign office guarantees -- for the FFIEC 031). Report the amount outstanding and unused as of the report date of all financial standby letters of credit (and all legally binding commitments to issue financial standby letters of credit) issued by any office of the bank. A financial standby letter of credit irrevocably obligates the bank to pay a third-party beneficiary when a customer (account party) fails to repay an outstanding loan or debt instrument. (See the Glossary entry for "letter of credit" for further information.)

Exclude from financial standby letters of credit:

- (1) Financial standby letters of credit where the beneficiary is a consolidated subsidiary of the reporting bank.
- (2) Performance standby letters of credit.
- (3) Signature or endorsement guarantees of the type associated with the clearing of negotiable instruments or securities in the normal course of business.
- 2.a Amount of financial standby letters of credit conveyed to others. Report that portion of the bank's total contingent liability for financial standby letters of credit reported in Schedule RC-L, item 2, above, that the bank has conveyed to others. Also include that portion of the reporting bank's financial standby letters of credit that are backed by other banks' financial standby letters of credit, as well as the portion that participating banks have reparticipated to others. Participations and backings may be for any part or all of a given obligation.
- Performance standby letters of credit (and foreign office guarantees -- for the FFIEC 031). Report the amount outstanding and unused as of the report date of all performance standby letters of credit (and all legally binding commitments to issue performance standby letters of credit) issued by any office of the bank. A performance standby letter of credit irrevocably obligates the bank to pay a third-party beneficiary when a customer (account party) fails to perform some contractual non-financial obligation. (See the Glossary entry for "letter of credit" for further information.)

Exclude from performance standby letters of credit:

- (1) Performance standby letters of credit where the beneficiary is a consolidated subsidiary of the reporting bank.
- (2) Financial standby letters of credit.
- (3) Signature or endorsement guarantees of the type associated with the clearing of negotiable instruments or securities in the normal course of business.
- Amount of performance standby letters of credit conveyed to others. Report that portion of the bank's total contingent liability for performance standby letters of credit reported in Schedule RC-L, item 3, above, that the bank has conveyed to others. Also include that portion of the reporting bank's performance standby letters of credit that are backed by other banks' financial standby letters of credit, as well as the portion that participating banks have reparticipated to others. Participations and backings may be for any part or all of a given obligation.

Commercial and similar letters of credit. Report the amount outstanding and unused as of the report date of issued or confirmed commercial letters of credit, travelers' letters of credit not issued for money or its equivalent, and all similar letters of credit, but excluding standby letters of credit (which are to be reported in Schedule RC-L, items 2 and 3, above). (See the Glossary entry for "letter of credit.") Legally binding commitments to issue commercial letters of credit are to be reported in this item.

Travelers' letters of credit and other letters of credit <u>issued</u> for money or its equivalent by the reporting bank or its agents should be reported as demand deposit liabilities in Schedule RC-E.

NOTE: On the FFIEC 041, item 5 is not applicable to banks that have less than \$100 million in total assets.

Participations in acceptances conveyed to others by the reporting bank. Report the amount of all participations conveyed to others by the reporting (accepting) bank in its acceptances that are outstanding regardless of the nature of the participation agreement and regardless of the system of debits and credits used to reflect the agreement on the reporting (accepting) bank's books. Thus, participations in acceptances conveyed to others by the reporting (accepting) bank are to include both those that provide for participation in the risk of loss in the event of default by the account party at the time of maturity and those that provide for participation in putting the holder of the acceptance in funds at the maturity of the acceptance. Also report the amount of participations in acceptances of other (accepting) banks that the reporting bank has acquired and subsequently conveyed to others.

Do <u>not</u> reduce the reporting (accepting) bank's "Bank's liability on acceptances executed and outstanding" (Schedule RC, item 18) or "Customers' liability to this bank on acceptances outstanding" (Schedule RC, item 9) by the amount of such participations <u>regardless</u> of the nature of the agreement and <u>regardless</u> of the system of debits and credits used to reflect the agreement on the reporting (accepting) bank's books. (See the Glossary entry for "bankers acceptances" for a detailed description of the required treatment of bankers acceptances in the Report of Condition.)

- Securities lent. Report the appropriate amount of all securities lent against collateral or on an uncollateralized basis. Report the book value of bank-owned securities that have been lent. In addition, for customers who have been indemnified against any losses by the reporting bank, report the market value as of the report date of such customers' securities, including customers' securities held in the reporting bank's trust department, that have been lent. If the reporting bank has indemnified its customers against any losses on their securities that have been lent by the bank, the commitment to indemnify -- either through a standby letter of credit or other means -- should not be reported in any other item on Schedule RC-L.
- Credit derivatives. Report in the appropriate subitem the notional amount and fair value of all credit derivatives. Credit derivatives are arrangements that allow one party (the "beneficiary") to transfer the credit risk of a "reference asset" to another party (the "guarantor"). Banks should include the notional amounts of credit default swaps, total rate of return swaps, and other credit derivative instruments.

All transactions within the consolidated bank should be reported on a net basis, i.e., intrabank (cont.) transactions should not be reported in this item. No other netting of contracts is permitted for purposes of this item. Therefore, do not net: (1) credit derivatives with third parties on which the reporting bank is the beneficiary against credit derivatives with third parties on which the reporting bank is the guarantor, or (2) contracts subject to bilateral netting agreements. The notional amount of credit derivatives should not be included in Schedule RC-L, items 12 through 14, and the fair value of credit derivatives should not be included in Schedule RC-L, item 15.

As defined in FASB Statement No. 133, fair value is the amount at which an asset (liability) could be bought (incurred) or sold (settled) in a current transaction between willing parties, that is, other than in a forced or liquidation sale. Quoted market prices in active markets are the best evidence of fair value and should be used as the basis for the measurement, if available. If a quoted market price is available, the fair value is the product of the number of trading units times that market price. If a quoted market price is not available, the estimate of fair value should be based on the best information available in the circumstances. The estimate of fair value should consider prices for similar assets or similar liabilities and the results of valuation techniques to the extent available in the circumstances. For purposes of this item, the reporting bank should determine the fair value of its credit derivative contracts in the same manner that it determines the fair value of these contracts for other financial reporting purposes.

- 7.a Notional amount of credit derivatives on which the reporting bank is the guarantor.

 Report the notional amount (stated in U.S. dollars) of all credit derivatives on which the bank has extended credit protection to other parties.
- **7.a.(1)** Gross positive fair value. Report the total fair value of those credit derivatives reported in Schedule RC-L, item 7.a, above, with positive fair values.
- **7.a.(2)** Gross negative fair value. Report the total fair value of those credit derivatives reported in Schedule RC-L, item 7.a, above, with negative fair values. Report the total fair value as an absolute value; do not enclose the total fair value in parentheses or use a minus (-) sign.
- 7.b Notional amount of credit derivatives on which the reporting bank is the beneficiary.

 Report the notional amount (stated in U.S. dollars) of all credit derivatives on which the bank has obtained a guarantee against credit losses from other parties.
- **7.b.(1)** Gross positive fair value. Report the total fair value of those credit derivatives reported in Schedule RC-L, item 7.b, above, with positive fair values.
- **Gross negative fair value.** Report the total fair value of those credit derivatives reported in Schedule RC-L, item 7.b, above, with negative fair values. Report the total fair value as an absolute value; do <u>not enclose</u> the total fair value in parentheses or use a minus (-) sign.
- Spot foreign exchange contracts. Report the gross amount (stated in U.S. dollars) of all spot contracts committing the reporting bank to purchase foreign (non-U.S.) currencies and U.S. dollar exchange that are outstanding as of the report date. All transactions within the consolidated bank should be reported on a net basis.

A spot contract is an agreement for the immediate delivery, usually within two business days, (cont.) of a foreign currency at the prevailing cash market rate. Spot contracts are considered outstanding (i.e., open) until they have been cancelled by acquisition or delivery of the underlying currencies.

Only one side of a spot foreign exchange contract is to be reported. In those transactions where foreign (non-U.S.) currencies are bought or sold against U.S. dollars, report only that side of the transaction that involves the foreign (non-U.S.) currency. For example, if the reporting bank enters into a spot contract which obligates the bank to purchase U.S. dollar exchange against which it sells Japanese yen, then the bank would report (in U.S. dollar equivalent values) the amount of Japanese yen sold in this item. In cross-currency spot foreign exchange transactions, which involve the purchase and sale of two non-U.S. currencies, only the purchase side is to be reported (in U.S. dollar equivalent values).

All other off-balance sheet liabilities. Report all significant types of off-balance sheet liabilities not covered in other items of this schedule. Exclude all items which are required to be reported as liabilities on the balance sheet of the Report of Condition (Schedule RC), contingent liabilities arising in connection with litigation in which the reporting bank is involved, commitments to purchase property being acquired for lease to others (report in Schedule RC-L, item 1.e, above), and signature and endorsement guarantees of the type associated with the regular clearing of negotiable instruments or securities in the normal course of business.

Report only the aggregate amount of those types of "other off-balance sheet liabilities" that individually exceed 10 percent of the bank's total equity capital reported in Schedule RC, item 28. If the bank has no types of "other off-balance sheet liabilities" that individually exceed 10 percent of total equity capital, report a zero or the word "none."

Disclose in items 9.a through 9.f each type of "other off-balance sheet liabilities" reportable in this item, and the dollar amount of the off-balance sheet liability, that individually exceeds 25 percent of the bank's total equity capital reported in Schedule RC, item 28. For each type of off-balance sheet liability that exceeds this disclosure threshold for which a preprinted caption has not been provided, describe the liability with a clear but concise caption in items 9.c through 9.f. These descriptions should not exceed 50 characters in length (including spacing between words).

Include as other off-balance sheet liabilities:

- (1) Securities borrowed against collateral (other than cash), or on an uncollateralized basis, for such purposes as pledge against deposit liabilities or delivery against short sales. Report borrowed securities that are fully collateralized by similar securities of equivalent value at market value at the time they are borrowed. Report other borrowed securities at market value as of the report date. (Report the amount of securities borrowed in Schedule RC-L, item 9.a, if this amount exceeds 25 percent of the bank's total equity capital reported in Schedule RC, item 28.)
- (2) Commitments to purchase when-issued securities that are excluded from the requirements of FASB Statement No. 133 (and therefore not reported as forward contracts in Schedule RC-L, item 12.b, below). (Report the amount of these commitments in Schedule RC-L, item 9.b, if this amount exceeds 25 percent of the bank's total equity capital reported in Schedule RC, item 28.)

- **9** (cont.)
- (3) Standby letters of credit issued by a Federal Home Loan Bank on behalf of the reporting bank, which is the account party on the letters of credit and therefore is obligated to reimburse the issuing Federal Home Loan Bank for all payments made under the standby letters of credit.
- (4) Financial guarantee insurance which insures the timely payment of principal and interest on bond issues.
- (5) Letters of indemnity other than those issued in connection with the replacement of lost or stolen or official checks.
- (6) Shipside or dockside guarantees or similar guarantees relating to missing bills of lading or title documents and other document guarantees that facilitate the replacement of lost or stolen official checks.
- All other off-balance sheet assets. Report to the extent feasible and practicable all significant types of off-balance sheet assets not covered in other items of this schedule. Exclude all items which are required to be reported as assets on the balance sheet of the Report of Condition (Schedule RC), contingent assets arising in connection with litigation in which the reporting bank is involved, and assets held in or administered by the reporting bank's trust department.

Report only the aggregate amount of those types of "other off-balance sheet assets" that individually exceed 10 percent of the bank's total equity capital reported in Schedule RC, item 28. If the bank has no types of "other off-balance sheet assets" that individually exceed 10 percent of total equity capital for which the reporting is feasible and practicable, report a zero or the word "none."

Disclose in items 10.a through 10.e each type of "other off-balance sheet assets" reportable in this item, and dollar amount of the off-balance sheet asset, that individually exceeds 25 percent of the bank's total equity capital reported in Schedule RC, item 28. For each type of off-balance sheet asset that exceeds this disclosure threshold for which a preprinted caption has not been provided, describe the asset with a clear and concise caption in items 10.b through 10.e. These descriptions should not exceed 50 characters in length (including space between words).

Include as "other off-balance sheet assets" such items as:

- (1) Commitments to sell when-issued securities that are excluded from the requirements of FASB Statement No. 133 (and therefore not reported as forward contracts in Schedule RC-L, item 12.b, below). (Report the amount of these commitments in Schedule RC-L, item 10.a, if this amount exceeds 25 percent of the bank's total equity capital reported in Schedule RC, item 28.)
- (2) Internally developed intangible assets.

Year-to-date merchant credit card sales volume. Merchant processing is the settlement of credit card transactions for merchants. It is a separate and distinct business line from credit card issuing. Merchant processing activity involves obtaining authorization for credit card sales transactions, gathering sales information from the merchant, collecting funds from the card-issuing bank or business, and crediting the merchants' accounts for their sales.

An <u>acquiring bank</u> is a bank that initiates and maintains contractual agreements with merchants, agent banks, and third parties (e.g., independent sales organizations and member service providers) for the purpose of accepting and processing credit card transactions. An acquiring bank has liability for chargebacks for the merchants' sales activity.

An <u>agent bank with risk</u> is a bank that, by agreement, participates in another bank's merchant credit card acceptance program. An agent bank with risk assumes liability for chargebacks for all or a portion of the loss for the merchants' sales activity.

For purposes of items 11.a and 11.b, banks should include credit card sales transactions involving bank credit cards, e.g., MasterCard and Visa.

For banks with total assets of \$10 billion or more, the year-to-date sales volume may be reported to the nearest million, with zeros reported in the thousands column, rather than to the nearest thousand.

- 11.a Sales for which the reporting bank is the acquiring bank. Report the year-to-date volume of sales (in U.S. dollars) generated through the bank's merchant processing activities where the reporting bank is the acquiring bank. This will include amounts processed for merchants contracted directly by the acquiring bank, amounts processed for agent banks with risk, and amounts processed for third parties (e.g., independent sales organizations and member service providers). Banks that are required to report sales data to the credit card associations of which they are members (e.g., MasterCard and Visa) should measure sales volume in the same manner for purposes of this item.
- 11.b Sales for which the reporting bank is the agent bank with risk. Report the year-to-date volume of sales (in U.S. dollars) generated through the bank's merchant processing activities where the reporting bank is acting as an agent bank with risk. Include all sales transactions for which the acquiring bank with whom the reporting bank contracted may hold the bank responsible.
- Gross amounts (e.g., notional amounts) of derivatives. Report in the appropriate column and subitem the gross par value (stated in U.S. dollars) (e.g., for futures, forwards, and option contracts) or the notional amount (stated in U.S. dollars) (e.g., for forward rate agreements and swaps), as appropriate, of all contracts that meet the definition of a derivative and must be accounted for in accordance with FASB Statement No. 133. Report each contract according to its underlying risk exposure: (a) interest rate, (b) foreign exchange, (c) equity, or (d) commodity and other. Contracts with multiple risk characteristics should be classified based upon the predominant risk characteristics at the origination of the derivative. However, exclude from Schedule RC-L, items 12 through 15, all credit derivatives, which should be reported in Schedule RC-L, item 7, above.

The notional amount or par value to be reported for a derivative contract with a multiplier (cont.) component is the contract's effective notional amount or par value. For example, a swap contract with a stated notional amount of \$1,000,000 whose terms called for quarterly settlement of the difference between 5% and LIBOR multiplied by 10 has an effective notional amount of \$10,000,000.

All transactions within the consolidated bank should be reported on a net basis. No other netting of contracts is permitted for purposes of this item. Therefore, do not net: (1) obligations of the reporting bank to purchase from third parties against the bank's obligations to sell to third parties, (2) written options against purchased options, or (3) contracts subject to bilateral netting agreements.

For each column, the sum of items 12.a through 12.e must equal the sum of items 13 and 14.

Column Instructions

Column A, Interest Rate Contracts: Interest rate contracts are contracts related to an interest-bearing financial instrument or whose cash flows are determined by referencing interest rates or another interest rate contract (e.g., an option on a futures contract to purchase a Treasury bill). These contracts are generally used to adjust the bank's interest rate exposure or, if the bank is an intermediary, the interest rate exposure of others. Interest rate contracts include interest rate futures, single currency interest rate swaps, basis swaps, forward rate agreements, and interest rate options, including caps, floors, collars, and corridors.

Exclude contracts involving the exchange of one or more foreign currencies (e.g., cross-currency swaps and currency options) and other contracts whose predominant risk characteristic is foreign exchange risk, which are to be reported in column B as foreign exchange contracts.

Unsettled securities transactions that exceed the regular way settlement time limit that is customary in each relevant market must be reported as forward contracts in Schedule RC-L, item 12.b.

Column B, Foreign Exchange Contracts: Foreign exchange contracts are contracts to purchase foreign (non-U.S.) currencies and U.S. dollar exchange in the forward market, i.e., on an organized exchange or in an over-the-counter market. A purchase of U.S. dollar exchange is equivalent to a sale of foreign currency. Foreign exchange contracts include cross-currency interest rate swaps where there is an exchange of principal, forward foreign exchange contracts (usually settling three or more business days from trade date), and currency futures and currency options. Exclude spot foreign exchange contracts, which are to be reported in Schedule RC-L, item 8.

Only one side of a foreign currency transaction is to be reported. In those transactions where foreign (non-U.S.) currencies are bought or sold against U.S. dollars, report only that side of the transaction that involves the foreign (non-U.S.) currency. For example, if the reporting bank enters into a futures contract which obligates the bank to purchase U.S. dollar exchange against which it sells Japanese yen, then the bank would report (in U.S. dollar equivalent values) the amount of Japanese yen sold in Schedule RC-L, item 12.a. In cross-currency transactions, which involve the purchase and sale of two non-U.S. currencies, only the purchase side is to be reported.

All amounts in column B are to be reported in U.S. dollar equivalent values.

Caption and Instructions Item No.

12 Column C, Equity Derivative Contracts: Equity derivative contracts are contracts that have a return, or a portion of their return, linked to the price of a particular equity or to an index of (cont.) equity prices, such as the Standard and Poor's 500.

> The contract amount to be reported for equity derivative contracts is the quantity, e.g., number of units, of the equity instrument or equity index contracted for purchase or sale multiplied by the contract price of a unit.

Column D, Commodity and Other Contracts: Commodity contracts are contracts that have a return, or a portion of their return, linked to the price of or to an index of precious metals, petroleum, lumber, agricultural products, etc. Commodity and other contracts also include any other contracts that are not reportable as interest rate, foreign exchange, or equity derivative contracts.

The contract amount to be reported for commodity and other contracts is the quantity, e.g., number of units, of the commodity or product contracted for purchase or sale multiplied by the contract price of a unit.

The notional amount to be reported for commodity contracts with multiple exchanges of principal is the contractual amount multiplied by the number of remaining payments (i.e., exchanges of principal) in the contract.

12.a **Futures contracts.** Futures contracts represent agreements for delayed delivery of financial instruments or commodities in which the buyer agrees to purchase and the seller agrees to deliver, at a specified future date, a specified instrument at a specified price or yield. Futures contracts are standardized and are traded on organized exchanges that act as the counterparty to each contract.

> Report, in the appropriate column, the aggregate par value of futures contracts that have been entered into by the reporting bank and are outstanding (i.e., open contracts) as of the report date. Do not report the par value of financial instruments intended to be delivered under such contracts if this par value differs from the par value of the contracts themselves.

Contracts are outstanding (i.e., open) until they have been cancelled by acquisition or delivery of the underlying financial instruments or by offset. Offset is the liquidating of a purchase of futures through the sale of an equal number of contracts of the same delivery month on the same underlying instrument on the same exchange, or the covering of a short sale of futures through the purchase of an equal number of contracts of the same delivery month on the same underlying instrument on the same exchange.

Column A, Interest Rate Futures: Report futures contracts committing the reporting bank to purchase or sell financial instruments and whose predominant risk characteristic is interest rate risk. Some of the more common interest rate futures include futures on 90-day U.S. Treasury bills; 12-year GNMA pass-through securities; and 2-, 4-, 6-, and 10-year U.S. Treasury notes.

Column B, Foreign Exchange Futures: Report the gross amount (stated in U.S. dollars) of all futures contracts committing the reporting bank to purchase foreign (non-U.S.) currencies and U.S. dollar exchange and whose predominant risk characteristic is foreign exchange risk.

12.a A currency futures contract is a standardized agreement for delayed delivery of a foreign (cont.) (non-U.S.) currency or U.S. dollar exchange in which the buyer agrees to purchase and the seller agrees to deliver, at a specified future date, a specified amount at a specified exchange rate.

Column C, Equity Derivative Futures: Report futures contracts committing the reporting bank to purchase or sell equity securities or instruments based on equity indexes such as the Standard and Poor's 500 or the Nikkei.

Column D, Commodity and Other Futures: Report the contract amount for all futures contracts committing the reporting bank to purchase or sell commodities such as agricultural products (e.g., wheat, coffee), precious metals (e.g., gold, platinum), and non-ferrous metals (e.g., copper, zinc). Include any other futures contract that is not reportable as an interest rate, foreign exchange, or equity derivative contract in column A, B, or C.

Forward contracts. Forward contracts represent agreements for delayed delivery of financial instruments or commodities in which the buyer agrees to purchase and the seller agrees to deliver, at a specified future date, a specified instrument or commodity at a specified price or yield. Forward contracts are not traded on organized exchanges and their contractual terms are not standardized.

Report the aggregate par value of forward contracts that have been entered into by the reporting bank and are outstanding (i.e., open contracts) as of the report date. Do not report the par value of financial instruments intended to be delivered under such contracts if this par value differs from the par value of the contracts themselves.

Contracts are outstanding (i.e., open) until they have been cancelled by acquisition or delivery of the underlying financial instruments or settled in cash. Such contracts can only be terminated, other than by receipt of the underlying asset, by agreement of both buyer and seller.

Include as forward contracts commitments to purchase and sell when-issued securities that are not excluded from the requirements of FASB Statement No. 133 as a regular-way security trade. Report such contracts on a gross basis (except that banks may net purchases and sales of the identical security with the same party). Report commitments to purchase when-issued securities that are excluded from the requirements of FASB Statement No. 133 as "Other off-balance sheet liabilities" in Schedule RC-L, item 9, and commitments to sell when-issued securities that are excluded from the requirements of FASB Statement No. 133 as "Other off-balance sheet assets" in Schedule RC-L, item 10, subject to the existing reporting thresholds for these two items.

Column A, Interest Rate Forwards: Report forward contracts committing the reporting bank to purchase or sell financial instruments and whose predominant risk characteristic is interest rate risk. Include in this item firm commitments (i.e., commitments that have a specific interest rate or price, selling date, and dollar amount) to sell loans secured by 1-to-4 family residential properties that meet the definition of a derivative contract under FASB Statement No. 133.

Column B, Foreign Exchange Forwards: Report the gross amount (stated in U.S. dollars) of all forward contracts committing the reporting bank to purchase foreign (non-U.S.) currencies and U.S. dollar exchange and whose predominant risk characteristic is foreign exchange risk.

12.b A forward foreign exchange contract is an agreement for delayed delivery of a foreign (cont.) (non-U.S.) currency or U.S. dollar exchange in which the buyer agrees to purchase and the seller agrees to deliver, at a specified future date, a specified amount at a specified exchange rate.

Column C, Equity Derivative Forwards: Report forward contracts committing the reporting bank to purchase or sell equity instruments.

Column D, Commodity and Other Forwards: Report the contract amount for all forward contracts committing the reporting bank to purchase or sell commodities such as agricultural products (e.g., wheat, coffee), precious metals (e.g., gold, platinum), and non-ferrous metals (e.g., copper, zinc). Include any other forward contract that is not reportable as an interest rate, foreign exchange, or equity derivative contract in column A, B, or C.

Exchange-traded option contracts. Option contracts convey either the right or the obligation, depending upon whether the reporting bank is the purchaser or the writer, respectively, to buy or sell a financial instrument or commodity at a specified price by a specified future date. Some options are traded on organized exchanges.

The buyer of an option contract has, for compensation (such as a fee or premium), acquired the right (or option) to sell to, or purchase from, another party some financial instrument or commodity at a stated price on a specified future date. The seller of the contract has, for such compensation, become obligated to purchase or sell the financial instrument or commodity at the option of the buyer of the contract. A put option contract obligates the seller of the contract. A call option contract obligates the seller of the contract to sell some financial instrument or commodity at the option of the buyer of the contract.

Written options. Report in this item the aggregate par value of the financial instruments or commodities that the reporting bank has, for compensation (such as a fee or premium), obligated itself to either purchase or sell under exchange-traded option contracts that are outstanding as of the report date.

Column A, Written Exchange-Traded Interest Rate Options: For exchange-traded option contracts obligating the reporting bank to either purchase or sell an interest rate futures contract and whose predominant risk characteristic is interest rate risk, report the par value of the financial instrument underlying the futures contract. An example of such a contract is a Chicago Board Options Exchange option on the 13-week Treasury bill rate.

Column B, Written Exchange-Traded Foreign Exchange Options: Report in this item the gross amount (stated in U.S. dollars) of foreign (non-U.S.) currency and U.S. dollar exchange that the reporting bank has, for compensation, obligated itself to either purchase or sell under exchange-traded option contracts whose predominant risk characteristic is foreign exchange risk. In the case of option contracts obligating the reporting bank to either purchase or sell a foreign exchange futures contract, report the gross amount (stated in U.S. dollars) of the foreign (non-U.S.) currency underlying the futures contract. Exchange-traded options on major currencies such as the Japanese Yen and British Pound Sterling and options on futures contracts of major currencies are examples of such contracts.

12.c.(1) Column C, Written Exchange-Traded Equity Derivative Options: Report the contract amount for those exchange-traded option contracts where the reporting bank has obligated itself, for compensation, to purchase or sell an equity instrument or equity index.

Column D, Written Exchange-Traded Commodity and Other Exchange-Traded Options: Report the contract amount for those exchange-traded option contracts where the reporting bank has obligated itself, for compensation, to purchase or sell a commodity or product. Include any other written, exchange-traded option that is not reportable as an interest rate, foreign exchange, or equity derivative contract in column A, B, or C.

Purchased options. Report in this item the aggregate par value of the financial instruments or commodities that the reporting bank has, for a fee or premium, purchased the right to either purchase or sell under exchange-traded option contracts that are outstanding as of the report date.

Column A, Purchased Exchange-Traded Interest Rate Options: For exchange-traded option contracts giving the reporting bank the right to either purchase or sell an interest rate futures contract and whose predominant risk characteristic is interest rate risk, report the par value of the financial instrument underlying the futures contract. An example of such a contract is a Chicago Board Options Exchange option on the 13-week Treasury bill rate.

Column B, Purchased Exchange-Traded Foreign Exchange Options: Report in this item the gross amount (stated in U.S. dollars) of foreign (non-U.S.) currency and U.S. dollar exchange that the reporting bank has, for a fee, purchased the right to either purchase or sell under exchange-traded option contracts whose predominant risk characteristic is foreign exchange risk. In the case of option contracts giving the reporting bank the right to either purchase or sell a currency futures contract, report the gross amount (stated in U.S. dollars) of the foreign (non-U.S.) currency underlying the futures contract. Exchange-traded options on major currencies such as the Japanese Yen and British Pound Sterling and options on futures contracts of major currencies are examples of such contracts.

Column C, Purchased Exchange-Traded Equity Derivative Options: Report the contract amount of those exchange-traded option contracts where the reporting bank has, for a fee, purchased the right to purchase or sell an equity instrument or equity index.

Column D, Purchased Exchange-Traded Commodity and Other Exchange-Traded Options: Report the contract amount for those exchange-traded option contracts where the reporting bank has, for a fee, purchased the right to purchase or sell a commodity or product. Include any other purchased, exchange-traded option that is not reportable as an interest rate, foreign exchange, or equity derivative contract in column A, B, or C.

Over-the-counter option contracts. Option contracts convey either the right or the obligation, depending upon whether the reporting bank is the purchaser or the writer, respectively, to buy or sell a financial instrument or commodity at a specified price by a specified future date. Options can be written to meet the specialized needs of the counterparties to the transaction. These customized option contracts are known as over-the-counter (OTC) options. Thus, over-the-counter option contracts include all option contracts not traded on an organized exchange.

12.d The buyer of an option contract has, for compensation (such as a fee or premium), acquired the right (or option) to sell to, or purchase from, another party some financial instrument or commodity at a stated price on a specified future date. The seller of the contract has, for such compensation, become obligated to purchase or sell the financial instrument or commodity at the option of the buyer of the contract. A put option contract obligates the seller of the contract. A call option contract obligates the seller of the contract to some financial instrument or commodity at the option of the buyer of the contract.

In addition, swaptions, i.e., options to enter into a swap contract, and contracts known as caps, floors, collars, and corridors should be reported as options.

Commitments to lend that meet the definition of a derivative and must be accounted for in accordance with FASB Statement No. 133 are considered options for purposes of Schedule RC-L, item 12. All other commitments to lend should be reported in Schedule RC-L, item 1.

Written options. Report in this item the aggregate par value of the financial instruments or commodities that the reporting bank has, for compensation (such as a fee or premium), obligated itself to either purchase or sell under OTC option contracts that are outstanding as of the report date. Also report an aggregate notional amount for written caps, floors, and swaptions and for the written portion of collars and corridors.

Column A, Written OTC Interest Rate Options: Interest rate options include options to purchase and sell interest-bearing financial instruments and whose predominant risk characteristic is interest rate risk as well as contracts known as caps, floors, collars, corridors, and swaptions. Include in this item the notional principal amount for interest rate caps and floors that the reporting bank sells. For interest rate collars and corridors, report a notional amount for the written portion of the contract in Schedule RC-L, item 12.d.(1), column A, and for the purchased portion of the contract in Schedule RC-L, item 12.d.(2), column A.

Column B, Written OTC Foreign Exchange Options: A written currency option contract conveys the obligation to exchange two different currencies at a specified exchange rate. Report in this item the gross amount (stated in U.S. dollars) of foreign (non-U.S.) currency and U.S. dollar exchange that the reporting bank has, for compensation, obligated itself to either purchase or sell under OTC option contracts whose predominant risk characteristic is foreign exchange risk.

Column C, Written OTC Equity Derivative Options: Report the contract amount for those OTC option contracts where the reporting bank has obligated itself, for compensation, to purchase or sell an equity instrument or equity index.

Column D, Written OTC Commodity and Other OTC Options: Report the contract amount for those OTC option contracts where the reporting bank has obligated itself, for compensation, to purchase or sell a commodity or product. Include any other written, OTC option that is not reportable as an interest rate, foreign exchange, or equity derivative contract in column A, B, or C.

Purchased options. Report in this item the aggregate par value of the financial instruments or commodities that the reporting bank has, for a fee or premium, purchased the right to either purchase or sell under OTC option contracts that are outstanding as of the report date. Also report an aggregate notional amount for purchased caps, floors, and swaptions and for the purchased portion of collars and corridors.

Column A, Purchased OTC Interest Rate Options: Interest rate options include options to purchase and sell interest-bearing financial instruments and whose predominant risk characteristic is interest rate risk as well as contracts known as caps, floors, collars, corridors, and swaptions. Include in this item the notional principal amount for interest rate caps and floors that the reporting bank purchases. For interest rate collars and corridors, report a notional amount for the written portion of the contract in Schedule RC-L, item 12.d.(1), column A, and for the purchased portion of the contract in Schedule RC-L, item 12.d.(2), column A.

Column B, Purchased OTC Foreign Exchange Options: Report in this item the gross amount (stated in U.S. dollars) of foreign (non-U.S.) currency and U.S. dollar exchange that the reporting bank has, for a fee, purchased the right to either purchase or sell under option contracts whose predominant risk characteristic is foreign exchange risk.

Column C, Purchased OTC Equity Derivative Options: Report the contract amount of those OTC option contracts where the reporting bank has, for a fee, purchased the right to purchase or sell an equity instrument or equity index.

Column D, Purchased OTC Commodity and Other OTC Options: Report the contract amount for those option contracts where the reporting bank has, for a fee, purchased the right to purchase or sell a commodity or product. Include any other purchased OTC option that is not reportable as an interest rate, foreign exchange or equity derivative contract in column A, B, or C.

Swaps. Swaps are transactions in which two parties agree to exchange payment streams based on a specified notional amount for a specified period. Forward starting swap contracts should be reported as swaps. The notional amount of a swap is the underlying principal amount upon which the exchange of interest, foreign exchange or other income or expense is based. The notional amount to be reported for a swap contract with a multiplier component is the contract's effective notional amount. In those cases where the reporting bank is acting as an intermediary, both sides of the transaction are to be reported.

Column A, Interest Rate Swaps: Report the notional amount of all outstanding interest rate and basis swaps whose predominant risk characteristic is interest rate risk.

Column B, Foreign Exchange Swaps: Report the notional principal amount (stated in U.S. dollars) of all outstanding cross-currency interest rate swaps. A cross-currency interest rate swap is a transaction in which two parties agree to exchange principal amounts of different currencies, usually at the prevailing spot rate, at the inception of an agreement that lasts for a certain number of years. At defined intervals over the life of the swap, the counterparties exchange payments in the different currencies based on specified rates of interest. When the agreement matures, the principal amounts will be re-exchanged at the same spot rate. The notional amount of a cross-currency interest rate swap is generally the underlying principal amount upon which the exchange is based.

12.e Column C, Equity Swaps: Report the notional amount of all outstanding equity or equity (cont.) index swaps.

Column D, Commodity and Other Swaps: Report the notional principal amount of all other swap agreements that are not reportable as either interest rate, foreign exchange, or equity derivative contracts in column A, B, or C. The notional amount to be reported for commodity contracts with multiple exchanges of principal is the contractual amount multiplied by the number of remaining payments (or exchanges of principal) in the contract.

Total gross notional amount of derivative contracts held for trading. Report, in the appropriate column, the total notional amount or par value of those derivative contracts reported in Schedule RC-L, item 12, above that are held for trading purposes. Contracts held for trading purposes include those used in dealing and other trading activities. Derivative instruments used to hedge trading activities should also be reported in this item.

Derivative trading activities include (a) regularly dealing in interest rate contracts, foreign exchange contracts, equity derivative contracts, and other off-balance sheet commodity contracts, (b) acquiring or taking positions in such items principally for the purpose of selling in the near term or otherwise with the intent to resell (or repurchase) in order to profit from short-term price movements, and (c) acquiring or taking positions in such items as an accommodation to customers.

The reporting bank's trading department may have entered into a derivative contract with another department or business unit within the consolidated bank (and which has been reported on a net basis in accordance with the instructions to Schedule RC-L, item 12 above). If the trading department has also entered into a matching contract with a counterparty outside the consolidated bank, the contract with the outside counterparty should be designated as held for trading or as held for purposes other than trading consistent with the contract's designation for other financial reporting purposes.

- Total gross notional amount of derivative contracts held for purposes other than trading. Report, in the appropriate column, the total notional amount or par value of those contracts reported in Schedule RC-L, item 12, above, that are held for purposes other than trading.
- 14.a Interest rate swaps where the bank has agreed to pay a fixed rate. Report the notional amount of all outstanding interest rate swaps included in Schedule RC-L, item 14, column A, above, on which the reporting bank is obligated to pay a fixed rate. The interest rate swaps that are reported in this item will also have been reported in Schedule RC-L, item 12.e, column A. Interest rate swaps that are held for trading should not be reported in this item 14.a.

A <u>fixed interest rate</u> is a rate that is specified at the origination of the transaction, is fixed and invariable during the term of the interest rate swap, and is known to both the bank and the swap counterparty. Also treated as a fixed interest rate is a predetermined interest rate which is a rate that changes during the term of the interest rate swap on a predetermined basis, with the exact rate of interest over the life of the swap known with certainty to both the bank and the swap counterparty at the origination of the transaction.

NOTE: On the FFIEC 041, item 15 and its subitems are not applicable to banks that have less than \$100 million in total assets.

Gross fair values of derivative contracts. Report in the appropriate column and subitem the fair value of all derivative contracts reported in Schedule RC-L, items 13 and 14, above. For each of the four types of underlying risk exposure in columns A through D, the gross positive and gross negative fair values will be reported separately for (i) contracts held for trading purposes (in item 15.a) and (ii) contracts held for purposes other than trading (in item 15.b). Guidance for reporting by type of underlying risk exposure is provided in the instructions for Schedule RC-L, item 12, above. Guidance for reporting by purpose is provided in the instructions for Schedule RC-L, items 13 and 14, above.

All transactions within the consolidated bank should be reported on a net basis. No other netting of contracts is permitted for purposes of this item. Therefore, do not net (1) obligations of the reporting bank to buy against the bank's obligations to sell, (2) written options against purchased options, (3) positive fair values against negative fair values, or (4) contracts subject to bilateral netting agreements.

As defined in FASB Statement No. 133, fair value is the amount at which an asset (liability) could be bought (incurred) or sold (settled) in a current transaction between willing parties, that is, other than in a forced or liquidation sale. Quoted market prices in active markets are the best evidence of fair value and should be used as the basis for the measurement, if available. If a quoted market price is available, the fair value is the product of the number of trading units times that market price. If a quoted market price is not available, the estimate of fair value should be based on the best information available in the circumstances. The estimate of fair value should consider prices for similar assets or similar liabilities and the results of valuation techniques to the extent available in the circumstances. For purposes of item 15, the reporting bank should determine the fair value of its derivative contracts in the same manner that it determines the fair value of these contracts for other financial reporting purposes.

- **Contracts held for trading.** Report in the appropriate column and subitem the gross positive and gross negative fair values of those contracts held for trading that are reported in Schedule RC-L, item 13, above.
- **15.a.(1) Gross positive fair value.** Report in the appropriate column the total fair value of those contracts reported in Schedule RC-L, item 13, above, with positive fair values.
- **Gross negative fair value.** Report in the appropriate column the total fair value of those contracts reported in Schedule RC-L, item 13, above, with negative fair values. Report the total fair value as an absolute value, do <u>not</u> enclose the total fair value in parentheses or use a minus (-) sign.
- **Contracts held for purposes other than trading.** Report in the appropriate column and subitem the gross positive and gross negative fair values of those contracts held for purposes other than trading that are reported in Schedule RC-L, item 14, above.
- **15.b.(1)** Gross positive fair value. Report in the appropriate column the total fair value of those contracts reported in Schedule RC-L, item 14, above, with positive fair values.

Gross negative fair value. Report in the appropriate column the total fair value of those contracts reported in Schedule RC-L, item 14, above, with negative fair values. Report the total fair value as an absolute value, do <u>not</u> enclose the total fair value in parentheses or use a minus (-) sign.

FFIEC 031 and 041 RC-M – MEMORANDA

SCHEDULE RC-M -- MEMORANDA

Item No. Caption and Instructions

Extensions of credit by the reporting bank to its executive officers, directors, principal shareholders, and their related interests as of the report date. For purposes of this item, the terms "extension of credit," "executive officer," "director," "principal shareholder," and "related interest," are as defined in Federal Reserve Board Regulation O.

An "extension of credit" is a making or renewal of any loan, a granting of a line of credit, or an extending of credit in any manner whatsoever. Extensions of credit include, among others, loans, overdrafts, cash items, standby letters of credit, and securities purchased under agreements to resell. For lines of credit, the amount to be reported as an extension of credit is normally the total amount of the line of credit extended to the insider, not just the current balance of the funds that have been advanced to the insider under the line of credit. See Section 215.3 of Regulation O for further details.

An "executive officer" of the reporting bank generally means a person who participates or has authority to participate (other than in the capacity of a director) in major policymaking functions of the reporting bank, an executive officer of a bank holding company of which the bank is a subsidiary, and (unless properly excluded by the bank's board of directors or bylaws) an executive officer of any other subsidiary of that bank holding company. See Section 215.2(e) of Regulation O for further details.

A "director" of the reporting bank generally means a person who is a director of a bank, whether or not receiving compensation, a director of a bank holding company of which the bank is a subsidiary, and (unless properly excluded by the bank's board of directors or bylaws) a director of any other subsidiary of that bank holding company.

See Section 215.2(d) of Regulation O for further details.

A "principal shareholder" of the reporting bank generally means an individual or a company (other than an insured bank or foreign bank) that directly or indirectly owns, controls, or has the power to vote more than ten percent of any class of voting securities of the reporting bank. See Section 215.11(a)(1) of Regulation O for further details.

A "related interest" means (1) a company (other than an insured bank or a foreign bank) that is controlled by an executive officer, director, or principal shareholder or (2) a political or campaign committee that is controlled by or the funds or services of which will benefit an executive officer, director, or principal shareholder. See Section 215.11(a)(2) of Regulation O.

1.a Aggregate amount of all extensions of credit to all executive officers, directors, principal shareholders, and their related interests. Report the aggregate amount outstanding as of the report date of all extensions of credit by the reporting bank to all of its executive officers, directors, and principal shareholders, and to all of the related interests of its executive officers, directors, and principal shareholders.

Include each extension of credit by the reporting bank in the aggregate amount only *one* time, regardless of the number of executive officers, directors, principal shareholders, and related interests thereof to whom the extension of credit has been made.

FFIEC 031 and 041 RC-M-1 RC-M - MEMORANDA

FFIEC 031 and 041 RC-M – MEMORANDA

Item No. Caption and Instructions

1.b Number of executive officers, directors, and principal shareholders to whom the amount of all extensions of credit by the reporting bank (including extensions of credit to related interests) equals or exceeds the lesser of \$500,000 or 5 percent of total capital as defined for this purpose in agency regulations. Report the number of executive officers, directors, and principal shareholders of the reporting bank to whom the amount of all extensions of credit by the reporting bank outstanding as of the report date equals or exceeds the lesser of \$500,000 or five percent of total capital as defined for this purpose in regulations issued by the bank's primary federal bank supervisory authority.

For purposes of this item, the amount of all extensions of credit by the reporting bank to an executive officer, director, or principal shareholder includes all extensions of credit by the reporting bank to the related interests of the executive officer, director, or principal shareholder. Furthermore, an extension of credit made by the reporting bank to *more than one* of its executive officers, directors, principal shareholders, or related interests thereof must be included in full in the amount of all extensions of credit for *each* such executive officer, director, or principal shareholder.

- Intangible assets other than goodwill. Report in the appropriate subitem the carrying amount of intangible assets other than goodwill. Intangible assets primarily result from business combinations accounted for under the purchase method in accordance with FASB Statement No. 141, Business Combinations, from acquisitions of portions or segments of another institution's business such as branch offices, mortgage servicing portfolios, and credit card portfolios, and from the sale or securitization of financial assets with servicing retained. Intangible assets with finite lives should be amortized over their estimated useful lives and tested for impairment at least annually in accordance with FASB Statement No. 142, Goodwill and Intangible Assets. Intangible assets with indefinite useful lives should not be amortized, but should be tested for impairment at least annually in accordance with FASB Statement No. 142.
- 2.a Mortgage servicing assets. Report the carrying amount of mortgage servicing assets, i.e., the unamortized cost of acquiring contracts to service loans secured by real estate (as defined for Schedule RC-C, part I, item 1, in the Glossary entry for "Loans secured by real estate") that have been securitized or are owned by another party, net of any related valuation allowances. Exclude servicing assets resulting from contracts to service financial assets other than loans secured by real estate (report nonmortgage servicing assets in Schedule RC-M, item 2.b). For further information, see the Glossary entry for "servicing assets and liabilities."
- **2.a.(1)** Estimated fair value of mortgage servicing assets. Report the estimated fair value of the capitalized mortgage servicing assets reported in Schedule RC-M, item 2.a, above.

According to FASB Statement No. 140, the fair value of mortgage servicing assets is the amount at which the assets could be bought or sold in a current transaction between willing parties, that is, other than in a forced or liquidation sale. Quoted market prices in active markets are the best evidence of fair value and should be used to measure fair value if available. If quoted market prices are not available, the estimate of fair value should be based on the best information available in the circumstances, considering prices for similar assets and the results of valuation techniques such as the present value of estimated future cash flows using a discount rate commensurate with the risks involved. Valuation techniques for measuring servicing assets should be consistent with the objective of measuring fair value and should incorporate assumptions that market participants would use. Estimates of expected future cash flows, if used to estimate fair value, should be the best estimate based on reasonable and supportable assumptions and projections.

FFIEC 031 and 041 RC-M – MEMORANDA

Item No. Caption and Instructions

2.a.(1) For purposes of this item, the reporting bank should determine the fair value of mortgage (cont.) servicing assets in the same manner that it determines the fair value of these assets for other financial reporting purposes, consistent with the guidance in FASB Statement No. 140.

2.b Purchased credit card relationships and nonmortgage servicing assets. Report the carrying amount of purchased credit card relationships plus the carrying amount of nonmortgage servicing assets.

Purchased credit card relationships represent the right to conduct ongoing credit card business dealings with the cardholders. In general, purchased credit card relationships are an amount paid in excess of the value of the purchased credit card receivables. Such relationships arise when the reporting bank purchases existing credit card receivables and also has the right to provide credit card services to those customers. Purchased credit card relationships may also be acquired when the reporting bank purchases an entire depository institution.

Purchased credit card relationships shall be carried at amortized cost, not in excess of the discounted amount of estimated future net cash flows. Management of the institution shall review the carrying amount at least quarterly, adequately document this review, and adjust the carrying amount as necessary. If unanticipated acceleration or deceleration of cardholder payments, account attrition, changes in fees or finance charges, or other events occur that reduce the amount of expected future net cash flows, a write-down of the carrying amount of the purchased credit card relationships shall be made to the extent that the discounted amount of estimated future net cash flows is less than the asset's carrying amount.

The carrying amount of *nonmortgage servicing assets* is the unamortized cost of acquiring contracts to service financial assets, other than loans secured by real estate (as defined for Schedule RC-C, part I, item 1), that have been securitized or are owned by another party, net of any related valuation allowances. For further information, see the Glossary entry for "servicing assets and liabilities."

- **All other identifiable intangibles.** Report the carrying amount of all other specifically identifiable intangible assets such as core deposit intangibles and favorable leasehold rights. Also include the carrying amount of any unidentifiable intangible assets recorded in accordance with FASB Statement No. 72, *Accounting for Certain Combinations of a Banking or Thrift Institution.* Exclude goodwill, which should be reported in Schedule RC, item 10.a.
- 2.d Total. Report the sum of items 2.a, 2.b, and 2.c. This amount must equal Schedule RC, item 10.b, "Other intangible assets."
- Other real estate owned. Report in the appropriate subitem the book value, less accumulated depreciation, if any, of all real estate other than bank premises owned or controlled by the bank and its consolidated subsidiaries. Do not deduct mortgages or other liens on such property (report in Schedule RC, item 16, "Other borrowed money"). Amounts should be reported net of any applicable valuation allowances.

<u>Exclude</u> any property necessary for the conduct of banking business (report in Schedule RC, item 6, "Premises and fixed assets").

FFIEC 031 and 041 RC-M-3 RC-M - MEMORANDA

Item No. Caption and Instructions

3.a <u>Direct and indirect investments in real estate ventures</u>. Report the net book value of direct and indirect investments in real estate ventures that are reportable as other real estate owned.

NOTE: 12 USC 29 limits the authority of national banks to hold real estate. State member banks are not authorized to invest in real estate except with the prior approval of the Board of Governors of the Federal Reserve System under Federal Reserve Regulation H (12 CFR Part 208). In certain states, nonmember banks may invest in real estate.

<u>Include</u> as direct and indirect investments in real estate ventures:

- (1) Any real estate acquired, directly or indirectly, by the bank or a consolidated subsidiary and held for development, resale, or other investment purposes. (Do <u>not</u> include real estate acquired in any manner for debts previously contracted, including, but not limited to, real estate acquired through foreclosure or acquired by deed in lieu of foreclosure. Report such real estate in Schedule RC-M, item 3.b, below.)
- (2) Real estate acquisition, development, or construction (ADC) arrangements which are accounted for as direct investments in real estate in accordance with guidance prepared by the American Institute of Certified Public Accountants (AICPA) in Notices to Practitioners issued in November 1983, November 1984, and February 1986.
- (3) Real estate acquired and held for investment by the bank or a consolidated subsidiary that has been sold under contract and accounted for under the deposit method of accounting in accordance with FASB Statement No. 66, Accounting for Sales of Real Estate. Under this method, the seller does not record notes receivable, but continues to report the real estate and any related existing debt on its balance sheet. The deposit method is used when a sale has not been consummated and is commonly used when recovery of the carrying value of the property is not reasonably assured. If the full accrual, installment, cost recovery, reduced profit, or percentage-of-completion method of accounting under FASB Statement No. 66 is being used to account for the sale, the receivable resulting from the sale of the real estate should be reported as a loan in Schedule RC-C and any gain on the sale should be recognized in accordance with FASB Statement No. 66.
- (4) Any other loans secured by real estate and advanced for real estate acquisition, development, or investment purposes if the reporting bank in substance has virtually the same risks and potential rewards as an investor in the borrower's real estate venture.
- (5) Investments in corporate joint ventures, unincorporated joint ventures, and general or limited partnerships that are primarily engaged in the holding of real estate for development, resale, or other investment purposes and over which the bank does not exercise significant influence.

FFIEC 031 and 041 RC-M-4 RC-M - MEMORANDA

Item No. Caption and Instructions

3.b All other real estate owned. Report the net book value of all other real estate owned. Include as all other real estate owned:

- (1) Foreclosed real estate, i.e.,
 - (a) Real estate acquired in any manner for debts previously contracted (including, but not limited to, real estate acquired through foreclosure and real estate acquired by deed in lieu of foreclosure), even if the bank has not yet received title to the property.
 - (b) Real estate collateral underlying a loan when the bank has obtained physical possession of the collateral, regardless of whether formal foreclosure proceedings have been instituted against the borrower.

Foreclosed real estate received in full or partial satisfaction of a loan should be recorded at the fair value less cost to sell of the property at the time of foreclosure. This amount becomes the "cost" of the foreclosed real estate. When foreclosed real estate is received in full satisfaction of a loan, the amount, if any, by which the recorded amount of the loan exceeds the fair value less cost to sell of the property is a loss which must be charged to the allowance for loan and lease losses at the time of foreclosure. The amount of any senior debt (principal and accrued interest) to which foreclosed real estate is subject at the time of foreclosure must be reported as a liability in Schedule RC, item 16, "Other borrowed money."

After foreclosure, each foreclosed real estate asset must be carried at the lower of (1) the fair value of the asset minus the estimated costs to sell the asset or (2) the cost of the asset (as defined in the preceding paragraph). This determination must be made on an asset-by-asset basis. If the fair value of a foreclosed real estate asset minus the estimated costs to sell the asset is less than the asset's cost, the deficiency must be recognized as a valuation allowance against the asset which is created through a charge to expense. The valuation allowance should thereafter be increased or decreased (but not below zero) through charges or credits to expense for changes in the asset's fair value or estimated selling costs. (For further information, see the Glossary entries for "foreclosed assets" and "troubled debt restructurings.")

- (2) Property originally acquired for future expansion but no longer intended to be used for that purpose.
- (3) Foreclosed real estate sold under contract and accounted for under the deposit method of accounting in accordance with FASB Statement No. 66, Accounting for Sales of Real Estate. Under this method, the seller does not record notes receivable, but continues to report the real estate and any related existing debt on its balance sheet. The deposit method is used when a sale has not been consummated and is commonly used when recovery of the carrying value of the property is not reasonably assured. If the full accrual, installment, cost recovery, reduced profit, or percentage-of-completion method of accounting under FASB Statement No. 66 is being used to account for the sale, the receivable resulting from the sale of the foreclosed real estate should be reported as a loan in Schedule RC-C and any gain on the sale should be recognized in accordance with FASB Statement No. 66. For further information, see the Glossary entry for "foreclosed assets."

Property formerly but no longer used for banking may be reported either in this item as "All other real estate owned" or in Schedule RC, item 6, as "Premises and fixed assets."

FFIEC 031 and 041 RC-M-5 RC-M - MEMORANDA (3-01)

Item No. Caption and Instructions

3.b.(1) Construction, land development, and other land (in domestic offices). Report the net book value of all other real estate owned (in domestic offices) in the form of, or for which the underlying real estate consists of, vacant land (but not farmland), land under development, or structures or facilities under construction, whether or not development or construction is continuing or has ceased prior to completion. When construction is substantially completed and the structure or facility is available for occupancy or use, report the net book value in the subitem below appropriate to the completed structure or facility.

For further information on the meaning of the term "construction, land development, and other land" see the instruction to Schedule RC-C, part I, item 1.a. However, the amount to be reported in this item should include all other real estate owned in the form of, or for which the underlying real estate consists of, vacant land, land under development, or structures or facilities under construction, <u>not</u> just real estate acquired through foreclosure on loans that were originally reported as "construction, land development, and other land loans" in Schedule RC-C, part I, item 1.a, column B.

3.b.(2) Farmland (in domestic offices). Report the net book value of all other real estate owned (in domestic offices) in the form of, or for which the underlying real estate consists of, farmland.

For further information on the meaning of the term "farmland," see the instruction to Schedule RC-C, part I, item 1.b. However, the amount to be reported in this item should include all other real estate owned in the form of, or for which the underlying real estate consists of, farmland, not just real estate acquired through foreclosure on loans that were originally reported as "loans secured by farmland" in Schedule RC-C, part I, item 1.b, column B.

1-4 family residential properties (in domestic offices). Report the net book value of all other real estate owned (in domestic offices) in the form of, or for which the underlying real estate consists of, 1-to-4 family residential properties.

For further information on the meaning of the term "1-4 family residential properties," see the instruction to Schedule RC-C, part I, item 1.c. However, the amount to be reported in this item should include all other real estate owned in the form of, or for which the underlying real estate consists of, 1-to-4 family residential properties, not just real estate acquired through foreclosure on loans that were originally reported as "loans secured by 1-4 family residential properties" in Schedule RC-C, part I, item 1.c, column B.

3.b.(4) Multifamily (5 or more) residential properties (in domestic offices). Report the net book value of all other real estate owned (in domestic offices) in the form of, or for which the underlying real estate consists of, multifamily residential properties.

For further information on the meaning of the term "multifamily residential properties," see the instruction to Schedule RC-C, part I, item 1.d. However, the amount to be reported in this item should include all other real estate owned in the form of, or for which the underlying real estate consists of, multifamily residential properties, <u>not</u> just real estate acquired through foreclosure on loans that were originally reported as "loans secured by multifamily residential properties" in Schedule RC-C, part I, item 1.d, column B.

FFIEC 031 and 041 RC-M-6 RC-M - MEMORANDA

Item No. Caption and Instructions

3.b.(5) Nonfarm nonresidential properties (in domestic offices). Report the net book value of all other real estate owned (in domestic offices) in the form of, or for which the underlying real estate consists of, nonfarm nonresidential properties.

For further information on the meaning of the term "nonfarm nonresidential properties," see the instruction to Schedule RC-C, part I, item 1.e. However, the amount to be reported in this item should include all other real estate owned in the form of, or for which the underlying real estate consists of, nonfarm nonresidential properties, <u>not</u> just real estate acquired through foreclosure on loans that were originally reported as "loans secured by nonfarm nonresidential properties" in Schedule RC-C, part I, item 1.e, column B.

NOTE: Item 3.b.(6) is not applicable to banks filing the FFIEC 041 report form.

- **3.b.(6)** In foreign offices. Report the net book value of all other real estate owned which is held in foreign offices of the reporting bank.
- **Total**. On the FFIEC 041, report the sum of items 3.a through 3.b.(5). On the FFIEC 031, report the sum of items 3.a through 3.b.(6). This amount must equal Schedule RC, item 7, "Other real estate owned."
- Investments in unconsolidated subsidiaries and associated companies. Report in the appropriate subitem the amount of the bank's investments in subsidiaries that have not been consolidated; associated companies; and corporate joint ventures, unincorporated joint ventures, general partnerships, and limited partnerships over which the bank exercises significant influence (collectively referred to as "investees"). Include loans and advances to investees and holdings of their bonds, notes, and debentures.

Investments in investees shall be reported using the equity method of accounting. Under the equity method the carrying value of the bank's investment in an investee is originally recorded at cost but is adjusted periodically to record as income the bank's proportionate share of the investee's earnings or losses and decreased by the amount of any cash dividends or similar distributions received from the investee. For purposes of these reports, the date through which the carrying value of the bank's investment in an investee has been adjusted should, to the extent practicable, match the report date of the Report of Condition, but in no case differ by more than 93 days from the report date.

Unconsolidated subsidiaries include those majority-owned subsidiaries that do not meet the significance standards for required consolidation that the bank chooses not to consolidate under the optional consolidation provisions. Refer to the General Instructions section of this book for a detailed discussion of consolidation. See also the Glossary entry for "subsidiaries."

4.a Direct and indirect investments in real estate ventures. Report the amount of the bank's investments in investees (as defined above) that are primarily engaged in the holding of real estate for development, resale, or other investment purposes. Investments by the bank in these investees may be in the form of common or preferred stock, partnership interests, loans or other advances, bonds, notes, or debentures. Such investments shall be reported using the equity method of accounting as described above. Include in this item real estate acquisition, development, or construction (ADC) arrangements which are accounted for as real estate joint ventures in accordance with guidance prepared by the American Institute of Certified Public Accountants (AICPA) in Notices to Practitioners issued in November 1983, November 1984, and February 1986.

Item No. Caption and Instructions

4.a NOTE: 12 USC 29 limits the authority of national banks to hold real estate. State member (cont.) banks are not authorized to invest in real estate except with the prior approval of the Board of Governors of the Federal Reserve System under Federal Reserve Regulation H (12 CFR Part 208). In certain states, nonmember banks may invest in real estate.

- All other investments in unconsolidated subsidiaries and associated companies.

 Report the amount of the bank's investments in investees (as defined above) that are not primarily engaged in the holding of real estate for development, resale, or other investment purposes. Investments by the bank in these investees may be in the form of common or preferred stock, partnership interests, loans or other advances, bonds, notes, or debentures. Such investments shall be reported using the equity method of accounting as described above.
- **Total**. Report the sum of items 4.a and 4.b. This amount must equal Schedule RC, item 8, "Investments in unconsolidated subsidiaries and associated companies."
- **Other borrowed money.** Report in the appropriate subitem by remaining maturity the amount borrowed by the consolidated bank.

Remaining maturity is amount of time remaining from the report date until the final contractual maturity without regard to the borrowing's repayment schedule, if any. Callable Federal Home Loan Bank advances should be reported without regard to their next call date unless the advance has actually been called. When an advance has been called, it should be reported based on the time remaining until the call date. Puttable Federal Home Loan Bank advances should be reported without regard to put dates if the bank has not exercised the put. If a put has been exercised but the advance has not yet been repaid, the puttable advance should be reported based on its scheduled repayment date.

For banks filing the FFIEC 031, for a discussion of borrowings in foreign offices, see the Glossary entry for "borrowings and deposits in foreign offices."

- **5.a Federal Home loan bank advances.** Report in the appropriate subitem by remaining maturity the amount of any outstanding advances obtained from a Federal Home Loan Bank. Report all outstanding advances regardless of maturity.
- **5.a.(1)** With a remaining maturity of one year or less. Report the amount of Federal Home Loan Bank advances with a remaining maturity of one year or less, including overnight advances.
- **5.a.(2)** With a remaining maturity of more than one year through three years. Report the amount of Federal Home Loan Bank advances with a remaining maturity of more than one year through three years.
- **5.a.(3)** With a remaining maturity of more than three years. Report the amount of Federal Home Loan Bank advances with a remaining maturity of more than three years.
- **Other borrowings.** Report in the appropriate subitem by remaining maturity the amount borrowed by the consolidated bank:

FFIEC 031 and 041 RC-M-8 RC-M - MEMORANDA

Item No. **Caption and Instructions**

by issuing interest-bearing demand notes issued by the bank to the U.S. Treasury.¹ 5.b (cont.)

- (2)on its promissory notes:
- (3)on notes and bills rediscounted (including commodity drafts rediscounted):
- on financial assets (other than securities) sold under repurchase agreements that have an original maturity of more than one business day and sales of participations in pools of loans that have an original maturity of more than one business day;
- by transferring financial assets in exchange for cash or other consideration (other than beneficial interests in the transferred assets) in transactions that do not satisfy the criteria for sale treatment under FASB Statement No. 140 (see the Glossary entry for "transfers of financial assets" for further information);
- by the creation of due bills representing the bank's receipt of payment and similar instruments, whether collateralized or uncollateralized (see the Glossary entry for "due bills");
- from Federal Reserve Banks: (7)
- by overdrawing "due from" balances with depository institutions, except overdrafts arising in connection with checks or drafts drawn by the reporting bank and drawn on, or payable at or through, another depository institution either on a zero-balance account or on an account that is not routinely maintained with sufficient balances to cover checks or drafts drawn in the normal course of business during the period until the amount of the checks or drafts is remitted to the other depository institution (in which case, report the funds received or held in connection with such checks or drafts as deposits in Schedule RC-E until the funds are remitted);
- on purchases of so-called "term federal funds" (as defined in the Glossary entry for "federal funds transactions");
- (10) on notes and debentures issued by consolidated subsidiaries of the reporting bank;
- (11) through mortgages, liens, or other encumbrances on bank premises and other real estate owned and obligations under capitalized leases;
- (12) by borrowing immediately available funds in foreign offices that have an original maturity of one business day or roll over under a continuing contrast that are not securities repurchase agreements.
- (13) on any other obligation for the purpose of borrowing money not reported elsewhere on Schedule RC, Balance Sheet.

Also include any borrowings by an Employee Stock Ownership Plan (ESOP) that the reporting bank must report as a borrowing on its own balance sheet in accordance with generally accepted accounting principles. For further information, see AICPA Statement of Position 93-6, Employers' Accounting for Employee Stock Ownership Plans.

¹ If the bank participates in the Treasury Tax and Loan note program, funds received for credit to the U.S. Government are demand deposits on the day received and become note balances on the following business day.

Item No. Caption and Instructions

5.b Exclude from other borrowings: (cont.)

(1) federal funds purchased (in domestic offices) and securities sold under agreements to repurchase (report in Schedule RC, items 14.a and 14.b, respectively);

- (2) liability for short positions (report in Schedule RC, item 15);
- (3) subordinated notes and debentures (report in Schedule RC, item 19).
- **With a remaining maturity of one year or less.** Report the total amount of the reporting bank's "Other borrowings" with a remaining maturity of one year or less. Include in this item those overdrawn "due from" balances with depository institutions that are reportable as "Other borrowed money," as described in the instructions to Schedule RC-M, item 5.b, above.
- **5.b.(2)** With a remaining maturity of more than one year through three years. Report the total amount of the reporting bank's "Other borrowings" with a remaining maturity of more than one year through three years.
- **5.b.(3)** With a remaining maturity of more than three years. Report the total amount of the reporting bank's "Other borrowings" with a remaining maturity of more than three years.
- **Total.** Report the sum of 5.a.(1) through 5.b.(3). This amount must equal Schedule RC, item 16, "Other borrowed money."
- Does the reporting bank sell private label or third party mutual funds and annuities? Indicate whether the reporting bank currently sells private label or third party mutual funds and annuities. Place an "X" in the box marked "YES" if the bank, a bank subsidiary or other bank affiliate, or an unaffiliated entity sells private label or third party mutual funds and annuities:
 - on bank premises;
 - (2) from which the bank receives income at the time of the sale or over the duration of the account (e.g., annual fees, Rule 12b-1 fees or "trailer fees," and redemption fees); or
 - (3) through the reporting bank's trust department in transactions that are <u>not</u> executed in a fiduciary capacity (e.g., trustee, executor, administrator, and conservator).

Otherwise, place an "X" in the box marked "NO".

Mutual fund is the common name for an open-end investment company whose shares are sold to the investing public. An annuity is an investment product, typically underwritten by an insurance company, that pays either a fixed or variable payment stream over a specified period of time. Both proprietary and private label mutual funds and annuities are established in order to be marketed primarily to a bank's or banking organization's customers. A proprietary product is a product for which the reporting bank or a subsidiary or other affiliate of the reporting bank acts as investment adviser and may perform additional support services. In a private label product, an unaffiliated entity acts as the investment adviser. The identity of the investment adviser is normally disclosed in the prospectus for a mutual fund or annuity. Mutual funds and annuities that are not proprietary or private label products are considered third party products. For example, third party mutual funds and annuities include products that are widely marketed by numerous parties to the investing public and have investment advisers that are not affiliated with the reporting bank.

FFIEC 031 and 041 RC-M-10 RC-M - MEMORANDA

Item No. Caption and Instructions

Assets under the reporting bank's management in proprietary mutual funds and annuities. Report the amount of assets (stated in U.S. dollars) held by mutual funds and annuities as of the report date for which the reporting bank or a subsidiary of the bank acts as investment adviser.

A general description of a proprietary product is included in the instruction to Schedule RC-M, item 6, above. Proprietary mutual funds and annuities are typically created by large banking organizations and offered to customers of the banking organization's subsidiary banks. Therefore, small, independent banks do not normally act as investment advisers for mutual funds and annuities.

If neither the bank nor any subsidiary of the bank acts as investment adviser for a mutual fund or annuity, the bank should report a zero or the word "none" in this item.

FFIEC 031 and 041 RC-M-11 RC-M - MEMORANDA

SCHEDULE RC-N -- PAST DUE AND NONACCRUAL LOANS, LEASES, AND OTHER ASSETS

General Instructions

Report on a fully consolidated basis all loans, leases, debt securities, and other assets that are past due or are in nonaccrual status, regardless of whether such credits are secured or unsecured and regardless of whether such credits are guaranteed by the government or by others. Loan amounts should be reported net of unearned income to the extent that they are reported net of unearned income in Schedule RC-C. All lease, debt security, and other asset amounts must be reported net of unearned income. Report the <u>full</u> outstanding balances of assets that are past due or in nonaccrual status, as reported for purposes of Schedule RC, Balance Sheet, not simply the delinquent payments.

For report dates through December 31, 2000, the information reported in column A on assets past due 30 through 89 days and still accruing and in all of Memorandum item 1 on restructured loans and leases included in the past due and nonaccrual totals will be treated as confidential on an individual bank basis by the federal bank supervisory agencies. Beginning with the March 31, 2001, report date, all of the information reported in Schedule RC-N for each bank will be publicly available.

Banks which service for others Government National Mortgage Association (GNMA) pools consisting of 1-to-4 family residential mortgage loans insured by the Federal Housing Administration (FHA) or the Farmers Home Administration (FmHA) or guaranteed by the Veterans Administration (VA) and which, in order to satisfy GNMA's servicing requirements, choose to purchase delinquent FHA, FmHA, or VA residential mortgages in foreclosure status from the pool in lieu of continuing to make monthly advances to the pool need not report such loans in Schedule RC-N provided the process of reimbursement by FHA, FmHA, or VA is proceeding normally.

Definitions

<u>Past Due</u> -- For purposes of this schedule, grace periods allowed by the bank after a loan or other asset technically has become past due but before the imposition of late charges are not to be taken into account in determining past due status. Furthermore, loans, leases, debt securities, and other assets are to be reported as past due when either interest <u>or</u> principal is unpaid in the following circumstances:

- (1) Closed-end installment loans, amortizing loans secured by real estate, and any other loans and lease financing receivables with payments scheduled monthly are to be reported as past due when the borrower is in arrears two or more monthly payments. (At a bank's option, loans and leases with payments scheduled monthly may be reported as past due when one scheduled payment is due and unpaid for 30 days or more.) Other multipayment obligations with payments scheduled other than monthly are to be reported as past due when one scheduled payment is due and unpaid for 30 days or more.
- (2) Open-end credit such as credit cards, check credit, and other revolving credit plans are to be reported as past due when the customer has not made the minimum payment for two or more billing cycles.
- (3) Single payment and demand notes, debt securities, and other assets providing for the payment of interest at stated intervals are to be reported as past due after one interest payment is due and unpaid for 30 days or more.
- (4) Single payment notes, debt securities, and other assets providing for the payment of interest at maturity are to be reported as past due after maturity if interest <u>or</u> principal remains unpaid for 30 days or more.

Definitions (cont.)

(5) Unplanned overdrafts are to be reported as past due if the account remains continuously overdrawn for 30 days or more.

For purposes of this schedule, banks should use one of two methods to recognize partial payments on "retail credit," i.e., open-end and closed-end credit extended to individuals for household, family, and other personal expenditures, including consumer loans and credit cards, and loans to individuals secured by their personal residence, including home equity and home improvement loans. A payment equivalent to 90 percent or more of the contractual payment may be considered a full payment in computing delinquency. Alternatively, a bank may aggregate payments and give credit for any partial payment received. For example, if a regular monthly installment is \$300 and the borrower makes payments of only \$150 per month for a six-month period, the loan would be \$900 (\$150 shortage times six payments), or three monthly payments past due. A bank may use either or both methods for its retail credit, but may not use both methods simultaneously with a single loan.

Nonaccrual -- For purposes of this schedule, an asset is to be reported as being in nonaccrual status if:

- (1) it is maintained on a cash basis because of deterioration in the financial condition of the borrower,
- (2) payment in full of principal or interest is not expected, or
- (3) principal or interest has been in default for a period of 90 days or more unless the asset is <u>both</u> well secured <u>and</u> in the process of collection.

An asset is "well secured" if it is secured (1) by collateral in the form of liens on or pledges of real or personal property, including securities, that have a realizable value sufficient to discharge the debt (including accrued interest) in full, or (2) by the guarantee of a financially responsible party. An asset is "in the process of collection" if collection of the asset is proceeding in due course either (1) through legal action, including judgment enforcement procedures, or, (2) in appropriate circumstances, through collection efforts not involving legal action which are reasonably expected to result in repayment of the debt or in its restoration to a current status in the near future.

For purposes of applying the third test for nonaccrual status listed above, the date on which an asset reaches nonaccrual status is determined by its contractual terms. If the principal or interest on an asset becomes due and unpaid for 90 days or more on a date that falls between report dates, the asset should be placed in nonaccrual status as of the date it becomes 90 days past due and it should remain in nonaccrual status until it meets the criteria for restoration to accrual status described below.

In the following situations, an asset need not be placed in nonaccrual status:

- (1) The criteria for amortization (i.e., accretion of discount) specified in AICPA Practice Bulletin No. 6 are met with respect to a loan or other debt instrument acquired at a discount (because there is uncertainty as to the amounts or timing of future cash flows) from an unaffiliated third party (such as another institution or the receiver of a failed institution), including those that the seller had maintained in nonaccrual status.
- (2) The asset upon which principal or interest is due and unpaid for 90 days or more is a consumer loan or a loan secured by a 1-to-4 family residential property. Nevertheless, such loans should be subject to other alternative methods of evaluation to assure that the bank's net income is not materially overstated. To the extent that the bank has elected to carry such a loan in nonaccrual status on its books, the loan must be reported as nonaccrual in this schedule.

Definitions (cont.)

As a general rule, a nonaccrual asset may be restored to accrual status when:

(1) none of its principal and interest is due and unpaid, and the bank expects repayment of the remaining contractual principal and interest, or

(2) when it otherwise becomes well secured and in the process of collection.

For purposes of meeting the first test for restoration to accrual status, the bank must have received repayment of the past due principal and interest unless, as discussed in the Glossary entry for "nonaccrual status."

- (1) the asset has been formally restructured and qualifies for accrual status,
- (2) the asset has been acquired at a discount (because there is uncertainty as to the amounts or timing of future cash flows) from an unaffiliated third party and meets the criteria for amortization (i.e., accretion of discount) specified in AICPA Practice Bulletin No. 6, or
- (3) the borrower has resumed paying the full amount of the scheduled contractual interest and principal payments on a loan that is past due and in nonaccrual status, even though the loan has not been brought fully current, and certain repayment criteria are met.

For further information, see the Glossary entry for "nonaccrual status."

Restructured -- For purposes of this schedule, restructured loans and leases are those loans and leases whose terms have been modified, because of a deterioration in the financial condition of the borrower, to provide for a reduction of either interest or principal. Once an obligation has been restructured because of such credit problems, it continues to be considered restructured until paid in full or, if the obligation yields a market rate, until the year subsequent to the year in which the restructuring takes place. A loan extended or renewed at a stated interest rate equal to the current interest rate for new debt with similar risk is not considered a restructured loan. Also, a loan to a purchaser of "other real estate owned" by the reporting bank for the purpose of facilitating the disposal of such real estate is not considered a restructured loan.

For further information, see the Glossary entry for "troubled debt restructurings."

Column Instructions

The columns of Schedule RC-N are mutually exclusive. Any given loan, lease, debt security, or other asset should be reported in only one of columns A, B, and C. Information reported for any given derivative contract should be reported in only column A or column B.

Report in columns A and B of Schedule RC-N (except for Memorandum item 5) the full outstanding balances (not just delinquent payments) of loans, leases, debt securities, and other assets that are past due and upon which the bank continues to accrue interest, as follows:

- (1) In column A, report closed-end monthly installment loans, amortizing loans secured by real estate, lease financing receivables, and open-end credit in arrears two or three monthly payments; other multipayment obligations with payments scheduled other than monthly when one scheduled payment is due and unpaid for 30 through 89 days; single payment and demand notes, debt securities, and other assets providing for payment of interest at stated intervals after one interest payment is due and unpaid for 30 through 89 days; single payment notes, debt securities, and other assets providing for payment of interest at maturity, on which interest or principal remains unpaid for 30 through 89 days after maturity; unplanned overdrafts, whether or not the bank is accruing interest on them, if the account remains continuously overdrawn for 30 through 89 days.
- (2) In column B, report the loans, lease financing receivables, debt securities, and other assets as specified above on which payment is due and unpaid for 90 days or more.

Include in columns A and B, as appropriate (except for Memorandum item 5), all loans, leases, debt securities, and other assets which, subsequent to their restructuring by means of a modification of terms, have become 30 days or more past due and upon which the bank continues to accrue interest. Exclude from columns A and B all loans, leases, debt securities, and other assets that are in nonaccrual status.

Report in columns A and B of Memorandum item 5 the fair value, if positive, of all for interest rate, foreign exchange rate, equity, and commodity and other contracts on which a required payment by the bank's counterparty is due and unpaid for 30 through 89 days and due and unpaid for 90 days or more, respectively.

Report in column C the full outstanding balances of loans, leases, debt securities, and other assets that are in nonaccrual status. Include all restructured loans, leases, debt securities, and other assets that are in nonaccrual status. However, restructured loans, leases, debt securities, and other assets with a zero percent effective interest rate are <u>not</u> to be reported in this column as nonaccrual assets.

Item Instructions

The loan and lease category definitions used in Schedule RC-N correspond with the loan and lease category definitions found in Schedule RC-C, part I. Consistent with Schedule RC-C, part I, the categoryby-category breakdown of loans and leases in Schedule RC-N includes (1) loans and leases held for sale and (2) loans and leases that the bank has the intent and ability to hold for the foreseeable future or until maturity or payoff.

Item No. **Caption and Instructions**

- 1 Loans secured by real estate. Report in the appropriate subitem and column all loans secured by real estate, as defined for Schedule RC-C, part I, item 1, that are past due 30 days or more or are in nonaccrual status as of the report date.
- Construction, land development, and other land loans (in domestic offices). Report in 1.a the appropriate column the amount of all construction, land development, and other land loans (in domestic offices), as defined for Schedule RC-C, part I, item 1.a, column B, that are past due 30 days or more or are in nonaccrual status as of the report date.
- 1.b Secured by farmland (in domestic offices). Report in the appropriate column the amount of all loans secured by farmland (in domestic offices) as defined for Schedule RC-C, part I, item 1.b, column B, that are past due 30 days or more or are in nonaccrual status as of the report date.
- 1.c Secured by 1-4 family residential properties (in domestic offices). Report in the appropriate subitem and column the amount of all loans secured by 1-4 family residential properties (in domestic offices), as defined for Schedule RC-C, part I, item 1.c, column B, that are past due 30 days or more or are in nonaccrual status as of the report date.
- 1.c.(1) Revolving, open-end loans secured by 1-4 family residential properties and extended under lines of credit. Report in the appropriate column the amount outstanding under all revolving, open-end loans secured by 1-to-4 family residential properties and extended under lines of credit (in domestic offices), as defined for Schedule RC-C, part I, item 1.c.(1), column B, that are past due 30 days or more or are in nonaccrual status as of the report date.
- Closed-end loans secured by 1-4 family residential properties. Report in the appropriate 1.c.(2) subitem and column the amount of all closed-end loans secured by 1-to-4 family residential properties (in domestic offices), as defined for Schedule RC-C, part I, item 1.c.(2), column B, that are past due 30 days or more or are in nonaccrual status as of the report date.
- 1.c.(2)(a) Secured by first liens. Report in the appropriate column the amount of all closed-end loans secured by first liens on 1-to-4 family residential properties (in domestic offices), as defined for Schedule RC-C, part I, item 1.c.(2)(a), column B, that are past due 30 days or more or are in nonaccrual status as of the report date.
- Secured by iunior liens. Report in the appropriate column the amount of all closed-end 1.c.(2)(b) loans secured by junior liens on 1-to-4 family residential properties (in domestic offices), as defined for Schedule RC-C, part I, item 1.c.(2)(b), column B, that are past due 30 days or more or are in nonaccrual status as of the report date. Include loans secured by junior liens in this item even if the bank also holds a loan secured by a first lien on the same 1-to-4 family residential property and there are no intervening junior liens.
- 1.d Secured by multifamily (5 or more) residential properties (in domestic offices). Report in the appropriate column the amount of all loans secured by multifamily (5 or more) residential properties (in domestic offices) as defined for Schedule RC-C, part I, item 1.d,

Item No. Caption and Instructions

1.d column B, that are past due 30 days or more or are in nonaccrual status as of the report (cont.) date.

Secured by nonfarm nonresidential properties (in domestic offices). Report in the appropriate column the amount of all loans secured by nonfarm residential properties (in domestic offices) as defined for Schedule RC-C, part I, item 1.e, column B, that are past due 30 days or more or are in nonaccrual status as of the report date.

NOTE: Item 1.f is not applicable to banks filing the FFIEC 041 report form.

- **1.f** In foreign offices. Report in the appropriate column the amount of all loans secured by real estate in foreign offices, as defined for Schedule RC-C, part I, item 1, that are past due 30 days or more or are in nonaccrual status as of the report date.
- Loans to depository institutions and acceptances of other banks. Report on the FFIEC 041 in the appropriate column and on the FFIEC 031 in the appropriate subitem and column the amount of all loans to depository institutions and acceptances of other banks, as defined for Schedule RC-C, part I, item 2, that are past due 30 days or more or are in nonaccrual status as of the report date.

NOTE: Items 2.a, 2.b, and 3 are not applicable to banks filing the FFIEC 041 report form.

- **To U.S. banks and other U.S. depository institutions.** Report in the appropriate column the amount of loans to and acceptances of U.S. banks and other U.S. depository institutions, as defined for Schedule RC-C, part I, items 2.a.(2), 2.b, and 2.c.(1), column A, that are past due 30 days or more or are in nonaccrual status as of the report date.
- **2.b To foreign banks**. Report in the appropriate column the amount of all loans to and acceptances of foreign banks, as defined for Schedule RC-C, part I, items 2.a.(1) and 2.c.(2), column A, that are past due 30 days or more or are in nonaccrual status as of the report date.
- Loans to finance agricultural production and other loans to farmers. Report in the appropriate column the amount of all loans to finance agricultural production and other loans to farmers, as defined for Schedule RC-C, part I, item 3, column A, that are past due 30 days or more or are in nonaccrual status as of the report date.
- Commercial and industrial loans. Report on the FFIEC 041 in the appropriate column and on the FFIEC 031 in the appropriate subitem and column the amount of all commercial and industrial loans as defined for Schedule RC-C, part I, item 4, that are past due 30 days or more or are in nonaccrual status as of the report date.

NOTE: Items 4.a and 4.b are <u>not</u> applicable to banks filing the FFIEC 041 report form.

- **To U.S. addressees (domicile)**. Report in the appropriate column the amount of all commercial and industrial loans to U.S. addressees, as defined for Schedule RC-C, part I, item 4.a, column A, that are past due 30 days or more or are in nonaccrual status as of the report date.
- **To non-U.S. addressees (domicile)**. Report in the appropriate column the amount of all commercial and industrial loans to non-U.S. addressees, as defined for Schedule RC-C, part I, item 4.b, column A, that are past due 30 days or more or are in nonaccrual status as of the report date.

Caption and Instructions Item No.

5 Loans to individuals for household, family, and other personal expenditures. Report in the appropriate subitem and column the amount of all loans to individuals for household, family, and other personal expenditures (i.e., consumer loans) as defined for Schedule RC-C, part I, item 6, that are past due 30 days or more or are in nonaccrual status as of the report date.

- 5.a <u>Credit cards</u>. Report in the appropriate column the amount of all extensions of credit to individuals for household, family, and other personal expenditures arising from credit cards, as defined for Schedule RC-C, part I, item 6.a, that are past due 30 days or more or are in nonaccrual status as of the report date.
- 5.b Other. Report in the appropriate column the amount of all other loans to individuals for household, family, and other personal expenditures, as defined for Schedule RC-C, part I, items 6.b and 6.c, that are past due 30 days or more or are in nonaccrual status as of the report date.
- 6 Loans to foreign governments and official institutions. Report in the appropriate column the amount of all loans to foreign governments and official institutions, as defined for Schedule RC-C, part I, item 7, that are past due 30 days or more or are in nonaccrual status as of the report date.
- 7 All other loans. Report in the appropriate column the amount of all:
 - obligations (other than securities and leases) of states and political subdivisions in the U.S., as defined for Schedule RC-C, part I, item 8;
 - other loans, as defined for Schedule RC-C, part I, item 9; and
 - on the FFIEC 041 only, all loans to finance agricultural production and other loans to farmers, as defined for Schedule RC-C, part I, item 3,

that are past due 30 days or more or are in nonaccrual status as of the report date.

8 Lease financing receivables (net of unearned income). Report on the FFIEC 041 in the appropriate column and on the FFIEC 031 in the appropriate subitem and column the amount of all lease financing receivables (net of unearned income), as defined for Schedule RC-C, part I, item 10, that are past due 30 days or more or are in nonaccrual status as of the report date.

NOTE: Items 8.a and 8.b are not applicable to banks filing the FFIEC 041 report form.

- 8.a Of U.S. addressees (domicile). Report in the appropriate column the amount of all lease financing receivables (net of unearned income) of U.S. addressees, as defined for Schedule RC-C, part I, item 10.a, column A, that are past due 30 days or more or are in nonaccrual status as of the report date.
- 8.b Of non-U.S. addressees (domicile). Report in the appropriate column the amount of all lease financing receivables (net of unearned income) of non-U.S. addressees, as defined for Schedule RC-C, part I, item 10.b, column A, that are past due 30 days or more or are in nonaccrual status as of the report date.

Item No. Caption and Instructions

Debt securities and other assets. Report in the appropriate column all assets other than loans and leases reportable in Schedule RC-C that are past due 30 days or more or are in nonaccrual status as of the report date. Include such assets as debt securities and interest-bearing balances due from depository institutions. Exclude other real estate owned reportable in Schedule RC, item 7, and other repossessed assets reportable in Schedule RC, item 11, such as automobiles, boats, equipment, appliances, and similar personal property.

Loans and leases reported in items 1 through 8 above which are wholly or partially guaranteed by the U.S. Government. Report in the appropriate column the aggregate book value of all loans and leases reported in items 1 through 8 above for which repayment of principal is wholly or partially guaranteed by the U.S. Government, including its agencies and its government-sponsored agencies. Examples include loans guaranteed by the FDIC (through loss-sharing arrangements in FDIC-assisted acquisitions), the Small Business Administration, and the Federal Housing Administration. Amounts need not be reported in this item and in item 10.a below if they are considered immaterial.

<u>Exclude</u> from this item loans and leases guaranteed by state or local governments, state or local government agencies, foreign (non-U.S.) governments, and private agencies or organizations. Also <u>exclude</u> loans and leases collateralized by securities issued by the U.S. Government, including its agencies and its government-sponsored agencies.

Guaranteed portion of loans and leases included in item 10 above. Report in the appropriate column the maximum amount recoverable from the U.S. Government, including its agencies and its government-sponsored agencies, under the guarantee provisions applicable to the loans and leases included in Schedule RC-N, item 10, above.

Memoranda

Item No. Caption and Instructions

Restructured loans and leases included in Schedule RC-N, items 1 through 8, above. Report in the appropriate column the amount of restructured loans and leases (as defined above) that under their modified terms are past due 30 days or more or are in nonaccrual status as of the report date. Such loans and leases will have been included in one or more of the loan categories in items 1 through 8 of this schedule. However, exclude from this item all restructured loans secured by 1-to-4 family residential properties (included in Schedule RC-N, items 1.c.(1), 1.c.(2)(a), and 1.c.(2)(b)) and all restructured loans to individuals for household, family, and other personal expenditures (included in Schedule RC-N, items 5.a and 5.b).

Loans to finance commercial real estate, construction, and land development activities included in Schedule RC-N, items 4 and 7, above. Report in the appropriate column the amount of loans to finance commercial real estate, construction, and land development activities not secured by real estate, as defined for Schedule RC-C, part I, Memorandum item 3, that are past due 30 days or more or are in nonaccrual status as of the report date. Such loans will have been included in items 4 and 7 of Schedule RC-N above. Exclude from this item all loans secured by real estate included in item 1 of Schedule RC-N above.

NOTE: Memorandum item 3 is not applicable to banks filing the FFIEC 041 report form.

Loans secured by real estate to non-U.S. addressees (domicile). Report in the appropriate column the amount of all loans secured by real estate to non-U.S. addressees that are 30 days or more past due or are in nonaccrual status as of the report date. Such loans will have been included in Schedule RC-N, items 1.a through 1.f, above.

NOTE: Memorandum items 3.a through 3.c are <u>not</u> applicable to banks filing the FFIEC 031 report form. On the FFIEC 041 report form, Memorandum items 3.a through 3.c are <u>not</u> applicable to banks that have less than \$300 million in total assets.

- 3.a Loans secured by real estate to non-U.S. addressees (domicile). Report in the appropriate column the amount of all loans secured by real estate to non-U.S. addressees that are 30 days or more past due or are in nonaccrual status as of the report date. Such loans will have been included in Schedule RC-N, items 1.a through 1.e, above.
- **Loans to and acceptances of foreign banks.** Report in the appropriate column the amount of all loans to and acceptances of foreign banks as defined for Schedule RC-C, part I, items 2.a.(1) and 2.c.(2), column A, that are past due 30 days or more or are in nonaccrual status as of the report date. Such loans and acceptances will have been included in Schedule RC-N, item 2, above.
- 3.c Commercial and industrial loans to non-U.S. addressees (domicile). Report in the appropriate column the amount of all commercial and industrial loans to non-U.S. addressees, as defined for Schedule RC-C, part I, item 4.b, column A, that are past due 30 days or more or are in nonaccrual status as of the report date. Such loans will have been included in Schedule RC-N, item 4, above.

FFIEC 031 and 041 RC-N-9 RC-N - PAST DUE

Memoranda

Item No. Caption and Instructions

NOTE: Memorandum item 3.d is <u>not</u> applicable to banks filing the FFIEC 031 report form. On the FFIEC 041 report form, Memorandum item 3.d is <u>not</u> applicable to banks that have less than \$300 million in total assets.

3.d Lease financing receivables of non-U.S. addressees (domicile). Report in the appropriate column the amount of all lease financing receivables (net of unearned income) of non-U.S. addressees, as defined for Schedule RC-C, part I, item 10.b, column A, that are past due 30 days or more or are in nonaccrual status as of the report date. Such leases will have been included in Schedule RC-N, item 8, above.

NOTE: Memorandum item 4 is <u>not</u> applicable to banks filing the FFIEC 031 report form. On the FFIEC 041 report form, Memorandum item 4 is to be completed by:

- banks with \$300 million or more in total assets, and
- banks with less than \$300 million in total assets that have loans to finance agricultural production and other loans to farmers, as defined for Schedule RC-C, part I, item 3, column B, exceeding five percent of total loans.
 - Loans to finance agricultural production and other loans to farmers. Report in the appropriate column the amount of all loans to finance agricultural production and other loans to farmers, as defined for as defined for Schedule RC-C, part I, item 3, column B, that are past due 30 days or more or are in nonaccrual status as of the report date. Such loans will have been included in Schedule RC-N, item 7, above.
 - Loans and leases held for sale. Report in the appropriate column the amount of all loans and leases held for sale, as defined for Schedule RC, item 4.a, that are past due 30 days or more or are in nonaccrual status as of the report date. Such loans and leases will have been included in one or more of the loan and lease categories in items 1 through 8 of Schedule RC-N above.

NOTE: On the FFIEC 041, Memorandum item 6 is <u>not</u> applicable to banks that have less than \$300 million in total assets.

Interest rate, foreign exchange rate, and other commodity and equity contracts:

Fair value of amounts carried as assets. Report in the appropriate column the fair value of all interest rate, foreign exchange rate, equity, and commodity and other contracts (as defined for Schedule RC-L, item 12) on which a required payment by the bank's counterparty is past due 30 days or more as of the report date.

FFIEC 031 and 041 RC-N-10 RC-N - PAST DUE

SCHEDULE RC-O -- OTHER DATA FOR DEPOSIT INSURANCE AND FICO ASSESSMENTS

For purposes of deposit insurance and Financing Corporation (FICO) assessments and this schedule, "time and savings deposits" consists of all transaction accounts other than demand deposits -- i.e., NOW accounts, ATS accounts, and telephone and preauthorized transfer accounts -- and all nontransaction accounts. However, for all other items in the Reports of Condition and Income involving time or savings deposits, a strict distinction, based on Federal Reserve Board Regulation D definitions, is to be maintained between transaction accounts and time and savings accounts.

Item Instructions

Item No. Caption and Instructions

Unposted debits. Report the actual amount of cash items in the bank's possession, drawn on itself, that are immediately chargeable but that have not been charged to the general ledger deposit controlling account (for deposits in domestic offices and in insured branches in Puerto Rico and U.S. territories and possessions) at the close of business on the report date. Report only those items the bank elects to take as deductions on the deposit insurance assessment form (Certified Statement). However, report all unposted debits in Schedule RC, item 1.a, "Noninterest-bearing balances and currency and coin," whether or not they are reported in this item.

Drafts or warrants that are "payable at" or "payable through" the reporting bank may be reported as unposted debits if allowed under applicable state statute or if a written authorization, on file at the bank, allows the bank, at its discretion, to charge such items to the demand deposit account of the drawee. Such drafts and warrants that have already been charged to the general ledger deposit controlling account at the close of business on the report date or that the drawee does not have sufficient funds on deposit to pay, shall not be reported as unposted debits.

Exclude cash items drawn on other banks, overdrafts, nonsufficient funds (NSF) items, and cash items that are returned unpaid to the last endorser for any reason (e.g., stop payment, missing endorsement, post or stale date, or account closed).

Complete either item 1.a or items 1.b.(1) and 1.b.(2).

1.a Actual amount of all unposted debits. Report all unposted debits.

OR

- 1.b Separate amount of unposted debits:
- **1.b.(1)** Actual amount of unposted debits to demand deposits. Report unposted debits to demand deposits.
- **1.b.(2)** Actual amount of unposted debits to time and savings deposits. Report unposted debits to time and savings accounts.

FFIEC 031 and 041 RC-O-1 RC-O - ASSESSMENTS

Item No. Caption and Instructions

Unposted credits. Report the actual amount of unposted credits to deposit accounts (in domestic offices and in insured branches in Puerto Rico and U.S. territories and possessions). Unposted credits are those deposits that the reporting bank had received but not posted to its general ledger deposit control account at the close of business on the report date which have not otherwise been reported as deposits (in domestic offices) in Schedule RC, item 13.a (or, for insured branches in Puerto Rico and U.S. territories and possessions, in Schedule RC, item 13.b).

Unposted credits do not include any deposits that have been credited to the general ledger deposit control account as of the close of business on the report date (even if the deposits have not been posted to individual customer accounts). Rather, unposted credits are deposits carried in suspense or similar nondeposit accounts that, following a review of the items included in these accounts, have <u>not</u> been reclassified as deposits on the reporting bank's balance sheet (refer to the Glossary entry for "suspense accounts").

Complete either item 2.a or item 2.b.(1) and 2.b.(2).

2.a Actual amount of all unposted credits. Report all unposted credits.

OR

- 2.b Separate amount of unposted credits:
- **2.b.(1)** Actual amount of unposted credits to demand deposits. Report unposted credits to demand deposits.
- **2.b.(2)** Actual amount of unposted credits to time and savings deposits. Report unposted credits to time and savings accounts.
 - Uninvested trust funds (cash) held in bank's own trust department (not included in total deposits in domestic offices). Report all trust funds held in the bank's own U.S.-domiciled trust department that the bank keeps segregated and apart from its general assets and does not use in the conduct of its business. Include any trust overdrafts (net of disbursements in excess of principal and/or income cash in an individual trust account or accounts maintained in the same right and capacity) that reduce the bank's liability for deposits. The amount of such trust overdrafts may be reduced by the amount of any loan or advance (including any reserve for trust overdrafts) to the trust department that is included as a deposit in the Report of Condition.

Exclude trust funds received or held by the bank, whether held or deposited in any other department of the bank (report in Schedule RC-E, Deposit Liabilities). Also exclude trust funds deposited or held in any other bank or financial institution.

Deposits of consolidated subsidiaries (in domestic offices and in insured branches in Puerto Rico and U.S. territories and possessions) (not included in total deposits).

Report all deposits held in domestic offices of the reporting bank by its consolidated subsidiaries (including any consolidated bank or savings association subsidiaries) and the interest accrued and unpaid on such deposits. On the FFIEC 031, also report all deposits held by consolidated subsidiaries in insured branches in Puerto Rico and U.S. territories and possessions and the interest accrued and unpaid on such deposits. All deposits of and interest accrued and unpaid on deposits of subsidiaries consolidated in the Report of Condition should be eliminated from deposits reported in Schedule RC-E and other liabilities reported in Schedule RC-G, respectively.

Item No. Caption and Instructions

4.a Demand deposits of consolidated subsidiaries. Report all demand deposits held by consolidated subsidiaries (including any consolidated bank or savings association subsidiaries) in domestic offices of the reporting bank and in the reporting bank's insured branches in Puerto Rico and U.S. territories and possessions.

- 4.b <u>Time and savings deposits of consolidated subsidiaries</u>. Report all time and savings deposits held by consolidated subsidiaries (including any consolidated bank or savings association subsidiaries) in domestic offices of the reporting bank and in the reporting bank's insured branches in Puerto Rico and U.S. territories and possessions.
- Interest accrued and unpaid on deposits of consolidated subsidiaries. Report the amount of interest on deposits of consolidated subsidiaries (including any consolidated bank or savings association subsidiaries) in domestic offices of the reporting bank and in the reporting bank's insured branches in Puerto Rico and U.S. territories and possessions that has been accrued through charges to expense during the current or prior periods, but not yet paid or credited to a deposit account. For savings banks, include in this item "dividends" accrued and unpaid on deposits of consolidated subsidiaries. The accrued interest to be reported in this item will have been eliminated in consolidation and is therefore not included in the amount reported for domestic offices in Schedule RC-G, item 1.a, "Interest accrued and unpaid on deposits (in domestic offices)," or for insured branches in Puerto Rico and U.S. territories and possessions in Schedule RC-G, item 1.b, "Other expenses accrued and unpaid."

NOTE: Items 5, 5.a, 5.b, and 5.c are not applicable to banks filing the FFIEC 041 report form.

- Deposits in insured branches in Puerto Rico and U.S. territories and possessions.

 Report all deposits held in the reporting bank's insured branches in Puerto Rico and territories and U.S. possessions and all interest accrued and unpaid on such deposits (see the Glossary entry for "U.S. territories and possessions" for the definition of this term).
- 5.a Demand deposits in insured branches (included in Schedule RC-E, part II). Report all demand deposits held in the reporting bank's insured branches in Puerto Rico and U.S. territories and possessions. The deposits to be reported in this item will also have been included in Schedule RC-E, part II, Deposits in Foreign Offices.
- 5.b Time and savings deposits in insured branches (included in Schedule RC-E, part II).

 Report all time and savings deposits held in the reporting bank's insured branches in Puerto Rico and U.S. territories and possessions. The deposits to be reported in this item will also have been included in Schedule RC-E, part II, Deposits in Foreign Offices.
- 5.c Interest accrued and unpaid on deposits in insured branches (included in Schedule RC-G, item 1.b). Report the amount of interest on deposits in insured branches in Puerto Rico and U.S. territories and possessions accrued through charges to expense during the current or prior periods, but not yet paid or credited to a deposit account. The accrued interest to be reported in this item will also have been included in Schedule RC-G, item 1.b, "Other expenses accrued and unpaid."

FFIEC 031 and 041 RC-O-3 RC-O - ASSESSMENTS

Item No. Caption and Instructions

Reserve balances actually passed through to the Federal Reserve by the reporting bank on behalf of its respondent depository institutions that are also reflected as deposit liabilities of the reporting bank. If the reporting bank is the correspondent bank in a pass-through reserve balance relationship, report the amount of such reserve balances actually passed through to the Federal Reserve on behalf of respondent depository institutions that are also reflected as deposit liabilities of the reporting correspondent bank.

This item is not applicable to a bank that does not act as a correspondent bank in any pass-through reserve balance relationship. A state nonmember bank generally cannot act as a pass-through correspondent unless it maintains an account for its own reserve balances directly with the Federal Reserve.

For further information, see the Glossary entry for "pass-through reserve balances."

Amount reflected in demand deposits. If the reporting bank is the correspondent bank in a pass-through reserve balance relationship, report the amount of reserve balances the reporting correspondent bank has actually passed through to the Federal Reserve on behalf of its respondent depository institutions that are also reflected as demand deposit liabilities of (the domestic offices of) the reporting bank. These deposit liabilities will have been included in the amount reported in Schedule RC-E, (part I on the FFIEC 031), item 4, column A, and in total demand deposits reported in Schedule RC-E, (part I on the FFIEC 031), item 7, column B.

If the reporting bank is not a correspondent bank in any pass-through reserve balance relationship, report a zero or the word "none."

Amount reflected in time and savings deposits. If the reporting bank is the correspondent bank in a pass-through reserve balance relationship, report the amount of reserve balances the reporting correspondent bank has actually passed through to the Federal Reserve on behalf of its respondent depository institutions that are also reflected as time or savings deposit liabilities of (the domestic offices of) the reporting bank. These deposit liabilities will have been included in the amount reported in Schedule RC-E, (part I on the FFIEC 031), item 4, column A or C, but not in total demand deposits reported in Schedule RC-E, (part I on the FFIEC 031), item 7, column B.

If the reporting bank is not a correspondent bank in any pass-through reserve balance relationship, report a zero or the word "none."

7 Unamortized premiums and discounts on time and savings deposits. Report in the appropriate subitem the amount of unamortized premiums and discounts included in the amounts at which time and savings deposits (in domestic offices and in insured branches in Puerto Rico and U.S. territories and possessions) are reported in Schedule RC -- Balance Sheet, item 13, "Deposits."

For purposes of these reports, an unamortized premium or discount on a time or savings deposit is the difference between the amount actually due to the depositor and the carrying amount at which the deposit is reported on the Report of Condition balance sheet under applicable accounting and reporting standards. For example, in an acquisition of a depository institution accounted for as a purchase, the assets acquired and liabilities assumed generally

FFIEC 031 and 041 RC-O-4 RC-O - ASSESSMENTS

Item No. Caption and Instructions

must be recorded at their fair values. Because of changes in interest rates, the fair value of the acquired institution's time deposits may differ from the amount due to the depositors, causing the time deposits to be recorded at a premium or discount. Premiums or discounts on deposits may also arise in other situations, such as when a derivative contract has been used as a fair value hedge of time deposits and the gain or loss (that is, the change in fair value) on the hedged time deposits attributable to the hedged risk is recorded as an adjustment of the carrying amount of the time deposits.

Do not report core deposit intangibles in item 7.a or 7.b.

- 7.a <u>Unamortized premiums</u>. Report the amount of unamortized premiums (as defined above) included in the amounts at which time and savings deposits are reported in Schedule RC, item 13.
- 7.b <u>Unamortized discounts</u>. Report the amount of unamortized discounts (as defined above) included in the amounts at which time and savings deposits are reported in Schedule RC, item 13.

If the reporting bank has issued certificates of deposit at a discount and the amount actually due to the depositor as of the report date (before considering any early withdrawal penalty) equals the amount at which the certificate of deposit is reported in Schedule RC, item 13, the unamortized discount on the certificate of deposit should be excluded from this item.

- 8 Items 8.a.(1), 8.a.(2), and 8.b are to be completed by banks with "Oakar deposits."
- 8.a Deposits purchased or acquired from other FDIC-insured institutions during the quarter. Exclude from items 8.a.(1) and 8.a.(2) below the amount of deposits purchased or acquired from foreign offices of other FDIC-insured institutions other than insured branches in Puerto Rico and U.S. territories and possessions.
- 8.a.(1) Total deposits purchased or acquired from other FDIC-insured institutions during the quarter. Report the total amount of deposits purchased or acquired from other FDIC-insured banks and savings associations during the quarter ending with the report date without regard to the insurance fund to which these deposits are attributable. Exclude deposits purchased or acquired from foreign offices of other FDIC-insured institutions other than insured branches in Puerto Rico and U.S. territories and possessions.
- 8.a.(2) Amount of purchased or acquired deposits reported in item 8.a.(1) above attributable to a secondary fund. For banks that are members of the Bank Insurance Fund (BIF), report the amount of purchased or acquired deposits reported in item 8.a.(1) above that are attributable to the Savings Association Insurance Fund (SAIF), if any. For banks that are members of the SAIF, report the amount of purchased or acquired deposits reported in item 8.a.(1) above that are attributable to the BIF, if any.
- 8.b Total deposits sold or transferred to other FDIC-insured institutions during the quarter.

 Report the total amount of deposits sold or transferred to other FDIC-insured banks and savings associations during the quarter ending with the report date. Exclude sales and transfers of deposits in the reporting bank's foreign offices other than insured branches in Puerto Rico and U.S. territories and possessions.

FFIEC 031 and 041 RC-0-5 RC-O - ASSESSMENTS

Item No. Caption and Instructions

Deposits in lifeline accounts. Report the amount of deposits in lifeline accounts (in domestic offices) for which the reporting bank seeks a reduced deposit insurance assessment rate. Lifeline accounts are transaction accounts which meet certain minimum requirements established by the Federal Reserve Board pursuant to Section 232 of the Federal Deposit Insurance Corporation Improvement Act of 1991.

NOTE: The minimum requirements for lifeline accounts will be established by the Federal Reserve Board. Banks will not be required to submit information on such accounts in this Schedule RC-O item until these requirements are established.

Benefit-responsive "Depository Institution Investment Contracts." Report the amount of liabilities arising under "investment contracts not treated as insured deposits" (as defined in Section 11(a)(8) of the Federal Deposit Insurance Act) that is included on the balance sheet, Schedule RC, in item 13.a, "Deposits in domestic offices."

For purposes of this item, "investment contracts not treated as insured deposits" are those in the form of deposits between the reporting insured depository institution and any "employee benefit plan" (as defined in Section 11(a)(8) of the Federal Deposit Insurance Act) which expressly permit "benefit-responsive withdrawals or transfers." A "Depository Institution Investment Contract" is generally a separately negotiated depository agreement between an employee benefit plan and an insured depository institution which guarantees a specified rate for all deposits made over a prescribed period.

"Benefit-responsive withdrawals or transfers" is defined by Section 11(a)(8) of the Federal Deposit Insurance Act to mean "any withdrawal or transfer of funds (consisting of any portion of the principal and any interest credited at a rate guaranteed by the insured depository institution investment contract) during the period in which any guaranteed rate is in effect, without substantial penalty or adjustment, to pay benefits provided by the employee benefit plan or to permit a plan participant or beneficiary to redirect the investment of his or her account balance."

- Adjustments to demand deposits in domestic offices (and in insured branches in Puerto Rico and U.S. territories and possessions) reported in Schedule RC-E for certain reciprocal demand balances. Reciprocal balances arise when two depository institutions maintain deposit accounts with each other; that is, when a depository institution has both a due to and a due from balance with another depository institution. When reporting deposit liabilities in Schedule RC-E, reciprocal balances may be reported on a net basis when a right of setoff exists. However, the Federal Deposit Insurance Act (FDI Act) limits the extent to which reciprocal balances may be netted for deposit insurance and FICO assessment purposes. Thus, the reporting bank may have reported its reciprocal balances, if any, in Schedule RC-E differently than required for assessment purposes. The following three items capture these differences.
- 11.a Amount by which demand deposits would be reduced if the reporting bank's reciprocal demand balances with the domestic offices of U.S. banks and savings associations (and insured branches in Puerto Rico and U.S. territories and possessions) that were reported on a gross basis in Schedule RC-E had been reported on a net basis. For assessment purposes under the FDI Act, reciprocal demand balances with the domestic offices of U.S. banks and savings associations (and insured branches in Puerto Rico and U.S. territories and possessions) are to be reported on a net basis. If the

FFIEC 031 and 041 RC-O-6 RC-O - ASSESSMENTS

Item No. Caption and Instructions

11.a reporting bank reported any reciprocal demand balances with these domestic offices and insured branches on a gross basis in Schedule RC-E, report in this item the amount by which demand deposits would be reduced if these reciprocal demand balances had instead been reported on a net basis in Schedule RC-E, (part I,) item 7, column B, "Total" demand deposits. For each reciprocal demand balance relationship with one of these domestic offices or insured branches that was reported on a gross basis, the amount of this reduction is equal to the lesser of the demand balances "due from" or "due to" that domestic office or insured branch. Overdrawn balances cannot be included in this calculation.

- 11.b Amount by which demand deposits would be increased if the reporting bank's reciprocal demand balances with foreign banks and foreign offices of other U.S. banks (other than insured branches in Puerto Rico and U.S. territories and possessions) that were reported on a net basis in Schedule RC-E had been reported on a gross basis. For assessment purposes under the FDI Act, reciprocal demand balances between the reporting bank and foreign banks and foreign offices of other U.S. banks (other than insured branches in Puerto Rico and U.S. territories and possessions) are to be reported on a gross basis. If the reporting bank reported any reciprocal demand balances with these foreign banks and foreign offices on a net basis in Schedule RC-E, report in this item the amount by which demand deposits would be increased if these reciprocal demand balances had instead been reported on a gross basis in Schedule RC-E, (part I,) item 7, column B, "Total" demand deposits. For each reciprocal demand balance relationship with one of these foreign banks or foreign offices that was reported on a net basis, the amount of this increase is equal to the amount by which the gross "due to" demand balance for that bank or office was reduced before it was reported in Schedule RC-E, (part I,) item 7, column B, i.e., the lesser of the demand balances "due from" or "due to" that foreign bank or foreign office.
- Amount by which demand deposits would be reduced if cash items in process of collection were included in the calculation of the reporting bank's net reciprocal demand balances with the domestic offices of U.S. banks and savings associations (and insured branches in Puerto Rico and U.S. territories and possessions) in Schedule RC-E. For purposes of the Report of Condition, balances due from other depository institutions reflect only those funds on deposit for which the reporting bank has already received credit and which are subject to immediate withdrawal. Therefore, "due from" balances and calculations of net reciprocal demand balances for purposes of Schedule RC-E exclude cash items in process of collection. However, for deposit insurance assessment purposes under the FDI Act, cash items in process of collection should be included in the net reciprocal calculation.

Report in this item the amount by which demand deposits would be reduced if cash items in process of collection were included in the calculation of net reciprocal demand balances between the reporting bank and the domestic offices of U.S. banks and savings associations (and insured branches in Puerto Rico and U.S. territories and possessions) in Schedule RC-E, (part I,) item 7, column B, "Total" demand deposits.

Amount of assets netted against deposit liabilities (in domestic offices and in insured branches in Puerto Rico and U.S. territories and possessions) on the balance sheet (Schedule RC) in accordance with generally accepted accounting principles. Under generally accepted accounting principles, banks are permitted to offset or net assets and liabilities when a right of setoff exists. However, under the Federal Deposit Insurance Act

FFIEC 031 and 041 RC-O-7 RC-O - ASSESSMENTS

Item No. Caption and Instructions

(cont.) (FDI Act), only certain specified assets may be netted against deposit liabilities for deposit insurance and FICO assessment purposes. Thus, the reporting bank may have reported its deposits on the balance sheet (Schedule RC) and in Schedule RC-E differently than required for assessment purposes. The following items capture these differences, but exclude information for assessment purposes on the netting of reciprocal demand balances which is covered in Schedule RC-O, item 11, above.

The following examples illustrate the amounts to be reported in items 12.a and 12.b:

Example: Bank A has a \$200,000 asset and a \$500,000 deposit liability for which a right of setoff exists under generally accepted accounting principles. Bank A nets the asset and liability on its balance sheet (Schedule RC) and reports a (net) \$300,000 deposit liability. Bank A should report \$200,000 in item 12.a or 12.b, depending on the type of deposit involved in the netting.

Example: Bank B has a \$400,000 asset and a \$250,000 deposit liability for which a right of setoff exists under generally accepted accounting principles. Bank B nets the asset and liability on its balance sheet (Schedule RC) and reports a (net) \$150,000 asset. Bank B should report \$250,000 in item 12.a or 12.b, depending on the type of deposit involved in the netting.

- Amount of assets netted against demand deposits. If the reporting bank has netted any assets and demand deposit liabilities (in domestic offices and in insured branches in Puerto Rico and U.S. territories and possessions) on the balance sheet (Schedule RC) and in Schedule RC-E in accordance with generally accepted accounting principles, report in this item the amount by which this netting reduced the bank's reported demand deposits. Exclude hypothecated demand deposits (see the Glossary entry for "hypothecated deposit" for the definition of this term). Also exclude reciprocal demand balances that have been reported on a net basis.
- Amount of assets netted against time and savings deposits. If the reporting bank has netted any assets and time and savings deposit liabilities (in domestic offices and in insured branches in Puerto Rico and U.S. territories and possessions) on the balance sheet (Schedule RC) and in Schedule RC-E in accordance with generally accepted accounting principles, report in this item the amount by which this netting reduced the bank's reported time and savings deposits. Exclude hypothecated time and savings deposits (see the Glossary entry for "hypothecated deposit" for the definition of this term).

FFIEC 031 and 041 RC-O-8 RC-O - ASSESSMENTS

Memoranda

Item No. Caption and Instruction

1 Total deposits (in domestic offices) of the bank (and in insured branches in Puerto Rico and U.S. territories and possessions). Memorandum items 1.a.(1), 1.b.(1), and 1.b.(2) are to be completed each quarter. Memorandum item 1.a.(2) is to be completed for the June report only.

When determining the number and size of deposit accounts, each individual certificate, passbook, account, and other evidence of deposit is to be treated as a separate account. For purposes of completing this Memorandum item, multiple accounts of the same depositor should not be aggregated. In situations where a bank assigns a single account number to each depositor so that one account number may represent multiple deposit contracts between the bank and the depositor (e.g., one demand deposit account, one money market deposit account, and three certificates of deposit), each deposit contract is a separate account.

On the FFIEC 041 report form, the sum of Memorandum items 1.a.(1) and 1.b.(1) must equal Schedule RC, item 13.a, "Deposits in domestic offices." On the FFIEC 031 report form, the sum of Memorandum items 1.a.(1) and 1.b.(1) must equal the sum of Schedule RC, item 13.a, "Deposits in domestic offices," plus Schedule RC-O, items 5.a, "Demand deposits in insured branches" in Puerto Rico and U.S. territories and possessions, and 5.b, "Time and savings deposits in insured branches" in Puerto Rico and U.S. territories and possessions.

- **1.a** Deposit accounts of \$100,000 or less. Report in the appropriate subitem the amount outstanding and the number of accounts with a balance of \$100,000 or less as of the report date.
- **1.a.(1)** Amount of deposit accounts of \$100,000 or less. Report the aggregate balance of all deposit accounts, certificates, or other evidences of deposit (demand, savings, and time) with balances on the report date of \$100,000 or less. This amount should represent the total of the balances of the accounts enumerated in Memorandum item 1.a.(2) below.
- **Number of deposit accounts of \$100,000 or less.** (To be completed for the June report only.) Report the total number of deposit accounts (demand, savings, and time) with balances on the report date of \$100,000 or less. Count <u>each</u> certificate, passbook, account, and other evidence of deposit which has a balance of \$100,000 or less.
- **1.b Deposit accounts of more than \$100,000.** Report in the appropriate subitem the amount outstanding and the number of accounts with a balance of more than \$100,000 as of the report date.
- **Amount of deposit accounts of more than \$100,000.** Report the aggregate balance of each deposit account, certificate, or other evidence of deposit (demand, savings, and time) with a balance on the report date of more than \$100,000. This amount should represent the total of the balances of the accounts enumerated in Memorandum item 1.b.(2) below.
- **1.b.(2)**Number of deposit accounts of more than \$100,000. Report the total number of deposit accounts (demand, savings, and time) with balances on the report date of more than \$100,000. Count each certificate, passbook, account, and other evidence of deposit which has a balance of more than \$100,000.

FFIEC 031 and 041 RC-O-9 RC-O - ASSESSMENTS

Memoranda

Item No. Caption and Instruction

Estimated amount of uninsured deposits (in domestic offices of the bank and in insured branches in Puerto Rico and U.S. territories and possessions). Report the estimated amount of the bank's deposits (in domestic offices and in insured branches in Puerto Rico and U.S. territories and possessions) that is not covered by federal deposit insurance. The reporting of this information is mandated by Section 7(a)(9) of the Federal Deposit Insurance Act, which directs the FDIC to ensure that each insured institution maintains information on the total amount of uninsured deposits and provides this information to the FDIC on a regular basis.

The bank's estimate of its uninsured deposits should be reported in accordance with the following criteria. In this regard, it is recognized that a bank may have multiple automated information systems for different types of deposits and that the capabilities of a bank's information systems to provide an estimate of its uninsured deposits will differ from bank to bank at any point in time and, within an individual institution, may improve over time.

- (1) If the bank has brokered deposits, which must be reported in Schedule RC-E, Memorandum item 1.b, "Total brokered deposits," it must use the information it has developed for completing Schedule RC-E, Memorandum item 1.c, "Fully insured brokered deposits," to determine its best estimate of the uninsured portion of its brokered deposits.
- (2) If the bank has deposit accounts with balances of \$100,000 or more whose ownership is based on a fiduciary relationship, Part 330 of the FDIC's regulations generally states that the titling of the deposit account (together with the underlying records) must indicate the existence of the fiduciary relationship in order for insurance coverage to be available on a "pass-through" basis. Fiduciary relationships include, but are not limited to, relationships involving a trustee, agent, nominee, guardian, executor, or custodian.
 - A bank with fiduciary deposit accounts with balances of \$100,000 or more must diligently use the available data on these deposit accounts, including data indicating the existence of different principal and income beneficiaries, to determine its best estimate of the uninsured portion of these accounts.
- (3) If the bank has deposit accounts with balances of \$100,000 or more of employee benefit plans and eligible deferred compensation plans, Part 330 of the FDIC's regulations states that these accounts are insured on a "pass-through" basis for the non-contingent interest of each plan participant provided, in general, that the bank met each applicable regulatory capital standard at the time the deposit was accepted. In some instances, eligibility for this "pass-through" coverage is subject to written notification requirements.
 - A bank with employee benefit plan and eligible deferred compensation plan deposit accounts with balances of \$100,000 or more must diligently use the available data on these deposit accounts to determine its best estimate of the uninsured portion of these accounts.
- (4) If the bank's deposit accounts include benefit-responsive "Depository Institution Investment Contracts," which must be reported in Schedule RC-O, item 10, these deposit liabilities are not eligible for federal deposit insurance pursuant to Section 11(a)(8) of the Federal Deposit Insurance Act. A bank with benefit-responsive "Depository Institution Investment Contracts" must include the entire amount of these contracts in the estimated amount of uninsured deposits it reports in this Memorandum item 2.

FFIEC 031 and 041 RC-O-10 RC-O - ASSESSMENTS

Memoranda

Item No. Caption and Instruction

2 (cont.)

- (5) If the bank has deposit accounts with balances in excess of the federal deposit insurance limit that it has collateralized by pledging assets, such as deposits of the U.S. Government and of states and political subdivisions in the U.S. (which must be reported in Schedule RC-E, items 2 and 3, and, on the FFIEC 031 report form, in Schedule RC-E, part II, item 5), the bank should make a reasonable estimate of the portion of these deposits that is uninsured using the data available from its information systems.
- (6) If the bank has deposit accounts with balances in excess of the federal deposit insurance limit for which it has acquired private deposit insurance to cover this excess amount, the bank should make a reasonable estimate of the portion of these deposits that is not insured by the FDIC using the data available from its information systems.
- (7) For all other deposit accounts, the bank should make a reasonable estimate of the portion of these deposits that is uninsured using the data available from its information systems. In developing this estimate, if the bank has automated information systems in place that enable it to identify jointly owned accounts and estimate the deposit insurance coverage of these deposits, the higher level of insurance afforded these joint accounts should be taken into consideration. Similarly, if the bank has automated information systems in place that enable it to classify accounts by deposit owner and/or ownership capacity, the bank should incorporate this information into its estimate of the amount of uninsured deposits by aggregating accounts held by the same deposit owner in the same ownership capacity before applying the \$100,000 insurance limit. Ownership capacities include, but are not limited to, single ownership, joint ownership, business (excluding sole proprietorships), revocable trusts, irrevocable trusts, and retirement accounts.

In the absence of automated information systems, a bank may use nonautomated information such as paper files or less formal knowledge of its depositors if such information provides reasonable estimates of appropriate portions of its uninsured deposits. A bank's use of such nonautomated sources of information is considered appropriate unless errors associated with the use of such sources would contribute significantly to an overall error in the FDIC's estimate of the amount of insured and uninsured deposits in the banking system.

Has the reporting institution been consolidated with a parent bank or savings association in that parent bank's or parent savings association's Call Report or Thrift Financial Report? If the reporting bank is owned by another bank or savings association and that parent bank or parent savings association is consolidating the reporting bank as part of the parent institution's Call Report or Thrift Financial Report for this report date, report the legal title and FDIC Certificate Number of the parent institution in this item.

FFIEC 031 and 041 RC-O-11 RC-O - ASSESSMENTS

SCHEDULE RC-R - REGULATORY CAPITAL

General Instructions

The instructions for Schedule RC-R should be read in conjunction with the capital guidelines issued by the reporting bank's primary federal supervisory authority. Under the banking agencies' risk-based capital guidelines, assets and credit equivalent amounts of derivatives and off-balance sheet items are assigned to one of several broad risk categories according to the obligor, or, if relevant, the guarantor or the nature of the collateral. The aggregate dollar amount in each risk category is then multiplied by the risk weight associated with that category. The resulting weighted values from each of the risk categories are added together, and generally this sum is the bank's total risk weighted assets which comprises the denominator of the risk-based capital ratio.

Risk weights for derivative contracts and off-balance sheet items are determined by a two-step process. First, the "credit equivalent amount" is determined. In the case of derivative contracts, the credit equivalent amount is the sum of the current credit exposure (fair value of the contract, if positive) and the potential future exposure. In the case of most off-balance sheet items, the credit equivalent amount is determined by multiplying the face value or notional amount of the off-balance sheet item by a credit conversion factor. Second, the credit equivalent amount is treated like a balance sheet asset and generally is assigned to the appropriate risk category according to the obligor or, if relevant, the guarantor or the nature of the collateral. A summary of the credit conversion factors for off-balance sheet items is presented below.

In general, if a particular asset, derivative contract, or off-balance sheet item has features that could place it in more than one risk category, it is assigned to the category that has the lowest risk weight. For example, a holding of a U.S. municipal revenue bond that is fully guaranteed by a U.S. bank would be assigned the 20 percent risk weight appropriate to claims guaranteed by U.S. banks, rather than the 50 percent risk weight appropriate to U.S. municipal revenue bonds.

At each bank's option, assets and the credit equivalent amounts of derivative contracts and off-balance sheet items that are assigned to a risk weight category of less than 100 percent may be included in the amount reported for a higher risk weight category (e.g., the 100 percent category) than the risk weight category to which the asset or credit equivalent amount of the off-balance sheet item would otherwise be assigned.

For risk-based capital purposes, the term "claim" refers to loans to, securities issued by, balances due from, accrued interest receivable from, and all other claims against the various entities with which the reporting bank conducts its business.

If a reporting bank has conveyed risk participations in bankers acceptances, standby letters of credit, and commitments, it may segregate the amounts conveyed from the total outstanding amount. The bank may then risk weight the amounts conveyed according to the guarantors (i.e., the parties that have acquired the conveyances) separately from the amounts retained if this results in a lower risk weight for the amounts conveyed.

When assets have been transferred with recourse, the amount of risk-based capital required to be maintained to support this exposure may not exceed the maximum amount of recourse for which the transferring institution is contractually liable under the recourse agreement. This rule applies to recourse transactions in which a bank contractually limits its recourse exposure to less than the full effective minimum risk-based capital requirement for the assets transferred -- generally, four percent for first lien residential mortgage loans and eight percent for most other assets. These types of asset transfers are referred to as low level recourse transactions and should be reported in Schedule RC-R, item 50, column A.

General Instructions (cont.)

<u>Credit Conversion Factors for Off-Balance Sheet Items</u> -- A summary of the credit conversion factors follows. For further information on these factors, refer to the risk-based capital guidelines.

Off-balance sheet items subject to a 100 percent conversion factor:

- (1) Direct credit substitutes, including general guarantees of indebtedness and guarantee -type instruments, such as financial standby letters of credit.
- (2) Risk participations acquired in bankers acceptances and in direct credit substitutes such as financial standby letters of credit.
- (3) Sale and repurchase agreements and assets sold with recourse, if not included on the balance sheet, except low level recourse transactions and small business obligations transferred with recourse under Section 208 of the Riegle Community Development and Regulatory Improvement Act of 1994, each of which is discussed below.
- (4) Forward agreements/contingent obligations to purchase assets with drawdown certain. (Exclude forward agreements that are reported as derivative contracts.)
- (5) Securities lent, if the lending bank is exposed to risk of loss.

Off-balance sheet items subject to a 50 percent conversion factor:

- (1) Transaction-related contingencies, including performance standby letters of credit, shipside guarantees, bid bonds, performance bonds, and warranties.
- (2) Unused portions of commitments with an original maturity exceeding one year, including underwriting commitments and commercial credit lines.
- (3) Revolving underwriting facilities (RUFs), note issuance facilities (NIFs), and other similar arrangements, regardless of maturity.

Off-balance sheet items subject to a 20 percent conversion factor:

(1) Short-term, self-liquidating, trade-related contingencies, including commercial letters of credit.

Off-balance sheet items subject to a zero percent conversion factor:

- (1) Unused portions of commitments with an original maturity of one year or less.
- (2) Unused portions of commitments (regardless of maturity) which are unconditionally cancellable at any time, provided a separate credit decision is made before each drawing.

Item Instructions

Item No. Caption and Instructions

Tier 1 Capital

- **Total equity capital.** Report the amount of the bank's total equity capital as reported in Schedule RC, item 28.
- LESS: Net unrealized gains (losses) on available-for-sale securities. Report the amount of net unrealized holding gains (losses) on available-for-sale securities that is included in Schedule RC, item 26.b, "Accumulated other comprehensive income." If the amount is a net unrealized holding gain, report it as a positive value in this item. If the amount is a net unrealized holding loss, report it as a negative value in this item.
- 3 <u>LESS: Net unrealized loss on available-for-sale equity securities.</u> Report as a positive value the amount of any net unrealized holding loss on available-for-sale equity securities that is included in Schedule RC, item 26.b, "Accumulated other comprehensive income."

Item No. Caption and Instructions

- LESS: Accumulated net gains (losses) on cash flow hedges. Report the amount of accumulated net gains (losses) on cash flow hedges that is included in Schedule RC, item 26.b, "Accumulated other comprehensive income." If the amount is an accumulated net gain, report it as a positive value in this item. If the amount is an accumulated net loss, report it as a negative value in this item.
- 5 <u>LESS: Nonqualifying perpetual preferred stock.</u> Report the portion of perpetual preferred stock (and any related surplus) included in Schedule RC, item 23, that **does not** qualify for inclusion in Tier 1 capital based on the capital guidelines of the bank's primary federal supervisory authority. Generally, banks should include in this item the book value of all perpetual preferred stock except for noncumulative perpetual preferred stock. However, noncumulative perpetual preferred stock in which the dividend rate is periodically reset based on the bank's credit standing or financial condition e.g., Dutch auction, money market, and remarketable preferred stock, is not eligible for Tier 1 capital and should be included in this item. Although the amount reported in this item is not eligible for Tier 1 capital, it may be eligible for inclusion in Tier 2 capital in Schedule RC-R, item 13.
- Qualifying minority interests in consolidated subsidiaries. Report the portion of minority interests in consolidated subsidiaries included in Schedule RC, item 22, that is eligible for inclusion in Tier 1 capital based on the capital guidelines of the bank's primary federal supervisory authority. Generally, banks may include minority interests in equity capital accounts (both common and noncumulative perpetual preferred stocks) of consolidated subsidiaries unless such accounts would not otherwise qualify for inclusion in Tier 1 capital. For example, a bank may not include minority interests representing cumulative preferred stock in consolidated subsidiaries since such preferred stock if issued directly by the bank would not eligible for inclusion in Tier 1 capital.
- The state of the portion of goodwill included in Schedule RC, item 10.a, and the portion of other identifiable intangible assets included in Schedule RC-M, item 2.c, that does not qualify for inclusion in Tier 1 capital based on the capital guidelines of the bank's primary federal supervisory authority. Generally, all goodwill reported in Schedule RC, item 10.a, and all other identifiable intangible assets reported in Schedule RC-M, item 2.c, do not qualify for Tier 1 capital and should be included in this item.

However, if the bank has a deferred tax liability that is specifically related to an intangible asset (other than servicing assets and purchased credit card relationships) acquired in a nontaxable purchase business combination that it chooses to net against the intangible asset for regulatory capital purposes, the amount of disallowed intangibles to be reported in this item should be reduced by the amount of this deferred tax liability. However, a deferred tax liability that the bank chooses to net against the related intangible asset for purposes of this item may not also be netted against deferred tax assets when the bank determines the amount of deferred tax assets that are dependent upon future taxable income and calculates the maximum allowable amount of such deferred tax assets for regulatory capital purposes.

For state member banks, if the amount reported for other identifiable intangible assets in Schedule RC-M, item 2.c, includes intangible assets that were recorded on the reporting bank's balance sheet on or before February 19, 1992, the remaining book value as of the report date of these intangible assets may be excluded from this item.

Item No. Caption and Instructions

- **Subtotal.** Report the sum of Schedule RC-R, items 1 and 6, less items 2, 3, 4, 5, and 7. The amount reported in this item should be used to determine the limitations on servicing assets and purchased credit card relationships for Schedule RC-R, item 9.a; deferred tax assets for Schedule RC-R, item 9.b; and credit-enhancing interest-only strips for Schedule RC-R, item 10, below.
- 9.a LESS: Disallowed servicing assets and purchased credit card relationships. Report the portion of servicing assets and purchased credit card relationships included in Schedule RC-M, items 2.a and 2.b, that does not qualify for inclusion in Tier 1 capital based on the capital guidelines of the bank's primary federal supervisory authority. Generally, servicing assets and purchased credit card relationships (PCCRs) are limited to 100 percent of Tier 1 capital. In addition, nonmortgage servicing assets and PCCRs are subject to a separate sublimit of 25 percent of Tier 1 capital. Banks may use the following approach to determine the amount of disallowed servicing assets and PCCRs.

Disallowed Mortgage Servicing Assets, Nonmortgage Servicing Assets, and PCCRs Calculation

(a)	Enter the amount from Schedule RC-R, item 8	
(b)	Enter 25% of the amount in (a) above	
(c)	Enter the amount of nonmortgage servicing assets and PCCRs reported in Schedule RC-M, item 2.b	
(d)	Enter 90% of the fair value of the nonmortgage servicing assets and PCCRs reported in (c) above	
(e)	Enter the lesser of (b), (c), or (d)	
(f)	Minimum amount of nonmortgage servicing assets and PCCRs to be deducted from Tier 1 capital: subtract (e) from (c); enter 0 if the result is a negative amount	
(g)	Enter the amount of mortgage servicing assets reported in Schedule RC-M, item 2.a	
(h)	Enter 90% of the estimated fair value of mortgage servicing assets reported in Schedule RC-M, item 2.a.(1)	
(i)	Enter the lesser of (a), (g), or (h)	
(j)	Minimum amount of mortgage servicing assets to be deducted from Tier 1 capital: subtract (i) from (g); enter 0 if the result is a negative amount	
(k)	Excess nonmortgage servicing assets, PCCRs, and mortgage servicing assets (i.e., the combined amount exceeding 100% of Tier 1 capital): sum of (e) and (i) minus (a); enter 0 if the result is a negative amount	
(I)	Disallowed nonmortgage servicing assets, PCCRs, and mortgage servicing assets: enter the sum of (f), (j), and (k)	

9.b

Item No. Caption and Instructions

LESS: Disallowed deferred tax assets. Report the portion of net deferred tax assets included in Schedule RC-F, item 2, that does not qualify for inclusion in Tier 1 capital based on the capital guidelines of the reporting bank's primary federal supervisory authority. Generally, deferred tax assets that are dependent upon future taxable income are limited to the lesser of: (i) the amount of such deferred tax assets that the bank expects to realize within one year of the calendar quarter-end date, based on its projected future taxable income for that year or (ii) 10% of the amount of the bank's Tier 1 capital that exists before the deduction of any disallowed servicing assets and purchased credit card relationships and any disallowed deferred tax assets. A bank may calculate one overall limit on deferred tax assets that covers all tax jurisdictions in which the bank operates.

Deferred tax assets that are dependent upon future taxable income are (a) deferred tax assets arising from deductible temporary differences that exceed the amount of taxes previously paid that a bank could recover through loss carrybacks if the bank's temporary differences (both deductible and taxable) fully reverse at the report date and (b) deferred tax assets arising from operating loss and tax credit carryforwards. Therefore, for purposes of this item, all temporary differences should be assumed to fully reverse at the report date.

A bank may use its future taxable income projection for its current fiscal year (adjusted for any significant changes that have occurred or are expected to occur) when determining the regulatory capital limit for its deferred tax assets at an interim calendar quarter-end date rather than preparing a new projection each quarter. Projected future taxable income should not include net operating loss carryforwards expected to be used within one year of the quarter-end report date or the amount of existing temporary differences expected to reverse within that year, but should include the estimated effect of tax planning strategies that are expected to be implemented to realize carryforwards that will otherwise expire during that year.

When determining the amount to be reported in this item, each reporting bank's calculations should be made on a separate entity basis. Under the separate entity method, a bank (together with its consolidated subsidiaries) that is a subsidiary of a holding company is treated as a separate taxpayer rather than as part of the consolidated group of which it is a member.

Deferred tax assets which can be realized from taxes paid in prior carryback years and from future reversals of existing taxable temporary differences should generally not be reported in this item. However, for a bank that is a subsidiary of a holding company, the parent holding company may not have the financial capability to reimburse the reporting bank for tax benefits derived from the bank's carryback of net operating losses or tax credits. In such a situation, when determining the amount of deferred tax assets that are dependent upon future taxable income, the amount of carryback potential the bank may consider as being available for the realization of its deferred tax assets shall be limited to the amount which the bank could reasonably expect to have refunded by its parent.

<u>Treatment of deferred tax assets relating to available-for-sale securities</u> -- In accordance with FASB Statement No. 115, *Accounting for Certain Investments in Debt and Equity Securities*, available-for-sale securities are reported in the Reports of Condition and Income at fair value, with unrealized holding gains and losses on such securities, net of tax effects, included in a separate component of equity capital. These tax effects may increase or decrease the reported amount of a bank's deferred tax assets. The federal banking agencies exclude from regulatory capital the amount of net unrealized holding gains and losses on available-for-sale securities (except net unrealized holding losses on available-for-sale equity securities with

Item No. Caption and Instructions

9.b (cont.)

readily determinable fair values). When determining the regulatory capital limit for deferred tax assets, a bank may, but is not required to, adjust the amount of its deferred tax assets for any deferred tax assets and liabilities arising from marking-to-market available-for-sale debt securities for purposes of these reports. A bank must follow a consistent approach with respect to such adjustments.

Banks may use the following approach to determine the amount of disallowed deferred tax assets.

Disallowed Deferred Tax Assets Calculation

(a)	Enter the amount from Schedule RC-R, item 8	
(b)	Enter 10% of the amount in (a) above	
(c)	Enter the amount of deferred tax assets reported in Schedule RC-F, item 2	
(d)	Enter the amount of taxes previously paid that the bank could recover through loss carrybacks if the bank's temporary differences (both deductible and taxable) fully reverse at the report date	
(e)	Amount of deferred tax assets that is dependent upon future taxable income: subtract (d) from (c); enter 0 if the result is a negative amount	
(f)	Enter the portion of (e) that the bank could realize within the next 12 months based on its projected future taxable income. Future taxable income should not include net operating loss carryforwards to be used during the next 12 months or existing temporary differences that are expected to reverse over the next 12 months.	
(g)	Enter the lesser of (b) and (f)	
(h)	Disallowed net deferred tax assets - subtract (g) from (e); enter 0 if the result is a negative amount	

Other additions to (deductions from) Tier 1 capital. Report the amount of any additions to or deductions from Tier 1 capital based on the capital guidelines of the reporting bank's primary federal supervisory authority that are not included in Schedule RC-R, items 1 through 9.b, above. If the amount to be reported in this item is a net deduction, enclose the amount in parentheses.

For example, include the portion of credit-enhancing interest-only strips included in the bank's total assets that **does not** qualify for inclusion in Tier 1 capital based on the capital guidelines of the bank's primary federal supervisory authority. A credit-enhancing interest-only strip is defined in the capital guidelines as "an on-balance sheet asset that, in form or in substance: (i) represents the contractual right to receive some or all of the interest due on transferred assets; and (ii) exposes the bank to credit risk directly or indirectly associated with the transferred assets that exceeds a pro rata share of the bank's claim on the assets, whether through subordination provisions or other credit enhancement techniques." Credit-enhancing interest-only strips include other similar "spread" assets and can be either retained or purchased. In general, credit-enhancing interest-only strips are limited to 25 percent of Tier 1

Item No. Caption and Instructions

amount

capital. Banks may use the following approach to determine the amount of disallowed credit-enhancing interest-only strips.

Disallowed Credit-Enhancing Interest-Only Strips Calculation			
(a)	Enter the amount from Schedule RC-R, item 8		
(b)	Enter 25% of the amount in (a) above		
(c)	Retained credit-enhancing interest-only strips from Schedule RC-S, items 2.a and 12: enter the fair value of those strips included in Schedule RC, item 5, "Trading assets," and the amortized cost of those strips not held for trading ¹		
(d)	Purchased credit-enhancing interest-only strips included in Schedule RC-S, item 9: ² enter the fair value of those strips included in Schedule RC, item 5, "Trading assets," and the amortized cost of those strips not held for trading ³		
(e)	Total credit-enhancing interest-only strips: enter the sum of (c) and (d)		
(f)	Enter the lesser of (b) and (e)		
(g)	Disallowed credit-enhancing interest-only strips: subtract (f) from (e); enter 0 if the result is a negative		

If the bank has disallowed credit-enhancing interest-only strips, i.e., line (g) in the preceding calculation is a positive amount, include this amount as a deduction from Tier 1 capital in this item. Banks are permitted, but not required, to deduct disallowed credit-enhancing interest-only strips, i.e., the amount from line (g) above, on a basis that is net of a proportional amount of any associated deferred tax liability recorded on the balance sheet. Any deferred tax liability used in this manner would not be available for the bank to use in determining the amount of disallowed deferred tax assets in Schedule RC-R, item 9.b, above.

In addition, insured state banks with real estate subsidiaries whose continued operations have been approved by the FDIC pursuant to Section 362.4 of the FDIC's Rules and Regulations should deduct from Tier 1 capital, as appropriate: (a) any equity investment in the subsidiary, (b) any debt issued by the subsidiary that is held by the bank or guarantees by the bank of any debt issued by the subsidiary, and (c) any extensions of credit from the bank to the subsidiary. (Insured state banks with FDIC-approved phase-out plans for real estate subsidiaries need not make these deductions.)

Banks with financial subsidiaries should exclude from this item adjustments to Tier 1 capital for the deconsolidation of such subsidiaries. Adjustments to Tier 1 capital for financial subsidiaries should be reported in Schedule RC-R, item 28.a, below.

FFIEC 031 and 041 RC-R-7 RC-R – REGULATORY CAPITAL (3-02)

¹ While credit-enhancing interest-only strips not held for trading are reported at fair value in Schedule RC-S, the amortized cost of these strips should be used in this calculation.

² Also include any purchased interest-only strips that act as credit enhancements for assets that have not been securitized because these strips are not reported in Schedule RC-S, item 9.

³ See footnote 1 above.

Tier 1 capital. Report the sum of Schedule RC-R, items 8 and 10, less items 9.a and 9.b. If the bank has no financial subsidiaries, the amount reported in this item is the numerator of the bank's Tier 1 risk-based capital ratio and its Tier 1 leverage ratio.

Tier 2 Capital

- Qualifying subordinated debt and redeemable preferred stock. Report the portion of the bank's qualifying limited-life capital instruments that is includible in Tier 2 capital based on the capital guidelines of the reporting bank's primary federal supervisory authority. This amount is the sum of:
 - the portion of qualifying subordinated debt and intermediate-term preferred stock includible in Tier 2 capital, and
 - (2) the portion of qualifying other limited-life capital instruments includible in Tier 2 capital.

The portion of limited-life capital instruments that is includible in Tier 2 capital is the amount that remains after discounting those instruments, if any, with five years or less until maturity and then applying any applicable percentage of Tier 1 capital limit. For limited-life capital instruments with serial maturities or with sinking fund provisions, the amount associated with each maturity date is to be treated as a separate issue and discounted on an individual basis. If the holder of the reporting bank's subordinated debt or intermediate-term or long-term preferred stock has the right to require the bank to redeem, repay, or repurchase the instrument prior to the original stated maturity, then maturity would be defined as the earliest possible date on which the holder can put the instrument back to the issuing bank.

Qualifying term subordinated debt and intermediate-term preferred stock (including any related surplus) must have an original weighted average maturity of at least five years. Intermediate-term preferred stock includes those issues of preferred stock with an original maturity of less than 20 years. Mandatory convertible debt, i.e., equity contract notes, is not considered a limited-life capital instrument for risk-based capital purposes and should be excluded from this item.

The portion of qualifying term subordinated debt and intermediate-term preferred stock that remains after discounting and is includible in Tier 2 capital is limited to 50 percent of Tier 1 capital. This portion is calculated as follows:

(A1)	Amount of subordinated debt and intermediate-term preferred stock with a remaining maturity of more than five years	x 100% =
(A2)	Amount of subordinated debt and intermediate-term preferred stock with a remaining maturity of more than four years, but less than five years	x 80% =
(A3)	Amount of subordinated debt and intermediate-term preferred stock with a remaining maturity of more than three years, but less than four years	x 60% =
(A4)	Amount of subordinated debt and intermediate-term preferred stock with a remaining maturity of more than two years, but less than three years	x 40% =
(A5)	Amount of subordinated debt and intermediate-term preferred stock with a remaining maturity of more than one year, but less than two years	x 20% =

12 (A6) Amount of subordinated debt and intermediate-term (cont.) preferred stock with a remaining maturity of one year or less Χ 0% = Qualifying subordinated debt and intermediate-term preferred stock (sum of discounted amounts of lines (A1) through (A6)) Tier 1 capital (from Schedule RC-R, item 11) (A9) Multiplied by 50 percent x 50% (A10) Limit for qualifying subordinated debt and intermediate-term preferred stock (line (A8) multiplied by 50 percent) (A11) Portion of qualifying subordinated debt and intermediate-term preferred stock includible in Tier 2

The entire amount of qualifying other limited-life capital instruments, such as long-term preferred stock with an original maturity of 20 years or more, that remains after discounting is includible in Tier 2 capital. This portion is calculated as follows:

(B1) Amount of other limited-life capital instruments with a remaining maturity of more than five years

____x 100% =____

(B2) Amount of other limited-life capital instruments with a remaining maturity of more than four years, but less than five years

capital (lesser of lines (A7) and (A10))

x 80% =

(B3) Amount of other limited-life capital instruments with a remaining maturity of more than three years, but less than four years

____x 60% =____

(B4) Amount of other limited-life capital instruments with a remaining maturity of more than two year, but less than three years

x 40% =

(B5) Amount of other limited-life capital instruments with a remaining maturity of more than one year, but less than two years

x 20% =

(B6) Amount of other limited-life capital instruments with a remaining maturity of one year or less

x 0% =

(B7) Portion of qualifying other limited-life capital instruments (sum of discounted amounts of lines (B1) through (B6))

Report the sum of the amounts from lines (A11) and (B7) above in Schedule RC-R, item 12.

Cumulative perpetual preferred stock includible in Tier 2 capital. Report the amount of outstanding cumulative perpetual preferred stock, including any amounts received in excess of its par or stated value, that is included in Schedule RC, item 23. Also include perpetual preferred stock issues that were excluded from Tier 1 capital such as noncumulative perpetual preferred where the dividend is reset periodically based, in whole or in part, upon the bank's current credit standing (including, but not limited to, auction rate, money market, and remarketable preferred stock).

Allowance for loan and lease losses includible in Tier 2 capital. Report the portion of the bank's allowance for loan and lease losses that is includible in Tier 2 capital. The amount reported in this item cannot exceed 1.25 percent of the bank's *gross* risk-weighted assets. For risk-based capital purposes, the allowance for loan and lease losses is the sum of Schedule RC, item 4.c, "Allowance for loan and lease losses," plus Schedule RC-G, item 3, "Allowance for credit losses on off-balance sheet credit exposures."

Gross risk-weighted assets is reported in Schedule RC-R, item 59. If the bank has any low level exposure transactions or residual interests and chooses to use the "direct reduction method" for reporting these transactions in Schedule RC-R, refer to the discussion of this subject in the instructions for Schedule RC-R, item 50, "Recourse and direct credit substitutes (other than financial standby letters of credit) subject to the low level exposure rule and residual interests subject to a dollar-for-dollar capital requirement," for guidance on determining the limit on the allowance for loan and lease losses for Tier 2 capital purposes.

- 15 Unrealized gains on available-for-sale equity securities includible in Tier 2 capital.

 Report the pretax net unrealized holding gain (i.e., the excess of fair value as reported in Schedule RC-B, item 7, column D, over historical cost as reported in Schedule RC-B, item 7, column C), if any, on available-for-sale equity securities that is includible in Tier 2 capital subject to the limits specified by the capital guidelines of the reporting bank's primary federal supervisory authority. The amount reported in this item cannot exceed 45 percent of the bank's pretax net unrealized holding gain on available-for-sale equity securities with readily determinable fair values.
- Other Tier 2 capital components. Report the amount of any items that qualify for inclusion in Tier 2 capital based on the capital guidelines of the reporting bank's primary federal supervisory authority that are not included in Schedule RC-R, items 12 through 15, above. Include mandatory convertible debt, i.e., equity contract notes, which is a form of subordinated debt that obligates the holder to take the common or perpetual preferred stock of the issuer in lieu of cash for repayment of principal.
- 17 <u>Tier 2 capital.</u> Report the sum of Schedule RC-R, items 12 through 16.
- Allowable Tier 2 capital. Report the amount of the bank's allowable Tier 2 capital. The maximum amount of Tier 2 capital that is allowable in a bank's qualifying total capital is 100 percent of Tier 1 capital. The amount reported in this item must be the lesser of Schedule RC-R, item 11, "Tier 1 capital," and item 17, "Tier 2 capital," if item 11 is a positive number. If Schedule RC-R, item 11, is a negative number, report a zero in this item.
- Tier 3 capital allocated for market risk. Report the amount of the bank's Tier 3 capital allocated for market risk. This item is only applicable to banks that are subject to the market risk capital guidelines. The amount reported in this item may only be used to satisfy the bank's market risk capital requirement and may not be used to support credit risk. The sum of the amount reported in this item and the amount reported in Schedule RC-R, item 18, "Allowable Tier 2 capital," must be less than or equal to the amount reported in Schedule RC-R, item 11, "Tier 1 capital." In addition, Tier 3 capital allocated for market risk plus Tier 2 capital allocated for market risk are limited to 71.4 percent of a bank's measure for market risk.

- LESS: Deductions for total risk-based capital. Report the amount of the bank's investments in banking and finance subsidiaries that are not consolidated for regulatory capital purposes, intentional reciprocal cross-holdings of banking organizations' capital instruments, and any other deductions for total risk-based capital as determined by the reporting bank's primary federal supervisory authority. Banks with financial subsidiaries should exclude adjustments to total risk-based capital for the deconsolidation of such subsidiaries. Adjustments to total risk-based capital for financial subsidiaries should be reported in Schedule RC-R, item 28.b, below.
- **Total risk-based capital.** Report the sum of Schedule RC-R, items 11, 18, and 19, less item 20. The amount reported in this item is the numerator of the bank's total risk-based capital ratio.

Total assets for leverage ratio

- **Average total assets.** Report the bank's average total assets as reported in Schedule RC-K, item 9.
- 23 <u>LESS: Disallowed goodwill and other disallowed intangible assets.</u> Report the amount of any disallowed goodwill and other disallowed intangible assets from Schedule RC-R, item 7, above.
- 24 <u>LESS: Disallowed servicing assets and purchased credit card relationships.</u> Report the amount of any disallowed servicing assets and purchased credit card relationships from Schedule RC-R, item 9.a, above.
- **LESS:** Disallowed deferred tax assets. Report the amount of any disallowed deferred tax assets from Schedule RC-R, item 9.b, above.
- LESS: Other deductions from assets for leverage capital purposes. Report the amount of any other assets that are deducted in determining Tier 1 capital in accordance with the capital standards issued by the reporting bank's primary federal supervisory authority. Include the amount of any disallowed credit-enhancing interest-only strips from Schedule RC-R, item 10, above.

Banks with financial subsidiaries should exclude from this item adjustments to average total assets for the deconsolidation of such subsidiaries. Adjustments to average total assets for financial subsidiaries should be reported in Schedule RC-R, item 30, below.

Average total assets for leverage capital purposes. Report Schedule RC-R, item 22, less items 23 through 26.

Adjustments for financial subsidiaries

NOTE: Schedule RC-R, items 28.a through 30, and column A of items 31 through 33 are only to be completed by banks with "financial subsidiaries" as defined by the Gramm-Leach-Bliley Act of 1999 (the Act). The Act effectively amends the federal banking agencies' capital guidelines to require all banks with financial subsidiaries to deconsolidate the assets and liabilities of all financial subsidiaries and to deduct the aggregate outstanding equity investment in the financial subsidiaries from capital and assets for purposes of calculating the bank's regulatory capital ratios.

Item No. Caption and Instructions

28.a Adjustment to Tier 1 capital reported in item 11. Report one half of the bank's aggregate outstanding equity investment in financial subsidiaries as of the report date, which should be determined in the following manner.

If a financial subsidiary is not consolidated into the bank for purposes of these reports, one half of the bank's aggregate outstanding equity investment in the subsidiary is one half of the amount of the bank's ownership interest accounted for under the equity method of accounting. The bank's ownership interest will have been included in Schedule RC, item 8, "Investments in unconsolidated subsidiaries and associated companies." However, the bank's ownership interest in a financial subsidiary should exclude any loans and advances to the subsidiary and any holdings of the subsidiary's bonds, notes, and debentures, which are included in Schedule RC, item 8.

If one or more financial subsidiaries are consolidated into the bank for purposes of these reports, the bank may use the following approach to determine one half of the bank's aggregate outstanding equity investment in these consolidated financial subsidiaries.

One Half of the Aggregate Outstanding Equity Investments in Consolidated Financial Subsidiaries

(a)	Enter the total assets of consolidated financial subsidiaries included in Schedule RC, item 12	
(b)	Enter the total liabilities of consolidated financial subsidiaries included in Schedule RC, item 21	
(c)	Enter the sum of the amounts included in Schedule RC-R, items 2, 3, 4, 5, 7, 9.a, and 9.b, that are attributable to the bank's consolidated financial subsidiaries (e.g., goodwill on a financial subsidiary's balance sheet that was included in the disallowed goodwill reported on Schedule RC-R, item 7)	
(d)	Enter the amount of "Other additions to (deductions from) Tier 1 capital" included in Schedule RC-R, item 10, that is attributable to the bank's consolidated financial subsidiaries	
(e)	Enter the amount of any minority interests in consolidated financial subsidiaries included in Schedule RC, item 22	
(f)	Enter the sum of (a) and (d) less (b), (c), and (e); enter 0 if the amount is a negative number	

28.a	(g) Adjustment to Tier 1 capital reported in Schedule RC-R,	
(cont.)	item 11 (one half of the bank's aggregate outstanding	
	equity investment for the bank's consolidated financial	
	subsidiaries): enter 50% of the amount in (f) above	

28.b Adjustment to total risk-based capital reported in item 21. Report the bank's aggregate outstanding equity investment in financial subsidiaries as of the report date, which should be determined in the following manner.

If a financial subsidiary is not consolidated into the bank for purposes of these reports, the bank's aggregate outstanding equity investment in the subsidiary is the amount of the bank's ownership interest accounted for under the equity method of accounting. The bank's ownership interest will have been included in Schedule RC, item 8, "Investments in unconsolidated subsidiaries and associated companies." However, the bank's ownership interest in a financial subsidiary should exclude any loans and advances to the subsidiary and any holdings of the subsidiary's bonds, notes, and debentures, which are included in Schedule RC, item 8.

If one or more financial subsidiaries are consolidated into the bank for purposes of these reports, the bank may use the following approach to determine the aggregate outstanding equity investments in these consolidated financial subsidiaries.

Aggregate Outstanding Equity Investments in Consolidated Financial Subsidiaries

(a)	Enter the amount from line (f) in the calculation of the adjustment to Tier 1 capital for consolidated financial subsidiaries in the instructions for Schedule RC-R, item 28.a, above	
(b)	Enter the sum of the amounts included in Schedule RC-R, items 12, 13, 14, 15, 16, and 19 that are attributable to the bank's consolidated financial subsidiaries	
(c)	Enter the amount of "Deductions for total risk-based capital" included in Schedule RC-R, item 20, that is attributable to the bank's consolidated financial subsidiaries	
(d)	Adjustment to total risk-based capital reported in Schedule RC-R, item 21, for the bank's consolidated financial subsidiaries: enter the sum of (a) and (b) less (c)	

29 <u>Adjustment to risk-weighted assets reported in item 62.</u> Report the amount of the adjustment to risk-weighted assets for financial subsidiaries, which should be determined in the following manner.

If a financial subsidiary is not consolidated into the bank, the adjustment to risk-weighted assets for the subsidiary will equal the bank's ownership interest accounted for under the equity method of accounting that is included in Schedule RC-R, item 62, "Total risk-weighted assets."

If a financial subsidiary is consolidated into the bank, the adjustment to risk-weighted assets for the subsidiary will be the total amount of the subsidiary's individual assets, derivatives, and off-balance sheet items as they have been allocated by risk weight across the risk weight

categories in Schedule RC-R, item 57, less the risk-weighted amount of bank assets (cont.) representing claims on the financial subsidiary, other than the bank's ownership interest in the subsidiary, that were eliminated in consolidation. These eliminated assets will not have been included in the amounts reported in Schedule RC-R, item 57.

Adjustment to average total assets reported in item 27. Report the amount of the adjustment to average total assets for financial subsidiaries, which should be determined in the following manner.

If a financial subsidiary is not consolidated into the bank, the adjustment to average total assets for the subsidiary will be the quarterly average of the bank's ownership interest accounted for under the equity method of accounting that is included in Schedule RC-R, item 27.

If a financial subsidiary is consolidated into the bank, the adjustment to average total assets for the subsidiary will be the quarterly average of the assets of the subsidiary that have been included in the consolidated assets of the bank, as reported in Schedule RC-R, item 22; less any disallowed intangible assets and deferred tax assets of the subsidiary that have been included in Schedule RC-R, items 23, 24, and 25; less any other assets of the subsidiary that have been included as other deductions in Schedule RC-R, item 26; and less the quarterly average of bank assets representing claims on the financial subsidiary, other than the bank's ownership interest in the subsidiary, that were eliminated in consolidation. These eliminated assets will not have been included in the amount reported in Schedule RC-R, item 22.

Capital Ratios

Tier 1 leverage ratio. Report the bank's Tier 1 leverage ratio as a percentage, rounded to two decimal places. Column B is to be completed by all banks. The ratio for column B is determined by dividing Schedule RC-R, item 11, by Schedule RC-R, item 27. Banks with financial subsidiaries must also complete column A. The ratio for column A is determined as follows:

Schedule RC-R, item 11, minus Schedule RC-R, item 28.a Schedule RC-R, item 27, minus Schedule RC-R, item 30

Tier 1 risk-based capital ratio. Report the bank's Tier 1 risk-based capital ratio as a percentage, rounded to two decimal places. Column B is to be completed by all banks. The ratio for column B is determined by dividing Schedule RC-R, item 11, by Schedule RC-R, item 62. Banks with financial subsidiaries must also complete column A. The ratio for column A is determined as follows:

Schedule RC-R, item 11, minus Schedule RC-R, item 28.a Schedule RC-R, item 62, minus Schedule RC-R, item 29

Total risk-based capital ratio. Report the bank's total risk-based capital ratio as a percentage, rounded to two decimal places. Column B is to be completed by all banks. The ratio for column B is determined by dividing Schedule RC-R, item 21, by Schedule RC-R, item 62. Banks with financial subsidiaries must also complete column A. The ratio for column A is determined as follows:

Schedule RC-R, item 21, minus Schedule RC-R, item 28.b Schedule RC-R, item 62, minus Schedule RC-R, item 29

Risk-Weighted Assets

The instructions for Schedule RC-R, items 34 through 54 provide general directions for the allocation of bank balance sheet assets and credit equivalent amounts of derivatives and off-balance sheet items to the risk weight categories in columns C through F and, for items 34 through 43 only, to the items not subject to risk-weighting in column B. These instructions should provide sufficient guidance for most banks for risk-weighting their balance sheet assets and credit equivalent amounts. However, these instructions may not identify every asset and other bank transaction that qualifies for a risk weight lower than the maximum risk weight. For further information on allocating assets and off-balance sheet transactions to the proper risk weight category, banks should consult the risk-based capital guidelines of their primary federal supervisory authority.

In order to save time and reduce burden, a bank may decide not to determine every asset or off-balance sheet transaction that is accorded a risk weight lower than 100% (50% for derivative contracts).

Accordingly, at its option, a bank may risk-weight any asset or credit equivalent amount at a higher risk weight than the risk weight that would otherwise apply to the asset or credit equivalent amount, e.g., an asset that qualifies for a 20% risk weight may be assigned a 100% risk weight.

For items 34 through 43 of Schedule RC-R, column B should include the amount of the reporting bank's on-balance sheet assets that are deducted or excluded (not risk weighted) in the determination of risk-weighted assets. Column B should include assets that are deducted from capital such as goodwill, disallowed deferred tax assets, disallowed servicing assets and purchased credit card relationships, disallowed credit-enhancing interest-only strips, intentional reciprocal cross-holdings of bank capital instruments, and any other assets that must be deducted in accordance with the requirements of a bank's primary federal supervisory authority. Column B should also include items that are excluded from the calculation of risk-weighted assets such as the allowance for loan and lease losses, allocated transfer risk reserves, and certain on-balance sheet asset amounts associated with derivative contracts that are included in the calculation of their credit equivalent amounts. For items 34 through 43 of Schedule RC-R, the sum of columns B through F must equal the balance sheet asset amount reported in column A.

For items 44 through 54 of Schedule RC-R, column B should include the credit equivalent amounts of the reporting bank's derivative contracts and off-balance sheet items that are covered by the risk-based capital standards. For off-balance sheet items, the credit equivalent amount to be reported in column B is calculated by multiplying the face or notional amount in column A by the appropriate credit conversion factor. The credit equivalent amounts in column B are to be risk weighted in columns C through F. For items 44 through 54 of Schedule RC-R, the sum of columns C through F must equal the credit equivalent amount reported in column B.

The following are some of the most common exceptions to the risk weight category assignments that are described below in the instructions for items 34 through 54. These exceptions enable a bank, **at its option**, to assign assets, derivatives, and off-balance sheet items to lower risk weight categories than under the instructions for each of these items.

Column C -- 0% column:

- All claims (defined broadly to include securities, loans, and leases) that are direct claims on, or the portion of claims that are directly and unconditionally guaranteed by, OECD central governments or U.S. Government agencies.
- For national and state member banks, claims that are collateralized by cash on deposit in the bank or by securities issued or guaranteed by OECD central governments or U.S. Government agencies (refer to the risk-based capital guidelines for specific criteria).

Risk-Weighted Assets (cont.)

Column D -- 20% column:

- The portion of claims that are conditionally guaranteed by OECD central governments or U.S. Government agencies
- The portion of claims that are collateralized by cash on deposit in the bank or by securities issued
 or guaranteed by OECD central governments or U.S. Government agencies that are not included
 in zero percent column
- The portion of local currency securities that are conditionally guaranteed by non-OECD central governments (to the extent that the bank has liabilities booked in that currency)
- General obligation claims on, or portions of claims guaranteed by the full faith and credit of, states or other political subdivisions of the U.S.
- Claims on, and the portions of claims guaranteed by, multilateral lending institutions or regional development banks in which the U.S. Government is a shareholder or contributing member.

The risk-based capital guidelines include a ratings-based approach that sets the risk-based capital requirements for asset-backed and mortgage-backed securities and other positions in securitization transactions (except credit-enhancing interest-only strips) according to their relative risk using credit ratings from nationally recognized statistical rating organizations, i.e., rating agencies, to measure the level of risk. (The ratings-based approach does **not** apply to corporate bonds, municipal bonds, or other debt securities that have been rated by a rating agency.) In general, under the ratings-based approach, the risk-based capital requirement for a position in a securitization is computed by multiplying the face amount of the position by the risk weight appropriate for the external credit rating of the position. The risk weights for long-term and short-term external ratings are as follows:

Long-Term Rating Category	Examples	Risk Weight
Highest or second highest investment grade	AAA or AA	20%
Third highest investment grade	Α	50%
Lowest investment grade	BBB	100%
One category below investment grade	BB	200%
More than one category below investment grade, or	B or unrated	Not eligible for ratings-
unrated		based approach

Short-Term Rating Category	Examples	Risk Weight
Highest investment grade	A-1, P-1	20%
Second highest investment grade	A-2, P-2	50%
Lowest investment grade	A-3, P-3	100%
Below investment grade, or unrated	B or unrated	Not eligible for ratings- based approach

Under the ratings-based approach, a position in a securitization that is a "traded position," as defined in the risk-based capital guidelines, must receive at least one external rating. If a traded position receives more than one external ratings, the lowest rating will apply. For a position in a securitization that is not a traded position to be eligible for the ratings-based approach, the position must receive at least two publicly available external ratings that are based on the same criteria used to rate traded positions. The lowest external rating will determine the risk weight category for the position.

In addition, a position (other than a residual interest) in a securitization or structured finance program that is not externally rated may use the credit rating for the position under one of three alternative standards to determine the risk weight for the position. These alternatives are internal risk ratings for direct credit substitutes (but not purchased credit-enhancing interest-only strips) supporting asset-backed commercial paper programs and program ratings and credit assessment computer programs for credit enhancements (but not residual interests) supporting structured finance programs. Under these alternatives, a position

Risk-Weighted Assets (cont.)

receiving an investment grade rating is assigned a 100% risk weight and a position receiving a rating one category below investment grade is assigned a 200% risk weight.

The extent to which qualifying securities are recognized as collateral for risk-based capital purposes is determined by their current market value. If a claim is partially secured, that is, the market value of the pledged securities is less than the face amount of an asset or off-balance sheet item, only the portion that is covered by the market value of the collateral is to be reported in this item. The face amount of a claim secured by two types of qualifying collateral is to be reported in the items appropriate to the collateral types, apportioned according to the market value of each of the two types of collateral.

If a claim is partially guaranteed or covered by two types of guarantees, then the preceding discussion on the treatment of claims that are collateralized is applicable. A guarantee is conditional if its validity is dependent upon some affirmative action by the bank or a third party (e.g., servicing requirements).

NOTE: Claims collateralized by deposits in other depository institutions (e.g., certificates of deposit issued by other banks) do *not* qualify for a 20 percent risk weight. Such collateralized claims are to be reported in the 50 percent or 100 percent risk weight category in columns E or F of Schedule RC-R, as appropriate, according to the obligor or, if relevant, the guarantor or the nature of any other collateral.

These instructions contain several references to the OECD, i.e., the Organization for Economic Cooperation and Development. The following countries are members of the OECD: Australia, Austria, Belgium, Canada, the Czech Republic, Denmark, Finland, France, Germany, Greece, Hungary, Iceland, Ireland, Italy, Japan, Korea, Luxembourg, Mexico, the Netherlands, New Zealand, Norway, Poland, Portugal, Slovak Republic, Spain, Sweden, Switzerland, Turkey, the United Kingdom, and the United States. In addition, Saudi Arabia should be treated as an OECD country. All other countries should be treated as non-OECD countries.

Banks that are subject to the market risk capital guidelines -- The banking agencies' risk-based capital standards require all banks with significant market risk to measure their market risk exposure and hold sufficient capital to mitigate this exposure. In general, a bank is subject to the market risk capital guidelines if its consolidated trading activity, defined as the sum of trading assets and liabilities as reported in its Call Report for the previous quarter, equals: (1) 10 percent or more of the bank's total assets as reported in its Call Report for the previous quarter, or (2) \$1 billion or more. However, the primary federal supervisory authority may exempt or include a bank if necessary or appropriate for safe and sound banking practices.

A bank that is subject to the market risk capital guidelines must hold capital to support its exposure to general market risk arising from fluctuations in interest rates, equity prices, foreign exchange rates, and commodity prices and its exposure to specific risk associated with certain debt and equity positions. Covered positions include all positions in a bank's trading account and foreign exchange and commodity positions, whether or not in the trading account. Covered positions generally should not be risk-weighted as part of the bank's gross risk-weighted assets. However, foreign exchange positions that are outside of the trading account and all over-the-counter (OTC) derivatives continue to have a counterparty credit risk capital charge. Those positions are included in both gross risk-weighted assets for credit risk and the bank's covered positions for market risk.

For a bank that is subject to the market risk capital guidelines, positions in the trading account arising from asset securitizations, including recourse obligations, residual interests, and direct credit substitutes, should be treated for risk-based capital purposes in accordance with those guidelines. However, the bank remains subject to the concentration limit for credit-enhancing interest-only strips (see the instructions for Schedule RC-R, item 10, "Other additions to (deductions from) Tier 1 capital").

Balance Sheet Asset Categories

Assets Sold with Recourse and Purchased Credit-Enhancing Interest-Only Strips – When an on-balance sheet asset that is a position in an asset securitization qualifies for the ratings-based approach, the asset should be reported in the appropriate asset category in Schedule RC-R (items 34 to 42) and risk-weighted 20%, 50%, 100%, or 200% according to its rating. (See the paragraph below for further information on assets subject to a 200% risk weight.)

Otherwise, in an asset sale with recourse in which a bank has retained on-balance sheet assets that act as credit enhancements (including retained credit-enhancing interest-only strips) that do not qualify for the ratings-based approach, these assets should be reported in column B, "Items Not Subject to Risk-Weighting," of the appropriate Schedule RC-R asset category (items 34 to 42). Similarly, purchased credit-enhancing interest-only strips should be reported in column B. Depending on the nature of the individual recourse transactions, the risk-weighting of these transactions will take place in Schedule RC-R, item 49, "Retained recourse on small business obligations sold with recourse," item 50, "Recourse and direct credit substitutes (other than financial standby letters of credit) subject to the low level exposure rule and residual interests subject to a dollar-for-dollar capital requirement," or item 51, "All other financial assets sold with recourse." Purchased credit-enhancing interest-only strips are to be risk-weighted in Schedule RC-R, item 50.

Assets Subject to a 200% Risk Weight – Asset-backed and mortgage-backed securities and other on-balance sheet positions in asset securitizations that are rated one category below investment grade (e.g., BB) by a rating agency are subject to a 200% risk weight. Because Schedule RC-R does not have a column for the 200% risk weight, assets in this risk weight category should be reported in the following manner in Schedule RC-R:

- If a 200% risk-weighted asset is reported on the balance sheet (Schedule RC) at amortized cost, e.g., in "Held-to-maturity securities," report (1) the asset's amortized cost multiplied by 2 in column F— 100% risk weight, and (2) the asset's amortized cost as a negative number in column B.
- If a 200% risk-weighted asset is reported on the balance sheet (Schedule RC) like an "Available-for-sale debt security," i.e., at fair value with unrealized gains (losses) reported in "Other comprehensive income," report (1) the difference between the asset's fair value and amortized cost in column B as a positive number if fair value exceeds cost or as a negative number if cost exceeds fair value, (2) the asset's amortized cost multiplied by 2 in column F—100% risk weight, and (3) the asset's amortized cost as a negative number in column B.
- If a 200% risk-weighted asset is reported on the balance sheet (Schedule RC) like a "Trading asset," i.e., at fair value with unrealized gains (losses) included in current earnings, report (1) the asset's fair value multiplied by 2 in column F—100% risk weight, and (2) the asset's fair value as a negative number in column B.

Treatment of Embedded Derivatives – If a bank has a hybrid contract containing an embedded derivative that must be separated from the host contract and accounted for as a derivative instrument under FASB Statement No. 133, then the host contract and embedded derivative should be treated separately for risk-based capital purposes. When the fair value of the embedded derivative has been reported as part of the bank's assets on Schedule RC – Balance Sheet, that fair value (whether positive or negative) should be reported (as a positive or negative number) in column B of the corresponding asset category item in Schedule RC-R (items 34 to 42). The host contract, if an asset, should be risk weighted according to the obligor or, if relevant, the guarantor or the nature of the collateral.

Balance Sheet Asset Categories (cont.)

Allocated Transfer Risk Reserves (ATRRs) – If the reporting bank is required to establish and maintain an ATRR as specified in Section 905(a) of the International Lending Supervision Act of 1983, in the agency regulations implementing the Act (Subpart D of Federal Reserve Regulation K, Part 347 of the FDIC's Rules and Regulations, and Part 20 of the Comptroller of the Currency's Regulations), and in any guidelines, letters, or instructions issued by the agencies, the ATRR should be reported in Schedule RC-R, item 61.

In addition, for each asset category that has been reported net of an ATRR in the balance sheet (Schedule RC), the ATRR should be reported as a negative number (i.e., in parentheses) in column B, "Items Not Subject to Risk-Weighting," of the corresponding asset category in Schedule RC-R, items 34 through 42. The amount to be risk-weighted for this asset in column C, D, E, or F, as appropriate, would be its net carrying value plus the ATRR. For example, a bank has a loan to a foreign commercial company against which it has established an ATRR of \$20. The loan, net of the ATRR, is included in Schedule RC, item 4.b, "Loans and leases, net of unearned income," at \$80. The loan should be included in Schedule RC-R, item 39, column A, at \$80. The bank should include \$(20) in Schedule RC-R, item 39, column B, and \$100 in item 39, column F.

Item No. Caption and Instructions

- 34 <u>Cash and balances due from depository institutions.</u> Report in column A the amount of cash and balances due from depository institutions reported in Schedule RC, sum of items 1.a and 1.b.
 - In column C--0% risk weight, include the amount of currency and coin plus any balances due from Federal Reserve Banks reported in Schedule RC, item 1.a and any balances due from central banks in other OECD countries reported in Schedule RC, items 1.a and 1.b.
 - In column F--100% risk weight, include balances due from non-OECD depository institutions with remaining maturities of over one year, all non-local currency claims on non-OECD central banks, and local currency claims on non-OECD central banks that exceed the local currency liability held by the bank.
 - In column D--20% risk weight, include all other amounts that are not reported in column C or F.

If the reporting bank is the correspondent bank in a pass-through reserve balance relationship, report in column C the amount of its own reserves as well as those reserve balances actually passed through to a Federal Reserve Bank on behalf of its respondent depository institutions.

If the reporting bank is the respondent bank in a pass-through reserve balance relationship, report in column C the amount of the bank's reserve balances due from its correspondent bank that its correspondent has actually passed through to a Federal Reserve Bank on the reporting bank's behalf, i.e., for purposes of this item, treat these balances as balances due from a Federal Reserve Bank. This treatment differs from that required in Schedule RC-A, item 2, "Balances due from depository institutions in the U.S.," which treats pass-through reserve balances held by a bank's correspondent as balances due from a depository institution as opposed to balances due from the Federal Reserve.

- Held-to-maturity securities. Report in column A the amortized cost of held-to-maturity (HTM) securities reported in Schedule RC, item 2.a.
 - In column B, include as a negative number the amortized cost of those mortgage-backed and asset-backed securities reported in Schedule RC-B, item 4.a.(3), column A, "Other pass-through securities," item 4.b.(2), column A, Other mortgage-backed securities "Collateralized by MBS issued or guaranteed by FNMA, FHLMC, or GNMA," item 4.b.(3), column A, "All other mortgage-backed securities," and item 5, column A, "Asset-backed securities," that are rated one category below investment grade, e.g., BB.
 - In column C--0% risk weight, include the amounts reported in Schedule RC-B, column A, for item 1, "U.S. Treasury securities," item 2.a, Securities "Issued by U.S. Government agencies," and item 4.a.(1), Pass-through securities "Guaranteed by GNMA. Also include the portion of Schedule RC-B, item 4.b.(1), column A, Other mortgage-backed securities "Issued or guaranteed by FNMA, FHLMC, or GNMA," that represents the amortized cost of GNMA securities.
 - In column D--20% risk weight, include the amounts reported in Schedule RC-B, column A, for item 2.b, Securities "Issued by U.S. Government-sponsored agencies," and item 4.a.(2), Pass-through securities "Issued by FNMA and FHLMC." Include the portion of Schedule RC-B, item 3, column A, "Securities issued by states and political subdivisions in the U.S.," that represents the amortized cost of general obligation securities and the portion of Schedule RC-B, item 4.b.(1), column A, Other mortgagebacked securities "Issued or guaranteed by FNMA, FHLMC, or GNMA," that represents the amortized cost of FHLMC and FNMA securities (excluding interest-only strips that are not credit-enhancing and principal-only strips, which must be assigned a 100 percent risk weight). Also include the portion of Schedule RC-B, item 4.b.(2), column A, Other mortgage-backed securities "Collateralized by MBS issued or guaranteed by FNMA. FHLMC, or GNMA," that represents the amortized cost of senior interests in such securities (excluding interest-only strips that are not credit-enhancing and principal-only strips, which must be assigned a 100 percent risk weight). Also include the portions of Schedule RC-B, item 4.a.(3), column A, "Other pass-through securities," item 4.b.(2), column A, Other mortgage-backed securities "Collateralized by MBS issued or guaranteed by FNMA, FHLMC, or GNMA," item 4.b.(3), column A, "All other mortgagebacked securities," and item 5, column A, "Asset-backed securities," that represents the amortized cost of securities that are rated in the highest or second highest investment grade, e.g., AAA or AA, in the case of long-term ratings, or in the highest rating category, e.g., A-1 or P-1, in the case of short-term ratings.

In column E--50% risk weight, include the portion of Schedule RC-B, item 3, column A, "Securities issued by states and political subdivisions in the U.S.," that represents the amortized cost of revenue obligation securities. Also include the portions of Schedule RC-B, item 4.a.(3), column A, "Other pass-through securities," item 4.b.(2), column A, Other mortgage-backed securities "Collateralized by MBS issued or guaranteed by FNMA, FHLMC, or GNMA," item 4.b.(3), column A, "All other mortgage-backed securities," and item 5, column A, "Asset-backed securities," that represents the amortized cost of securities that are rated in the third highest investment grade, e.g., A, in the case of long-term ratings, or in the second highest rating category, e.g., A-2 or P-2, in the case of short-term ratings (excluding interest-only strips that are not credit-enhancing and principal-only strips, which must be assigned a 100 percent risk weight).

• In column F--100% risk weight, include the amortized cost of all other HTM securities reported in Schedule RC, item 2.a, that are not included in columns C through E.

35 (cont.)

However, for those mortgage-backed and asset-backed securities reported in Schedule RC-B, item 4.a.(3), column A, "Other pass-through securities," item 4.b.(2), column A, Other mortgage-backed securities "Collateralized by MBS issued or guaranteed by FNMA, FHLMC, or GNMA," item 4.b.(3), column A, "All other mortgage-backed securities," and item 5, column A, "Asset-backed securities," that are rated one category below investment grade, e.g., BB, include in column F the amortized cost of these securities multiplied by 2.

- Available-for-sale securities. Report in column A the fair value of available-for-sale (AFS) securities reported in Schedule RC, item 2.b. For regulatory capital purposes, however, AFS debt securities are risk weighted at their amortized cost. In addition, when AFS equity securities with readily determinable fair values have a net unrealized loss, they are risk weighted at their fair value. When such equity securities have a net unrealized gain, they are risk weighted at their historical cost plus the portion of the unrealized gain (up to 45 percent) included in Tier 2 capital. This unrealized gain is reported in Schedule RC-R, item 15.
 - In column B, include the difference between the fair value and amortized cost of AFS debt securities. This difference equals Schedule RC-B, items 1 through 6, column D, minus items 1 through 6, column C. When fair value exceeds cost, report the difference as a positive number in Schedule RC-R, item 36, column B. When cost exceeds fair value, report the difference as a negative number (i.e., in parentheses) in Schedule RC-R, item 36, column B. If AFS equity securities with readily determinable fair values have a net unrealized gain (i.e., Schedule RC-B, item 7, column D, exceeds item 7, column C), the portion of the net unrealized gain (55 percent or more) not included in Tier 2 capital should be included in Schedule RC-R, item 36, column B. The portion that is not included in Tier 2 capital equals Schedule RC-B, item 7, column D minus column C, minus Schedule RC-R, item 15.

Also include *in column B* as a negative number the amortized cost of those mortgage-backed and asset-backed securities reported in Schedule RC-B, item 4.a.(3), column C, "Other pass-through securities," item 4.b.(2), column C, Other mortgage-backed securities "Collateralized by MBS issued or guaranteed by FNMA, FHLMC, or GNMA," item 4.b.(3), column C, "All other mortgage-backed securities," and item 5, column C, "Asset-backed securities," that are rated one category below investment grade, e.g., BB.

- In column C--0% risk weight, include the amounts reported in Schedule RC-B, column C, for item 1, "U.S. Treasury securities," item 2.a, Securities "Issued by U.S. Government agencies," and item 4.a.(1), Pass-through securities "Guaranteed by GNMA. Also include the portion of Schedule RC-B, item 4.b.(1), column C, Other mortgage-backed securities "Issued or guaranteed by FNMA, FHLMC, or GNMA," that represents the amortized cost of GNMA securities.
- In column D--20% risk weight, include the amounts reported in Schedule RC-B, column C, for item 2.b, Securities "Issued by U.S. Government-sponsored agencies," and item 4.a.(2), Pass-through securities "Issued by FNMA and FHLMC." Include the portion of Schedule RC-B, item 3, column C, "Securities issued by states and political subdivisions in the U.S.," that represents the amortized cost of general obligation securities and the portion of Schedule RC-B, item 4.b.(1), column C, Other mortgage-backed securities "Issued or guaranteed by FNMA, FHLMC, or GNMA," that represents the amortized cost of FHLMC and FNMA securities (excluding interest-only strips that are not credit-enhancing and principal-only strips, which must be assigned a 100 percent risk weight). Also include the portion of Schedule RC-B, item 4.b.(2), column C, Other mortgage-backed securities "Collateralized by MBS issued or guaranteed by FNMA, FHLMC, or GNMA," that represents the amortized cost of senior interests in such

36 (cont.)

securities (excluding interest-only strips that are not credit-enhancing and principal-only strips, which must be assigned a 100 percent risk weight). Also include the portions of Schedule RC-B, item 4.a.(3), column C, "Other pass-through securities," item 4.b.(2), column C, Other mortgage-backed securities "Collateralized by MBS issued or guaranteed by FNMA, FHLMC, or GNMA," item 4.b.(3), column C, "All other mortgage-backed securities," and item 5, column A, "Asset-backed securities," that represents the amortized cost of securities that are rated in the highest or second highest investment grade, e.g., AAA or AA, in the case of long-term ratings, or in the highest rating category, e.g., A-1 or P-1, in the case of short-term ratings.

- In column E--50% risk weight, include the portion of Schedule RC-B, item 3, column C, "Securities issued by states and political subdivisions in the U.S.," that represents the amortized cost of revenue obligation securities. Also include the portions of Schedule RC-B, item 4.a.(3), column C, "Other pass-through securities," item 4.b.(2), column C, Other mortgage-backed securities "Collateralized by MBS issued or guaranteed by FNMA, FHLMC, or GNMA," item 4.b.(3), column C, "All other mortgage-backed securities," and item 5, column C, "Asset-backed securities," that represents the amortized cost of securities that are rated in the third highest investment grade, e.g., A, in the case of long-term ratings, or in the second highest rating category, e.g., A-2 or P-2, in the case of short-term ratings (excluding interest-only strips that are not credit-enhancing and principal-only strips, which must be assigned a 100 percent risk weight).
- In column F--100% risk weight, include the amortized cost of all other AFS debt securities reported in Schedule RC-B, column C, that are not included in columns B through E. However, for those mortgage-backed and asset-backed securities reported in Schedule RC-B, item 4.a.(3), column C, "Other pass-through securities," item 4.b.(2), column C, Other mortgage-backed securities "Collateralized by MBS issued or guaranteed by FNMA, FHLMC, or GNMA," item 4.b.(3), column C, "All other mortgage-backed securities," and item 5, column C, "Asset-backed securities," that are rated one category below investment grade, e.g., BB, include in column F the amortized cost of these securities multiplied by 2.

In addition, for AFS equity securities with readily determinable fair values reported in Schedule RC-B, item 7, include the fair value of these equity securities (as reported in Schedule RC-B, item 7, column D) if they have a net unrealized loss. If these equity securities have a net unrealized gain, include their historical cost (as reported in Schedule RC-B, item 7, column C) plus the portion of the unrealized gain (up to 45 percent) included in Tier 2 capital (as reported in Schedule RC-R, item 15). (NOTE: Certain investments in mutual funds reported in Schedule RC-B, item 7, may qualify for less than a 100 percent risk weight. For further information, refer to the risk-based capital standards of the bank's primary federal supervisory authority.)

- 37 <u>Federal funds sold and securities purchased under agreements to resell.</u> Report in column A the amount of federal funds sold and securities purchased under agreements to resell reported in Schedule RC, sum of items 3.a and 3.b.
 - In column C--0% risk weight, include the portion of Schedule RC, item 3, that is directly
 and unconditionally guaranteed by U.S. Government agencies or OECD central
 governments.
 - In column F--100% risk weight, include claims on nondepository institution counterparties that lack qualifying collateral (refer to the risk based capital guidelines for specific criteria) and claims on non-OECD depository institutions with maturities of over one year.

• In column D--20% risk weight, include the amount of federal funds sold and securities resalle agreements reported in Schedule RC, item 3, that are not included in columns C and F.

- **Loans and leases held for sale.** Report in column A the carrying value of loans and leases held for sale (HFS) reported in Schedule RC, item 4.a.
 - In column C--0% risk weight, include the carrying value of the guaranteed portion of HFS SBA loans purchased in the secondary market that are included in Schedule RC-C, part I, items 3, "Loans to finance agricultural production and other loans to farmers," and 4, "Commercial and industrial loans."
 - In column D--20% risk weight, include the carrying value of HFS loans to and acceptances of other depository institutions that are reported in Schedule RC-C, part I, item 2, (excluding the carrying value of any long-term claims on non-OECD banks that are HFS), plus the carrying value of the guaranteed portion of HFS FHA and VA mortgage loans included in Schedule RC-C, part I, item 1.c.(2)(a), the carrying value of the guaranteed portion of HFS SBA loans originated and held by the reporting bank included in Schedule RC-C, part I, items 3 and 4, and the carrying value of the portion of HFS student loans reinsured by the U.S. Department of Education included in Schedule RC-C, part I, item 6.c, "Other consumer loans."
 - In column E--50% risk weight, include the carrying value of HFS loans secured by 1-4 family residential properties and by multifamily residential properties included in Schedule RC-C, part I, items 1.c.(2)(a) and 1.d, respectively, that are prudently underwritten, are fully secured by first liens on 1-4 family or multifamily residential properties, are not 90 days or more past due or in nonaccrual status, and meet other requirements specified in the risk-based capital guidelines.
 - In column F--100% risk weight, include the carrying value of HFS loans reported in Schedule RC, item 4.a, that is not included in columns B through E.
- **Loans and leases, net of unearned income.** Report in column A the amount of loans and leases, net of unearned income, reported in Schedule RC, item 4.b.
 - In column C--0% risk weight, include the carrying value of the guaranteed portion of SBA loans purchased in the secondary market that are included in Schedule RC-C, part I, items 3, "Loans to finance agricultural production and other loans to farmers," and 4, "Commercial and industrial loans."
 - In column D--20% risk weight, include the carrying value of loans to and acceptances of other depository institutions that are reported in Schedule RC-C, part I, item 2, (excluding the carrying value of any long-term claims on non-OECD banks), plus the carrying value of the guaranteed portion of FHA and VA mortgage loans included in RC-C, part I, item 1.c.(2)(a), the carrying value of the guaranteed portion of SBA loans originated and held by the reporting bank included in Schedule RC-C, part I, items 3 and 4, and the carrying value of the portion of student loans reinsured by the U.S. Department of Education included in Schedule RC-C, part I, item 6.c, "Other consumer loans."
 - In column E--50% risk weight, include the carrying value of loans secured by 1-4 family residential properties and by multifamily residential properties included in Schedule RC-C, part I, items 1.c.(2)(a) and 1.d, respectively, that are prudently underwritten, are fully secured by first liens on 1-4 family or multifamily residential

- properties, are not 90 days or more past due or in nonaccrual status, and meet other requirements specified in the risk-based capital guidelines.
 - In column F--100% risk weight, include the carrying value of loans reported in Schedule RC, item 4.b, that is not included in columns B through E.
- **LESS:** Allowance for loan and lease losses. Report in columns A and B the balance of the allowance for loan and lease losses reported in Schedule RC, item 4.c.
- Trading assets. Report in column A the fair value of trading assets reported in Schedule RC, item 5.

If the bank is subject to the market risk capital requirement, also include the fair value of all trading assets reported in Schedule RC, item 5, in column B. The bank will report its market risk equivalent assets in Schedule RC-R, item 58.

For banks not subject to the market risk capital requirement:

- In column B, if the bank completes Schedule RC-D, include the fair value of derivative
 contracts that are reported as assets in Schedule RC-D, item 11. If the bank does not
 complete Schedule RC-D, include the portion of the amount reported in Schedule RC,
 item 5, that represents the fair value of derivative contracts that are assets.
 - Also include *in column B* as a negative number the fair value of those mortgage-backed and asset-backed securities reported in Schedule RC-D, item 4, "Mortgage-backed securities," item 5, "Other debt securities," and, on the FFIEC 031 report form, item 10, "Trading assets in foreign offices," that are rated one category below investment grade, e.g., BB. If the bank does not complete Schedule RC-D, include the portion of the amount reported in Schedule RC, item 5, that represents the fair value of mortgage-backed and asset-backed securities that are rated one category below investment grade, e.g., BB.
- In column C--0% risk weight, if the bank completes Schedule RC-D, include amount reported in Schedule RC-D, item 1, "U.S. Treasury securities," the portion of the amount reported in Schedule RC-D, item 2, that represents the fair value of securities issued by U.S. Government agencies, and the portion of the amounts reported in Schedule RC-D, items 4.a and 4.b, that represents the fair value of mortgage-backed securities guaranteed by GNMA. If the bank does not complete Schedule RC-D, include the portion of the amount reported in Schedule RC, item 5, that represents the fair value of these types of securities.
- In column D--20% risk weight, if the bank completes Schedule RC-D, include the portion of the amount reported in Schedule RC-D, item 2, that represents the fair value of securities issued by U.S. Government-sponsored agencies, the portion of the amount reported in Schedule RC-D, item 3, that represents the fair value of general obligations issued by states and political subdivisions in the U.S., the portion of the amount reported in Schedule RC-D, items 4.a and 4.b, that represents the fair value of mortgage-backed securities issued by FNMA and FHLMC (excluding interest-only strips that are not creditenhancing and principal-only strips, which must be assigned a 100 percent risk weight). and the portion of the amount reported in Schedule RC-D, item 9, "Other trading assets," that represents the fair value of certificates of deposit and bankers acceptances (excluding the fair of any long-term claims on non-OECD banks). Also include the fair

41 (cont.)

value of those mortgage-backed and asset-backed securities reported in Schedule RC-D, item 4, "Mortgage-backed securities," item 5, "Other debt securities," and, on the FFIEC 031 report form, item 10, "Trading assets in foreign offices," that are rated in the highest or second highest investment grade, e.g., AAA or AA, in the case of long-term ratings, or in the highest rating category, e.g., A-1 or P-1, in the case of short-term ratings. If the bank does not complete Schedule RC-D, include the portion of the amount reported in Schedule RC, item 5, that represents the fair value of these types of trading assets.

- In column E--50% risk weight, if the bank completes Schedule RC-D, include the portion of the amount reported in RC-D, item 3, that represents the fair value of revenue obligations issued by states and political subdivisions in the U.S. Also include the fair value of those mortgage-backed and asset-backed securities reported in Schedule RC-D, item 4, "Mortgage-backed securities," item 5, "Other debt securities," and, on the FFIEC 031 report form, item 10, "Trading assets in foreign offices," that are rated in the third highest investment grade category, e.g., A, in the case of long-term ratings, or in the second highest rating category, e.g. A-2 or P-2, in the case of short-term ratings (excluding interest-only strips that are not credit-enhancing and principal-only strips, which must be assigned a 100 percent risk weight). If the bank does not complete Schedule RC-D, include the portion of the amount reported in Schedule RC, item 5, that represents the fair value of these types of securities.
- In column F--100% risk weight, include the fair value of trading assets reported in Schedule RC, item 5, that is not included in columns B through E. However, for those mortgage-backed and asset-backed securities reported in Schedule RC, item 5, that are rated one category below investment grade, e.g., BB, include in column F the fair value of these securities multiplied by 2.
- All other assets. Report in column A the sum of the amounts reported in Schedule RC, item 6, "Premises and fixed assets," item 7, "Other real estate owned," item 8, "Investments in unconsolidated subsidiaries and associated companies," item 9, "Customers' liability to this bank on acceptances outstanding," item 10.a, "Goodwill," item 10.b, "Other intangible assets," and item 11, Other assets."
 - In column B, include the amount of any disallowed goodwill and other disallowed intangible assets reported in Schedule RC-R, item 7; disallowed servicing assets and purchased credit card relationships reported in Schedule RC-R, item 8; disallowed deferred tax assets reported in Schedule RC-R, item 9; all credit-enhancing interest-only strips reported in Schedule RC, item 11; all residual interests (as defined in the instructions for Schedule RC-R, item 50) not eligible for the ratings-based approach; the fair value of derivative contracts that are reported as assets in Schedule RC, item 11; and the carrying value of other assets reported in Schedule RC, item 11, that act as credit enhancements for those recourse transactions that must be reported in Schedule RC-R, items 49 and 51. Also include the amount of the bank's investments in unconsolidated banking and finance subsidiaries that are reported in Schedule RC, item 8, and are deducted for risk-based capital purposes in Schedule RC-R, item 20.

If the bank has residual interests in asset securitizations that are eligible for the ratings-based approach, report the difference between these residuals' fair value carrying amount and their amortized cost in column B as a positive number if fair value exceeds cost and as a negative number (i.e., in parentheses) if cost exceeds fair value. Also, include *in column B* as a negative number the amortized cost of any residual interests in asset securitizations (other than credit-enhancing interest-only strips) included in Schedule RC, item 11, that are rated one category below investment grade, e.g., BB.

42 (cont.)

- In column C--0% risk weight, include the carrying value of Federal Reserve Bank stock included in Schedule RC-F, item 4; accrued interest receivable on assets included in the zero percent risk weight category (column C of Schedule RC-R, items 34 through 41); and the carrying value of gold bullion not held for trading that is held in the bank's own vault or in another bank's vault on an allocated basis.
- In column D--20% risk weight, include the carrying value of Federal Home Loan Bank stock included in Schedule RC-F, item 4; accrued interest receivable on assets included in the 20 percent risk weight category (column D of Schedule RC-R, items 34 through 41); and the portion of customers' acceptance liability reported in Schedule RC, item 9, that has been participated to other depository institutions. (These participations in acceptances conveyed to other depository institutions should be included in the amount reported in Schedule RC-L, item 5.) Also include the amortized cost of residual interests in asset securitizations (other than credit-enhancing interest-only strips) included in Schedule RC, item 11, that are rated in the highest or second highest investment grade, e.g., AAA or AA, in the case of long-term ratings, or in the highest rating category, e.g., A-1 or P-1, in the case of short-term ratings.
- In column E--50% risk weight, include accrued interest receivable on assets included in the 50 percent risk weight category (column E of Schedule RC-R, items 34 through 41). Also include the amortized cost of residual interests in asset securitizations (other than credit-enhancing interest-only strips) included in Schedule RC, item 11, that are rated in the third highest investment grade, e.g., A, in the case of long-term ratings, or in the second highest rating category, e.g., A-2 or P-2, in the case of short-term ratings.
- In column F--100% risk weight, include the amount of all other assets reported in column A that is not included in columns B through E. However, for residual interests in asset securitizations (other than credit-enhancing interest-only strips) included in Schedule RC, item 11, include the amortized cost of those that are rated in the lowest investment grade category, e.g., BBB, and the amortized cost multiplied by 2 of those that are rated one category below investment grade, e.g., BB.
- 43 <u>Total assets.</u> For columns A through F, report the sum of items 34 through 42. The sum of columns B through F must equal column A.

Derivatives and Off-Balance Sheet Items

Banks should refer to the supervisory guidance issued by their primary federal supervisory authority for information on how they should treat credit derivatives for risk-based capital purposes and, as a consequence, for purposes of completing the section of Schedule RC-R for derivatives and off-balance sheet items.

Item No. Caption and Instructions

- **Financial standby letters of credit.** For financial standby letters of credit reported in Schedule RC-L, item 2, that act as credit enhancements for asset-backed or mortgage-backed securities and to which the ratings-based approach applies, report *in column A:*
 - the amount outstanding and unused of those letters of credit subject to a risk weight of 100% or less and
 - (2) two times the amount outstanding and unused of those letters of credit subject to a 200% risk weight.

For these financial standby letters of credit, report *in column B* 100% of the amount reported in column A.

For all other financial standby letters of credit reported in Schedule RC-L, item 2, report *in column A*:

- (1) the amount outstanding and unused of those letters of credit for which this amount is less than the effective risk-based capital requirement for the assets that are credit-enhanced by the letter of credit. These financial standby letters of credit are subject to the low-level exposure rule. For these financial standby letters of credit, report as the credit equivalent amount in column B their amount outstanding and unused multiplied by either 12.5 or by the institution-specific factor determined in the manner described in the instructions for Schedule RC-R, item 50.
- (2) the full amount of the assets that are credit-enhanced by those letters of credit that are not subject to the low-level exposure rule. For these financial standby letters of credit, report *in column B* 100% of the amount reported in column A.
- In column D—20% risk weight, include the credit equivalent amount of the portion of financial standby letters of credit reported in Schedule RC-L, item 2.a, that has been conveyed to U.S. and other OECD depository institutions (and to non-OECD depository institutions for letters of credit with remaining maturities of one year or less). Also include in column D the credit equivalent amount of financial standby letters of credit to which the ratings-based approach applies that are rated in the highest or second highest investment grade category, e.g., AAA or AA, in the case of long-term ratings, or in the highest rating category, e.g., A-1 or P-1, in the case of short-term ratings.
- In column E—50% risk weight, include the credit equivalent amount of financial standby letters of credit to which the ratings-based approach applies that are rated in the third highest investment grade category, e.g., A, in the case of long-term ratings, or in the second highest rating category, e.g., A-2 or P-2, in the case of short-term ratings.
- In column F—100% risk weight, include the portion of the credit equivalent amount reported in column B that is not included in columns C through E.

- **Performance standby letters of credit.** Report in column A the face amount of performance standby letters of credit reported in Schedule RC-L, item 3.
 - In column B, report 50 percent of the face amount reported in column A.
 - In column D--20% risk weight, include the credit equivalent amount of the portion of performance standby letters of credit reported in Schedule RC-L, item 3.a, that has been conveyed to U.S. and other OECD depository institutions (and to non-OECD depository institutions for letters of credit with remaining maturities of one year or less).
 - In column F--100% risk weight, include the portion of the credit equivalent amount reported in column B that is not included in columns C through E.
- **Commercial and similar letters of credit.** Report in column A the face amount of commercial and similar letters of credit reported in Schedule RC-L, item 4.
 - In column B, report 20 percent of the face amount reported in column A.
 - In column F--100% risk weight, include the portion of the credit equivalent amount reported in column B that is not included in columns C through E.
- 47 Risk participations in bankers acceptances acquired by the reporting institution.

 Report in column A the face amount of risk participations in bankers acceptances that have been acquired by the reporting institution and are outstanding.
 - In column B, report 100 percent of the face amount reported in column A.
 - In column D--20% risk weight, include the credit equivalent amount of the portion of risk
 participations in bankers acceptances that the reporting bank has acquired and
 subsequently conveyed to U.S. and other OECD depository institutions (and to nonOECD depository institutions for bankers acceptances with remaining maturities of one
 year or less).
 - In column F--100% risk weight, include the portion of the credit equivalent amount reported in column B that is not included in columns C and D.
- 48 <u>Securities lent.</u> Report in column A the amount of securities lent reported in Schedule RC-L, item 6.
 - In column B, report 100 percent of the face amount reported in column A.
 - In column C--0% risk weight, include the credit equivalent amount of securities lent that is supported by the appropriate amount of collateral that qualifies for the zero percent risk weight under the risk based capital guidelines of the reporting bank's primary federal supervisory authority (refer to these guidelines for the specific qualifying criteria).
 - In column D--20% risk weight, include the credit equivalent amount of securities lent that is supported by the appropriate amount of collateral that qualifies for the 20 percent risk weight under the risk based capital guidelines of the reporting bank's primary federal supervisory authority (refer to these guidelines for specific qualifying criteria). Also include the credit equivalent amount of securities lent that represents claims on U.S. and other OECD depository institutions (and claims on non-OECD depository institutions for securities lent with remaining maturities of one year or less).

• In column F--100% risk weight, include the portion of the credit equivalent amount reported in column B that is not included in columns C through E.

49 Retained recourse on small business obligations sold with recourse. Report in column A the amount of retained recourse on small business obligations reported in Schedule RC-S, Memorandum item 1.b.

Under Section 208 of the Riegle Community Development and Regulatory Improvement Act of 1994, a "qualifying institution" that transfers small business loans and leases on personal property (small business obligations) with recourse in a transaction that qualifies as a sale under generally accepted accounting principles (GAAP) must maintain risk-based capital only against the amount of recourse retained, provided the institution establishes a recourse liability account that is sufficient under GAAP. Only loans and leases to businesses that meet the criteria for a small business concern established by the Small Business Administration under Section 3(c) of the Small Business Act (12 U.S.C. 631) are eligible for this favorable risk-based capital treatment.

In general, a "qualifying institution" is one that is well capitalized without regard to the Section 208 provisions. If a bank ceases to be a qualifying institution or exceeds the retained recourse limit set forth in banking agency regulations implementing Section 208, all new transfers of small business obligations with recourse would not be treated as sales. However, the reporting and risk-based capital treatment described above will continue to apply to any transfers of small business obligations with recourse that were consummated during the time the bank was a "qualifying institution" and did not exceed the limit.

- In column B, report 100 percent of the amount reported in column A.
- In column F--100% risk weight, include the portion of the credit equivalent amount reported in column B that is not included in columns C through E.
- 50 Recourse and direct credit substitutes (other than financial standby letters of credit) subject to the low level exposure rule and residual interests subject to a dollar-for-dollar capital requirement. As defined in the agencies' risk-based capital standards,
 - "Recourse" means an arrangement in which a bank retains, in form or in substance, any
 credit risk directly or indirectly associated with an asset it has sold (in accordance with
 generally accepted accounting principles) that exceeds a pro rata share of the bank's
 claim on the asset.
 - "Direct credit substitute" means an arrangement in which a bank assumes, in form or in substance, credit risk directly or indirectly associated with an on- or off-balance sheet asset or exposure that was not previously owned by the bank (third-party asset) and the risk assumed by the bank exceeds the pro rata share of the bank's interest in the third party asset.
 - "Residual interest" means any on-balance sheet asset that represents an interest (including a beneficial interest) created by a transfer that qualifies as a sale (in accordance with generally accepted accounting principles) of financial assets, whether through a securitization or otherwise, and that exposes a bank to credit risk directly or indirectly associated with the transferred asset that exceeds a pro rata share of the bank's claim on the asset, whether through subordination provisions or other credit enhancement techniques. In general, residual interests include credit-enhancing interest-only strips (both retained and purchased), spread accounts, cash collateral accounts,

50 (cont.)

retained subordinated interests, other forms of overcollateralization, accrued but uncollected interest on transferred assets that (when collected) will be available to serve in a credit-enhancing capacity, and similar on-balance sheet assets that function as a credit enhancement.

Under these definitions, all recourse arrangements in the form of on-balance sheet assets are residual interests. The only type of residual interest that is not a recourse arrangement is a purchased credit-enhancing interest-only strip. Purchased credit-enhancing interest-only strips are a type of direct credit substitute. Recourse arrangements not in the form of on-balance sheet assets (e.g., off-balance sheet recourse obligations, which may have an associated on-balance sheet recourse liability) are not residual interests.

The banking agencies' risk-based capital standards include a low-level exposure rule, which states that if the maximum exposure to loss retained or assumed by a bank in connection with a recourse arrangement, a direct credit substitute, or a residual interest is less than the effective risk-based capital requirement for the credit-enhanced assets (generally, four percent for qualifying first lien 1-4 family residential mortgages and eight percent for most other assets), the risk-based capital requirement is limited to the bank's maximum contractual exposure, less any recourse liability account established in accordance with generally accepted accounting principles.

However, for residual interests (other than credit-enhancing interest-only strips that have been deducted from Tier 1 capital and assets) not eligible for the ratings-based approach, a bank must maintain risk-based capital equal to the face amount of the residual interest (net of any existing associated deferred tax liability recorded on the balance sheet), even if the amount of risk-based capital required to be maintained exceeds the full risk-based capital requirement for the assets transferred. The effect of this requirement is that, notwithstanding the low level exposure rule, a bank must hold one dollar in total risk-based capital against every dollar of the face amount of its residual interests that are not eligible for the ratings-based approach (a dollar-for-dollar capital requirement), except for any credit-enhancing interest-only strips that are required to be deducted from Tier 1 capital and assets.

Because all residual interests (including all retained and purchased credit-enhancing interestonly strips) are on-balance sheet assets, the on-balance sheet amount of a bank's residual interests not eligible for the ratings-based approach should be reported in column B of the Balance Sheet Asset Category section of Schedule RC-R. Similarly, when a direct credit substitute is carried as an asset on the bank's Call Report balance sheet and the low level exposure rule applies, the on-balance sheet asset amount should be reported in column B of the Balance Sheet Asset Category section of Schedule RC-R.

For purposes of this item, the "maximum contractual dollar amount of exposure" of a residual interest and a direct credit substitute that is an on-balance sheet asset is its "face amount" as of the report date, i.e., its amortized cost if it is not held for trading purposes and its fair value if it is held for trading purposes. In determining the "maximum contractual dollar amount of exposure" for a residual interest, a bank is permitted, but not required, to reduce the face amount by the amount of any existing associated deferred tax liability. The "maximum contractual dollar amount of exposure" of a recourse arrangement and a direct credit substitute that is not in the form of an on-balance sheet asset is the maximum contractual amount of the bank's exposure as of the report date, less the balance of any associated recourse liability account established in accordance with generally accepted accounting principles and reported in Schedule RC-G, item 4, "Other" liabilities.

¹ Any deferred tax liability used in this manner would not be available for the bank to use in determining the amount of disallowed deferred tax assets in Schedule RC-R, item 9.b, above.

50 (cont.)

Banks that have entered into (a) recourse arrangements and direct credit substitutes (other than financial standby letters of credit) that are subject to the low level exposure rule and (b) residual interests subject to a dollar-for-dollar capital requirement should report these transactions in this item using either the "direct reduction method" or the "gross-up method" in accordance with the following guidance. When using the "gross-up method," a bank includes an amount in its risk-weighted assets (the denominator of its risk-based capital ratios) for its "maximum contractual dollar amount of exposure" that is calculated under the assumption that the bank's total risk-based capital ratio equals the 8 percent minimum requirement. In contrast, when using the "direct reduction method," a bank includes an institution-specific amount in its risk-weighted assets for its "maximum contractual dollar amount of exposure" that is calculated using the actual amount of the bank's total risk-based capital. This institution-specific calculation produces the effect of directly reducing Tier 1 and total risk-based capital by the "maximum contractual dollar amount of exposure" without lowering the bank's Tier 1 leverage capital ratio. For a bank whose risk-based capital ratios exceed the required minimums, it is normally preferable to use the "direct reduction method."

• If the bank chooses to use the "direct reduction method," the bank should report as the credit equivalent amount in Schedule RC-R, item 50, column B, an "institution-specific add-on factor" for its low-level exposure or residual interest. This credit equivalent amount should then be assigned to the 100 percent risk weight category in column F of this item. The "institution-specific add-on factor," which is independent of the risk weight category of the assets to which the exposure relates, is calculated as follows:

$$F = C \times A - A$$

$$C - R$$

where F = institution-specific add-on factor;

C = total risk-based capital (as reported in Schedule RC-R, item 21);

A = net risk-weighted assets excluding low-level exposures and residual interests; and

R = maximum contractual dollar amount of exposure in low-level exposure transactions or of residual interests (as reported in column A of this item)

For purposes of calculating the amount of the bank's total risk-based capital to be used in the preceding formula (C in the formula) and to be reported in Schedule RC-R, item 21, the bank should determine the Tier 2 capital limit on the allowance for loan and lease losses by multiplying its "maximum contractual dollar amount of exposure" (R in the preceding formula, as defined in these instructions) by 12.5 and adding this product to its gross risk-weighted assets excluding low level exposures and residual interests. This adjusted gross risk-weighted-assets figure multiplied by 1.25 percent is the bank's Tier 2 capital limit on the allowance for loan and lease losses. Once this limit on the allowance has been calculated, the limit is fixed at this amount. This limit should not be changed after the bank calculates the actual amount of its net risk-weighted assets excluding low level exposures and residual interests (A in the preceding formula) or its institution-specific add-on factor for low level exposures and residual interests under the "direct reduction method" (F in the preceding formula). This means that a bank will measure its Tier 2 capital and its total risk-based capital prior to its application of the "direct reduction method" and will not recalculate these two amounts once the add-on factor is known.

• If the bank chooses to use the "gross-up method," the "maximum contractual dollar amount of exposure" for the bank's low level exposure transactions and its residual interests, as reported in column A of this item, should be multiplied by a factor of 12.5. The resulting dollar amount should be reported as the credit equivalent amount in column B of this item and assigned to the 100 percent risk weight category in column F.

50 (cont.)

For example, a bank has sold \$2 million in first lien residential mortgages subject to two percent recourse. The bank has removed the \$2 million in mortgages from its Call Report balance sheet and, in accordance with GAAP, has also established a recourse liability account with a balance of \$10,000. The maximum amount for which the bank is liable is \$40,000. The mortgages qualify for a 50 percent risk weight and the bank's recourse exposure is less than the \$80,000 minimum risk-based capital requirement for these assets sold with recourse. Thus, the low level exposure rule applies. The "maximum contractual dollar amount of exposure" for this transaction is \$30,000, the \$40,000 maximum contractual amount of the bank's recourse exposure as of the report date, less the \$10,000 balance of the recourse liability account for this transaction. The bank has no other transactions that would qualify for the low level exposure rule. It has gross risk-weighted assets excluding low level exposures and residual interests of \$100 million, Tier 1 capital of \$8 million, an allowance for loan and lease losses of \$1.1 million, and other qualifying Tier 2 capital components of \$1.4 million.

- If the bank chooses to use the "direct reduction method," the bank would report \$30,000 - its "maximum contractual dollar amount of exposure" - as the "face value or notional amount" in column A of this item and would use this amount to calculate its institutionspecific add-on factor using the formula provided above. To determine the Tier 2 capital limit for the bank's allowance for loan and lease losses, the bank would first add \$375,000 (\$30,000 -- its "maximum contractual dollar amount of exposure" -- multiplied by 12.5) to its \$100 million of gross risk-weighted assets excluding low level exposures and residual interests. Its Tier 2 capital limit for the allowance would be \$1,254,688 (\$100,375,000 - its adjusted gross risk-weighted assets -- multiplied by 1.25 percent -the limit for the allowance). Since the bank's \$1.1 million allowance is less than its Tier 2 capital limit for the allowance, the bank would report an "excess allowance for loan and lease losses" of \$0 in Schedule RC-R, item 60, column F. The bank's total risk-based capital is \$10.5 million and its net risk-weighted assets excluding low level exposures and residual interests are \$100 million. Based on the facts in the example, the bank calculates that its institution-specific add-on factor is \$286,533. The bank would report the amount of this add-on factor as the credit equivalent amount in column B of this item and assign this amount to the 100 percent risk weight category in column F.
- If the bank chooses to use the "gross-up method," the bank would report \$30,000 (its "maximum contractual dollar amount of exposure") as the "face value or notional amount" in column A of this item. The bank would report \$375,000 as the credit equivalent amount in column B (\$30,000 -- its "maximum contractual dollar amount of exposure" -- multiplied by 12.5). It would also assign this amount to the 100 percent risk weight category in column F of this item. Because the \$2 million in mortgages sold have been removed from the balance sheet, the difference between the \$375,000 credit equivalent amount and the \$2 million is not reported in Schedule RC-R. In addition, the bank would include the \$375,000 in its gross risk-weighted assets for purposes of determining the Tier 2 capital limit for the allowance for loan and lease losses.
- All other financial assets sold with recourse. Include in this item all recourse arrangements (as defined in Schedule RC-R, item 50, above) in which the bank's exposure has not already been included in Schedule RC-R, item 44, "Financial standby letters of credit," item 49, "Retained recourse on small business obligations sold with recourse," or item 50, "Recourse and direct credit substitutes (other than financial standby letters of credit) subject to the low level exposure rule and residual interests subject to a dollar-for-dollar capital requirement." For example, include in this item recourse arrangements where the bank is obligated to repurchase a loan or otherwise compensate the purchaser of a loan in the event of the borrower's failure to pay when due (unless the loan is a small business obligation sold with recourse that has been reported in Schedule RC-R, item 49, above).

51 (cont.)

For those recourse arrangements that must be included in this item that are not eligible for the ratings-based approach, report *in column A* the outstanding principal balance of the loans or other financial assets that were sold with recourse, minus the amount of any recourse liability account associated with these transactions that is included in Schedule RC-G, item 4, "Other" liabilities. For those recourse arrangements that must be included in this item that act as credit enhancements for asset-backed or mortgage-backed securities and to which the ratings-based approach applies, report *in column A*:

- (1) the maximum contractual remaining amount of the bank's recourse exposures that are subject to a risk weight of 100% or less, minus the amount of any recourse liability account associated with these exposures that is included in Schedule RC-G, item 4, and
- (2) two times the maximum contractual remaining amount of the bank's recourse exposures that are subject to a 200% risk weight, minus the amount of any recourse liability account associated with these exposures that is included in Schedule RC-G, item 4.
- In column B, report 100 percent of the amount reported in column A.
- In column C—0% risk weight, include the credit equivalent amount of financial assets
 sold with recourse (not eligible for the ratings-based approach) that, if they were
 carried as assets on the balance sheet, would meet the criteria for the zero percent risk
 weight category as described in the instructions for Risk-Weighted Assets and for
 Schedule RC-R, items 34 through 42, above.
- In column D—20% risk weight, include the credit equivalent amount of financial assets sold with recourse (not eligible for the ratings-based approach) that, if they were carried as assets on the balance sheet, would meet the criteria for the 20 percent risk weight category as described in the instructions for Risk-Weighted Assets and for Schedule RC-R, items 34 through 42, above. Also include in column D the credit equivalent amount of those recourse arrangements to which the ratings-based approach applies that are rated in the highest or second highest investment grade category, e.g., AAA or AA, in the case of long-term ratings, or in the highest rating category, e.g., A-1 or P-1, in the case of short-term ratings.
- In column E—50% risk weight, include the credit equivalent amount of financial assets sold with recourse (not eligible for the ratings-based approach) that, if they were carried as assets on the balance sheet, would meet the criteria for the 50 percent risk weight category as described in the instructions for Risk-Weighted Assets and for Schedule RC-R, items 34 through 42, above. Also include in column E the credit equivalent amount of those recourse arrangements to which the ratings-based approach applies that are rated in the third highest investment grade category, e.g., A, in the case of long-term ratings, or in the second highest rating category, e.g., A-2 or P-2, in the case of short-term ratings.
- *In column F—100% risk weight*, include the portion of the credit equivalent amount reported in column B that is not included in columns C through E.
- All other off-balance sheet liabilities. Report in column A the notional amount of all other off-balance sheet liabilities reported in Schedule RC-L, item 9, that are covered by the risk based capital guidelines. Also include in column A the notional amount of written option contracts that act as financial guarantees, which have been reported as derivatives in Schedule RC-L, item 11, but are treated as direct credit substitutes rather than derivatives for risk-based capital purposes. However, do not report in column A the notional amount of

standby letters of credit issued by a Federal Home Loan Bank on behalf of the reporting bank (cont.) that are reported in Schedule RC-L, item 9, because these letters of credit are not covered by the risk-based capital guidelines.

- In column B, report 100 percent of the notional amount reported in column A.
- In column C--0% risk weight, include the credit equivalent amount of liabilities to
 counterparties who meet, or that have guarantees or collateral that meets, the criteria for
 the zero percent risk weight category as described in the instructions for Risk-Weighted
 Assets and for Schedule RC-R, items 34 through 42, above.
- In column D--20% risk weight, include the credit equivalent amount of liabilities to
 counterparties who meet, or that have guarantees or collateral that meets, the criteria for
 the 20 percent risk weight category as described in the instructions for Risk-Weighted
 Assets and for Schedule RC-R, items 34 through 42, above.
- In column E--50% risk weight, include the credit equivalent amount of liabilities to counterparties who meet, or that have guarantees or collateral that meets, the criteria for the 50 percent risk weight category as described in the instructions for Risk-Weighted Assets and for Schedule RC-R, items 34 through 42, above.
- In column F--100% risk weight, include the portion of the credit equivalent amount reported in column B that is not include in columns C through E.
- the unused portion of commitments to make or purchase extensions of credit in the form of loans or participations in loans, lease financing receivables, or similar transactions as reflected in Schedule RC-L, item 1, that have an original maturity exceeding one year and are subject to the risk-based capital guidelines. Under the risk-based capital guidelines, the unused portion of commitments (facilities) with an original maturity of one year or less or which are unconditionally cancelable (without cause) at any time by the bank, provided a separate credit decision is made before each drawing, have a zero percent conversion factor. The unused portion of such commitments should be excluded from this item. "Original maturity" is defined as the length of time between the date a commitment is issued and the date of maturity, or the earliest date on which the bank (1) is scheduled to (and as a normal practice actually does) review the facility to determine whether or not it should be extended and (2) can unconditionally cancel the commitment. Also include in column A all revolving underwriting facilities (RUFs) and note issuance facilities (NIFs), regardless of maturity.

In the case of consumer home equity or mortgage lines of credit secured by liens on 1-4 family residential properties, a bank is deemed able to unconditionally cancel the commitment if, at its option, it can prohibit additional extensions of credit, reduce the credit line, and terminate the commitment to the full extent permitted by relevant federal law. Retail credit cards and related plans are defined to be short-term commitments that should be converted at zero percent and excluded from this item 53 if the bank has the unconditional right to cancel the line of credit at any time in accordance with applicable law.

For commitments providing for increases in the dollar amount of the commitment, the amount to be converted to an on-balance sheet credit equivalent amount and risk weighted is the maximum dollar amount that the bank is obligated to advance at any time during the life of the commitment. This includes seasonal commitments where the dollar amount of the commitment increases during the customer's peak business period. In addition, this risk-

53 (cont.)

based capital treatment applies to long-term commitments that contain short-term options which, for a fee, allow the customer to increase the dollar amount of the commitment. Until the short-term option has expired, the reporting bank must convert and risk weight the amount which it is obligated to lend if the option is exercised. After the expiration of a short-term option which has not been exercised, the unused portion of the original amount of the commitment is to be used in the credit conversion process.

- In column B, report 50 percent of the amount of unused commitments reported in column A.
- In column C--0% risk weight, include the credit equivalent amount of unused commitments for extensions of credit to counterparties who meet, or that have guarantees or collateral that meets, the criteria for the zero percent risk weight category as described in the instructions for Risk-Weighted Assets and for Schedule RC-R, items 34 through 42, above.
- In column D--20% risk weight, include the credit equivalent amount of unused commitments for extensions of credit to counterparties who meet, or that have guarantees or collateral that meets, the criteria for the 20 percent risk weight category as described in the instructions for Risk-Weighted Assets and for Schedule RC-R, items 34 through 42, above. Include commitments that have been conveyed to U.S. and other OECD depository institutions.
- In column E--50% risk weight, include the credit equivalent amount of unused commitments for extensions of credit to counterparties who meet, or that have guarantees or collateral that meets, the criteria for the 50 percent risk weight category as described in the instructions for Risk-Weighted Assets and for Schedule RC-R, items 34 through 42, above.
- In column F--100% risk weight, include the portion of the credit equivalent amount reported in column B that is not included in columns C through E.
- Derivative contracts. Report in column B the credit equivalent amount of derivative contracts covered by the risk-based capital guidelines. Under these guidelines, the maximum risk weight to be applied to the credit equivalent amount of any derivative contract is 50 percent.

The credit equivalent amount of a bank's derivative contracts is the sum of the current credit exposure reported in Schedule RC-R, Memorandum item 1, plus the total potential future exposure over the remaining lives of all derivative contracts (regardless of their current credit exposure, if any). The potential future credit exposure of a contract, which is based on the type of contract and the contract's remaining maturity, is determined by multiplying the notional principal amount of the contract by the appropriate credit conversion factor from the chart presented below. The notional principal amounts of the reporting bank's derivatives that are subject to the risk-based capital requirements are reported in Schedule RC-R, Memorandum items 2.a through 2.f.

		Foreign		Precious	
	Interest	exchange		metals	Other
	rate	and gold	Equity	contracts	commodity
Remaining maturity	contracts	contracts	contracts	(except gold)	contracts
One year or less	0.0%	1.0%	6.0%	7.0%	10.0%
More than one year					
through five years	0.5%	5.0%	8.0%	7.0%	12.0%
More than five years	1.5%	7.5%	10.0%	8.0%	15.0%

Under the banking agencies' risk-based capital standards and for purposes of Schedule RC-R, the existence of a legally enforceable bilateral netting agreement between the reporting bank and a counterparty may be taken into consideration when determining both the current credit exposure and the potential future exposure of derivative contracts. For further information on the treatment of bilateral netting agreements covering derivative contracts, refer to the instructions for Schedule RC-R, Memorandum item 1, and the risk-based capital standards issued by the reporting bank's primary federal supervisory authority.

- In column C-0% risk weight, include the credit equivalent amount of derivative contracts. with counterparties who meet, or that have guarantees or collateral that meets, the criteria for the zero percent risk weight category as described in the instructions for Risk-Weighted Assets and for Schedule RC-R, items 34 through 42, above.
- In column D-20% risk weight, include the credit equivalent amount of derivative contracts with counterparties who meet, or that have guarantees or collateral that meets, the criteria for the 20 percent risk weight category as described in the instructions for Risk-Weighted Assets and for Schedule RC-R, items 34 through 42, above.
- In column E-50% risk weight, include the portion of the credit equivalent amount reported in column B that is not included in columns C and D.

Totals

- 55 <u>Total assets, derivatives, and off-balance sheet items by risk weight category.</u> Report the sum of items 43 through 54 for each column (columns C through F).
- 56 Risk weight factor.
- **Risk-weighted assets by risk weight category.** For each of columns C through F, multiply the amount in item 55 by the risk weight factor specified for that column in item 56.

NOTE: Item 58 is applicable only to banks that are subject to the market risk capital guidelines.

Market risk equivalent assets. Report the amount of the bank's market risk equivalent assets. For further background information, banks should refer to the discussion of "Banks that are subject to the market risk capital guidelines" in the Risk-Weighted Assets section of these instructions and the capital guidelines of their primary federal supervisory authority for specific instructions on the calculation of the measure for market risk.

The value-at-risk (VAR) of the a bank's covered positions should be used to determine the bank's measure for market risk. Covered positions include all positions in a bank's trading account and foreign exchange and commodity positions, whether or not in the trading account. VAR is an estimate of the amount by which a bank's positions in a risk category could decline due to expected losses in the bank's portfolio due to market movements during a given period, measured with a specified confidence level. A bank's measure for market risk equals the sum of its VAR-based capital charge, the specific risk add-on (if any), and the capital charge for de minimus exposures (if any). A bank's market risk equivalent assets equal its measure for market risk multiplied by 12.5 (the reciprocal of the minimum 8.0 percent capital ratio).

- Banks subject to the market risk capital guidelines must maintain an overall minimum 8.0 percent ratio of total qualifying capital (the sum of Tier 1 capital (both allocated and excess), Tier 2 capital (both allocated and excess), and Tier 3 capital (allocated for market risk), net of all deductions) to risk-weighted assets and market risk equivalent assets. Banks should refer to the capital guidelines of their primary federal supervisory authority for specific instructions on the calculation of the measure for market risk.
- Risk-weighted assets before deductions for excess allowance for loan and lease losses and allocated transfer risk reserve. Report the sum of item 57, columns C through F, and item 58.
- LESS: Excess allowance for loan and lease losses. Report the amount, if any, by which the bank's allowance for loan and lease losses exceeds 1.25 percent of the bank's *gross* risk-weighted assets. The amount to be reported in this item is determined by subtracting Schedule RC-R, item 14, from the sum of Schedule RC, item 4.c, plus Schedule RC-G, item 3.
- LESS: Allocated transfer risk reserve. Report the amount of any allocated transfer risk reserve the reporting bank is required to establish and maintain as specified in Section 905(a) of the International Lending Supervision Act of 1983, in the agency regulations implementing the Act (Subpart D of Federal Reserve Regulation K, Part 347 of the FDIC's Rules and Regulations, and Part 20 of the Comptroller of the Currency's Regulations), and in any guidelines, letters, or instructions issued by the agencies.
- **Total risk-weighted assets.** Report the amount derived by subtracting items 60 and 61 from item 59.

Memoranda

Item No. **Caption and Instructions**

1 Current credit exposure across all derivative contracts covered by the risk-based capital standards. Report the total current credit exposure amount for all interest rate, foreign exchange, commodity, and equity derivative contracts covered by the risk-based capital standards after considering applicable legally enforceable bilateral netting agreements. Banks that are subject to the market risk capital guidelines should exclude all covered positions subject to these quidelines, except for foreign exchange derivatives that are outside of the trading account and all over-the-counter (OTC) derivatives. Foreign exchange derivatives that are outside of the trading account and all OTC derivatives continue to have a counterparty credit risk capital charge and, therefore, a current credit exposure amount for these derivatives should be reported in this item.

The following types of derivative contracts are not covered by the risk-based capital standards:

- (1) interest rate, foreign exchange, equity, commodity and other derivative contracts traded on exchanges that require daily payment of variation margin,
- (2) foreign exchange contracts with an original maturity of fourteen calendar days or less. and
- (3) all written option contracts except for those that are, in substance, financial guarantees.

Purchased options held by the reporting bank that are traded on an exchange are covered by the risk-based capital standards unless such options are subject to a daily variation margin. Variation margin is defined as the gain or loss on open positions, calculated by marking to market at the end of each trading day. Such gain or loss is credited or debited by the clearing house to each clearing member's account, and by members to their customers' accounts.

If a written option contract acts as a financial guarantee, then it will be treated as a direct credit substitute for risk-based capital purposes and the notional amount of the option should be included in Schedule RC-R, item 52, column A, as an "other off-balance sheet liability." An example of such a contract occurs when the reporting bank writes a put option to a second bank which has a loan to a third party. The strike price would be the equivalent of the par value of the loan. If the credit quality of the loan deteriorates, thereby reducing the value of the loan to the second bank, the reporting bank would be required by the second bank to take the loan onto its books.

Current credit exposure (sometimes referred to as the replacement cost) is the fair value of a contract when that fair value is positive. The current credit exposure is zero when the fair value is negative or zero. Current credit exposure should be derived as follows: Determine whether a legally enforceable bilateral netting agreement is in place between the reporting bank and a counterparty. If such an agreement is in place, the fair values of all applicable derivative contracts with that counterparty that are included in the netting agreement are netted to a single amount. Next, for all other contracts covered by the risk-based capital standards that have positive fair values, the total of the positive fair values is determined. Then, report in this item the sum of (i) the net positive fair values of applicable derivative contracts subject to legally enforceable bilateral netting agreements and (ii) the total positive fair values of all other contracts covered by the risk-based capital standards. The current credit exposure reported in this item is a component of the credit equivalent amount of derivative contracts that is to be reported in Schedule RC-R, item 54, column B.

Memoranda

Item No. Caption and Instructions

Consistent with the risk-based capital guidelines, if a bilateral netting agreement covers off-balance sheet derivative contracts that are normally not covered by the risk-based capital standards (e.g., foreign exchange contracts with an original maturity of 14 calendar days or less and contracts traded on exchanges that require daily payment of variation margin), the reporting bank may elect to consistently either include or exclude the fair values of all such derivative contracts when determining the net current credit exposure for that agreement.

The definition of a legally enforceable bilateral netting agreement for purposes of this item is the same as that set forth in the risk-based capital rules. These rules require a written bilateral netting contract that creates a single legal obligation covering all included individual contracts and that does not contain a walkaway clause. The bilateral netting agreement must be supported by a written and reasoned legal opinion representing that an organization's claim or obligation, in the event of a legal challenge, including one resulting from default, insolvency, bankruptcy, or similar circumstances, would be found by the court and administrative authorities of all relevant jurisdictions to be the net sum of all positive and negative fair values of contracts included in the bilateral netting contract.

Notional principal amounts of derivative contracts. Report in the appropriate subitem and column the notional amount or par value of all derivative contracts that are subject to the risk-based capital requirements for derivatives. Such contracts include swaps, forwards, and purchased options. Report notional amounts and par values in the column corresponding to the contract's remaining term to maturity from the report date. Remaining maturities are to be reported as (1) one year or less in column A, (2) over one year through five years in column B, or (3) over five years in column C.

Do not report the notional amount for single currency interest rate swaps in which payments are made based upon two floating rate indices, so-called floating/floating or basis swaps; foreign exchange contracts with an original maturity of 14 days or less; and futures contracts.

The notional amount or par value to be reported for an off-balance-sheet derivative contract with a multiplier component is the contract's effective notional amount or par value. (For example, a swap contract with a stated notional amount of \$1,000,000 whose terms call for quarterly settlement of the difference between 5% and LIBOR multiplied by 10 has an effective notional amount of \$10,000,000.)

The notional amount to be reported for an amortizing derivative contract is the contract's current (or, if appropriate, effective) notional amount. This notional amount should be reported in the column corresponding to the contract's remaining term to final maturity.

For descriptions of "interest rate contracts," "foreign exchange contracts," "commodity and other contracts," and "equity derivative contracts," refer to the instructions for Schedule RC-L, item 11.

- **2.a** <u>Interest rate contracts.</u> Report the remaining maturities of interest rate contracts that are subject to risk-based capital requirements.
- **2.b** Foreign exchange contracts. Report the remaining maturities of foreign exchange contracts that are subject to risk-based capital requirements.
- **2.c Gold contracts.** Report the remaining maturities of gold contracts that are subject to risk-based capital requirements.

Memoranda

Item No. Caption and Instructions

- **Other precious metals contracts.** Report the remaining maturities of other precious metals contracts that are subject to risk-based capital requirements. Report all silver, platinum, and palladium contracts.
- **2.e**Other commodity contracts. Report the remaining maturities of other commodity contracts that are subject to risk-based capital requirements. For contracts with multiple exchanges of principal, notional amount is determined by multiplying the contractual amount by the number of remaining payments (i.e., exchanges of principal) in the derivative contract.
- **2.f** Equity derivative contracts. Report the remaining maturities of equity derivative contracts that are subject to risk-based capital requirements.

SCHEDULE RC-S – SERVICING, SECURITIZATION, AND ASSET SALE ACTIVITIES

General Instructions

Schedule RC-S should be completed on a fully consolidated basis. Schedule RC-S includes information on 1-4 family residential mortgages and other financial assets serviced for others (in Memorandum items 2.a, 2.b, and 2.c). Schedule RC-S also includes information on assets that have been securitized or sold and are not reportable on the balance sheet of the Report of Condition, except for certain on-balance-sheet retained interest-only strips (which are reported in item 2.a of this schedule), subordinated securities and other enhancements (which are reported in items 2.b and 9 and Memorandum items 3.a.(1) and (2)), and seller's interests (which are reported in items 6.a and 6.b).

Column Instructions

Column A, 1-4 Family Residential Loans: 1-4 family residential loans are permanent closed-end loans secured by first or junior liens on 1-to-4 family residential properties as defined for Schedule RC-C, part I, items 1.c.(2)(a) and 1.c.(2)(b).

Column B, Home Equity Lines: Home equity lines are revolving, open-end lines of credit secured by 1-to-4 family residential properties as defined for Schedule RC-C, part I, item 1.c.(1).

Column C, Credit Card Receivables: Credit card receivables are extensions of credit to individuals for household, family, and other personal expenditures arising from credit cards as defined for Schedule RC-C, part I, item 6.a.

Column D, Auto Loans: Auto loans are loans to individuals for the purpose of purchasing private passenger vehicles, including minivans, vans, sport-utility vehicles, pickup trucks, and similar light trucks for personal use, and are a subset of "Other consumer loans," as defined for Schedule RC-C, part I, item 6.c.

Column E, Other Consumer Loans: Other consumer loans are loans to individuals for household, family, and other personal expenditures as defined for Schedule RC-C, part I, items 6.b and 6.c, excluding auto loans as described in Column D of this schedule.

Column F, Commercial and Industrial Loans: Commercial and industrial loans are loans for commercial and industrial purposes to sole proprietorships, partnerships, corporations, and other business enterprises, whether secured (other than by real estate) or unsecured, single-payment or installment, as defined for Schedule RC-C, part I, item 4.

Column G, All Other Loans and All Leases: All other loans are loans that cannot properly be reported in Columns A through F of this schedule and all lease financing receivables as defined for Schedule RC-C, part I, items 1.a, 1.b, 1.d, 1.e, 2, 3, and 7 through 10.

For purposes of items 1 through 10 of Schedule RC-S on bank securitization activities and other securitization facilities, information about each separate securitization should be included in only one of the seven columns of this schedule. The appropriate column for a particular securitization should be based on the predominant type of loan included in the securitization and this column should be used consistently over time. For example, a securitization may include auto loans to individuals and to business enterprises. If these auto loans are predominantly loans to individuals, all of the requested information about this securitization should be included in Column D, Auto Loans.

Definitions

For purposes of this schedule, the following definitions of terms are applicable.

Recourse or other seller-provided credit enhancement means an arrangement in which the reporting bank retains, in form or in substance, any risk of credit loss directly or indirectly associated with a transferred (sold) asset that exceeds its pro rata claim on the asset. It also includes a representation or warranty extended by the reporting bank when it transfers an asset, or assumed by the bank when it services a transferred asset, that obligates the bank to absorb credit losses on the transferred asset. Such an arrangement typically exists when a bank transfers assets and agrees to protect purchasers or some other party, e.g., investors in securitized assets, from losses due to default by or nonperformance of the obligor on the transferred assets or some other party. The bank provides this protection by retaining:

- (a) an interest in the transferred assets, e.g., credit-enhancing interest-only strips, "spread" accounts, subordinated interests or securities, collateral invested amounts, and cash collateral accounts, that absorbs losses, or
- (b) an obligation to repurchase the transferred assets

in the event of a default of principal or interest on the transferred assets or any other deficiency in the performance of the underlying obligor or some other party. Subordinated interests and subordinated securities retained by a bank when it securitizes assets expose the bank to more than its pro rata share of loss and thus are considered a form of credit enhancement to the securitization structure.

Credit-enhancing interest-only strip, as defined in the banking agencies' regulatory capital standards, means an on-balance sheet asset that, in form or in substance: (i) represents the contractual right to receive some or all of the interest due on transferred assets; and (ii) exposes the bank to credit risk directly or indirectly associated with the transferred assets that exceeds a pro rata share of the bank's claim on the assets, whether through subordination provisions or other credit enhancement techniques. Credit-enhancing interest-only strips include other similar "spread" assets and can be either retained or purchased.

Liquidity facility means any arrangement, including servicer cash advances, in which the reporting bank is obligated to provide funding to a securitization structure to ensure investors of timely payments on issued securities, e.g., by smoothing timing differences in the receipt of interest and principal payments on the underlying securitized assets, or to ensure investors of payments in the event of market disruptions. Advances under such a facility are typically reimbursed from subsequent collections by the securitization structure and are not subordinated to other claims on the cash flows from the underlying assets and, therefore, should generally not be construed to be a form of credit enhancement. However, if the advances under such a facility are subordinated to other claims on the cash flows, the facility should be treated as a credit enhancement for purposes of this schedule.

Seller's interest means the reporting bank's ownership interest in loans that have been securitized, except an interest that is a form of recourse or other seller-provided credit enhancement. Seller's interests should be reported on Schedule RC – Balance Sheet – as securities or as loans depending on the form in which the interest is held. However, seller's interests differ from the securities issued to investors by the securitization structure. The principal amount of a seller's interest is generally equal to the total principal amount of the pool of assets included in the securitization structure less the principal amount of those assets attributable to investors, i.e., in the form of securities issued to investors.

Item Instructions

Item No. Caption and Instructions

Bank Securitization Activities

- Outstanding principal balance of assets sold and securitized by the reporting bank with servicing retained or with recourse or other seller-provided credit enhancements.

 Report in the appropriate column the principal balance outstanding as of the report date of loans and leases which the reporting bank has sold and securitized while:
 - (1) retaining the right to service these assets or
 - (2) when servicing has not been retained, retaining recourse or providing other seller-provided credit enhancements to the securitization structure.

Exclude the principal balance of loans underlying seller's interests owned by the reporting bank; report the amount of seller's interests in Schedule RC-S, item 6. Also exclude small business obligations transferred with recourse under Section 208 of the Riegle Community Development and Regulatory Improvement Act of 1994, which are to be reported in Schedule RC-S, Memorandum item 1, below.

Do *not* report in this item the outstanding balance of 1-4 family residential mortgages sold to the Federal National Mortgage Association (Fannie Mae) or the Federal Home Loan Mortgage Corporation (Freddie Mac) that the government-sponsored agency in turn securitizes. Report 1-4 family residential mortgages sold to Fannie Mae or Freddie Mac with recourse or other seller-provided credit enhancements in Schedule RC-S, item 11, column A, and report the maximum credit exposure arising from the enhancements in item 12, column A. If servicing has been retained on the 1-4 family residential mortgages, report the outstanding principal balance of the mortgages in Schedule RC-S, Memorandum item 2.a or 2.b depending on whether the servicing is performed with or without recourse or other servicer-provided credit enhancements. If the bank has both retained the servicing and provided credit enhancements, report the principal balance of the 1-4 family residential mortgages in Schedule RC-S, item 11, column A, and in Memorandum item 2.a.

<u>Exclude</u> securitizations that the reporting bank has accounted for as secured borrowings because the transactions do not meet the criteria for sale accounting under generally accepted accounting principles. The securitized loans and leases should continue to be carried as assets on the reporting bank's balance sheet.

2 Maximum amount of credit exposure arising from recourse or other seller-provided credit enhancements provided to structures reported in item 1. Report in the appropriate subitem the maximum contractual credit exposure remaining as of the report date under recourse arrangements and other seller-provided credit enhancements provided by the reporting bank to securitization structures reported in Schedule RC-S, item 1, above. Do not report as the remaining maximum contractual exposure a reasonable estimate of the probable loss under the recourse arrangements or credit enhancement provisions or the fair value of any liability incurred under such provisions. Furthermore, do not reduce the remaining maximum contractual exposure by the amount of any associated recourse liability account. Report exposure amounts gross rather than net of any tax effects, e.g., any associated deferred tax liability.

Do not include unused portions of commitments that function as liquidity facilities (report such unused commitments in Schedule RC-S, item 3).

- **Retained interest-only strips.** Report in the appropriate column the carrying value of credit-enhancing interest-only strips included as securities in Schedules RC-B, as other assets in Schedule RC-F, or as trading assets in Schedule RC, item 5, that the reporting bank has retained as credit enhancements in connection with the securitization structures reported in Schedule RC-S, item 1, above.
- 2.b Standby letters of credit, subordinated securities, and other enhancements. Report in the appropriate column the unused portion of standby letters of credit, the carrying value of subordinated securities or other retained interests (other than retained credit-enhancing interest-only strips reported in Schedule RC-S, item 2.a, above), and the maximum contractual amount of recourse or other credit exposure arising from other on- and off-balance sheet credit enhancements that the reporting bank has provided or retained in connection with the securitization structures reported in Schedule RC-S, item 1, above.
- Reporting bank's unused commitments to provide liquidity to structures reported in item 1. Report in the appropriate column the unused portions of commitments provided by the reporting bank to the securitization structures reported in Schedule RC-S, item 1, above that function as liquidity facilities.
- Past due loan amounts included in item 1. Report in the appropriate subitem the outstanding principal balance of loans and leases reported in Schedule RC-S, item 1, above that are 30 days or more past due as of the report date. For purposes of determining whether a loan or lease reported in item 1 above is past due, the reporting criteria to be used are the same as those for columns A and B of Schedule RC-N.
- **4.a 30-89 days past due.** Report in the appropriate column the outstanding principal balance of loans and leases reported in Schedule RC-S, item 1, above that are 30 to 89 days past due as of the report date.
- **4.b 90 days or more past due.** Report in the appropriate column the outstanding principal balance of loans and leases reported in Schedule RC-S, item 1, above that are 90 days or more past due as of the report date.
- Charge-offs and recoveries on assets sold and securitized with servicing retained or with recourse or other seller-provided credit enhancements (calendar year-to-date).

 Report in the appropriate subitem the amount of charge-offs and recoveries during the calendar year to date on loans and leases that have been sold and securitized in the securitization structures reported in Schedule RC-S, item 1, above.
- **Charge-offs.** Report in the appropriate column the amount of loans and leases that have been sold and securitized by the reporting bank in the securitization structures reported in Schedule RC-S, item 1, above that have been charged off or otherwise designated as losses by the trustees of the securitizations, or other designated parties, during the calendar year-to-date.
- **Recoveries.** Report in the appropriate column the amount of recoveries of previously charged-off loans and leases in the securitization structures reported in Schedule RC-S, item 1, above during the calendar year-to-date.
- Amount of ownership (or seller's) interests carried as. Report in the appropriate subitem the carrying value of the reporting bank's ownership (or seller's) interests associated with the securitization structures reported in Schedule RC-S, item 1, above.

- **Securities.** Report in the appropriate column the carrying value of seller's interests in the form of a security that are included as available-for-sale or held-to-maturity securities in Schedule RC-B Securities or as trading securities in Schedule RC, item 5, "Trading assets."
- **Loans.** Report in the appropriate column the carrying value of seller's interests not in the form of a security. Such seller's interests are to be reported as loans and included in Schedule RC-C Loans and Lease Financing Receivables.
- Past due loan amounts included in interests reported in item 6.a. Report in the appropriate subitem the outstanding principal balance of loans underlying the reporting bank's seller's interests reported in Schedule RC-S, item 6.a, above that are 30 days or more past due as of the report date. For purposes of determining whether a loan underlying a seller's interest reported in item 6.a is past due, the reporting criteria to be used are the same as those for columns A and B of Schedule RC-N.
- **7.a 30-89 days past due.** Report in the appropriate column the outstanding principal balance of loans underlying the seller's interests reported in Schedule RC-S, item 6.a, above that are 30-89 days past due as of the report date.
- **7.b 90 days or more past due.** Report in the appropriate column the outstanding principal balance of loans underlying the seller's interests reported in Schedule RC-S, item 6.a, above that are 90 or more days past due as of the report date.
- Charge-offs and recoveries on loan amounts included in interests reported in item 6.a (calendar year-to-date). Report in the appropriate subitem the amount of charge-offs and recoveries during the calendar year to date on loans that had been underlying the seller's interests reported in Schedule RC-S, item 6.a, above.
- **8.a** Charge-offs. Report in the appropriate column the amount of loans that had been underlying the seller's interests reported in Schedule RC-S, item 6.a, above that have been charged off or otherwise designated as losses by the trustees of the securitizations, or other designated parties, during the calendar year-to-date.
- **Recoveries.** Report in the appropriate column the amount of recoveries of previously charged-off loans that had been underlying the seller's interests reported in Schedule RC-S, item 6.a, above during the calendar year-to-date.

For Securitization Facilities Sponsored By or Otherwise Established By Other Institutions

Maximum amount of credit exposure arising from credit enhancements provided by the reporting bank to other institutions' securitization structures in the form of standby letters of credit, purchased subordinated securities, and other enhancements. Report in the appropriate column the maximum contractual credit exposure remaining as of the report date under credit enhancements provided by the reporting bank to securitization structures sponsored by or otherwise established by other institutions or entities, i.e., securitizations not reported in Schedule RC-S, item 1, above. Report the unused portion of standby letters of credit, the carrying value of purchased subordinated securities and purchased credit-enhancing interest-only strips, and the maximum contractual amount of credit exposure arising from other on- and off-balance sheet credit enhancements that provide credit support to these securitization structures. Do not report as the remaining maximum contractual exposure a reasonable estimate of the probable loss under credit enhancement provisions or the fair value of any liability incurred under such provisions.

9 Furthermore, do not reduce the remaining maximum contractual exposure by the amount of (cont.) any associated recourse liability account. Report exposure amounts gross rather than net of any tax effects, e.g., any associated deferred tax liability.

Exclude the amount of credit exposure arising from loans and leases that the reporting bank has sold with recourse or other seller-provided credit enhancements to other institutions or entities, which then securitized the loans and leases purchased from the bank (report this exposure in Schedule RC-S, item 12, below). Also exclude the amount of credit exposure arising from credit enhancements provided to asset-backed commercial paper conduits (report this exposure in Schedule RC-S, Memorandum item 3.a).

Reporting bank's unused commitments to provide liquidity to other institutions'
securitization structures. Report in the appropriate column the unused portions of commitments provided by the reporting bank that function as liquidity facilities to securitization structures sponsored by or otherwise established by other institutions or entities, i.e., securitizations not reported in Schedule RC-S, item 1, above. Exclude the amount of unused commitments to provide liquidity to asset-backed commercial paper conduits (report this amount in Schedule RC-S, Memorandum item 3.b).

Bank Asset Sales

Assets sold with recourse or other seller-provided credit enhancements and not securitized by the reporting bank. Report in the appropriate column the unpaid principal balance as of the report date of loans and leases, which the reporting bank has sold with recourse or other seller-provided credit enhancements, but which were not securitized by the reporting bank. Include loans and leases that the reporting bank has sold with recourse or other seller-provided credit enhancements to other institutions or entities, whether or not the purchaser has securitized the loans and leases purchased from the bank. Include 1-4 family residential mortgages that the reporting bank has sold to the Federal National Mortgage Association (Fannie Mae) or the Federal Home Loan Mortgage Corporation (Freddie Mac) with recourse or other seller-provided credit enhancements.

Exclude small business obligations transferred with recourse under Section 208 of the Riegle Community Development and Regulatory Improvement Act of 1994, which are to be reported in Schedule RC-S, Memorandum item 1, below.

Maximum amount of credit exposure arising from recourse or other seller-provided credit enhancements provided to assets reported in item 11. Report in the appropriate column the maximum contractual credit exposure remaining as of the report date under recourse arrangements or other seller-provided credit enhancements provided by the reporting bank in connection with its sales of the loans and leases reported in Schedule RC-S, item 11, above. Report the unused portion of standby letters of credit, the carrying value of retained interests, and the maximum contractual amount of recourse or other credit exposure arising from other on- and off-balance sheet credit enhancements that the reporting bank has provided. Do not report as the remaining maximum contractual exposure a reasonable estimate of the probable loss under the recourse arrangements or credit enhancement provisions or the fair value of any liability incurred under such provisions. Furthermore, do not reduce the remaining maximum contractual exposure by the amount of any associated recourse liability account. Report exposure amounts gross rather than net of any tax effects, e.g., any associated deferred tax liability.

Memoranda

- Small business obligations transferred with recourse under Section 208 of the Riegle Community Development and Regulatory Improvement Act of 1994. Report in the appropriate subitem the outstanding principal balance of and recourse exposure on small business loans and leases on personal property (small business obligations) which the bank has transferred with recourse during the time the bank was a "qualifying institution" and did not exceed the retained recourse limit set forth in banking agency regulations implementing Section 208. Transfers of small business obligations with recourse that were consummated during such a time should be reported as sales for Call Report purposes if the transactions are treated as sales under generally accepted accounting principles (GAAP) and the institution establishes a recourse liability account that is sufficient under GAAP.
- **1.a** Outstanding principal balance. Report the principal balance outstanding as of the report date for small business obligations which the bank has transferred with recourse while it was a "qualifying institution" and did not exceed the retained recourse limit.
- 1.b Amount of retained recourse on these obligations as of the report date. Report the maximum contractual amount of recourse the bank has retained on the small business obligations whose outstanding principal balance was reported in Schedule RC-S, Memorandum item 1.a. above, not a reasonable estimate of the probable loss under the recourse provision and not the fair value of the liability incurred under this provision. Furthermore, the remaining maximum contractual exposure should not be reduced by the amount of any associated recourse liability account. The amount of recourse exposure to be reported should not include interest payments the bank has advanced on delinquent obligations. For small business obligations transferred with full (unlimited) recourse, the amount of recourse exposure to be reported is the outstanding principal balance of the obligations as of the report date. For small business obligations transferred with limited recourse, the amount of recourse exposure to be reported is the maximum amount of principal the transferring bank would be obligated to pay the holder of the obligations in the event the entire outstanding principal balance of the obligations transferred becomes uncollectible.
- Qutstanding principal balance of assets serviced for others. Report in the appropriate subitem the outstanding principal balance of loans and other financial assets the bank services for others. Include (1) the principal balance of loans and other financial assets owned by others for which the reporting bank has purchased the servicing (i.e., purchased servicing) and (2) the principal balance of loans and other financial assets that the reporting bank has either originated or purchased and subsequently sold, whether or not securitized, but for which it has retained the servicing duties and responsibilities (i.e., retained servicing).
- 2.a 1–4 family residential mortgages serviced with recourse or other servicer- provided credit enhancements. Report the outstanding principal balance of 1-to-4 family residential mortgage loans that the reporting bank services for others under servicing arrangements in which the reporting bank also provides recourse or other servicer-provided credit enhancements. Include 1-to-4 family residential mortgages serviced under regular option contracts (i.e., with recourse) with the Federal National Mortgage Association, serviced with recourse for the Federal Home Loan Mortgage Corporation, and serviced with recourse under other servicing contracts.
- 2.b 1—4 family residential mortgages serviced with no recourse or other servicer- provided credit enhancements. Report the outstanding principal balance of 1-to-4 family residential mortgage loans that the reporting bank services for others under servicing arrangements in which the reporting bank does not provide recourse or other servicer-provided credit enhancements.

Memoranda

Item No. Caption and Instructions

2.c Other financial assets. NOTE: Memorandum item 2.c is to be completed if the principal balance of loans and other financial assets serviced for others is more than \$10 million.

Report the outstanding principal balance of loans and other financial assets, other than 1-to-4 family residential mortgage loans, that the reporting bank services for others. These serviced financial assets may include, but are not limited to, credit cards, automobile loans, and loans guaranteed by the Small Business Administration.

- 3 Asset-backed commercial paper conduits:
- 3.a Maximum amount of credit exposure arising from credit enhancements provided to conduit structures in the form of standby letters of credit, subordinated securities, and other enhancements. Report in the appropriate subitem the maximum contractual credit exposure remaining as of the report date under standby letters of credit, subordinated securities, and other credit enhancements provided by the reporting bank to asset-backed commercial paper conduit structures. Do not report in these subitems a reasonable estimate of the probable loss under the credit enhancement provisions or the fair value of any liability incurred under such provisions.
- 3.a.(1) Conduits sponsored by the bank, a bank affiliate, or the bank's holding company.

 Report the unused portion of standby letters of credit, the carrying value of subordinated securities, and the maximum contractual amount of credit exposure arising from other credit enhancements that the reporting bank has provided to asset-backed commercial paper conduit structures sponsored by the reporting bank, an affiliate of the reporting bank, or the reporting bank's holding company.
- 3.a.(2) Conduits sponsored by other unrelated institutions. Report the unused portion of standby letters of credit, the carrying value of subordinated securities, and the maximum contractual amount of credit exposure arising from other credit enhancements that the reporting bank has provided to asset-backed commercial paper conduit structures other than those sponsored by the reporting bank, an affiliate of the reporting bank, or the reporting bank's holding company.
- 3.b Unused commitments to provide liquidity to conduit structures. Report in the appropriate subitem the unused portions of commitments provided by the reporting bank that function as liquidity facilities to asset-backed commercial paper conduit structures. Typically, these facilities take the form of a Backstop Line (Loan Agreement) or an Asset Purchase Agreement. Under a backstop line, the reporting bank advances funds to the conduit when a draw is required under the liquidity facility. The advance is secured by the cash flow of the underlying asset pools. Under an asset purchase agreement, the reporting bank purchases a specific pool of assets from the conduit when a draw is required under the liquidity facility. Typically, the reporting bank is repaid from the cash flow on the purchased assets or from the sale of the purchased pool of assets.
- 3.b.(1) Conduits sponsored by the bank, a bank affiliate, or the bank's holding company.

 Report the unused portions of commitments provided by the reporting bank that function as liquidity facilities to asset-backed commercial paper conduit structures sponsored by the reporting bank, an affiliate of the reporting bank, or the reporting bank's holding company.
- 3.b.(2) Conduits sponsored by other unrelated institutions. Report the unused portions of commitments provided by the reporting bank that function as liquidity facilities to asset-backed commercial paper conduit structures other than those sponsored by the reporting bank, an affiliate of the reporting bank, or the reporting bank's holding company.

SCHEDULE RC-T – FIDUCIARY AND RELATED SERVICES

Note: Schedule RC-T is to be completed beginning December 31, 2001.

This schedule should be completed on a fully consolidated basis, i.e., including any trust company subsidiary (or subsidiaries) of the reporting institution.

The information reported in Schedule RC-T, items 12 through 23, on fiduciary and related services income and in all of Memorandum item 4 on fiduciary settlements, surcharges, and other losses will not be made available to the public on an individual institution basis.

Item No. Caption and Instructions

- Does the institution have fiduciary powers? Institutions granted trust powers by a state or national regulatory authority to administer accounts in a fiduciary capacity should answer "Yes." Institutions with trust company subsidiaries should also answer "Yes." Institutions responding "No" should not complete the remainder of this schedule. Fiduciary capacity generally means trustee, executor, administrator, registrar of stocks and bonds, transfer agent, guardian, assignee, receiver, custodian under a uniform gifts to minors act, investment adviser (if the institution receives a fee for its investment advice), any capacity in which the institution possesses investment discretion on behalf of another, or any other similar capacity. For state-chartered institutions, this schedule should be completed if the state has granted trust powers to the institution to offer fiduciary services as defined by the state.
- Does the institution exercise the fiduciary powers it has been granted? Institutions exercising their fiduciary powers should respond "Yes." Exercising fiduciary powers means that an institution, or a trust company subsidiary of the institution, serves in a fiduciary capacity as defined in the instructions for item 1 of this schedule.
- Does the institution have fiduciary or related services to report in this schedule?

 Institutions including their trust company subsidiaries) with fiduciary assets, accounts, income, or other reportable fiduciary related services should respond "Yes." Institutions responding "No" should not complete the remainder of this schedule.

Reportable fiduciary and related services include activities that do not require trust powers but are incidental to fiduciary services. Specifically, this includes custodial services for assets held by the institution in a fiduciary capacity. An institution should report custodial activities that are offered through the fiduciary business unit or through another distinct business unit that is devoted to institutional custodial services. Institutions should exclude those custodial and escrow activities related to commercial bank services such as retail and institutional brokerage assets, escrow assets held for the benefit of third parties, safety deposit box assets, and any other similar commercial arrangement.

Institutions with fiduciary activities that are limited to only land trusts and/or custodial activity for mortgage-backed securities (such as GNMA or FNMA) should respond "No."

If the answer to item 3 is "YES" complete the applicable items of Schedule RC-T, as follows:

Institutions with total fiduciary assets (item 9, sum of columns A and B) greater than \$250 million (as of the preceding December 31) or with gross fiduciary and related services income greater than 10 percent of revenue (net interest income plus noninterest income) for the preceding calendar year must complete:

3 (cont.)

- Items 4 through 19 on the FFIEC 041 quarterly; items 4 through 19.a. on the FFIEC 031 quarterly;
- Items 20 through 23 annually with the December report; and
- Memorandum items 1 through 4 annually with the December report.

Institutions with total fiduciary assets (item 9, sum of columns A and B) greater than \$100 million but less than \$250 million (as of the preceding December 31) that do not meet the fiduciary income test for quarterly reporting must complete:

- Items 4 through 23 annually with the December report; and
- Memorandum items 1 through 4 annually with the December report.

Institutions with total fiduciary assets (Item 9, sum of columns A and B) of \$100 million or less (as of the preceding December 31) that do not meet the fiduciary income test for quarterly reporting must complete:

- Items 4 through 10 on the FFIEC 041 annually with the December report; items 4 through 11 on the FFIEC 031 annually with the December report; and
- Memorandum items 1 through 3 annually with the December report.

Fiduciary and Related Assets

Institutions should generally report fiduciary and related assets using their market value as of the report date. While market value quotations are readily available for marketable securities, many financial and physical assets held in fiduciary accounts are not widely traded or easily valued. If the methodology for determining market values is not set or governed by applicable law (including the terms of the prevailing fiduciary agreement), the institution may use any reasonable method to establish values for fiduciary and related assets for purposes of reporting on this schedule. Reasonable methods include appraised values, book values, or reliable estimates. Valuation methods should be consistent from reporting period to reporting period. This "reasonable method" approach to reporting market values applies both to financial assets that are not marketable and to physical assets. Common physical assets held in fiduciary accounts include real estate, equipment, collectibles, and household goods.

If two institutions are named co-fiduciary in the governing instrument, both institutions should report the account. In addition, where one institution contracts with another for fiduciary or related services (i.e., Bank A provides custody services to the trust accounts of Bank B, or Bank A provides investment management services to the trust accounts of Bank B) both institutions should report the accounts in their respective capacities.

Exclude unfunded insurance trusts, testamentary executor appointments, and any other arrangements representing potential future fiduciary accounts.

Asset values reported on this schedule should generally exclude liabilities. For example, an employee benefit account with associated loans against account assets should be reported gross of the outstanding loan balances. As another example, an account with a real estate asset and corresponding mortgage loan should be reported gross of the mortgage liability. However, there are two exceptions. First, for purposes of this schedule, overdrafts should be netted against gross fiduciary assets. Second, the fair value of derivative instruments, as defined in FASB Statement No. 133, should be included in (i.e., netted against) gross assets even if the fair value is negative.

Securities borrowing/lending transactions should be reflected as sales or as secured borrowings according to FASB Statement No. 140. A transferee ("borrower") of securities generally is required to provide "collateral" to the transferor ("lender") of securities. When such transactions do not qualify as sales, securities "lenders" and "borrowers" should account for the transactions as secured borrowings in

Fiduciary and Related Assets (cont.)

which cash (or securities that the holder is permitted by contract or custom to sell or repledge) received as "collateral" by the securities "lender" is considered the amount borrowed and the securities "loaned" are considered pledged against the amount borrowed. For purposes of this schedule, securities held in fiduciary accounts that are "loaned" in securities lending transactions (that are accounted for as secured borrowings) should be reported as an asset of the fiduciary account that "loaned" the securities, but the "collateral" received should not also be reported as an asset of this fiduciary account.

In the Fiduciary and Related Assets section, the market value of Collective Investment Fund (CIF) units should be reported along with individual participant accounts in the Column and Item that corresponds to each participant. The aggregate amount of a CIF that is operated by an institution should NOT also be reported as a separate, additional account in the Fiduciary and Related Assets section of this schedule.

Managed Assets - Column A

Report the total market value of assets held in managed fiduciary accounts. An account should be categorized as managed if the institution has investment discretion. Investment discretion is defined as the sole or shared authority (whether or not that authority is exercised) to determine what securities or other assets to purchase or sell on behalf of the fiduciary related account. An institution that delegates its authority over investments and an institution that receives delegated authority over investments are BOTH deemed to have investment discretion. An entire account should be reported as either managed or non-managed based on the predominant responsibility of the reporting institution.

Non-Managed Assets - Column B

Report the total market value of assets held in non-managed fiduciary accounts. An account should be categorized as non-managed if the institution does not have investment discretion. Those accounts for which the institution provides a menu of investment options but the ultimate selection authority remains with the account holder or an external manager should be categorized as non-managed. For example, an institution that offers a choice of sweep vehicles is not necessarily exercising investment discretion. The process of narrowing investment options from a range of alternatives does not create a managed fiduciary account for the purposes of this schedule.

Number of Managed Accounts - Column C

Report the total number of managed fiduciary accounts.

Number of Non-Managed Accounts – Column D

Report the total number of non-managed fiduciary accounts.

- Personal trust and agency accounts. Report the market value and number of accounts for all testamentary trusts, revocable and irrevocable living trusts, other personal trusts, and non-managed personal agency accounts. Include accounts in which the institution serves as executor, administrator, guardian, or conservator. Exclude personal investment management agency accounts, which should be reported in Schedule RC-T, item 7. Also exclude Keogh Act plans, Individual Retirement Accounts (IRAs), and other pension or profit-sharing plans for self-employed individuals which should be reported in Schedule RC-T, item 5.c. Personal accounts that are solely custody or safekeeping should be reported in item 10 of this schedule.
- 5 Retirement related trust and agency accounts:
- **5.a** Employee benefit defined contribution. Report the market value and number of accounts for all employee benefit defined contribution accounts in which the institution serves as either trustee or agent. Include 401(k) plans, 403(b) plans, profit-sharing plans, money

- 5.a purchase plans, target benefit plans, stock bonus plans, employee stock ownership plans, (cont.) and thrift/savings plans. The number of accounts reported should reflect the total number of plans administered rather than the number of plan participants. Employee benefit accounts that are solely custody and safekeeping accounts should be reported in Schedule RC-T, item 10.
- **Employee benefit defined benefit**. Report the market value and number of accounts for all employee benefit defined benefit plans in which the institution serves as either trustee or agent. The number of accounts reported should reflect the total number of plans administered rather than the number of plan participants. Employee benefit accounts that are solely custody and safekeeping accounts should be reported in Schedule RC-T, item 10.
- 5.c Other retirement accounts. Report the market value and number of accounts for all other retirement related fiduciary accounts in which the institution serves as trustee or agent. Include Keogh Act plans, Individual Retirement Accounts, and other pension or profit-sharing plans for self-employed individuals. Exclude accounts, originated by fiduciary or non-fiduciary personnel, that are solely administered to hold own-bank deposits. Also exclude those retirement accounts that are originated and managed through a brokerage account. Other retirement accounts that are solely custody and safekeeping accounts should be reported in Schedule RC-T, item 10.
- Corporate trust and agency accounts. Report the market value of assets held by the institution for all corporate trust and agency accounts. Report assets that are the responsibility of the institution to manage or administer in accordance with the corporate trust agreement. Include assets relating to unpresented bonds or coupons relating to issues that have been called or matured. Do NOT report the entire market value of the associated securities or the outstanding principal of associated debt issues. Include accounts for which the institution is trustee for corporate securities, tax-exempt and other municipal securities, and other debt securities including unit investment trusts. Also include accounts for which the institution is dividend or interest paying agent, and any other type of corporate trustee or agent appointment. Accounts that are solely custodial or safekeeping should be reported in Schedule RC-T, item 10.
- Investment management agency accounts. Report the market value and number of accounts for all individual and institutional investment management agency accounts that are administered within the fiduciary area of the institution. Investment management agencies are those agency accounts in which the institution has investment discretion; however, title to the assets remain with the client. Include accounts in which the institution serves as a subadvisor. Exclude investment management agency accounts that are administered in bank subsidiaries that are SEC registered investment advisors. Include those mutual funds that are advised by the fiduciary area that is a separately identifiable department or division (as defined in section 217 of the Gramm-Leach-Billey Act). Classes of the same mutual fund should be combined and reported as a single account.
- **Other fiduciary accounts.** Report the market value and number of accounts for all other trusts and agencies not reported in Schedule RC-T, items 4 through 7. Custody and safekeeping accounts should be reported in Schedule RC-T, item 10.
- **9 Total fiduciary accounts.** Report the sum of items 4 through 8.

Custody and safekeeping accounts. Report the market value and the number of accounts for all personal and institutional custody and safekeeping accounts held by the institution. Safekeeping and custody accounts are a type of agency account in which the reporting institution performs one or more specified agency functions but the institution is not a trustee and also is not responsible for managing the asset selection for account assets. These agency services may include holding assets, processing income and redemptions, and other recordkeeping and customer reporting services. For employee benefit custody or safekeeping accounts, the number of accounts reported should reflect the total number of plans administered rather than the number of plan participants. Include accounts in which the institution serves in a sub-custodian capacity. For example, where one institution contracts with another for custody services, both institutions should report the accounts in their respective capacity.

Accounts in which the institution serves as trustee or in an agency capacity in addition to being custodian should be reported in the category of the primary relationship. For example, personal trust accounts in which the institution also serves as custodian should be reported as personal trust accounts and not as custodian accounts. An institution should report an account only once in Schedule RC-T, items 4 through 8 and 10.

Report custodian accounts that are incidental to fiduciary services. Include those custody and safekeeping accounts that are administered by the trust department, and those that are administered in other areas of the institution through an identifiable business unit that focuses on offering fiduciary related custodial services to institutional clients. Exclude those custodial and escrow activities related to commercial bank services such as retail and institutional brokerage assets, securities safekeeping services for correspondent banks, escrow assets held for the benefit of third parties, safety deposit box assets, and any other similar commercial arrangement.

NOTE: Item 11 is applicable only to banks filing the FFIEC 031 report form.

11 <u>Fiduciary accounts held in foreign offices.</u> Report the dollar amount and number of accounts included in Schedule RC-T, items 9 and 10, above that are attributable to accounts held in foreign offices.

Fiduciary and Related Services Income

The following income categories correspond to the fiduciary asset categories described in Schedule RC-T, items 4 through 10, above. For a detailed definition of the categories, please refer to the corresponding account descriptions. Income and expenses should be reported on an accrual basis. Institutions may report income and expense accounts on a cash basis if the results would not materially differ from those obtained using an accrual basis. The information reported in Schedule RC-T, items 12 through 23, on fiduciary and related services income will not be made available to the public on an individual institution basis.

- **Personal trust and agency accounts.** Report gross income generated from personal trust and agency accounts as defined for item 4 of this schedule.
- 13 Retirement related trust and agency accounts:

- **13.a** Employee benefit defined contribution. Report gross income generated from defined contribution employee benefit trust and agency accounts as defined for item 5.a of this schedule.
- **13.b** Employee benefit defined benefit. Report gross income generated from defined benefit employee benefit trust and agency accounts as defined for item 5.b of this schedule.
- **Other retirement accounts.** Report gross income generated from other retirement accounts as defined for item 5.c of this schedule.
- **Corporate trust and agency accounts.** Report gross income generated from corporate trust and agency relationships as defined for item 6 of this schedule.
- **Investment management agency accounts.** Report gross income generated from investment management agency accounts as defined for item 7 of this schedule.
- Other fiduciary accounts. Report gross income generated from other trust and agency accounts as defined for item 8 of this schedule.
- **Custody and safekeeping accounts.** Report gross income generated from custody and safekeeping agency accounts as defined for item 10 of this schedule.
- Other fiduciary and related services income. Report all other gross fiduciary related income that cannot properly be reported in Schedule RC-T, items 12 through item 17, above. Include income received from others (including affiliates) for fiduciary and related services provided by the institution. Also include income received from investment advisory activities when the assets are not held by the institution. Income received from investment advisory services in which the account assets are held in a custody or safekeeping account at the reporting institution should be reported in item 17 of this schedule. Also include net income generated from securities lending activities (i.e., after broker rebates and income paid to lending accounts). Include income from custodial activities for land trusts and mortgage-backed securities. Exclude allocations of income to the trust department from other areas of the institution such as credits for fiduciary cash held as a deposit in the commercial bank.
- **Total gross fiduciary and related services income.** Report the sum of items 12 through 18. This item must equal Schedule RI, item 5.a, "Income from fiduciary activities."

NOTE: Item 19.a is applicable only to banks filing the FFIEC 031 report form.

- **19.a** Fiduciary and related services income -- foreign offices. Report the total amount of fiduciary and related services income included in Schedule RC-T, item 19, above that is attributable to fiduciary accounts held in foreign offices.
- Less: Expenses. Report total direct and indirect expenses attributable to the fiduciary and related services reported in this schedule. Include salaries, wages, bonuses, incentive pay, and employee benefits for employees assigned to reportable activities. If only a portion of their time is allocated to reportable activities, report that proportional share of their salaries and employee benefits. Include direct expenses related to the use of premises, furniture, fixtures and equipment, as well as depreciation/amortization, ordinary repairs and maintenance, service or maintenance contracts, utilities, lease or rental payments, insurance coverage, and real estate and other property taxes if they are directly chargeable to the

reportable activities. Income taxes attributable to reportable activity earnings should not be included. Also exclude settlements, surcharges, and other losses, which are to be reported in Schedule RC-T, item 21.

Include indirect expenses charged to the department or function offering reportable activities by other departments or functions of the institution as reflected in the institution's internal management accounting system. Include proportional shares of corporate expenses that cannot be directly charged to particular departments or functions. Examples of indirect expenses include such items as audit and examination fees, marketing, charitable contributions, customer parking, holding company overhead, proportional share of building rent or depreciation, utilities, real estate taxes, insurance, human resources, corporate planning, and corporate financial staff. Reporting methods for indirect expenses should remain consistent from period to period.

- Less: Net losses from fiduciary and related services. Report net losses resulting from fiduciary and related services. Net losses are gross losses less recoveries. Gross losses include settlements, surcharges, and other losses that are realized in the reporting period attributable to the fiduciary and related services. Recoveries should include those that are attributable to prior and current period losses. This item must equal Schedule RC-T, Memorandum item 4.e, sum of columns A and B minus column C. For further information, see the instruction to Schedule RC-T, Memorandum item 4.
- Plus: Intracompany income credits for fiduciary and related services. If applicable to the reporting institution, report credits from other areas of the institution for activities reportable in this schedule. Include intracompany income credit made available to the fiduciary area for fiduciary account holdings of own-bank deposits. Also include credits for other intracompany services and transactions.
- Net fiduciary and related services income. Report the total from item 19 less the amount reported in item 20 and item 21 plus the amount reported in item 22.

Memoranda

Item No. Caption and Instructions

Managed assets held in personal trust and agency accounts. Report in Memorandum items 1.a. through 1.k. the market value of managed assets held in the Personal Trust and Agency Accounts included in Schedule RC-T, item 4, column A. Assets of common trust funds and collective investment funds should be reported in Memorandum items 1.a through 1.k, as appropriate, regardless of whether participating accounts are managed or non-managed because the institution exercises investment discretion over the fund assets. However, to avoid duplication, the value of units of participation in collective investment funds should not be reported as assets of participating account. Where several institutions in the same affiliated group participate accounts in a collective investment fund maintained by one member of the affiliated group, each participating institution should report its proportionate share of the assets in the appropriate item. To compute the proportionate share of assets, multiply the total market value of the various assets groupings in the collective investment fund by the percentage of units of participation held to total units outstanding.

Securities held in fiduciary accounts that are "loaned" in securities lending transactions (that are accounted for as secured borrowings) should be reported as an asset of the fiduciary account that "loaned" the securities, but the "collateral" received should not also be reported as an asset of this fiduciary account.

Memoranda

Item No. Caption and Instructions

- **1.a Noninterest-bearing deposits.** Report all noninterest-bearing deposits. Report noninterest-bearing deposits of both principal and income cash.
- **1.b** Interest-bearing deposits. Report all interest-bearing savings and time deposits. Include NOW accounts, MMDA accounts, "BICs" (bank investment contracts) which are insured by the FDIC, and certificates of deposit. Report interest-bearing deposits of both principal and income cash.
- 1.c U.S. Government and U.S. Government agency obligations. Report all securities of and/or loans to the U.S. Government and U.S. Government corporations and agencies. Include certificates or other obligations, however named, that represent pass-through participations in pools of real estate loans when the participation instruments: (1) are issued by FHA approved mortgagees and guaranteed by the Government National Mortgage Association, or (2) are issued, insured, or guaranteed by a U.S. Government agency or corporation (e.g., the Federal Home Loan Mortgage Corporation's Mortgage Participation Certificates). Collateralized mortgage obligations (CMOs) and real estate mortgage investment conduits (REMICs) issued by the Federal National Mortgage Association (FNMA) ("Fannie Mae") and the Federal Home Loan Mortgage Corporation (FHLMC) ("Freddie Mac") should be included.
- 1.d State, county, and municipal obligations. Report all short and long-term obligations of state and local governments, and political subdivisions of the United States. Include obligations of U.S. territories and insular possessions and their political subdivisions and all Federal income tax exempt obligations of authorities such as local housing and industrial development authorities that derive their tax-exempt status from relationships with State or local governments. Tax-exempt money market mutual funds should be reported with money market mutual fund in Schedule RC-T, Memorandum item 1.e.
- **Money market mutual funds.** Report all holdings of open-end registered investment companies mutual funds which attempt to maintain net asset values at \$1.00 per share. Include taxable and tax-exempt money market mutual funds. Exclude short-term collective investment funds.
- 1.f Other short-term obligations. Report all short-term obligations (i.e., original maturities of less than 1 year, or 13 months in the case of the time portion of master notes). In addition to short-term notes, this would include such money market instruments as master note arrangements, commercial paper, bankers acceptances, securities repurchase agreements, and other short-term liquidity investments. Exclude state, county, and municipal obligations.
- Other notes and bonds. Report all other bonds, notes (except personal notes), and debentures. Include corporate debt, insurance annuity contracts, "GICs" (guaranteed investment contracts), "BICs" (bank investment contracts) which are not insured by the FDIC, and obligations of foreign governments. Also include certificates or other obligations, however named, representing pass-through participations in pools of real estate loans when the participation instruments are issued by financial institutions and guaranteed in whole or in part by private guarantors. Collateralized mortgage obligations (CMOs) and real estate mortgage investment conduits (REMICs) which are not issued by the Federal National Mortgage Association (FNMA) ("Fannie Mae") and the Federal Home Loan Mortgage Corporation (FHLMC) ("Freddie Mac") should be reported here, even if the collateral consists of GNMA ("Ginnie Mae") or FNMA pass-throughs or FHLMC participation certificates. Exclude short- term obligations which should be reported in Schedule RC-T, Memorandum item 1.f, above.

Memoranda

- 1.h Common and preferred stocks. Report all holdings of domestic and foreign common and preferred equities, including warrants and options. Include holdings of all mutual funds (openend and closed-end) except money market funds which are reported in Schedule RC-T, Memorandum item 1.e, above. Also include all unit investment trusts, regardless of the securities they are invested in (e.g., stocks, corporate bonds, and municipal bonds). Include ownership interests in private equity investments, limited liability companies, and any other pooled investment vehicle except those that are primarily invested in real estate which should be included in Schedule RC-T, Memorandum item 1.j.
- **1.i** Real estate mortgages. Report real estate mortgages, real estate contracts, land trust certificates, and ground rents. These assets may be reported at unpaid balance if that figure is a fair approximation of market value.
- **Real estate.** Report real estate, mineral interests, royalty interests, leaseholds, and other similar assets. Land and buildings associated with farm management accounts should be reported in this Item. Investments in limited partnerships that are solely or primarily invested in real estate should also be reported here.
- 1.k <u>Miscellaneous assets.</u> Report personal notes, tangible personal property, and other miscellaneous assets that cannot properly be reported in Schedule RC-T, Memorandum items 1.a through 1.j, above. Crops, equipment and livestock associated with farm management accounts should be reported in this item.
- **1.I Total managed assets held in personal trust and agency accounts.** Report the sum of Memorandum items 1.a. through 1.k. This item must equal Schedule RC-T, item 4, Column A.
- 2 Corporate trust and agency accounts:
- 2.a Corporate and municipal trusteeships. Report in column A the total number of corporate and municipal issues, as well as other debt issues such as unit investment trusts, for which the institution serves as trustee. If more than one institution is trustee for an issue, each institution should report the issue. Securities with different CUSIP numbers should be considered separate issues; however, serial bond issues should be considered as a single issue. When an institution serves as trustee of a bond issue, it may also perform agency functions for the issue such as registrar (transfer agent) or interest and principal paying agent. In those cases, report the issue only in Memorandum item 2.a, "Corporate and Municipal Trusteeships," as the trustee appointment is considered the primary function. Consider the primary function of the appointment when selecting the item in which to report the appointment. Exclude issues that have been called in their entirety or have matured even if there are unpresented bonds or coupons for which funds are being held.

Report in column B the total par value of outstanding debt securities for the issues reported in column A for which the institution serves as trustee. For zero-coupon bonds, report the final maturity amount. Exclude assets (i.e., cash, deposits, and investments) that are being held for corporate trust purposes; they should be reported in Schedule RC-T, item 6, above.

Memoranda

- Transfer agent, registrar, paying agent, and other corporate agency. Report in column A the total number of issues for which the institution acts in a corporate agency capacity. Include the total number of equity, debt, and mutual fund issues for which the institution acts as transfer agent or registrar. Separate classes of a mutual fund should be consolidated and reflected as a single issue. Include the total number of stock or bond issues for which the institution disburses dividend or interest payments. Also include the total number of issues of any other corporate appointments that are performed by the institution through its fiduciary capacity. Issues for which the institution serves in a dual capacity should be reported once. Corporate and Municipal Trusteeships reported in Schedule RC-T, Memorandum item 2.a, above in which the institution also serves as transfer agent, registrar, paying agent, or other corporate agency capacity should not be included in Memorandum item 2.b. Include only those agency appointments that do not relate to issues reported in Schedule RC-T, Memorandum item 2.a, above.
- Collective investment funds and common trust funds. Report the number and market value of the assets held in Collective Investment Funds (CIFs) and Common Trust Funds operated by the reporting institution. If an institution operates a CIF that is used by more than one institution, the entire CIF should be reported in this section only by the institution which operates the CIF. Exclude mutual funds from this section. Each CIF should be categorized in the one item that best fits the fund type.
- 3.a <u>Domestic equity.</u> Report funds investing primarily in U.S. equities. Include those seeking growth, income, growth and income, U.S. index funds and those concentrating on small, mid, or large cap domestic stocks. Exclude funds specializing in a particular sector (e.g., technology, health care, financial, and real estate), which should be reported in Schedule RC-T, Memorandum item 3.g, "Specialty/Other."
- **3.b** International/Global equity. Report funds investing exclusively in equities of issuers located outside the U.S. and those funds representing a combination of U.S. and foreign issuers. Include funds that specialize in a particular country, region, or emerging market.
- **Stock/Bond blend.** Report funds investing in a combination of equity and bond investments. Include funds with a fixed allocation along with those having the flexibility to shift assets between stocks, bonds, and cash.
- Taxable bond. Report funds investing in taxable debt securities. Include funds that specialize in U.S. Treasury and U.S. Government agency debt, investment grade corporate bonds, high-yield debt securities, mortgage-related securities, and global, international, and emerging market debt funds. Exclude funds that invest in municipal bonds, which should be reported in Schedule RC-T, Memorandum item 3.e, and funds that qualify as short-term investments, which should be reported in Schedule RC-T, Memorandum item 3.f.
- **Municipal bond.** Report funds investing in debt securities issued by states and political subdivisions in the U.S. Such securities may be taxable or tax-exempt.. Include funds that invest in municipal debt issues from a single state. Exclude funds that qualify as short-term investments, which should be reported in Schedule RC-T, Memorandum item 3.f.

Memoranda

Item No. Caption and Instructions

- 3.f Short term investments/Money market. Report funds that invest in short-term money market instruments with an average portfolio maturity that is limited to 90 days with individual securities limited to maturities of 13 months or less. Money market instruments may include U.S. Treasury bills, commercial paper, bankers acceptances, and repurchase agreements. Include taxable and nontaxable funds.
- **Specialty/Other.** Include funds that specialize in equity securities of particular sectors (e.g., technology, health care, financial, and real estate). Also include funds that do not fit into any of the above categories.
- **3.h** Total collective investment funds. Report the sum of Memorandum items 3.a. through 3.g.
- Fiduciary settlements, surcharges, and other losses. Report aggregate gross settlements, surcharges, and other losses arising from errors, misfeasance, or malfeasance on managed accounts in column A and on non-managed accounts in column B. For the definitions of managed and non-managed accounts, refer to the instructions for the Fiduciary and Related Assets section of this schedule. Gross losses should reflect losses recognized on an accrual basis before recoveries or insurance payments. Exclude contingent liabilities for fiduciary-related loss contingencies, including pending or threatened litigation, for which a loss has not yet been recognized in accordance with FASB Statement No. 5.

Report recoveries in column C. Recoveries may be for current or prior years' losses and should be reported when payment is actually realized. The filing of an insurance claim does not serve as support for a recovery.

The information reported in all of Schedule RC-T, Memorandum item 4, on fiduciary settlements, surcharges, and other losses will not be made available to the public on an individual institution basis.

- **4.a** Personal trust and agency accounts. Report gross losses and recoveries for personal trust and agency accounts as defined for item 4 of this schedule.
- **4.b** Retirement related trusts and agency accounts. Report gross losses and recoveries for retirement related trust or agency accounts as defined for item 5 of this schedule.
- **4.c** <u>Investment management agency accounts.</u> Report gross losses and recoveries for investment management agency accounts as defined for item 7 of this schedule.
- 4.d Other fiduciary accounts and related services. Report gross losses and recoveries for all other fiduciary accounts and related services that are not included in Schedule RC-T, Memorandum items 4.a, 4.b, and 4.c, above. Include losses and recoveries from corporate trust or agency accounts, other fiduciary accounts, custody or safekeeping accounts, and other fiduciary related services.
- **Total fiduciary settlements, surcharges, and other losses.** Report the sum of Memorandum items 4.a through 4.d. The sum of columns A and B minus column C must equal Schedule RC-T, item 21, above.

FFIEC 031 and 041 NARRATIVE

OPTIONAL NARRATIVE STATEMENT CONCERNING THE AMOUNTS REPORTED IN THE REPORTS OF CONDITION AND INCOME

The management of the reporting bank may, if it wishes, submit a brief narrative statement on the amounts reported in the Reports of Condition and Income. This optional statement will be made available to the public, along with the publicly available data in the Reports of Condition and Income, in response to any request for individual bank report data. However, the information reported in Schedule RC-T, items 12 through 23 and Memorandum item 4, is regarded as confidential and will not be released to the public. BANKS CHOOSING TO SUBMIT THE NARRATIVE STATEMENT SHOULD ENSURE THAT THE STATEMENT DOES NOT CONTAIN THE NAMES OR OTHER IDENTIFICATIONS OF INDIVIDUAL BANK CUSTOMERS, REFERENCES TO THE AMOUNTS REPORTED IN THE CONFIDENTIAL ITEMS IN SCHEDULE RC-T, OR ANY OTHER INFORMATION THAT THEY ARE NOT WILLING TO HAVE MADE PUBLIC OR THAT WOULD COMPROMISE THE PRIVACY OF THEIR CUSTOMERS. Banks choosing not to make a statement may check the "No comment" box and should make no entries of any kind in the space provided for the narrative statement; i.e., DO NOT enter in this space such phrases as "No statement," "Not applicable," "N/A," "No comment," and "None."

The optional statement must be entered on the sheet provided by the agencies. The statement should not exceed 100 words. Further, regardless of the number of words, the statement must not exceed 750 characters, including punctuation, indentation, and standard spacing between words and sentences. If any submission should exceed 750 characters, as defined, it will be truncated at 750 characters with no notice to the submitting bank and the truncated statement will appear as the bank's statement both on agency computerized records and in computer-file releases to the public.

All information furnished by the bank in the narrative statement must be accurate and not misleading. Appropriate efforts shall be taken by the submitting bank to ensure the statement's accuracy. The statement must be signed, in the space provided, by a senior officer of the bank who thereby attests to its accuracy.

If, subsequent to the original submission, <u>material</u> changes are submitted for the data reported in the Reports of Condition and Income, the existing narrative statement will be deleted from the files, and from disclosure; the bank, at its option, may replace it with a statement, under signature, appropriate to the amended data.

The optional narrative statement will appear in agency records and in release to the public exactly as submitted (or amended as described in the preceding paragraph) by the management of the bank (except for the truncation of statements exceeding the 750-character limit described above). THE STATEMENT WILL NOT BE EDITED OR SCREENED IN ANY WAY BY THE SUPERVISORY AGENCIES FOR ACCURACY OR RELEVANCE. DISCLOSURE OF THE STATEMENT SHALL NOT SIGNIFY THAT ANY FEDERAL SUPERVISORY AGENCY HAS VERIFIED OR CONFIRMED THE ACCURACY OF THE INFORMATION CONTAINED THEREIN. A STATEMENT TO THIS EFFECT WILL APPEAR ON ANY PUBLIC RELEASE OF THE OPTIONAL STATEMENT SUBMITTED BY THE MANAGEMENT OF THE REPORTING BANK.

GLOSSARY

The definitions in this Glossary apply to the Reports of Condition and Income and are not necessarily applicable for other regulatory or legal purposes. Similarly, the accounting discussions in this Glossary are those relevant to the preparation of these reports and are not intended to constitute a comprehensive presentation on bank accounting.

Acceptances: See "bankers acceptances."

Accounting Changes: Changes in accounting principles -- The accounting principles that banks have adopted for the preparation of their Reports of Condition and Income should be changed only in the direction of more preferable accounting practices. If a bank changes from the use of one acceptable accounting principle to one that is more preferable at any time during the calendar year, it must report the income or expense item(s) affected by the change for the entire year on the basis of the newly adopted accounting principle regardless of the date when the change is actually made. However, a change from an accounting principle that is neither accepted nor sanctioned by bank supervisors to one that is acceptable to supervisors is to be reported as a correction of an error as discussed below.

New accounting standards that are adopted by the Financial Accounting Standards Board (or such other body officially designated to establish accounting principles) may apply retroactively and may require or allow a bank to restate prior years' financial statements prepared in accordance with generally accepted accounting principles. Because each Report of Income covers a single discrete period, retroactive restatement of prior years' Reports of Condition and Income is not permitted. However, the effects of restatement should be reported in the Reports of Condition and Income in a manner consistent with a bank's financial statements for the same reporting period prepared in accordance with generally accepted accounting principles. Therefore, if restatement of prior periods is required (or if the bank elects to restate prior periods if restatement is allowed but not required), the effect on the amount of retained earnings at the beginning of the year in which the new standard is first adopted for purposes of the Reports of Condition and Income (net of applicable income taxes, if any) is to be excluded from net income and reported as a direct adjustment to equity capital in Schedule RI-A, item 2, and detailed in Schedule RI-E, item 4.

If a new standard must be applied retroactively but restatement of prior years' financial statements is not allowed (or if the bank elects not to restate prior periods if restatement is allowed but not required), the effect of the retroactive application on retained earnings at the beginning of the year in which the new standard is first adopted for purposes of the Reports of Condition and Income is to be included in net income like the cumulative effect of a change in accounting principle as described above. The amount of this effect (net of applicable income taxes, if any) is to be reported in Schedule RI, item 11, and detailed in Schedule RI-E, item 3.

<u>Changes in accounting estimates</u> -- Accounting and the preparation of financial statements involve the use of estimates. As more current information becomes known, estimates may be changed. In particular, accruals are derived from estimates based on judgments about the outcome of future events and changes in these estimates are an inherent part of accrual accounting.

Reasonable changes in accounting estimates do <u>not</u> require the restatement of amounts of income and expenses and assets, liabilities, and capital reported in previously submitted Reports of Condition and Income. Computation of the cumulative effect of these changes is also not ordinarily necessary. Rather, the effect of such changes is handled on a prospective basis. That is, beginning in the period when an accounting estimate is revised, the related item of income or expense for that period is adjusted accordingly. For example, if the bank's estimate of the remaining useful life of certain bank equipment is increased, the remaining undepreciated cost of the equipment would be spread over its

Accounting Changes (cont.):

revised remaining useful life. Similarly, immaterial accrual adjustments to items of income and expenses, including provisions for loan and lease losses and income taxes, are considered changes in accounting estimates and would be taken into account by adjusting the affected income and expense accounts for the year in which the adjustments were found to be appropriate.

However, large and unusual changes in accounting estimates <u>may</u> be more properly treated as constituting accounting errors, and if so, <u>must</u> be reported accordingly as described below.

Corrections of accounting errors -- A bank may become aware of an error in a Report of Condition or Report of Income after it has been submitted to the appropriate federal bank regulatory agency through either its own or its regulator's discovery of the error. An error in a report for a prior period may result from:

- (1) a mathematical mistake;
- (2) a mistake in applying accounting principles; or
- (3) the improper use of information that existed when the Reports of Condition and Income for prior periods were prepared.

When a bank's primary federal bank regulatory agency determines that the bank's Reports of Condition and Income contain a <u>material</u> accounting error, the bank <u>may</u> be directed to file amended condition and/or income report data for each prior period that was significantly affected by the error. Normally, such refilings will not be retroactively required for a period exceeding five years. If amended reports are not required, the bank should report the effect of such corrections on retained earnings at the beginning of the year, net of applicable income taxes, in Schedule RI-A, item 2, "Restatements due to corrections of material accounting errors and changes in accounting principles," and in Schedule RI-E, item 4. The effect of such corrections on income and expenses since the beginning of the year in which the error is discovered should be reflected in each affected income and expense account on a year-to-date basis in the next quarterly Report of Income to be filed and <u>not</u> as a direct adjustment to retained earnings.

In addition, a change from an accounting principle that is neither accepted nor sanctioned by bank supervisors to one that is acceptable to supervisors is to be reported as a correction of an error. When such a change is implemented, the cumulative effect that applies to prior periods, calculated in the same manner as described above for other changes in accounting principles, should be reported in Schedule RI-A, item 2, "Restatements due to corrections of material accounting errors and changes in accounting principles," and in Schedule RI-E, item 4. In most cases of this kind undertaken voluntarily by the reporting bank in order to adopt more acceptable accounting practices, such a change will not result in a request for amended reports for prior periods unless substantial distortions in the bank's previously reported results are in evidence.

For further information on these three topics, see APB Opinion No. 20, "Accounting Changes," as amended.

Accounting Errors, Corrections of: See "accounting changes."

Accounting Estimates, Changes in: See "accounting changes."

Accounting Principles, Changes in: See "accounting changes."

Acquisition, Development, or Construction (ADC) Arrangements: An ADC arrangement is an arrangement in which a bank provides financing for real estate acquisition, development, or construction purposes and participates in the expected residual profit resulting from the ultimate sale or other use of the property. ADC arrangements should be reported as loans, real estate joint ventures, or direct investments in real estate in accordance with guidance presented by the American Institute of Certified Public Accountants in a Notice to Practitioners issued in February 1986 (or, if appropriate, in notices issued in November 1983 and November 1984).

12 USC 29 limits the authority of national banks to hold real estate. National banks should review real estate ADC arrangements carefully for compliance. State member banks are not authorized to invest in real estate except with the prior approval of the Federal Reserve Board under Federal Reserve Regulation H (12 CFR Part 208).

Agreement Corporation: See "Edge and Agreement corporation."

Allowance for Loan and Lease Losses: Each bank must maintain an allowance for loan and lease losses (allowance) that is adequate to absorb estimated credit losses associated with its loan and lease portfolio, i.e., loans and leases that the bank has intent and ability to hold for the foreseeable future or until maturity or payoff. Each bank should also maintain, as a separate liability account, an allowance sufficient to absorb estimated credit losses associated with off-balance sheet credit instruments such as standby letters of credit. This separate allowance should be reported in Schedule RC-G, item 3, "Allowance for credit losses on off-balance sheet credit exposures."

With respect to the loan and lease portfolio, the term "estimated credit losses" means an estimate of the current amount of loans and leases that is not likely to be collected; that is, net charge-offs that are likely to be realized for a loan or pool of loans given facts and circumstances as of the evaluation date. These estimated credit losses should meet the criteria for accrual of a loss contingency (i.e., a provision to the allowance) set forth in generally accepted accounting principles (GAAP).

As of the end of each quarter, or more frequently if warranted, the management of each bank must evaluate, subject to examiner review, the collectibility of the loan and lease portfolio, including any recorded accrued and unpaid interest (i.e., not already reversed or charged off), and make appropriate entries to maintain the balance of the allowance for loan and lease losses on the balance sheet at a level adequate to absorb estimated credit losses. Management must maintain reasonable records in support of their evaluations and entries.

Additions to, or reductions of, the allowance account resulting from such evaluations are to be made through charges or credits to the "provision for loan and lease losses" (provision) in the Report of Income. When available information confirms that specific loans and leases, or portions thereof, are uncollectible, these amounts should be promptly charged off against the allowance. All charge-offs of loans and leases shall be charged directly to the allowance and any recoveries on loans or leases previously charged off shall be credited to the allowance. Under no circumstances can loan or lease losses be charged directly to "Retained earnings."

When a bank makes a full or partial direct write-down of a loan or lease that is uncollectible, the bank establishes a new cost basis for the asset. Consequently, once a new cost basis has been established for a loan or lease through a direct write-down, this cost basis may not be "written up" at a later date. Reversing the previous write-down and "re-booking" the charged-off asset after the bank concludes that the prospects for recovering the charge-off have improved, regardless of whether the bank assigns a new account number to the asset or the borrower signs a new note, is not an acceptable accounting practice.

Allowance for Loan and Lease Losses (cont.):

The allowance account must <u>never</u> have a debit balance. If losses charged off exceed the amount of the allowance, a provision sufficient to restore the allowance to an adequate level <u>must</u> be charged to expense on the income statement <u>immediately</u>. A bank shall <u>not</u> increase the allowance account by transferring an amount from undivided profits or any segregation thereof to the allowance for loan and lease losses.

To the extent that a bank's reserve for bad debts for tax purposes is greater than or less than its "allowance for loan and lease losses" on the balance sheet of the Report of Condition, the difference is referred to as a temporary difference. See the Glossary entry for "income taxes" for guidance on how to report the tax effect of such a temporary difference.

Recourse liability accounts that arise from recourse obligations for any transfers of loans that are reported as sales for purposes of these reports should <u>not</u> be included in the allowance for loan and lease losses. These accounts are considered separate and distinct from the allowance account and from the allowance for credit losses on off-balance sheet credit exposures. Recourse liability accounts should be reported in Schedule RC-G, item 4, "Other" liabilities.

For comprehensive guidance on the maintenance of an adequate allowance for loan and lease losses, banks should refer to the Interagency Policy Statement on the Allowance for Loan and Lease Losses dated December 21, 1993. National banks should also refer to the Office of the Comptroller of the Currency's Handbook for National Bank Examiners discussing the allowance for loan and lease losses. Information on the application of FASB Statement No. 114, "Accounting by Creditors for Impairment of a Loan," to the determination of an allowance for loan and losses on those loans covered by that accounting standard is provided in the Glossary entry for "loan impairment."

For information on reporting on foreclosed and repossessed assets, <u>see</u> the Glossary entry for "foreclosed assets."

Applicable Income Taxes: See "income taxes."

Associated Company: See "subsidiaries."

ATS Account: See "deposits."

Bankers Acceptances: A banker's acceptance, for purposes of these reports, is a draft or bill of exchange that has been drawn on and accepted by a banking institution (the "accepting bank") or its agent for payment by that institution at a future date that is specified in the instrument. Funds are advanced to the drawer of the acceptance by the discounting of the accepted draft either by the accepting bank or by others; the accepted draft is negotiable and may be sold and resold subsequent to its original discounting. At the maturity date specified, the holder or owner of the acceptance at that date, who has advanced funds either by initial discount or subsequent purchase, presents the accepted draft to the accepting bank for payment.

The accepting bank has an unconditional obligation to put the holder in funds (to pay the holder the face amount of the draft) on presentation on the specified date. The account party (customer) has an unconditional obligation to put the accepting bank in funds at or before the maturity date specified in the instrument.

Bankers Acceptances (cont.):

The following description covers the treatment in the Report of Condition of (1) acceptances that have been executed by the reporting bank, that is, those drafts that have been drawn on and accepted by it; (2) "participations" in acceptances, that is, "participations" in the accepting bank's obligation to put the holder of the acceptance in funds at maturity, or participations in the accepting bank's risk of loss in the event of default by the account party; and (3) acceptances owned by the reporting bank, that is, those acceptances -- whether executed by the reporting bank or by others -- that the bank has discounted or purchased.

(1) Acceptances executed by the reporting bank -- With the exceptions described below, the accepting bank <u>must</u> report on its balance sheet the <u>full</u> amount of the acceptance in both (1) the liability item, "Bank's liability on acceptances executed and outstanding" (Schedule RC, item 18), reflecting the accepting bank's obligation to put the holder of the acceptance in funds at maturity, and (2) the asset item, "Customers' liability to this bank on acceptances outstanding" (Schedule RC, item 9), reflecting the account party's liability to put the accepting bank in funds at or before maturity.

Exceptions to the mandatory reporting by the accepting bank of the <u>full</u> amount of all outstanding drafts accepted by the reporting bank in both Liability Item 18 and Asset Item 9 on the balance sheet of the Consolidated Report of Condition occur in the following situations:

- (a) One exception occurs in situations where the accepting bank acquires -- through initial discounting or subsequent purchase -- and holds its own acceptance (i.e., a draft that it has itself accepted). In this case, the reporting bank's own acceptances that are held by it should not be reported in the acceptance liability and asset items noted above (i.e., "Bank's liability on acceptances executed and outstanding" and "Customers' liability to this bank on acceptances outstanding"). The bank's holdings of its own acceptances should be reported in "Loans and leases held for sale" (Schedule RC, item 4.a), "Loans and leases, net of unearned income" (Schedule RC, item 4.b), or "Trading assets" (Schedule RC, item 5), as appropriate.
- (b) Another exception occurs in situations where the account party anticipates its liability to the reporting bank on an acceptance outstanding by making a payment to the bank that reduces the customer's liability in advance of the maturity of the acceptance. In this case, the reporting bank should decrease the asset item "Customers' liability to this bank on acceptances outstanding" (Schedule RC, item 9) by the amount of such prepayment; the prepayment will not affect the liability item "Bank's liability on acceptances executed and outstanding" (Schedule RC, item 18), which would continue to reflect the full amount of the acceptance until the bank has repaid the holder of the acceptance at the maturity date specified in the instrument. If the account party's payment to the accepting bank before the maturity date is <u>not</u> for the purpose of immediate reduction of its indebtedness to the reporting bank or if receipt of the payment does not immediately reduce or extinguish that indebtedness, such advance payment will not reduce item 9 of Schedule RC but should be reflected in the bank's deposit liabilities.

In all situations other than these two exceptions just described, the accepting bank must report the <u>full</u> amount of its acceptances in its liability item, "Bank's liability on acceptances executed and outstanding," and in its asset item, "Customers' liability to this bank on acceptances outstanding." There are <u>no</u> other circumstances in which the accepting bank can report as a balance sheet liability anything less than the <u>full</u> amount of the obligation to put the holder of the acceptance in funds at maturity. Moreover, there are <u>no</u> circumstances in which the reporting bank can net its acceptance assets against its acceptance liabilities.

Bankers Acceptances (cont.):

NOTE: The amount of a reporting member (both national and state) bank's acceptances that are subject to statutory limitations on eligible acceptances as set forth in federal statute 12 USC 372 and in Federal Reserve regulation 12 CFR Part 250 may differ from the required reporting of acceptances on the balance sheet of the Consolidated Report of Condition, as described above. These differences are mainly attributable to ineligible acceptances, to participations in the reporting bank's acceptances conveyed to others, to participations acquired by the reporting bank in other banks' acceptances, and to the effect of the consolidation of subsidiaries in the Report of Condition.

(2) "Participations" in acceptances -- The general requirement for the accepting bank to report on its balance sheet the <u>full</u> amount of the total obligation to put the <u>holder</u> of the acceptance in funds applies also, in particular, to any situation in which the accepting bank enters into any kind of arrangement with others for the purpose of having the latter share, or participate, in the obligation to put the holder of the acceptance in funds at maturity or in the risk of loss in the event of default on the part of the account party. In <u>any</u> such sharing arrangement or participation agreement -- regardless of its form or its contract provisions, regardless of the terminology (e.g., "funded," "risk," "unconditional," or "contingent") used to describe it and the relationships under it, regardless of whether it is described as a participation in the customer's liability or in the accepting bank's obligation or in the risk of default by the account party, and regardless of the system of debits and credits used by the accepting bank to reflect the participation arrangement -- the existence of the participation or other agreement does <u>not</u> reduce the accepting bank's obligation to honor the full amount of the acceptance at maturity nor change the requirement for the accepting bank to report the full amount of the acceptance in the liability and asset items described above.

The existence of such participations is <u>not</u> to be recorded on the <u>balance sheet</u> (Schedule RC) of the accepting bank that conveys shares in its obligation to put the holder of the acceptance in funds or shares in its risk of loss in the event of default on the part of the account party, and similarly is <u>not</u> to be recorded on the <u>balance sheets</u> (Schedule RC) of the other banks that are party to, or acquire, such participations. However, in such cases of agreements to participate, the accepting bank engaging in the participation agreement will report the participation in Schedule RC-L, item 5, "Participations in acceptances conveyed to others by the reporting bank," if it has foreign offices or \$100 million or more in total assets. The nonaccepting bank acquiring the participation will report the participation in Schedule RC-R, item 47, "Risk participations in bankers acceptances acquired by the reporting institution." This same reporting treatment applies to a bank that acquires a participation in an acceptance of another (accepting) bank and subsequently conveys the participation to others and to a bank that acquires such a participation. Moreover, the bank that both acquires and conveys a participation in another bank's acceptance must report the amounts of the participations in both acceptance participation items in Schedule RC-L and Schedule RC-R.

NOTE: The amount of participations in acceptances reported in Schedule RC-L by a member bank may differ from the amount of such participations that enter into the calculation of the bank's acceptances to be counted toward its acceptance limit under federal statute 12 USC 372 and Federal Reserve regulation 12 CFR Part 250. Such differences are mainly attributable to participations in ineligible acceptances, to participations with "noncovered" institutions, and to participations that do not conform to the minimum requirements set forth in 12 CFR Part 250.

FFIEC 031 and 041 A-6 GLOSSARY (6-01)

¹ This discussion does <u>not</u> deal with participations in <u>holdings</u> of bankers acceptances, which are reportable as loans. Such participations are treated like any participations in loans as described in the Glossary entry for "transfers of financial assets."

Bankers Acceptances (cont.):

(3) Acceptances owned by the reporting bank -- The treatment of acceptances owned or held by the reporting bank (whether acquired by initial discount or subsequent purchase) depends upon whether the acceptances are held for trading, for sale, or in portfolio and upon whether the acceptances held have been accepted by the reporting bank or by other banks.

All acceptances held for trading by the reporting bank (whether acceptances of the reporting bank or of other banks) are to be reported in Schedule RC, item 5, "Trading assets." Banks that must complete Schedule RC-D, Trading Assets and Liabilities, will identify these holdings (in domestic offices) in item 9, "Other trading assets (in domestic offices)." Banks with foreign offices that must complete Schedule RC-D will identify these holdings in foreign offices in item 10, "Trading assets in foreign offices."

The reporting bank's holdings of acceptances other than those held for trading (whether acceptances of the reporting bank or of other banks) are to be reported in Schedule RC, item 4.a, "Loans and leases held for sale," or in item 4.b, "Loans and leases, net of unearned income," as appropriate, and in Schedule RC-C, part I, "Loans and Lease financing receivables."

In Schedule RC-C, part I, the reporting bank's holdings of <u>other</u> banks' acceptances, other than those held for trading, are to be reported in "Loans to depository institutions and acceptances of other banks" (item 2). On the other hand, the bank's holdings of its <u>own</u> acceptances, other than those held for trading, are to be reported in Schedule RC-C, part I, according to the account party of the draft. Thus, holdings of own acceptances for which the account parties are commercial or industrial enterprises are to be reported in Schedule RC-C, part I, in "Commercial and industrial loans" (item 4); holdings of own acceptances for which the account parties are other banks (e.g., in connection with the refinancing of another acceptance or for the financing of dollar exchange) are to be reported in Schedule RC-C, part I, in "Loans to depository institutions and acceptances of other banks" (item 2); and holdings of own acceptances for which the account parties are foreign governments or official institutions (e.g., for the financing of dollar exchange) are to be reported in Schedule RC-C, part I, "Loans to foreign governments and official institutions" (item 7).

The difference in treatment between holdings of own acceptances and holdings of other banks' acceptances reflects the fact that, for other banks' acceptances, the holding bank's immediate claim is on the accepting bank, regardless of the account party or of the purpose of the loan. On the other hand, for its holdings of its own acceptances, the bank's immediate claim is on the account party named in the accepted draft.

If the account party prepays its acceptance liability on an acceptance of the reporting bank that is held by the reporting bank (in the held-for-sale account, in the loan portfolio, or as trading assets) so as to immediately reduce its indebtedness to the reporting bank, the recording of the holding -- in "Commercial and industrial loans," "Loans to depository institutions and acceptances of other banks," or "Trading assets," as appropriate -- is reduced by the prepayment.

Banks, U.S. and Foreign: In the classification of banks as <u>customers</u> of the reporting bank, distinctions are drawn for purposes of the Reports of Condition and Income between "U.S. banks" and "commercial banks in the U.S." and between "foreign banks" and "banks in foreign countries." Some report items call for one set of these categories and other items call for the other set. The distinctions center around the inclusion or exclusion of foreign branches of U.S. banks and U.S. branches and agencies of foreign banks. For purposes of describing the office location of banks as <u>customers</u> of the reporting bank, the term "United States" covers the 50 states of the United States, the District of Columbia, Puerto Rico, and U.S. territories and possessions. (This is in contrast to the usage with respect to the offices of the reporting bank, where offices in Puerto Rico and U.S. territories and possessions and U.S.-domiciled Edge and Agreement subsidiaries and IBFs are included in "foreign" offices.)

Banks, U.S. and Foreign (cont.):

<u>U.S. banks</u> - The term "U.S. banks" covers both the U.S. and foreign branches of banks chartered and headquartered in the U.S. (including U.S.-chartered banks owned by foreigners), but <u>excluding</u> U.S. branches and agencies of foreign banks. On the other hand, the term "banks in the U.S." or "commercial banks in the U.S." (the institutional coverage of which is described in detail later in this entry) covers the U.S. offices of U.S. banks (including their IBFs) and the U.S. branches and agencies of foreign banks, but <u>excludes</u> the foreign branches of U.S. banks.

<u>Foreign banks</u> - Similarly, the term "foreign banks" covers all branches of banks chartered and headquartered in foreign countries (including foreign banks owned by U.S. nationals and institutions), including their U.S.-domiciled branches and agencies, but <u>excluding</u> the foreign branches of U.S. banks. In contrast, the term "banks in foreign countries" covers foreign-domiciled branches of banks, including the foreign branches of U.S. banks, but <u>excluding</u> the U.S. branches and agencies of foreign banks.

The following table summarizes these contrasting categories of banks considered as customers as used in the Reports of Condition and Income ("X" indicates inclusion; no entry indicates exclusion.)

	"Commercial			"Banks in
	"U.S. banks"	banks in the U.S."	"Foreign banks"	foreign countries"
U.S. branches of U.S. banks				
(including IBFs)	Χ	Χ		
Foreign branches				
of U.S. banks	Χ			Χ
Foreign branches				
of foreign banks			Χ	X
U.S. branches and				
agencies of foreign banks		Χ	X	

Commercial banks in the U.S. -- The detailed institutional composition of "commercial banks in the U.S." includes:

- (1) the U.S.-domiciled head offices and branches of:
 - (a) national banks;
 - (b) state-chartered commercial banks;
 - (c) trust companies that perform a commercial banking business;
 - (d) industrial banks;
 - (e) private or unincorporated banks;
 - (f) International Banking Facilities (IBFs) of U.S. banks;
 - (g) Edge and Agreement corporations; and
- (2) the <u>U.S.-domiciled</u> branches and agencies of foreign banks (as defined below).

Banks. U.S. and Foreign (cont.):

This coverage includes the U.S. institutions listed above that are owned by foreigners. Excluded from commercial banks in the U.S. are branches located in foreign countries of U.S. banks.

U.S. savings and loan associations and savings banks are treated as "other depository institutions in the U.S." for purposes of the Reports of Condition and Income.

U.S. branches and agencies of foreign banks -- U.S. branches of foreign banks include any offices or places of business of foreign banks that are located in the United States at which deposits are accepted. U.S. agencies of foreign banks include any offices or places of business of foreign banks that are located in the United States at which credit balances are maintained incidental to or arising out of the exercise of banking powers but at which deposits may not be accepted from citizens or residents of the United States.

For purposes of the Reports of Condition and Income, the term "U.S. branches and agencies of foreign banks" covers:

- (1) the U.S. branches and agencies of foreign banks;
- (2) the U.S. branches and agencies of foreign official banking institutions, including central banks, nationalized banks, and other banking institutions owned by foreign governments; and
- investment companies that are chartered under Article XII of the New York State banking law and that are majority-owned by one or more foreign banks.

Banks in foreign countries - The institutional composition of "banks in foreign countries" includes:

- (1) the foreign-domiciled head offices and branches of:
 - (a) foreign commercial banks (including foreign-domiciled banking subsidiaries of U.S. banks and Edge and Agreement corporations);
 - (b) foreign savings banks or discount houses;
 - (c) nationalized banks not functioning either as central banks, as foreign development banks, or as banks of issue;
 - (d) other similar foreign institutions that accept short-term deposits; and
- (2) the foreign-domiciled branches of U.S. banks.

See also "International Banking Facility (IBF)."

Banks in Foreign Countries: See "banks, U.S. and foreign."

Bill-of-Lading Draft: See "commodity or bill-of-lading draft."

Borrowings and Deposits in Foreign Offices: Borrowings in foreign offices include assets rediscounted with central banks, certain participations sold in loans and securities, government fundings of loans, borrowings from the Export-Import Bank, and rediscounted trade acceptances. Federal funds sold and repurchase agreements in foreign offices should be reported in accordance with the Glossary entries for "federal funds transactions" and "repurchase/resale agreements." Liability accounts such as accruals and allocated capital shall not be reported as borrowings. Deposits consist of such other short-term and long-term liabilities issued or undertaken as a means of obtaining funds to be used in the banking business and include those liabilities generally characterized as placements and takings, call money, and deposit substitutes.

Brokered Deposits: Brokered deposits represent funds which the reporting bank obtains, directly or indirectly, by or through any deposit broker for deposit into one or more deposit accounts. Thus, brokered deposits include both those in which the entire beneficial interest in a given bank deposit account or instrument is held by a single depositor and those in which the deposit broker sells participations in a given bank deposit account or instrument to one or more investors.

<u>Fully insured brokered deposits</u> are brokered deposits that are issued in denominations of \$100,000 or less or that are issued in denominations greater than \$100,000 and participated out by the deposit broker in shares of \$100,000 or less.

For purposes of these reports, the term <u>deposit broker</u> includes:

- (1) any person engaged in the business of placing deposits, or facilitating the placement of deposits, of third parties with insured depository institutions or the business of placing deposits with insured depository institutions for the purpose of selling interests in those deposits to third parties, and
- (2) an agent or trustee who establishes a deposit account to facilitate a business arrangement with an insured depository institution to use the proceeds of the account to fund a prearranged loan.

The term deposit broker does not include:

- (1) an insured depository institution, with respect to funds placed with that depository institution;
- an employee of an insured depository institution, with respect to funds placed with the employing depository institution;
- (3) a trust department of an insured depository institution, if the trust in question has not been established for the primary purpose of placing funds with insured depository institutions;
- (4) the trustee of a pension or other employee benefit plan, with respect to funds of the plan;
- (5) a person acting as a plan administrator or an investment adviser in connection with a pension plan or other employee benefit plan provided that that person is performing managerial functions with respect to the plan;
- (6) the trustee of a testamentary account;
- (7) the trustee of an irrevocable trust (other than a trustee who establishes a deposit account to facilitate a business arrangement with an insured depository institution to use the proceeds of the account to fund a prearranged loan), as long as the trust in question has not been established for the primary purpose of placing funds with insured depository institutions;
- (8) a trustee or custodian of a pension or profit-sharing plan qualified under Section 401(d) or 430(a) of the Internal Revenue Code of 1986; or
- (9) an agent or nominee whose primary purpose is not the placement of funds with depository institutions. (For purposes of applying this ninth exclusion from the definition of deposit broker, "primary purpose" does not mean "primary activity," but should be construed as "primary intent.")

Notwithstanding these nine exclusions, the term <u>deposit broker</u> (as amended on September 23, 1994, by the Riegle Community Development and Regulatory Improvement Act of 1994) includes any insured depository institution that is not well capitalized (as defined in Section 38 of the Federal Deposit Insurance Act, Prompt Corrective Action), and any employee of such institution, which engages, directly or indirectly, in the solicitation of deposits by offering rates of interest which are significantly higher than the prevailing rates of interest on deposits offered by other insured depository institutions in such depository institution's normal market area. For purposes of these reports, only those deposits accepted, renewed, or rolled over on or after June 16, 1992, in connection with this form of deposit solicitation are to be reported as brokered deposits. For further information, see Section 337.6(b) of the FDIC's Rules and Regulations.

¹ Any deposit accepted, renewed, or rolled over by a well capitalized institution before September 23, 1994, in connection with this form of deposit solicitation should continue to be reported as a brokered deposit as long as the deposit remains outstanding under the terms in effect before September 23, 1994. Notwithstanding the amendment to the "deposit broker" definition, all institutions that obtain deposits, directly or indirectly, by or through any other deposit broker must report such funds as brokered deposits in the Report of Condition.

Brokered Deposits (cont.):

In addition, deposit instruments of the reporting bank that are sold to brokers, dealers, or underwriters (including both bank affiliates of the reporting bank and nonbank subsidiaries of the reporting bank's parent holding company) who then reoffer and/or resell these deposit instruments to one or more investors, regardless of the minimum denomination which the investor must purchase, are considered brokered deposits.

In some cases, brokered deposits are issued in the name of the depositor whose funds have been placed in a bank by a deposit broker. In other cases, a bank's deposit account records may indicate that the funds have been deposited in the name of a third party custodian for the benefit of others (e.g., "XYZ Corporation as custodian for the benefit of others," or "Custodial account of XYZ Corporation"). Unless the custodian meets one of the specific exemptions from the "deposit broker" definition in Section 29 of the Federal Deposit Insurance Act and this Glossary entry, these custodial accounts should be reported as brokered deposits in Schedule RC-E, Deposit Liabilities.

A deposit listing service whose only function is to provide information on the availability and terms of accounts is not facilitating the placement of deposits and therefore is not a deposit broker per se. However, if a deposit broker uses a deposit listing service to identify an institution offering a high rate on deposits and then places its customers' funds at that institution, the deposits would be brokered deposits and the institution should report them as such in Schedule RC-E. The designation of these deposits as brokered deposits is based not on the broker's use of the listing service but on the placement of the deposits in the institution by the deposit broker.

Broker's Security Draft: A broker's security draft is a draft with securities or title to securities attached that is drawn to obtain payment for the securities. This draft is sent to a bank for collection with instructions to release the securities only on payment of the draft.

Business Combinations: The accounting and reporting standards for business combinations are set forth in FASB Statement No. 141, "Business Combinations." Statement No. 141 requires that all business combinations *initiated* after June 30, 2001, must be accounted for using the purchase method. The use of the pooling-of-interests method to account for business combinations *initiated* after June 30, 2001, is prohibited. However, for combinations between two or more mutual institutions, Statement No.141 will not take effect until interpretive guidance related to the application of the purchase method to those transactions is issued. Business combinations initiated before July 1, 2001, were accounted for using one of two methods, the pooling-of-interests method or the purchase method. A business combination involving the exchange of voting common stock between unrelated stock institutions and meeting all 12 of the conditions specified in APB Opinion No. 16, "Business Combinations," was accounted for using the pooling-of-interests method; all other unrelated party business combinations were accounted for using the purchase method.

<u>Pooling-of-interests method</u> – Under the pooling-of-interests method, the assets, liabilities, and capital of the bank and the business being acquired are added together on a line-by-line basis without any adjustments for fair market value. The historical cost-based amount (cost adjusted for amortization of premiums and discounts or depreciation) of each asset, liability, and capital account of the acquiring bank is added to the corresponding account of the business being acquired to arrive at the balance sheet for the combined bank. However, the capital stock outstanding of the combined bank must be equal to the number of shares issued and outstanding (including the shares issued in connection with the acquisition) multiplied by par or stated value.

If the sum of the capital stock accounts of the entities being combined does not equal this amount (and it rarely, if ever, will), adjustment is required. If the sum of the capital stock accounts is less than the number of shares outstanding of the combined bank multiplied by par or stated value, "Surplus," Schedule RC, item 25, must be debited for the amount of the difference and "Common stock," Schedule RC, item 24, is credited. If the surplus account is insufficient to absorb such an adjustment

Business Combinations (cont.):

the remainder must be debited to "Retained earnings," Schedule RC, item 26.a. If the sum of the capital stock accounts is more than the amount of the outstanding stock of the combined bank, "Surplus" must be credited and "Common stock" debited.

Any adjustments necessary to conform the accounting methods of the acquired entity to those of the reporting bank must be made, net of related tax effects, to "Retained earnings."

For the year in which a pooling of interests occurs, income and expenses must be reported as though the companies had combined at the beginning of the year. The portion of the adjustment necessary to conform the accounting methods applicable to the current period must also be allocated to income and expenses for the period.

<u>Purchase method</u> – In general, under the purchase method an acquiring entity must allocate the cost of an acquired entity to the assets acquired and liabilities assumed based on their <u>estimated fair values</u> at the date of acquisition. Any cash payments, the fair values of securities or other assets distributed as consideration, and the fair values of liabilities incurred by an acquiring entity must be used to measure the cost of an acquired entity. The cost of an acquired entity also includes the direct costs of the business combination. Costs of registering and issuing equity securities must be recognized as a reduction of the otherwise determinable fair value of the securities. However, indirect and general expenses related to business combinations must be expensed as incurred.

Statement No. 141 provides general guidance for assigning amounts to assets acquired and liabilities assumed. Acquired assets may be tangible (such as securities or fixed assets) or intangible (as discussed in the following paragraph). An acquiring entity must not recognize the goodwill, if any, or the deferred income taxes recorded by an acquired entity before its acquisition. However, a deferred tax liability or asset must be recognized for differences between the assigned values and the tax bases of the recognized assets acquired and liabilities assumed in a business combination in accordance with FASB Statement No. 109, "Accounting for Income Taxes." (For further information, see the Glossary entry for "income taxes.")

Under Statement No. 141, an intangible asset must be recognized as an asset apart from goodwill if it arises from contractual or other legal rights (regardless of transferability or separability). Otherwise, an intangible asset must be recognized as an asset apart from goodwill only if it is separable, that is, it is capable of being separated or divided from the acquired entity and sold, transferred, licensed, rented or exchanged either individually or in combination with a related contract, asset, or liability. Examples of intangible assets that must be recognized as an asset apart from goodwill are core deposit intangibles, purchase credit card relationships, servicing assets, favorable leasehold rights, trademarks, tradenames, Internet domain names, and noncompetition agreements. These intangible assets, as well as any unidentifiable intangible assets recorded in accordance with FASB Statement No. 72, must be reported in Schedule RC, item 10.b, "Other intangible assets," and in Schedule RC-M, item 2.

The excess of the cost of an acquired entity over the net of the amounts assigned to assets acquired and liabilities must be recognized as goodwill, which is reported in Schedule RC, item 10.a. An acquired intangible asset that does not meet the criteria described in the preceding paragraph must be included in the amount recognized as goodwill. After initial recognition, goodwill must be accounted for in accordance with FASB Statement No. 142, "Goodwill and Other Intangible Assets," and the instructions for Schedule RI, item 7.c.(1), "Goodwill impairment losses."

In contrast, if the sum of the amounts assigned to assets acquired and liabilities assumed exceeds the cost of the acquired entity, that excess must be allocated as a pro rata reduction of the amounts that otherwise would have been assigned to all of the acquired assets except financial assets (other than investments accounted for by the equity method), assets to be disposed of by sale (such as foreclosed real estate), deferred tax assets, prepaid assets relating to pension or other postretirement benefit

Business Combinations (cont.):

plans, and any other current assets. If any excess remains after reducing to zero the amounts that otherwise would have been assigned to those assets, that remaining excess shall be recognized as an extraordinary gain, generally in the period in which the business combination is completed, and reported in Schedule RI, item 11, "Extraordinary items and other adjustments, net of income taxes."

Under the purchase method, the historical equity capital balances of the acquired business are *not* to be carried forward to the balance sheet of the combined bank. The operating results of the acquired bank or business are to be included in the income and expenses of the reporting bank <u>only</u> from the date of acquisition.

<u>Push down accounting</u> -- Push down accounting is the establishment of a new accounting basis for a bank in its separate financial statements as a result of a substantive change in control. Under push down accounting, when a bank is acquired, yet retains its separate corporate existence, the assets and liabilities of the acquired bank are restated to their fair values as of the acquisition date. These values, including any goodwill, are reflected in the separate financial statements of the acquired bank as well as in any consolidated financial statements of the bank's parent.

Push down accounting is <u>required</u> for purposes of the Reports of Condition and Income if a direct or indirect change in control of at least 95 percent of the voting stock of the bank has occurred, and the bank does not have an outstanding issue of publicly traded debt or preferred stock. Push down accounting also is <u>required</u> if the bank's separate financial statements are presented on a push down basis in reports filed with the Securities and Exchange Commission. Push down accounting may also be used when a direct or indirect change in control of at least 80 percent, but less than 95 percent, of the voting stock of the bank has occurred.

In all cases, the bank's primary federal supervisory authority reserves the right to determine whether or not a bank must use push down accounting for purposes of the Reports of Condition and Income.

When push down accounting is used by a bank in the preparation of its Reports of Condition and Income, <u>both</u> of the following conditions should be met:

- (1) An arm's-length purchase acquisition resulting in a substantive change in control of at least 80 percent must have occurred, and
- (2) The push down adjusting entries must have eliminated the retained earnings account (therefore, the entire retained earnings of the bank before the acquisition will not be available for the payment of dividends after the acquisition).

In the Reports of Condition and Income for the remainder of the year in which the acquisition occurs, a bank shall report the initial increase or decrease in its equity capital that results from the application of push down accounting in item 7, "Changes incident to business combinations, net," of Schedule RI-A, Changes in Equity Capital. In addition, when push down accounting is used, no income or expense for the period of the calendar year prior to the acquisition date should be included in subsequent Reports of Income.

Reorganization -- A combination of two or more entities involving related parties is considered a reorganization and not a business combination. For example, two subsidiary banks of a bank holding company may combine into one bank, which is a change in legal organization but not a change in the entity. The assets and liabilities transferred in the combination are accounted for at historical cost in a manner similar to that described above under "pooling-of-interests method."

FFIEC 031 and 041 A-13 GLOSSARY

¹ Prior to the allocation of the excess, the acquiring entity must reassess whether all acquired assets and assumed liabilities have been identified and recognized and perform remeasurements to verify that the consideration paid, assets acquired, and liabilities assumed have been properly valued.

Business Combinations (cont.):

A bank holding company's investment in a bank or other business that was acquired in a purchase business combination may differ from the book value of the net assets in that bank's or business's financial statements because push down accounting was not applied. This situation will generally exist with respect to acquisitions that occurred prior to the September 30, 1989, effective date of the push down accounting instructions set forth above in this Glossary entry.

A bank holding company may transfer its ownership interest in an acquired bank or other business to another one of its subsidiary banks subsequent to its acquisition of the bank or other business. When this occurs, the financial statements of the surviving bank must be adjusted, as set forth in FASB Emerging Issues Task Force Issue No. 90-5, to reflect the assets and liabilities of the acquired bank or other business at the historical cost included in the holding company's financial statements. The necessity and extent of such adjustments should be determined in consultation with the bank's primary federal supervisory authority.

For further information on the accounting for business combinations, see FASB Statement No. 141 and FASB Statement No. 72, "Accounting for Certain Acquisitions of Banking or Thrift Institutions."

<u>Call Option</u>: <u>See</u> "derivative contracts."

Capitalization of Interest Costs: Interest costs associated with the construction of a building shall, if material, be capitalized as part of the cost of the building. Such interest costs include both the actual interest incurred when the construction funds are borrowed and the interest costs imputed to internal financing of a construction project.

The interest rate utilized to capitalize interest on internally financed projects in a reporting period shall be the rate(s) applicable to the bank's borrowings outstanding during the period. For this purpose, a bank's borrowings include interest-bearing deposits and other interest-bearing liabilities.

The interest capitalized shall not exceed the total amount of interest cost incurred by the bank during the reporting period.

For further information, see FASB Statement No. 34, "Capitalization of Interest Costs," as amended.

Carrybacks and Carryforwards: See "income taxes."

Cash Management Arrangements: A cash management arrangement is a group of related transaction accounts of a single type maintained in the same right and capacity by a customer (a single legal entity), whereby the customer and the financial institution understand that payments from one account will be honored so long as a net credit balance exists in the group of related transaction accounts taken as a whole. Such accounts function as, and will be regarded for reporting and deposit insurance assessment purposes as, one account rather than separate accounts, provided adequate documentation of the arrangement is maintained as discussed below. (Note: For reporting and deposit insurance assessment purposes, transaction accounts of affiliates and subsidiaries of a parent company that are separate legal entities may not be offset because accounts of separate legal entities are not permitted within a bona fide cash management arrangement.)

"Transaction accounts of a single type" means demand deposit accounts or NOW accounts, but not a combination thereof. For purposes of cash management arrangements, the terms "right" and "capacity" relate to the form of legal ownership such as being held in an agency or trust capacity, as a joint tenant, or as an individual. "Single legal entity" means a natural person, partnership, corporation, trust, or estate.

Cash Management Arrangements (cont.):

The reporting bank must maintain readily available records that will allow for the verification of cash management arrangements. Such documentation must provide account numbers, account titles, ownership of accounts, and the terms and conditions surrounding the management of the accounts, and must also clearly show that both the customer and the reporting bank have agreed to such terms and conditions. These terms and conditions must clearly indicate the understanding that payments from one account will be honored as long as a net credit balance exists within the group of related transaction accounts taken as a whole and maintained in the same right and capacity. A written cash management agreement, signed by both the customer (a single legal entity) and the reporting bank, accurately maintained and incorporating the above information, will be acceptable evidence of a bona fide cash management arrangement. In addition, the reporting bank must maintain readily available records that will allow for the verification of account balances within cash management arrangements.

<u>See</u> "deposits" for the definitions of transaction account, demand deposit, and NOW account. <u>See also</u> "overdraft."

Certificate of Deposit: See "deposits."

Changes in Accounting Estimates: See "accounting changes."

Changes in Accounting Principles: See "accounting changes."

<u>Clearing Accounts</u>: <u>See</u> "suspense accounts."

Commercial Banks in the U.S.: See "banks, U.S. and foreign."

Commercial Letter of Credit: See "letter of credit."

Commercial Paper: Commercial paper consists of short-term negotiable promissory notes issued in the United States by commercial businesses, including finance companies and banks. Commercial paper usually matures in 270 days or less and is not collateralized. Commercial paper may be backed by a standby letter of credit from a bank, as in the case of documented discounted notes. Holdings of commercial paper are to be reported as "securities" in Schedule RC-B, normally in item 6, "Other debt securities," unless held for trading and therefore reportable in Schedule RC, item 5, "Trading assets."

Commodity or Bill-of-Lading Draft: A commodity or bill-of-lading draft is a draft that is issued in connection with the shipment of goods. If the commodity or bill-of-lading draft becomes payable only when the shipment of goods against which it is payable arrives, it is an arrival draft. Arrival drafts are usually forwarded by the shipper to the collecting depository institution with instructions to release the shipping documents (e.g., bill of lading) conveying title to the goods only upon payment of the draft. Payment, however, cannot be demanded until the goods have arrived at the drawee's destination. Arrival drafts provide a means of insuring payment of shipped goods at the time that the goods are released.

Common Stock of Unconsolidated Subsidiaries, Investments in: See "equity method of accounting" and "subsidiaries."

Continuing Contract: See "federal funds transactions."

Corporate Joint Venture: See "subsidiaries."

Corrections of Accounting Errors: See "accounting changes."

Coupon Stripping, Treasury Receipts, and STRIPS: Coupon stripping occurs when a security holder physically detaches unmatured coupons from the principal portion of a security and sells either the detached coupons or the ex-coupon security separately. (Such transactions are generally considered by federal bank supervisory agencies to represent "improper investment practices" for banks.) In accounting for such transactions, the carrying amount of the security must be allocated between the ex-coupon security and the detached coupons based on their relative fair values at the date of the sale in accordance with FASB Statement No. 140. (See the Glossary entry for "transfers of financial assets.")

Detached U.S. Government security coupons and ex-coupon U.S. Government securities that are held for purposes other than trading, whether resulting from the coupon stripping activities of the reporting bank or from its purchase of stripped securities, shall be reported as "Other domestic debt securities" in Schedule RC-B, item 6.a. The amount of any discount or premium relating to the detached coupons or ex-coupon securities must be amortized. (See the Glossary entry for "premiums and discounts.")

A variation of coupon stripping has been developed by several securities firms which have marketed instruments with such names as CATS (Certificates of Accrual on Treasury Securities), TIGR (Treasury Investment Growth Receipts), COUGAR (Certificates on Government Receipts), LION (Lehman Investment Opportunity Notes), and ETR (East Treasury Receipts). A securities dealer purchases U.S. Treasury securities, delivers them to a trustee, and sells receipts representing the rights to future interest and/or principal payments on the U.S. Treasury securities held by the trustee. Such Treasury receipts are not an obligation of the U.S. Government and, when held for purposes other than trading, shall be reported as "Other domestic debt securities" in Schedule RC-B, item 6.a. The discount on these Treasury receipts must be accreted.

Coupon Stripping, Treasury Receipts, and STRIPS (cont.):

Under a program called Separate Trading of Registered Interest and Principal of Securities (STRIPS), the U.S. Treasury has issued certain long-term note and bond issues that are maintained in the book-entry system operated by the Federal Reserve Banks in a manner that permits separate trading and ownership of the interest and principal payments on these issues. Even after the interest or principal portions of U.S. Treasury STRIPS have been separately traded, they remain obligations of the U.S. Government. STRIPS held for purposes other than trading shall be reported as U.S. Treasury securities in Schedule RC-B, item 1. The discount on separately traded portions of STRIPS must be accreted.

Detached coupons, ex-coupon securities, Treasury receipts, and U.S. Treasury STRIPS held for trading purposes shall be reported at fair value in Schedule RC, item 5.

<u>Custody Account</u>: A custody account is one in which securities or other assets are held by a bank on behalf of a customer under a safekeeping arrangement. Assets held in such capacity are not to be reported in the balance sheet of the reporting bank nor are such accounts to be reflected as a liability. Assets of the reporting bank held in custody accounts at other banks are to be reported on the reporting bank's balance sheet in the appropriate asset categories as if held in the physical custody of the reporting bank.

Dealer Reserve Account: A dealer reserve account arises when a bank purchases at full face value a dealer's installment note receivables, but credits less than the full face value directly to the dealer's account. The remaining amount is credited to a separate dealer reserve account. That account is held by the bank as collateral for the installment notes and, for reporting purposes, is treated as a deposit in the appropriate items of Schedule RC-E. The bank will subsequently disburse to the dealer predetermined portions of the reserve as the purchased notes are paid in a timely manner.

For example, if a bank purchases \$100,000 in notes from a dealer for the full face amount (\$100,000) and pays to the dealer \$90,000 in cash or credits to his/her deposit account, the remaining \$10,000, which is held as collateral security, would be credited to the dealer reserve account.

See also "deposits."

Deferred Income Taxes: See "income taxes."

Demand Deposits: See "deposits."

Depository Institutions in the U.S.: Depository institutions in the U.S. consist of:

- (1) U.S. branches and agencies of foreign banks;
- (2) U.S.-domiciled head offices and branches of U.S. banks, i.e.,
 - (a) national banks,
 - (b) state-chartered commercial banks,
 - (c) trust companies that perform a commercial banking business,
 - (d) industrial banks,
 - (e) private or unincorporated banks,
 - (f) Edge and Agreement corporations, and
 - (g) International Banking Facilities (IBFs) of U.S. banks; and

Depository Institutions in the U.S. (cont.):

- (3) U.S.-domiciled head offices and branches of other depository institutions in the U.S., i.e.,
 - (a) mutual or stock savings banks,
 - (b) savings or building and loan associations.
 - (c) cooperative banks,
 - (d) credit unions,
 - (e) homestead associations,
 - (f) other similar depository institutions in the U.S., and
 - (g) International Banking Facilities (IBFs) of other depository institutions in the U.S.

Deposits: The basic statutory and regulatory definitions of "deposits" are contained in Section $3(\ell)$ of the Federal Deposit Insurance Act (FDI Act) and in Federal Reserve Regulation D. The definitions in these two legal sources differ in certain respects. Furthermore, for purposes of these reports, the reporting standards for deposits specified in these instructions do not strictly follow the precise legal definitions in these two sources. The definitions of deposits to be reported in the deposit items of the Reports of Condition and Income are discussed below under the following headings:

- FDI Act definition of deposits.
- (II) Transaction-nontransaction deposit distinction.
- (III) Interest-bearing-noninterest-bearing deposit distinction.
- FDI Act definition of deposits Section $3(\ell)$ states that the term "deposit" means --
 - (1) the unpaid balance of money or its equivalent received or held by a bank or savings association in the usual course of business and for which it has given or is obligated to give credit, either conditionally or unconditionally, to a commercial, checking, savings, time, or thrift account, or which is evidenced by its certificate of deposit, thrift certificate, investment certificate, certificate of indebtedness, or other similar name, or a check or draft drawn against a deposit account and certified by the bank or savings association, or a letter of credit or a traveler's check on which the bank or savings association is primarily liable: Provided, That, without limiting the generality of the term "money or its equivalent", any such account or instrument must be regarded as evidencing the receipt of the equivalent of money when credited or issued in exchange for checks or drafts or for a promissory note upon which the person obtaining any such credit or instrument is primarily or secondarily liable, or for a charge against a deposit account, or in settlement of checks, drafts, or other instruments forwarded to such bank or savings association for collection,
 - (2) trust funds as defined in this Act received or held by such bank or savings association, whether held in the trust department or held or deposited in any other department of such bank or savings association,
 - (3) money received or held by a bank or savings association, or the credit given for money or its equivalent received or held by a bank or savings association, in the usual course of business for a special or specific purpose, regardless of the legal relationship thereby established, including without being limited to, escrow funds, funds held as security for an obligation due to the bank or savings association or others (including funds held as dealers reserves) or for securities loaned by the bank or savings association, funds deposited by a debtor to meet maturing obligations, funds deposited as advance payment on subscriptions to United States Government securities, funds held for distribution or purchase of securities, funds held to meet its acceptances or letters of credit, and withheld taxes: Provided, That there shall not be included funds which are received by the bank or savings association for immediate application to the reduction of an indebtedness to the receiving bank or savings association, or under condition that the receipt thereof immediately reduces or extinguishes such an indebtedness,

Deposits (cont.):

(4) outstanding draft (including advice or authorization to charge a bank's or a savings association's balance in another bank or savings association), cashier's check, money order, or other officer's check issued in the usual course of business for any purpose, including without being limited to those issued in payment for services, dividends, or purchases, and

- (5) such other obligations of a bank or savings association as the Board of Directors, after consultation with the Comptroller of the Currency, Director of the Office of Thrift Supervision, and the Board of Governors of the Federal Reserve System, shall find and prescribe by regulation to be deposit liabilities by general usage, except that the following shall not be a deposit for any of the purposes of this Act or be included as part of the total deposits or of an insured deposit:
 - (A) any obligation of a depository institution which is carried on the books and records of an office of such bank or savings association located outside of any State, unless --
 - (i) such obligation would be a deposit if it were carried on the books and records of the depository institution, and would be payable at, an office located in any State; and
 - (ii) the contract evidencing the obligation provides by express terms, and not by implication, for payment at an office of the depository institution located in any State; and
 - (B) any international banking facility deposit, including an international banking facility time deposit, as such term is from time to time defined by the Board of Governors of the Federal Reserve System in regulation D or any successor regulation issued by the Board of Governors of the Federal Reserve System; and
 - (C) any liability of an insured depository institution that arises under an annuity contract, the income of which is tax deferred under section 72 of the Internal Revenue Code of 1986.
- (II) Transaction-nontransaction deposit distinction: The Monetary Control Act of 1980 and the current Federal Reserve Regulation D, "Reserve Requirements of Depository Institutions," establish, for purposes of federal reserve requirements on deposit liabilities, a category of deposits designated as "transaction accounts." All deposits that are not transaction accounts are "nontransaction accounts."
 - (1) <u>Transaction accounts</u> -- With the exceptions noted below, a "transaction account," as defined in Regulation D and in these instructions, is a deposit or account from which the depositor or account holder is permitted to make transfers or withdrawals by negotiable or transferable instruments, payment orders of withdrawal, telephone transfers, or other similar devices for the purpose of making payments or transfers to third persons or others or from which the depositor may make third party payments at an automated teller machine (ATM), a remote service unit (RSU), or another electronic device, including by debit card.

Excluded from transaction accounts are savings deposits (both money market deposit accounts (MMDAs) and other savings deposits) as defined below in the nontransaction account category, even though such deposits permit some third-party transfers. However, an account that otherwise meets the definition of a savings deposit but that authorizes or permits the depositor to exceed the transfer limitations specified for that account shall be reported as a transaction account. (Please refer to the definition of savings deposits for further detail.)

Deposits (cont.):

NOTE: Under the Federal Reserve's current Regulation D, no transaction account, regardless of its other characteristics, is classified either as a savings deposit or as a time deposit. Thus, those transaction accounts that are <u>not</u> demand deposits--NOW accounts, ATS (Automatic Transfer Service) accounts, and telephone and preauthorized transfer accounts--are <u>excluded</u> from Regulation D time and savings deposits. However, for FDIC insurance assessment purposes as set forth in the FDI Act, all such transaction accounts that are <u>not</u> demand deposits are included in "time and savings deposits." This FDIC usage is to be followed <u>only</u> in Schedule RC-O. For all other items in the Reports of Condition and Income involving time or savings deposits, a strict distinction, based on Regulation D definitions, is to be maintained between transaction accounts and time and savings accounts.

Transaction accounts consist of the following types of deposits: (a) demand deposits; (b) NOW accounts; (c) ATS accounts; and (d) telephone and preauthorized transfer accounts, all as defined below. Interest that is paid by the crediting of transaction accounts is also included in transaction accounts.

- (a) <u>Demand deposits</u> are noninterest-bearing deposits that are payable immediately on demand, or that are issued with an original maturity or required notice period of less than seven days, or that represent funds for which the depository institution does not reserve the right to require at least seven days' written notice of an intended withdrawal. Demand deposits include any matured time deposits without automatic renewal provisions, unless the deposit agreement provides for the funds to be transferred at maturity to another type of account. Demand deposits do <u>not</u> include: (i) money market deposit accounts (MMDAs) or (ii) NOW accounts, as defined below in this entry.
- (b) <u>NOW accounts</u> are interest-bearing deposits (i) on which the depository institution has reserved the right to require at least seven days' written notice prior to withdrawal or transfer of any funds in the account <u>and</u> (ii) that can be withdrawn or transferred to third parties by issuance of a negotiable or transferable instrument.

NOW accounts, as authorized by federal law, are limited to accounts held by:

- (i) Individuals or sole proprietorships;
- (ii) Organizations that are operated primarily for religious, philanthropic, charitable, educational, or other similar purposes and that are not operated for profit. These include organizations, partnerships, corporations, or associations that are not organized for profit and are described in section 501(c)(3) through (13) and (19) and section 528 of the Internal Revenue Code, such as church organizations; professional associations; trade associations; labor unions; fraternities, sororities and similar social organizations; and nonprofit recreational clubs; or
- (iii) Governmental units including the federal government and its agencies and instrumentalities; state governments; county and municipal governments and their political subdivisions; the District of Columbia; the Commonwealth of Puerto Rico, American Samoa, Guam, and any territory or possession of the United States and their political subdivisions.

Also included are the balances of all NOW accounts of certain other nonprofit organizations that may not fall within the above description but that had established NOW accounts with the reporting institution prior to September 1, 1981.

Deposits (cont.):

<u>NOTE</u>: There are no regulatory requirements with respect to minimum balances to be maintained in a NOW account or to the amount of interest that may be paid on a NOW account.

(c) ATS accounts are deposits or accounts of individuals or sole proprietorships on which the depository institution has reserved the right to require at least seven days' written notice prior to withdrawal or transfer of any funds in the account and from which, pursuant to written agreement arranged in advance between the reporting institution and the depositor, withdrawals may be made automatically through payment to the depository institution itself or through transfer of credit to a demand deposit or other account in order to cover checks or drafts drawn upon the institution or to maintain a specified balance in, or to make periodic transfers to, such other accounts.

Some institutions may have entered into agreements with their customers providing that in the event the customer should overdraw a demand deposit (checking) or NOW account, the institution will transfer from that customer's savings account an amount sufficient to cover the overdraft. The availability of the overdraft protection plan would not in and of itself require that such a savings account be regarded as a transaction account provided that the overall transfer and withdrawal restrictions of a savings deposit are not exceeded. Please refer to the definition of savings deposit for further detail.

(d) Telephone or preauthorized transfer accounts consist of deposits or accounts, other than savings deposits, (1) in which the entire beneficial interest is held by a party eligible to hold a NOW account, (2) on which the reporting institution has reserved the right to require at least seven days' written notice prior to withdrawal or transfer of any funds in the account, and (3) under the terms of which, or by practice of the reporting institution, the depositor is permitted or authorized to make more than six withdrawals per month or statement cycle (or similar period) of at least four weeks for purposes of transferring funds to another account of the depositor at the same institution (including a transaction account) or for making payment to a third party by means of preauthorized transfer, or telephonic (including data transmission) agreement, order or instruction. An account that permits or authorizes more than six such withdrawals in a "month" (a calendar month or any period approximating a month that is at least four weeks long, such as a statement cycle) is a transaction account whether or not more than six such withdrawals actually are made in the "month."

A "preauthorized transfer" includes any arrangement by the reporting institution to pay a third party from the account of a depositor (1) upon written or oral instruction (including an order received through an automated clearing house (ACH)), or (2) at a predetermined time or on a fixed schedule.

Telephone and preauthorized transfer accounts also include:

(i) Deposits or accounts maintained in connection with an arrangement that permits the depositor to obtain credit directly or indirectly through the drawing of a negotiable or nonnegotiable check, draft, order or instruction or other similar device (including telephone or electronic order or instruction) on the issuing institution that can be used for the purpose of making payments or transfers to third parties or others, or to another deposit account of the depositor.

Deposits (cont.):

(ii) The balance of deposits or accounts that otherwise meet the definition of time deposits, but from which payments may be made to <u>third parties</u> by means of a debit card, an automated teller machine, remote service unit or other electronic device, regardless of the number of payments made.

However, an account is <u>not</u> a transaction account merely by virtue of arrangements that permit the following types of transfers or withdrawals, regardless of the number:

- (i) Transfers for the purpose of repaying loans and associated expenses at the same depository institution (as originator or servicer).
- (ii) Transfers of funds from this account to another account of the same depositor at the same depository institution when made by mail, messenger, automated teller machine, or in person.
- (iii) Withdrawals for payment directly to the depositor when made by mail, messenger, automated teller machine, in person, or by telephone (via check mailed to the depositor).
- (2) Nontransaction accounts -- All deposits that are not transaction accounts (as defined above) are nontransaction accounts. Nontransaction accounts include: (a) savings deposits ((i) money market deposit accounts (MMDAs) and (ii) other savings deposits) and (b) time deposits ((i) time certificates of deposit and (ii) time deposits, open account). Regulation D no longer distinguishes between money market deposit accounts (MMDAs) and other savings deposits. However, these two types of accounts are defined below for purposes of these reports, which call for separate data on each in Schedule RC-E, (part I,) Memorandum items 2.a.(1) and (2).

NOTE: Under the Federal Reserve's current Regulation D, no transaction accounts, regardless of other characteristics, are defined as savings or time deposits. Thus, savings deposits as defined here, under the heading nontransaction accounts, constitute the entire savings deposit category. Likewise, time deposits, also defined here under nontransaction accounts, constitute the entire time deposits category. However, for FDIC insurance assessment purposes, as set forth in the FDI Act, all transaction accounts other than demand deposits--i.e., NOW accounts, ATS accounts, and telephone and preauthorized transfer accounts--are included in "time and savings deposits." This FDIC usage is to be followed only in Schedule RC-0.

(a) <u>Savings deposits</u> are deposits with respect to which the depositor is not required by the deposit contract but may at any time be required by the depository institution to give written notice of an intended withdrawal not less than seven days before withdrawal is made, and that is not payable on a specified date or at the expiration of a specified time after the date of deposit.

The term savings deposit also means a deposit or account, such as an account commonly known as a passbook savings account, a statement savings account, or a money market deposit account (MMDA), that otherwise meets the requirements of the preceding paragraph and from which, under the terms of the deposit contract or by practice of the depository institution, the depositor is permitted or authorized to make no more than six transfers and withdrawals, or a combination of such transfers and withdrawals, per calendar month or statement cycle (or similar period) of at least four weeks, to another account (including a transaction account) of the depositor at the same institution or to a third party by means of a preauthorized or automatic transfer, or

Deposits (cont.):

telephonic (including data transmission) agreement, order, or instruction, and no more than three of the six such transfers may be made by check, draft, debit card, or similar order made by the depositor and payable to third parties. Transfers from savings deposits for purposes of covering overdrafts (overdraft protection plans) are included under the withdrawal limits specified for savings deposits.

There are no regulatory restrictions on the following types of transfers or withdrawals from a savings deposit account, regardless of the number:

- (1) Transfers for the purpose of repaying loans and associated expenses at the same depository institution (as originator or servicer).
- (2) Transfers of funds from this account to another account of the same depositor at the same institution when made by mail, messenger, automated teller machine, or in person.
- (3) Withdrawals for payment directly to the depositor when made by mail, messenger, automated teller machine, in person, or by telephone (via check mailed to the depositor).

Further, for a savings deposit account, no minimum balance is required by regulation, there is no regulatory limitation on the amount of interest that may be paid, and no minimum maturity is required (although depository institutions must reserve the right to require at least seven days' written notice prior to withdrawal as stipulated above for a savings deposit).

Any depository institution may place restrictions and requirements on savings deposits in addition to those stipulated above. In the case of such further restrictions, the account would still be reported as a savings deposit.

On the other hand, an account that otherwise meets the definition of a savings deposit but that authorizes or permits the depositor to exceed the six-transfer/withdrawal rule or three-draft rule shall be reported as a transaction account, as follows:

- (1) If the depositor is ineligible to hold a NOW account, such an account is considered a demand deposit.
- (2) If the depositor is eligible to hold a NOW account, the account will be considered either a NOW account, a telephone or preauthorized transfer account, or an ATS account:
 - (a) If withdrawals or transfers by check, draft, or similar instrument are permitted or authorized, the account is considered a NOW account.
 - (b) If withdrawals or transfers by check, draft, or similar instrument are <u>not</u> permitted or authorized, the account is considered either an ATS account or a telephone or preauthorized transfer account.

Regulation D no longer distinguishes between money market deposit accounts (MMDAs) and other savings deposits. However, these two types of accounts are defined as follows for purposes of these reports, which call for separate data on each.

Deposits (cont.):

(1) Money market deposit accounts (MMDAs) are deposits or accounts that meet the above definition of a savings deposit and that permit <u>up to (but no more than) three</u> of the six allowable transfers to be made by check, draft, debit card or similar order made by the depositor and payable to third parties.

(2) Other savings deposits are deposits or accounts that meet the above definition of a savings deposit but that permit no transfers by check, draft, debit card, or similar order made by the depositor and payable to third parties. Other savings deposits are commonly known as passbook savings or statement savings accounts.

Examples illustrating distinctions between MMDAs and other savings deposits for purposes of these reports are provided at the end of this Glossary entry.

(b) Time deposits are deposits that the depositor does not have a right, and is not permitted, to make withdrawals from within six days after the date of deposit unless the deposit is subject to an early withdrawal penalty of at least seven days' simple interest on amounts withdrawn within the first six days after deposit. A time deposit from which partial early withdrawals are permitted must impose additional early withdrawal penalties of at least seven days' simple interest on amounts withdrawn within six days after each partial withdrawal. If such additional early withdrawal penalties are not imposed, the account ceases to be a time deposit. The account may become a savings deposit if it meets the requirements for a savings deposit; otherwise it becomes a demand deposit.

<u>NOTE</u>: The above prescribed penalties are the minimum required by Federal Reserve Regulation D. Institutions may choose to require penalties for early withdrawal in excess of the regulatory minimums.

Time deposits take two forms:

- (i) <u>Time certificates of deposit</u> (including rollover certificates of deposit) are deposits evidenced by a negotiable or nonnegotiable instrument, or a deposit in book entry form evidenced by a receipt or similar acknowledgement issued by the bank, that provides, on its face, that the amount of such deposit is payable to the bearer, to any specified person, or to the order of a specified person, as follows:
 - (1) on a certain date not less than seven days after the date of deposit,
 - (2) at the expiration of a specified period not less than seven days after the date of the deposit, or
 - (3) upon written notice to the bank which is to be given not less than seven days before the date of withdrawal.
- (ii) <u>Time deposits, open account</u> are deposits (other than time certificates of deposit) for which there is in force a written contract with the depositor that neither the whole nor any part of such deposit may be withdrawn prior to:
 - (1) the date of maturity which shall be not less than seven days after the date of the deposit, or
 - (2) the expiration of a specified period of written notice of not less than seven days.

Deposits (cont.):

These deposits include those club accounts, such as Christmas club and vacation club accounts, that are made under written contracts that provide that no withdrawal shall be made until a certain number of periodic deposits has been made during a period of not less than three months, even though some of the deposits are made within six days of the end of such period.

Time deposits <u>do not include</u> the following categories of liabilities even if they have an original maturity of seven days or more:

- (1) Any deposit or account that otherwise meets the definition of a time deposit but that allows withdrawals within the first six days after deposit and that does <u>not</u> require an early withdrawal penalty of at least seven days' simple interest on amounts withdrawn within those first six days. Such deposits or accounts that meet the definition of a savings deposit shall be reported as savings deposits; otherwise they shall be reported as demand deposits.
- (2) The remaining balance of a time deposit if a partial early withdrawal is made and the remaining balance is not subject to additional early withdrawal penalties of at least seven days' simple interest on amounts withdrawn within six days after each partial withdrawal. Such time deposits that meet the definition of a savings deposit shall be reported as savings deposits; otherwise they shall be reported as demand deposits.

Reporting of Retail Sweep Arrangements Affecting Transaction and Nontransaction Accounts – In an effort to reduce their reserve requirements, some banks have established sweep arrangements that involve transfers of retail customers' deposits between two subaccounts. In a typical arrangement, a bank creates a master account and two subaccounts: a transaction subaccount (either a demand deposit account or a NOW account), which is subject to reserve requirements, and a nontransaction savings subaccount (a special-purpose money market deposit account (MMDA)), which is not subject to reserve requirements. Depending upon the balances in the two subaccounts on a particular day, the bank will shift funds from the transaction subaccount to the MMDA subaccount or vice versa. On some days, the balance in the MMDA subaccount may be zero. (For purposes of the Federal Reserve's Regulation D, there is no distinction between an MMDA and any other form of savings account in terms of legally required restrictions on transfers.)

For purposes of these reports, the transaction subaccount and MMDA subaccount must be treated separately when a bank reports its quarter-end deposit information in Schedules RC, RC-E, and RC-O, its quarterly averages in Schedule RC-K, and its interest expense (if any) in Schedule RI. Thus, when reporting quarterly averages in Schedule RC-K, a bank should include the amounts held in the transaction subaccounts (if interest-bearing) and the MMDA (nontransaction savings) subaccounts each day or each week in the appropriate separate items for average deposits. In addition, if the bank pays interest on the accounts involved in retail sweep arrangements, the interest expense reported in Schedule RI should be allocated between the transaction subaccount and the MMDA (nontransaction savings) subaccount based on the balances in these subaccounts during the reporting period.

- (III) Interest-bearing-noninterest-bearing deposit distinction:
 - (a) <u>Interest-bearing deposit accounts</u> consist of deposit accounts on which the issuing depository institution pays compensation to the holder for the use of the funds. Such compensation may be in the form of cash, merchandise, or property or as a credit to an account. Deposits with a zero percent interest rate that are <u>issued</u> on a <u>discount basis</u> are to be treated as interest-bearing.

Deposits (cont.):

(b) <u>Noninterest-bearing deposit accounts</u> consist of deposit accounts on which the issuing depository institution pays no compensation to the holder for the use of the funds.

Noninterest-bearing deposit accounts include (i) matured time deposits that are not automatically renewable (unless the deposit agreement provides for the funds to be transferred at maturity to another type of account) and (ii) deposits with a zero percent stated interest rate that are issued at face value.

See also "brokered deposits" and "hypothecated deposits."

Examples Illustrating Distinctions Between

MONEY MARKET DEPOSIT ACCOUNTS (MMDAs) and OTHER SAVINGS DEPOSITS

Example 1

A savings deposit account permits <u>no</u> transfers of any type to other accounts or to third parties. Report this account as an other savings deposit.

Example 2

A savings deposit permits <u>up to six</u>, <u>but no more than six</u>, "preauthorized, automatic, or telephonic" transfers to other accounts or to third parties. <u>None of the third-party payments</u> may be made by check, draft, or similar order (including debit card).

Report this account as an other savings deposit.

Example 3

A savings deposit permits <u>no more than six</u> "preauthorized, automatic, or telephonic" transfers to other accounts or to third parties. <u>Up to three, but no more than three</u>, of the six transfers may be by check, draft, debit card or similar order made by the depositor and payable to third parties.

Report this account as an MMDA.

Example 4

A savings deposit permits <u>up to three, but no more than three</u>, "preauthorized, automatic, or telephonic" transfers to other accounts or to third parties, <u>any or all which</u> may be by check, draft, debit card or similar order made by the depositor and payable to third parties.

Report this account as an MMDA.

Derivative Contracts: Banks commonly use derivative instruments for managing (positioning or hedging) their exposure to market risk (including interest rate risk and foreign exchange risk), cash flow risk, and other risks in their operations and for trading. The accounting and reporting standards for derivative instruments, including certain derivative instruments embedded in other contracts, and for hedging activities are set forth in FASB Statement No. 133, "Accounting for Derivative Instruments and Hedging Activities," as amended. Statement No. 133 requires all derivatives to be recognized on the balance sheet as either assets or liabilities at their fair value. A summary of the principal provisions of Statement No. 133 follows. For further information, see Statement No. 133 and the implementation guidance issued by the FASB's Derivatives Implementation Group, which may be found at the FASB's Web site at www.fasb.org.

Derivative Contracts (cont.):

Statement No. 133 is effective for fiscal years beginning after June 15, 2000. For purposes of these reports, banks must adopt Statement No. 133 upon the statement's effective date based on their fiscal year, with earlier application permitted consistent with the statement. Banks are also expected to follow the accounting guidance issued by the Derivatives Implementation Group.

Definition of Derivative

Statement No. 133 defines a "derivative instrument" as a financial instrument or other contract with all three of the following characteristics:

- (1) It has one or more underlyings (i.e., specified interest rate, security price, commodity price, foreign exchange rate, index of prices or rates, or other variable) and one or more notional amounts (i.e., number of currency units, shares, bushels, pounds, or other units specified in the contract) or payment provisions or both. These terms determine the amount of the settlement or settlements, and in some cases, whether or not a settlement is required.
- (2) It requires no initial net investment or an initial net investment that is smaller than would be required for other types of contracts that would be expected to have similar response to changes in market factors.
- (3) Its terms require or permit net settlement, it can be readily settled net by a means outside the contract, or it provides for delivery of an asset that puts the recipient in a position not substantially different from net settlement.

Certain contracts that may meet the definition of a derivative are specifically excluded from the scope of Statement No. 133, including:

- "regular-way" securities trades, which are trades that are completed within the time period generally
 established by regulations and conventions in the marketplace or by the exchange on which the
 trade is executed;
- normal purchases and sales of an item other than a financial instrument or derivative instrument (e.g., a commodity) that will be delivered in quantities expected to be used or sold by the reporting entity over a reasonable period in the normal course of business;
- traditional life insurance and property and casualty contracts; and
- certain financial guarantee contracts.

However, a loan commitment may meet Statement No. 133's definition of a derivative instrument. For example, loan commitments to originate or acquire mortgage loans that will be resold as part of an institution's mortgage banking operations are derivative instruments.

Types of Derivatives

The most common types of freestanding derivatives are forwards, futures, swaps, options, caps, floors, and collars.

<u>Forward contracts</u> are agreements that obligate two parties to purchase (long) and sell (short) a specific financial instrument, foreign currency, or commodity at a specified price with delivery and settlement at a specified future date.

<u>Futures contracts</u> are standardized forward contracts that are traded on organized exchanges. Exchanges in the U.S. are registered with and regulated by the Commodity Futures Trading Commission. The deliverable financial instruments underlying interest-rate future contracts are specified investment-grade financial instruments, such as U.S. Treasury securities or mortgage-backed securities. <u>Foreign currency futures contracts</u> involve specified deliverable amounts of a particular

Derivative Contracts (cont.):

foreign currency. The deliverable products under <u>commodity futures contracts</u> are specified amounts and grades of commodities such as gold bullion. <u>Equity futures contracts</u> are derivatives that have a portion of their return linked to the price of a particular equity or to an index of equity prices, such as the Standard and Poor's 500.

Other forward contracts are traded over the counter and their terms are not standardized. Such contracts can only be terminated, other than by receipt of the underlying asset, by agreement of both buyer and seller. A <u>forward rate agreement</u> is a forward contract that specifies a reference interest rate and an agreed on interest rate (one to be paid and one to be received), an assumed principal amount (the notional amount), and a specific maturity and settlement date.

<u>Swap contracts</u> are forward-based contracts in which two parties agree to swap streams of payments over a specified period. The payments are based on an agreed upon notional principal amount. An <u>interest rate swap</u> generally involves no exchange of principal at inception or maturity. Rather, the notional amount is used to calculate the payment streams to be exchanged. However, <u>foreign exchange swaps</u> often involve the exchange of principal.

Option contracts (standby contracts) are traded on exchanges and over the counter. Option contracts grant the right, but do not obligate, the purchaser (holder) to buy (call) or sell (put) a specific or standard commodity, financial, or equity instrument at a specified price during a specified period or at a specified date. A <u>purchased option</u> is a contract in which the buyer has paid compensation (such as a fee or premium) to acquire the right to sell or purchase an instrument at a stated price on a specified future date. A <u>written option</u> obligates the option seller to purchase or sell the instrument at the option of the buyer of the contract. Option contracts may relate to purchases or sales of securities, money market instruments, futures contracts, other financial instruments, or commodities.

Interest rate caps are option contracts in which the cap seller, in return for a premium, agrees to limit the cap holder's risk associated with an increase in interest rates. If rates go above a specified interest-rate level (the strike price or cap rate), the cap holder is entitled to receive cash payments equal to the excess of the market rate over the strike price multiplied by the notional principal amount. For example, an issuer of floating-rate debt may purchase a cap to protect against rising interest rates, while retaining the ability to benefit from a decline in rates.

Interest rate floors are option contracts in which the floor seller, in return for a premium, agrees to limit the risk associated with a decline in interest rates based on a notional amount. If rates fall below an agreed rate, the floor holder will receive cash payments from the floor writer equal to the difference between the market rate and an agreed rate, multiplied by the notional principal amount.

Interest rate collars are option contracts that combine a cap and a floor (one held and one written). Interest rate collars enable a user with a floating rate contract to lock into a predetermined interest-rate range often at a lower cost than a cap or a floor.

Embedded Derivatives

Contracts that do not in their entirety meet the definition of a derivative instrument, such as bonds, insurance policies, and leases, may contain "embedded" derivative instruments. Embedded derivatives are implicit or explicit terms within a contract that affect some or all of the cash flows or the value of other exchanges required by the contract in a manner similar to a derivative instrument. The effect of embedding a derivative instrument in another type of contract ("the host contract") is that some or all of the cash flows or other exchanges that otherwise would be required by the host contract, whether

Derivative Contracts (cont.):

unconditional or contingent upon the occurrence of a specified event, will be modified based on one or more of the underlyings. An embedded derivative instrument shall be separated from the host contract and accounted for as a derivative instrument if and only if <u>all</u> three of the following conditions are met:

- (1) The economic characteristics and risks of the embedded derivative instrument are not clearly and closely related to the economic characteristics and risks of the host contract,
- (2) The contract ("the hybrid instrument") that embodies the embedded derivative and the host contract is not remeasured at fair value under otherwise applicable generally accepted accounting principles with changes in fair value reported in earnings as they occur, and
- (3) A separate instrument with the same terms as the embedded derivative instrument would be a considered a derivative.

An embedded derivative instrument in which the underlying is an interest rate or interest rate index that alters net interest payments that otherwise would be paid or received on an interest-bearing host contract is considered to be clearly and closely related to the host contract <u>unless</u> either of the following conditions exist:

- (1) The hybrid instrument can contractually be settled in such a way that the investor (holder) would not recover substantially all of its initial recorded investment, or
- (2) The embedded derivative could at least double the investor's initial rate of return on the host contract and could also result in a rate of return that is at least twice what otherwise would be the market return for a contract that has the same terms as the host contract and that involves a debtor with a similar credit quality.

Examples of hybrid instruments (not held for trading purposes) with embedded derivatives which meet the three conditions listed above and must be accounted for separately include debt instruments (including deposit liabilities) whose return or yield is indexed to: changes in an equity securities index (e.g., the Standard & Poor's 500); changes in the price of a specific equity security; or changes in the price of gold, crude oil, or some other commodity. For purposes of these reports, when an embedded derivative must be accounted for separately from the host contract under Statement No. 133, the carrying value of the host contract and the fair value of the embedded derivative may be combined and presented together on the balance sheet in the asset or liability category appropriate to the host contract.

Interest-only and principal-only strips are not subject to the requirements of Statement No. 133 provided they (1) initially resulted from separating the rights to receive contractual cash flows of a financial instrument that, in and of itself, did not contain an embedded derivative that otherwise would have been accounted for separately and (2) do not incorporate any terms not present in that original financial instrument. However, questions have been raised about how this provision of FAS 133 should be applied in light of other accounting guidance in FASB Statement No. 140, "Accounting for Transfers and Servicing of Financial Assets and Extinguishments of Liabilities." As a result, the FASB Board has decided that, pending the issuance of further guidance, institutions should continue to account for interest-only and principal-only strips and other beneficial interests in securitizations in accordance with Statement No. 140. (For further information, see Derivatives Implementation Group Issue No. D1, "Application of Statement 133 to Beneficial Interests in Securitized Financial Assets.")

Derivative Contracts (cont.):

Recognition of Derivatives and Measurement of Derivatives and Hedged Items

A bank should recognize all of its derivative instruments on its balance sheet as either assets or liabilities at fair value. As defined in FASB Statement No. 133, fair value is the amount at which an asset (liability) could be bought (incurred) or sold (settled) in a current transaction between willing parties, that is, other than in a forced or liquidation sale. Quoted market prices in active markets are the best evidence of fair value and should be used as the basis for the measurement, if available. If a quoted market price is available, the fair value is the product of the number of trading units times that market price. If a quoted market price is not available, the estimate of fair value should be based on the best information available in the circumstances. The estimate of fair value should consider prices for similar assets or similar liabilities and the results of valuation techniques to the extent available in the circumstances.

Examples of valuation techniques include the present value of expected future cash flows using discount rates commensurate with the risks involved, option-pricing models, matrix pricing, option-adjusted spread analysis, and fundamental analysis. Valuation techniques for measuring assets and liabilities should be consistent with the objective of measuring fair value. Those techniques should incorporate assumptions that market participants would use in their estimates of values, future revenues, and future expenses, including assumptions about interest rates, default, prepayment, and volatility.

If expected future cash flows are used to estimate fair value, those expected future cash flows should be the best estimate based on reasonable and supportable projections. All available evidence should be considered in developing estimates of expected future cash flows. The weight given to the evidence should be commensurate with the extent to which the evidence can be objectively verified. If a range is estimated for either the amount or the timing of possible cash flows, the likelihood of possible outcomes should be considered in determining the best estimate of future cash flows.

The accounting for changes in the fair value (that is, gains and losses) of a derivative depends on whether it has been designated and qualifies as part of a hedging relationship and, if so, on the reason for holding it. Either all or a proportion of a derivative may be designated as a hedging instrument. The proportion must be expressed as a percentage of the entire derivative. Gains and losses on derivative instruments are accounted for as follows:

- (1) No hedging designation The gain or loss on a derivative instrument not designated as a hedging instrument, including all derivatives held for trading purposes, is recognized currently in earnings.
- (2) <u>Fair value hedge</u> For a derivative designated as hedging the exposure to changes in the fair value of a recognized asset or liability or a firm commitment, which is referred to as a fair value hedge, the gain or loss on the derivative as well as the offsetting loss or gain on the hedged item attributable to the risk being hedged should be recognized currently.
- (3) <u>Cash flow hedge</u> For a derivative designated as hedging the exposure to variable cash flows of an existing recognized asset or liability or a forecasted transaction, which is referred to as a cash flow hedge, the effective portion of the gain or loss on the derivative should initially be reported outside of earnings as a component of other comprehensive income and subsequently reclassified into earnings in the same period or periods during which the hedged transaction affects earnings. The remaining gain or loss on the derivative instrument, if any, (i.e., the ineffective portion of the gain or loss and any component of the gain or loss excluded from the assessment of hedge effectiveness) should be recognized currently in earnings.

Derivative Contracts (cont.):

(4) Foreign currency hedge - For a derivative designated as hedging the foreign currency exposure of a net investment in a foreign operation, the gain or loss is reported outside of earnings in other comprehensive income as part of the cumulative translation adjustment. For a derivative designated as a hedge of the foreign currency exposure of an unrecognized firm commitment or an available-for-sale security, the accounting for a fair value hedge should be applied. Similarly, for a derivative designated as a hedge of the foreign currency exposure of a foreign-currency denominated forecasted transaction, the accounting for a cash flow hedge should be applied.

To qualify for hedge accounting, the risk being hedged must represent an exposure to an institution's earnings. In general, if the hedged item is a financial asset or liability, the designated risk being hedged can be (1) all risks, i.e., the risk of changes in the overall fair value of the hedged item or the risk of overall changes in the hedged cash flows; (2) the risk of changes in the fair value or cash flows of the hedged item attributable to changes in the benchmark interest rate; (3) the risk of changes in the fair value or cash flows of the hedged item attributable to changes in foreign exchange rates; or (4) the risk of changes in the fair value or cash flows of the hedged item attributable to changes in the obligor's creditworthiness. For held-to-maturity securities, only credit risk, foreign exchange risk, or both may be hedaed.

Designated hedging instruments and hedged items qualify for fair value or cash flow hedge accounting if all of the criteria specified in Statement No. 133 are met. These criteria include:

- (1) At inception of the hedge, there is formal documentation of the hedging relationship and the institution's risk management objective and strategy for undertaking the hedge, including identification of the hedging instrument, the hedged item or transaction, the nature of the risk being hedged, and how the hedging instrument's effectiveness will be assessed. There must be a reasonable basis for how the institution plans to assess the hedging instrument's effectiveness.
- (2) Both at inception of the hedge and on an ongoing basis, the hedging relationship is expected to be highly effective in achieving offsetting changes in fair value or offsetting cash flows attributable to the hedged risk during the period that the hedge is designated or the term of the hedge. An assessment of effectiveness is required whenever financial statements or earnings are reported, and at least every three months. All assessments of effectiveness shall be consistent with the risk management strategy documented for that particular hedging relationship.

In a fair value hedge, an asset or a liability is eligible for designation as a hedged item if the hedged item is specifically identified as either all or a specific portion of a recognized asset or liability or of an unrecognized firm commitment, the hedged item is a single asset or liability (or a specific portion thereof) or is a portfolio of similar assets or a portfolio of similar liabilities (or a specific portion thereof), and certain other criteria specified in Statement No. 133 are met. If similar assets or similar liabilities are aggregated and hedged as a portfolio, the individual assets or individual liabilities must share the risk exposure for which they are designated as being hedged. The change in fair value attributable to the hedged risk for each individual item in a hedged portfolio must be expected to respond in a generally proportionate manner to the overall change in fair value of the aggregate portfolio attributable to the hedged risk.

In a cash flow hedge, the individual cash flows related to a recognized asset or liability and the cash flows related to a forecasted transaction are both referred to as a forecasted transaction. Thus, a forecasted transaction is eligible for designation as a hedged transaction if the forecasted transaction is

GLOSSARY FFIEC 031 and 041 A-30

¹ The benchmark interest rate is a widely recognized and quoted rate in an active financial market that is broadly indicative of the overall level of interest rates attributable to high-credit-quality obligors in that market. In theory, this should be a risk-free rate. In the U.S., interest rates on U.S. Treasury securities and the LIBOR swap rate are considered benchmark interest rates.

Derivative Contracts (cont.):

specifically identified as a single transaction or a group of individual transactions, the occurrence of the forecasted transaction is probable, and certain other criteria specified in Statement No. 133 are met. If the hedged transaction is a group of individual transactions, those individual transactions must share the same risk exposure for which they are designated as being hedged.

An institution should discontinue prospectively its use of fair value or cash flow hedge accounting for an existing hedge if any of the qualifying criteria for hedge accounting is no longer met; the derivative expires or is sold, terminated, or exercised; or the institution removes the designation of the hedge. When this occurs for a cash flow hedge, the net gain or loss on the derivative should remain in "Accumulated other comprehensive income" and be reclassified into earnings in the periods during which the hedged forecasted transaction affects earnings. However, if it is probable that the forecasted transaction will not occur by the end of the originally specified time period (as documented at the inception of the hedging relationship) or within an additional two-month period of time thereafter (except as noted in Statement No. 133), the derivative gain or loss reported in "Accumulated other comprehensive income" should be reclassified into earnings immediately.

For a fair value hedge, in general, if a periodic assessment of hedge effectiveness indicates noncompliance with the highly effective criterion that must be met in order to qualify for hedge accounting, an institution should not recognize adjustment of the carrying amount of the hedged item for the change in the item's fair value attributable to the hedged risk after the last date on which compliance with the effectiveness criterion was established.

With certain limited exceptions, a nonderivative instrument, such as a U.S. Treasury security, may not be designated as a hedging instrument.

Reporting Derivative Contracts

When an institution enters into a derivative contract, it should classify the derivative as either held for trading or held for purposes other than trading (end-user derivatives) based on the reasons for entering into the contract. All derivatives must be reported at fair value on the balance sheet (Schedule RC).

Trading derivatives with positive fair values should be reported as trading assets in Schedule RC, item 5. Trading derivatives with negative fair values should be reported as trading liabilities in Schedule RC, item 15. Changes in the fair value (that is, gains and losses) of trading derivatives should be recognized currently in earnings and included in Schedule RI, item 5.c, "Trading revenue."

Derivatives held for purposes other than trading that have positive fair values should be included in Schedule RC-F, item 5, "Other" assets, and, if the total fair value exceeds 25 percent of "Other" assets, this amount should be disclosed in Schedule RC-F, item 5.d. Derivatives held for purposes other than trading that have negative fair values should be included in Schedule RC-G, item 4, "Other" liabilities, and, if the total fair value exceeds 25 percent of "Other" liabilities, this amount should be disclosed in Schedule RC-G, item 4.d. Net gains (losses) on derivatives held for purposes other than trading that are not designated as hedging instruments should be recognized currently in earnings and reported consistently as either "Other noninterest income" or "Other noninterest expense" in Schedule RI, item 5.l or item 7.d, respectively.

Netting of derivative assets and liabilities is prohibited on the balance sheet except as permitted under FASB Interpretation No. 39. <u>See</u> the Glossary entry for "offsetting."

Banks must report the notional amounts of their derivative contracts by risk exposure in Schedule RC-L, first by type of contract in Schedule RC-L, item 11, and then by purpose of contract (i.e., trading, other than trading) in Schedule RC-L, items 12 and 13. Banks with foreign offices or with \$100 million or more in total assets must report the gross fair values of their derivatives, both positive and negative, by risk exposure and purpose of contract in Schedule RC-L, item 14.

Discounts: See "premiums and discounts."

Dividends: Cash dividends are payments of cash to stockholders in proportion to the number of shares they own. Cash dividends on preferred and common stock are to be reported on the date they are declared by the bank's board of directors (the declaration date) by debiting "retained earnings" and crediting "dividends declared not yet payable," which is to be reported in other liabilities. Upon payment of the dividend, "dividends declared not yet payable" is debited for the amount of the cash dividend with an offsetting credit, normally in an equal amount, to "dividend checks outstanding" which is reportable in the "demand deposits" category of the bank's deposit liabilities.

A liability for dividends payable may <u>not</u> be accrued in advance of the formal declaration of a dividend by the board of directors. However, the bank may segregate a portion of retained earnings in the form of a net worth reserve in anticipation of the declaration of a dividend.

Stock dividends are distributions of additional shares to stockholders in proportion to the number of shares they own. Stock dividends are to be reported by transferring an amount equal to the fair value of the additional shares issued from retained earnings to a category of permanent capitalization (common stock and surplus). However, the amount transferred from retained earnings must be reduced by the amount of any mandatory and discretionary transfers previously made (such as those from retained earnings to surplus for increasing the bank's legal lending limit) provided such transfers have not already been used to record a stock dividend. In any event, the amount transferred from retained earnings may not be less than the par or stated value of the additional shares being issued.

<u>Property dividends</u>, also known as dividends in kind, are distributions to stockholders of assets other than cash. The transfer of securities of other companies, real property, or any other asset owned by the reporting bank to a stockholder or related party is to be recorded at the fair value of the asset on the declaration date of the dividend. A gain or loss on the transferred asset must be recognized in the same manner as if the property had been disposed of in an outright sale at or near the declaration date. In those instances where a bank transfers bank premises to a parent holding company in the form of a property dividend and the parent immediately enters into a sale-leaseback transaction with a third party, the gain must be deferred by the bank and amortized over the life of the lease.

Domestic Office: For purposes of these reports, a domestic office of the reporting bank is a branch or subsidiary (other than an Edge or Agreement subsidiary) located in the 50 states of the United States or the District of Columbia or a branch on a U.S. military facility wherever located. The domestic offices of the reporting bank exclude all International Banking Facilities (IBFs); all offices of Edge and Agreement subsidiaries, including their U.S. offices; and all branches and other subsidiaries of the bank located in Puerto Rico, U.S. territories and possessions, or foreign countries.

Domicile: Domicile is used to determine the foreign (non-U.S. addressee) or domestic (U.S. addressee) status of a customer of the reporting bank for the purposes of these reports. Domicile is determined by the principal residence address of an individual or the principal business address of a corporation, partnership, or sole proprietorship. If other addresses are used for correspondence or other purposes, only the principal address, insofar as it is known to the reporting bank, should be used in determining whether a customer should be regarded as a U.S. or non-U.S. addressee.

For purposes of defining customers of the reporting bank, U.S. addressees include residents of the 50 states of the United States, the District of Columbia, Puerto Rico, and U.S. territories and possessions. Non-U.S. addressees includes residents of any foreign country. The term non-U.S. addressee generally includes foreign-based subsidiaries of other U.S. banks.

For customer identification purposes, the IBFs of other U.S. depository institutions are U.S. addressees. (This is in contrast to the treatment of the IBFs of the <u>reporting</u> bank, which are treated as foreign offices of the reporting bank.)

Due Bills: A due bill is an obligation that results when a bank sells an asset and receives payment, but does not deliver the security or other asset. A due bill can also result from a promise to deliver an asset in exchange for value received. In both cases, the receipt of the payment creates an obligation regardless of whether the due bill is issued in written form. Outstanding due bill obligations shall be reported as borrowings in Schedule RC, item 16, "Other borrowed money," by the issuing bank. Conversely, when the reporting bank is the holder of a due bill, the outstanding due bill obligation of the seller shall be reported as a loan to that party.

Edge and Agreement Corporation: An Edge corporation is a federally-chartered corporation organized under Section 25(a) of the Federal Reserve Act and subject to Federal Reserve Regulation K. Edge corporations are allowed to engage only in international banking or other financial transactions related to international business.

An <u>Agreement corporation</u> is a state-chartered corporation that has agreed to operate as if it were organized under Section 25 of the Federal Reserve Act and has agreed to be subject to Federal Reserve Regulation K. Agreement corporations are restricted, in general, to international banking operations. Banks must apply to the Federal Reserve for permission to acquire stock in an Agreement corporation.

A reporting bank's Edge or Agreement subsidiary, i.e., the bank's majority-owned Edge or Agreement corporation, is treated for purposes of these reports as a "foreign" office of the reporting bank.

Equity Method of Accounting: The equity method of accounting is used to account for investments in subsidiaries that have not been consolidated; associated companies; and corporate joint ventures, unincorporated joint ventures, general partnerships, and limited partnerships over which the bank exercises significant influence (collectively referred to as "investees").

Under the equity method, the carrying value a bank's investment in an investee is originally recorded at cost but is adjusted periodically to record as income the bank's proportionate share of the investee's earnings or losses and decreased by the amount of cash dividends or similar distributions received from the investee. For purposes of these reports, the date through which the carrying value of the bank's investment in an investee has been adjusted should, to the extent practicable, match the report date of the Report of Condition, but in no case differ by more than 93 days from the report.

See also "subsidiaries."

Extinguishments of Liabilities: The accounting and reporting standards for extinguishments of liabilities are set forth in FASB Statement No. 140, "Accounting for Transfers and Servicing of Financial Assets and Extinguishments of Liabilities." Under Statement No. 140, a bank should remove a previously recognized liability from its balance sheet if and only if the liability has been extinguished. A liability has been extinguished if either of the following conditions is met:

- (1) The bank pays the creditor and is relieved of its obligation for the liability. Paying the creditor includes delivering cash, other financial assets, goods, or services or the bank's reacquiring its outstanding debt.
- (2) The bank is legally released from being the primary obligor under the liability, either judicially or by the creditor.

Extraordinary Items: Extraordinary items are material events and transactions that are (1) unusual <u>and</u> (2) infrequent. Both of those conditions <u>must</u> exist in order for an event or transaction to be reported as an extraordinary item.

To be unusual, an event or transaction must be highly abnormal or clearly unrelated to the ordinary and typical activities of banks. An event or transaction that is beyond bank management's control is not automatically considered to be unusual.

To be infrequent, an event or transaction should not reasonably be expected to recur in the foreseeable future. Although the past occurrence of an event or transaction provides a basis for estimating the likelihood of its future occurrence, the absence of a past occurrence does not automatically imply that an event or transaction is infrequent.

Only a limited number of events or transactions qualify for treatment as extraordinary items. Among these are losses which result directly from a major disaster such as an earthquake (except in areas where earthquakes are expected to recur in the foreseeable future), an expropriation, or a prohibition under a newly enacted law or regulation.

For further information, see APB Opinion No. 30, "Reporting the Results of Operations."

Fails: When a bank has sold an asset and, on settlement date, does not deliver the security or other asset <u>and</u> does not receive payment, a sales fail exists. When a bank has purchased a security or other asset and, on settlement date, does not receive the asset <u>and</u> does not pay for it, a purchase fail exists. Fails do not affect the way securities are reported in the Reports of Condition and Income.

Federal Funds Transactions: For purposes of the Reports of Condition and Income, federal funds transactions involve the reporting bank's lending (federal funds sold) or borrowing (federal funds purchased) in domestic offices of immediately available funds under agreements or contracts that have an original maturity of one business day or roll over under a continuing contract. However, funds lent or borrowed in the form of securities resale or repurchase agreements, due bills, borrowings from the Discount and Credit Department of a Federal Reserve Bank, deposits with and advances from a Federal Home Loan Bank, and overnight loans for commercial and industrial purposes are excluded from federal funds. Transactions that are to be reported as federal funds transactions may be secured or unsecured or may involve an agreement to resell loans or other instruments that are not securities.

<u>Immediately available funds</u> are funds that the purchasing bank can either use or dispose of on the same business day that the transaction giving rise to the receipt or disposal of the funds is executed.

The borrowing and lending of immediately available funds has an original maturity of one business day if the funds borrowed on one business day are to be repaid or the transaction reversed on the next business day, that is, if immediately available funds borrowed today are to be repaid tomorrow (in tomorrow's immediately available funds). Such transactions include those made on a Friday to mature or be reversed the following Monday and those made on the last business day prior to a holiday (for either or both of the parties to the transaction) to mature or be reversed on the first business day following the holiday.

A <u>continuing contract</u> is a contract or agreement that remains in effect for more than one business day, but has no specified maturity and does not require advance notice of either party to terminate. Such contracts may also be known as rollovers or as open-ended agreements.

Federal funds may take the form of the following two types of transactions in domestic offices <u>provided</u> that the transactions meet the above criteria (i.e., immediately available funds with an original maturity of one business day or under a continuing contract):

Federal Funds Transactions (cont.):

(1) Unsecured loans (federal funds sold) or borrowings (federal funds purchased). (In some market usage, the term "fed funds" or "pure fed funds" is confined to unsecured loans of immediately available balances.)

(2) Purchases (sales) of financial assets (other than securities) under agreements to resell (repurchase) that have original maturities of one business day (or are under continuing contracts) and are in immediately available funds.

Any borrowing or lending of immediately available funds in domestic offices that has an original maturity of more than one business day, other than securities repurchase or resale agreements, is to be treated as a borrowing or as a loan, <u>not</u> as federal funds. Such transactions are sometimes referred to as "term federal funds."

Federally-Sponsored Lending Agency: A federally-sponsored lending agency is an agency or corporation that has been chartered, authorized, or organized as a result of federal legislation for the purpose of providing credit services to a designated sector of the economy. These agencies include Banks for Cooperatives, Federal Home Loan Banks, the Federal Home Loan Mortgage Corporation, Federal Intermediate Credit Banks, Federal Land Banks, the Federal National Mortgage Association, and the Student Loan Marketing Association.

Fees, Loan: See "loan fees."

Foreclosed Assets: The accounting and reporting standards for foreclosed assets are set forth in FASB Statement No. 15, "Accounting by Debtors and Creditors for Troubled Debt Restructurings," and FASB Statement No. 144, "Accounting for the Impairment or Disposal of Long-Lived Assets." A summary of the relevant provisions of these accounting standards follows. For further information, see FASB Statements No. 15 and 144.

A bank that receives from a borrower in full satisfaction of a loan either receivables from third parties, an equity interest in the borrower, or other types of assets (except long-lived assets that will be sold) shall account for those assets at their fair value at the time of the restructuring. A bank that receives long-lived assets that will be sold, such as real estate, from a borrower in full satisfaction of a loan shall account for those long-lived assets at their fair value less cost to sell. This fair value (less cost to sell) becomes the "cost" of the foreclosed asset. The amount, if any, by which the recorded amount of the loan exceeds the fair value (less cost to sell) of the asset is a loss which must be charged to the allowance for loan and lease losses at the time of foreclosure or repossession. (The recorded amount of the loan is the loan balance adjusted for any unamortized premium or discount and unamortized loan fees or costs, less any amount previously charged off, plus recorded accrued interest.)

If an asset is sold <u>shortly</u> after it is received in a foreclosure or repossession, it would generally be appropriate to substitute the value received in the sale (net of the cost to sell for long-lived assets that will be sold such as real estate) for the fair value (less cost to sell for long-lived assets that will be sold such as real estate) that had been estimated at the time of foreclosure or repossession. Any adjustments should be made to the loss charged against the allowance. In those cases where property is received in full satisfaction of an asset other than a loan (e.g., a debt security), the loss should be reported on the income statement in a manner consistent with the balance sheet classification of the asset satisfied.

Foreclosed Assets (cont.):

An asset received in partial satisfaction of a loan should be accounted for as described above and the recorded amount of the loan should be reduced by the fair value (less cost to sell) of the asset at the time of foreclosure.

For purposes of these reports, foreclosed assets include loans where the bank, as creditor, has received physical possession of a borrower's assets, regardless of whether formal foreclosure proceedings take place. In such situations, the secured loan should be recategorized on the balance sheet in the asset category appropriate to the underlying collateral (e.g., as other real estate owned for real estate collateral) and accounted for as described above.

The amount of any senior debt (principal and accrued interest) to which foreclosed real estate is subject at the time of foreclosure must be reported as a liability in Schedule RC, item 16, "Other borrowed money."

After foreclosure, each foreclosed real estate asset (including any real estate for which the bank receives physical possession, regardless of whether formal foreclosure proceedings take place) must be carried at the lower of (1) the fair value of the asset minus the estimated costs to sell the asset or (2) the cost of the asset (as defined in the preceding paragraphs). This determination must be made on an asset-by-asset basis. If the fair value of a foreclosed real estate asset minus the estimated costs to sell the asset is less than the asset's cost, the deficiency must be recognized as a valuation allowance against the asset which is created through a charge to expense. The valuation allowance should thereafter be increased or decreased (but not below zero) through charges or credits to expense for changes in the asset's fair value or estimated selling costs.

If an asset received in a foreclosure or repossession is held for more than a short period of time, any additional losses in value and any gain or loss from the sale or disposition of the asset shall <u>not</u> be reported as a loan or lease loss or recovery and shall <u>not</u> be debited or credited to the allowance for loan and lease losses. Such additional declines in value and the gain or loss from the sale or disposition shall be reported net on the income statement in Schedule RI, item 5.j, "Net gains (losses) on sales of other real estate owned."

<u>Dispositions of Foreclosed Real Estate</u> -- The primary accounting guidance for sales of foreclosed real estate is FASB Statement No. 66, "Accounting for Sales of Real Estate." This standard, which applies to all transactions in which the seller provides financing to the buyer of the real estate, establishes the following methods to account for dispositions of real estate. If a profit is involved in the sale of real estate, each method sets forth the manner in which the profit is to be recognized. Regardless of which method is used, however, any losses on the disposition of real estate should be recognized immediately.

<u>Full Accrual Method</u> -- Under the full accrual method, the disposition is recorded as a sale. Any profit resulting from the sale is recognized in full and the asset resulting from the seller's financing of the transaction is reported as a loan. This method may be used when the following conditions have been met:

- (1) A sale has been consummated;
- (2) The buyer's initial investment (down payment) and continuing investment (periodic payments) are adequate to demonstrate a commitment to pay for the property;
- (3) The receivable is not subject to future subordination; and
- (4) The usual risks and rewards of ownership have been transferred.

Guidelines for the minimum down payment that must be made in order for a transaction to qualify for the full accrual method are set forth in the Appendix A to FASB Statement No. 66. These vary

Foreclosed Assets (cont.):

from five percent to 25 percent of the property's sales value. These guideline percentages vary by type of property and are primarily based on the inherent risk assumed for the type and characteristics of the property. To meet the continuing investment criteria, the contractual loan payments must be sufficient to repay the loan over the customary loan term for the type of property involved. Such periods may range up to 30 years for loans on single family residential property.

<u>Installment Method</u> -- Dispositions of foreclosed real estate that do not qualify for the full accrual method may qualify for the installment method. This method recognizes a sale and the corresponding loan. Any profits on the sale are only recognized as the bank receives payments from the purchaser/borrower. Interest income is recognized on an accrual basis, when appropriate.

The installment method is used when the buyer's down payment is not adequate to allow use of the full accrual method but recovery of the cost of the property is reasonably assured if the buyer defaults. Assurance of recovery requires careful judgment on a case-by-case basis. Factors which should be considered include: the size of the down payment, loan-to-value ratios, projected cash flows from the property, recourse provisions, and guarantees.

Since default on the loan usually results in the seller's reacquisition of the real estate, reasonable assurance of cost recovery may often be achieved with a relatively small down payment. This is especially true in situations involving loans <u>with recourse</u> to borrowers who have verifiable net worth, liquid assets, and income levels. Reasonable assurance of cost recovery may also be achieved when the purchaser/borrower pledges additional collateral.

<u>Cost Recovery Method</u> -- Dispositions of foreclosed real estate that do not qualify for either the full accrual or installment methods are sometimes accounted for using the cost recovery method. This method recognizes a sale and the corresponding loan, but all income recognition is deferred. Principal payments are applied as a reduction of the loan balance and interest increases the unrecognized gross profit. No profit or interest income is recognized until either the aggregate payments by the borrower exceed the recorded amount of the loan or a change to another accounting method is appropriate (e.g., installment method). Consequently, the loan is maintained in nonaccrual status while this method is being used.

Reduced-Profit Method -- This method is used in certain situations where the bank receives an adequate down payment, but the loan amortization schedule does not meet the requirements for use of the full accrual method. The method recognizes a sale and the corresponding loan. However, like the installment method, any profit is apportioned over the life of the loan as payments are received. The method of apportionment differs from the installment method in that profit recognition is based on the present value of the lowest level of periodic payments required under the loan agreement.

Since sales with adequate down payments are generally not structured with inadequate loan amortization requirements, this method is seldom used in practice.

<u>Deposit Method</u> -- The deposit method is used in situations where a sale of the foreclosed real estate has not been consummated. It may also be used for dispositions that could be accounted for under the cost recovery method. Under this method a sale is not recorded and the asset continues to be reported as foreclosed real estate. Further, no profit or interest income is recognized. Payments received from the borrower are reported as a liability until sufficient payments or other events have occurred which allow the use of one of the other methods.

The preceding discussion represents a brief summary of the methods included in FASB Statement No. 66 for accounting for sales of real estate. Refer to FASB Statement No. 66 for a more complete description of the accounting principles that apply to sales of real estate, including the determination of the down payment percentage.

Foreign Banks: See "banks, U.S. and foreign."

Foreign Currency Transactions and Translation: Foreign currency transactions are transactions occurring in the ordinary course of business (e.g., purchases, sales, borrowings, and lendings) denominated in a currency other than the office's functional currency (as described below).

<u>Foreign currency translation</u>, on the other hand, is the process of translating financial statements from the foreign office's functional currency into the reporting currency. Such translation normally is performed only at reporting dates.

A <u>functional currency</u> is the currency of the primary economic environment in which an office operates. For most banks, the functional currency will be the U.S. dollar. However, if a bank has foreign offices, one or more foreign offices may have a functional currency other than the U.S. dollar.

Accounting for foreign currency transactions -- A change in exchange rates between the functional currency and the currency in which a transaction is denominated will increase or decrease the amount of the functional currency expected to be received or paid. These increases or decreases in the expected functional currency cash flow are foreign currency transaction gains and losses and are to be included in the determination of the income of the period in which the transaction takes place, or if the transaction has not yet settled, the period in which the rate change takes place.

Except for foreign currency derivatives and transactions described in the following section, banks should consistently report net gains (losses) from foreign currency transactions other than trading transactions in Schedule RI, item 5.I, "Other noninterest income," or item 7.d, "Other noninterest expense." Net gains (losses) from foreign currency trading transactions should be reported in Schedule RI, item 5.c, "Trading revenue."

Foreign currency transaction gains or losses to be excluded from the determination of net income -- Gains and losses on the following foreign currency transactions shall not be included in "Noninterest income" or "Noninterest expense," but shall be reported in the same manner as translation adjustments (as described below):

- (1) Foreign currency transactions that are designated as, and are effective as, economic hedges of a net investment in a foreign office.
- (2) Intercompany foreign currency transactions that are of a long-term investment nature (i.e., settlement is not planned or anticipated in the foreseeable future), when the parties to the transaction are consolidated, combined, or accounted for by the equity method in the bank's Reports of Condition and Income.

<u>See</u> the Glossary entry for "derivative contracts" for information on the accounting and reporting for foreign currency derivatives.

Accounting for foreign currency translation (applicable only to banks with foreign offices)--The Reports of Condition and Income must be reported in U.S. dollars. Balances of foreign subsidiaries or branches of the reporting bank denominated in a functional currency other than U.S. dollars shall be converted to U.S. dollar equivalents and consolidated into the reporting bank's Reports of Condition and Income. The translation adjustments for each reporting period, determined utilizing the current rate method, should be reported in Schedule RI-A, item 10, "Other comprehensive income." Amounts accumulated in the "Cumulative foreign currency translation adjustments" component of "Accumulated other comprehensive income" in Schedule RC, item 26.b, will not be included in the bank's results of operations until such time as the foreign office is disposed of, when they will be used as an element to determine the gain or loss on disposition.

For further guidance, refer to FASB Statement No. 52, "Foreign Currency Translation."

Foreign Debt Exchange Transactions: Foreign debt exchange transactions generally fall into three categories: (1) loan swaps, (2) debt/equity swaps, and (3) debt-for-development swaps. These transactions are to be reported in the Reports of Condition and Income in accordance with generally accepted accounting principles as summarized below. The accounting pronouncements mentioned below should be consulted for more detailed reporting guidance in these areas.

Generally accepted accounting principles require that these transactions be reported at their fair value. There is a significant amount of precedent in the accounting for exchange transactions to consider both the fair value of the consideration given up as well as the fair value of the assets received in arriving at the most informed valuation, especially if the value of the consideration given up is not readily determinable or may not be a good indicator of the value received. It is the responsibility of management to make the valuation considering all of the circumstances. Such valuations are subject to examiner review.

Among the factors to consider in determining fair values for foreign debt exchange transactions are:

- (1) Similar transactions for cash;
- (2) Estimated cash flows from the debt or equity instruments or other assets received;
- (3) Market values, if any, of similar instruments; and
- (4) Currency restrictions, if any, affecting payments on or sales of the debt or equity instruments, local currency, or other assets received, including where appropriate those affecting the repatriation of capital.

Losses arise from swap transactions when the fair value determined for the transaction is less than the recorded investment in the sovereign debt and other consideration paid, if any. Such losses should generally be charged to the allowance for loan and lease losses (or allocated transfer risk reserve, if appropriate) and must include any discounts from official exchange rates that are imposed by sovereign obligors as transaction fees. All other fees and transaction costs involved in such transactions must be charged to expense as incurred.

Loss recoveries or even gains might be indicated in a swap transaction as a result of the valuation process. However, due to the subjective nature of the valuation process, such loss recoveries or gains ordinarily should not be recorded until the debt or equity instruments, local currency, or other assets received in the exchange transaction are realized in unrestricted cash or cash equivalents.

Loan swaps -- The reporting guidance for this type of transaction is presented in the AICPA's Notice to Practitioners, "Accounting for Foreign Loan Swaps," issued on May 27, 1985.

Foreign loan swaps, or debt/debt swaps, involve the exchange of one foreign loan for another. This type of transaction represents an exchange of monetary assets that must be reported at current fair value. Normally, when monetary assets are exchanged, with or without additional cash payments, and the parties have no remaining obligations to each other, the earnings process is complete.

Debt/equity swaps -- The reporting treatment for this type of transaction is presented in AICPA Practice Bulletin No. 4, "Accounting for Foreign Debt/Equity Swaps."

A foreign debt/equity swap represents an exchange of monetary for nonmonetary assets that must be measured at fair value. This type of swap is typically accomplished when holders of U.S. dollar-denominated sovereign debt agree to convert that debt into approved local equity investments. The holders are generally credited with local currency at the official exchange rate. A discount from the

Foreign Debt Exchange Transactions (cont.):

official exchange rate is often imposed as a transaction fee. The local currency is generally not available to the holders for any purposes other than approved equity investments. Restrictions may be placed on dividends on the equity investments and capital usually cannot be repatriated for several years.

In arriving at the fair value of the transaction, both the secondary market price of the debt given up and the fair value of the equity investment or assets received should be considered.

<u>Debt-for-development swaps</u> -- In this type of exchange, sovereign debt held by a bank is generally purchased by a nonprofit organization or contributed to the nonprofit the nonprofit organization. When the sovereign debt is purchased by or donated to a nonprofit organization, the organization may enter into an agreement with the debtor country to cancel the debt in return for the country's commitment to provide local currency or other assets for use in connection with specific projects or programs in that country. Alternatively, a bank may exchange the sovereign debt with the country and receive local currency. In this alternative, the local currency will be donated or sold to the nonprofit organization for use in connection with specific projects or programs in that country.

These transactions, including amounts charged to expense as donations, must be reported at their fair values in accordance with generally accepted accounting principles applicable to foreign debt exchange transactions. This includes appropriate consideration of the market value of the instruments involved in the transaction and the fair value of any assets received, taking into account any restrictions that would limit the use of the assets. In debt-for-development swaps where a bank receives local currency in exchange for the sovereign loan it held and the local currency has no restrictions on its use and is freely convertible, it is generally appropriate for fair value to be determined by valuing the local currency received at its fair market exchange value.

Foreign Governments and Official Institutions: Foreign governments and official institutions are central, state, provincial, and local governments in foreign countries and their ministries, departments, and agencies. These include treasuries, ministries of finance, central banks, development banks, exchange control offices, stabilization funds, diplomatic establishments, fiscal agents, and nationalized banks and other banking institutions that are owned by central governments and that have as an important part of their function activities similar to those of a treasury, central bank, exchange control office, or stabilization fund. For purposes of these reports, other government-owned enterprises are not included.

Also included as foreign official institutions are international, regional, and treaty organizations, such as the International Monetary Fund, the International Bank for Reconstruction and Development (World Bank), the Bank for International Settlements, the Inter-American Development Bank, and the United Nations.

Foreign Office: For purposes of these reports, a foreign office of the reporting bank is a branch or subsidiary located in Puerto Rico, in a U.S. territory or possession, or in a foreign country; an Edge or Agreement subsidiary, including both its U.S. and its foreign offices; or an IBF. Branches on U.S. military facilities wherever located are treated as domestic offices, <u>not</u> foreign offices.

Forward Contracts: See "derivative contracts."

Functional Currency: See "foreign currency transactions and translation."

Futures Contracts: See "derivative contracts."

Goodwill: See "purchase acquisition" in the entry for "business combinations."

Hypothecated Deposit: A hypothecated deposit is the aggregation of periodic payments on an installment contract received by a reporting institution in a state in which, under law, such payments are not immediately used to reduce the unpaid balance of the installment note, but are accumulated until the sum of the payments equals the entire amount of principal and interest on the contract, at which time the loan is considered paid in full. For purposes of these reports, hypothecated deposits are to be netted against the related loans.

Deposits that simply serve as collateral for loans are not considered hypothecated deposits for purposes of these reports.

See also "deposits."

IBF: See "International Banking Facility (IBF)."

Income Taxes: All banks, regardless of size, are required to report income taxes (federal, state and local, and foreign) in the Reports of Condition and Income on an accrual basis. Note that, in almost all cases, applicable income taxes as reported on the Report of Income will differ from amounts reported to taxing authorities. The applicable income tax expense or benefit that is reflected in the Report of Income should include both taxes currently paid or payable (or receivable) and deferred income taxes. The following discussion of income taxes is based on FASB Statement No. 109, "Accounting for Income Taxes."

Applicable income taxes in the year-end Report of Income shall be the sum of the following:

(1) Taxes currently paid or payable (or receivable) for the year determined from the bank's federal, state, and local income tax returns for that year. Since the bank's tax returns will not normally be prepared until after the year-end Reports of Condition and Income have been completed, the bank must estimate the amount of the current income tax liability (or receivable) that will ultimately be reported on its tax returns. Estimation of this liability (or receivable) may involve consultation with the bank's tax advisers, a review of the previous year's tax returns, the identification of significant expected differences between items of income and expense reflected on the Report of Income and on the tax returns, and the identification of expected tax credits.)

and

(2) Deferred income tax expense or benefit measured as the change in the net deferred tax assets or liabilities for the period reported. Deferred tax liabilities and assets represent the amount by which taxes payable (or receivable) are expected to increase or decrease in the future as a result of "temporary differences" and net operating loss or tax credit carryforwards that exist at the reporting date.

The actual tax liability (or receivable) calculated on the bank's tax returns may differ from the estimate reported as currently payable or receivable on the year-end Report of Income. An amendment to the bank's year-end and subsequent Reports of Condition and Income may be appropriate if the difference is significant. Minor differences should be handled as accrual adjustments to applicable income taxes in Reports of Income during the year the differences are detected. The reporting of applicable income taxes in the Report of Income for report dates other than year-end is discussed below under "interim period applicable income taxes."

Income Taxes (cont.):

<u>Temporary differences</u> result when events are recognized in one period on the bank's books but are recognized in another period on the bank's tax return. These differences result in amounts of income or expense being reported in the Report of Income in one period but in another period in the tax returns. There are two types of temporary differences. Deductible temporary differences reduce taxable income in future periods. Taxable temporary differences result in additional taxable income in future periods.

For example, a bank's provision for loan and lease losses is expensed for financial reporting purposes in one period. However, for some banks, this amount may not be deducted for tax purposes until the loans are actually charged off in a subsequent period. This deductible temporary difference "originates" when the provision for loan and lease losses is recorded in the financial statements and "turns around" or "reverses" when the loans are subsequently charged off, creating tax deductions. Other deductible temporary differences include writedowns of other real estate owned, the recognition of loan origination fees, and other postemployment benefits expense.

Depreciation can result in a taxable temporary difference if a bank uses the straight-line method to determine the amount of depreciation expense to be reported in the Report of Income but uses an accelerated method for tax purposes. In the early years, tax depreciation under the accelerated method will typically be larger than book depreciation under the straight-line method. During this period, a taxable temporary difference originates. Tax depreciation will be less than book depreciation in the later years when the temporary difference reverses. Therefore, in any given year, the depreciation reported in the Report of Income will differ from that reported in the bank's tax returns. However, total depreciation taken over the useful life of the asset will be the same under either method. Other taxable temporary differences include the undistributed earnings of unconsolidated subsidiaries and associated companies and amounts funded to pension plans that exceed the recorded expense.

Some events do not have tax consequences and therefore do not give rise to temporary differences. Certain revenues are exempt from taxation and certain expenses are not deductible. These events were previously known as "permanent differences." Examples of such events (for federal income tax purposes) are interest received on certain obligations of states and political subdivisions in the U.S., premiums paid on officers' life insurance policies where the bank is the beneficiary, and 70 percent of cash dividends received on the corporate stock of domestic U.S. corporations owned less than 20 percent.

<u>Deferred tax assets</u> shall be calculated at the report date by applying the "applicable tax rate" (defined below) to the bank's total deductible temporary differences and operating loss carryforwards. A deferred tax asset shall also be recorded for the amount of tax credit carryforwards available to the bank. Based on the estimated realizability of the deferred tax asset, a valuation allowance should be established to reduce the recorded deferred tax asset to the amount that is considered "more likely than not" (i.e., greater than 50 percent chance) to be realized.

<u>Deferred tax liabilities</u> should be calculated by applying the "applicable tax rate" to total taxable temporary differences at the report date.

Operating loss carrybacks and carryforwards and tax credit carryforwards -- When a bank's deductions exceed its income for federal income tax purposes, it has sustained an operating loss. An operating loss that occurs in a year following periods when the bank had taxable income may be carried back to recover income taxes previously paid. The tax effects of any loss carrybacks that are realizable through a refund of taxes previously paid is recognized in the year the loss occurs. In this situation, the applicable income taxes on the Report of Income will reflect a credit rather than an expense. Banks may carry back operating losses for two years.

Income Taxes (cont.):

Generally, an operating loss that occurs when loss carrybacks are not available (e.g., occurs in a year following periods of losses) becomes an operating loss carryforward. Banks may carry operating losses forward 20 years.

Tax credit carryforwards are tax credits which cannot be used for tax purposes in the current year, but which can be carried forward to reduce taxes payable in a future period.

Deferred tax assets are recognized for operating loss and tax credit carryforwards just as they are for deductible temporary differences. As a result, a bank can recognize the benefit of a net operating loss for tax purposes or a tax credit carryforward to the extent the bank determines that a valuation allowance is not considered necessary (i.e., if the realization of the benefit is more likely than not).

Applicable tax rate -- The income tax rate to be used in determining deferred tax assets and liabilities is the rate under current tax law that is expected to apply to taxable income in the periods in which the deferred tax assets or liabilities are expected to be realized or paid. If the bank's income level is such that graduated tax rates are a significant factor, then the bank shall use the average graduated tax rate applicable to the amount of estimated taxable income in the period in which the deferred tax asset or liability is expected to be realized or settled. When the tax law changes, banks shall determine the effect of the change, adjust the deferred tax asset or liability and include the effect of the change in Schedule RI, item 9, "Applicable income taxes (on item 8)."

<u>Valuation allowance</u> -- A valuation allowance must be recorded, if needed, to reduce the amount of deferred tax assets to an amount that is more likely than not to be realized. Changes in the valuation allowance generally shall be reported in Schedule RI, item 9, "Applicable income taxes (on item 8)." The following discussion of the valuation allowance relates to the allowance, if any, included in the amount of net deferred tax assets or liabilities to be reported on the balance sheet (Schedule RC) and in Schedule RC-F, item 2, or Schedule RC-G, item 2. This discussion does not address the determination of the amount of deferred tax assets, if any, that is disallowed for regulatory capital purposes and reported in Schedule RC-R, item 9.

Banks must consider all available evidence, both positive and negative, in assessing the need for a valuation allowance. The future realization of deferred tax assets ultimately depends on the existence of sufficient taxable income of the appropriate character in either the carryback or carryforward period. Four sources of taxable income may be available to realize the deferred tax assets:

- (1) Taxable income in carryback years (which can be offset to recover taxes previously paid),
- (2) Reversing taxable temporary differences,
- (3) Future taxable income (exclusive of reversing temporary differences and carryforwards.
- (4) Tax-planning strategies.

In general, positive evidence refers to the existence of one or more of the four sources of taxable income. To the extent evidence about one or more sources of income is sufficient to support a conclusion that a valuation allowance is not necessary (i.e., the bank can conclude that the deferred tax asset is more likely than not to be realized), other sources need not be considered. However, if a valuation allowance is needed, each source of income must be evaluated to determine the appropriate amount of the allowance needed.

Evidence used in determining the valuation allowance should be subject to objective verification. The weight given to evidence when both positive and negative evidence exist should be consistent with the extent to which it can be verified. Sources (1) and (2) listed above are more susceptible to objective verification and, therefore, may provide sufficient evidence regardless of future events.

Income Taxes (cont.):

The consideration of future taxable income (exclusive of reversing temporary differences and carryforwards) as a source for the realization of deferred tax assets will require subjective estimates and judgments about future events which may be less objectively verifiable.

Examples of <u>negative evidence</u> include:

- Cumulative losses in recent years.
- A history of operating loss or tax credit carryforwards expiring unused.
- Losses expected in early future years by a presently profitable bank.
- Unsettled circumstances that, if unfavorably resolved, would adversely affect future profit levels.
- A brief carryback or carryforward that would limit the ability to realize the deferred tax asset.

Examples of <u>positive evidence</u> include:

- A strong earnings history exclusive of the loss that created the future deductible amount (tax loss carryforward or deductible temporary difference) coupled with evidence indicating that the loss is an aberration rather than a continuing condition.
- Existing contracts that will generate significant income.
- An excess of appreciated asset value over the tax basis of an entity's net assets in an amount sufficient to realize the deferred tax asset.

When realization of a bank's deferred tax assets is dependent upon future taxable income, the reliability of a bank's projections is very important. The bank's record in achieving projected results under an actual operating plan will be a strong measure of this reliability. Other factors a bank should consider in evaluating evidence about its future profitability include but are not limited to current and expected economic conditions, concentrations of credit risk within specific industries and geographical areas, historical levels and trends in past due and nonaccrual assets, historical levels and trends in loan loss reserves, and the bank's interest rate sensitivity.

When strong negative evidence, such as the existence of cumulative losses, exists, it is extremely difficult for a bank to determine that no valuation allowance is needed. Positive evidence of significant quality and quantity would be required to counteract such negative evidence.

For purposes of determining the valuation allowance, a <u>tax-planning strategy</u> is a prudent and feasible action that would result in realization of deferred tax assets and that management ordinarily might not take, but would do so to prevent an operating loss or tax credit carryforward from expiring unused. For example, a bank could accelerate taxable income to utilize carryforwards by selling or securitizing loan portfolios, selling appreciated securities, or restructuring nonperforming assets. Actions that management would take in the normal course of business are <u>not</u> considered tax-planning strategies.

Significant expenses to implement the tax-planning strategy and any significant losses that would result from implementing the strategy shall be considered in determining any benefit to be realized from the tax-planning strategy. Also, banks should consider all possible consequences of any tax-planning strategies. For example, loans pledged as collateral would not be available for sale.

The determination of whether a valuation allowance is needed for deferred tax assets should be made for total deferred tax assets, not for deferred tax assets net of deferred tax liabilities. In addition, the evaluation should be made on a jurisdiction-by-jurisdiction basis. Separate analyses should be performed for amounts related to each taxing authority (e.g., federal, state, and local).

Deferred tax assets (net of the valuation allowance) and deferred tax liabilities related to a particular tax jurisdiction (e.g., federal, state, and local) may be offset against each other for reporting purposes. A resulting debit balance shall be included in "Other assets" and reported in Schedule RC-F, item 2. A

Income Taxes (cont.):

resulting credit balance shall be included in "Other liabilities" and reported in Schedule RC-G, item 2. (A bank may report a net deferred tax debit, or asset, for one tax jurisdiction (e.g., federal taxes) and also report a net deferred tax credit, or liability, for another tax jurisdiction (e.g., state taxes).

Interim period applicable income taxes -- When preparing its year-to-date Report of Income as of the end of March, June, and September ("interim periods"), a bank generally should determine its best estimate of its effective annual tax rate for the full year, including both current and deferred portions and considering all tax jurisdictions (e.g., federal, state and local). To arrive at its estimated effective annual tax rate, a bank should divide its estimated total applicable income taxes (current and deferred) for the year by its estimated pretax income for the year (excluding extraordinary items). This rate would then be applied to the year-to-date pretax income to determine the year-to-date applicable income taxes at the interim date.

Intraperiod allocation of income taxes -- When the Report of Income for a period includes "Extraordinary items and other adjustments" that are reportable in Schedule RI, item 11, the total amount of the applicable income taxes for the year to date shall be allocated in Schedule RI between item 9, "Applicable income taxes (on item 8)," and item 11, "Extraordinary items and other adjustments, net of income taxes."

The applicable income taxes on operating income (item 9) shall be the amount that the total applicable income taxes on pretax income, including both current and deferred taxes (calculated as described above), would have been for the period had "Extraordinary items and other adjustments" been zero. The difference between item 9, "Applicable income taxes (on item 8)," and the total amount of the applicable taxes shall then be reflected in item 11 as applicable income taxes on extraordinary items and other adjustments.

Tax calculations by tax jurisdiction -- Separate calculations of income taxes, both current and deferred amounts, are required for each tax jurisdiction. However, if the tax laws of the state and local jurisdictions do not significantly differ from federal income tax laws, then the calculation of deferred income tax expense can be made in the aggregate. The bank would calculate both current and deferred tax expense considering the combination of federal, state and local income tax rates. The rate used should consider whether amounts paid in one jurisdiction are deductible in another jurisdiction. For example, since state and local taxes are deductible for federal purposes, the aggregate combined rate would generally be (1) the federal tax rate plus (2) the state and local tax rates minus (3) the federal tax effect of the deductibility of the state and local taxes at the federal tax rate.

Income taxes of a bank subsidiary of a holding company -- A bank should generally report income tax amounts in its Reports of Condition and Income as if it were a separate entity. A bank's separate entity taxes include taxes of subsidiaries of the bank that are included with the bank in a consolidated tax return. In other words, when a bank has subsidiaries of its own, the bank and its consolidated subsidiaries are treated as one separate taxpayer for purposes of computing the bank's applicable income taxes. This treatment is also applied in determining net deferred tax asset limitations for regulatory capital purposes.

During profitable periods, a bank subsidiary of a holding company that files a consolidated tax return should record current tax expense for the amount that would be due on a separate entity basis. Certain adjustments resulting from the consolidated status may, however, be made to the separate entity calculation as long as these adjustments are made on a consistent and equitable basis. For example, the consolidated group's single surtax exemption may be allocated among the holding company affiliates if such an allocation is equitable and applied consistently. Such allocations should be reflected in the bank's applicable income taxes, rather than as "Other transactions with parent holding company" in Schedule RI-A, Changes in Equity Capital.

Income Taxes (cont.):

In addition, bank subsidiaries should first compute their taxes on a separate entity basis without considering the alternative minimum tax (AMT). The AMT should be determined on a consolidated basis, and if it exceeds the regular tax on a consolidated basis, the holding company should allocate that excess to its affiliates on an equitable and consistent basis. The allocation method must be based upon the portion of tax preferences, adjustments, and other items causing the AMT to be applicable at the consolidated level that are generated by the parent holding company and each bank and nonbank subsidiary. In no case should amounts be allocated to bank subsidiaries that have not generated any tax preference or positive tax adjustment items. Furthermore, the AMT allocated to banks within the consolidated group should not exceed the consolidated AMT in any year.

In future years when a consolidated AMT credit carryforward is utilized, the credit must be reallocated to the subsidiary banks. The allocation should be done on an equitable and consistent basis based upon the amount of AMT giving rise to the credit that had been previously allocated. In addition, the amount of AMT credit reallocated to affiliates within the consolidated group should not exceed the consolidated AMT credit in any year. All AMT allocations should be reflected in the bank's applicable income taxes, rather than as "Other transactions with parent holding company" in Schedule RI-A, Changes in Equity Capital.

Similarly, bank subsidiaries incurring a loss should record an income tax benefit and receive an equitable refund from their parent, if appropriate. The refund should be based on the amount they would have received on a separate entity basis, adjusted for statutory tax considerations, and shall be made on a timely basis.

An exception to this rule is made when the bank, on a separate entity basis, would not be entitled to a current refund because it has exhausted benefits available through carryback on a separate entity basis, yet the holding company can utilize the bank's tax loss to reduce the <u>consolidated</u> liability for the current year. In this situation, realization of the tax benefit is assured. Accordingly, the bank may recognize a current tax benefit in the year in which the operating loss occurs, <u>provided</u> the holding company reimburses the bank on a timely basis for the amount of benefit recognized. Any such tax benefits recognized in the loss year should be reflected in the bank's applicable income taxes and not as an extraordinary item. If timely reimbursement is not made, the bank cannot recognize the tax benefit in the current year. Rather, the tax loss becomes a net operating loss carryforward for the bank.

A parent holding company shall not adopt an <u>arbitrary</u> tax allocation policy within its consolidated group if it results in a significantly different amount of subsidiary bank applicable income taxes than would have been provided on a separate entity basis. If a holding company forgives payment by the subsidiary of all or a significant portion of the current portion of the applicable income taxes computed in the manner discussed above, such forgiveness should be treated as a capital contribution and reported in Schedule RI-A in "Other transactions with parent holding company" and in Schedule RI-E, item 5.

Further, if the subsidiary bank pays an amount greater than its separate entity current tax liability (calculated as previously discussed), the excess should be reported as a cash dividend to the holding company in Schedule RI-A, item 9. Payment by the bank of its deferred tax liability, in addition to its current tax liability, is considered an excessive payment of taxes. As a result, the deferred portion should likewise be reported as a cash dividend. Failure to pay the subsidiary bank an equitable refund attributable to the bank's net operating loss should also be considered a cash dividend paid by the bank to the parent holding company.

Income Taxes (cont.):

<u>Purchase business combinations</u> -- In purchase business combinations (as described in the Glossary entry for "business combinations"), banks shall recognize as a temporary difference the difference between the tax basis of acquired assets or liabilities and the amount of the purchase price allocated to the acquired assets and liabilities (with certain exceptions specified in FASB Statement No. 109). As a result, the acquired asset or liability shall be recorded gross and a deferred tax asset or liability shall be recorded for any resulting temporary difference.

In a purchase business combination, a deferred tax asset shall generally be recognized at the date of acquisition for deductible temporary differences and net operating loss and tax credit carryforwards of either company in the transaction, net of an appropriate valuation allowance. The determination of the valuation allowance should consider any provisions in the tax law that may restrict the use of an acquired company's carryforwards.

Subsequent recognition (i.e., by elimination of the valuation allowance) of the benefit of deductible temporary differences and net operating loss or tax credit carryforwards not recognized at the acquisition date will depend on the source of the benefit. If the valuation allowance relates to deductible temporary differences and carryforwards of the acquiring company established before the acquisition, then subsequent recognition is reported as a reduction of income tax expense. If the benefit is related to the acquired company's deductible temporary differences and carryforwards, then the benefit is subsequently recognized by first reducing any goodwill related to the acquisition, then by reducing all other noncurrent intangible assets related to the acquisition, and finally, by reducing income tax expense.

Alternative Minimum Tax -- Any taxes a bank must pay in accordance with the alternative minimum tax (AMT) shall be included in the bank's current tax expense. Amounts of AMT paid can be carried forward in certain instances to reduce the bank's regular tax liability in future years. The bank may record a deferred tax asset for the amount of the AMT credit carryforward, which shall then be evaluated in the same manner as other deferred tax assets to determine whether a valuation allowance is needed.

Other tax effects -- A bank may have transactions or items that are reportable in Schedule RI-A of the Report of Income such as "Restatements due to corrections of material accounting errors and changes in accounting principles," and, on the FFIEC 031 only, "Foreign currency translation adjustments" that are included in "Other comprehensive income." These transactions or other items will enter into the determination of taxable income in some year (not necessarily the current year), but are not included in the pretax income reflected in Schedule RI of the Report of Income. They shall be reported in Schedule RI-A net of related income tax effects. These effects may increase or decrease the bank's total tax liability calculated on its tax returns for the current year or may be deferred to one or more future periods.

For further information, see FASB Statement No. 109, "Accounting for Income Taxes."

Income Taxes (cont.):

The following table has been included to aid banks in calculating their "applicable income taxes" for purposes of the Reports of Condition and Income. The table includes the tax rates in effect for the years presented.

FEDERAL INCOME TAX RATES APPLICABLE TO BANKS

<u>Year</u>	First <u>\$25,000</u>	Second <u>\$25,000</u>	Third <u>\$25,000</u>	Fourth \$25,000		Capital Alternative Gains Minimum Tax
1993-2001	15%	15%	25%	34%	1	Regular 20% tax rates

Intangible Assets: See "business combinations" and the instruction to Report of Condition Schedule RC-M, item 2.

Interest-Bearing Account: See "deposits."

Interest Capitalization: See "capitalization of interest costs."

Interest Rate Swaps: See "derivative contracts."

Internal-Use Computer Software: Guidance on the accounting and reporting for the costs of internal-use computer software is set forth in AICPA Statement of Position 98-1, "Accounting for the Costs of Computer Software Developed or Obtained for Internal Use." A summary of this accounting guidance follows. For further information, see AICPA Statement of Position 98-1.

Internal-use computer software is software that meets both of the following characteristics:

- (1) The software is acquired, internally developed, or modified solely to meet the bank's internal needs; and
- (2) During the software's development or modification, no substantive plan exists or is being developed to market the software externally.

Statement of Position 98-1 identifies three stages of development for internal-use software: the preliminary project stage, the application development stage, and the post-implementation/operation stage. The processes that occur during the preliminary project stage of software development are the conceptual formulation of alternatives, the evaluation of alternatives, the determination of the existence of needed technology, and the final selection of alternatives. The application development stage involves the design of the chosen path (including software configuration and software interfaces), coding, installation of software to hardware, and testing (including the parallel processing phase). Generally, training and application maintenance occur during the post-implementation/operation stage. Upgrades of and enhancements to existing internal-use software, i.e., modifications to software that result in additional functionality, also go through the three aforementioned stages of development.

FFIEC 031 and 041 A-48 GLOSSARY

A 39% tax rate applies to taxable income from \$100,001 to \$335,000; a 34% tax rate applies to taxable income from \$335,001 to \$10,000,000; a tax rate of 35% applies to taxable income from \$10,000,001 to \$15,000,000; a taxrate of 38% applies to taxable income from \$15,000,001 to \$18,333,333; and a 35% tax rate applies to taxable income over \$18,333,333.

Internal-Use Computer Software (cont.):

Computer software costs that are incurred in the preliminary project stage should be expensed as incurred.

Internal and external costs incurred to develop internal-use software during the application development stage should be capitalized. Capitalization of these costs should begin once (a) the preliminary project stage is completed and (b) management, with the relevant authority, implicitly or explicitly authorizes and commits to funding a computer software project and it is probable that the project will be completed and the software will be used to perform the function intended. Capitalization should cease no later than when a computer software project is substantially complete and ready for its intended use, i.e., after all substantial testing is completed. Capitalized internal-use software costs generally should be amortized on a straight-line basis overthe estimated useful life of the software.

Only the following application development stage costs should be capitalized:

- (1) External direct costs of materials and services consumed in developing or obtaining internal-use software:
- (2) Payroll and payroll-related costs for employees who are directly associated with and who devote time to the internal-use computer software project (to the extent of the time spent directly on the project); and
- (3) Interest costs incurred when developing internal-use software.

Costs to develop or obtain software that allows for access or conversion of old data by new systems also should be capitalized. Otherwise, data conversion costs should be expensed as incurred. General and administrative costs and overhead costs should not be capitalized as internal-use software costs.

During the post-implementation/operation stage, internal and external training costs and maintenance costs should be expensed as incurred.

Impairment of capitalized internal-use computer software costs should be recognized and measured in accordance with FASB Statement No. 121, "Accounting for the Impairment of Long-Lived Assets and for Long-Lived Assets to Be Disposed Of."

The costs of internally developed computer software to be sold, leased, or otherwise marketed as a separate product or process should be reported in accordance with FASB Statement No. 86, "Accounting for the Costs of Computer Software to Be Sold, Leased, or Otherwise Marketed." If, after the development of internal-use software is completed, a bank decides to market the software, proceeds received from the license of the software, net of direct incremental marketing costs, should be applied against the carrying amount of the software.

International Banking Facility (IBF): General definition. -- An International Banking Facility (IBF) is a set of asset and liability accounts, segregated on the books and records of the establishing entity, which reflect international transactions. An IBF is established in accordance with the terms of Federal Reserve Regulation D and after appropriate notification to the Federal Reserve. The establishing entity may be a U.S. depository institution, a U.S. office of an Edge or Agreement corporation, or a U.S. branch or agency of a foreign bank pursuant to Federal Reserve Regulations D and Q. An IBF is permitted to hold only certain assets and liabilities. In general, IBF accounts are limited, as specified in the paragraphs below, to non-U.S. residents of foreign countries, residents of Puerto Rico and U.S. territories and possessions, other IBFs, and U.S. and non-U.S. offices of the establishing entity.

International Banking Facility (IBF) (cont.):

Permissible IBF assets include extensions of credit to the following:

- (1) non-U.S. residents (including foreign branches of other U.S. banks);
- (2) other IBFs; and
- (3) U.S. and non-U.S. offices of the establishing entity.

Credit may be extended to non-U.S. <u>nonbank</u> residents only if the funds are used in their operations outside the United States. IBFs may extend credit in the form of a loan, deposit, placement, advance, security, or other similar asset.

<u>Permissible IBF liabilities</u> include (as specified in Federal Reserve Regulations D and Q) liabilities to non-U.S. nonbank residents only if such liabilities have a minimum maturity or notice period of at least two business days. IBF liabilities also may include overnight liabilities to:

- (1) non-U.S. offices of other depository institutions and of Edge or Agreement corporations;
- (2) non-U.S. offices of foreign banks;
- (3) foreign governments and official institutions;
- (4) other IBFs; and
- (5) the establishing entity.

IBF liabilities may be issued in the form of deposits, borrowings, placements, and other similar instruments. However, IBFs are prohibited from issuing negotiable certificates of deposit, bankers acceptances, or other negotiable or bearer instruments.

Treatment of the reporting bank's IBFs in the Reports of Condition and Income -- IBFs established by the reporting bank (i.e., by the bank or by its Edge or Agreement subsidiaries) are to be consolidated in the Reports of Condition and Income. In the consolidated balance sheet (Schedule RC) and income statement (Schedule RI), transactions between the IBFs of the reporting bank and between these IBFs and other offices of the bank are to be eliminated. (See the discussion of consolidation in the General Instructions section of this book.)

For purposes of these reports, the reporting bank's IBFs are to be treated as foreign offices of the bank. Thus, a bank with an IBF, even if it has no other foreign offices, must submit the Reports of Condition and Income applicable to banks with foreign offices (FFIEC 031). Similarly, the reporting bank's IBFs are to be treated as foreign offices where, in the supporting schedules, a distinction is made between foreign and domestic offices of the reporting bank.

Assets of the reporting bank's IBFs should be reported in the asset categories of the report by type of instrument and customer, as appropriate. For example, IBFs are to report their holdings of securities in Schedule RC, item 2, and in the appropriate items of Schedule RC-B; their holdings of loans that the IBF has the intent and ability to hold for the foreseeable future or until maturity or payoff in Schedule RC, item 4.b, and in the appropriate items of Schedule RC-C, part I; and federal funds sold and securities purchased under agreements to resell in Schedule RC, item 3.

For purposes of these reports, all liabilities of the reporting bank's IBFs to outside parties are classified under three headings:

- (1) federal funds purchased and securities sold under agreements to repurchase, which are to be reported in Schedule RC, item 14;
- (2) accrued liabilities, which are to be reported in Schedule RC, item 20; and

International Banking Facility (IBF) (cont.):

(3) all other liabilities, including deposits, placements, and borrowings, which are to be treated as deposit liabilities in foreign offices and reported in Schedule RC, item 13.b, and by customer detail in Schedule RC-E, part II.

In addition to being included in the appropriate items of the balance sheet, the total assets and total liabilities of the reporting bank's IBFs are to be reported separately in Schedule RC-I, Assets and Liabilities of IBFs, by banks with IBFs and other "foreign" offices. For a bank whose only foreign offices are IBFs, the total assets and liabilities of the reporting bank's IBFs are not reported separately in Schedule RC-I, but are derived from Schedule RC-H, Selected Balance Sheet Items for Domestic Offices.

<u>Treatment of transactions with IBFs of other depository institutions</u> -- Transactions between the reporting bank and IBFs outside the scope of the reporting bank's consolidated Reports of Condition and Income are to be reported as transactions with depository institutions in the U.S., as appropriate. (Note, however, that only foreign offices of the reporting bank and the reporting bank's IBFs are permitted to have transactions with other IBFs.)

Interoffice Accounts: See "suspense accounts."

Investments in Common Stock of Unconsolidated Subsidiaries: See "equity method of accounting" and "subsidiaries."

Joint Venture: See "subsidiaries."

Lease Accounting: A lease is an agreement that transfers the right to use land, buildings, or equipment for a specified period of time. This financing device is essentially an extension of credit evidenced by an obligation between a lessee and a lessor.

Standards for lease accounting are set forth in FASB Statement No. 13, "Accounting for Leases," as amended and interpreted.

Accounting with bank as lessee -- Any lease entered into by a lessee bank that meets certain criteria (defined in the following paragraph) shall be accounted for as a property acquisition financed with a debt obligation. The property shall be amortized according to the bank's normal depreciation policy (except, if appropriate, the amortization period shall be the lease term) unless the lease involves land only. The interest expense portion of each lease payment shall be calculated to result in a constant rate of interest on the balance of the debt obligation. In the Report of Condition, the property "asset" is to be reported in Schedule RC, item 6, and the liability for capitalized leases in Schedule RC, item 16, "Other borrowed money." In the Report of Income, the interest expense portion of the capital lease payments is to be reported in Schedule RI, item 2.c, "Interest on trading liabilities and other borrowed money," and the amortization expense on the asset is to be reported in Schedule RI, item 7.b, "Expenses of premises and fixed assets."

If any one of the following criteria is met, a lease must be accounted for as a capital lease:

- (1) ownership of the property is transferred to the lessee at the end of the lease term, or
- (2) the lease contains a bargain purchase option, or

Lease Accounting (cont.):

(3) the lease term represents at least 75 percent of the estimated economic life of the leased property, or

(4) the present value of the minimum lease payments at the beginning of the lease term is 90 percent or more of the fair value of the leased property to the lessor at the inception of the lease less any related investment tax credit retained by and expected to be realized by the lessor.

If none of the above criteria is met, the lease should be accounted for as an <u>operating lease</u>. Normally, rental payments should be charged to expense over the term of the operating lease as they become payable.

NOTE: If a lease involves land only, the lease must be capitalized if either of the first two criteria above is met. Where a lease that involves land <u>and</u> building meets either of these two criteria, the land and building must be separately capitalized by the lessee. The accounting for a lease involving land and building that meets neither of the first two criteria should conform to the standards prescribed by FASB Statement No. 13.

Accounting for sales with leasebacks -- Sale-leaseback transactions involve the sale of property by the owner and a lease of the property back to the seller. If a bank sells premises or fixed assets and leases back the property, the lease shall be treated as a capital lease if it meets any one of the four criteria above for capitalization. Otherwise, the lease shall be accounted for as an operating lease.

As a general rule, the bank shall defer any gain resulting from the sale. For capital leases, this deferred gain is amortized in proportion to the depreciation taken on the leased asset. For operating leases, the deferred gain is amortized in proportion to the rental payments the bank will make over the lease term. The unamortized deferred gain is to be reported in Schedule RC-G, item 4, "Other" liabilities. (Exceptions to the general rule on deferral that permit full or partial recognition of a gain at the time of the sale may occur if the leaseback covers less than substantially all of the property that was sold or if the total gain exceeds the minimum lease payments.)

If the fair value of the property at the time of the sale is less than the book value of the property, the difference between these two amounts shall be recognized as a loss immediately. In this case, if the sales price is less than the fair value of the property, the additional loss shall be deferred since it is in substance a prepayment of rent. Similarly, if the fair value of the property sold is greater than its book value, any loss on the sale shall also be deferred. Deferred losses shall be amortized in the same manner as deferred gains as described above.

For further information, see FASB Statement No. 28, "Accounting for Sales with Leasebacks."

Accounting with bank as lessor -- Unless a long-term creditor is also involved in the transaction, a lease entered into by a lessor bank that meets one of the four criteria above for a capital lease plus two additional criteria (as defined below) shall be treated as a <u>direct financing lease</u>. The unearned income (minimum lease payments plus estimated residual value plus initial direct costs less the cost of the leased property) shall be amortized to income over the lease term in a manner which produces a constant rate of return on the net investment (minimum lease payments plus estimated residual value plus initial direct costs less unearned income). Other methods of income recognition may be used if the results are not materially different.

The following two additional criteria must be met for a lease to be classified as a direct financing lease:

- (1) Collectability of the minimum lease payments is reasonably predictable.
- (2) No important uncertainties surround the amount of unreimbursable costs yet to be incurred by the lessor under the lease.

Lease Accounting (cont.):

When a lessor bank enters into a lease that has all the characteristics of a direct financing lease but where a long-term creditor provides nonrecourse financing to the lessor, the transaction shall be accounted for as a leveraged lease. The lessor's net investment in a leveraged lease shall be recorded in a manner similar to that for a direct financing lease but net of the principal and interest on the nonrecourse debt. Based on a projected cash flow analysis for the lease term, unearned and deferred income shall be amortized to income at a constant rate only in those years of the lease term in which the net investment is positive. In the years in which the net investment is not positive, no income is to be recognized on the leveraged lease.

If a lease is neither a direct financing lease nor a leveraged lease, the lessor bank shall account for it as an operating lease. The leased property shall be reported as "Other assets" and depreciated in accordance with the bank's normal policy. Rental payments are generally credited to income over the term of an operating lease as they become receivable.

Letter of Credit: A letter of credit is a document issued by a bank on behalf of its customer (the account party) authorizing a third party (the beneficiary), or in special cases the account party, to draw drafts on the bank up to a stipulated amount and with specified terms and conditions. The letter of credit is a conditional commitment (except when prepaid by the account party) on the part of the bank to provide payment on drafts drawn in accordance with the terms of the document.

As a matter of sound practice, letters of credit should:

- (1) be conspicuously labeled as a letter of credit;
- (2) contain a specified expiration date or be for a definite term;
- (3) be limited in amount;
- (4) call upon the issuing bank to pay only upon the presentation of a draft or other documents as specified in the letter of credit and not require the issuing bank to make determinations of fact or law at issue between the account party and the beneficiary; and
- (5) be issued only subject to an agreement between the account party and the issuing bank that establishes the unqualified obligation of the account party to reimburse the issuing bank for all payments made under the letter of credit.

There are four basic types of letters of credit:

- (1) commercial letters of credit,
- (2) letters of credit sold for cash,
- (3) travelers' letters of credit, and
- (4) standby letters of credit,

each of which is discussed separately on the following page.

A commercial letter of credit is issued specifically to facilitate trade or commerce. Under the terms of a commercial letter of credit, as a general rule, drafts will be drawn when the underlying transaction is consummated as intended.

A letter of credit sold for cash is a letter of credit for which the bank has received funds from the account party at the time of issuance. This type of letter of credit is not to be reported as an outstanding letter of credit but as a demand deposit. These letters are considered to have been sold for cash even though the bank may have advanced funds to the account party for the purchase of such letters of credit on a secured or unsecured basis.

Letter of Credit (cont.):

A travelers' letter of credit is issued to facilitate travel. This letter of credit is addressed by the bank to its correspondents authorizing the correspondents to honor drafts drawn by the person named in the letter of credit in accordance with specified terms. These letters are generally sold for cash.

A <u>standby letter of credit</u> is a letter of credit or similar arrangement that:

- (1) represents an obligation on the part of the issuing bank to a designated third party (the beneficiary) contingent upon the failure of the issuing bank's customer (the account party) to perform under the terms of the underlying contract with the beneficiary, or
- (2) obligates the bank to guarantee or stand as surety for the benefit of a third party to the extent permitted by law or regulation.

The underlying contract may entail either financial or nonfinancial undertakings of the account party with the beneficiary. The underlying contract may involve such things as the customer's payment of commercial paper, delivery of merchandise, completion of a construction contract, release of maritime liens, or repayment of the account party's obligations to the beneficiary. Under the terms of a standby letter, as a general rule, drafts will be drawn only when the underlying event fails to occur as intended.

Limited-Life Preferred Stock: See "preferred stock."

Loan: For purposes of these reports, a loan is generally an extension of credit resulting from direct negotiations between a lender and a borrower. The reporting bank may originate a loan by directly negotiating with a borrower or it may purchase a loan or a portion of a loan originated by another lender that directly negotiated with a borrower. The reporting bank may also sell a loan or a portion of a loan, regardless of the method by which it acquired the loan.

Loans may take the form of promissory notes, acknowledgments of advance, due bills, invoices, overdrafts, acceptances, and similar written or oral obligations.

Among the extensions of credit reportable as loans in Schedule RC-C, which covers both loans held for sale and loans that the reporting bank has the intent and ability to hold for the foreseeable future or until maturity or payoff, are:

- (1) acceptances of other banks purchased in the open market, not held for trading:
- (2) acceptances executed by or for the account of the reporting bank and subsequently acquired by it through purchase or discount;
- (3) customers' liability to the reporting bank on drafts paid under letters of credit for which the bank has not been reimbursed;
- (4) "advances" and commodity or bill-of-lading drafts payable upon arrival of goods against which drawn, for which the reporting bank has given deposit credit to customers;
- (5) paper pledged by the bank whether for collateral to secure bills payable (e.g., margin collateral to secure bills rediscounted) or for any other purpose;
- (6) sales of so-called "term federal funds" (i.e., sales of immediately available funds with a maturity of more than one business day), other than those involving security resale agreements;
- (7) factored accounts receivable;

Loan (cont.):

(8) loans arising out of the purchase of assets (other than securities) under resale agreements with a maturity of more than one business day if the agreement requires the bank to resell the identical asset purchased; and

(9) participations (acquired or held) in a single loan or in a pool of loans or receivables (see the discussion of loan participations in the Glossary entry for "transfers of financial assets").

Loan assets held for trading are to be reported in Schedule RC, item 5, "Trading assets."

See also "loan secured by real estate," "overdraft," and "transfers of financial assets."

Loan Fees: The accounting standards for nonrefundable fees and costs associated with lending, committing to lend, and purchasing a loan or group of loans are set forth in FASB Statement No. 91, "Accounting for Nonrefundable Fees and Costs Associated with Originating or Acquiring Loans and Initial Direct Costs of Leases," a summary of which follows. The statement applies to all types of loans as well as to debt securities (but not to loans or debt securities carried at market value if the changes in market value are included in earnings) and to all types of lenders. For further information, see FASB Statement No. 91.

A bank may acquire a loan by originating the loan (lending) or by acquiring a loan from a party other than the borrower (purchasing). Lending, committing to lend, refinancing or restructuring loans, arranging standby letters of credit, syndicating loans, and leasing activities are all considered "lending activities." Nonrefundable loan fees paid by the borrower to the lender may have many different names, such as origination fees, points, placement fees, commitment fees, application fees, management fees, restructuring fees, and syndication fees, but in this Glossary entry, they are referred to as loan origination fees, commitment fees, or syndication fees.

FASB Statement No. 91 applies to both a lender and a purchaser, and should be applied to individual loan contracts. Aggregation of similar loans for purposes of recognizing net fees or costs and purchase premiums or discounts is permitted under certain circumstances specified in FASB Statement No. 91 or if the result does not differ materially from the amount that would have been recognized on an individual loan-by-loan basis. In general, the statement specifies that:

- (1) Loan origination fees should be deferred and recognized over the life of the related loan as an adjustment of yield (interest income). Once a bank adopts FASB Statement No. 91, recognizing a portion of loan fees as revenue to offset all or part of origination costs in the reporting period in which a loan is originated is no longer acceptable.
- (2) Certain direct loan origination costs specified in the Statement should be deferred and recognized over the life of the related loan as a reduction of the loan's yield. Loan origination fees and related direct loan origination costs for a given loan should be offset and only the net amount deferred and amortized.
- (3) Direct loan origination costs should be offset against related commitment fees and the net amounts deferred except for: (a) commitment fees (net of costs) where the likelihood of exercise of the commitment is remote, which generally should be recognized as service fee income on a straight line basis over the loan commitment period, and (b) retrospectively determined fees, which are recognized as service fee income on the date as of which the amount of the fee is determined. All other commitment fees (net of costs) shall be deferred over the entire commitment period and recognized as an adjustment of yield over the related loan's life or, if the commitment expires unexercised, recognized in income upon expiration of the commitment.

Loan Fees (cont.):

(4) Loan syndication fees should be recognized by the bank managing a loan syndication (the syndicator) when the syndication is complete unless a portion of the syndication loan is retained. If the yield on the portion of the loan retained by the syndicator is less than the average yield to the other syndication participants after considering the fees passed through by the syndicator, the syndicator should defer a portion of the syndication fee to produce a yield on the portion of the loan retained that is not less than the average yield on the loans held by the other syndication participants.

- (5) Loan fees, certain direct loan origination costs, and purchase premiums and discounts on loans shall be recognized as an adjustment of yield generally by the interest method based on the contractual term of the loan. However, if the bank holds a large number of similar loans for which prepayments are probable and the timing and amount of prepayments can be reasonably estimated, the bank may consider estimates of future principal prepayments in the calculation of the constant effective yield necessary to apply the interest method. Once a bank adopts FASB Statement No. 91, the practice of recognizing fees over the estimated average life of a group of loans is no longer acceptable.
- (6) A refinanced or restructured loan, other than a troubled debt restructuring, should be accounted for as a new loan if the terms of the new loan are at least as favorable to the lender as the terms for comparable loans to other customers with similar collection risks who are not refinancing or restructuring a loan. Any unamortized net fees or costs and any prepayment penalties from the original loan should be recognized in interest income when the new loan is granted. If the refinancing or restructuring does not meet these conditions or if only minor modifications are made to the original loan contract, the unamortized net fees or costs from the original loan and any prepayment penalties should be carried forward as a part of the net investment in the new loan. The investment in the new loan should consist of the remaining net investment in the original loan, any additional amounts loaned, any fees received, and direct loan origination costs associated with the transaction. In a troubled debt restructuring involving a modification of terms, fees received should be applied as a reduction of the recorded investment in the loan, and all related costs. including direct loan origination costs, should be charged to expense as incurred. (See the Glossary entry for "troubled debt restructurings" for further guidance.)
- (7) Deferred net fees or costs shall not be amortized during periods in which interest income on a loan is not being recognized because of concerns about realization of loan principal or interest.

Direct loan origination costs of a completed loan are defined to include only (a) incremental direct costs of loan origination incurred in transactions with independent third parties for that particular loan and (b) certain costs directly related to specified activities performed by the lender for that particular loan. Incremental direct costs are costs to originate a loan that (a) result directly from and are essential to the lending transaction and (b) would not have been incurred by the lender had that lending transaction not occurred. The specified activities performed by the lender are evaluating the prospective borrower's financial condition; evaluating and recording guarantees, collateral, and other security arrangements; negotiating loan terms; preparing and processing loan documents; and closing the transaction. The costs directly related to those activities include only that portion of the employees' total compensation and payroll-related fringe benefits directly related to time spent performing those activities for that particular loan and other costs related to those activities that would not have been incurred but for that particular loan.

FFIEC 031 and 041 **GLOSSARY** A-56

¹ For purposes of these reports, a bank which deems its costs for these lending activities not to be material and which need not maintain records on a loan-by-loan basis for other purposes may expense such costs as incurred.

Loan Fees (cont.):

All other lending-related costs, whether or not incremental, should be charged to expense as incurred, including costs related to activities performed by the lender for advertising, identifying potential borrowers, soliciting potential borrowers, servicing existing loans, and other ancillary activities related to establishing and monitoring credit policies, supervision, and administration. Employees' compensation and fringe benefits related to these activities, unsuccessful loan origination efforts, and idle time should be charged to expense as incurred. Administrative costs, rent, depreciation, and all other occupancy and equipment costs are considered indirect costs and should be charged to expense as incurred.

Net unamortized loan fees represent an adjustment of the loan yield, and shall be reported in the same manner as unearned income on loans, i.e., deducted from the related loan balances (to the extent possible) or deducted from total loans in "Any unearned income on loans reflected in items 1-9 above" in Schedule RC-C, part I. Net unamortized direct loan origination costs shall be added to the related loan balances in Schedule RC-C, part I. Amounts of loan origination, commitment, and other fees and costs recognized as an adjustment of yield should be reported under the appropriate subitem of item 1, "Interest income," in Schedule RI. Other fees, such as (a) commitment fees that are recognized during the commitment period or included in income when the commitment expires (i.e. fees retrospectively determined and fees for commitments where exercise is remote) and (b) syndication fees that are not deferred, should be reported as "Other noninterest income" on Schedule RI.

Loan Impairment: The accounting standard for impaired loans is FASB Statement No. 114, "Accounting by Creditors for Impairment of a Loan." For further information, refer to FASB Statement No. 114.

Each institution is responsible for maintaining an allowance for loan and lease losses (allowance) adequate to absorb estimated credit losses in its entire loan and lease portfolio. As indicated in the Interagency Policy Statement on the Allowance for Loan and Lease Losses dated December 21, 1993, a bank should rely on several methods when analyzing its loan and lease portfolio and determining the appropriate level for its allowance. FASB Statement No. 114 sets forth measurement methods for estimating the portion of the overall allowance for loan and lease losses attributable to individually impaired loans. An appropriate allowance must be maintained for other loans in accordance with FASB Statement No. 5. "Accounting for Contingencies." For comprehensive guidance on the maintenance of an adequate allowance, banks should refer to the Interagency Policy Statement and the Glossary entry for "allowance for loan and lease losses." National banks should also refer to the Office of the Comptroller of the Currency's Handbook for National Bank Examiners discussing the allowance for loan and lease losses.

In general, certain loans are impaired under FASB Statement No. 114 when, based on current information and events, it is likely that an institution will be unable to collect all amounts due (i.e., both principal and interest) according to the contractual terms of the original loan agreement. An institution should apply its normal loan review procedures when determining whether a loan covered by FASB Statement No. 114 is impaired. When an individually reviewed loan is deemed impaired under FASB Statement No. 114, an institution may choose to measure impairment using (1) the present value of expected future cash flows discounted at the loan's effective interest rate (i.e., the contractual interest rate adjusted for any net deferred loan fees or costs, premium, or discount existing at the origination or acquisition of the loan), (2) the loan's observable market price, or (3) the fair value of the collateral, if the loan is collateral dependent. (See the additional regulatory reporting guidance on collateral dependent loans in the following paragraph.) A loan is collateral dependent if repayment of the loan is expected to be provided solely by the underlying collateral and there are no other available and reliable sources of repayment. A creditor should consider estimated costs to sell, on a discounted basis, in the measurement of impairment if those costs are expected to reduce the cash flows available to repay or otherwise satisfy the loan. If the measure of an impaired loan is less than the recorded investment in the loan, an impairment should be recognized by creating an allowance for estimated credit losses for the impaired loan or by adjusting an existing allowance with a corresponding charge or credit to "Provision for loan and lease losses."

Loan Impairment (cont.):

For purposes of the Reports of Condition and Income, impairment of a <u>collateral dependent loan</u> must be measured using the fair value of the collateral. In general, any portion of the recorded investment in a collateral dependent loan (including recorded accrued interest, net deferred loan fees or costs, and unamortized premium or discount) in excess of the fair value of the collateral that can be identified as uncollectible should be promptly charged off against the allowance for loan and lease losses.

An institution should not provide an additional allowance for estimated credit losses on an individually impaired loan over and above what is specified by FASB Statement No. 114. The allowance established under FASB Statement No. 114 should take into consideration all available information existing as of the Call Report date that indicates that it is probable that a loan has been impaired. All available information would include existing environmental factors such as industry, geographical, economic, and political factors that affect collectibility.

FASB Statement No. 114 also addresses the accounting by creditors for all loans that are restructured in a troubled debt restructuring involving a modification of terms, except loans that are measured at fair value or the lower of cost or fair value. For guidance on troubled debt restructurings, see the Glossary entry for "troubled debt restructurings."

As with all other loans, all impaired loans should be reported as past due or nonaccrual loans in Schedule RC-N in accordance with the schedule's instructions. Since full collection of principal and interest is not expected for impaired loans, income accrual should normally be discontinued on such loans at the time that they first become impaired. Any cash payments received on impaired loans should be reported in accordance with the criteria for the cash basis recognition of income in the Glossary entry for "nonaccrual status." For further guidance, see that Glossary entry.

Loan Secured by Real Estate: For purposes of these reports, loans secured by real estate are loans predicated upon a security interest in real property. A loan predicated upon a security interest in real property is a loan secured wholly or substantially by a lien on real property for which the lien is central to the extension of the credit--that is, the borrower would not have been extended credit in the same amount or on terms as favorable without the lien on real property. All loans satisfying the criteria above are to be reported as loans secured by real estate (Schedule RC-C, part I, item 1), regardless of whether secured by first or junior liens, regardless of the department within the bank or bank subsidiary that made the loans, regardless of how the loans are categorized in the bank's records, and regardless of the purpose of the financing. Only in transactions where a lien on real property has been taken as collateral solely through an abundance of caution and where the terms as a consequence have not been made more favorable than they would have been in the absence of the lien, would the loans not be considered to be secured by real estate and not be classifiable as loans secured by real estate in the Report of Condition.

Loss Contingencies: A loss contingency is an existing condition, situation, or set of circumstances that involves uncertainty as to possible loss that will be resolved when one or more future events occur or fail to occur. An estimated loss (or expense) from a loss contingency (for example, pending or threatened litigation) must be accrued by a charge to income if it is probable that an asset has been impaired or a liability incurred as of the report date and the amount of the loss can be reasonably estimated.

A contingency that might result in a gain, for example, the filing of an insurance claim, shall <u>not</u> be recognized as income prior to realization.

For further information, see FASB Statement No. 5, "Accounting for Contingencies."

Majority-Owned Subsidiary: See "subsidiaries."

Mandatory Convertible Debt: Mandatory convertible debt is a subordinated note or debenture with a maturity of 12 years or less that obligates the holder to take the common or perpetual preferred stock of the issuer in lieu of cash for repayment of principal by a date at or before the maturity date of the debt instrument (so-called "equity contract notes").

Market Value of Securities: The market value of securities should be determined, to the extent possible, by timely reference to the best available source of current market quotations or other data on relative current values. For example, securities traded on national, regional, or foreign exchanges or in organized over-the-counter markets should be valued at the most recently available quotation in the most active market. Rated securities for which no organized market exists should be valued on the basis of a yield curve estimate. Quotations from brokers or others making markets in securities that are neither widely nor actively traded are acceptable if prudently used. Unrated debt securities for which no reliable market price data are available may be valued at cost adjusted for amortization of premium or accretion of discount unless credit problems of the obligor or upward movements in the level of interest rates warrant a lower estimate of current value. Equity securities that do not have readily determinable fair values such as Federal Reserve stock or equity securities in closely held businesses should be valued at historical cost.

Mergers: See "business combinations."

Money Market Deposit Account (MMDA): See "deposits."

Nonaccrual Status: This entry covers, for purposes of these reports, the criteria for placing assets in nonaccrual status (presented in the general rule below) and related exceptions, the reversal of previously accrued but uncollected interest, the treatment of cash payments received on nonaccrual assets and the criteria for cash basis income recognition, the restoration of a nonaccrual asset to accrual status, and the treatment of multiple extensions of credit to one borrower.

General rule -- Banks shall not accrue interest, amortize deferred net loan fees or costs, or accrete discount on any asset (1) which is maintained on a cash basis because of deterioration in the financial condition of the borrower, (2) for which payment in full of principal or interest is not expected, or (3) upon which principal or interest has been in default for a period of 90 days or more unless the asset is both well secured and in the process of collection.

An asset is "well secured" if it is secured (1) by collateral in the form of liens on or pledges of real or personal property, including securities, that have a realizable value sufficient to discharge the debt (including accrued interest) in full, or (2) by the guarantee of a financially responsible party. An asset is "in the process of collection" if collection of the asset is proceeding in due course either (1) through legal action, including judgment enforcement procedures, or, (2) in appropriate circumstances, through collection efforts not involving legal action which are reasonably expected to result in repayment of the debt or in its restoration to a current status in the near future.

For purposes of applying the third test for nonaccrual status listed above, the date on which an asset reaches nonaccrual status is determined by its contractual terms. If the principal or interest on an asset becomes due and unpaid for 90 days or more on a date that falls between report dates, the asset should be placed in nonaccrual status as of the date it becomes 90 days past due and it should remain in nonaccrual status until it meets the criteria for restoration to accrual status described below.

Any state statute, regulation, or rule that imposes more stringent standards for nonaccrual of interest takes precedence over this instruction.

Nonaccrual Status (cont.):

Exceptions to the general rule -- In the following situations, an asset need not be placed in nonaccrual status:

(1) The criteria for amortization (i.e., accretion of discount) specified in AICPA Practice Bulletin No. 6¹ are met with respect to a loan or other debt instrument acquired at a discount (because there is uncertainty as to the amounts or timing of future cash flows) from an unaffiliated third party (such as another institution or the receiver of a failed institution), including those that the seller had maintained in nonaccrual status.

(2) The asset upon which principal or interest is due and unpaid for 90 days or more is a consumer loan or a loan secured by a 1-to-4 family residential property. Nevertheless, such loans should be subject to other alternative methods of evaluation to assure that the bank's net income is not materially overstated.

<u>Treatment of previously accrued interest</u> -- The reversal of previously accrued but uncollected interest applicable to any asset placed in nonaccrual status should be handled in accordance with generally accepted accounting principles. Acceptable accounting treatment includes a reversal of all previously accrued but uncollected interest applicable to assets placed in a nonaccrual status against appropriate income and balance sheet accounts.

For example, one acceptable method of accounting for such uncollected interest on a loan placed in nonaccrual status is (1) to reverse all of the unpaid interest by crediting the "accrued interest receivable" account on the balance sheet, (2) to reverse the uncollected interest that has been accrued during the calendar year-to-date by debiting the appropriate "interest and fee income on loans" account on the income statement, and (3) to reverse any uncollected interest that had been accrued during previous calendar years by debiting the "allowance for loan and lease losses" account on the balance sheet. The use of this method presumes that bank management's additions to the allowance through charges to the "provision for loan and lease losses" on the income statement have been based on an evaluation of the collectability of the loan and lease portfolios and the "accrued interest receivable" account.

Treatment of cash payments and criteria for the cash basis recognition of income -- When doubt exists as to the collectability of the remaining book balance of an asset in nonaccrual status, any payments received must be applied to reduce principal to the extent necessary to eliminate such doubt. Placing an asset in nonaccrual status does not, in and of itself, require a charge-off, in whole or in part, of the asset's principal. However, any identified losses must be charged off.

While an asset is in nonaccrual status, some or all of the cash interest payments received may be treated as interest income on a cash basis as long as the remaining book balance of the asset (i.e., after charge-off of identified losses, if any) is deemed to be fully collectible.² A bank's determination as to the ultimate collectability of the asset's remaining book balance must be supported by a current, well documented credit evaluation of the borrower's financial condition and prospects for repayment, including consideration of the borrower's historical repayment performance and other relevant factors.

When recognition of interest income on a cash basis is appropriate, it should be handled in accordance with generally accepted accounting principles. One acceptable accounting practice involves allocating

FFIEC 031 and 041 A-60 **GLOSSARY** (6-01)

¹ American Institute of Certified Public Accountants Practice Bulletin No. 6, "Amortization of Discounts on Certain Acquired Loans," August 1989.

² An asset subject to the cost recovery method required by AICPA Practice Bulletin No. 6 should follow that method for reporting purposes.

Nonaccrual Status (cont.):

contractual interest payments among interest income, reduction of principal, and recovery of prior charge-offs. If this method is used, the amount of income that is recognized would be equal to that which would have been accrued on the asset's remaining book balance at the contractual rate. A bank may also choose to account for the contractual interest in its entirety either as income, reduction of principal, or recovery of prior charge-offs, depending on the condition of the loan, consistent with its accounting policies for other financial reporting purposes.

Restoration to accrual status -- As a general rule, a nonaccrual asset may be restored to accrual status when (1) none of its principal and interest is due and unpaid, and the bank expects repayment of the remaining contractual principal and interest, or (2) when it otherwise becomes well secured and in the process of collection.

For purposes of meeting the first test, the bank must have received repayment of the past due principal and interest unless, as discussed below, (1) the asset has been formally restructured and qualifies for accrual status, (2) the asset has been acquired at a discount (because there is uncertainty as to the amounts or timing of future cash flows) from an unaffiliated third party and meets the criteria for amortization (i.e., accretion of discount) specified in AICPA Practice Bulletin No. 6, or (3) the borrower has resumed paying the full amount of the scheduled contractual interest and principal payments on a loan that is past due and in nonaccrual status, even though the loan has not been brought fully current, and the following two criteria are met. These criteria are, first, that all principal and interest amounts contractually due (including arrearages) are reasonably assured of repayment within a reasonable period and, second, that there is a sustained period of repayment performance (generally a minimum of six months) by the borrower in accordance with the contractual terms involving payments of cash or cash equivalents. A loan that meets these two criteria may be restored to accrual status but must continue to be disclosed as past due in Schedule RC-N until it has been brought fully current or until it later must be placed in nonaccrual status.

A loan or other debt instrument that has been formally restructured so as to be reasonably assured of repayment and of performance according to its modified terms need not be maintained in nonaccrual status, provided the restructuring and any charge-off taken on the asset are supported by a current, well documented credit evaluation of the borrower's financial condition and prospects for repayment under the revised terms. Otherwise, the restructured asset must remain in nonaccrual status. The evaluation must include consideration of the borrower's sustained historical repayment performance for a reasonable period prior to the date on which the loan or other debt instrument is returned to accrual status. A sustained period of repayment performance generally would be a minimum of six months and would involve payments of cash or cash equivalents. (In returning the asset to accrual status, sustained historical repayment performance for a reasonable time prior to the restructuring may be taken into account.) Such a restructuring must improve the collectability of the loan or other debt instrument in accordance with a reasonable repayment schedule and does not relieve the bank from the responsibility to promptly charge off all identified losses.

A formal restructuring may involve a multiple note structure in which, for example, a troubled loan is restructured into two notes. The first or "A" note represents the portion of the original loan principal amount that is expected to be fully collected along with contractual interest. The second or "B" note represents the portion of the original loan that has been charged off and, because it is not reflected as an asset and is unlikely to be collected, could be viewed as a contingent receivable. The "A" note may be returned to accrual status provided the conditions in the preceding paragraph are met and: (1) there is economic substance to the restructuring and it qualifies as a troubled debt restructuring under generally accepted accounting principles, (2) the portion of the original loan represented by the "B" note has been charged off before or at the time of the restructuring, and (3) the "A" note is reasonably assured of repayment and of performance in accordance with the modified terms.

Nonaccrual Status (cont.):

Until the restructured asset is restored to accrual status, if ever, cash payments received must be treated in accordance with the criteria stated above in the preceding section of this entry. In addition, after a formal restructuring, if a restructured asset that has been returned to accrual status later meets the criteria for placement in nonaccrual status as a result of past due status based on its modified terms or for any other reasons, the asset must be placed in nonaccrual status.

For further information on formally restructured assets, see the Glossary entry for "troubled debt restructurings."

<u>Treatment of multiple extensions of credit to one borrower</u> -- As a general principle, nonaccrual status for an asset should be determined based on an assessment of the individual asset's collectability and payment ability and performance. Thus, when one loan to a borrower is placed in nonaccrual status, a bank does not automatically have to place all other extensions of credit to that borrower in nonaccrual status. When a bank has multiple loans or other extensions of credit outstanding to a single borrower, and one loan meets the criteria for nonaccrual status, the bank should evaluate its other extensions of credit to that borrower to determine whether one or more of these other assets should also be placed in nonaccrual status.

Noninterest-Bearing Account: See "deposits."

Nontransaction Account: See "deposits."

NOW Account: See "deposits."

Offsetting: Offsetting is the reporting of assets and liabilities on a net basis in the balance sheet. Banks are permitted to offset assets and liabilities recognized in the Report of Condition when a "right of setoff" exists. Under FASB Interpretation No. 39, "Offsetting of Amounts Related to Certain Contracts," a right of setoff exists when all of the following conditions are met:

- (1) Each of two parties owes the other determinable amounts. Thus, only bilateral netting is permitted.
- (2) The reporting party has the right to set off the amount owed with the amount owed by the other party.
- (3) The reporting party intends to set off. This condition does not have to be met for fair value amounts recognized for conditional or exchange contracts that have been executed with the same counterparty under a master netting arrangement.
- (4) The right of setoff is enforceable at law. Legal constraints should be considered to determine whether the right of setoff is enforceable. Accordingly, the right of setoff should be upheld in bankruptcy (or receivership). Offsetting is appropriate only if the available evidence, both positive and negative, indicates that there is reasonable assurance that the right of setoff would be upheld in bankruptcy (or receivership).

According to Interpretation No. 39, for forward, interest rate swap, currency swap, option, and other conditional and exchange contracts, a master netting arrangement exists if the reporting bank has multiple contracts, whether for the same type of conditional or exchange contract or for different types of contracts, with a single counterparty that are subject to a contractual agreement that provides for the net settlement of all contracts through a single payment in a single currency in the event of default or termination of any one contract.

Offsetting (cont.):

Offsetting the assets and liabilities recognized for conditional or exchange contracts outstanding with a single counterparty results in the net position between the two counterparties being reported as an asset or a liability in the Report of Condition. The reporting entity's choice to offset or not to offset assets and liabilities recognized for conditional or exchange contracts must be applied consistently.

Offsetting of assets and liabilities is also permitted by other accounting pronouncements identified in Interpretation No. 39. These pronouncements apply to such items as leveraged leases, pension plan and other postretirement benefit plan assets and liabilities, and deferred tax assets and liabilities. In addition, FASB Interpretation No. 41, "Offsetting of Amounts Related to Certain Repurchase and Reverse Repurchase Agreements," describes the circumstances in which amounts recognized as payables under repurchase agreements may be offset against amounts recognized as receivables under reverse repurchase agreements and reported as a net amount in the balance sheet. The reporting entity's choice to offset or not to offset payables and receivables under Interpretation No. 41 must be applied consistently.

See also "reciprocal balances."

One-Day Transaction: See "federal funds transactions."

Option: See "derivative contracts."

Organization Costs: See "start-up activities."

Other Depository Institutions in the U.S.: See "depository institutions in the U.S."

Other Real Estate Owned: See "foreclosed assets" and the instruction to Schedule RC-M, item 3.

Overdraft: An overdraft can be either planned or unplanned. An unplanned overdraft occurs when a depository institution honors a check or draft drawn against a deposit account when insufficient funds are on deposit and there is no advance contractual agreement to honor the check or draft. When a contractual agreement has been made in advance to allow such credit extensions, overdrafts are referred to as planned or prearranged. Any overdraft, whether planned or unplanned, is an extension of credit and is to be treated and reported as a "loan" rather than being treated as a negative deposit balance.

Planned overdrafts in depositors' accounts are to be classified in Schedule RC-C, part I, by type of loan according to the nature of the overdrawn depositor. For example, a planned overdraft by a commercial customer is to be classified as a "commercial and industrial loan."

Unplanned overdrafts in depositors' accounts are to be classified in Schedule RC-C, part I, as "All other loans," unless the depositor is a depository institution, a foreign government or foreign official institution, or a state or political subdivision in the U.S. Such unplanned overdrafts would be reported in Schedule RC-C, part I, item 2, "Loans to depository institutions and acceptances of other banks," item 7, "Loans to foreign governments and official institutions," and item 8, "Obligations (other than securities and leases) of states and political subdivisions in the U.S.," respectively.

For purposes of treatment of overdrafts in depositors' accounts, a group of related transaction accounts of a single type (i.e., demand deposit accounts or NOW accounts, but not a combination thereof) maintained in the same right and capacity by a customer (a single legal entity) that is established under a bona fide cash management arrangement by this customer function as, and are regarded as, one account rather than as multiple separate accounts. In such a situation, overdrafts in one or more of the

Overdraft (cont.):

transaction accounts within the group are not to be classified as loans unless there is a net overdraft position in the group of related transaction accounts taken as a whole. (NOTE: Affiliates and subsidiaries are considered separate legal entities.) For further information, see "cash management arrangements."

The reporting bank's overdrafts on deposit accounts it holds with other banks (i.e., its "due from" accounts) are to be reported as borrowings in Schedule RC, item 16, except overdrafts arising in connection with checks or drafts drawn by the reporting bank and drawn on, or payable at or through, another depository institution either on a zero-balance account or on an account that is not routinely maintained with sufficient balances to cover checks or drafts drawn in the normal course of business during the period until the amount of the checks or drafts is remitted to the other depository institution (in which case, report the funds received or held in connection with such checks or drafts as deposits in Schedule RC-E until the funds are remitted).

Participations: See "transfers of financial assets."

Participations in Acceptances: See "bankers acceptances."

Participations in Pools of Securities: See "repurchase/resale agreements."

Pass-through Reserve Balances: Under the Monetary Control Act of 1980, and as reflected in Federal Reserve Regulation D, depository institutions that are members of the Federal Reserve System must maintain their required reserves (in excess of vault cash) directly with a Federal Reserve Bank. However, nonmember depository institutions may maintain their required reserves (in excess of vault cash) in one of two ways: either (1) directly with a Federal Reserve Bank or (2) indirectly in an account with another institution (referred to here as a "correspondent"), which, in turn, is required to pass the reserves through to a Federal Reserve Bank. This second type of account is called a "pass-through account," and a depository institution passing its reserves to the Federal Reserve through a correspondent is referred to here as a "respondent." This pass-through reserve relationship is legally and for supervisory purposes considered to constitute an asset/debt relationship between the respondent and the correspondent, and an asset/debt relationship between the correspondent and the Federal Reserve. The required reporting of the "pass-through reserve balances" reflects this structure of asset/debt relationships.

In the balance sheet of the respondent bank, the pass-through reserve balances are to be treated as a claim on the correspondent (not as a claim on the Federal Reserve) and, as such, are to be reflected in the balance sheet of the Report of Condition, Schedule RC, item 1.a, "Noninterest-bearing balances and currency and coin," or item 1.b, "Interest-bearing balances," as appropriate. For respondent banks with foreign offices or with \$300 million or more in total assets, the pass-through reserve balances would also be reflected in Schedule RC-A, item 2, "Balances due from depository institutions in the U.S."

In the balance sheet of the correspondent bank, the pass-through reserve balances are to be treated as balances due to respondents and, to the extent that the balances have actually been passed through to the Federal Reserve, as balances due from the Federal Reserve. The balances due to respondents are to be reflected in the balance sheet of the Report of Condition, Schedule RC, item 13.a, "Deposits in domestic offices," and on in Schedule RC-E, Deposit Liabilities, (part I), item 4.1 The balances due from the Federal Reserve are to be reflected on the balance sheet in Schedule RC, item 1.a, "Noninterest-bearing balances and currency and coin," and, for correspondent banks with foreign offices or with \$300 million or more in total assets, in Schedule RC-A, item 4.

FFIEC 031 and 041 A-64 **GLOSSARY**

When an Edge or Agreement Corporation acts as a correspondent, its balances due to respondents are to be reflected on the FFIEC 031 report form in Schedule RC, item 13.b, "Deposits in foreign offices," and in Schedule RC-E, part II, item 2.

Perpetual Preferred Stock: See "preferred stock."

<u>Placements and Takings:</u> Placements and takings are deposits between a foreign office of the reporting bank and a foreign office of another bank and are to be treated as due from or due to depository institutions. Such transactions are always to be reported gross and are not to be netted as reciprocal balances.

Pooling of Interests: See "business combinations."

Preauthorized Transfer Account: See "deposits."

Preferred Stock: Preferred stock is a form of ownership interest in a bank or other company which entitles its holders to some preference or priority over the owners of common stock, usually with respect to dividends or asset distributions in a liquidation.

<u>Limited-life preferred stock</u> is preferred stock that has a stated maturity date or that can be redeemed at the option of the holder. It excludes those issues of preferred stock that automatically convert into perpetual preferred stock or common stock at a stated date.

<u>Perpetual preferred stock</u> is preferred stock that does not have a stated maturity date or that cannot be redeemed at the option of the holder. It includes those issues of preferred stock that automatically convert into common stock at a stated date.

Premiums and Discounts: A premium arises when a bank purchases a security, loan, or other asset at a price in excess of its par or face value, typically because the current level of interest rates for such assets is less than its contract or stated rate of interest. The difference between the purchase price and par or face value represents the premium, which <u>all</u> banks are required to amortize.

A <u>discount</u> arises when a bank purchases a security, loan, or other asset at a price below its par or face value, typically because the current level of interest rates for such assets is greater than its contract or stated rate of interest. A discount is also present on instruments that do not have a stated rate of interest such as U.S. Treasury bills and commercial paper. The difference between par or face value and the purchase price represents the discount that <u>all</u> banks are required to accrete.

Premiums and discounts are accounted for as adjustments to the yield on an asset over the life of the asset. A premium must be amortized and a discount must be accreted from date of purchase to maturity, not to call or put date. The preferable method for amortizing premiums and accreting discounts involves the use of the interest method for accruing income on the asset. The objective of the interest method is to produce a constant yield or rate of return on the carrying value of the asset (par or face value plus unamortized premium or less unaccreted discount) at the beginning of each amortization period over the asset's remaining life. The difference between the periodic interest income that is accrued on the asset and interest at the stated rate is the periodic amortization or accretion. However, a straight-line method of amortization or accretion is acceptable if the results are not materially different from the interest method.

A premium or discount may also arise when the reporting bank, acting either as a lender or a borrower, is involved in an exchange of a note for assets other than cash and the interest rate is either below the market rate or not stated, or the face amount of the note is materially different from the fair value of the

FFIEC 031 and 041 A-65 GLOSSARY

¹ For an asset acquired at a premium prior to the effective date of a bank's adoption of FASB Statement No. 91, the premium should be amortized to the asset's maturity date unless it is more conservative in its effect on current income to amortize the premium in two stages: (1) first to the call or "put" date and price and (2) then to the maturity date and par or face value.

Premiums and Discounts (cont.):

noncash assets exchanged. The noncash assets and the related note shall be recorded at either the fair value of the noncash assets or the market value of the note, whichever is more clearly determinable. The market value of the note would be its present value as determined by discounting all future payments on the note using an appropriate interest rate, i.e., a rate comparable to that on new loans of similar risk. The difference between the face amount and the recorded value of the note is a premium or discount. This discount or premium shall be accounted for as an adjustment of the interest income or expense over the life of the note using the interest method described above.

For further information, see APB Opinion No. 21, "Interest on Receivables and Payables."

Purchase Acquisition: See "business combinations."

Put Option: See "derivative contracts."

Real Estate ADC Arrangements: See "acquisition, development, or construction (ADC) arrangements."

Real Estate, Loan Secured By: See "loan secured by real estate."

Reciprocal Balances: Reciprocal balances arise when two depository institutions maintain deposit accounts with each other; that is, when a reporting bank has both a due to and a due from balance with another depository institution.

For purposes of the balance sheet of the Report of Condition, reciprocal balances between the reporting bank and other depository institutions may be reported on a net basis when a right of setoff exists. See the Glossary entry for "offsetting" for the conditions that must be met for a right of setoff to exist.

Renegotiated Troubled Debt: See "troubled debt restructurings."

Reorganizations: See "business combinations."

Repurchase/Resale Agreements: A repurchase agreement is a transaction involving the "sale" of financial assets by one party to another, subject to an agreement by the "seller" to repurchase the assets at a specified date or in specified circumstances. A resale agreement (also known as a reverse repurchase agreement) is a transaction involving the "purchase" of financial assets by one party from another, subject to an agreement by the "purchaser" to resell the assets at a specified date or in specified circumstances.

As stated in the AICPA's Audit and Accounting Guide for Banks and Savings Institutions, dollar repurchase agreements (also called dollar rolls) are agreements to sell and repurchase similar but not identical securities. The dollar roll market consists primarily of agreements that involve mortgage-backed securities (MBS). Dollar rolls differ from regular repurchase agreements in that the securities sold and repurchased, which are usually of the same issuer, are represented by different certificates, are collateralized by different but similar mortgage pools (for example, single-family residential mortgages), and generally have different principal amounts.

General rule -- Consistent with FASB Statement No. 140, "Accounting for Transfers and Servicing of Financial Assets and Extinguishments of Liabilities," repurchase and resale agreements involving financial assets (e.g. securities and loans), including dollar repurchase agreements, are either reported as (a) secured borrowings and loans or (b) sales and forward repurchase commitments based on whether the transferring ("selling") institution maintains control over the transferred assets. (See the Glossary entry for "transfers of financial assets" for further discussion of control criteria).

Repurchase/Resale Agreements (cont.):

If a repurchase agreement both entitles and obligates the "selling" bank to repurchase or redeem the transferred assets from the transferee ("purchaser"), the "selling" bank should report the transaction as a secured borrowing if and only if the following conditions have been met:

- (1) The assets to be repurchased or redeemed are the same or "substantially the same" as those transferred, as defined by FASB Statement No. 140.
- (2) The "selling" institution has the ability to repurchase or redeem the transferred assets on substantially the agreed terms, even in the event of default by the transferee ("purchaser"). This ability is presumed to exist if the "selling" bank has obtained cash or other collateral sufficient to fund substantially all of the cost of purchasing replacement assets from others.
- (3) The agreement is to repurchase or redeem the transferred assets before maturity, at a fixed or determinable price.
- (4) The agreement is entered into concurrently with the transfer.

Participations in pools of securities are to be reported in the same manner as security repurchase/resale transactions.

Repurchase agreements reported as secured borrowings. If a repurchase agreement qualifies as a secured borrowing, the "selling" institution should report the transaction as indicated below based on whether the agreement involves a security or some other financial asset.

- (1) Securities "sold" under agreements to repurchase are reported in Schedule RC, item 14.b, "Securities sold under agreements to repurchase."
- (2) Financial assets (other than securities) "sold" under agreements to repurchase are reported as follows:
 - (a) If the repurchase agreement has an original maturity of one business day (or is under a continuing contract) and is in immediately available funds, it should be reported in Schedule RC, item 14.a, "Federal funds purchased (in domestic offices)," if it is in a domestic office, and in Schedule RC, item 16, "Other borrowed money," if it is in a foreign office.
 - (b) If the repurchase agreement has an original maturity of more than one business day or is not in immediately available funds, it should be reported in Schedule RC, item 16.

In addition, the "selling" institution may need to record further entries depending on the terms of the agreement. If the "purchaser" has the right to sell or repledge noncash assets, the "selling" institution should recategorize the transferred financial assets as "assets receivable" and report them in Schedule RC, item 11, "Other assets." Otherwise, the financial assets should continue to be reported in the same asset category as before the transfer (e.g., securities should continue to be reported in Schedule RC, item 2, "Securities," or item 5, "Trading assets," as appropriate).

Resale agreements reported as secured borrowings. Similarly, if a resale agreement qualifies as a secured borrowing, the "purchasing" institution should report the transaction as indicated below based on whether the agreement involves a security or some other financial asset.

- (1) Securities "purchased" under agreements to resell are reported in Schedule RC, item 3.b, "Securities purchased under agreements to resell."
- (2) Financial assets (other than securities) "purchased" under agreements to resell are reported as follows:

Repurchase/Resale Agreements (cont.):

(a) If the resale agreement has an original maturity of one business day (or is under a continuing contract) and is in immediately available funds, it should be reported in Schedule RC, item 3.a, "Federal funds sold (in domestic offices)," if it is in a domestic office, and in Schedule RC, item 4.b, "Loans and leases, net of unearned income," if it is in a foreign office.

(b) If the resale agreement has an original maturity of more than one business day or is not in immediately available funds, it should be reported in Schedule RC, item 4.b.

In addition, the "purchasing" institution may need to record further entries depending on the terms of the agreement. If the "purchasing" institution has the right to sell the noncash assets it has "purchased" and sells these assets, it should recognize the proceeds from the sale and report its obligation to return the assets in Schedule RC, item 20, "Other liabilities." If the "selling" institution defaults under the terms of the repurchase agreement and is no longer entitled to redeem the noncash assets, the "purchasing" bank should recognize these assets on its own balance sheet (e.g., securities should be reported in Schedule RC, item 2, "Securities," or item 5, "Trading assets," as appropriate) and initially measure them at fair value. However, if the "purchasing" bank has already sold the assets it has "purchased," it should derecognize its obligation to return the assets. Otherwise, the "purchasing" bank should not recognize the transferred financial assets (i.e., the financial assets "purchased" under the resale agreement) on its balance sheet.

Repurchase/resale agreements reported as sales -- If a repurchase agreement does not qualify as a secured borrowing under FASB Statement No. 140, the selling bank should account for the transaction as a sale of financial assets and a forward repurchase commitment. The selling bank should remove the transferred assets from its balance sheet, record the proceeds from the sale of the transferred assets (including the forward repurchase commitment), and record any gain or loss on the transaction. Similarly, if a resale agreement does not qualify as a borrowing under Statement No. 140, the purchasing bank should account for the transaction as a purchase of financial assets and a forward resale commitment. The purchasing bank should record the transferred assets on its balance sheet, initially measure them at fair value, and record the payment for the purchased assets (including the forward resale commitment).

Reserve Balances, Pass-through: See "pass-through reserve balances."

Retail Sweep Arrangements: See "deposits."

Sales of Assets for Risk-Based Capital Purposes: This entry should be read in conjunction with the banking agencies' final rule revising the regulatory capital treatment of recourse arrangements and direct credit substitutes, including residual interests and credit-enhancing interest-only strips, which was published on November 29, 2001. This entry provides guidance for determining whether sales of loans, securities, receivables, and other assets are subject to the agencies' risk-based capital requirements and are reportable in Schedule RC-R, Regulatory Capital, and Schedule RC-S, Securitization and Asset Sale Activities. For information on the reporting of transfers of financial assets for purposes of the balance sheet, income statement, and related schedules, see the Glossary entry for "transfers of financial assets."

Under the agencies' risk-based capital standards, assets sold with recourse, if not already included on the balance sheet, are risk-weighted by using a two-step process. First, the full outstanding amount of assets sold with recourse must be converted to an on-balance sheet credit equivalent amounts using a 100 percent credit conversion factor, except for low level recourse transactions and small business obligations transferred with recourse under Section 208 of the Riegle Community Development and Regulatory Improvement Act of 1994. (The reporting treatment of these two specific types of asset sales with recourse is discussed in the instructions for items 50 and 49 of Schedule RC-R, respectively.) Second, the credit equivalent amount is assigned to the appropriate risk weight category according to the obligor or, if relevant, the guarantor or the nature of the collateral.

Sales of Assets for Risk-Based Capital Purposes (cont.):

For purposes of reporting in Schedule RC-R, some transactions involving the "sale" of assets are not subject to the risk-based capital requirements and others are subject to these requirements and must be treated as "asset sales with recourse." Under the following general rule, the risk-based capital treatment required for any particular transfer of assets depends upon whether the "seller" retains risk of loss in connection with the transfer of the assets.

<u>General rule</u> -- A transferring institution should treat a transfer of loans, securities, receivables, or other assets that qualifies for sale treatment under generally accepted accounting principles as a sale of the transferred assets that is not subject to risk-based capital <u>only if</u> the transferring institution:

- (1) retains no risk of loss from the assets transferred resulting from any cause and
- (2) has no obligation to any party for the payment of principal or interest on the assets transferred resulting from:
 - (a) default on principal or interest by the obligor of the underlying instrument or from any other deficiencies in the obligor's performance,
 - (b) changes in the market value of the assets after they have been transferred,
 - (c) any contractual relationship between the seller and purchaser incident to the transfer that, by its terms, could continue even after final payment, default, or other termination of the assets transferred, or
 - (d) any other cause.

If risk of loss or obligation for payment of principal or interest is retained by, or may fall back upon, the seller in an asset transfer that qualifies for sale treatment under generally accepted accounting principles, the transaction <u>must</u> be considered an "asset sale with recourse" for purposes of reporting risk-based capital information in Schedule RC-R. The transaction must also be reported as an asset sale with recourse in Schedule RC-S, item 1 or item 11, as appropriate, depending on whether the asset was securitized by the reporting bank.

Assets transferred in transactions that do not qualify as sales under generally accepted accounting principles should continue to be reported as assets on the Call Report balance sheet and are subject to the agencies' regulatory capital requirements.

Exception to the general rule -- Contractual provisions in sales of assets that

- (1) provide for the return of the assets to the seller in instances of incomplete documentation or fraud, or
- (2) allow the purchaser a specific limited period of time to determine that the assets transferred are in fact as represented by the seller and to return deficient paper to the seller

will not by themselves and in the absence of any other recourse provision or retention of risk cause the transfer to be treated as an "asset sale with recourse" for purposes of Schedule RC-R.

Sales of Assets for Risk-Based Capital Purposes (cont.):

Interpretations and illustrations of the general rule:

(1) For any given transfer, the determination of whether risk is retained by the transferring institution is to be based upon the substance of the transfer agreement or other relevant documents or informal commitments and understandings, or subsequent actions of the parties to the transactions, not upon the form or particular terminology used. The presence of a bona fide "sale with recourse" provision would establish the transaction as an asset sale with recourse for purposes of risk-based capital and Schedule RC-R. However, the absence of a recourse provision, the absence of the term "recourse," even the presence of a statement to the effect that there is no recourse or, in the case of a participation, the use of the terms "pass-through" or "pure pass-through" will not by themselves establish a transaction as a sale that is not subject to risk-based capital. If other conditions and provisions of the transfer are such as to leave the transferor with risk of loss as described in the general rule, the transfer is an asset sale with recourse for purposes of risk-based capital and Schedule RC-R.

- (2) If assets are sold subject to specific contractual terms that limit the seller's risk to a percentage of the value of the assets sold or to a specific dollar amount, the entire outstanding amount of the assets sold represents an asset sale with recourse for risk-based capital purposes. For example, if assets are sold subject to a ten percent recourse provision (i.e., the seller's risk is limited to ten percent of the value of the assets sold), the total outstanding amount of the assets sold is subject to risk-based capital, not just the ten percent limit, unless the low level recourse rule (discussed in the General Instructions to Schedule RC-R) applies.
 - However, if the risk retained by the seller is limited to <u>some fixed percentage of any losses</u> that might be incurred and there are no other provisions resulting in retention of risk, either directly or indirectly, by the seller, the maximum amount of possible loss for which the selling bank is at risk (the stated percentage times the amount of assets to which the percentage applies) is subject to risk-based capital and reportable in Schedule RC-R and the remaining amount of the assets transferred would be treated as a sale that is not subject to the risk-based capital requirements. For example, a seller would treat a sale of \$1,000,000 in assets, with a recourse provision that the seller and buyer proportionately share in losses incurred on a ten percent and 90 percent basis, and with no other retention of risk by the seller, as a \$100,000 asset sale with recourse and a \$900,000 sale not subject to risk-based capital.
- (3) Among the transfers where risk of loss has been retained by the seller and that should be considered by the seller as asset sales with recourse for purposes of Schedule RC-R are arrangements such as the following (this list is illustrative of the principles involved in the application of the general rule and is not all-inclusive) --
 - (a) the sale of an asset with a realistic bona fide put option allowing the purchaser, at its option, to return the asset to the seller;
 - (b) the sale of an asset guaranteed by a standby letter of credit issued by the seller:
 - (c) the sale of an asset guaranteed by a standby letter of credit issued by any other party in which risk, either directly or indirectly, rests with the seller;
 - (d) the sale of an asset guaranteed by an insurance contract in which the seller, either directly or indirectly, indemnifies or otherwise protects the insurer in any manner against loss;
 - (e) the sale of a short-term loan under a long-term credit commitment (a so-called "strip participation"); and

Sales of Assets for Risk-Based Capital Purposes (cont.):

(f) sales and securitizations of assets which use contractual cash flows (e.g., interest-only strips receivable and so-called "spread accounts"), retained subordinated interests, or retained securities (e.g., collateral invested amounts and cash collateral accounts) as credit enhancements. If the low-level recourse rule applies to these credit enhancements, the maximum contractual dollar amount of the bank's recourse exposure is generally limited to the amount carried as an asset on the balance sheet in accordance with generally accepted accounting principles.

- (4) A transfer where the seller retains risk as a result of a difference in terms between the instrument of transfer and the asset transferred, regardless of the other characteristics of the sale or participation, should be treated by the seller as an asset sale with recourse for purposes of Schedule RC-R. For example, any transfer in which there is a difference in maturity between the underlying asset and the instrument of transfer should be treated as an asset sale with recourse.
 - However, the sale of a loan or other asset subject to an agreement under which the seller will pass through to the purchaser a rate of interest that differs from the stated rate of interest on the transferred asset would not, for this reason alone, require the transaction to be treated as an asset sale with recourse for risk-based capital purposes provided (1) the seller's obligation to pass interest through to the purchaser is contingent upon the continued interest payment performance of the underlying obligor of the transferred asset (i.e., the seller has no obligation to pass interest through if the obligor defaults in whole or in part on interest or principal) and (2) none of the other characteristics of the sale or participation results in risk to the seller.
- (5) The general rule applies to all transfers of assets (other than those specifically covered in the exception), including sales of a single asset or of a pool of assets and sales of participations in a single asset or in a pool of assets (whether of similar or dissimilar instruments). In participations that are not "syndications" (as described in the Glossary item for that term), the seller of the participations should handle the transfer of shares to participants in accordance with the general rule on sales of assets for risk-based capital purposes, even though the assets being participated were acquired or accumulated for the express purpose of issuing participations and even though the participation was prearranged with the purchasers of the participations. However, the rule does not apply to the initial operation and distribution of participations in the form of syndications, since in a syndication there is no transfer of assets involved of the type to which the general rule on sales of assets for risk-based capital purposes is addressed. Any subsequent transfers of shares, or parts of shares, in a syndicated loan would be subject to the general rule.
- (6) The general rule (and interpretations and exception) is also applicable to asset transfers that are made to special or limited purpose entities that are not technically affiliated with the seller. Regardless of the legal structure of the transaction, if risk of loss is retained by the seller, either contractually or otherwise, either directly or indirectly, the seller should treat the transaction as an asset sale with recourse for purposes of risk-based capital and Schedule RC-R even if the sale to the special purpose entity is stated as being without recourse.

Savings Deposits: See "deposits."

Securities Activities: Institutions should categorize each security as trading, available-for-sale, or held-to-maturity consistent with FASB Statement No. 115, "Accounting for Certain Investments in Debt and Equity Securities," as amended. Management should periodically reassess its security categorization decisions to ensure that they remain appropriate.

Securities that are intended to be held principally for the purpose of selling them in the near term should be classified as trading assets. Trading activity includes active and frequent buying and selling of securities for the purpose of generating profits on short-term fluctuations in price. Securities held for trading purposes must be reported at fair value, with unrealized gains and losses recognized in current earnings and regulatory capital.

Held-to-maturity securities are debt securities that an institution has the positive intent and ability to hold to maturity. Held-to-maturity securities are generally reported at amortized cost. Securities not categorized as trading or held-to-maturity must be reported as available-for-sale. An institution must report its available-for-sale securities at fair value on the balance sheet, but unrealized gains and losses are excluded from earnings and reported in a separate component of equity capital.

If a decline in fair value of a held-to-maturity or available-for-sale security is judged to be other than temporary, the cost basis of the individual security shall be written down to fair value as a new cost basis and the amount of the write-down shall be included in earnings. For example, if it is probable that an institution will be unable to collect all amounts due according to the contractual terms of a debt security not impaired at acquisition, an other-than-temporary impairment has occurred.

The proper categorization of securities is important to ensure that trading gains and losses are promptly recognized in earnings and regulatory capital. This will not occur when securities intended to be held for trading purposes are categorized as held-to-maturity or available-for-sale. The following practices are considered trading activities:

- (1) Gains Trading -- Gains trading is characterized by the purchase of a security and the subsequent sale of the same security at a profit after a short holding period, while securities acquired for this purpose that cannot be sold at a profit are typically retained in the available-for-sale or held-tomaturity portfolio. Gains trading may be intended to defer recognition of losses, as unrealized losses on available-for-sale and held-to-maturity debt securities do not directly affect regulatory capital and generally are not reported in income until the security is sold.
- (2) When-Issued Securities Trading -- When-issued securities trading is the buying and selling of securities in the period between the announcement of an offering and the issuance and payment date of the securities. A purchase of a "when-issued" security acquires the risks and rewards of owning a security and may sell the when-issued security at a profit before having to take delivery and pay for it. Because such transactions are intended to generate profits from short-term price movements, they should be categorized as trading.
- (3) Pair-offs -- Pair-offs are security purchase transactions that are closed-out or sold at, or prior to, settlement date. In a pair-off, an institution commits to purchase a security. Then, prior to the predetermined settlement date, the institution will pair-off the purchase with a sale of the same security. Pair-offs are settled net when one party to the transaction remits the difference between the purchase and the sale price to the counterparty. Pair-offs may also involve the same sequence of events using swaps, options on swaps, forward commitments, options on forward commitments, or other off-balance sheet derivative contracts.

Securities Activities (cont.):

(4) Extended Settlements -- In the U.S., regular-way settlement for federal government and federal agency securities (except mortgage-backed securities and derivative contracts) is one business day after the trade date. Regular-way settlement for corporate and municipal securities is three business days after the trade date. For mortgage-backed securities, it can be up to 60 days or more after the trade date. The use of extended settlements may be offered by securities dealers in order to facilitate speculation on the part of the purchaser, often in connection with pair-off transactions. Securities acquired through the use of a settlement period in excess of the regular-way settlement periods in order to facilitate speculation should be reported as trading assets.

- (5) Repositioning Repurchase Agreements -- A repositioning repurchase agreement is a funding technique offered by a dealer in an attempt to enable an institution to avoid recognition of a loss. Specifically, an institution that enters into a "when-issued" trade or a "pair-off" (which may include an extended settlement) that cannot be closed out at a profit on the payment or settlement date will be provided dealer financing in an effort to fund its speculative position until the security can be sold at a gain. The institution purchasing the security typically pays the dealer a small margin that approximates the actual loss in the security. The dealer then agrees to fund the purchase of the security, typically buying it back from the purchaser under a resale agreement. Any securities acquired through a dealer financing technique such as a repositioning repurchase agreement that is used to fund the speculative purchase of securities should be reported as trading assets.
- (6) Short Sales -- A short sale is the sale of a security that is not owned. The purpose of a short sale generally is to speculate on a fall in the price of the security. (For further information, see the Glossary entry for "short position.")

One other practice, referred to as "adjusted trading," is not acceptable under any circumstances. Adjusted trading involves the sale of a security to a broker or dealer at a price above the prevailing market value and the contemporaneous purchase and booking of a different security, frequently a lower-rated or lower quality issue or one with a longer maturity, at a price above its market value. Thus, the dealer is reimbursed for losses on the purchase from the institution and ensured a profit. Such transactions inappropriately defer the recognition of losses on the security sold and establish an excessive cost basis for the newly acquired security. Consequently, such transactions are prohibited and may be in violation of 18 U.S.C. Sections 1001--False Statements or Entries and 1005--False Entries.

See also "trading account."

Securities Borrowing/Lending Transactions: Securities borrowing/lending transactions are typically initiated by broker-dealers and other financial institutions that need specific securities to cover a short sale or a customer's failure to deliver securities sold. A transferee ("borrower") of securities generally is required to provide "collateral" to the transferor ("lender") of securities, commonly cash but sometimes other securities or standby letters of credit, with a value slightly higher than that of the securities "borrowed."

Most securities borrowing/lending transactions do not qualify as sales under FASB Statement No. 140 because the agreement entitles and obligates the securities lender to repurchase or redeem the transferred assets before their maturity. (See the Glossary entry for "transfers of financial assets" for further discussion of sale criteria.) When such transactions do not qualify as sales, securities lenders and borrowers should account for the transactions as secured borrowings in which cash (or securities that the holder is permitted by contract or custom to sell or repledge) received as "collateral" by the securities lender is considered the amount borrowed, the securities "loaned" are considered pledged as collateral against the amount borrowed, and the "loaned" securities are recategorized on the securities lender's balance sheet as "assets receivable" and reported in Schedule RC, item 11, "Other assets."

Securities Borrowing/Lending Transactions (cont.):

If the securities borrowing/lending transaction meets the criteria for a sale under FASB Statement No. 140, the lender of the securities should remove the securities from its balance sheet, record the proceeds from the sale of the securities (including the forward repurchase commitment), and recognize any gain or loss on the transaction. The borrower of the securities should record the securities on its balance sheet at fair value and record the payment for the purchased assets (including the forward resale commitment).

Securities, Participations in Pools of: See "repurchase/resale agreements."

Servicing Assets and Liabilities: The accounting and reporting standards for servicing assets and liabilities are set forth in FASB Statement No. 140, "Accounting for Transfers and Servicing of Financial Assets and Extinguishments of Liabilities" and FASB Statement No. 65, "Accounting for Certain Mortgage Banking Activities," as amended by Statement No. 140. A summary of the relevant sections of these accounting standard follows. For further information, see FASB Statements No. 140 and No. 65 and the Glossary entry for "transfers of financial assets."

Servicing of mortgage loans, credit card receivables, or other financial assets includes, but is not limited to, collecting principal, interest, and escrow payments from borrowers; paying taxes and insurance from escrowed funds; monitoring delinquencies; executing foreclosure if necessary; temporarily investing funds pending distribution; remitting fees to guarantors, trustees, and others providing services; and accounting for and remitting principal and interest payments to the holders of beneficial interests in the financial assets. Servicers typically receive certain benefits from the servicing contract and incur the costs of servicing the assets.

Servicing is inherent in all financial assets; it becomes a distinct asset or liability only when contractually separated from the underlying financial assets by sale or securitization of the assets with servicing retained or by a separate purchase or assumption of the servicing. When a bank undertakes an obligation to service financial assets, it must recognize a servicing asset or liability for that servicing contract unless it securitizes the assets, retains all of the resulting securities, and classifies the securities as held-to-maturity debt securities. Servicing assets result from contracts to service financial assets for which the benefits of servicing (revenues from contractually specified servicing fees, late charges, and other ancillary sources) are expected to more than adequately compensate the servicer for performing the servicing. Servicing liabilities result from contracts to service financial assets for which the benefits of servicing are not expected to adequately compensate the servicer for performing the servicing. Contractually specified servicing fees are all amounts that, per contract, are due to the servicer in exchange for servicing the financial asset and would no longer be received by a servicer if the beneficial owners of the serviced assets or their trustees or agents were to exercise their actual or potential authority under the contract to shift the servicing to another servicer. Adequate compensation is the amount of benefits of servicing that would fairly compensate a substitute servicer should one be required including the profit that would be demanded by a substitute servicer in the marketplace.

When a bank sells or securitizes financial assets and retains the servicing asset, the bank shall allocate the cost of the financial assets to the servicing assets and the financial assets (without the servicing) based on their relative fair values. If it is not practicable to estimate the fair values of the servicing assets and the financial assets (without the servicing), the entire cost shall be allocated to the financial assets (without the servicing) and no cost shall be allocated to the servicing assets. If a bank incurs a servicing liability in a sale or securitization, the servicing liability should initially be measured at fair value. If a bank securitizes assets, retains all of the resulting securities, and classifies the securities as held-to-maturity debt securities, no separate servicing asset or liability shall be recorded. If a bank purchases servicing assets or assumes servicing liabilities in a transaction other than a sale or securitization of the financial assets being serviced, the asset or liability shall be recorded at fair value. For purchased servicing assets, the fair value is presumptively the price paid to acquire the servicing.

Servicing Assets and Liabilities (cont.):

All servicing assets and liabilities carried on the books of reporting banks shall be amortized in proportion to, and over the period of, estimated net servicing income (servicing revenue in excess of servicing costs) or net servicing loss (servicing costs in excess of servicing revenue). The book value of servicing assets and liabilities should be reviewed at least quarterly. The servicing assets shall be stratified into groups based on one or more of the predominant risk characteristics of the underlying financial assets for purposes of determining fair value. If the book value of a stratum of a servicing asset exceeds its fair value, the servicing asset is considered to be impaired and the book value shall be reduced to fair value through a valuation allowance for that stratum. If the fair value of a servicing liability increases above the book value, the increased obligation shall be recognized as a loss in current earnings. The fair value of servicing assets (liabilities) is the amount at which the assets (liabilities) could be bought (incurred) or sold (settled) in a bona fide transaction between willing parties.

For purposes of these reports, servicing assets resulting from contracts to service loans secured by real estate (as defined for Schedule RC-C, Part I, item 1, in the Glossary entry for "Loans secured by real estate") should be reported in Schedule RC-M, item 2.a, "Mortgage servicing assets." Servicing assets resulting from contracts to service all other financial assets should be reported in Schedule RC-M, item 2.b, "Purchased credit card relationships and nonmortgage servicing assets." In addition, certain information about assets serviced by the reporting bank should be reported in Schedule RC-S, Securitization and Asset Sale Activities.

Settlement Date Accounting: See "trade date and settlement date accounting."

Shell Branches: Shell branches are limited service branches that do not conduct transactions with residents, other than with other shell branches, in the country in which they are located. Transactions at shell branches are usually initiated and effected by their head office or by other related branches outside the country in which the shell branches are located, with records and supporting documents maintained at the initiating offices. Examples of such locations are the Bahamas and the Cayman Islands.

Short Position: When a bank sells an asset that it does not own, it has established a short position. If on the report date a bank is in a short position, it shall report its liability to purchase the asset in Schedule RC, item 15, "Trading liabilities." In this situation, the right to receive payment shall be reported in Schedule RC-F, item 5, "Other" assets. Short positions shall be reported gross. Short trading positions shall be revalued consistent with the method used by the reporting bank for the valuation of its trading assets.

Significant Subsidiary: See "subsidiaries."

Standby Letter of Credit: See "letter of credit."

Start-Up Activities: Guidance on the accounting and reporting for the costs of start-up activities, including organization costs, is set forth in AICPA Statement of Position 98-5, "Reporting on the Costs of Start-Up Activities." A summary of this accounting guidance follows. For further information, see AICPA Statement of Position 98-5.

Start-up activities are defined broadly as those one-time activities related to opening a new facility, introducing a new product or service, conducting business in a new territory, conducting business with a new class of customer, or commencing some new operation. Start-up activities include activities related to organizing a new entity, such as a new bank, the costs of which are commonly referred to as organization costs.

FFIEC 031 and 041 A-75 GLOSSARY (6-01)

¹ Organization costs for a bank are the <u>direct</u> costs incurred to incorporate and charter the bank. Such costs include, but are not limited to, professional (e.g., legal, accounting, and consulting) fees and printing costs directly related to the chartering or incorporation process, filing fees paid to chartering authorities, and the cost of economic impact studies.

Start-Up Activities (cont.):

Costs of start-up activities, including organization costs, should be expensed as incurred. Costs of acquiring or constructing premises and fixed assets and getting them ready for their intended use are not start-up costs, but the costs of using such assets that are allocated to start-up activities (e.g., depreciation of computers) are considered start-up costs.

For a new bank, pre-opening expenses such as salaries and employee benefits, rent, depreciation, supplies, directors' fees, training, travel, postage, and telephone are considered start-up costs. Pre-opening income earned and expenses incurred from the bank's inception until the date the bank commences operations should be reported in the Report of Income using one of the two following methods, consistent with the manner in which the bank reports pre-opening income and expenses for other financial reporting purposes:

- (1) Pre-opening income and expenses for the entire period from the bank's inception until the date the bank commences operations should be reported in the appropriate items of Schedule RI, Income Statement, each quarter during the calendar year in which operations commence; or
- (2) Pre-opening income and expenses for the period from the bank's inception until the beginning of the calendar year in which the bank commences operations should be included, along with the bank's opening (original) equity capital, in Schedule RI-A, item 5, "Sale, conversion, acquisition, or retirement of capital stock, net." The net amount of these pre-opening income and expenses should be identified and described in Schedule RI-E, item 7. Pre-opening income earned and expenses incurred during the calendar year in which the bank commences operations should be reported in the appropriate items of Schedule RI, Income Statement, each quarter during the calendar year in which operations commence.

STRIPS: See "coupon stripping, Treasury receipts, and STRIPS."

Subordinated Notes and Debentures: A subordinated note or debenture is a form of debt issued by a bank or a consolidated subsidiary. When issued by a bank, a subordinated note or debenture is not insured by a federal agency, is subordinated to the claims of depositors, and has an original weighted average maturity of five years or more. Such debt shall be issued by a bank with the approval of, or under the rules and regulations of, the appropriate federal bank supervisory agency and is to be reported in Schedule RC, item 19, "Subordinated notes and debentures."

When issued by a subsidiary, a note or debenture may or may not be explicitly subordinated to the deposits of the parent bank and is to be reported in Schedule RC, item 16, "Other borrowed money," or item 19, "Subordinated notes and debentures," as appropriate.

Those subordinated notes and debentures that are to be reported in Schedule RC, item 19, include mandatory convertible debt.

Subsidiaries: The treatment of subsidiaries in the Reports of Condition and Income depends upon the degree of ownership held by the reporting bank.

A majority-owned subsidiary of the reporting bank is a subsidiary in which the parent bank directly or indirectly owns more than 50 percent of the outstanding voting stock.

A significant subsidiary of the reporting bank is a majority-owned subsidiary that meets any one or more of the following tests:

Subsidiaries (cont.):

(1) The bank's direct and indirect investment in and advances to the subsidiary equals five percent or more of the total equity capital of the parent bank.

NOTE: For the purposes of this test, the amount of direct and indirect investments and advances is either (a) the amount carried on the books of the parent bank or (b) the parent's proportionate share in the total equity capital of the subsidiary, whichever is greater.

- (2) The parent bank's proportional share (based on equity ownership) of the subsidiary's gross operating income or revenue amounts to five percent or more of the gross operating income or revenue of the consolidated parent bank.
- (3) The subsidiary's income or loss before income taxes amounts to five percent or more of the parent bank's income or loss before income taxes.
- (4) The subsidiary is, in turn, the parent of one or more subsidiaries which, when consolidated with the subsidiary, constitute a significant subsidiary as defined in one or more of the above tests.

An associated company is a corporation in which the bank, directly or indirectly, owns 20 to 50 percent of the outstanding voting stock and over which the bank exercises significant influence. This 20 to 50 percent ownership is presumed to carry "significant" influence unless the bank can demonstrate the contrary to the satisfaction of the appropriate federal supervisory authority.

A corporate joint venture is a corporation owned and operated by a group of banks or other businesses ("joint venturers"), no one of which has a majority interest, as a separate and specific business or project for the mutual benefit of the joint venturers. Each joint venturer may participate, directly or indirectly, in the management of the joint venture. An entity that is a majority-owned subsidiary of one of the joint venturers is not a corporate joint venture.

The equity ownership in majority-owned subsidiaries that are not consolidated on the Reports of Condition and Income (e.g., subsidiaries held on a temporary basis) and in associated companies is accounted for using the equity method of accounting and is reported in Schedule RC-M, item 4, and in Schedule RC, item 8, "Investments in unconsolidated subsidiaries and associated companies."

Ownership in a corporate joint venture is to be treated in the same manner as an associated company (defined above) only to the extent that the equity share represents significant influence over management. Otherwise, equity holdings in a joint venture are treated as holdings of corporate stock and income is recognized only when distributed in the form of dividends.

See also "equity method of accounting."

Suspense Accounts: Suspense accounts are temporary holding accounts in which items are carried until they can be identified and their disposition to the proper account can be made. Such accounts may also be known as interoffice or clearing accounts. The balances of suspense accounts as of the report date should not automatically be reported as "Other assets" or "Other liabilities." Rather, the items included in these accounts should be reviewed and material amounts should be reported in the appropriate accounts of the Reports of Condition and Income.

Syndications: A syndication is a participation, usually involving shares in a single loan, in which several participants agree to enter into an extension of credit under a bona fide binding agreement that provides that, regardless of any event, each participant shall fund and be at risk only up to a specified percentage of the total extension of credit or up to a specified dollar amount. In a syndication, the participants agree to the terms of the participation prior to the execution of the final agreement and the contract is executed by the obligor and by <u>all</u> the participants, although there is usually a lead institution organizing or managing the credit. Large commercial and industrial loans, large loans to finance companies, and large foreign loans may be handled through such syndicated participations.

Each participant in the syndicate, including the lead bank, records its own share of the participated loan and the total amount of the loan is not entered on the books of one bank to be shared through transfers of loans. Thus, the initial operation and distribution of this type of participation does not require a determination as to whether a transfer that should be accounted for as a sale has occurred. However, any subsequent transfers of shares, or parts of shares, in the syndicated loan would be subject to the provisions of FASB Statement No. 140 governing whether these transfers should be accounted for as a sale or a secured borrowing. (See the Glossary entry for "transfers of financial assets.")

Telephone Transfer Account: See "deposits."

Term Federal Funds: See "federal funds transactions."

Time Deposits: See "deposits."

Trade Date and Settlement Date Accounting: For purposes of the Reports of Condition and Income, the preferred method for reporting transactions in held-to-maturity securities, available-for-sale securities, and trading assets (including money market instruments) other than derivative contracts (see the Glossary entry for "derivative contracts") is on the basis of trade date accounting. However, if the reported amounts under settlement date accounting would not be materially different from those under trade date accounting, settlement date accounting is acceptable. Whichever method a bank elects should be used consistently, unless the bank has elected settlement date accounting and subsequently decides to change to the preferred trade date method.

Under trade date accounting, assets purchased shall be recorded in the appropriate asset category on the trade date and the bank's obligation to pay for those assets shall be reported in Schedule RC-G, item 4, "Other" liabilities. Conversely, when an asset is sold, it shall be removed on the trade date from the asset category in which it was recorded, and the proceeds receivable resulting from the sale shall be reported in Schedule RC-F, item 5, "Other" assets. Any gain or loss resulting from such transaction shall also be recognized on the trade date. On the settlement date, disbursement of the payment or receipt of the proceeds will eliminate the respective "Other liability" or "Other asset" entry resulting from the transaction.

Under <u>settlement date accounting</u>, assets purchased are not recorded until settlement date. On the trade date, no entries are made. Upon receipt of the assets on the settlement date, the asset is reported in the proper asset category and payment is disbursed. The selling bank, on the trade date, would make no entries. On settlement date, the selling bank would reduce the appropriate asset category and reflect the receipt of the payment. Any gain or loss resulting from such transaction would be recognized on the settlement date.

Trading Account: Banks that (a) regularly underwrite or deal in securities, interest rate contracts, foreign exchange rate contracts, other off-balance sheet commodity and equity contracts, other financial instruments, and other assets for resale, (b) acquire or take positions in such items principally for the purpose of selling in the near term or otherwise with the intent to resell in order to profit from short-term price movements, or (c) acquire or take positions in such items as an accommodation to customers or for other trading purposes shall report such assets or positions as trading assets or liabilities.

Trading Account (cont.):

All trading assets should be segregated from a bank's other assets and reported in Schedule RC, item 5, "Trading assets." In addition, for banks that reported average trading assets (Schedule RC-K, item 7) of \$2 million or more for any quarter of the preceding calendar year should detail the types of assets and liabilities in the trading account in Schedule RC-D, Trading Assets and Liabilities. A bank's failure to establish a separate account for assets that are used for trading purposes does not prevent such assets from being designated as trading for purposes of these reports. For further information, see FASB Statement No. 115, "Accounting for Certain Investments in Debt and Equity Securities."

All trading account assets should be reported at their fair value with unrealized gains and losses recognized in current income. When a security or other asset is acquired, a bank should determine whether it intends to hold the asset for trading or for investment (e.g., for securities, available-for-sale or held-to-maturity). A bank should not record a newly acquired asset in a suspense account and later determine whether it was acquired for trading or investment purposes. Regardless of how a bank categorizes a newly acquired asset, management should document its decision.

All trading liabilities should be segregated from other transactions and reported in Schedule RC, item 15, "Trading liabilities." The trading liability account includes the fair value of derivative contracts held for trading that are in loss positions and short positions arising from sales of securities and other assets that the bank does not own. (See the Glossary entry for "short position.") Trading account liabilities should be reported at fair value with unrealized gains and losses recognized in current income in a manner similar to trading account assets.

Given the nature of the trading account, transfers into or from the trading category should be rare. Transfers between a trading account and any other account of the bank must be recorded at fair value at the time of the transfer. For a security transferred from the trading category, the unrealized holding gain or loss at the date of the transfer will already have been recognized in earnings and should not be reversed. For a security transferred into the trading category, the unrealized holding gain or loss at the date of the transfer should be recognized in earnings.

Transaction Account: See "deposits."

Transfers of Financial Assets: The accounting and reporting standards for transfers of financial assets are set forth in FASB Statement No. 140, "Accounting for Transfers and Servicing of Financial Assets and Extinguishments of Liabilities," which replaces FASB Statement No. 125 of the same name. These standards are based on consistent application of a financial components approach that focuses on control. Under the financial components approach, after the reporting bank transfers financial assets, it recognizes the financial and servicing assets it controls and the liabilities it has incurred, removes financial assets from the balance sheet when control has been surrendered, and removes liabilities from the balance sheet when extinguished. A summary of these accounting and reporting standards follows. For further information, see FASB Statement No. 140, the FASB staff implementation guide to Statement No. 140, and the Glossary entries for "Extinguishments of Liabilities" and "Servicing Assets and Liabilities."

FASB Statement No. 140 is effective for transfers of assets, including repurchase agreements, loan participations, dollar-rolls, securities lending, and similar transactions, occurring after March 31, 2001. However, the provisions of Statement No. 140 governing the accounting for collateral are effective for December 31, 2000, year-end financial statements. Banks should apply Statement No. 140 prospectively after its effective dates, with earlier or retroactive application not permitted, except for the provisions of this accounting standard applicable to servicing contracts in existence before January 1, 1997 (see the Glossary entry for "Servicing Assets and Liabilities"), and financial assets subject to prepayment held on or acquired after January 1, 1997 (discussed below in this Glossary entry). FASB Statement No. 125 generally applies to transfers of financial assets occurring after December 31, 1996, but before April 1, 2001.

Transfers of Financial Assets (cont.):

A financial asset is cash, evidence of an ownership interest in another entity, or a contract that conveys to the bank a contractual right either to receive cash or another financial instrument from another entity or to exchange other financial instruments on potentially favorable terms with another entity. Most of the assets on a bank's balance sheet are financial assets, including balances due from depository institutions, securities, federal funds sold, securities purchased under agreements to resell, loans and lease financing receivables, and interest-only strips receivable. However, servicing assets are not financial assets. Financial assets also include financial futures contracts, forward contracts, interest rate swaps, interest rate caps, interest rate floors, and certain option contracts.

Determining Whether a Transfer Should be Accounted for as a Sale or a Secured Borrowing -- A bank should account for a transfer of its financial assets (or a transfer of all or a portion of one of its financial assets) in which it surrenders control over those financial assets as a sale to the extent that it receives consideration other than beneficial interests in the transferred assets in exchange. According to FASB Statement No. 140, a transferor (i.e., the entity that transfers all or a portion of one or more financial assets) has surrendered control over transferred assets, and therefore has sold the assets, if and only if all three of the following conditions are met:

- (1) The transferred assets have been isolated from the transferor, i.e., put presumptively beyond the reach of the transferor and its creditors, even in bankruptcy or other receivership.
- (2) Each transferee (i.e., the entity that receives all or a portion of one or more financial assets from the transferor), or each holder of the beneficial interests in a qualifying special purpose entity that is a transferee, has the right to pledge or exchange the assets it received, and no condition both constrains the transferee from taking advantage of that right and provides more than a trivial benefit to the transferor.
- (3) The transferor does not maintain effective control over the transferred assets through (a) an agreement that both entitles and obligates it to repurchase or redeem the transferred assets before their maturity or (b) the ability to unilaterally cause the holder to return specific assets, other than through a cleanup call option.

If a transfer of financial assets in exchange for cash or other consideration (other than beneficial interests in the transferred assets) does not satisfy the criteria for sale treatment, the transfer should be accounted for as a secured borrowing with pledge of collateral.

Accounting for a Transfer That Qualifies as a Sale -- Upon the completion of a transfer of financial assets that satisfies all three of the conditions to be accounted for as a sale, the purchaser(s) must recognize on the balance sheet all assets obtained and any liabilities incurred and initially measure them at fair value. The aggregate fair value is presumed to be the price paid by the purchaser(s). As for the selling bank, it must:

Remove all assets sold from the balance sheet while continuing to carry on its balance sheet any retained interest in the transferred assets, including, if applicable, servicing assets, retained undivided interests, and beneficial interests in assets transferred to a qualifying special-purpose entity in a securitization. The selling bank must allocate the amount at which the transferred assets were carried on the balance sheet at the date of the transfer between the assets sold and the retained interests, if any, based on their relative fair values at that date.

FFIEC 031 and 041 A-80 **GLOSSARY**

Both FASB Statement Nos. 125 and 140 define an interest-only strip receivable as the contractual right to receive some or all of the interest due on a bond, mortgage loan, collateralized mortgage obligation, or other interest-bearing financial asset.

Transfers of Financial Assets (cont.):

(2) Recognize on the balance sheet all cash, derivative financial instruments, and other assets obtained and all servicing liabilities and other liabilities incurred in consideration as proceeds of the sale. Derivatives include put or call options held or written (e.g., guarantee or recourse obligations), forward commitments (e.g., commitments to deliver additional receivables in some securitizations), and swaps (e.g., provisions that convert interest rates from fixed to variable).

- (3) Initially measure the assets obtained and liabilities incurred in a sale at fair value. However, if it is not practicable to estimate the fair value of an asset obtained, the selling bank must record the asset at zero. If it is not practicable to estimate the fair value of a liability incurred, the selling bank must not recognize any gain on the sale. The liability should be recorded on the balance sheet at the greater of:
 - (a) The amount, if any, by which the fair values of the assets obtained in the sale less the fair values of the liabilities incurred in the sale exceeds the sum of the carrying values of the assets transferred, or
 - (b) The amount of loss that is probable of occurring in accordance with FASB Statement No. 5, "Accounting for Contingencies," as interpreted by FASB Interpretation No. 14, "Reasonable Estimation of the Amount of a Loss." Under that interpretation, when the reasonable estimate of the loss is a range and some amount within the range appears at the time to be a better estimate than any other amount within the range, that amount should be considered probable. When no amount within the range is a better estimate than any other amount, the minimum amount in the range should be considered probable.
- (4) Recognize in income any gain or loss on the sale.

Banks should refer to FASB Statement No. 140 for implementation guidance for accounting for transfers of partial interests, transfers of certain lease receivables, securities lending transactions, repurchase agreements including "dollar rolls," "wash sales," loan syndications, loan participations (discussed below), risk participations in bankers acceptances, factoring arrangements, and transfers of receivables with recourse. However, this accounting standard does not provide guidance on the accounting for most assets and liabilities recorded on the balance sheet following a transfer accounted for as a sale. As a result, after their initial measurement or carrying amount allocation, these assets and liabilities should be accounted for in accordance with the existing generally accepted accounting principles applicable to them.

Loan Participations – FASB Statement No. 140 applies to loan participations occurring after March 31, 2001, including transfers by the originating lender to a participating institution that take place after that date under loan participation agreements that originated before April 1, 2001. However, for transfers by an FDIC-insured institution, the isolation test in Statement No. 140 (described above under "Determining Whether a Transfer Should be Accounted for as a Sale or a Secured Borrowing") applies to transfers occurring after December 31, 2001. If a loan participation agreement gives a participating institution the right to pledge or exchange the participation, the isolation test has been met, and the originating lender does not maintain effective control over the participation, then the conditions for the surrender of control have been met and the originating lender should account for transfers to the participating institution as sales of financial assets.

An originating lender's right of first refusal on a bona fide offer to the participating institution from a third party, a requirement for a participating institution to obtain the originating lender's permission that shall not be unreasonably withheld, or a prohibition on the participating institution's sale of the participation to the originating lender's competitor (if other potential willing buyers exist) is a limitation on the participating institution's rights, but is presumed not to constrain a participant from exercising its right to

Transfers of Financial Assets (cont.):

pledge or exchange the participation. However, if the participation agreement constrains the participating institution from pledging or exchanging its participation, the originating lender presumptively receives more than a trivial benefit, has not relinquished control over the loan, and should account for the transfer as a secured borrowing.

A loan participation agreement may give the originating lender the contractual right to repurchase a loan participation at any time. In this situation, the right to repurchase is effectively a call option on a specific loan participation, i.e., a participation that is not readily obtainable in the marketplace. Regardless of whether this option is freestanding or attached, it either constrains the participating institution from pledging or exchanging its participation or results in the originating lender maintaining effective control over the participation. As a consequence, the contractual right to repurchase precludes sale accounting and the transfer should be accounted for as a secured borrowing.

In addition, under a loan participation agreement, the originating lender may give the participating institution the right to resell the participation, but reserves the right to call the loan participation at any time from whomever holds it and can enforce that right by discontinuing the flow of interest to the holder of the participation at the call date. In this situation, the originating lender has maintained effective control over the participation and the transfer should be accounted for as a secured borrowing, not as a sale.

If an originating FDIC-insured lender has transferred a loan participation to a participating institution with recourse prior to January 1, 2002, the existence of the recourse obligation in and of itself does not preclude sale accounting for the transfer under FASB Statement No. 140. If a loan participation transferred with recourse prior to January 1, 2002, meets the three conditions identified above in order for the transferor to have surrendered control over the transferred assets, the transfer should be accounted for as a sale for financial reporting purposes. However, a loan participation sold with recourse is subject to the banking agencies' risk-based capital requirements as discussed in the Glossary entry for "sales of assets for risk-based capital purposes" and in the instructions for Schedule RC-R, Regulatory Capital.

If an originating FDIC-insured lender transfers a loan participation with recourse after December 31, 2001, the participation generally will not be considered isolated from the transferor, i.e., the originating lender, in the event of an FDIC receivership. Section 360.6 of the FDIC's regulations limits the FDIC's ability to reclaim loan participations transferred "without recourse," as defined in the regulations, but does not limit the FDIC's ability to reclaim loan participations transferred with recourse. Under Section 360.6, a participation that is subject to an agreement that requires the originating lender to repurchase the participation or to otherwise compensate the participating institution due to a default on the underlying loan is considered a participation "with recourse." As a result, a loan participation transferred "with recourse" after December 31, 2001, generally should be accounted for as a secured borrowing and not as a sale for financial reporting purposes. This means that the originating lender should not remove the participation from its loan assets on the balance sheet, but should report the secured borrowing in Schedule RC, item 16, "Other borrowed money."

<u>Financial Assets Subject to Prepayment</u> -- Financial assets such as interest-only strips receivable and certain loans, debt securities, other receivables, and retained interests in securitizations can be contractually prepaid or otherwise settled in such a way that the holder of the financial asset would not recover substantially all of its recorded investment. After their initial recording on the balance sheet, financial assets of this type must be subsequently measured at fair value like available-for-sale securities or trading securities.

Traveler's Letter of Credit: See "letter of credit."

Treasury Receipts: See "coupon stripping, Treasury receipts, and STRIPS."

Treasury Stock: Treasury stock is stock that the bank has issued and subsequently acquired, but that has not been retired or resold. As a general rule, treasury stock, whether carried at cost or at par value, is a deduction from a bank's total equity capital. For purposes of the Reports of Condition and Income, the carrying value of treasury stock should be reported (as a negative number) in Schedule RC, item 27, "Other equity capital components."

"Gains" and "losses" on the sale, retirement, or other disposal of treasury stock are <u>not</u> to be reported in Schedule RI, Income Statement, but should be reflected in Schedule RI-A, item 6, "Treasury stock transactions, net." Such gains and losses, as well as the excess of the cost over the par value of treasury stock carried at par, are generally to be treated as adjustments to Schedule RC, item 25, "Surplus."

NOTE: National banks are generally prohibited by 12 USC 83 from purchasing shares of their own stock.

For further information, see Accounting Research Bulletin No. 43, as amended by APB Opinion No. 6.

Troubled Debt Restructurings: The accounting standards for troubled debt restructurings are set forth in FASB Statement No. 15, "Accounting by Debtors and Creditors for Troubled Debt Restructurings," as amended by FASB Statement No. 114, "Accounting by Creditors for Impairment of a Loan." A summary of this amended accounting standard follows. For further information, see FASB Statements No. 15 and No. 114.

A troubled debt restructuring is a restructuring in which a bank, for economic or legal reasons related to a borrower's financial difficulties, grants a concession to the borrower that it would not otherwise consider. The restructuring of a loan or other debt instrument (hereafter referred to collectively as a "loan") may include (1) the transfer from the borrower to the bank of real estate, receivables from third parties, other assets, or an equity interest in the borrower in full or partial satisfaction of the loan (see the Glossary entry for "foreclosed assets" for further information), (2) a modification of the loan terms, or (3) a combination of the above. A loan extended or renewed at a stated interest rate equal to the current interest rate for new debt with similar risk is not to be reported as a restructured loan.

The <u>recorded amount of a loan</u> is the loan balance adjusted for any unamortized premium or discount and unamortized loan fees or costs, less any amount previously charged off, plus <u>recorded</u> accrued interest.

In cases where the new terms of the restructured troubled debt provide for a reduction of either interest or principal (referred to as a modification of terms), the institution should measure any loss on the restructuring in accordance with the guidance concerning impaired loans set forth in the Glossary entry for "loan impairment," except that a troubled debt restructuring involving a modification of terms before the effective date of FASB Statement No. 114 may continue to be accounted for and disclosed in accordance with FASB Statement No. 15 as long as the restructured loan is not impaired based on the terms of the restructuring agreement. See the Glossary entry for "nonaccrual status" for a discussion of the conditions under which a nonaccrual asset which has undergone a troubled debt restructuring (including those that involve a multiple note structure) may be returned to accrual status.

A troubled debt restructuring in which a bank receives physical possession of the borrower's assets, regardless of whether formal foreclosure or repossession proceedings take place, should be accounted for in accordance with paragraph 34 of FASB Statement No. 15, as amended. Thus, in such situations, the loan should be treated as if assets have been received in satisfaction of the loan and reported as described in the Glossary entry for "foreclosed assets."

Despite the granting of some type of concession by a bank to a borrower, a troubled debt restructuring may still result in the recorded amount of the loan bearing a market yield, i.e., an effective interest rate that at the time of the restructuring is greater than or equal to the rate that the bank is willing to accept for a new extension of credit with comparable risk. This may arise as a result of reductions in the recorded amount of the loan prior to the restructuring (e.g., by charge-offs). All loans that have undergone troubled debt restructurings and that are in compliance with their modified terms must be reported as restructured loans in Schedule RC-C, part I, Memorandum item 1. However, a restructured loan that is in compliance with its modified terms and yields a market rate need not continue to be reported as a troubled debt restructuring in this memorandum item in calendar years after the year in which the restructuring took place.

A restructuring may include both a modification of terms and the acceptance of property in partial satisfaction of the loan. The accounting for such a restructuring is a two step process. First, the recorded amount of the loan is reduced by the fair value less cost to sell of the property received. Second, the institution should measure any impairment on the remaining recorded balance of the restructured loan in accordance with the guidance concerning impaired loans set forth in FASB Statement No. 114.

Troubled Debt Restructurings (cont.):

A restructuring may involve the substitution or addition of a new debtor for the original borrower. The treatment of these situations depends upon their substance. Restructurings in which the substitute or additional debtor controls, is controlled by, or is under common control with the original borrower, or performs the custodial function of collecting certain of the original borrower's funds, should be accounted for as modifications of terms. Restructurings in which the substitute or additional debtor does not have a control or custodial relationship with the original borrower should be accounted for as a receipt of a "new" loan in full or partial satisfaction of the original borrower's loan. The "new" loan should be recorded at its fair value.

A credit analysis should be performed for a restructured loan in conjunction with its restructuring to determine its collectibility and estimated credit loss. When available information confirms that a specific restructured loan, or a portion thereof, is uncollectible, the uncollectible amount should be charged off against the allowance for loan and lease losses at the time of the restructuring. As is the case for all loans, the credit quality of restructured loans should be regularly reviewed. The bank should periodically evaluate the collectibility of the restructured loan so as to determine whether any additional amounts should be charged to the allowance for loan and lease losses or, if the restructuring involved an asset other than a loan, to another appropriate account.

U.S. Banks: See "banks, U.S. and foreign."

U.S. Territories and Possessions: United States territories and possessions include American Samoa, Guam, the Northern Mariana Islands, the U.S. Virgin Islands, and the U.S. trust territories.

Valuation Allowance: In general, a valuation allowance is an account established against a specific asset category or to recognize a specific liability, with the intent of absorbing some element of estimated loss. Such allowances are created by charges to expense in the Report of Income and those established against asset accounts are netted from the accounts to which they relate for presentation in the Report of Condition. Provisions establishing or augmenting such allowances are to be reported as "Other noninterest expense" except for the provision for loan and lease losses which is reported in a separate, specifically designated income statement item on Schedule RI.

When-Issued Securities Transactions: Transactions involving securities described as "when-issued" or "when-as-and-if-issued" are, for the purposes of these reports, to be treated as conditional transactions in a security authorized for issuance but not yet actually issued. Purchases and sales of when-issued securities for which settlement date has not occurred as of the report date are <u>not</u> to be reflected in the balance sheet, Schedule RC, <u>until</u> settlement date. Banks should report as forward contracts in Schedule RC-L, item 11.b, commitments to purchase and sell when-issued securities that are not excluded from the requirements of FASB Statement No. 133 as a regular-way security trade. Such contracts should be reported on a gross basis (except that banks may net purchases and sales of the identical security with the same party). Commitments to purchase when-issued securities that are excluded from the requirements of Statement No. 133 should be reported as "Other off-balance sheet liabilities" in Schedule RC-L, item 9, and commitments to sell when-issued securities that are excluded from the requirements of Statement No. 133 should be reported as "Other off-balance sheet assets" in Schedule RC-L, item 10, subject to the existing reporting thresholds for these two items.

Trading in when-issued securities normally begins when the U.S. Treasury or some other issuer of securities announces a forthcoming issue. (In some cases, trading may begin in anticipation of such an announcement and should also be reported as described herein.) Such transactions are contingent upon the actual issuance of the security. Since the exact price and terms of the security are unknown before the auction date, trading prior to that date is on a "yield" basis. On the auction date the exact terms and price of the security become known and when-issued trading continues until settlement date, when the securities are delivered and the issuer paid. On settlement date, the securities purchased by the bank shall be reported as held-to-maturity securities in Schedule RC, item 2.a, as available-for-sale securities in Schedule RC, item 2.b, or as trading assets in Schedule RC, item 5, as

appropriate.

INDEX

	1
Acceptances	RI-4, RI-13, RI-B-2, RI-B-4, RC-C-5, RC-C-15, RC-L-5, RC-N-6, RC-N-9, RC-R-18, RC-R-19, RC-T-8, A-4, A-54
Bank's Acceptance Liability	RC-10, RC-H-1, A-5
Customers' Acceptance Liability	RC-8, RC-H-1, A-5
Participations in	RC-L-5, RC-R-1, RC-R-2, RC-R-20, RC-R-21, A-6
Accounting Changes	A-1
Accounting Errors	RI-A-1, RI-E-2, A-2
Accounting Research Bulletin No. 43	A-82
Accounts Payable	RC-G-2
Accrual Basis Reporting	12
Accrued Expenses	RC-G-1
Accrued Interest Receivable	RC-F-1, A-60
Accumulated Net Gains (Losses) on Cash Flow Hedges	13, RI-A-4, RC-14, RC-R-3
Change in	RI-A-4
Accumulated Other Comprehensive Income	13, RC-13, A-31, A-38
Acquisition, Development, or Construction (ADC) Arrangements	13, RC-14, RC-R-3
Adjusted Trading	A-73
Advertising Expense	RI-20, RI-E-1
Advisory Fees	RI-11
Agreement Corporation	A-8, A-16, A-33, A-40
AICPA	
Audit and Accounting Guide for Banks and Savings Institutions	A-66
Practice Bulletin No. 4	A-39
Practice Bulletin No. 6	RC-N-2, A-60, A-61
Statement of Position No. 93-6	RC-15, RC-M-9
Statement of Position No. 98-1	A-48
Statement of Position No. 98-5	A-75

Allocated Transfer Risk Reserve	RI-B-7, RC-C-1, RC-R-12, RC-R-14, RC-R-29
Provision for Allocated Transfer Risk	RI-22
Allowance for Credit Losses on Off-Balance Sheet Credit Exposures	RI-B-6, RC-G-1, RC-R-8
Provision	RI-22
Allowance for Loan and Lease Losses	11, 12, RI-9, RI-B-1, RI-B-6, RI-B-7, RI-E-2, RC-6, RC-R-8, RC-R-12, RC-R-18, A-3, A-57
Changes in	RI-B-6
Excess	RC-R-29
Interagency Policy Statement	11, A-4, A-57
Provision	RI-9, RI-B-7, RI-D-1, A-3, A-57
Amended Reports	7, RI-A-1, RI-B-6
Annuities	RC-M-11, RC-T-8
Sales	RI-12, RI-26, RC-M-10
APB	
Opinion No. 6	A-82
Opinion No. 16	RC-M-2, A-11
Opinion No. 20	A-2
Opinion No. 21	A-66
Opinion No. 30	RI-24, A-34
Applicability of Generally Accepted Accounting Principles	11
Asset-Backed Securities	RI-6, RC-B-7, RC-K-2, RC-S-1
Commercial Paper Conduits	RC-S-7
Asset Sale Activities	RC-S-1
Assets and Liabilities of IBFs	RC-I-1
Assets Netted Against Deposit Liabilities	RC-O-7
Assets Under Management	RC-M-11
Associated Company	12, RI-11, RI-12, RI-15, RC-8, RC-M-7, RC-R-20, A-33, A-77

ATS Account	RC-E-4, RC-K-3, RI-7, A-20
Audit Fees	RI-21, RC-T-7
Auditing Work Performed	RC-16
Automated Teller Machines	RI-10, RI-13, A-18, A-21, A-22
Automobile Loans	RC-B-8, RC-C-14, RC-S-1
Average Total Assets	RC-K-3, RC-R-9, RC-R-10

Balance Sheet	RC-1
Balances Due From Depository Institutions	RI-5, RC-1, RC-A-4, RC-K-1, RC-R-15, A-64
Bank Investment Contracts	RC-T-8
Bank Premises	12, RI-12, RI-18, RC-7, RC-R-20
Bankers Acceptances	RI-4, RI-13, RC-C-5, RC-C-15, RC-H-1, RC-L-5, RC-R-18, RC-R-19, RC-T-8, A-4
Banks	A-7
Commercial Banks in the U.S.	RC-A-4, RC-C-8, RC-E-8, A-8
Foreign Banks	RI-B-2, RC-E-18, RC-N-6, RC-O-7, A-7
Foreign Central Banks	RC-A-5
in Foreign Countries	RC-A-5, RC-C-8, RC-E-9, A-9
U.S. Banks	RI-B-2, RC-E-18, RC-N-6, RC-O-6, RC-O-7, A-8
U.S. Branches and Agencies of Foreign Banks	RC-A-4, RC-C-8, RC-E-8, RC-E-18, A-9, A-16
Benefit-Responsive Depository Institution Investment Contracts	RC-O-6
Bilateral Netting Agreements	RC-R-28, RC-R-30
Bill-of-Lading Draft	A-15
Borrowings in Foreign Offices	A-9
Branch Acquisition	4
Branch Sales	RI-14, RI-20
Brokerage Fees	RI-11
Broker's Security Draft	A-11
Business Combinations	4, RI-1, RI-A-3, RI-B-6, RI-B-7, RC-K-1, A-11, A-47

Capital Allocation Adjustment	RI-D-2
Capital Reserves	RC-12
Capital Stock Transactions	RI-A-2
Capitalization of Interest Costs	A-13
Caps	RC-L-14, RC-L-15, A-27
Carrybacks and Carryforwards	RI-23, A-44
Cash and Balances Due From Depository Institutions	RC-1, RC-A-1, RC-R-15
Cash Collateral Accounts	RC-R-23, RC-S-2, A-71
Cash Flow Hedges	A-29, A-30
Accumulated Net Gains (Losses) on	13, RI-A-4, RC-14, RC-R-3
Cash Items	
in Process of Collection	RC-1, RC-2, RC-A-2
Not in Process of Collection	RC-F-3
Cash Management Arrangements	A-14
Cash Surrender Value of Life Insurance	RI-14, RC-F-3
Cashiers' Checks	RI-13, RC-E-6, A-18
Certificates of Deposit	RC-4, RC-6, RC-A-4, RC-E-12, RC-E-13, RC-E-15, RC-R-19, RC-T-8, A-23
Certified Checks	RI-10, RC-E-5, RC-E-6, RC-E-18
Changes in Accounting Estimates	A-1
Changes in Accounting Principles	RI-24, RI-A-1, RI-E-2, A-1
Charge-offs and Recoveries	RI-B-1, RC-S-4
Close of Business	1
Collars	RC-L-14, RC-L-15, A-27
Collateral Invested Amounts	RC-R-23, RC-S-2, A-71
Collateralized Mortgage Obligations (CMOs)	RC-B-6, RC-B-16, RC-H-3, RC-T-8
Collective Investment Funds	RC-T-3, RC-T-7, RC-T-10
Commercial Paper	RC-6, RC-B-8, RC-B-9, RC-T-8, A-15
Commercial Paper Conduits	DO 0.7
'	RC-S-7

Commitments	RC-L-1, RC-L-14, RC-R-2, RC-R-26, RC-S-3, RC-S-5, RC-S-7, A-26
Fees	RI-2, RI-14, RC-E-3, A-55
Commodity and Other Contracts	RI-30, RC-L-10, RC-N-10, RC-R-27, RC-R-30, RC-R-32, A-27
Commodity Draft	A-15
Common Stock	RI-A-1, RI-A-2, RI-A-3, RC-12, RC-B-9, RC-T-9, A-11, A-12
Common Trust Funds	RC-T-10
Computer Software	RI-22, RC-F-4, A-48
Consolidation	8, 10, RC-O-10
Exclusions from	8
Rules of	9
Contingencies	RC-12, RC-L-1, A-58
Continuing Contract	RC-5, RC-9, A-34
Convertible Debt	RI-A-2
Core Deposit Intangibles	RC-M-3
Corporate Joint Venture	RI-11, RI-12, RI-15, RC-M-7, A-33, A-77
Corporate Trust and Agency Accounts	RC-T-4, RC-T-6, RC-T-9, RC-T-11
Corrections of Accounting Errors	RI-A-1, RI-E-2, A-2
Cost Recovery Method	A-37, A-60
Coupon Stripping	A-15
Covered Positions	RC-R-14, RC-R-28
Credit Cards	RI-4, RI-B-3, RC-B-7, RC-C-12, RC-C-31, RC-K-2, RC-N-7, RC-R-26, RC-S-1
Credit Balances on	RC-E-3
Credit Card Lines	RC-L-2
Fees	RI-14
Merchant Income and Expense	RI-14, RI-22
Credit Conversion Factors	RC-R-2, RC-R-27
Credit Enhancements	RC-S-2, RC-S-3, RC-S-5, RC-S-6, RC-S-7
Cumulative Effect of Changes in Accounting Principles	RI-24, RI-A-1, RI-E-2
Cumulative Foreign Currency Translation Adjustments	RC-14, RI-A-4

Currency and Coin	RC-1, RC-3, RC-A-3, RC-R-15
Custodial Services	RC-T-1
Custody Account	9, RC-T-5, RC-T-6, RC-T-11, A-16

Data Processing Services	RI-14, RI-19
Dealer Reserve Account	A-16
Debt/Equity Swaps	A-39
Debt-for-Development Swaps	A-40
Deferred Compensation Liabilities	RC-G-2
Deferred Tax Assets	A-42, A-63
Disallowed	RC-R-5, RC-R-12, RC-R-20
Net Deferred Tax Assets	RC-F-1
Deferred Tax Liabilities	A-42, A-63
Net Deferred Tax Liabilities	RC-G-1
Demand Notes Issued to the U.S. Treasury	RC-M-9
Deposit Broker	RI-7, RI-21, A-10
Deposit Insurance Expense	RI-20
Deposit Method	RC-M-4, RC-M-5, A-37
Depository Institution Investment Contracts	RC-O-6
Depository Institutions in the U.S.	RC-A-4, A-16
Deposits	RI-7, RI-9, RC-9, RC-E-1, A-17
Accounts of More Than \$100,000	RC-O-9
Accounts of \$100,000 or Less	RC-O-9
Adjustments to Demand Deposits for Reciprocal Balances	RC-O-6
Assets Netted Against Deposits	RC-O-7
ATS Account	RI-7, RC-E-4, RC-K-3, A-20
Brokered Deposits	RI-7, RI-21, RC-E-10, A-10
Cashiers' Checks	RI-13, RC-E-6, A-18

	1
Deposits (cont.)	
Certificates of Deposit	RC-4, RC-A-4, RC-E-12, RC-E-13, RC-E-15, RC-R-19, RC-T-8, A-23
Certified Checks	RI-10, RC-E-5, RC-E-6, RC-E-18
Demand Deposits	RC-E-4, RC-E-5, A-19
Early Withdrawal Penalties	RI-7, RI-15, A-23
Hypothecated	RC-C-1, RC-E-2, A-41
in Insured Branches in Puerto Rico and U.S. Territories and Possessions	RC-O-3
in Domestic Offices	RI-7, RC-9, RC-E-1
in Foreign Offices	RI-8, RC-9, RC-E-17, RC-K-4, A-9
Individuals, Partnerships, and Corporations, Deposits of	RC-E-5, RC-E-18
Interest Accrued and Unpaid on	RC-G-1, RC-O-3
Interest on	RI-7
Interest-Bearing	RC-9, RC-T-8, A-24
Maturity and Repricing Data for Time Deposits	RC-E-13, RC-E-18
Money Market Deposit Accounts (MMDAs)	RC-E-4, RC-E-5, RC-E-12, RC-T-8, A-23, A-25
Money Orders	RI-13, RC-E-3, RC-E-6, A-18
Noninterest-Bearing	RC-9, RC-T-8, A-25
Nontransaction Accounts	RI-8, RC-E-5, RC-E-11, RC-K-4, A-21
NOW Accounts	RI-7, RC-E-4, RC-K-3, RC-T-8, A-19
Number of Deposit Accounts	RC-O-9
Oakar Deposits	RC-O-5
of Consolidated Subsidiaries	RC-0-2
Official Checks	RC-E-5, RC-E-6, RC-E-18
Open-Account Time Deposits	RC-E-12, RC-E-13, RC-E-15, A-23
Other Savings Deposits	RC-E-12, A-23, A-25
Overdraft	RC-C-18, RC-E-2, A-63
Preauthorized Transfer Accounts	RI-7, RC-K-3, A-20

Preferred Deposits	RC-E-11
Retail Sweep Arrangements	A-24
Savings Deposits	RI-8, RC-E-4, RC-E-5, RC-E-12, A-21
Service Charges	RI-9, RI-14
States and Political Subdivisions in the U.S., Deposits of	RC-E-8, RC-E-18
Telephone Transfer Accounts	RI-7, RC-E-5, RC-K-3, A-20
Time Deposits	RC-E-5, A-23
Time Deposits of Less Than \$100,000	RI-8, RC-E-12, RC-E-13, RC-K-4
Time Deposits of \$100,000 or More	RI-8, RC-E-13, RC-E-15, RC-K-4
Transaction Accounts	RI-7, RC-E-4, RC-E-5, RC-K-3, A-18
Travelers' Checks	RI-13, RC-E-3, RC-E-6, RC-E-7
U.S. Government Deposits	RC-E-7, RC-E-18
Unamortized Premiums and Discounts	RC-O-4
Uninsured	RC-O-10
Depreciation	12, RI-18, RC-7, RC-T-6, A-76
Derivative Contracts	RI-10, RI-15, RI-21, RI-29, RI-31, RC-14, RC-F-3, RC-G-2, RC-L-5, RC-L-8, RC-L-16, RC-L-17, RC-N-10, RC-O-5, RC-R-1, RC-R-12, RC-R-20, RC-R-27, RC-R-30, RC-R-31, RC-T-2, A-25, A-62, A-81
Cash Flow Hedges	A-29, A-30
Accumulated Net Gains (Losses) on	13, RI-A-4, RC-14, RC-R-3
Benchmark Interest Rate	A-30
Credit Derivatives	RC-L-5
Credit Losses	RI-31
Current Credit Exposure Across	RC-R-30
Definition	A-26
Derivatives Implementation Group	A-25
Embedded	RC-R-14, A-27

Derivatives (cont.)	
Fair Value Hedges	A-29, A-30
Fair Values	RC-L-17, A-29
Foreign Currency Hedges	A-30
Held for Purposes Other Than Trading	RI-15, RI-21, RI-31, RC-L-16, RC-L-17, A-31
Held for Trading	RI-10, RI-29, RC-L-16, RC-L-17, A-31
Revaluation Gains (Losses)	RC-6, RC-D-2, RC-D-3
Impact on Income of	RI-31
Remaining Maturity of	RC-R-31
Differences in Detail of Reports	2
Direct Credit Substitutes	RC-R-2
Director Attestation	6
Directors, Extensions of Credit to	RC-M-1
Directors' Fees	RI-19, RI-E-1, A-76
Discounts	RC-B-1, RC-O-4, A-65
Disposals of Business Segments	RI-24
Dividend Income on Securities	RI-6, RI-7
Dividends	RC-E-6, A-32
Cash Dividends	RI-A-4, RC-12, RC-G-2, A-32
Declared But Not Yet Payable	RC-G-2
Property Dividends	11, RI-A-5, A-32
Stock Dividends	RI-A-3, RC-12, A-32
Dollar Repurchase Agreements	A-66
Domestic Office	A-32
Domicile	A-32
Due Bills	A-33, A-54

Edge Corporation	A-8, A-16, A-33, A-40
EITF Issue No. 90-5	A-13
Electronic Filing	6
Employee Benefits	RI-16, RC-T-6, A-76

Employee Benefit Trust and Agency Accounts	RC-T-3, RC-T-4, RC-T-6
Employee Stock Ownership Plan (ESOP)	RI-16, RI-A-2, RC-15, RC-C-17, RC-M-9
Equity Capital	RI-A-1, RI-A-5, RC-15, RC-R-2
Changes in	RI-A-1
Equity Contract Notes	RC-R-9, A-59
Equity Derivative Contracts	RI-30, RC-L-9, RC-N-10, RC-R-27, RC-R-30, RC-R-32
Equity Method of Accounting	RC-M-7, A-33
Escrow Funds	RC-E-3, A-17
Examination Fees	RI-20, RC-T-7
Executive Officers, Extensions of Credit to	RC-M-1
Explanations	RI-E-1
Extended Settlements	A-73
Extensions of Credit to Executive Officers, Directors, Principal Shareholders, and Their Related Interests	RC-M-1
Extinguishments of Liabilities	RI-24, A-33
Extraordinary Items	RI-24, RI-D-1, RI-E-1, A-34

Fails	A-34
Fair Value	RC-L-17, A-11, A-29, A-39, A-80, A-81
Fair Value Hedges	A-29, A-30
Farm Management Accounts	RC-T-9
FASB	
Derivatives Implementation Group	A-25
Interpretation No. 14	A-81
Interpretation No. 39	RC-D-2, RC-D-3, A-31, A-62
Interpretation No. 41	RI-6, RI-8, RC-5, RC-10, A-63
Statement No. 4	RI-24
Statement No. 5	A-57, A-58, A-81
Statement No. 13	A-51

FASB (cont.) RI-24, A-36, A-83 Statement No. 15 RI-24, A-36, A-83 Statement No. 28 A-52 Statement No. 34 A-14 Statement No. 52 RC-14, A-29, A-38 Statement No. 65 RC-M-4, RC-M-5, A-36 Statement No. 72 A-13 Statement No. 72 A-13 Statement No. 91 A-55, A-65 Statement No. 91 A-55, A-65 Statement No. 109 A-42 Statement No. 109 A-42 Statement No. 114 A-57, A-83 Statement No. 115 RC-13, RC-B-1, RC-F-2, A-72 Statement No. 121 A-36, A-49 Statement No. 123 RC-14, RC-L-8, RC-L-14, RC-L-17, RC-T-12, A-25 Statement No. 140 RC-F-1, RC-M-9, RC-T-2, A-25 Statement No. 140 RC-F-1, RC-M-9, RC-T-2, A-25 Technical Bulletin No. 85-4 RC-F-3 Federal Funds Purchased RI-8, RC-9, RC-H-1, RC-K-4, A-34 Federal Funds Sold RI-6, RC-5, RC-H-1, RC-K-2, A-34 Federal Home Loan Bank A-35 Advances RC-M-8 Balances Due From Federal Reserve Banks RC-		T
Statement No. 28	FASB (cont.)	
Statement No. 34 A-14 Statement No. 52 RC-14, A-29, A-38 Statement No. 65 RC-C-1, A-74 Statement No. 66 RC-M-4, RC-M-5, A-36 Statement No. 72 A-13 Statement No. 94 RI-22, RC-F-4, A-49 Statement No. 94 9 Statement No. 109 A-42 Statement No. 114 A-57, A-83 Statement No. 115 RC-13, RC-B-1, RC-F-2, A-72, A-79 Statement No. 121 A-36, A-49 Statement No. 123 RC-14, RC-L-8, RC-L-14, RC-L-17, RC-R-14, RC-L-17, RC-R-14, RC-L-17, RC-R-14, RC-L-17, RC-R-14, RC-T-2, A-25 Statement No. 140 RC-F-1, RC-M-9, RC-T-2, A-28, A-33, A-66, A-73, A-74, A-79, A-78 Technical Bulletin No. 85-4 RC-F-1, RC-M-9, RC-T-2, A-28, A-33, A-66, A-73, A-74, A-79, A-78 Federal Funds Purchased RI-8, RC-9, RC-H-1, RC-K-4, A-34 Federal Funds Purchased RI-8, RC-9, RC-H-1, RC-K-2, A-34 Federal Funds Purchased RI-8, RC-9, RC-H-1, RC-K-2, A-34 Federal Home Loan Bank A-35 Advances RC-M-8 Balances Due From RC-3, RC-4, RC-A-4 Federal Home Loan Bank RC-F-2, RC-R-20	Statement No. 15	RI-24, A-36, A-83
Statement No. 52 RC-14, A-29, A-38 Statement No. 65 RC-C-1, A-74 Statement No. 66 RC-M-4, RC-M-5, A-36 Statement No. 72 A-13 Statement No. 94 RI-22, RC-F-4, A-49 Statement No. 91 A-55, A-65 Statement No. 109 A-42 Statement No. 114 A-57, A-83 Statement No. 115 RC-13, RC-B-1, RC-F-2, A-72, A-79 Statement No. 121 A-36, A-49 Statement No. 125 A-79 Statement No. 133 RC-14, RC-L-8, RC-L-14, RC-T-2, A-25 Statement No. 140 RC-F-1, RC-M-9, RC-T-2, A-28, A-33, A-66, A-73, A-74, A-79, A-78 Technical Bulletin No. 85-4 RC-F-3 Federal Funds Purchased RI-8, RC-9, RC-H-1, RC-K-4, A-34 Federal Funds Sold RI-8, RC-9, RC-H-1, RC-K-2, A-34 Federal Home Loan Bank A-35 Advances RC-M-8 Balances Due From RC-3, RC-4, RC-A-4 Federal Home Loan Bank Stock RC-F-2, RC-R-20 Standby Letters of Credit RC-1-7 Federal Reserve Banks RC-3, RC-A-6, RC-R-15, A-64 Borrowings from Fede	Statement No. 28	A-52
Statement No. 65 RC-C-1, A-74 Statement No. 66 RC-M-4, RC-M-5, A-36 Statement No. 72 A-13 Statement No. 94 RI-22, RC-F-4, A-49 Statement No. 94 9 Statement No. 109 A-42 Statement No. 114 A-57, A-83 Statement No. 115 RC-13, RC-B-1, RC-F-2, A-79 Statement No. 121 A-36, A-49 Statement No. 125 A-79 Statement No. 133 RC-14, RC-L-8, RC-L-14, RC-L-17, RC-R-14, RC-L-7, RC-R-14, RC-T-2, A-25 Statement No. 140 RC-F-1, RC-M-9, RC-T-2, A-28, A-33, A-66, A-73, A-74, A-79, A-78 Technical Bulletin No. 85-4 RC-F-1, RC-M-9, RC-T-2, A-28, A-33, A-66, A-73, A-74, A-79, A-78 Federal Funds Purchased RI-8, RC-9, RC-H-1, RC-K-2, A-34 Federal Funds Sold RI-8, RC-9, RC-H-1, RC-K-2, A-34 Federal Funds Durchased RI-8, RC-9, RC-H-1, RC-K-2, A-34 Federal Home Loan Bank A-35 Advances RC-M-8 Balances Due From RC-3, RC-4, RC-A-4 Federal Reserve RC-S, RC-A-6, RC-R-15, A-64 Borrowings from Federal Reserve Banks RC-F-2, RC-R-20 Red	Statement No. 34	A-14
Statement No. 66 RC-M-4, RC-M-5, A-36 Statement No. 72 A-13 Statement No-35. 86 RI-22, RC-F-4, A-49 Statement No. 91 A-55, A-65 Statement No. 109 A-42 Statement No. 114 A-57, A-83 Statement No. 115 RC-13, RC-B-1, RC-F-2, A-72, A-79 Statement No. 121 A-36, A-49 Statement No. 125 A-79 Statement No. 133 RC-14, RC-L-8, RC-L-14, RC-L-17, RC-R-14, RC-T-2, A-25 Statement No. 140 RC-F-1, RC-M-9, RC-T-2, A-28, A-33, A-66, A-73, A-74, A-79, A-78 Technical Bulletin No. 85-4 RC-F-1, RC-M-9, RC-H-1, RC-K-4, A-34 Federal Funds Purchased RI-8, RC-9, RC-H-1, RC-K-4, A-34 Federal Funds Sold RI-8, RC-9, RC-H-1, RC-K-2, A-34 Federal Funds Durchased RI-8, RC-9, RC-H-1, RC-K-2, A-34 Federal Funds Durchased RC-8, RC-9, RC-H-1, RC-K-2, A-34 Federal Funds Durchased RC-8, RC-9, RC-H-1, RC-K-2, A-34 Federal Home Loan Bank A-35 Advances RC-M-8 Balances Due From RC-3, RC-4, RC-A-4 Federal Reserve RC-8, RC-R-15, RC-R-15, RC-R-15, RC-R-15, RC-R-15, RC-R-15, RC-R	Statement No. 52	RC-14, A-29, A-38
Statement No. 72 A-13 Statement No-35. 86 RI-22, RC-F-4, A-49 Statement No. 91 A-55, A-65 Statement No. 109 A-42 Statement No. 114 A-57, A-83 Statement No. 115 RC-13, RC-B-1, RC-F-2, A-72, A-79 Statement No. 121 A-36, A-49 Statement No. 133 RC-14, RC-L-8, RC-L-14, RC-L-17, RC-R-14, RC-T-2, A-25 Statement No. 140 RC-F-1, RC-M-9, RC-T-2, A-28, A-33, A-66, A-73, A-74, A-79, A-78 Technical Bulletin No. 85-4 RC-F-3 Federal Funds Purchased RI-8, RC-9, RC-H-1, RC-K-4, A-34 Federal Funds Sold RI-6, RC-5, RC-H-1, RC-K-2, A-34 Federal Home Loan Bank A-35 Advances RC-M-8 Balances Due From RC-3, RC-4, RC-A-4 Federal Home Loan Bank Stock RC-F-2, RC-R-20 Standby Letters of Credit RC-L-7 Federal Reserve RC-3, RC-A-6, RC-R-15, A-64 Borrowings from Federal Reserve Banks RC-M-9 Federal Reserve Bank RC-F-2, RC-R-20 Regulation D RC-E-3, A-17, A-49	Statement No. 65	RC-C-1, A-74
Statement No. 91 A-55, A-65 Statement No. 94 9 Statement No. 109 A-42 Statement No. 114 A-57, A-83 Statement No. 115 RC-13, RC-B-1, RC-F-2, A-72, A-79 Statement No. 121 A-36, A-49 Statement No. 125 A-79 Statement No. 133 RC-14, RC-L-8, RC-L-14, RC-L-7, RC-R-14, RC-L-17, RC-R-14, RC-L-7, A-25 Statement No. 140 RC-F-1, RC-M-9, RC-T-2, A-28, A-33, A-66, A-73, A-74, A-79, A-78 Technical Bulletin No. 85-4 RC-F-3 Federal Funds Purchased RI-8, RC-9, RC-H-1, RC-K-4, A-34 Federal Funds Sold RI-6, RC-5, RC-H-1, RC-K-2, A-34 Federal Home Loan Bank A-35 Advances RC-M-8 Balances Due From RC-3, RC-4, RC-A-4 Federal Home Loan Bank Stock RC-F-2, RC-R-20 Standby Letters of Credit RC-F-2, RC-R-15, A-64 Borrowings from Federal Reserve Banks RC-3, RC-A-6, RC-R-15, A-64 Borrowings from Federal Reserve Banks RC-F-2, RC-R-20 Rederal Reserve Banks RC-F-2, RC-R-20 Regulation D RC-E-3, A-17, A-49	Statement No. 66	RC-M-4, RC-M-5, A-36
Statement No. 91 A-55, A-65 Statement No. 109 A-42 Statement No. 114 A-57, A-83 Statement No. 115 RC-13, RC-B-1, RC-F-2, A-72, A-79 Statement No. 121 A-36, A-49 Statement No. 125 A-79 Statement No. 133 RC-14, RC-L-8, RC-L-14, RC-L-17, RC-R-14, RC-T-2, A-25 Statement No. 140 RC-F-1, RC-M-9, RC-T-2, A-28, A-33, A-66, A-73, A-74, A-79, A-78 Technical Bulletin No. 85-4 RC-F-3, RC-H-1, RC-K-4, A-34 Federal Funds Purchased RI-8, RC-9, RC-H-1, RC-K-2, A-34 Federal Funds Sold RI-6, RC-5, RC-H-1, RC-K-2, A-34 Federal Home Loan Bank A-35 Advances RC-M-8 Balances Due From RC-3, RC-4, RC-A-4 Federal Home Loan Bank Stock RC-F-2, RC-R-20 Standby Letters of Credit RC-F-2, RC-R-15, A-64 Borrowings from Federal Reserve Banks RC-3, RC-A-6, RC-R-15, A-64 Borrowings from Federal Reserve Banks RC-F-2, RC-R-20 Regulation D RC-E-3, A-17, A-49	Statement No. 72	A-13
Statement No. 109 A-42 Statement No. 114 A-57, A-83 Statement No. 115 RC-13, RC-B-1, RC-F-2, A-72, A-79 Statement No. 121 A-36, A-49 Statement No. 125 A-79 Statement No. 133 RC-14, RC-L-8, RC-L-14, RC-L-17, RC-R-14, RC-L-17, RC-R-14, RC-T-2, A-25 Statement No. 140 RC-F-1, RC-M-9, RC-T-2, A-28, A-33, A-66, A-73, A-74, A-79, A-78 Technical Bulletin No. 85-4 RC-F-3 Federal Funds Purchased RI-8, RC-9, RC-H-1, RC-K-4, A-34 Federal Funds Sold RI-6, RC-5, RC-H-1, RC-K-2, A-34 Federal Home Loan Bank A-35 Advances RC-M-8 Balances Due From RC-3, RC-4, RC-A-4 Federal Home Loan Bank Stock RC-F-2, RC-R-20 Standby Letters of Credit RC-F-2, RC-R-15, A-64 Borrowings from Federal Reserve Banks RC-3, RC-A-6, RC-R-15, A-64 Borrowings from Federal Reserve Banks RC-F-2, RC-R-20 Regulation D RC-E-3, A-17, A-49	Statement No-35. 86	RI-22, RC-F-4, A-49
Statement No. 109	Statement No. 91	A-55, A-65
Statement No. 114 A-57, A-83 Statement No. 115 RC-13, RC-B-1, RC-F-2, A-72, A-79 Statement No. 121 A-36, A-49 Statement No. 125 A-79 Statement No. 133 RC-14, RC-L-8, RC-L-14, RC-R-14, RC-R-17, RC-R-14, RC-R-72, A-25 Statement No. 140 RC-F-1, RC-M-9, RC-T-2, A-28, A-33, A-66, A-73, A-74, A-79, A-78 Technical Bulletin No. 85-4 RC-F-3 Federal Funds Purchased RI-8, RC-9, RC-H-1, RC-K-2, A-34 Federal Funds Sold RI-6, RC-5, RC-H-1, RC-K-2, A-34 Federal Home Loan Bank A-35 Advances RC-M-8 Balances Due From RC-3, RC-4, RC-A-4 Federal Home Loan Bank Stock RC-F-2, RC-R-20 Standby Letters of Credit RC-F-2, RC-R-20 Balances Due From Federal Reserve RC-3, RC-A-6, RC-R-15, A-64 Borrowings from Federal Reserve Banks RC-M-9 Federal Reserve Bank Stock RC-F-2, RC-R-20 Regulation D RC-E-3, A-17, A-49	Statement No. 94	9
Statement No. 115 RC-13, RC-B-1, RC-F-2, A-72, A-79	Statement No. 109	A-42
A-72, A-79	Statement No. 114	A-57, A-83
Statement No. 125	Statement No. 115	
Statement No. 133	Statement No. 121	A-36, A-49
RC-L-17, RC-R-14, RC-T-2, A-25	Statement No. 125	A-79
A-28, A-33, A-66, A-73, A-74, A-79, A-78 Technical Bulletin	Statement No. 133	RC-L-17, RC-R-14,
Federal Funds Purchased RI-8, RC-9, RC-H-1, RC-K-4, A-34 Federal Funds Sold RI-6, RC-5, RC-H-1, RC-K-2, A-34 Federal Home Loan Bank A-35 Advances RC-M-8 Balances Due From RC-3, RC-4, RC-A-4 Federal Home Loan Bank Stock Standby Letters of Credit RC-F-2, RC-R-20 Balances Due From Federal Reserve Balances Due From Federal Reserve Banks RC-3, RC-A-6, RC-R-15, A-64 Borrowings from Federal Reserve Banks Federal Reserve Bank RC-F-2, RC-R-20 RC-M-9 RC-F-2, RC-R-20	Statement No. 140	A-28, A-33, A-66, A-73,
Federal Funds Sold RI-6, RC-5, RC-H-1, RC-K-2, A-34 Federal Home Loan Bank A-35 Advances RC-M-8 Balances Due From RC-3, RC-4, RC-A-4 Federal Home Loan Bank Stock Standby Letters of Credit RC-L-7 Federal Reserve Balances Due From RC-3, RC-A-6, RC-R-15, Federal Reserve Banks Borrowings from Federal Reserve Banks Federal Reserve Bank RC-F-2, RC-R-20 RC-M-9 RC-F-2, RC-R-20 RC-F-2, RC-R-20 RC-F-2, RC-R-20 RC-F-2, RC-R-20 RC-F-3, A-17, A-49		RC-F-3
RC-K-2, A-34 Federal Home Loan Bank A-35 Advances RC-M-8 Balances Due From RC-3, RC-4, RC-A-4 Federal Home Loan Bank Stock Standby Letters of Credit RC-L-7 Federal Reserve Balances Due From Federal Reserve Banks RC-3, RC-A-6, RC-R-15, Federal Reserve Banks RC-M-9 RC-M-9 RC-F-2, RC-R-20 RC-M-9 RC-F-2, RC-R-20 RC-F-2, RC-R-20 RC-F-2, RC-R-20 RC-F-2, RC-R-20 RC-F-2, RC-R-20	Federal Funds Purchased	
Advances RC-M-8 Balances Due From RC-3, RC-4, RC-A-4 Federal Home Loan Bank Stock Standby Letters of Credit RC-L-7 Federal Reserve Balances Due From Federal Reserve Banks Borrowings from Federal Reserve Banks Federal Reserve Bank RC-M-9 RC-F-2, RC-R-20 RC-F-2, RC-R-20 RC-F-2, RC-R-20 Regulation D RC-E-3, A-17, A-49	Federal Funds Sold	
Balances Due From RC-3, RC-4, RC-A-4 Federal Home Loan Bank Stock Standby Letters of Credit RC-L-7 Federal Reserve Balances Due From Federal Reserve Banks Borrowings from Federal Reserve Banks Federal Reserve Banks Federal Reserve Bank RC-M-9 RC-F-2, RC-R-20 RC-F-2, RC-R-20 RC-F-3, A-17, A-49	Federal Home Loan Bank	A-35
Federal Home Loan Bank Stock Standby Letters of Credit RC-L-7 Federal Reserve Balances Due From Federal Reserve Banks Borrowings from Federal Reserve Banks Federal Reserve Bank Federal Reserve Bank RC-M-9 RC-F-2, RC-R-20 RC-F-2, RC-R-20 RC-E-3, A-17, A-49	Advances	RC-M-8
Stock Standby Letters of Credit RC-L-7 Federal Reserve Balances Due From Federal Reserve Banks Borrowings from Federal Reserve Banks Federal Reserve Bank Federal Reserve Bank RC-H-9 RC-F-2, RC-R-20 Regulation D RC-E-3, A-17, A-49	Balances Due From	RC-3, RC-4, RC-A-4
Federal Reserve Balances Due From Federal Reserve Banks Borrowings from Federal Reserve Banks Federal Reserve Bank Federal Reserve Bank RC-F-2, RC-R-20 Regulation D RC-E-3, A-17, A-49		RC-F-2, RC-R-20
Balances Due From Federal Reserve Banks Borrowings from Federal Reserve Banks Federal Reserve Bank Federal Reserve Bank RC-F-2, RC-R-20 Regulation D RC-E-3, A-17, A-49	Standby Letters of Credit	RC-L-7
Federal Reserve Banks Borrowings from Federal Reserve Banks Federal Reserve Bank RC-F-2, RC-R-20 Stock Regulation D RC-E-3, A-17, A-49	Federal Reserve	
Reserve Banks Federal Reserve Bank Stock Regulation D RC-F-2, RC-R-20 RC-E-3, A-17, A-49		
Stock Regulation D RC-E-3, A-17, A-49	J J	RC-M-9
		RC-F-2, RC-R-20
Regulation H RC-M-4, RC-M-8, A-3	Regulation D	RC-E-3, A-17, A-49
d I	Regulation H	RC-M-4, RC-M-8, A-3

	1
Regulation K	A-33
Regulation O	RC-M-1
Regulation Q	A-49
Regulation U	RC-C-17, RC-C-18
Federally-Sponsored Lending Agency	RC-C-19, A-35
Fee Income	RI-2, RI-11, RI-12, RI-13, RI-26, RI-28, A-55
Insurance	RI-12
Investment Banking, Advisory, Brokerage, and Underwriting	RI-11
Net Servicing Fees	RI-11
Fiduciary and Related Services	11, RI-9, RC-T-1
Fiduciary Settlements, Surcharges, and Other Losses	11, RC-T-7, RC-T-11
Financial Assets	A-79, A-80
Sold With Recourse	RC-R-1, RC-R-2, RC-R-14, RC-R-22, RC-R-25, RC-S-2, RC-S-5, A-68
Financial Guarantee Insurance	RC-L-7
Financial Subsidiaries	RC-R-10
Fixed Assets	12, RI-12, RI-18, RC-7, RC-R-20
Floors	RC-L-14, RC-L-15, A-27
Food Stamps	RI-13, RC-2, RC-A-2
Foreclosed Assets	RI-12, RC-M-5, A-35
Foreign Branch Report of Condition	14
Foreign Currency Hedges	A-30
Foreign Currency Transactions	RI-14, RI-21, A-38
Foreign Currency Translation Adjustments	RI-A-4, RI-B-7, RC-14, A-38, A-47
Foreign Debt Exchange Transactions	A-39
Foreign Exchange Contracts	RI-30, RC-L-9, RC-N-10, RC-R-27, RC-R-30, RC-R-31
Spot Contracts	RC-L-6
Foreign Governments and Official Institutions	RC-C-15, RC-E-9, RC-E-18, A-40
Foreign Office	4, A-40

Foreign Office Guarantees	RC-L-3, RC-L-4
Foreign Official Institutions	A-40
Forward Agreement	RC-R-2
Forward Contracts	RC-B-2, RC-L-11, RC-R-31, A-26, A-62
Forward Rate Agreement	A-27
Frequency of Reporting	2
Full Accrual Method	RC-M-4, RC-M-5, A-36
Full-Time Equivalent Employees	RI-28
Functional Currency	A-38
Futures Contracts	RC-B-2, RC-L-10, RC-R-30, A-26, A-30

Gain Contingencies	A-58
Gains Trading	A-72
General Instructions	1
General Obligations	RC-B-4, RC-R-15, RC-R-16
Generally Accepted Accounting Principles	11
Gold Contracts	RC-R-27, RC-R-31
Goodwill	RI-19, RC-8, RC-R-3, RC-R-9, RC-R-12, RC-R-20, A-12
Ground Rents	RI-15, RC-F-4, RC-T-9
Guaranteed Investment Contracts	RC-T-8

Hedge Accounting	A-30
Home Equity Lines	RC-B-7, RC-L-1, RC-R-26, RC-S-1
Host Contract	A-27
Hybrid Instrument	A-28

Immediately Available Funds	RC-5, RC-9, A-34
Impairment	11, A-57, A-72, A-75
Income	
Fee Income	RI-2, RI-11, RI-12, RI-13, RI-26, RI-28, A-55

from Fiduciary Activities	9, 11, RI-9, RI-16, RC-T-1, RC-T-5
from Lease Financing Receivables	RI-5
from International Operations	RI-D-1
from the Sale and Servicing of Mutual Funds and Annuities	RI-11, RI-26
Income Earned, Not Collected	RC-F-1
Rental Income	RI-14, RI-15, RI-18, A-53
Servicing Income	RI-11, A-75
Tax-Exempt Income	RI-27, RI-28
Trust Income	RI-9, RC-T-1, RC-T-5
Income Statement	RI-1
Income Taxes	11, 12, A-41
Alternative Minimum Tax	A-46, A-47
Applicable Income Taxes	RI-23, RI-24, RI-D-2, RI-E-1, A-45
Applicable Tax Rate	A-43
Carrybacks and Carryforwards	RI-23, A-42
Current	RI-23, A-41
Deferred Income Taxes	RI-23, A-41
Deferred Tax Assets	RC-F-1, RC-R-5, RC-R-10, RC-R-12, RC-R-20, A-42, A-63
Deferred Tax Liabilities	RC-G-1, RC-R-3, A-42, A-63
Interim Period	A-45
Intraperiod Allocation	A-45
Separate Entity Method	11, A-45
Tax-Planning Strategy	A-44
Tax Rates	A-48
Indirect Expenses	RC-T-7
Individual Retirement Accounts (IRAs)	RI-10, RC-E-10, RC-T-4
Individuals, Partnerships, and Corporations, Deposits of	RC-E-5, RC-E-18
Industrial Development Obligations	RC-B-1, RC-B-4, RC-C-16
Installment Method	RC-M-4, RC-M-5, A-37
Insurance Commissions and Fees	RI-12

	T
Insurance Expense	RI-17, RI-18, RI-20, RC-T-6
Intangible Assets	RI-19, RC-8, RC-L-8, RC-M-2, RC-R-3, RC-R-9, A-11
Amortization of	RI-19, A-12
Disallowed	RC-R-3, RC-R-4, RC-R-20
Identifiable	RC-M-3, A-11
Interchange Fees	RI-14
Interest Accrued and Unpaid on Deposits	RC-G-1, RC-O-3
Interest-Bearing Due From Balances	RI-5, RC-4, RC-K-2
Interest Capitalization	A-13
Interest Expense	RI-7, RI-D-1
Incurred to Carry Tax-Exempt Assets	RI-26
on Trading Liabilities and Other Borrowed Money	RI-8, A-51
on Deposits	RI-7
on Federal Funds Purchased and Securities Sold Under Agreements to Repurchase	RI-8
on Subordinated Notes and Debentures	RI-8
Interest Income	RI-2, RI-D-1
from Trading Assets	RI-6
on Balances Due From Depository Institutions	RI-5
on Federal Funds Sold and Securities Purchased Under Agreements to Resell	RI-6
on Loans	RI-2
on Securities	RI-5
Other	RI-7
Interest-Only Strips Receivable	RI-7, RC-F-1, RC-R-23, RC-S-2, RC-S-3, A-28, A-71, A-82
Interest Rate	
Caps	RC-L-14, RC-L-15, A-27
Collars	RC-L-14, RC-L-15, A-27
Contracts	RI-30, RC-L-9, RC-N-10, RC-R-27, RC-R-30, RC-R-31

Floors	RC-L-14, RC-L-15, A-27
Swaps	RC-L-15, RC-L-16, A-27, A-62
Internal-Use Computer Software	A-48
International Banking Facility (IBF)	RC-I-1, A-8, A-16, A-18, A-32, A-49
International Operations	RI-D-1
Internet Web Address	5
Interoffice Accounts	A-77
Intrabank Transactions	10
Intracompany Income Credits	RC-T-7
Investment Banking, Advisory,	RI-11
Investment Management Agency Accounts	RC-T-4, RC-T-6, RC-T-11
Investments in	
Mutual Funds	RC-B-9, RC-H-3, RC-R-17
Real Estate Ventures	RC-M-4, RC-M-7
Unconsolidated Subsidiaries and Associated Companies	8, 12, RI-12, RI-15, RC-8, RC-M-7, RC-R-20, A-76
Issue Costs	RI-8, RC-F-4

Joint Venture	RI-11, RI-12, RI-15, RC-M-7, A-33, A-77
	,

Keogh Plan Accounts	RI-10, RC-E-10, RC-T-4
---------------------	------------------------

Leases	
Capital Lease	A-51
Charge-Offs and Recoveries	RI-B-3, RI-B-4
Direct Financing Lease	RC-C-20, A-52
Favorable Leasehold Rights	RC-M-3
Held for Sale	RI-12, RC-6, RC-C-1
Income from	RI-5, RI-15, RI-27
Lease Accounting	A-51

Leases (cont.)	
Lease Financing Receivables	RI-7, RI-12, RI-27, RC-6, RC-C-1, RC-C-20, RC-K-3
Leveraged Lease	RC-C-20, A-52, A-63
Maturity and Repricing Data	RC-C-22
Net Gains (Losses) on Sales of	RI-12
Obligations Under Capitalized Leases	RC-M-9
Operating Lease	RI-15, RI-18, RC-F-4, A-52, A-53
Past Due and Nonaccrual	RC-N-7
Restructured	RC-C-21, RC-N-3, RC-N-9
Sale-Leaseback Transactions	RC-G-2, A-52
Leasehold Improvements	RC-7, RI-18
Legal Fees	RI-20, RI-E-1
Letters of Credit	RI-13, A-53
Commercial	RI-13, RC-L-5, RC-R-2, A-53
Deferred Payment	RI-13, RC-F-4, RC-G-2
Sold for Cash	RI-13, RC-E-7, A-53
Standby	RI-13, RC-L-3, RC-S-3, RC-S-5, RC-S-7, A-53, A-70
Financial Standby	RC-L-4, RC-R-2, RC-R-21
Performance Standby	RC-L-4, RC-R-2, RC-R-21
Traveler's	RC-E-7, A-54
Letters of Indemnity	RC-L-7
Leverage Capital Ratio	RC-R-11
Life Insurance	RI-12, RI-14, RI-E-1, RC-F-3, A-26
Liquidity Facility	RC-S-2, RC-S-3, RC-S-5, RC-S-7
Loans	RI-2, RI-12, RI-27, RI-28, RC-6, RC-C-1, RC-K-2, RC-K-4, RC-R-17, RC-R-18, A-54, A-68
1-4 Family Residential Real Estate Loans	RI-B-1, RC-C-4, RC-C-24, RC-L-3, RC-N-2, RC-N-5, RC-R-18, RC-S-1, A-60
Adjustable Rate Closed-End First Lien Loans	RC-C-28
Serviced for Others	RC-S-6, RC-S-7

I	I I
Agricultural	RC-C-9, RC-C-35
All Other	RI-4, RI-B-3, RC-C-18, RC-C-19, RC-N-7, RC-S-1, A-63
Automobile	RC-B-8, RC-C-14, RC-S-1
Charge-Offs	RI-B-1, RI-B-7, RC-S-4
Collateral Dependent	11, A-57, A-58
Commercial and Industrial	RI-3, RI-B-2, RI-B-4, RC-B-8, RC-C-10, RC-K-2, RC-N-6, RC-N-9, RC-S-1, A-7
Commercial Real Estate	RI-B-4, RC-C-5, RC-C-28, RC-L-2, RC-N-5, RC-N-9
Construction, Land Development, and Other Land Loans	RI-B-1, RC-C-3, RC-L-2, RC-N-5
Consumer	RC-B-8, RC-C-12, RC-N-2, RC-S-1, A-60
Credit Cards	RI-4, RI-B-3, RC-C-12, RC-K-2, RC-L-2, RC-N-7, RC-S-1
Farm	RC-C-9
Farmland	RI-B-1, RC-C-4, RC-N-5
Fees	RC-C-1, RC-G-2, RI-2, A-55
for Purchasing or Carrying Securities	RC-C-17, RC-C-19
Government Guaranteed	RC-N-8, RC-R-17, RC-R-18
Held for Sale	RI-12, RC-6, RC-C-1
Home Equity	RI-B-1, RC-C-4, RC-L-1, RC-N-5, RC-S-1
Impairment	11, A-57
in Foreign Offices	RI-4, RI-B-2, RC-K-3, RC-N-6
Insider	RC-M-1
Interest and Fee Income	RI-2
Land Loans	RI-B-1, RC-C-3, RC-N-5
Loan Losses	RI-B-1, RI-B-7
Maturity and Repricing Data	RC-C-22
Multifamily Real Estate	RI-B-2, RC-C-5, RC-L-2, RC-N-5, RC-R-18
Net Gains (Losses) on Sales	RI-12
Nonaccrual	11, 12, RC-N-2, A-58, A-59

1	T
Loans (cont.)	
Nonfarm Nonresidential Real Estate	RI-B-2, RC-C-5, RC-L-2, RC-N-5
Origination Fees and Costs	RC-C-1, A-55
Other	RI-4, RC-C-17
Overdraft Checking	RC-C-13
Participations	A-55, A-81
Past Due	RC-N-1, RC-S-3, RC-S-4, A-58
Real Estate	RI-3, RI-B-4, RC-C-2, RC-C-29, RC-K-2, RC-L-2, RC-N-5, RC-N-9, RC-T-9, A-58
Recoveries	RI-B-1, RI-B-7, RC-S-4
Residential Real Estate	RI-B-1, RC-C-4, RC-C-24, RC-N-5, RC-R-18, RC-S-1
Restructured	RC-C-21, RC-N-3, RC-N-9, A-56, A-61, A-83
Revolving Credit Plans	RC-C-13
SBA Loans	RC-C-9, RC-C-10, RC-N-8, RC-R-17, RC-R-18
Secured by Real Estate	RI-3, RI-B-4, RC-C-2, RC-C-29, RC-K-2, RC-L-2, RC-N-5, RC-N-9, A-58
Serviced for Others	RC-S-2, RC-S-6, RC-S-7
Small Business	RC-C-30, RC-C-31
Small Farm	RC-C-30, RC-C-35
States and Political Subdivisions in the U.S.	RI-4, RI-B-3, RC-C-16, RC-N-7, A-63
Student	RC-C-14, RC-R-18
Swaps	A-39
Tax-Exempt	RI-27
to Depository Institutions and Acceptances of Other Banks	RI-4, RI-B-2, RI-B-4, RC-C-5, RC-N-6, RC-N-9, RC-R-18, A-7, A-63
to Finance Commercial Real Estate, Construction, and Land Development	RI-B-4, RC-C-28, RC-L-2, RC-N-9
to Finance Agricultural Production and Other Loans to Farmers	RI-3, RI-4, RI-28, RI-B-2, RI-B-5, RC-C-9, RC-K-2, RC-K-5, RC-N-6, RC-N-10
to Foreign Governments and Official Institutions	RI-4, RI-B-3, RC-C-15, RC-N-7, A-7, A-63

to Individuals for Household, Family, and Other Personal Expenditures	RI-3, RI-B-3, RC-C-12, RC-K-2, RC-N-7
to Nonprofit Organizations	RC-C-18
Unearned Income on	RC-C-1, RC-C-20
Loss Contingencies	A-58
Losses from Fiduciary and Related Services	RC-T-7, RC-T-11

Managed Assets	RC-T-3, RC-T-7
Mandatory Convertible Debt	RC-10, RC-R-9, A-59
Market Risk Equivalent Assets	RC-R-14, RC-R-28
Master Netting Arrangement	A-62
Marketing Expenses	RI-20, RI-E-1, RC-T-7
Materiality	7
Maturity and Repricing Data	
for Debt Securities	RC-B-11
for Loans and Leases	RC-C-22
for Time Deposits	RC-E-13, RC-E-15, RC-E-18
Mergers	A-11
Minority Interests in Consolidated Subsidiaries	10, RC-11, RC-R-3
Money Market Deposit Accounts (MMDAs)	RC-E-4, RC-E-5, RC-E-12, RC-T-8, A-23, A-25
Money Market Mutual Funds	RC-B-9, RC-T-8
Money Orders	RI-13, RC-E-3, RC-E-6, A-18
Mortgage Indebtedness	RC-M-9
Mortgage Servicing Assets	RI-11, RC-M-2, RC-R-4, RC-R-10, RC-R-12, RC-R-20, A-74
Mutual Funds	RC-B-9, RC-T-8, RC-T-9
Assets Under Management	RC-M-11
Sales	RI-11, RI-12, RI-26, RC-M-10

Negative Entries	12
Negative Goodwill	RC-G-2, A-12
Net Due From (To) Own Foreign Offices	RC-H-1
Net Gains (Losses) From Sales 0f Assets	RI-12
Net Income (Loss)	RI-25, RI-A-2
Net Income Attributable to International Operations	RI-D-2
Net Interest Income	RI-9, RI-D-1
Net Losses from Fiduciary and	RC-T-7, RC-T-11
Net Securitization Income	RI-12
Net Servicing Fees	RI-11
Net Unrealized Gain on Available-for-Sale Equity Securities	RC-R-9, RC-R-16, RC-R-17
Net Unrealized Holding Gains (Losses) on Available-for- Sale Securities	13, RC-13, RC-R-2
Change in	RI-A-4
Net Unrealized Loss on Available-for-Sale Equity Securities	RC-R-2, RC-R-16, RC-R-17
Netting	RI-6, RI-8, RC-5, RC-10, RC-0-7, RC-R-30, A-62
Nonaccrual Status	11, 12, RC-N-2, A-59
Noninterest Expense	RI-16, RI-23, RI-D-1
Other	RI-19, RI-E-1
Noninterest Income	RI-9, RI-15, RI-D-1
Other	RI-13, RI-E-1
Noninterest-Bearing Due From Balances	RC-1, RC-3
Non-Managed Assets	RC-T-3
Nonmortgage Servicing Assets	RI-11, RC-M-3, RC-R-4, RC-R-10, RC-R-12, RC-R-20, A-74
Nontransaction Accounts	RI-8, RC-E-5, RC-E-11, RC-K-4, A-21
Note Issuance Facilities (NIFs)	RC-L-1, RC-L-3, RC-R-2, RC-R-26
NOW Accounts	RI-7, RC-E-4, RC-K-3, RC-T-8, A-19
Number of Deposit Accounts	RC-O-9
Number of Full-Time Equivalent Employees	RI-28

Obligations Under Capitalized Leases	RC-M-9
Off-Balance Sheet Items	RC-L-1, RC-R-2, RC-R-21
All Other Off-Balance Sheet Assets	RC-L-7
All Other Off-Balance Sheet Liabilities	RC-L-6
Office Supplies	RI-20, RI-E-1
Officer Declaration	5
Official Checks	RC-E-5, RC-E-6, RC-E-18
Offsetting	RI-6, RI-8, RC-5, RC-10, RC-0-7, RC-R-30, A-62
One-Day Transaction	RC-5, RC-9, A-34
Option Contracts	RC-B-2, RC-L-12, RC-L-13, A-27, A-62
Call Option	A-27
Exchange-Traded Option	RC-L-12
Over-the-Counter Option	RC-L-13
Purchased Option	RC-L-13, RC-L-15, A-27
Put Option	A-27, A-70
Written Option	RC-L-12, RC-L-14, RC-R-26, A-27
Optional Narrative Statement	RC-X-1
Organization Costs	A-75
Other Assets	RC-8, RC-F-1
Other Borrowed Money	RI-8, RC-10, RC-H-1, RC-K-4, RC-M-8, A-33, A-36, A-51, A-67
Other Comprehensive Income	RI-A-4, A-29, A-38
Other Data for Deposit Insurance and FICO Assessments	RC-O-1
Other Depository Institutions in the U.S.	RC-C-8, RC-E-8, A-17
Other Expenses Accrued and Unpaid	RC-G-1
Other Fiduciary Accounts	RC-T-4, RC-T-6, RC-T-11
Other Liabilities	RC-11, RC-G-1
Other Real Estate Owned	RI-12, RI-14, RI-20, RC-8, RC-M-3, RC-M-5, RC-R-20, A-35
Other U.S. Depository Institutions	RI-B-2, RC-E-18, RC-N-6
Overdraft	RI-10, RC-C-18, RC-E-2, RC-T-2, A-54, A-63

Pair-Offs	A-72
Partnerships	RI-11, RI-12, RI-15, RC-M-7, A-33
Pass-Through Reserve Balances	RC-4, RC-A-4, RC-A-6, RC-O-4, RC-R-15, A-64
Past Due and Nonaccrual Loans, Leases, and Other Assets	RC-N-1
Payable Through Drafts	RC-E-3, RC-O-1
Paying Agent	RC-T-10
Personal Trust and Agency Accounts	RC-T-3, RC-T-5, RC-T-7, RC-T-11
Placements and Takings	A-65
Pooling of Interests	RI-1, RI-A-2, RI-B-6, RC-K-1, A-11
Postage	RI-20, RI-E-1, A-76
Pre-Opening Income and Expenses	RI-1, RI-A-3, A-76
Precious Metals Contracts	RC-R-27, RC-R-32
Preferred Stock	RI-A-1, RI-A-2, RC-B-9, RC-R-3, RC-R-6a, RC-R- 8, RC-T-9, A-65
Auction Rate	RC-R-8
Intermediate-Term	RC-R-6a, RC-R-7
Limited-Life	RI-A-2, RI-A-4, RC-10, RC-12, RC-R-6a, A-12, A-65
Long-Term	RC-R-6a, RC-R-8
Perpetual	RI-A-1, RI-A-2, RI-A-3, RI-A-4, RC-12, A-65
Cumulative	RC-R-8
Nonqualifying	RC-R-3
Redeemable	RC-R-6a
Premises and Fixed Assets	12, RI-12, RC-7, RC-R-20
Expenses of	RI-18, RC-T-6, A-51
Premiums	12, RC-B-1, RC-O-4, A-65
Prepaid Expenses	RC-F-3
Preparation of the Reports	5
Prepayment Penalties	RI-2
Principal-Only Strips	RC-R-16, RC-R-17, RC-R-19, A-28
Principal Shareholders, Extensions of Credit to	RC-M-1
Property Taxes	RI-18, RC-T-6

Proprietary Mutual Funds and Annuities	RC-M-11
Provision for Allocated Transfer Risk	RI-22
Provision for Credit Losses on Off-Balance Sheet Credit Exposures	RI-22
Provision for Loan and Lease Losses	RI-9, RI-B-7, RI-D-1, A-3, A-57
Publication Requirements	10
Purchase Acquisition	RI-1, RI-A-3, RI-B-6, RC-K-1, A-11
Purchased Credit Card Relationships	RC-M-3, RC-R-4, RC-R-10, RC-R-12, RC-R-20
Push Down Accounting	11, RI-1, RI-29, RI-A-4, RI-B-6, RI-B-7, RC-K-1, A-12

Qualifying Subordinated Debt and Redeemable Preferred Stock	RC-R-6a
Quarterly Averages	RC-K-1

Real Estate	RC-T-9
Real Estate Mortgage Investment Conduits (REMICs)	RC-B-6, RC-B-7, RC-B-16, RC-H-3
Reciprocal Balances	RC-A-1, RC-E-2, RC-O-6, RC-O-7, A-66
Reciprocal Holdings of Capital Instruments	RC-R-9, RC-R-12
Recourse	RC-S-2, A-68
Financial Assets Transferred With Recourse	RC-R-1, RC-R-2, RC-R-14, RC-R-22, RC-R-25, RC-S-2, RC-S-5, A-68
Liability Account	RC-G-2, A-4
Low Level Recourse	RC-R-1, RC-R-22, A-70, A-71
Small Business Obligations Transferred With Recourse	RC-R-22, RC-S-6
Recoveries on Loans and Leases	RI-B-1, RI-B-7, RC-S-4
Reduced-Profit Method	RC-M-4, RC-M-5, A-37
Registrar	RC-T-10

Regular Way Securities Trades	A-26, A-73
	RC-R-1
Regulatory Capital Related Interests, Extensions of	RC-M-1
Credit to Release of Reports	
Remote Service Units	RI-10, RI-13, RC-E-4,
Tromote Gerrico Crinto	RC-E-5, A-18, A-21
Renegotiated Troubled Debt	A-83
Rental Income	RI-14, RI-18, RI-27
Reorganization	A-13
Reporting by Type of Office	10
Repossessed Property	RI-12, RC-F-3, A-35
Repurchase/Resale Agreements	A-35, A-63, A-66, A-68, A-73
Research and Development Costs	RI-21
Reserve for Contingencies	RC-12
Restructured Loans and Leases	RC-C-21, RC-N-3, RC-N-9, A-56, A-61, A-83
Residuals	RC-R-16, RC-R-17, RC-R-19
Restatements	RI-A-1, RI-E-2, A-2
Retained Earnings	12, RI-A-1, RC-12, A-11, A-13
Retained Subordinated Interests	RC-R-23, A-71
Retirement of Capital Stock	RI-A-2
Retirement Plan Contributions	RI-16
Retirement Related Trust and Agency Accounts	RC-T-3, RC-T-4, RC-T-5, RC-T-6, RC-T-11
Revenue Obligations	RC-B-4, RC-R-16, RC-R-17
Revolving Underwriting Facilities (RUFs)	RC-L-1, RC-L-3, RC-R-2, RC-R-26
Right of Setoff	A-62
Risk-Based Capital	RC-R-1, A-68
20 Percent Risk Category	RC-R-13
Covered Positions	RC-R-14, RC-R-28
Credit Conversion Factors	RC-R-2, RC-R-27
Items Not Subject to Risk- Weighting	13, RC-R-12

Market Risk Equivalent Assets	RC-R-28
Ratios	RC-R-12
Risk-Weighted Assets	RC-R-12, RC-R-29
Sales of Assets for Risk-Based Capital Purposes	A-68
Total Risk-Based Capital	13, RC-R-9
Zero Percent Risk Category	RC-R-13
Rounding	12

П	T
Safe Deposit Boxes	RI-13, RI-E-1
Safekeeping Accounts	RC-T-5, RC-T-6, RC-T-11
Salaries and Employee Benefits	RI-16, RC-T-6, A-76
Sale-Leaseback Transactions	RC-G-2, A-52
Sales of Assets for Risk-Based Capital Purposes	A-68
Sales of Capital Stock	RI-A-2
Sales Taxes	RI-21
Savings Bonds	RI-13, RC-2, RC-A-2, RC-E-7
SEC Staff Accounting Bulletin No. 92	9
Securities	RI-6, RC-5, RC-B-1, RC-H-2, RC-H-3, RC-K-1, RC-K-2, RC-N-8, RC-R-5, RC-R-16, A-72
Accrued Interest on Securities Purchased	RC-F-3
Available-for-Sale	13, RI-A-4, RC-5, RC-13, RC-B-1, RC-B-17, RC-H-2, RC-R-5, RC-R-16, A-72
Borrowed	RC-B-2, RC-L-7, RC-T-2, A-73
Collateralized Mortgage Obligations (CMOs)	RC-B-6, RC-B-16, RC-H-3, RC-T-8
Commercial Paper	RC-6, RC-B-8, RC-B-9, A-15
Equity Securities	RC-R-2, RC-R-9
That Do Not Have Readily Determinable Fair Values	RI-7, RC-F-2, RC-H-4

Securities (cont.)	
Equity Securities (cont.)	
With Readily Determinable Fair Values	RI-6, RC-B-9, RC-H-3, RC-K-3, RC-R-15, RC-R-16
Federal Home Loan Mortgage Corporation (FHLMC)	RC-B-3, RC-B-6, RC-B-7, RC-B-9, RC-H-3, RC-R-15, RC-R-16, RC-R-17, RC-R-19, RC-T-8
Federal National Mortgage Association (FNMA)	RC-B-3, RC-B-6, RC-B-7, RC-B-9, RC-H-3, RC-R-15, RC-R-16, RC-R-17, RC-R-19, RC-T-8
Foreign Debt Securities	RC-B-9, RC-H-3, RC-T-8
Government National Mortgage Association (GNMA)	RC-B-3, RC-B-6, RC-B-7, RC-H-3, RC-R-15, RC-R-16, RC-R-17, RC-R-19, RC-T-8
Held-to-Maturity	RC-5, RC-B-1, RC-B-17, RC-H-2, RC-R-15, A-72
Impairment of	RI-16, A-72
Interest and Dividend Income on	RI-5, RI-28
Lent	RC-B-2, RC-L-5, RC-R-2, RC-R-22, RC-T-2, RC-T-7, A-73
Market Value of	A-59
Maturity and Repricing Data for Debt Securities	RC-B-11
Mortgage-Backed Securities	RI-6, RC-B-5, RC-B-6, RC-B-13, RC-B-14, RC-D-1, RC-H-2, RC-H-3, RC-K-1, RC-R-15, RC-R-16, RC-R-17, RC-R-19, A-66
Mutual Funds	RI-6, RC-B-9, RC-H-3, RC-K-3
Net Unrealized Holding Gains (Losses) on Available-for-Sale Securities	13, RI-A-4, RC-13, RC-R-2
Other Debt Securities	RI-6, RC-B-8, RC-B-13, RC-D-2, RC-H-3, RC-K-2, RC-T-8
Participations in Pools of Securities	RC-5, RC-9, RC-B-1, A-35, A-67
Pass-Through Securities	RC-B-6, RC-B-13, RC-B-14, RC-D-1, RC-H-2, RC-T-8
Past Due and Nonaccrual	RC-N-8

I	
Pledged	RC-B-1, RC-B-11
Purchased Under Agreements to Resell	RI-6, RC-5, RC-B-1, RC-H-1, RC-K-2, RC-R-17, RC-T-8, A-35, A-63, A-66, A-68
Real Estate Mortgage Investment Conduits (REMICs)	RC-B-6, RC-B-16, RC-H-3, RC-T-8
Realized Gains (Losses)	RI-16, RI-D-1
Securities Activities	A-72
Sold Under Agreements to Repurchase	RI-8, RC-10, RC-B-1, RC-H-1, RC-K-4, A-35, A-63, A-66, A-68
States and Political Subdivisions in the U.S.	RI-6, RC-6, RC-B-4, RC-B-13, RC-D-1, RC-H-2, RC-K-2, RC-R-15, RC-R-16, RC-R-17, RC-R-19, RC-T-8
Stripped Mortgage- Backed Securities	RC-B-6, RC-B-16, RC-H-3, RC-R-16, RC-R-17, RC-R-19
STRIPS	RC-B-2, A-16
Structured Notes	RC-B-17
Tax-Exempt	RI-26, RI-28
Trading	RC-6, RC-B-17, RC-D-1, A-72
U.S. Government Agency Obligations	RI-6, RC-6, RC-B-3, RC-B-13, RC-D-1, RC-H-2, RC-K-1, RC-R-13, RC-R-15, RC-R-16, RC-R-19, RC-T-8
U.S. Government- Sponsored Agency Obligations	RC-B-3, RC-R-19
U.S. Treasury	RI-6, RC-6, RC-B-2, RC-B-13, RC-D-1, RC-H-2, RC-K-1, RC-R-15, RC-R-16, RC-R-19, RC-T-8
Underwriting	RC-L-3
When-Issued	RC-L-7, RC-L-8, RC-L-11, A-72, A-84
Securitization and Asset Sale Activities	RC-S-1
Securitization Income	RI-12
Selected Balance Sheet Items for Domestic Offices	RC-H-1
Seller-Provided Credit Enhancement	RC-S-2, RC-S-3, RC-S-5, RC-S-7
Seller's Interest	RC-S-2, RC-S-4

Separate Entity Method	11, A-45
Service Charges on Deposit Accounts	RI-9, RI-14
Servicing	
Assets Serviced for Others	RC-S-2, RC-S-6
Contractually Specified Servicing Fees	A-74
Mortgage Servicing Assets	RI-11, RC-M-2, RC-R-4, RC-R-10, RC-R-12, RC-R-20, A-74
Net Servicing Fees	RI-11
Nonmortgage Servicing Assets	RI-11, RC-M-3, RC-R-4, RC-R-10, RC-R-12, RC-R-20, A-74
Servicing Assets and Liabilities	A-74
Setoff	A-62
Settlement Date Accounting	RC-B-1, A-78
Shell Branches	A-75
Shifts in Reporting Status	3
Short Position	RC-D-3, A-73, A-75
Short-Term Obligations	RC-T-8
Signatures	5
Small Business Obligations	RC-R-22
Social Security Taxes	RC-E-7, RI-16
Spread Accounts	RC-R-23, RC-S-2, A-71
Start-Up Activities	A-76
States and Political Subdivisions in the U.S.	
Deposits of	RC-E-8, RC-E-18
Obligations of	RI-4, RI-26, RI-27, RC-C-16
Securities Issued By	RI-6, RI-26, RI-28, RC-6, RC-B-4, RC-B-13, RC-D-1, RC-H-2, RC-K-2, RC-R-15, RC-R-16, RC-R-17, RC-R-19
Stock Options	RI-A-2
Strip Participation	A-70
STRIPS	RC-B-2, A-16
Structured Notes	RC-B-17
Subchapter S Election	RI-32
Submission Date	7
Submission of Reports	6

Subordinated Notes and Debentures	RI-8, RC-10, RC-12, RC-R-6a, A-76
Subsidiaries	9, 10, A-76
Deposits of Consolidated Subsidiaries	RC-O-2
Financial	RC-R-10
Investments in Unconsolidated Subsidiaries	8, 12, RI-11, RI-12, RI-15, RC-8, RC-M-7, RC-R-20, A-33, A-77
Majority-Owned	A-76
Minority Interests in Consolidated Subsidiaries	RC-11, RC-R-3
Real Estate	RC-R-6
Significant	A-76
Trust Company	RC-T-1
Surplus	RI-A-1, RC-12, A-11
Suspense Accounts	A-77
Swap Contracts	RC-L-8, RC-L-15, A-27, A-62
Sweep Arrangements, Retail	A-24
Syndications	A-56, A-78

Tax-Exempt Income	RI-27, RI-28
Telephone Expenses	RI-20, A-76
Tellers' Overages and Shortages	RI-14, RI-21
Temporary Differences	A-4, A-11, A-42
Term Federal Funds	A-35, A-54
Tier 1 Capital	13, RC-R-6
Tier 2 Capital	RC-R-8
Tier 3 Capital	RC-R-9
Total Assets	RC-8, RC-H-2, RC-I-1, RC-K-3, RC-R-20
Total Equity Capital	13, RI-A-1, RI-A-5, RC-15, RC-R-2
Total Liabilities	RC-11, RC-H-2, RC-I-1
Total Risk-Based Capital	13, RC-R-9
Trade Date Accounting	RC-B-1, A-78
Trading	
Trading Account	A-72, A-78

	T
Trading (cont.)	
Trading Assets	RI-6, RC-6, RC-D-1, RC-D-3, RC-K-3, RC-R-18, A-79
Trading Derivatives	RC-D-2, RC-D-3, A-31
Trading Liabilities	RI-8, RC-10, RC-D-1, RC-D-3, A-79
Trading Revenue	RI-10, RI-29, A-31
Transaction Accounts	RI-7, RC-E-4, RC-E-5, RC-K-3, A-18
Transactions Near End of Period	13
Transactions with Parent Holding Company	RI-A-5, RI-E-2
Transfer Agent	RC-T-10
Transfers of Financial Assets	A-79
Travelers' Checks	RI-13, RC-E-3, RC-E-6, RC-E-7
Treasury Receipts	RC-B-9, A-15
Treasury Stock	RI-A-3, RC-15, A-82
Treasury Tax and Loan Accounts	RI-13, RC-E-7
Troubled Debt Restructurings	RI-24, RC-C-21, RC-N-3, RC-N-9, A-56, A-61, A-83
Trusteeships, Corporate and Municipal	RC-T-9
Trust Funds	RC-E-2, RC-O-2, A-17
Trust Income	RI-9, RC-T-5

Municipal	
Trust Funds	RC-E-2, RC-O-2, A-17
Trust Income	RI-9, RC-T-5
Underlying	A-26
Underwriting Fees	RI-11
Undivided Profits	RC-12
Unearned ESOP Shares	RC-15
Unemployment Taxes	RI-16
Uniform Resource Locator (URL)	5
Uninvested Trust Funds	9, RC-O-2
Unit Investment Trusts	RC-T-9

Unposted Credits

Unposted Debits

Unused Commitments

U.S. Branches and Agencies of Foreign Banks	RC-A-4, RC-C-8, RC-E-8, RC-E-18, A-9, A-16
U.S. Territories and Possessions	A-84
Utility Costs	RI-18, RC-T-6

Valuation Allowance	RI-12, RC-6, RC-C-1, RC-M-5, A-43, A-75, A-82, A-84
Venture Capital Revenue	RI-11
Verification	13

When-Issued Securities	RC-L-7, RC-L-8, RC-L-11, A-72, A-84
Withheld Taxes	RC-E-7, RC-E-8, A-17

RC-O-2

RC-3, RC-A-3, RC-O-1

RC-L-1, RC-R-2, RC-R-26, A-57