Redaction of PDF Files Using Adobe Acrobat Professional X

Enterprise Applications Division of the Systems and Network Analysis Center (SNAC)

Information Assurance Directorate



National Security Agency 9800 Savage Rd. Ft. Meade, MD 20755

Executive Summary

Redaction is the process of selectively removing visible and non-visible classified or sensitive information from a document for release to a recipient (s) not cleared to view that information. The goal of the process is to prevent *inadvertent* release of the information. The Portable Document Format (PDF) is a common format for publishing documents on the web and for exchanging files between government entities and government contractors. Redaction of PDF files is an ongoing challenge for these entities. This document describes how to use Adobe Acrobat Professional X for redaction of PDF files.

What This Document Addresses

This document describes a procedure using Adobe Acrobat Professional X to redact information from PDF documents. The original source of the document can be any application, but the process described applies to documents that are already in PDF.

What This Document Does Not Address

This document does not address the purposeful or covert release of classified information, nor does it address countermeasures for executable content vulnerabilities or any features of Adobe Acrobat Professional X other than those related to redaction. The process described does not address starting with documents in other formats or redaction using other tools.

Sources for Further Research

The NSA website, www.nsa.gov, contains related papers:

Redacting with Confidence: How to Safely Publish Sanitized Reports Converted From Word 2007 to PDF, I333-TR-015R-2005.pdf

Hidden Data and Metadata in Adobe PDF Files, I733-028R-2008.pdf

The Adobe website, www.adobe.com, contains many resources on the PDF format and Adobe products, including forums for discussion of product questions.

Table of Contents

1.	Introduction	. 1
2.	New Features in Adobe Acrobat Professional X	. 1
3.	Recommended Procedure for Redaction Using Adobe Acrobat X	. 1
4.	Detailed Steps	. 2
4.1.	Turning Off JavaScript	. 2
4.2.	Redacting Information and Apply Redactions	. 3
4.3.	Sanitize Document	. 5
4.4.	Changing Redaction Properties	. 5
4.5.	Choosing Remove Hidden Information instead of Sanitize Document	. 7
4.6.	(Optional) File->SaveAs->Optimized PDF	. 7
5.	Conclusion	. 8

Table of Figures

Figure 1: Preferences Dialog	2
Figure 2: Protection Menu	3
Figure 3: Redaction Dialog	1
Figure 4: Redaction Outline Marks	1
Figure 5: Redaction Black Box Marks	1
Figure 6: Sanitize Document Dialog	5
Figure 7a: Default Redaction Properties Dialog6	5
Figure 7b: Modified Redaction Properties Dialog6	5
Figure 8: Redaction Mark with Custom Text6	5
Figure 9: Remove Hidden Information Check List	7
Figure 10: PDF Optimizer Dialog	3

1. Introduction

Redaction of information from documents is an ongoing challenge. There are multiple tools to assist the user depending on the source file and the desired destination file type. NSA has released several papers on the topic of redaction and the removal of hidden data in Microsoft Word and PDF files. These papers are on the NSA.gov website. Adobe Acrobat Professional X (AAPX) includes improvements on the redaction process and a new feature, *Sanitize Document*, to greatly enhance redaction capabilities. This paper describes the use of AAPX in redaction.

2. New Features in Adobe Acrobat Professional X

Prior versions of Acrobat Pro had redaction functions spread across two menus, and the user had to perform multiple steps to remove hidden data. Even after completing the steps, some complex structures may have retained hidden data, such as layers in diagrams. In version X, Adobe added a *Sanitize Document* function to accomplish a one-button sanitization that removes metadata, embedded content and attached files, scripts, hidden layers, embedded search indexes, bookmarks, stored form data, review and comment data, hidden data from previous document saves, obscured text and images, comments hidden within the body of the PDF file, unreferenced data, links, actions and JavaScripts, and overlapping objects.

The new *Sanitize Document* feature is different from the *Remove Hidden Information* feature which allows the user to choose what content to remove and what to leave in. When the user selects *Remove Hidden Information*, AAPX creates a list of items to remove and the user can un-select things to keep in the document. The user must then click the *Remove* button to remove all of the selected items. On the other hand, *Sanitize Document* removes everything in one step creating a "what you see is what you get" document. In environments where the user must prepare many documents for declassification or for release where no advanced functionality is necessary in the final copy, *Sanitize Document* will save time and reduce the likelihood of process errors.

Complex images with hidden layers had to be handled individually in prior versions of Acrobat Pro. Documents with diagrams, embedded spreadsheets, etc. had to be saved as JPEGs to insure removal of hidden layers – the whole document had to be converted to JPEG images to ensure removal of all hidden layers. AAPX now handles hidden layers correctly with both *Sanitize Document* and *Remove Hidden Information*. The user is given the option to leave those items as is with the *Remove Hidden Information* option.

3. Recommended Procedure for Redaction Using Adobe Acrobat X

Assuming the user is starting the redaction process with a PDF document (rather than a Microsoft Word or other format), these are the high-level steps to perform redaction in AAPX (detailed steps are listed in the next section):

- 1. Start AAPX.
- 2. Turn off JavaScript. If you are trying to remove hidden malicious code from a document, it is best to not be hit with it yourself.
- 3. Open a copy of the original document in AAPX (always work with a copy).
- 4. Redact Information.
- 5. Apply Redactions.
- 6. Sanitize Document.
- 7. (Optional) Save Document with File->SaveAs->Optimized PDF.

4. Detailed Steps

4.1. Turning Off JavaScript

For documents created by the user or from a known source, turning off JavaScript is optional. However, this step is essential for sanitization of documents of unknown origin that might contain malware or other executable content.

JavaScript is one of the things that should be removed from PDF documents during the redaction process when the desire is to produce a "what you see is what you get" document. Since some PDF documents might contain malicious JavaScript, it is best to not be hit with such attacks while trying to prevent them. After opening AAPX and before opening a document, the user should turn off JavaScript:

- 1. On the top menu, select *Edit->Preferences* to bring up the Preferences dialog
- 2. Under *Categories*, select *JavaScript*. This brings up the JavaScript palate shown in Figure 1.

Categories:	JavaScript
Commenting A Documents	V Enable Acrobat JavaScript
Full Screen General Page Display	JavaScript Security Enable menu items JavaScript execution privileges V Enable global object security policy
3D & Multimedia Accessibility Action Wizard Cotalog Color Management Convert from PDF Convert Ton PDF Forms Identity International Internet JavaScript	JavaScript Debugger JavaScript debugger after Acrobat is restarted Store breakpoints in PDF file When exception is thrown: Ignore Ignore Trace Break Enable interactive console Show console on errors and messages
Measuring (2D) Measuring (2D) Measuring (3E0) Measuring (Geo) Multimedia Trust (legacy) Online Services Reading Reviewing Search Security (Enhanced)	JavaScript Editor Use Acrobat JavaScript Editor Font: Courier New Use external JavaScript editor Browse Browse

Figure 1: Preferences Dialog

3. JavaScript is enabled by default as shown in Figure 1. Uncheck *Enable Acrobat JavaScript* and leave everything else as shown above, then click OK.

Now it is safe to open the document for redaction.

4.2. Redacting Information and Apply Redactions

After opening a document in AAPX:

- Open the Tools menu by clicking on *Tools* on the top right menu bar. This will open a menu that should look like Figure 2 without the Protection menu expanded. Another way to get to this menu is on the top menu bar, select *View->Tools->Protection*.
- 2. Expand the *Protection* menu option which will look like the Figure 2.



Figure 2: Protection Menu

3. Select *Mark For Redaction*. This will display the dialog shown in Figure 3 stating that redaction requires two steps: *Mark for Redaction* and *Apply Redactions*. Click OK.




Figure 3: Redaction Dialog

4. The cursor is now a redaction cursor. Place the cursor at the beginning of the area you want to redact. Click the left mouse button, hold it down, and drag the cursor over the information to redact. This will create a red outline around the information you are redacting as shown in Figure 4. When you mouse over an outlined area, it will turn black to indicate how the area will look in the final copy.




Figure 4: Redaction Outline Marks

5. After you have marked all of the areas for redaction, select *Apply Redactions* on the right panel menu. This will display a dialog stating "You are about to permanently remove all content that has been marked for redaction. Once the document is saved, this operation cannot be undone. Are you sure you want to continue?" Select OK.

After Apply Redactions, the red outlines are filled with black as shown in Figure 5.




Figure 5: Redaction Black Box Marks

- 6. After applying redactions, you will see a dialog box that says "Redactions have been successfully applied. Would you like to also find and remove hidden information in your document?" Select no. You can choose this option from the right panel later, or later chose *Sanitize Document* instead.
- 7. You can continue to Mark and Apply in the document. When you are finished marking all of the redactions, you are ready to sanitize the document.

4.3. Sanitize Document

After marking and applying all of the redactions for the document:

1. Select *Sanitize Document* from the right panel menu. This brings up a dialog shown in Figure 6.

Sanitize [Document 📃
1	Sanitize Document removes hidden data and metadata from your document so that sensitive information is not inadvertently passed along when you publish your PDF. Sanitize Document will remove:
	* Metadata
	* Embedded content and attached files
	* Scripts
	* Hidden layers
	* Embedded search indexes
	* Stored form data
	* Review and comment data
	* Hidden data from previous document saves
	* Obscured text and images
	* Comments hidden within the body of the PDF file
	* Unreferenced data
	* Links, actions and javascripts
	* Overlapping objects
	Press OK to begin the sanitization process by selecting a location to save your sanitized document.
Do 🗐	not show this message again OK Cancel

Figure 6: Sanitize Document Dialog


Select OK, you will be prompted to save a copy of the document. AAPX tries to minimize the risk
of overwriting the original after you have removed all of the functionality of forms and scripts.
Save the document. The changes are not final until you save the document. If you started with a
copy, just save to whatever file you are working with. If you started with the original, be sure to
save to a different filename.

4.4. Changing Redaction Properties

The user can customize the redaction properties rather than using the default black box mark. The right panel menu includes a *Redaction Properties* choice which displays the dialog in Figure 7a.

edacted Area Fill Color: 🔳 🔲 Use Overlay Text	Redacted Area Fill Color: 🔳 🐨 Use Overlay Text
Overlay Text	Overlay Text
Font: Helvetica + Font Size: 10	Font: Helvetica Font Size: 10
Auto-Size text to fit redaction region Repeat Overlay Text	Auto-Size text to fit redaction region 📃 Repeat Overlay Text
Text Alignment: 📰 🚍 Font Color: 🔳	Text Alignment: 📰 🚍 🗐 Font Color: 📕
Custom Text:	Custom Text: MY OVERLAY TEXT
C Redaction Code:	Redaction Code: (b) (1) (A)
Code Sets: Code Entries:	Code Sets: Code Entries:
U.S. POIA U.S. Privacy Act (b) (1) (A) (b) (2) (b) (3) (A) (b) (3) (B)	U.S. FOIA U.S. Privacy Act (b) (1) (A) (b) (1) (B) (b) (2) (b) (3) (A) (b) (3) (B)
Add Selected Entry Edit Codes	Remove Selected Entry Edit Codes
Redaction Mark Appearance	Redaction Mark Appearance
Outline Color: 📕 Fill Color: 📐	Outline Color: 🔳 Fill Color: 🔟
Fill Opacity: 100%	Fill Opacity: 100%

Figure 7a: Default Redaction Properties Dialog



The figure on the left shows the default settings. Some redaction may require redaction marks that explain the reason for the redaction, such as for U.S. FOIA or U.S. Privacy Act requirements. AAPX allows the user to insert custom text in the redaction marks. To insert custom text, check *Use Overlay Text* on the top right of the dialog. The greyed-out fields become usable and the user can insert either custom text or choose *Redaction Code* from the codes shown in the dialog. Be careful not to use classified or sensitive text as the custom overlay text.

Figure 8 shows how the redaction marks appear with the *Custom Text* set to MY OVERLAY TEXT as shown in figure 7b above:




Figure 8: Redaction Mark with Custom Text

The user can change the outline, font and fill colors using the *Redaction Properties* dialog.

4.5. Choosing Remove Hidden Information instead of Sanitize Document

Sanitize Document removes all form and JavaScript functionality from the document, all tags, all comments, everything! In those cases where the user needs to leave some functionality in the document, the user can use the *Remove Hidden Information* option and select individual items to leave in the document; however, this reduces the assurance that all hidden data is removed and means the user must save the document as optimized PDF (see next section). *Sanitize Document* includes optimizing the PDF format. The *Remove Hidden Information* option should only be used for special circumstances. *Sanitize Document* is the recommended option otherwise.

When the user selects *Remove Hidden Information*, AAPX searches the document for hidden information and displays a checklist on the left menu pane as shown in Figure 9:

Cont Oscilla	_risks_old.pdf - Adobe Acrobat Pro Edit View Window Help
-	Create - 🎦 🗒 🖨 🖂 🏟 🦻 🖓
	■ 10 / 26 IN (1) = ⊕ 47% ▼
	Remove Hidden Information
P	8.
	Status: Finding Hidden InformationDone
Ŋ	Remove
LJ2	
	Results:
	 □ pdf_risks_old.pdf □ I Document (1 item) □ Document (1 item) □ Show preview □ I Deleted or cropped content (1 item) □ Deleted or cropped content (1 item) □ Links, actions and javascripts (1 item) □ Overlapping objects (4 pages)

Figure 9: Remove Hidden Information Check List

The user can preview each piece of hidden information identified by AAPX and de-select items to leave in the document. When finished reviewing the checklist, the user has to hit the *Remove* button which brings up a warning dialog requiring the user to hit OK.

4.6. (Optional) File->SaveAs->Optimized PDF

Multiple vendors have applications that create PDF files. These files are not always well-formed or standardized PDF and could contain sensitive or classified remnant data within the file format. The *Sanitize Document* option includes optimizing the PDF format to correct these problems. However, if the

user chose *Remove Hidden Data* instead of *Sanitize Document* (see previous section), the user should then save the file as Optimized PDF.

Current PDF Ver	sion: 1.6 (Acrobat 7.x) Make compatible with:
Images	Image Settings
Fonts	Color Images :
 □ Transparency ☑ Discard Objects ☑ Discard User Data 	Downsample: Bicubic Downsampling to V 150 ppi for images above 225 ppi.
Clean Up	Compression: JPEG Quality: Medium
	Grayscale Images :
	Downsample: Bicubic Downsampling to 🔹 150 ppi for images above 225 ppi.
	Compression: JPEG Quality: Medium
	Monochrome Images :
	Downsample: Bicubic Downsampling to 💌 300 ppi for images above 450 ppi.
	Compression: JBIG2 Quality: Lossy
K III K	All units are in pixels per inch (ppi
	Optimize images only if there is a reduction in size

1. Select *File->SaveAs->Optimized PDF* from the top menu. This brings up the dialog in Figure 10.

Figure 10: PDF Optimizer Dialog

- 2. Uncheck *Fonts* to retain embedded fonts. If the embedded fonts are removed and not available on the recipient's system, the system will substitute fonts which could affect the appearance of the document and the alignment of the redaction marks. Some situations may require removal of embedded fonts, but in general redaction tasks this is optional.
- 3. If you have already run *Remove Hidden Data* or plan to run it, you do not need to change any other options. Hit OK. You will be prompted for a filename, enter a filename and hit OK again.

5. Conclusion

When using AAPX for redaction of sensitive or classified information from documents meant for public release, the steps outlined in this paper with the *Sanitize Document* option are the recommended procedure. This produces a "what you see is what you get" final document.