Traffic Safety Facts

NHTSA www.nhtsa.gov

2005 Data

DOT HS 810 629

Speeding

"The economic cost of speeding-related crashes is estimated to be \$40.4 billion each year."


NHTSA considers a crash to be speeding-related if the driver was charged with a speeding-related offense or if an officer indicated that racing, driving too fast for conditions, or exceeding the posted speed limit was a contributing factor in the crash.

Speeding is one of the most prevalent factors contributing to traffic crashes. The economic cost to society of speeding-related crashes is estimated by NHTSA to be \$40.4 billion per year. In 2005, speeding was a contributing factor in 30 percent of all fatal crashes, and 13,113 lives were lost in speeding-related crashes.

Motor vehicle crashes cost society an estimated \$7,300 per second. The total economic cost of crashes was estimated at \$230.6 billion in 2000. In 2000, the cost of speeding-related crashes was estimated to be \$40.4 billion — \$76,865 per minute or \$1,281 per second.

Speeding reduces a driver's ability to steer safely around curves or objects in the roadway, extends the distance necessary to stop a vehicle, and increases the distance a vehicle travels while the driver reacts to a dangerous situation.

Figure 1 Fatal Crashes by Speeding Status, 1995-2005





"In 2005, 38 percent of 15- to 20-year-old male drivers involved in fatal crashes were speeding." For drivers involved in fatal crashes, young males are the most likely to be speeding. The relative proportion of speeding-related crashes to all crashes decreases with increasing driver age. In 2005, 38 percent of the male drivers age 15 to 20 who were involved in fatal crashes were speeding at the time of the crash.




Figure 2 **Speeding Drivers in Fatal Crashes by Age and Sex, 2005**


Alcohol and speeding are clearly a deadly combination. Alcohol involvement is prevalent for drivers involved in speeding-related crashes. In 2005, 40 percent of the drivers with a blood alcohol concentration (BAC) of .08 grams per deciliter (g/dL) or higher involved in fatal crashes were speeding, compared with only 14 percent of the drivers with a BAC of .00 g/dL involved in fatal crashes.

In 2005, 25 percent of the speeding drivers under age 21 who were involved in fatal crashes also had a BAC of .08 g/dL or higher. In contrast, only 11 percent of the nonspeeding drivers under age 21 involved in fatal crashes in 2005 had a BAC of .08 g/dL or higher.

For drivers between the ages of 21 and 24 who were involved in fatal crashes in 2005, 50 percent of speeding drivers had a BAC of .08 g/dL or higher, compared with only 24 percent of nonspeeding drivers.

Figure 3
Percentage of All Drivers Involved in Fatal Crashes Who Were Speeding, by BAC Level, 2005

"In 2005, 40 percent of the drivers with a BAC of .08 g/dL or higher involved in fatal crashes were speeding, compared with only 14 percent of drivers with a BAC of .00 g/dL involved in fatal crashes."



For both speeding and nonspeeding drivers involved in fatal crashes, the percentage of those who had been drinking, with a BAC of .01 g/dL or higher, at the time the crash occurred was higher at night than during the day. Between midnight and 3 a.m., 75 percent of speeding drivers involved in fatal crashes had been drinking.

"Between midnight and 3 a.m., 75 percent of speeding drivers involved in fatal crashes had been drinking."

Figure 4
Drivers in Fatal Crashes by Alcohol Involvement, Speeding Status, and Time of Day, 2005





Figure 5
Percentages of Fatalities Related to Speeding and to Alcohol, 1995-2005

"In fatal crashes, 34 percent of motorcyclists were speeding."




In 2005, 34 percent of all motorcyclists involved in fatal crashes were speeding, compared to 22 percent for passenger car drivers, 18 percent for light-truck drivers, and 7 percent for large-truck drivers.

Figure 6

Speeding, Alcohol Involvement, and Failure to Use Restraints

Among Drivers Involved in Fatal Crashes by Vehicle Type, 2005



"Among passenger vehicle drivers age 21 and over in fatal crashes in 2005, those who were not speeding were about 72 percent more likely to be wearing safety belts than those who were speeding at the time of the crash."

In 2005, only 49 percent of speeding passenger vehicle drivers under age 21 who were involved in fatal crashes were wearing safety belts at the time of the crash. In contrast, 67 percent of nonspeeding drivers in the same age group were restrained. For drivers age 21 and older, the percentage of speeding drivers involved in fatal crashes who were using restraints at the time of the crash was 43 percent, but 72 percent of nonspeeding drivers in fatal crashes were restrained.


In 2005, 22 percent of speeding drivers involved in fatal crashes had an invalid license at the time of the crash, compared with 11 percent of nonspeeding drivers.


Speeding was a factor in 28 percent of the fatal crashes that occurred on dry roads in 2005 and in 33 percent of those that occurred on wet roads. Speeding was a factor in 51 percent of the fatal crashes that occurred when there was snow or slush on the road and in 58 percent of those that occurred on icy roads.

Speeding was involved in over one-fourth (27%) of the fatal crashes that occurred in construction/maintenance zones in 2005.

In 2005, 86 percent of speeding-related fatalities occurred on roads that were not Interstate highways.

Figure 7 **Speeding-Related Fatalities by Road Type, 2005**





For more information:

Information on speeding involvement in traffic fatalities is available from the National Center for Statistics and Analysis, NPO-121, 400 Seventh Street SW., Washington, DC 20590. NCSA information can also be obtained by telephone or by fax-on-demand at 800-934-8517. Fax messages should be sent to 202-366-7078. General information on highway traffic safety can be accessed by Internet users **www.nhtsa.dot.gov/people/ncsa**. To report a safety-related problem or to inquire about motor vehicle safety information, contact the Vehicle Safety Hotline at 888-327-4236.

Other fact sheets available from the National Center for Statistics and Analysis are *Overview, Alcohol, Bicyclists and Other Cyclists* (formerly titled *Pedalcyclists*), *Children, Large Trucks, Motorcycles, Occupant Protection, Older Population, Pedestrians, School Transportation-Related Crashes, State Alcohol Estimates, State Traffic Data,* and *Young Drivers*. Detailed data on motor vehicle traffic crashes are published annually in *Traffic Safety Facts: A Compilation of Motor Vehicle Crash Data from the Fatality Analysis Reporting System and the General Estimates System*. The fact sheets and annual Traffic Safety Facts report can be accessed online at www.nhtsa.dot. gov/people/ncsa.

Table 1 Speeding-Related Traffic Fatalities by Road Type and Speed Limit, 2005

| State | Total Traffic | Speeding-Related Fatalities by Road Type and Speed Limit | | | | | | | | |
|-------------------|------------------|--|---------------------------|----------------|---------|--------|---------|---------|---------|-------------------|
| | | Total | Interstate Non-Interstate | | | | | | | |
| A la la ausa a | Fatalities | 400 | >55 mph | ≤55 mph | 55 mph | 50 mph | 45 mph | 40 mph | 35 mph | <35 mph |
| Alabama Alaska | 1,131 | 493 | 53 | 7 | 118 | 15 | 175 | 31 | 39 | |
| Alaska Arizona | 72 1,177 | 27 460 | 7 109 | 3 15 | 4 36 | 0 23 | 2 71 | 1 73 | 5 32 | 3 35 |
| | | | | | | | | | | |
| Arkansas | 648 | 104 | 5 | 0 | 52 | 3 | 11 | 7 | 17 | 5 |
| California | 4,329 | 1,471 | 203 | 30 | 344 | 60 | 145 | 131 | 181 | 156 |
| Colorado | 606 | 204 | 16 | 11 | 25 | 10 | 30 | 24 | 22 | 30 |
| Connecticut | 274 | 92 | 3 | 7 | 1 | 0 | 9 | 9 | 9 | 49 |
| Delaware | 134 | 52 | 1 | 5 | 4 | 26 | 0 | 5 | 6 | 2 |
| Dist of Columbia | 48 | 17 | 0 | 5 | 0 | 0 | 0 | 0 | 2 | 10 |
| Florida | 3,543 | 239 | 14 | 7 | 30 | 11 | 52 | 20 | 33 | 33 |
| Georgia | 1,729 | 340 | 22 | 5 | 105 | 6 | 51 | 5 | 43 | 18 |
| Hawaii | 140 | 69 | 0 | 6 | 6 | 1 | 6 | 1 | 25 | 20 |
| Idaho | 275 | 95 | 14 | 0 | 11 | 11 | 7 | 5 | 8 | 8 |
| Illinois | 1,361 | 525 | 68 | 22 | 199 | 16 | 48 | 46 | 62 | 61 |
| Indiana | 938 | 258 | 19 | 17 | 59 | 10 | 42 | 34 | 27 | 46 |
| lowa | 450 | 44 | 5 | 0 | 19 | 2 | 5 | 0 | 7 | 4 |
| Kansas | 428 | 119 | 16 | 0 | 37 | 2 | 6 | 4 | 4 | 19 |
| Kentucky | 985 | 187 | 12 | 6 | 117 | 0 | 22 | 2 | 17 | 10 |
| Louisiana | 955 | 180 | 14 | 3 | 70 | 4 | 34 | 7 | 27 | 13 |
| Maine | 169 | 86 | 11 | 3 | 9 | 9 | 21 | 11 | 9 | 10 |
| Maryland | 614 | 214 | 14 | 15 | 19 | 34 | 22 | 29 | 30 | 46 |
| Massachusetts | 442 | 146 | 11 | 3 | 4 | 3 | 11 | 21 | 28 | 57 |
| Michigan | 1,129 | 243 | 26 | 11 | 120 | 4 | 24 | 2 | 14 | 25 |
| Minnesota | 559 | 152 | 13 | 4 | 85 | 7 | 6 | 4 | 2 | 20 |
| Mississippi | 931 | 254 | 36 | 0 | 91 | 20 | 45 | 9 | 21 | 8 |
| Missouri | 1,257 | 529 | 59 | 9 | 197 | 6 | 31 | 28 | 66 | 51 |
| Montana | 251 | 97 | 17 | 0 | 2 | 2 | 4 | 0 | 9 | 10 |
| Nebraska | 276 | 51 | 10 | 0 | 5 | 11 | 2 | 3 | 8 | 5 |
| Nevada | 427 | 160 | 24 | 0 | 10 | 8 | 23 | 1 | 23 | 9 |
| New Hampshire | 166 | 56 | 4 | 1 | 4 | 5 | 1 | 6 | 14 | 16 |
| New Jersey | 748 | 79 | 0 | 3 | 10 | 21 | 12 | 3 | 9 | 13 |
| New Mexico | 488 | 165 | 33 | 2 | 28 | 1 | 12 | 7 | 10 | 11 |
| New York | 1,429 | 456 | 13 | 13 | 173 | 15 | 27 | 37 | 21 | 77 |
| North Carolina | 1,534 | 560 | 40 | 7 | 287 | 4 | 121 | 1 | 72 | 14 |
| North Dakota | 123 | 28 | 2 | 1 | 8 | 2 | 0 | 1 | 0 | 3 |
| Ohio | 1,323 | 277 | 23 | 6 | 123 | 4 | 28 | 7 | 51 | 21 |
| Oklahoma | 802 | 292 | 27 | 2 | 64 | 8 | 71 | 13 | 18 | 15 |
| Oregon | 488 | 161 | 10 | 2 | 76 | 3 | 11 | 7 | 19 | 14 |
| Pennsylvania | 1,616 | 757 | 44 | 18 | 195 | 18 | 167 | 91 | 144 | 54 |
| Rhode Island | 87 | 40 | 6 | 3 | 1 | 3 | 2 | 2 | 6 | 17 |
| South Carolina | 1,093 | 480 | 59 | 2 | 158 | 9 | 93 | 22 | 55 | 24 |
| South Dakota | 186 | 62 | 7 | 0 | 26 | 0 | 1 | 3 | 4 | 4 |
| Tennessee | 1,270 | 266 | 12 | 10 | 9 | 0 | 9 | 4 | 4 | 4 |
| Texas | 3,504 | 1,426 | 162 | 49 | 174 | 35 | 147 | 117 | 121 | 143 |
| Utah | 282 | 75 | 38 | 0 | 3 | 3 | 2 | 6 | 7 | 6 |
| Vermont | 73 | 33 | 2 | 0 | 0 | 13 | 3 | 3 | 5 | 3 |
| Virginia | 947 | 313 | 42 | 19 | 128 | 3 | 52 | 8 | 35 | 19 |
| Washington | 647 | 247 | 14 | 4 | 18 | 54 | 12 | 19 | 57 | 41 |
| West Virginia | 374 | 82 | 10 | 0 | 33 | 3 | 13 | 8 | 6 | 6 |
| Wisconsin | 815 | 294 | 16 | 6 | 157 | 2 | 27 | 7 | 18 | 42 |
| Wyoming | 170 | 56 | 18 | 0 | 8 | 0 | 3 | 1 | 1 | 6 |
| U.S. Total* | 43,443 | 13,113 | 1,384 | 342 | 3,462 | 510 | 1,719 | 886 | 1,453 | 1,341 |
| Puerto Rico | 453 | 215 | 45 | 0 | 7 | 3 | 30 | 21 | 84 | 25 |

^{*}Of the total number of speeding-related fatalities in 2005, 5,562 occurred on roads with posted speed limits between 55 and 65 mph, and 902 occurred on roads with speed limits above 65 mph.

Note: The total column for speeding-related fatalities includes fatalities that occurred on roads for which the speed limit was unknown.