Traffic Safety Facts 1996

U.S. Department of Transportation
National Highway Traffic
Safety Administration



School Buses




Since 1986 there have been about 424,000 fatal traffic crashes. Just over 0.3 percent (1,305) were classified as school bus-related.

A school bus-related crash is a crash which involves, either directly or indirectly, a school bus-type vehicle, or a vehicle functioning as a school bus, transporting children to or from school or school-related activities.

Since 1986, 1,458 people have died in school bus-related crashes — an average of 133 fatalities per year. Most of the people who lost their lives in those crashes (61 percent) were occupants of other vehicles involved. Nonoccupants (pedestrians, bicyclists, etc.) accounted for 29 percent of the deaths, and school bus occupants accounted for 10 percent (drivers 2 percent, passengers 8 percent).

Since 1986, 283 school-age pedestrians (less than 19 years old) have died in school bus-related crashes. Nearly two-thirds (63 percent) were killed by school buses, 5 percent by vehicles functioning as school buses, and 33 percent by other vehicles involved in the crashes. Half of all schoolage pedestrians killed in school bus-related crashes were between the ages of 5 and 7.

Figure 1. Occupant and Pedestrian Fatalities in School Bus-Related Crashes, by Age, 1986-1996



Note: Occupant fatalities shown are for occupants of school buses or vehicles used as school buses.

"An average of 35 school-age children die in school bus-related traffic crashes each year — 9 school bus occupants and 26 pedestrians."



On average, 17 school-age pedestrians are killed by school buses (or vehicles used as school buses) each year, and 8 are killed by other vehicles involved in school bus-related crashes.

More school-age pedestrians are killed in the afternoon than in the morning, with 42 percent of the fatalities occurring in crashes between 3:00 and 4:00 PM.

Table 1. Fatalities in School Bus-Related Crashes by Time of Day, 1986-1996

| Time of Day | Occupant Fatalities* | Pedestrians (School Age) | Total Fatalities |
|----------------|----------------------|-----------------------------|---------------------|
| 12:00-6:59 AM | 5 | 6 | 11 |
| 7:00-7:59 AM | 49 | 34 | 83 |
| 8:00-8:59 AM | 14 | 21 | 35 |
| 9:00-9:59 AM | 5 | 6 | 11 |
| 10:00-10:59 AM | 4 | 0 | 4 |
| 11:00-11:59 AM | 2 | 6 | 8 |
| 12:00-12:59 PM | 4 | 8 | 12 |
| 1:00-1:59 PM | 6 | 4 | 10 |
| 2:00-2:59 PM | 16 | 43 | 59 |
| 3:00-3:59 PM | 25 | 119 | 144 |
| 4:00-4:59 PM | 8 | 30 | 38 |
| 5:00-11:59 PM | 4 | 6 | 10 |
| Total | 142 | 283 | 425 |

"From 1986 to 1996, half of all schoolage pedestrians killed in school busrelated crashes were 5 to 7 years old."

Between 1986 and 1996, 95 crashes occurred in which at least one occupant of a school bus or a vehicle functioning as a school bus died. Half of those crashes (49 percent) involved another vehicle. In the 48 single-vehicle crashes, 60 occupants — 13 drivers and 47 passengers — were killed. In the 47 multiple-vehicle crashes, 15 drivers and 67 passengers died. In the 48 single-vehicle crashes, the first harmful events were as follows: striking a fixed object (28 crashes), the vehicle overturning (6 crashes), a person falling from the vehicle (10 crashes), the vehicle colliding with a train (2 crashes), collision with object not fixed (1 crash), and other noncollision (1 crash).

In 40 percent of all crashes involving fatalities to occupants of a school bus or vehicle used as a school bus, the principal point of impact was the front of the vehicle.

Since 1986, 7 drivers and 48 passengers have died in school buses providing transportation *for purposes other than school or school-related activities (churches, civic organizations, etc.)*. In one such multi-vehicle crash, 27 occupants, including the driver, died.

^{*} Does not include occupants of other vehicles in school bus-related crashes.

Table 2. Occupant Fatalities in School Bus-Related Crashes by Principal Impact Point on School Bus Vehicle, 1986-1996

| Principal | Type of Crash | | | | | | | | |
|---------------|--------------------|---------|--------------------|----------|---------|------------|--|--|--|
| Impact Point | Single- | Vehicle | Multiple | -Vehicle | Total | | | | |
| on Bus | Crashes Fatalities | | Crashes Fatalities | | Crashes | Fatalities | | | |
| Front | 15 | 18 | 23 | 53 | 38 | 71 | | | |
| Right Side | 6 | 6 | 9 | 14 | 15 | 20 | | | |
| Left Side | 2 | 2 | 9 | 9 | 11 | 11 | | | |
| Rear | 3 | 9 | 5 | 5 | 8 | 14 | | | |
| Тор | 2 | 3 | 0 | 0 | 2 | 3 | | | |
| Undercarriage | 1 | 1 | 1 | 1 | 2 | 2 | | | |
| Noncollision | 18 | 20 | 0 | 0 | 18 | 20 | | | |
| Unknown | 1 | 1 | 0 | 0 | 1 | 1 | | | |
| Total | 48 | 60 | 47 | 82 | 95 | 142 | | | |

"Impacts to the front of the school bus occur in 40 percent of fatal school busrelated crashes."

Table 3. School-Age Pedestrians Killed in School Bus-Related Crashes by Vehicle Maneuver, 1986-1996

| | Striking Vehicle | | | | | |
|--|------------------|----------------------------------|------------------|-------|--|--|
| Vehicle Maneuver | School Bus | Vehicle Used as School Bus | Other Vehicle | Total | | |
| Going Straight | 66 | 9 | 62 | 137 | | |
| Slowing or Stopping in Traffic Lane | 6 | 0 | 3 | 9 | | |
| Starting in Traffic Lane | 73 | 2 | 1 | 76 | | |
| Passing or Overtaking Another Vehicle | 0 | 0 | 14 | 14 | | |
| Leaving a Parked Position | 8 | 1 | 0 | 9 | | |
| Maneuvering to Avoid an Animal, Pedestrian, Object, Other Vehicle, etc. | 0 | 0 | 5 | 5 | | |
| Turning Right | 10 | 0 | 0 | 10 | | |
| Turning Left | 7 | 0 | 0 | 7 | | |
| Backing Up (Other Than for Parking) | 4 | 0 | 0 | 4 | | |
| Negotiating a Curve | 1 | 0 | 5 | 6 | | |
| Entering Parked Position | 2 | 0 | 0 | 2 | | |
| Changing Lanes | 1 | 0 | 1 | 2 | | |
| Other/Unknown | 0 | 1 | 1 | 2 | | |
| Total School-Age Pedestrians Killed | 178 | 13 | 92 | 283 | | |

Table 4. School Bus-Related Crashes Involving Occupant Fatalities, 1986-1996

| | School Bus Body-Type | | | Vehicle Used as School Bus | | | Total | | | | | |
|-------|----------------------|------------|------------------|----------------------------|----------------|------------|------------------|------------|----------------|------------|------------------|------------|
| | Single-Vehicle | | Multiple-Vehicle | | Single-Vehicle | | Multiple-Vehicle | | Single-Vehicle | | Multiple-Vehicle | |
| Year | Crashes | Fatalities | Crashes | Fatalities | Crashes | Fatalities | Crashes | Fatalities | Crashes | Fatalities | Crashes | Fatalities |
| 1986 | 0 | 0 | 1 | 1 | 1 | 1 | 0 | 0 | 1 | 1 | 1 | 1 |
| 1987 | 0 | 0 | 6 | 11 | 3 | 3 | 3 | 3 | 3 | 3 | 9 | 14 |
| 1988 | 2 | 2 | 4 | 5 | 1 | 1 | 0 | 0 | 3 | 3 | 4 | 5 |
| 1989 | 7 | 8 | * 5 | 25 | 3 | 3 | 1 | 1 | 10 | 11 | 6 | 26 |
| 1990 | 5 | 7 | 4 | 4 | 0 | 0 | 0 | 0 | 5 | 7 | 4 | 4 |
| 1991 | 0 | 0 | 6 | 10 | 4 | 6 | 1 | 1 | 4 | 6 | 7 | 11 |
| 1992 | 3 | 3 | 4 | 4 | 2 | 3 | 0 | 0 | 5 | 6 | 4 | 4 |
| 1993 | 5 | 5 | 2 | 5 | 2 | 2 | 1 | 1 | 7 | 7 | 3 | 6 |
| 1994 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 4 | 0 | 0 | 3 | 4 |
| 1995 | 2 | 8 | 3 | 4 | 1 | 1 | 0 | 0 | 3 | 9 | 3 | 4 |
| 1996 | 5 | 5 | 3 | 3 | 2 | 2 | 0 | 0 | 7 | 7 | 3 | 3 |
| Total | 29 | 38 | 38 | 72 | 19 | 22 | 9 | 10 | 48 | 60 | 47 | 82 |

^{*} Includes one crash with 21 occupant fatalities.

Note: Does not include occupants of other vehicles in school bus-related crashes.

Table 5. Fatalities in School Bus-Related Crashes, 1986-1996

| | Occup | ants of Schoo | l Bus* | F | Pedestrians | | | | |
|---------|--------|---------------|--------|--------------------------|----------------------------|-------|-----------------------|----------------------------------|-------|
| Year | Driver | Passenger | Total | Struck by School Bus* | Struck by Other Vehicle | Total | Other Nonoccupants | Occupants of Other Vehicle | Total |
| 1986 | 2 | 0 | 2 | 31 | 16 | 47 | 6 | 73 | 128 |
| 1987 | 8 | 9 | 17 | 32 | 11 | 43 | 5 | 113 | 178 |
| 1988 | 2 | 6 | 8 | 19 | 17 | 36 | 6 | 80 | 130 |
| 1989 | 4 | 33 | 37 | 25 | 7 | 32 | 1 | 72 | 142 |
| 1990 | 4 | 7 | 11 | 32 | 7 | 39 | 1 | 64 | 115 |
| 1991 | 2 | 15 | 17 | 21 | 5 | 26 | 5 | 86 | 134 |
| 1992 | 1 | 9 | 10 | 21 | 8 | 29 | 2 | 83 | 124 |
| 1993 | 1 | 12 | 13 | 32 | 8 | 40 | 2 | 86 | 141 |
| 1994 | 2 | 2 | 4 | 28 | 9 | 37 | 2 | 64 | 107 |
| 1995 | 0 | 13 | 13 | 24 | 10 | 34 | 4 | 72 | 123 |
| 1996 | 2 | 8 | 10 | 16 | 7 | 23 | 2 | 101 | 136 |
| Total | 28 | 114 | 142 | 281 | 105 | 386 | 36 | 894 | 1,458 |
| Average | 3 | 10 | 13 | 26 | 10 | 35 | 3 | 81 | 133 |

^{*} Includes school bus body type and vehicle used as school bus.

For more information:

Information on school bus traffic fatalities is available from the National Center for Statistics and Analysis, NRD-31, 400 Seventh Street, S.W., Washington, D.C. 20590. Telephone inquiries should be addressed to Ms. Louann Hall at 1-800-934-8517. FAX messages should be sent to (202) 366-7078. General information on highway traffic safety can be accessed by Internet users at http://www.nhtsa.dot.gov/people/ncsa. To report a safety-related problem or to inquire about motor vehicle safety information, contact the Auto Safety Hotline at 1-800-424-9393.