U.S. Department of Transportation National Highway Traffic Safety Administration

## Traffic Safety Facts 1997

School Buses

# People Saving People

http://www.nhtsa.dot.gov DOT HS 808 774


"An average of 33 school-age children die in school busrelated traffic crashes each year — 9 school bus occupants and 23 pedestrians." A school bus-related crash is a crash which involves, either directly or indirectly, a school bus-type vehicle, or a vehicle functioning as a school bus, transporting children to or from school or school-related activities.

Since 1987 there have been about 420,000 fatal traffic crashes. Just over 0.3 percent (1,298) were classified as school bus-related.

Since 1987, 1,458 people have died in school bus-related crashes — an average of 132 fatalities per year. Most of the people who lost their lives in those crashes (63 percent) were occupants of other vehicles involved. Nonoccupants (pedestrians, bicyclists, etc.) accounted for 27 percent of the deaths, and school bus occupants accounted for 10 percent (drivers 2 percent, passengers 8 percent).

Since 1987, 257 school-age pedestrians (less than 19 years old) have died in school bus-related crashes. Nearly two-thirds (64 percent) were killed by school buses, 5 percent by vehicles functioning as school buses, and 32 percent by other vehicles involved in the crashes. Half of all schoolage pedestrians killed in school bus-related crashes were between the ages of 5 and 7.

## Figure 1. Occupant and Pedestrian Fatalities in School Bus-Related Crashes, by Age, 1987-1997



Note: Occupant fatalities shown are for occupants of school buses or vehicles used as school buses.

On average, 16 school-age pedestrians are killed by school buses (or vehicles used as school buses) each year, and 7 are killed by other vehicles involved in school bus-related crashes.

More school-age pedestrians are killed in the afternoon than in the morning, with 43 percent of the fatalities occurring in crashes between 3:00 and 4:00 PM.

Time of Day	Occupant Fatalities*	Pedestrians (School Age)	Total Fatalities
12:00-6:59 AM	5	6	11
7:00-7:59 AM	48	29	77
8:00-8:59 AM	17	19	36
9:00-9:59 AM	5	6	11
10:00-10:59 AM	4	0	4
11:00-11:59 AM	2	6	8
12:00-12:59 PM	5	8	13
1:00-1:59 PM	6	4	10
2:00-2:59 PM	17	36	53
3:00-3:59 PM	25	110	135
4:00-4:59 PM	9	29	38
5:00-11:59 PM	7	4	11
Total	150	257	407

Table 1. Fatalities in School Bus-Related Crashes	by Time of Day,
1987-1997	

\* Does not include occupants of other vehicles in school bus-related crashes.

Between 1987 and 1997, 100 crashes occurred in which at least one occupant of a school bus or a vehicle functioning as a school bus died. Half of those crashes (52 percent) involved another vehicle. In the 48 single-vehicle crashes, 60 occupants — 13 drivers and 47 passengers — were killed. In the 52 multiple-vehicle crashes, 18 drivers and 72 passengers died. In the 48 single-vehicle crashes, the first harmful events were as follows: striking a fixed object (28 crashes), a person falling from the vehicle (10 crashes), the vehicle overturning (6 crashes), the vehicle colliding with a train (2 crashes), and collision with object not fixed (1 crash).

In 42 percent of all crashes involving fatalities to occupants of a school bus or vehicle used as a school bus, the principal point of impact was the front of the vehicle.

Since 1987, 7 drivers and 47 passengers have died in school buses providing transportation *for purposes other than school or school-related activities (churches, civic organizations, etc.).* In one such multi-vehicle crash, 27 occupants, including the driver, died.

*"From 1987 to 1997, half of all schoolage pedestrians killed in school busrelated crashes were 5 to 7 years old."* 

Principal	Type of Crash								
Impact Point	Single-	Vehicle	Multiple	-Vehicle	Total				
on Bus	Crashes	ashes Fatalities Crashes Fatalities		Crashes	Fatalities				
Front	16	19	26	59	42	78			
Right Side	6	6	10	15	16	21			
Left Side	1	1	10	10	11	11			
Rear	3	9	5	5	8	14			
Тор	2	3	0	0	2	3			
Undercarriage	1	1	1	1	2	2			
Noncollision	18	20	0	0	18	20			
Unknown	Unknown 1		0	0	1	1			
Total	48	60	52	90	100	150			

## Table 2. Occupant Fatalities in School Bus-Related Crashes by Principal Impact Point on School Bus Vehicle, 1987-1997

*"Impacts to the front of the school bus occur in 42 percent of fatal school bus-related crashes."* 

## Table 3. School-Age Pedestrians Killed in School Bus-RelatedCrashes by Vehicle Maneuver, 1987-1997

	Striking Vehicle						
Vehicle Maneuver	School Bus	Vehicle Used as School Bus	Other Vehicle	Total			
Going Straight	61	9	56	126			
Slowing or Stopping in Traffic Lane	6	0	3	9			
Starting in Traffic Lane	66	1	1	68			
Passing or Overtaking Another Vehicle	0	0	11	11			
Leaving a Parked Position	7	7 1		8			
Maneuvering to Avoid an Animal, Pedestrian, Object, Other Vehicle, etc.	0 0		5	5			
Turning Right	11	0	0	11			
Turning Left	6	0	0	6			
Backing Up (Other Than for Parking)	4	0	0	4			
Negotiating a Curve	1	1 0		4			
Entering Parked Position	2	0	0	2			
Changing Lanes	0	0	1	1			
Other/Unknown	0 1		1	2			
Total School-Age Pedestrians Killed	164	12	81	257			

	School Bus Body-Type					Vehicle Used as School Bus				Total			
	Single-	Vehicle	e Multiple-Vehicle		Single-Vehicle M		Multiple-Vehicle		Single-Vehicle		Multiple-Vehicle		
Year	Crashes	Fatalities	Crashes	Fatalities	Crashes	Fatalities	Crashes	Fatalities	Crashes	Fatalities	Crashes	Fatalities	
1987	0	0	6	11	3	3	3	3	3	3	9	14	
1988	2	2	4	5	1	1	0	0	3	3	4	5	
1989	7	8	* 5	25	3	3	1	1	10	11	6	26	
1990	5	7	4	4	0	0	0	0	5	7	4	4	
1991	0	0	6	10	4	6	1	1	4	6	7	11	
1992	3	3	4	4	2	3	0	0	5	6	4	4	
1993	5	5	2	5	2	2	1	1	7	7	3	6	
1994	0	0	0	0	0	0	3	4	0	0	3	4	
1995	2	8	3	4	1	1	0	0	3	9	3	4	
1996	5	5	3	3	2	2	0	0	7	7	3	3	
1997	0	0	4	7	1	1	2	2	1	1	6	9	
Total	29	38	41	78	19	22	11	12	48	60	52	90	

#### Table 4. School Bus-Related Crashes Involving Occupant Fatalities, 1987-1997

\* Includes one crash with 21 occupant fatalities.

Note: Does not include occupants of other vehicles in school bus-related crashes.

	Occup	ants of Schoo	ol Bus*	F	Pedestrians			0	
Year	Driver	Passenger	Total	Struck by School Bus*	Struck by Other Vehicle	Total	Other Nonoccupants	Occupants of Other Vehicle	Total
1987	8	9	17	32	11	43	5	113	178
1988	2	6	8	19	17	36	6	80	130
1989	4	33	37	25	7	32	1	72	142
1990	4	7	11	32	7	39	1	64	115
1991	2	15	17	21	5	26	5	86	134
1992	1	9	10	21	8	29	2	83	124
1993	1	12	13	32	8	40	2	86	141
1994	2	2	4	28	9	37	2	64	107
1995	0	13	13	24	10	34	4	72	123
1996	2	8	10	16	7	23	2	101	136
1997	5	5	10	16	2	18	5	95	128
Total	31	119	150	266	91	357	35	916	1,458
Average	3	11	14	24	8	32	3	83	132

#### Table 5. Fatalities in School Bus-Related Crashes, 1987-1997

\* Includes school bus body type and vehicle used as school bus.

### For more information:

Information on school bus traffic fatalities is available from the National Center for Statistics and Analysis, NRD-31, 400 Seventh Street, S.W., Washington, D.C. 20590. Telephone inquiries should be addressed to Ms. Louann Hall at 1-800-934-8517. FAX messages should be sent to (202) 366-7078. General information on highway traffic safety can be accessed by Internet users at http://www.nhtsa.dot.gov/people/ncsa. To report a safety-related problem or to inquire about motor vehicle safety information, contact the Auto Safety Hotline at 1-800-424-9393.