DOT HS 809 095

U.S. Department of Transportation National Highway Traffic Safety Administration





"An average of 29 school-age children die in school busrelated traffic crashes each year — 9 school bus occupants and 21 pedestrians."

Traffic Safety Facts 1999

School Buses


A school bus-related crash is a crash which involves, either directly or indirectly, a school bus-type vehicle, or a vehicle functioning as a school bus, transporting children to or from school or school-related activities.

Since 1989 there have been about 411,000 fatal traffic crashes. Of those, 0.31 percent (1,291) were classified as school bus-related.

Since 1989, 1,445 people have died in school bus-related crashes — an average of 131 fatalities per year. Most of the people who lost their lives in those crashes (65 percent) were occupants of other vehicles involved. Nonoccupants (pedestrians, bicyclists, etc.) accounted for 25 percent of the deaths, and school bus occupants accounted for 10 percent (drivers 2 percent, passengers 8 percent).

Since 1989, 226 school-age pedestrians (less than 19 years old) have died in school bus-related crashes. Nearly two-thirds (66 percent) were killed by school buses, 5 percent by vehicles functioning as school buses, and 29 percent by other vehicles involved in the crashes. More than half of all school-age pedestrians killed in school bus-related crashes were between the ages of 5 and 7.

Figure 1. Occupant and Pedestrian Fatalities in School Bus-Related Crashes, by Age, 1989-1999



Note: Occupant fatalities shown are for occupants of school buses or vehicles used as school buses.

On average, 15 school-age pedestrians are killed by school buses (or vehicles used as school buses) each year, and 6 are killed by other vehicles involved in school bus-related crashes.

More school-age pedestrians are killed in the afternoon than in the morning, with 42 percent of the fatalities occurring in crashes between 3:00 and 4:00 PM.

Time of Day	Occupant Fatalities*	Pedestrians (School Age)	Total Fatalities		
12:00-6:59 AM	6	8	14		
7:00-7:59 AM	50	27	77		
8:00-8:59 AM	14	15	29		
9:00-9:59 AM	6	7	13		
10:00-10:59 AM	4	0	4		
11:00-11:59 AM	1	6	7		
12:00-12:59 PM	5	7	12		
1:00-1:59 PM	4	5	9		
2:00-2:59 PM	11	32	43		
3:00-3:59 PM	24	96	120		
4:00-4:59 PM	10	20	30		
5:00-11:59 PM	6	3	9		
Total	141	226	367		

Table 1. Fatalities in School Bus-Related Crashes by Time of Day, 1989-1999

*Does not include occupants of other vehicles in school bus-related crashes.

Between 1989 and 1999, 96 crashes occurred in which at least one occupant of a school bus or a vehicle functioning as a school bus died. More than half of those crashes (53 percent) involved another vehicle. In the 45 single-vehicle crashes, 58 occupants — 10 drivers and 48 passengers — were killed. In the 51 multiple-vehicle crashes, 20 drivers and 63 passengers died. In the 45 single-vehicle crashes, the first harmful events were as follows: striking a fixed object (25 crashes), a person falling from the vehicle (10 crashes), the vehicle overturning (5 crashes), the vehicle colliding with a train (3 crashes), and collision with object not fixed (1 crash).

In 41 percent of all crashes involving fatalities to occupants of a school bus or vehicle used as a school bus, the principal point of impact was the front of the vehicle.

Since 1989, 5 drivers and 16 passengers have died in school buses providing transportation *for purposes other than school or school-related activities (churches, civic organizations, etc.).* In 1987, one such multi-vehicle crash resulted in the deaths of 27 occupants, including the driver.

"From 1989 to 1999, more than half of all school-age pedestrians killed in school bus-related crashes were 5 to 7 years old."

	Type of Crash								
Principal	Single-	Vehicle	Multiple	-Vehicle	Total				
Impact Point on Bus	Crashes Fatalities		Crashes	Fatalities	Crashes	Fatalities			
Front	14	17	25	52	39	69			
Right Side	6	6	11	16	17	22			
Left Side	2	3	11	11	13	14			
Rear	4	10	3	3	7	13			
Тор	2	3	0	0	2	3			
Undercarriage	1	1	1	1	2	2			
Noncollision	16	18	0	0	16	18			
Total	45	58	51	83	96	141			

Table 2. Occupant Fatalities in School Bus-Related Crashes by Principal Impact Point on School Bus Vehicle, 1989-1999

"Impacts to the front of the school bus occur in 41 percent of fatal school bus-related crashes."

Table 3. School-Age Pedestrians Killed in School Bus-Related
Crashes by Vehicle Maneuver, 1989-1999

Vehicle Maneuver	School Bus	Vehicle Used as School Bus	Other Vehicle	Total
Going Straight	61	7	45	113
Slowing or Stopping in Traffic Lane	7	0	3	10
Starting in Traffic Lane	56	2	1	59
Passing or Overtaking Another Vehicle	0	0	8	8
Leaving a Parked Position	5	1	0	6
Maneuvering to Avoid an Animal, Pedestrian, Object, Other Vehicle, etc.	0	0	4	4
Turning Right	9	0	0	9
Turning Left	5	0	0	5
Backing Up (Other Than for Parking)	2	0	0	2
Negotiating a Curve	2	0	3	5
Entering Parked Position	2	0	0	2
Changing Lanes	0	0	1	1
Other/Unknown	0	1	1	2
Total School-Age Pedestrians Killed	149	11	66	226

	School Bus Body Type			Vehicle Used as School Bus				Total				
	Single-	Vehicle	Multiple	-Vehicle	Single-Vehicle		Multiple-Vehicle		Single-Vehicle		Multiple-Vehicle	
Year	Crashes	Fatalities	Crashes	Fatalities	Crashes	Fatalities	Crashes	Fatalities	Crashes	Fatalities	Crashes	Fatalities
1989	7	8	5	25	3	3	1	1	10	11	6	26
1990	5	7	4	4	0	0	0	0	5	7	4	4
1991	0	0	6	10	4	6	1	1	4	6	7	11
1992	3	3	4	4	2	3	0	0	5	6	4	4
1993	5	5	2	5	2	2	1	1	7	7	3	6
1994	0	0	0	0	0	0	3	4	0	0	3	4
1995	2	8	3	4	1	1	0	0	3	9	3	4
1996	5	5	3	3	2	2	0	0	7	7	3	3
1997	0	0	5	8	1	1	1	1	1	1	6	9
1998	1	2	4	4	0	0	0	0	1	2	4	4
1999	2	2	6	6	0	0	2	2	2	2	8	8
Total	30	40	42	73	15	18	9	10	45	58	51	83

Table 4. School Bus-Related Crashes Involving Occupant Fatalities, 1989-1999

*Includes one crash with 21 occupant fatalities.

Note: Does not include occupants of other vehicles in school bus-related crashes.

Table 5. Fatalities in School Bus-Related Crashes, 1989-1999

	Оссира	ints of School B	us*	Pedestrians					
Year	Driver	Passenger	Total	Struck by School Bus*	Struck by Other Vehicle	Total	Other Nonoccupants	Occupants of Other Vehicle	Total
1989	4	33	37	25	7	32	1	72	142
1990	4	7	11	32	7	39	1	64	115
1991	2	15	17	21	5	26	5	86	134
1992	1	9	10	21	8	29	2	83	124
1993	1	12	13	32	8	40	2	86	141
1994	2	2	4	28	9	37	2	64	107
1995	0	13	13	24	10	34	4	72	123
1996	2	8	10	16	7	23	2	101	136
1997	5	5	10	17	2	19	5	97	131
1998	3	3	6	21	3	24	7	91	128
1999	6	4	10	19	6	25	3	126	164
Total	30	111	141	256	72	328	34	942	1,445
Average	3	10	13	23	7	30	3	86	131

*Includes school bus body type and vehicle used as school bus.

For more information:

Information on school bus traffic fatalities is available from the National Center for Statistics and Analysis, NRD-31, 400 Seventh Street, S.W., Washington, D.C. 20590. NCSA information can also be obtained by telephone or by fax-on-demand at 1-800-934-8517. FAX messages should be sent to (202) 366-7078. General information on highway traffic safety can be accessed by Internet users at http://www.nhtsa.dot.gov/people/ncsa. To report a safety-related problem or to inquire about motor vehicle safety information, contact the Auto Safety Hotline at 1-800-424-9393.