


































	Calling Serving RFSS	Calling Home RFSS	Called Home RFSS	Called Serving RFSS	Number of ISSI interfaces
1					3
Here there are four RFSSs each with only one function.					
2					2
Here one RFSS is functioning both as a calling serving RFSS and a called serving RFSS. Both the calling SU and the called SU are currently located in one RFSS, but their homes are in different RFSSs, each with only one function.					
3					2
Here one RFSS is functioning both as a calling home RFSS and a called home RFSS. Both the calling SU and the called SU are in different serving RFSSs, but they share the same home RFSS.					
4					1
Here one RFSS is functioning both as a calling serving RFSS and a called serving RFSS and another is functioning both as a calling home RFSS and a called home RFSS. Both the calling SU and the called SU are currently located in one RFSS, and both their homes are in the same RFSS.					

	Calling Serving RFSS	Calling Home RFSS	Called Home RFSS	Called Serving RFSS	Number of ISSI interfaces
5					2
Here one RFSS is functioning both as a calling serving RFSS and a calling home RFSS. The calling SU is located in its home RFSS.					
9					2
Here one RFSS is functioning both as a called home RFSS and a called serving RFSS. The called SU is located in its home RFSS.					
13					1
Here one RFSS is functioning both as a calling serving RFSS and a calling home RFSS and another RFSS is functioning both as a called home RFSS and a called serving RFSS. The calling SU is located in its home RFSS and the called SU is located in its home RFSS.					
17					2
Here one RFSS is functioning both as a calling serving RFSS and a called home RFSS. The calling SU is located in the home RFSS of the called SU.					


	Calling Serving RFSS	Calling Home RFSS	Called Home RFSS	Called Serving RFSS	Number of ISSI interfaces
23					1
<p>Here one RFSS is functioning as a calling serving RFSS, a calling home RFSS, and a called home RFSS. The calling SU is located in its home RFSS, which is also the home RFSS of the called SU.</p>					
26					1
<p>Here one RFSS is functioning as a calling serving RFSS, a called home RFSS, and a called serving RFSS. The calling SU and the called SU are both located in the called home RFSS.</p>					
33					2
<p>Here one RFSS is functioning both as a calling home RFSS and a called serving RFSS. The called SU is located in the home RFSS of the calling SU.</p>					
38					1
<p>Here one RFSS is functioning as a calling serving RFSS, a calling home RFSS, and a called serving RFSS. Both the calling SU and the called SU are located in calling home RFSS.</p>					

Calling Serving RFSS	Calling Home RFSS	Called Home RFSS	Called Serving RFSS	Number of ISSI interfaces
----------------------	-------------------	------------------	---------------------	---------------------------



Here one RFSS is functioning as a calling home RFSS, a called home RFSS, and a called serving RFSS.  
The called SU is located in its home RFSS, which is also the home RFSS for the calling SU.

1



Here one RFSS is functioning as a calling home RFSS and a called serving RFSS and another RFSS is functioning as a calling serving RFSS and a called home RFSS.  
The calling SU and the called SU are located in the other SU's home RFSS.

1



Here one RFSS has all four functions.  
The calling SU and called SU are both in their home RFSS.  
NOTE: In this case there is no ISSI, therefore all happens internally to the single RFSS.

0

Legend / Key							
Calling Serving RFSS		Calling Home RFSS		Called Home RFSS		Called Serving RFSS	