APPENDIX E

PART 572, SUBPART R (12-MONTH-OLD) DUMMY PERFORMANCE CALIBRATION TEST PROCEDURE

APPENDIX E

PART 572, SUBPART R DUMMY PERFORMANCE CALIBRATION TEST PROCEDURE

TABLE OF CONTENTS

PURPOSE A	AND APPLICATION	E-1
GENERAL F	REQUIREMENTS	E-1
SECURITY		E-1
GOOD HOU	SEKEEPING	E-2
TEST SCHE	DULING AND MONITORING	E-2
TEST DATA	DISPOSITION	E-2
GOVERNME	ENT FURNISHED PROPERTY (GFP)	E-2
CALIBRATIO	ON AND TEST INSTRUMENTATION	E-5
PHOTOGRA	NPHY	E-6
DEFINITION	IS	E-6
PRETEST R	EQUIREMENTS	E-6
11.1 11.2 11.3 11.4	TRANSDUCER REQUIREMENTSOTHER TRANSDUCER CONDITIONSTHORAX IMPACTOR PROBEGENERAL TEST CONDITIONS	E-7
CALIBRATIO	ON TEST EXECUTION	E-11
POST TEST	REQUIREMENTS	E-11
REPORTS		E-11
14.1 14.2	APPARENT TEST FAILUREFINAL PERFORMANCE CALIBRATION REPORTS	
E1 E2 E3 E4 E5 E6 E7	DUMMY DAMAGE CHECKLIST EXTERNAL MEASUREMENTS FRONTAL HEAD DROP TEST REAR HEAD DROP TEST NECK FLEXION TEST NECK EXTENSION TEST THORAX IMPACT TEST	E-14 E-16 E-21 E-27 E-29 E-34
	GENERAL F SECURITY GOOD HOU TEST SCHE TEST DATA GOVERNME CALIBRATIO PHOTOGRA DEFINITION PRETEST R 11.1 11.2 11.3 11.4 CALIBRATIO POST TEST REPORTS 14.1 14.2 DATA SHEE E1 E2 E3 E4 E5 E6	11.2 OTHER TRANSDUCER CONDITIONS 11.3 THORAX IMPACTOR PROBE 11.4 GENERAL TEST CONDITIONS. CALIBRATION TEST EXECUTION. POST TEST REQUIREMENTS. REPORTS 14.1 APPARENT TEST FAILURE. 14.2 FINAL PERFORMANCE CALIBRATION REPORTS DATA SHEETS. E1 DUMMY DAMAGE CHECKLIST. E2 EXTERNAL MEASUREMENTS. E3 FRONTAL HEAD DROP TEST. E4 REAR HEAD DROP TEST. E5 NECK FLEXION TEST. E6 NECK EXTENSION TEST. E6 NECK EXTENSION TEST. E7 THORAX IMPACT TEST.

FIGURES

1E	DUMMY HANGER PLATE	PAGE F3
2E	DUMMY HANGER	_
3E	SIGN CONVENTION	E-9
4E	EXTERNAL DIMENSIONS	E-20
5E	FRONTAL HEAD DROP TEST SET-UP SPECIFICATIONS	E-23
6E	REAR HEAD DROP TEST SET-UP SPECIFICATIONS	E-26
7E	NECK PENDULUM SPECIFICATIONS	
8E	NECK FLEXION TEST SETUP SPECIFICATIONS	E-32
9E	NECK EXTENSION TEST SETUP SPECIFICATIONS	E-33
10E	THORAX IMPACT TEST SETUP SPECIFICATIONS	E-36
	TABLES	
1F	SIGN CONVENTION FOR HYBRID III TRANSDUCER OUTPUTS	F-10

1. PURPOSE AND APPLICATION

The purpose of this laboratory procedure is to provide dummy users (independent testing laboratories under contract with the Office of Vehicle Safety Compliance) with standard test procedures for performing receiving-inspection and performance calibration tests on the Part 572, Subpart R dummy so that repetitive and correlative test results can be obtained. The following tests have been developed to establish a uniform calibration procedure for all users as the means of verifying the performance of the dummy.

- A. EXTERNAL DIMENSIONS (PADI)
- B. HEAD DROP TEST (572.152)
- C. NECK FLEXION TEST (572.153(b)(1))
- D. NECK EXTENSION TEST 572.153(b)(2)
- E. THORAX IMPACT TEST ((572.154)

National Highway Traffic Safety Administration (NHTSA) contract laboratories performing FMVSS 213 testing for the Office of Vehicle Safety Compliance (OVSC) must use this laboratory procedure for the calibration of Part 572, Subpart R dummies.

2. GENERAL REQUIREMENTS

The Code of Federal Regulations (49CFR), Parts 571 and 572, was amended to adopt the Hybrid III, CRABI 12-Month-Old Dummy as the means of determining a Child Restraint System's (CRS's) conformance to the performance requirements of FMVSS 213. Each Part 572, Subpart R dummy used in a compliance test must meet the specifications and performance criteria of Part 572 before and after each CRS test in order to be an acceptable compliance test tool.

The Part 572, Subpart R Hybrid III, CRABI 12-Month-Old Dummy consists of components and assemblies specified in the drawing and specifications package which is available from Reprographics Technologies, 9000 Virginia Manor, Beltsville, MD 20705, telephone - (301) 419-5070.

3. SECURITY

All NHTSA Part 572, Subpart R test dummies delivered to the contract laboratory as Government Furnished Property (GFP) will be stored in a safe and secure area such as the dummy calibration laboratory. The contractor is financially responsible for any acts of theft and/or vandalism that occur during the storage of GFP. Any security problems shall be reported by telephone to the Industrial Property Manager (IPM), Office of Contracts and Procurement, within two working days after the incident. A letter containing specific details of the security problem will be sent to the IPM (with copy to the COTR) within 48 hours.

The contractor is responsible for maintaining the NHTSA test dummies in good working order, and shall protect and segregate the data that evolves from conducting Part 572, Subpart R dummy calibration tests before and after each CRS test.

No Information concerning the Part 572, Subpart R dummy calibration data shall be released to anyone except the COTR, unless specifically authorized by the COTR or the COTR's Branch or Division Chief.

NOTE: No Individuals, other than contractor personnel directly involved in the dummy calibration test program, shall be allowed to witness dummy calibration tests unless specifically authorized by the COTR.

4. GOOD HOUSEKEEPING

Contractors shall maintain the entire dummy calibration laboratory, test fixtures, and instrumentation in a neat, clean, and painted condition with test instruments arranged in an orderly manner consistent with good test laboratory housekeeping practices.

5. TEST SCHEDULING AND MONITORING

The Part 572, Subpart R dummies are being calibrated as test tools to be used in determining CRS compliance with the requirements of FMVSS 213. The schedule for these performance calibration tests must be correlated with that of the CRS tests. All testing shall be coordinated to allow monitoring by the COTR.

6. TEST DATA DISPOSITION

The contractor shall make all dummy calibration data available to the COTR for review and analysis as required. All calibration test data for each particular Part 572, Subpart R dummy will be sent to the COTR with each test report.

All backup data sheets, strip charts, recordings, plots, technicians notes, etc. shall be either sent to the COTR or destroyed at the conclusion of each delivery order, purchase order, etc.

7. GOVERNMENT FURNISHED PROPERTY (GFP)

Part 572, Subpart R test dummies will be furnished to the contract laboratory by the OVSC. The dummies shall be stored in a hanging position using the bracket and positioning shown in Figures 1E and 2E.




FIGURE 1E




FIGURE 2E

These dummies shall be stored in a secured room that is kept between 55°F and 85°F. The contractor will check dummy components for damage after each low risk deployment test and complete a dummy damage checklist that will be included with the posttest dummy calibration. The COTR will be kept informed of the dummies condition in order that replacement parts can be provided.

8. CALIBRATION AND TEST INSTRUMENTATION

Before the contractor initiates the dummy performance calibration test program, a test instrumentation calibration system must be implemented and maintained in accordance with established calibration practices. The calibration system shall be set up and maintained as follows:

- A. Standards for calibrating the measuring and test equipment shall be stored and used under appropriate environmental conditions to assure their accuracy and stability.
- B. All measuring instruments and standards shall be calibrated by the contractor, or a commercial facility, against a higher order standard at periodic intervals not exceeding 6 months for instruments and 12 months for calibration standards. Records, showing the calibration traceability to the National Institute of Standards and Technology (NIST), shall be maintained for all measuring and test equipment.
- C. All measuring and test equipment and measuring standards shall be labeled with the following information:
 - (1) Date of calibration
 - (2) Date of next scheduled calibration
 - (3) Name of the technician who calibrated the equipment
- D. The contractor shall provide a written calibration procedure that includes, as a minimum, the following information for all measurement and test equipment:
 - (1) Type of equipment, manufacturer, model number, etc.
 - (2) Measurement range
 - (3) Accuracy
 - (4) Calibration interval

- (5) Type of standard used to calibrate the equipment (calibration traceability of the standard must be evident)
- (6) The actual procedures and forms used to perform calibrations.
- E. The contractor shall keep records of calibrations for all test instrumentation in a manner that assures the maintenance of established calibration schedules. All such records shall be readily available for inspection when requested by the COTR. The calibration system will need the written acceptance of the COTR before testing begins.
- F. Test equipment shall receive a calibration check immediately prior to and after each test. This check shall be recorded by the test technician(s) and submitted with the final report.

9. RESERVED

10. DEFINITIONS

PADI: Procedures for Assembly, Disassembly, and Inspection

11. PRETEST REQUIREMENTS

11.1 TRANSDUCER REQUIREMENTS

The contractor shall provide and install the following instrumentation to the GFP dummies (excluding the chest deflection transducer).

A. HEAD – The head accelerometers shall have dimensions, response characteristics and sensitive mass locations specified in drawing SA572-S4 and be mounted in the head as shown in drawing 921022-000. (572.155(b))

Three accelerometers shall be mounted in the head cavity to measure orthogonal accelerations (Ax, Ay, Az) at the center of gravity (CG) of the head assembly.

- B. NECK The neck force-moment transducer shall have the dimensions, response characteristics, and sensitive axis locations specified in drawing SA572-S23 and shall be mounted as shown in drawing 921022-000. (572.155(c))
- C. CHEST The chest accelerometers shall have the dimensions, response characteristics, and sensitive mass locations specified in drawing

SA572-S4 and be mounted in the torso assembly in traxial configuration at the T4 location as shown drawing 921022-000. The chest accelerometers are not required for dummy calibration testing but are required for FMVSS 213 CRS testing. (572.155(e))

D. TEST FIXTURE – The neck pendulum, and thorax accelerometers shall have the dimensions and characteristics of drawing SA572-S4.

11.2 OTHER TRANSDUCER CONDITIONS

- A. TRANSDUCER MOUNTS The mountings for sensing devices shall have no resonance frequency less than 3 times the frequency range of the applicable channel class. (572.155(k))
- B. TRANSDUCER SIGN CONVENTION The sign convention for outputs of transducers mounted within the dummy that measure head and chest accelerations, chest deflection and neck loads are located in Figure 3E and Table 1E. For other transducers see SAE J1733DEC94. (572.155(j))
- C. TRANSDUCER OUTPUTS and FILTERING- The outputs of acceleration and force-sensing devices installed in the dummy and in the test apparatus specified by this part are recorded with individual data channels. Each data channel will be comprised of a sensor, signal conditioner, data acquisition device, and all interconnecting cables, and must conform to the requirements of SAE Recommended Practice J211/1 MAR95, "Instrumentation for Impact Test," with channel classes as follows: (572.155(i))

(1) Head acceleration	Class 1000	(572.155(i)(1))
(2) Neck force	Class 1000	(572.155(i)(2)(i))
(3) Neck moment	Class 600	(572.155(i)(2)(ii))
(4) Neck pendulum acceleration	Class 180	(572.155(i)(2)(iii))
(5) Neck rotation transducers	Class 60	(572.155(i)(2)(iv))
(6) Thorax spine acceleration	Class 180	(572.155(i)(3)(i))
(7) Thorax pendulum	Class 180	(572.155(i)(3)(i))
acceleration		(/(/(//

All filter classes should be of the "phaseless" type to be compatible with the "time" dependent test parameters.

11.3 THORAX IMPACTOR PROBE (572.155(a))

- A. The test probe for thoracic impacts shall be of rigid metallic construction, concentric about its longitudinal axis.
- B. It shall have a mass of 2.86 ± 0.02 kg (6.3 ± 0.05 lbs). 1/3 of the weight of the suspension cables and any attachments to the impact probe must be

- included in the calculation of mass, and such components may not exceed 5 percent of the total weight of the test probe.
- C. It shall have a minimum mass moment of inertia of 164 kg-cm² (0.145 lbs-in-sec²) in yaw and pitch about the center of gravity.
- D. The impacting end of the probe is perpendicular to and concentric with the longitudinal axis. The face has a diameter of 101.6 ± 0.25 mm (4.00 ± 0.01 in), a maximum edge radius of 7.6 to 12.7 mm (0.3 to 0.5 in) and is flat, continuous and non-deformable.
- E. A 101-103 mm diameter cylinder surface extends at least 12.5 mm to the rear of the impact face.
- F. The probe's end opposite to the impact face must have provisions for mounting of an accelerometer with its sensitive axis collinear with the longitudinal axis of the probe.
- G. The impact probe shall have a free air resonant frequency of not less than 1000 Hz measured in line with the longitudinal axis of the impactor.

SIGN CONVENTION FOR PART 572 TEST DUMMIES




TABLE 1E

SIGN CONVENTION	FOR HYBRID III TRANSDUCER OUTPUTS
BODY SEGMENT — MEASURED FORCE	POSITIVE OUTPUT DIRECTION
NECK FX SHEAR FY SHEAR FZ AXIAL	HEAD REARWARD OR CHEST FORWARD HEAD LEFTWARD, CHEST RIGHTWARD HEAD UPWARD, CHEST DOWNWARD
MX MOMENT (ROLL) MY MOMENT (PITCH) MZ MOMENT (YAW)	LEFT EAR TOWARD LEFT SHOULDER CHIN TOWARD STERNUM CHIN TOWARD LEFT SHOULDER
LEFT SHOULDER FX FZ	LEFT ARM/SHOULDER FORWARD, CHEST REARWARD LEFT ARM/SHOULDER DOWNWARD, CHEST
RIGHT SHOULDER	UPWARD
FX FZ	RIGHT ARM/SHOULDER FORWARD, CHEST REARWARD RIGHT ARM/SHOULDER DOWNWARD, CHEST UPWARD
LUMBAR SPINE FX FY FZ MX MOMENT MY MOMENT MZ MOMENT	CHEST REARWARD, PELVIS FORWARD CHEST LEFTWARD, PELVIS RIGHTWARD CHEST UPWARD, PELVIS DOWNWARD LEFT SHOULDER TOWARD LEFT HIP STERNUM TOWARD FRONT OF LEGS RIGHT SHOULDER FORWARD, LEFT SHOULDER REARWARD
PUBIC FX SHEAR FZ AXIAL	PUBIC REARWARD, CHEST FORWARD PUBIC UPWARD, CHEST DOWNWARD

NOTE: DIRECTIONS ARE DEFINED IN RELATION TO A SEATED DUMMY

11.4 GENERAL TEST CONDITIONS

- A. Surfaces of dummy components are not painted unless otherwise specified. (572.155(n))
- B. Dummy performance tests of the same component, segment, assembly, or fully assembled dummy are separated in time by a period of not less than 30 minutes unless otherwise specified. (572.155(m))
- C. The dummy head performance tests are conducted at any temperature from 18.9°C (66°F) to 25.6°C (78°F) and at any relative humidity from 10% to 70% after exposure of the dummy to these conditions for a period of not less than 4 hours. For the neck-headform assembly and thorax assembly, the temperature range is 20.6°C (69°F) to 22.2°C (72°F) and at any relative humidity from 10% to 70% after exposure of the dummy to these conditions for a period of not less than 4 hours.
- D. Dummy limb joints are set at 1 G, barely restraining the weight of the limb when it is extended horizontally. The force required to move a limb segment does not exceed 2 Gs throughout the range of limb motion. (572.155(I))
- E. Dummies will be clothed for the thorax calibration tests with a form fitting cotton-polyester-based tight-fitting sweat shirt with long sleeves and ankle length pants. The total weight of the shirt and pants shall not exceed 0.25 kg (0.55 lb). (572.154(c)(2))

12. CALIBRATION TEST EXECUTION

Complete the Data Sheets in section 15.

13. POST TEST REQUIREMENTS

The contractor shall verify all instrumentation and check data sheets and photographs. Make sure data is recorded in all data blocks on every performance calibration test data sheet.

14. REPORTS

14.1 APPARENT NONCONFORMANCE

During the posttest calibration verification, any indication of apparent nonconformance to the requirements of Regulation P572 shall be communicated by telephone to the COTR within 24 hours with written notification mailed within 48 hours (Saturdays and Sundays excluded). Written notification shall be

submitted with a copy of the particular test data sheet(s) and preliminary data plot(s).

In the event of an apparent nonconformance, a posttest calibration check of some critically sensitive test equipment and instrumentation may be required for verification of accuracy. The necessity for the calibration shall be at the COTR's discretion and shall be performed without additional costs to the OVSC.

14.2 FINAL PERFORMANCE CALIBRATION REPORTS

14.2.1 COPIES

A report containing the pre-test calibration and post test calibration verification data for each Part 572, Subpart R dummy used in the CRS testing shall be submitted with FMVSS 213 final test reports.

Contractors are required to PROOF READ all Final Test Reports before submittal to the COTR. The OVSC will not act as a report quality control office for contractors. Reports containing a significant number of errors will be returned to the contractor for correction, and a "hold" will be placed on invoice payment for the particular test.

14.2.2 REQUIREMENTS

Performance calibration report Table of Contents shall include the following:

- A. Section 1 Purpose of Calibration Test
- B. Section 2 Calibration Data Summary
- C. Section 3 Test Data
- D. Section 4 Test Equipment List and Calibration Information
- E. Section 5 Photographs (if applicable)

The test data for each dummy will be presented in separate sections. Each section shall contain a title page, test results summary and the test data. The title page shall include the dummy's serial number and the manufacturer's name. It will also indicate whether the calibration data is pre or posttest. The test results sheets will provide a summary of each test and describe any damage, failures and/or corrective action taken. The test data shall include the pass/fail data sheets, the time histories for each data channel used to determine the pass or fail status, and instrumentation calibration data sheets.

14.2.3 FIRST PAGE

FRONT COVER

A heavy paperback cover (or transparency) shall be provided for the protection of the final report. The information required on the cover is as follows:

A. Final Report Title And Subtitle such as

DUMMY PERFORMANCE CALIBRATION
IN SUPPORT OF
CHILD RESTRAINT SYSTEM
DYNAMIC TESTS
FMVSS No. 213

B. Contractor's Name and Address such as

ABC TESTING LABORATORIES, INC. 405 Main Street Detroit, Michigan 48070

NOTE: DOT SYMBOL WILL BE PLACED BETWEEN ITEMS B AND C

- C. Date of Final Performance Calibration Report completion
- D. The sponsoring agency's name and address as follows

U. S. DEPARTMENT OF TRANSPORTATION
National Highway Traffic Safety Administration
Enforcement
Office of Vehicle Safety Compliance
400 Seventh Street, SW
Room 6115 (NVS-222)
Washington, DC 20590

15. Data Sheets

DATA SHEET E1DUMMY DAMAGE CHECKLIST

Dummy Serial Number	Test Date
Technician	-
This check sheet is completed as part of the p	posttest calibration verification.
Indicate NA in the OK column for any compor	nents not applicable to this size dummy.
Perform general cleaning.	

Divino non il Hores	I be a section	Comments	Damagas	OK
Dummy Item	Inspect for	Comments	Damaged	OK
Outer skin	Gashes, rips, cracks			
Head	Ballast secure			
	General appearance			
Neck	Broken or cracked			
	rubber			
	Upper neck bracket			
	firmly attached to			
	the lower neck			
	bracket			
	Looseness at the			
	condyle joint			
	Nodding blocks			
	cracked or out of			
	position			
Spine	Broken or cracks in			
	rubber.			
Ribs	Broken or bent ribs			
	Broken or bent rib			
	supports			
	Damping material			
	separated or			
	cracked			
	Rubber bumpers in			
	place			
Chest	Bent shaft			
Displacement				
Assembly				
•	Slider arm riding in			
	track			
Transducer	Torn cables			
leads				

Dummy Item	Inspect for	Comments	Damaged	OK
Accelerometer	Head mounting			
Mountings	secure			
	Chest mounting			
	secure			
Knees	Skin condition			
	Insert (do not			
	remove)			
	Casting			
Limbs	Normal movement			
	and adjustment			
Knee Sliders	Wires intact			
	Rubber returned to			
	"at rest" position			
Pelvis	Broken			
Other				
endineer or		n is to be consulted for a decision or	repair or	
replacemen	it of parts. eplacement approved l	by:		
replacemen		by: Date		
replacemen Repair or R Signature		Date		
replacemen Repair or R Signature	eplacement approved l	Date		
replacemen Repair or R Signature	eplacement approved l	Date		
replacemen Repair or R Signature	eplacement approved l	Date		
Repair or R Signature Describe th	eplacement approved l	Date		
replacemen Repair or R Signature	eplacement approved l	Date		

Date

Signature

DATA SHEET E2EXTERNAL MEASUREMENTS


Dumm	ny Serial Number	Test Date
Techn	ician	
	test calibration It test calibration verification	
123456789.	seating surface is at least 406 with a vertical section at least attached to the rear of the seavertical and centered on the test secure the dummy to the test tangent to the rear vertical sur Push the dummy's forehead reagainst the seat back surface. Place the centerlines of the up Place the centerlines of the lo Position the upper legs so that Position the lower legs so that bottom of the foot is horizontal Record the dimensions listed (reference figure 4E). Place the dummy in supine pot that is perpendicular to the talk Position the blocks perpendicular.	fixture so that the upper torso and buttocks are face of the fixture (as tangent as possible). earward and secure the head (at the forehead) oper arms vertical. wer arms horizontal. It they are parallel to one another. It they are perpendicular to the upper legs and the limit following table, except for dimension Q operations on the measurement surface. Place a block one of the dummy. It is said to the midsaggital plane of the dummy. It is in contact with the head and the heels of the
Signat	ture	Date

EXTERNAL DIMENSIONS

HYBRID III, PA	RT 572, SUBPART O EXTERNA	AL DIMENSIONS		
DIMENSION	DESCRIPTION	DETAILS	ASSEMBLY DIMENSION (mm)	ACTUAL MEASUREMENT
А	TOTAL SITTING HEIGHT	Seat surface to highest point on top of the head with head pulled back to touch vertical surface of fixture.	456-471.2	
В	SHOULDER PIVOT HEIGHT	Centerline of shoulder pivot bolt to the seat surface.	276.6-291.8	
С	HIP PIVOT HEIGHT	Centerline of hip pivot bolt to seat surface	27.9-38.1	
D	HIP PIVOT FROM BACKLINE	Centerline of hip pivot bolt to vertical surface of seat	40.1-50.3	
E	SHOULDER PIVOT FROM BACKLINE	Center of the shoulder pivot bolt to the fixture's rear vertical surface.	50.3-60.5	
F	THIGH CLEARANCE	Fixture's seat surface to highest point on the upper femur segment	63.0-73.2	
G	ELBOW PIVOT TO FINGERTIP	Elbow pivot to the finger tip, in line with the elbow and wrist centerlines	176.6-191.8	
I	SHOULDER PIVOT TO- ELBOW PIVOT	Shoulder pivot bolt to elbow pivot bolt	99.1-114.3	
J	ELBOW REST HEIGHT	Seat surface to bottom of lower arm	150.1-165.3	
К	BUTTOCK TO KNEE LENGTH	The forward most part of the knee flesh to the fixture's rear vertical surface	202.7-217.9	
L	POPLITEAL HEIGHT	Seat surface to the horizontal plane of the bottom of the feet.	138.7-153.9	
М	KNEE PIVOT HEIGHT	Centerline of knee pivot bolt to the horizontal plane of the bottom of the feet.	165.1-180.3	
N	BUTTOCK POPLITEAL LENGTH	The rearmost surface of the lower leg to the same point on the rear surface of buttocks used for dimension K	144.8-160	

HYBRID III, SU	JBPART R EXTERNAL DIMENSI	ONS, continued		
DIMENSION	DESCRIPTION	DETAILS	ASSEMBLY DIMENSION (mm)	ACTUAL MEASUREMENT
0	CHEST DEPTH WITH JACKET	Measured 261.6 ± 5.1 mm above seat surface	107.5-122.7	
Р	FOOT LENGTH	Tip of toe to rear of heal	92.4-102.6	
Q	STATURE	Place the dummy in supine position on the measurement surface. Place a block that is perpendicular to the table at both the head and feet of the dummy. Position the blocks perpendicular to the midsaggital plane of the dummy. Position the blocks so they are in contact with the head and the heels of the dummy. Measure the distance between the blocks.	727.7-753.1	N/A
R	BUTTOCK TO KNEE PIVOT LENGTH	Knee pivot bolt to the fixture's rear vertical surface.	178.5-188.7	
S	HEAD BREADTH	Distance across the head at its widest point	124.4-134.6	
Т	HEAD DEPTH	Distance from the forward most surface of the head to the rearmost surface of the head, in line with the midsgittal plane.	149.9-165.1	
U	HIP BREADTH	Distance across the width of the hip at the widest point of the jacket	158.5-173.7	
V	SHOULDER BREADTH	Distance between the outside edges of the shoulder flesh, in line with the shoulder pivot bolts	200.7-215.9	
W	FOOT BREADTH	The widest part of the foot	39.1-49.3	
Υ	CHEST CIRCUMFERENCE WITH JACKET	Distance around chest at reference location AA, with jacket on. Measured 261.6 ± 5.1 mm above the seat surface.	452.4-477.8	
Z	WAIST CIRCUMFERENCE	Distance around waist at reference location BB, with jacket on. Measured 111.8 ± 5.1 mm above the seat surface.	447-472.4	
AA	REFERENCE LOCATION FOR DIMENSION Y & O	Reference: 261.6 ± 5.1 mm above the seat surface	256.5-266.7	

HYBRID III, SU	BPART R EXTERNAL DIMENSI	ONS, continued		
DIMENSION	DESCRIPTION	DETAILS	ASSEMBLY DIMENSION (mm)	ACTUAL MEASUREMENT
ВВ	REFERENCE LOCATION FOR DIMENSION Z	Reference: 111.8 ± 5.1 mm above seat surface	106.7-116.9	
CC	SHOULDER HEIGHT	Top of arm to seat surface	299.7-314.9	
DD	CHIN HEIGHT	Bottom of chin to seat surface	289.6-304.8	



EXTERNAL DIMENSIONS

FIGURE 4E


DATA SHEET E3

FRONTAL HEAD DROP TEST (572.152)

Dumn	ny Serial Number Test Date
Techn	iician
	test calibration st test calibration verification
Test a	attempt no (when successive head drops are necessary)
1.	It has been at least 2 hours since the last frontal head drop and at least 30 minutes since the last rear head drop. (572.152(c)(5))
2.	N/A, ONLY one head drop performed The head assembly consists of the head (921022-001), triaxial accelerometer mounting block (SA572-S80), and three (3) accelerometers (SA572-S4). (572.152(a))
3. 4.	Accelerometers and their respective mounts are smooth and clean. The data acquisition system, including transducers, conforms to the requirements of SAE Recommended Practice J211/1 MAR95. (572.155(i))
5.	The head assembly soaked at a temperature between 18.9°C (66°F) and 25.6°C (78°F) and at a relative humidity from 10% to 70% for a period of at least four (4) hours prior to a test. (572.152(c)(1)) Record the maximum temperature Record the minimum temperature Record the maximum humidity Record the minimum humidity
6.	Visually inspect the head skin for cracks, cuts, abrasions, etc. Repair or replace the head if the damaged area is more than superficial. Note: If the damage resulted from the CRS test in which the dummy was an occupant, the damaged area is to be documented with photography and the post test calibration verification testing completed before any replacement or repairs are made. Record findings and actions:
7.	Clean the impact surface of the skin and the impact surface of the fixture with isopropyl alcohol, trichloroethane or equivalent prior to the test (572, 152(c)(2))

Signa	ture	Date			
15.	Plots of the x, y, z, and resultant accel	eration data follow this sheet.			
	Lateral acceleration	y-axis acceleration ≤ ±15 g			
		resultant acceleration			
	Resultant versus time history curve Oscillations after the main pulse	Unimodal Less than 17% of the peak			
	Peak resultant acceleration	100 g ≤ x ≤ 120 g			
	Parameter	Specification	Result		
14.	Complete the following table: (572.152	.(D)).			
1.1	surface. (572.152(b) & (572.152(c)(4)) Complete the following table. (572.152				
	0.04 inches) by a means that ensures				
13.	Drop the head assembly from a height	of 376.0 ± 1.0 mm (14.8 inches	±		
	Record width Record length				
	Record thickness				
	610 mm (24 inches) square. (572.152)	(c)(4))			
12.	The impact surface is a flat horizontal	steel plate 50.8 mm (2 inches) th	nick and		
	Record actual micro finish				
	203.2x10 ⁻⁶ mm (8 micro inches) to 203 (572.152(c)(4))	sz.ux tu min (80 micro inches) (KIVIS).		
11.	The impact surface is clean and dry ar	nd has a micro finish in the range	OMC)		
	Record the angle		_		
	simulator (910420-003) and the plane (572.152(c)(3)(i))		egrees.		
10.	The angle between the lower surface painting of the plane				
	Record the left side distance				
	Record the right side distance		5)(5)(1))		
9.	The 3.3 mm (0.13 inch) diameter holes head are equidistance within 2 mm fro		•		
		pension device and the accelerolight as possible to minimize thei			
	NOTE: The masses of the cure	annion device and the accolors	motor		
	Record the actual distance				
0.	on the forehead is 376.0 ± 1.0 mm (14.8 ± 0.04 inch) from the impact surface. ($572.152(c)(3)(i)$)				
8.	Suspend and orient the head assembly	v as shown in Figure 5E. The lo	west point		

FRONTAL HEAD DROP TEST SET-UP SPECIFICATIONS



DATA SHEET E4

REAR HEAD DROP TEST (572.152)

Dumn	ny Serial Number Test Date
Techn	nician
	etest calibration st test calibration verification
Test a	attempt no (when successive head drops are necessary)
1.	It has been at least 2 hours since the last rear head drop and at least 30 minutes since the last frontal head drop. (572.152(c)(5))
2.	N/A, ONLY one head drop performed The head assembly consists of the head (921022-001), triaxial accelerometer mounting block (SA572-S80), and three (3) accelerometers (SA572-S4). (572.152(a))
3. 4.	Accelerometers and their respective mounts are smooth and clean. The data acquisition system, including transducers, conforms to the requirements of SAE Recommended Practice J211/1 MAR95. (572.155(i))
5.	The head assembly soaked at a temperature between 18.9°C (66°F) and 25.6°C (78°F) and at a relative humidity from 10% to 70% for a period of at least four (4) hours prior to a test. (572.152(c)(1)) Record the maximum temperature Record the minimum temperature Record the maximum humidity Record the minimum humidity
6.	Visually inspect the head skin for cracks, cuts, abrasions, etc. Repair or replace the head if the damaged area is more than superficial. Note: If the damage resulted from the CRS test in which the dummy was an occupant, the damaged area is to be documented with photography and the post test calibration verification testing completed before any replacement or repairs are made. Record findings and actions:
7.	Clean the impact surface of the skin and the impact surface of the fixture with isopropyl alcohol, trichloroethane or equivalent prior to the test (572, 152(c)(2))

8.	Suspend and orient the head assembly on the back of the head is 376.0 ± 1.0 surface. (572.152(c)(3)(ii)) Record the actual distance			
	•	pension device and the acceleror ight as possible to minimize their		
9.	The 3.3 mm (0.13 inch) diameter holes		•	
	head are equidistance within 2 mm from Record the right side distance	т tne ітраст surface. (5/2.152(с ——	s)(3)(II))	
	Record the left side distance			
10.	The angle between the lower surface p			
	simulator (910420-003) and the plane (of the impact surface is 90 ± 1 de	egrees.	
	(572.152(c)(3)(ii)) Record the angle			
11.	The impact surface is clean and dry an	d has a micro finish in the range	of	
	203.2x10 ⁻⁶ mm (8 micro inches) to 203	2.0x10 ⁻⁶ mm (80 micro inches) (I	RMS).	
	(572.152(c)(4))	, ,	,	
	Record actual micro finish			
12.	The impact surface is a flat horizontal s		ick and	
	610 mm (24 inches) square. (572.152(c)(4))		
	Record thickness Record width			
	Record length			
13.	Drop the head assembly from a height	of 376.0 ± 1.0 mm (14.8 inches :	±	
	0.04 inches) by a means that ensures			
	surface. (572.152(b) & (572.152(c)(4))		•	
14.	Complete the following table. (572.152	(b)):		
	Parameter	Specification	Result	
	Peak resultant acceleration	55 g ≤ x ≤ 71 g		
	Resultant versus time history curve	Unimodal		
	Oscillations after the main pulse	Less than 17% of the peak		
		resultant acceleration		
	Lateral acceleration	y-axis acceleration ≤ ±15 g		
15.	Plots of the x, y, z, and resultant accele	eration data follow this sheet.		
Signa	ture	Date		

REAR HEAD DROP TEST SET-UP SPECIFICATIONS




FIGURE 6E

DATA SHEET E5

NECK FLEXION TEST (572.153)

Dumn	ny Serial Number Test Date
Techn	ician
Pos	test calibration st test calibration verification
Test a	ttempt no (when successive flexion tests are necessary)
123.	It has been at least 30 minutes since the last neck test. (572.155(m)) N/A, this is the first neck test performed The components required for the neck tests include the neck assembly (921022-041), and headform (TE-3200-160). (572.153(a)) The assembly soaked at a temperature between 20.6°C (69°F) and 22.2°C (72°F) and at a relative humidity from 10% to 70% for a period of at least four (4) hours prior to a test. (572.153(c)(1)) Record the maximum temperature Record the minimum temperature Record the minimum humidity Visually inspect neck assembly for cracks, cuts and separation of the rubber from the metal segments. Note: If the damage resulted from the CRS test, the damaged area is to be documented with photography and the post test calibration verification testing completed before any replacement or repairs are made. Record findings and actions:
8. 9.	Torque the jam nut (9001336) on the neck cable (ATD-6206) between 0.2 Nm and 0.3 Nm. (572.153(c)(2) The data acquisition system, including transducers, conforms to the requirements of SAE Recommended Practice J211/1 MAR95. (572.155(i)) The test fixture pendulum conforms to the specifications in Figure 7E. The head-neck assembly is mounted on the pendulum so the midsagittal plane of the headform is vertical and coincides with the plane of motion of the pendulum as shown in Figure 8E for the flexion test. (572.153(c)(3)) Install the transducers or other devices for measuring the "D" plane rotation with respect to the pendulum longitudinal centerline. Note: Plane "D" is the top horizontal surface of the neck load cell. These measurement devices should be designed to minimize their influence upon the performance of the head-neck assembly and not induce neck torsion. (572.153(c)(3)(ii))

 11. Plane D is perpendicular ± 1 degree to the centerline of the pendulum. 12. Set the instrumentation so that the moment and rotation are defined to be zero when the longitudinal centerline of the neck and pendulum are parallel. (572.153(c)(3)(i)) 13. Release the pendulum and allow it to fall freely from a height to achieve an impact speed of 5.1 m/s to 5.3 m/s as measured at the center of the pendulum accelerometer at the instant of contact with the honeycomb. (572.153(c)(4)) 14. Complete the following table: 			
Parameter	1011 1001 1100	sults (572.153(b)(1) & (572.153(c)(4)(ii) Specification	Result
Pendulum impac	t speed	5.1 m/s ≤ speed ≤ 5.3 m/s	rtoourt
Pendulum	@ 10ms	1.6 m/s $\leq \Delta V \leq 2.3$ m/s	
ΔV with respect	@ 20 ms	3.4 m/s $\leq \Delta V \leq 4.2$ m/s	
to impact .	@25ms	4.3 m/s $\leq \Delta V \leq 5.2$ m/s	
speed	@_ 56	1.6 11.6 = 24 = 6.2 11.6	
Plane D Rotation		Peak moment*	Nm @
		36 Nm ≤ moment ≤ 45 Nm during the	degrees
		following rotation range 75° ≤ angle ≤ 86°	
Positive Moment	Decay**	Time to decay to 5Nm	
(Flexion)		$60 \text{ ms} \leq \text{time} \leq 80 \text{ms}$	
*Moment about the occipital condyle = M _y – (0.005842 m x F _x) (572.153(b)(1)(iii) My = Moment in Nm measured by the transducer Fx = Force, in N measured by the transducer **Time zero is defined as the time of initial contact between the pendulum striker plate and the honeycomb material. (572.153(c)(4)(i)) 15. Plots of pendulum acceleration, pendulum velocity, neck y-axis moment, and neck rotation about the y-axis follow this sheet.			
Signature		 Date	

DATA SHEET E6

NECK EXTENSION TEST (572.153)

Dumn	ny Serial Number Test Date
Techn	nician
	test calibration st test calibration verification
Test a	attempt no (when successive flexion tests are necessary)
123.	It has been at least 30 minutes since the last neck test. (572.155(m)) N/A, this is the first neck test performed The components required for the neck tests include the neck assembly (921022-041), and headform (TE-3200-160). (572.153(a)) The assembly soaked at a temperature between 20.6°C (69°F) and 22.2°C (72°F) and at a relative humidity from 10% to 70% for a period of at least four (4) hours prior to a test. (572.153(c)(1)) Record the maximum temperature Record the minimum temperature Record the minimum humidity Visually inspect neck assembly for cracks, cuts and separation of the rubber from the metal segments. Note: If the damage resulted from the CRS test, the damaged area is to be documented with photography and the post test calibration verification testing completed before any replacement or repairs are made. Record findings and actions:
8. 9.	Torque the jam nut (9001336) on the neck cable (ATD-6206) between 0.2 Nm and 0.3 Nm. (572.153(c)(2) The data acquisition system, including transducers, conforms to the requirements of SAE Recommended Practice J211/1 MAR95. (572.155(i)) The test fixture pendulum conforms to the specifications in Figure 7E. The head-neck assembly is mounted on the pendulum so the midsagittal plane of the headform is vertical and coincides with the plane of motion of the pendulum as shown in Figure 9E for the flexion test. (572.153(c)(3)) Install the transducers or other devices for measuring the "D" plane rotation with respect to the pendulum longitudinal centerline. Note: Plane "D" is the top horizontal surface of the neck load cell. These measurement devices should be designed to minimize their influence upon the performance of the head-neck assembly and not induce neck torsion. (572.153(c)(3)(ii))

 11. Plane D is perpendicular ± 1 degree to the centerline of the pendulum. 12. Set the instrumentation so that the moment and rotation are defined to be zero when the longitudinal centerline of the neck and pendulum are parallel. (572.153(c)(3)(i)) 13. Release the pendulum and allow it to fall freely from a height to achieve an impact speed of 2.4 m/s to 2.6 m/s as measured at the center of the pendulum accelerometer at the instant of contact with the honeycomb. (572.153(c)(4)) 14. Complete the following table: 			
Parameter		ts (572.153(b)(2) & (572.153(c)(4)(ii)	Result
Pendulum impac	t speed	2.4 m/s ≤ speed ≤ 2.6 m/s	rtoourt
Pendulum	@ 6 ms	$0.8 \text{ m/s} \le \Delta V \le 1.2 \text{ m/s}$	
ΔV with respect	@ 10 ms	$1.5 \text{ m/s} \le \Delta V \le 2.1 \text{ m/s}$	
to impact	@ 14 ms	$2.2 \text{ m/s} \le \Delta V \le 2.9 \text{ m/s}$	
speed			
Plane D Rotation		Peak moment*	Nm @
		-12 Nm ≥ moment ≥ -23 Nm during the	degrees
		following rotation range 80° ≤ angle ≤ 92°	
Negative Momen	t Decay**	Time to decay to -5Nm	
(Extension)		76 ms ≤ time ≤ 90ms	
*Moment about the occipital condyle = M _y – (0.005842 m x F _x) (572.153(b)(2)(iii) My = Moment in Nm measured by the transducer Fx = Force, in N measured by the transducer **Time zero is defined as the time of initial contact between the pendulum striker plate and the honeycomb material. (572.153(c)(4)(i))			
15. Plots of pendulum acceleration, pendulum velocity, neck y-axis moment, and neck rotation about the y-axis follow this sheet.			
Signature		Date	

PENDULUM SPECIFICATIONS






FIGURE 7E

NECK FLEXION TEST SET-UP SPECIFICATIONS



NOTE: MOUNT NECK AT LEADING EDGE OF PENDULUM TO AVOID INTERFERENCE.
FIGURE 8E

NECK EXTENSION TEST SET-UP SPECIFICATIONS



NOTE: MOUNT NECK AT LEADING EDGE OF PENDULUM TO AVOID INTERFERENCE.
FIGURE 9E

DATA SHEET E7THORAX IMPACT TEST (572.154)

Dumn	ny Serial Number lest Date
Techn	nician
	etest calibration
Pos	st test calibration verification
Test a	attempt no (when successive thorax impact tests are necessary)
1.	It has been at least 30 minutes since the last thorax impact test. (572.155(m)) N/A, ONLY one thorax impact test performed
2.	The test fixture conforms to the specifications in Figure 10E.
<u></u> 3.	The complete assembled dummy (921022-000) is used (572.154(b)) and is
	dressed in cotton-polyester-based tight-fitting long-sleeved sweat shirt and ankle length pants. The weight of the shirt and pants shall not exceed 0.25 kg. (572.154(c)(2))
4.	The dummy assembly soaked at a temperature between 20.6°C (69°F) and
	22.2°C (72°F) and at a relative humidity from 10% to 70% for a period of at least
	four (4) hours prior to this test. (572.154(c)(1))
	Record the maximum temperature
	Record the minimum temperature
	Record the maximum humidity
_	Record the minimum humidity
5.	Seat the dummy, without back support on the test fixture surface as shown in
	Figure 10E. The legs are extended forward, parallel to the midsagittal plane.
	The surface must be long enough to support the pelvis and outstretched legs.
0	(572.154(c)(3))
<u></u> 6.	The midsagittal plane of the dummy is vertical within \pm 1°. (572.154(c)(3))
7.	The posterior surface of the upper spine box is $90^{\circ} \pm 1^{\circ}$ from the horizontal.
	Shim material may be used under the upper legs to maintain the dummy's
0	specified spine box surface alignment. (572.154(c)(3))
8.	Place the upper arms parallel to the torso. Place the lower arms 0° to 5° forward
0	of vertical. (572.154(c)(3))
9.	The longitudinal centerline of the test probe is centered within ±2.5 mm of the
	midsagittal plane, 196 ± 2.5 mm vertically from the plane of the seating surface
	and is within ±0.5° of a horizontal line in the dummy's midsagittal plane.
10	(572.154(c)(4)) The data acquisition eveters including transducers must conform to the
10.	The data acquisition system, including transducers, must conform to the
4.4	requirements of SAE Recommended Practice J211/1 MAR95 (572.155(i)).
11.	Impact the anterior surface of the thorax with the test probe so the longitudinal
	centerline of the probe is within 2° of a horizontal line in the dummy's midsagittal
	plane at the moment of impact. (572.154(c)(5)) The velocity of the test probe at
	the time of impact is between 4.9 m/s and 5.1 m/s. (572.154(b)) The probe is

guided so there is no significant lateral, vertical or rotational movement during the impact. (572.154(c)(6)) Neither the suspension hardware, suspension cables, nor other attachments to the probe, including the velocity vane, shall make contact with the dummy during the test. (572.154(c)(7))

__12. Complete the following table:

Thorax Impact Results (572.154(b))


Parameter*	Specification	Result
Test Probe Speed	4.9 m/s ≤ speed ≤ 5.1 m/s	
Peak force**	1514 N ≤ peak force ≤ 1796 N	

^{*}Time zero is defined as the time of initial contact between the test probe and the chest skin.

13. Plots of pendulum acceleration, and pendulum force, follow this sheet.		
Signature	Date	

^{**}Force = impactor mass x acceleration

THORAX IMPACT TEST SET-UP SPECIFICATIONS



^{* 1/3} OF CABLE WEIGHT NOT TO EXCEED 5% OF THE TOTAL IMPACT PROBE WEIGHT.

Probe specifications:

- 1. Rigid metallic construction and concentric about its longitudinal axis.
- 2. A mass of 2.86 ± 0.02 kg (6.3 ± 0.05 lbs). 1/3 of the weight of the suspension cables and their attachments to the impact probe are included in the calculation of mass, and such components may not exceed 5 percent of the total weight of the test probe.
- 3. Minimum mass moment of inertia of 164 kg-cm² (0.145 lbs-in-sec²) in yaw and pitch about the center of gravity.
- 4. The impacting end of the probe is perpendicular to and concentric with the longitudinal axis. It has a flat, continuous, and non-deformable face with diameter of 101.6 ± 0.25 mm $(4.00 \pm 0.01$ in) and a edge radius of 7.6 to 12.7 mm (0.3) to 0.5 in.).
- 5. A 101-103 mm (4.0-4.1 in) diameter cylinder surface extends at least 12.5 mm to the rear of the impact face.
- 6. The probe's end opposite to the impact face must have provisions for mounting of an accelerometer with its sensitive axis collinear with the longitudinal axis of the probe.
- 7. The impact probe shall have a free air resonant frequency of not less than 1000 Hz in line with the longitudinal axis of the impactor.

FIGURE 10E

DATA SHEET E8 PART 572 INSTRUMENTATION CALIBRATION INFORMATION

I.D. NO.	MANUFACTURER	MODEL NO.	SERIAL NO.	DATE OF LAST CALIBRATION	DATE OF NEXT CALIBRATION
		DUMMY INSTRUM	ENTATION		
		HEAD ACCELERO	OMETERS		
(1) LONGITUDINAL					
(2) LATERAL					
(3) VERTICAL					
NECK TRANSDUCER					
		CHEST ACCELER	OMETERS		
(1) LONGITUDINAL					
(2) LATERAL					
(3) VERTICAL					
CHEST POTENTIOMETER					
		FEMUR LOAD	CELLS		
(1) RIGHT FEMUR					
(2) LEFT FEMUR					
		LABORATORY INSTR	UMENTATION		
NECK PENDULUM ACCELEROMETER					
THORAX PENDULUM ACCELEROMETER					
KNEE PENDULUM ACCELEROMETER					
NECK ROTATION TRANSDUCER 1 (OPTIONAL)					
NECK ROTATION TRANSDUCER 2 (OPTIONAL)					

LABORATORY TECHNICIAN:	
LADOINATOINT TEOLINIOIAIN.	