APPENDIX F BUILT-IN CHILD RESTRAINT REPORT TEMPLATE

REPORT NUMBER: 213-ABC-#

BUILT-IN RESTRAINT SYSTEM TESTS - FMVSS NO. 213

Manufacturer Manufacturer Child Seat - Type Automobile

Performing Organization Address

Date

FINAL REPORT

PREPARED FOR: U. S. Department of Transportation National Highway Traffic Safety Administration 400 Seventh Street, S. W. Washington, DC 20590

Prepared for the United States Department of Transportation, National Highway Traffic Safety Administration, under Contract No. _____. This publication is distributed by the U.S. Department of Transportation, National Highway Traffic Safety Administration, in the interest of information exchange. The opinions, findings and conclusions expressed in this publication are those of the author(s) and not necessarily those of the Department of Transportation or the National Highway Traffic Safety Administration. The United States Government assumes no liability for its contents or use thereof. If trade or manufacturers' names or products are mentioned, it is only because they are considered essential to the object of the publication and should not be construed as an endorsement. The United States Government does not endorse products or manufacturers.

REPORT ACCEPTED BY:

Contract Officer's Technical Representative (COTR) Office of Vehicle Safety Compliance

Acceptance Date

TECHNICAL REPORT STANDARD TITLE PAGE

1. Report No.	2. Government Accession No.	3. Recipient's Catalog No.
 4. Title and Subtitle Child Restraint Systems Tests - FMVSS 213 Manufacturer Manufacturer Child Seat - Type 		 S. Report Date Date 6. Performing Organization Code
7. Author(s)		8. Performing Organization Report No.
9. Performing Organizat	ion Name and Address	10. Work Unit No. 11. Contract or Grant No.
 12. Sponsoring Agency Name and Address U.S. Department of Transportation National Highway Traffic Safety Administration 400 Seventh, S.W. Washington, D.C. 20590 		 13. Type of Report and Period Covered Final Report Dates 14. Sponsoring Agency Code
15. Supplementary Note Reviewed by Approved by	?S	Program Manager

16. Abstract

This report contains the results of tests performed in accordance with FMVSS 213, Child Restraint Systems, on the Manufacturer, Automobile, equipped with a Manufacturer Child Restraint. The child restraint appears to comply with the requirements of FMVSS 213. Final determination of compliance is made by the National Highway Traffic Safety Administration.

17. Key Words FMVSS 213 Child Restraint Systems Compliance Testing		 18. Distribution Statement National Highway Traffic Safety Administration Technical Information Services (NPO-405) 400 Seventh St., SW, Room 2336 Washington, DC 20590 		
19. Security Classify. (of this report)	20. Security Classify. page)	(of this	21. No. of Pages	22. Price
UNCLASSIFIED	UNCLASSIFI	ED		

TABLE OF CONTENTS

Section 1 –	Purpose and Test Procedure
Section 2 –	Introduction and Summary
Section 3 –	Inspection and Test Data
Appendix A –	Equipment List and Calibration Schedules
Appendix B –	Photographs of Equipment

SECTION 1

PURPOSE AND TEST PROCEDURE

- Purpose: The purpose of the test was to determine if the production built-in child restraint system(s) in the Manufacturer Automobile met the requirements of Federal Motor Vehicle Safety Standard (FMVSS) No. 213, Child Restraint Systems.
- Test Procedure: The "Performing Organization Operating Test Procedure for FMVSS No. 213", submitted to and approved by the Office of Vehicle Safety Compliance, National Highway Traffic Safety Administration, contains the specific procedures used to conduct this test. This procedure shall not be interpreted to be in conflict with any portion of FMVSS No. 213 and amendments in effect as noted in the applicable contract.

SECTION 2

INTRODUCTION AND SUMMARY

This report presents all of the FMVSS 213 compliance inspection and test data obtained on the Manufacturer Child Seat - Type child restraint system. This test was performed in conjunction with a full-scale FMVSS 208 compliance test of a Automobile. The restraint was dynamically tested in the forward-facing upright configuration. The results from all inspections and tests indicate that the Manufacturer Child Seat - Type child restraint complied with all of the requirements of FMVSS 213.

Restraint system inspection and, full-scale dynamic testing were performed by the Performing Organization. Compliance test data sheets for all tests are found in Section 3 of this report.

SECTION 3 INSPECTION AND TEST DATA FMVSS 213 - BUILT-IN CHILD RESTRAINT SYSTEMS

Rep	oort No.	213-ABC-96-#				
Nar		-	ESTRAINT	SYS	TEM IDENTIFICATION	
Add	dres					
Мо	del No.					
Gro	oup No.					
1.	Item Co	ode		2.	Item Code	
	Date of	Manufacture		_	Date of Manufacture	
	Sled Te	est No.		_	Sled Test No.	
3.	Item Co	ode		4.	Item Code	
	Date of	Manufacture			Date of Manufacture	
	Sled Te	est No.		_	Sled Test No.	
5.	Item Co	ode		6.	Item Code	
	Date of	Manufacture		_	Date of Manufacture	
	Sled Te	est No.		-	Sled Test No.	
				_		

REMARKS:

Technician: _____

Date: _____

COMPLIANCE TEST DATA: FMVSS 213 LABELING (FMVSS 213, S5.5)

Date of Tes	t Item Code	
		PASS / FAIL
S5.5.4	(a) Each built-in child restraint system other than a factory-installed built-in restraint shall be permanently labeled with the information specified in S5.5.5 (a) through (I). The information specified in S5.5.5 (a) through (j) and in S5.5.5(I) shall be visible when the system is activated for use.	
	(b) Each factory-installed built-in child restraint shall be permanently labeled with the information specified in S5.5.5 (f) through (j) and S5.5.5(l), so that the information is visible when the restraint is activated for use. The information shall also be included in the vehicle owner's manual.	
S5.5.5	The information specified in paragraphs (a) through (l) of this section that is required by S5.5.4 shall be in English and lettered in letters and numbers using a not smaller than 10 point type. Unless specified otherwise, the information shall be labeled on a white background with black text. Unless written in all capitals, the information shall be stated in sentence capitalization.	
REMARKS:		

Technician: _____

LABE		
		PASS/FAIL
The fo	bllowing information is included:	
(a)	The model name or number of the system.	
(b)	The manufacturer's name. A distributor's or dealer's name may be used instead if the distributor or dealer assumes all responsibility for all duties and liabilities imposed on the manufacturer with respect to the system by the National Traffic and Motor Vehicle Safety Act, as amended.	
(c)	The statement: "Manufactured in," inserting the month and year of manufacture.	
(d)	The place of manufacture (city and State, or foreign country). However, if the manufacturer uses the name of the distributor or dealer, then it shall state the location (city and State, or foreign country) of the principle offices of the distributor or dealer.	
(e)	The statement: "This child restraint system conforms to all applicable Federal Motor Vehicle Safety Standards."	
	78KS.	

REMARKS:

Technician: _____

LABELING (Continued)

- (f) One of the following statements, as appropriate, inserting the manufacturer's recommendations for the maximum mass of children who can safely occupy the system, except that booster seats shall not be recommended for children whose masses are less than 13.6 kg. For seats that can only be used as belt-positioning seats, manufacturers must include the maximum and minimum recommended height, but may delete the reference to weight:
 - Use only with children who weigh _____ pounds (_____ kg) or less and whose height is (*insert values in English and metric units; use of word "mass" in label is optional*) or less; or
 - (2) Use only with children who weigh between _____ and _____ pounds (_____ and _____ kg) and whose height is (*insert* appropriate values in English and metric units; use of word "mass" in label is optional) or less and who are capable of sitting upright alone; or
 - (3) Use only with children who weigh between _____ and _____ pounds (_____ and _____ kg) and whose height is (*insert* appropriate values in English and metric units; use of word "mass" in label is optional) or less.
 - (4) Use only with children who weigh between _____ and _____ pounds (*insert appropriate English and metric values; use of word "mass" is optional*) and whose height is between _____ and _____ (*insert appropriate values in English and metric units*).

REMARKS:

Technician: _____

Date: _____

Program Manager: _____

PASS/FAIL

LABELING (Continued)

- (g) The heading and statement specified in paragraph (1), and if appropriate, the statements in paragraph (2) and (3). If used, the statements in paragraphs (2) and (3) shall be bulleted and precede the bulleted statement required by paragraph (1) after the heading.
 - A heading as specified in S5.5.2(k)(3)(i), with the statement (1) "WARNING! DEATH or SERIOUS INJURY can occur" capitalized as written and followed by the bulleted statement: Follow all instructions on this child restraint and in the vehicle's owner's manual. At the manufacturer's option the phrase "DEATH or SERIOUS INJURY can occur" in the heading can be on either a white or yellow background.
 - (2) In the case of each built-in child restraint system which is not intended for use in motor vehicles in certain adjustment positions or under certain circumstances, an appropriate statement of the manufacturers restrictions regarding those positions or circumstances.
 - (3) As appropriate, the statements required by the following sections will be bulleted and placed after the statement required by 5.5.5(g)(1) in the following order: 5.5.5(g)(2), 5.5.5(f), S5.5.5(h) and S5.5.5(i).
- In the case of each built-in child restraint system that has belts designed to restrain children using them and which do not adjust automatically to fit the child, the statement:

Snugly adjust the belts provided with this child restraint around your child.

REMARKS:

Technician:

Program Manager: _____

PASS/FAIL

(h)

LABELING (Continued)		PASS/FAIL
(i)	In the case of each built-in child restraint which can be used in a rear facing position, the following statement:	
	Place an infant in a rear-facing position in this child restraint.	
(j)	A diagram or diagrams showing the fully activated child restraint system in infant and/or child configurations.	
(k)	The following statement, inserting an address and telephone number:	
	"Child restraints could be recalled for safety reasons. You must register this restraint to be reached in a recall. Send your name, address and the restraint's model number and manufacturing date to (<i>insert address</i>) or call (<i>insert telephone</i> <i>number</i>). For recall information, call the U. S. Government's Auto Safety Hotline at 1-800-424-9393 (202-366-0123 in D.C. area Effective November 8, 2005:	a)."
	One of the following statements, inserting an address and a U.S. telephone number. If manufacturer opts to provide a Web site on the registration card as permitted in Figure 9a of this section (FMVSS 213), the manufacturer must include the statement in part (ii):	
	(i) "Child restraints could be recalled for safety reasons. You must register this restraint to be reached in a recall. Send your name, address, e-mail address if available [preceding four words is optional] and the restraint's model number and manufacturing date to (<i>insert address</i>) or call (<i>insert a U.S. telephone number</i>). For recall	

information, call the U. S. Government's Auto Safety Hotline at 1-800-424-9393."

(ii)"Child restraints could be recalled for safety reasons. You must register this restraint to be reached in a recall. Send your name, address, e-mail address if available [preceding four words is optional] and the restraint's model number and manufacturing date to (*insert address*) or call (*insert a U.S. telephone number*) or register online (*insert web site for electronic registration form*). For recall information, call the U. S. Government's Auto Safety Hotline at 1-800-424-9393."

	APPENDIX FContinued: LABELING (Continued)		PASS/FAIL
	Effective June 21, 2006 (voluntary compliance is perm before this time):	nitted	
	"Child restraints could be recalled for safety reasons. register this restraint to be reached in a recall. Send y address and the restraint's model number and manufa date to (<i>insert address</i>) or call (<i>insert telephone numb</i> For recall information, call the U. S. Government's Vel Safety Hotline at 1-888-327-4236 (TTY:1-800-424-915 to <i>http://www.NHTSA.gov.</i> "	/our name, acturing <i>er</i>). hicle	
(1)	In the case of a built-in belt-positioning seat that uses of vehicles Type I or Type II belt systems or both, a state describing the manufacturer's recommendations for the height and weight of children who can safely occupy the and how the booster should be used (e.g.; with or with with the different vehicle belt systems.	ment e maximum ne system,	
REMA	NRKS:		
Techn	ician:	Date:	

COMPLIANCE TEST DATA: FMVSS 213 INSTALLATION INSTRUCTIONS (FMVSS 213, S5.6)

Date	of Test Item Code		
S5.6	Any labels or written instructions provided in addi		PASS/FAIL
	required by this section shall not obscure or confi of the required information or be otherwise mislea customer. Any labels or written instructions othe English language shall be an accurate translation or written instructions. Unless written in all capita required by S5.6.2 and S5.6.3 shall be stated in s capitalization.	ading to the than in the of English labels als, the information	
S5.6.2	2		
(a)	Each built-in child restraint system shall be accord by printed instructions in English that provide a step-by-step procedure, including diagrams, for a the restraint system, positioning a child in the system adjusting the restraint and, if provided, the restraint to fit the child. The instructions for each built-in of shall explain that the child should be positioned in in such a way that the child's head is near the cert of the vehicle.	ctivating tem, nt harness ar bed n the bed	
(b)	Each motor vehicle equipped with a factory-instal built-in child restraint shall have the information s in paragraph (a) of this section included in it's ve owner's manual.	pecified	
REMA	ARKS:		
Techn	iician:	Date:	

(Installation continued)

S5.6.2.1

The instructions shall explain the primary consequences of not following the manufacturer's warnings for proper use of the child restraint system in accordance with S5.5.5 (f) through (i).

S5.6.2.2

The instructions for each built-in child restraint system, other than a factory-installed restraint, shall include the following statement, inserting an address and telephone number:

"Child restraints could be recalled for safety reasons. You must register this restraint to be reached in a recall. Send your name, address and the restraint's model number and manufacturing date to (*insert address*) or call (*insert telephone number*). For recall information, call the U. S. Government's Auto Safety Hotline at 1-800-424-9393 (202-366-0123 in D.C. area)."

Effective November 8, 2005:

The instructions for each built-in child restraint system other than a factory-installed restraint, shall include one of the following statements, inserting an address and a U.S. telephone number. If a manufacturer opts to provide a Web site on the registration card as permitted in Figure 9a of this section (FMVSS 213), the manufacturer must include the statement in part (ii):

(i) "Child restraints could be recalled for safety reasons. You must register this restraint to be reached in a recall. Send your name, address, e-mail address if available [preceding four words is optional] and the restraint's model number and manufacturing date to (*insert address*) or call (*insert a U.S. telephone number*). For recall information, call the U. S. Government's Auto Safety Hotline at 1-800-424-9393."

REMARKS:

Technician: _____

PASS/FAIL

Program Manager: _____

Date: _____

(Installation continued)

(ii)"Child restraints could be recalled for safety reasons. You must register this restraint to be reached in a recall. Send your name, address, e-mail address if available [preceding four words is optional] and the restraint's model number and manufacturing date to (*insert address*) or call (*insert a U.S. telephone number*) or register online (*insert web site for electronic registration form*). For recall information, call the U. S. Government's Auto Safety Hotline at 1-800-424-9393."

Effective June 21, 2006 (voluntary compliance is permitted before this time):

"Child restraints could be recalled for safety reasons. You must register this restraint to be reached in a recall. Send your name, address and the restraint's model number and manufacturing date to (*insert address*) or call (*insert telephone number*). For recall information, call the U. S. Government's Vehicle Safety Hotline at 1-888-327-4236 (TTY:1-800-424-9153), or go to <u>http://www.NHTSA.gov</u>."

S5.6.2.3

Each built-in child restraint system other than a factory-installed built-in restraint, shall have a location on the restraint for storing the instructions.

S5.6.2.4

Each built-in child restraint system, other than a system that has been installed in a vehicle or a factory installed built-in system that is designed for a specific vehicle model and seating position, shall be accompanied by instructions in English that provide a step-by-step procedure for installing the system in a motor vehicle. The instructions shall specify the types of vehicles and the seating positions into which the restraint can or cannot be installed. The instructions for each car bed shall explain that the bed should be installed so that the child's head will be near the center of the vehicle.

REMARKS:

Technician: _____

Date: _____

PASS/FAIL

(Installation continued)

S5.6.2.5

In the case of a built-in belt-positioning seat that uses either the vehicle's Type I or Type II belt systems or both, the instructions shall include a statement describing the manufacturer's recommendations for the maximum height and weight of children who can safely occupy the system and how the booster must be used with the vehicle belt systems appropriate for the booster seat. The instructions shall explain the consequences of not following the directions. The instructions shall specify that, if the booster seat is recommended for use with only the lap-belt part of a Type II assembly, the shoulder belt portion of the assembly must be placed behind the child.

S5.6.3

In the case of each child restraint system that has belts designed to restrain children using them and which do not adjust automatically to fit the child, the printed instructions shall include the following statement:

A snug strap should not allow any slack. It lies in a relatively straight line without sagging. It does not press on the child's flesh or push the child's body into an unnatural position.

REMARKS:

Technician: _____

PASS/FAIL

Date: _____

Program	Manager:	
0	0	

MINIMUM HEAD SUPPORT SURFACE (FMVSS 213, S5.2.1)

Date of Test		Item Code	
S5.2.1.2	The child restraint syste	m is too low to	o be exempt
	from this requirement.		

S5.2.1.1

BACK SUPPORT HEIGHT

Maximum Child Weight kg (lbs.)	Required Minimum Height cm (in.)	Measured Height cm (in.)	PASS/ FAIL

BACK SUPPORT WIDTH

Required Minimum Width cm (in.)	Measured Width cm (in.)	Side Wing Depth cm (in.)	PASS/ FAIL

REMARKS:

Technician: _____

|--|

YES/NO

TORSO IMPACT PROTECTION (FMVSS 213, S5.2.2)

Date of Test

Item Code _____

S5.2.2.1

Test	Compliance Requirement	Test Result	PASS/ FAIL
Back Support Surface	Flat or concave		
	Area ≥ 548 sq. cm (85 sq. in.)	sq. cm (sq. in.)	
Side Support Surface	Flat or concave		
Max. weight ≥ 9 kg (20 lb.)	Area ≥ 155 sq. cm (24 sq. in.)	sq. cm (sq. in.)	
Max. weight < 9 kg (20 lb.)	Area ≥ 310 sq. cm (48 sq. in.)	sq. cm (sq. in.)	
Forward Restraining Surface			
Horiz. Cross Section	Flat or concave		
Vertical Longitudinal	Flat or convex		
Cross Section	Radius of curvature ≥ 5 cm (2 in.)		
		YES/NO	PASS/DEFERRED

S5.2.2.2 Forward Fixed or Movable Surface

REMARKS:

Technician: _____

PROTRUSION LIMITATION (FMVSS 213, S5.2.4)

Item Code

Test	Compliance Requirement mm (in.)	Test Result mm (in.)	PASS/ FAIL
Height	≤ 9.53 mm (3/8 in.)		
Edge Radius	≥ 6.35 mm (1/4 in.)		

REMARKS:

Technician: _____

Date: _____

DYNAMIC IMPACT TEST CONDITIONS (FMVSS 213, S6.1)

Date of Test		Т	est No.	
	-		em ode	
Laboratory Ambient Conditions Duri Temperature Range	ng Testin to	ŋg	Degre (F)	ees C
Relative Humidity Range	% to		- (1) % -	
Test Device				
Nominal velocity (km/h)				
[mph] Dummy Used Child Restraint System				S/N:
Location				
Installation mode				
Adjustment mode				
"Misuse" mode				
Test Results				
Actual velocity		m	/s (ft/s)	
		kr	n/h (mp	h)
Vehicle Seat Position				
Vertical position				
Horizontal position				
Vehicle seat back position				
Include pretest and post test photog	raphs an	d accel	eration-	time history plot.
REMARKS:				
Pretest and posttest photographs ar	e presen	ted in A	ppendi	х В.
Technician:				Date:

_____ Date: _____

Date of Test

Test No.

Item Code

"SLED PULSE"

FMVSS 213 30 MPH PULSE ENVELOPE

BELT RESTRAINT (FMVSS 213, S5.4.3)

Date of Test

Test No.

Item Code	

S5.4.3.1 Snug Fit of Belts

PASS/FAIL

EXTRA WEBBING

Dummy	Each Shoulder Belt cm	Each Lap Belt Side	Crotch Belt
	(in.)	cm (in.)	cm (in.)

YES/NO

S5.4.3.2 Direct Restraint Belts

		. = •/•
(1)	Belt / dummy contact for	
(2)	Rigid structure behind	
(3)	Belt / child restraint slip	
Note:	If all "yes", restraint fails.	
S5.4.3.3 (1)	Seating System Belts and/o Upper torso	r Shields
(2)	Lower torse	

- (2) Lower torso(3) Crotch restraint
- S5.4.3.4 Child Harness Belts
 - (1) Upper torso
 - (2) Lower torso
 - (3) Prevent standing
- **REMARKS**:

Technician: _____

Date: _____

BUCKLE RELEASE (FMVSS 213, S5.4.3.5, S6.2)

Date of Test

Test No.

Item Code

Test	Compliance Requirement	Test Result	PASS/ FAIL
Buckle Minimum Surface Area	Area ≥ 3.9 cm² (0.6 in.²)	cm² (in.²)	
Preimpact Release Force	Force range: 40 to 62 N (9 to 14 lbs.)	N (lbs.)	
Buckle Integrity	Not release during test		
Post Impact Release Force	Force range: ≤ 71 N (16 lbs.)	N (lbs.)	

REMARKS:

The buckle is an integral part of the seat and, therefore, the buckle release test was performed on the entire seat assembly.

Technician: _____

RESTRAINT SYSTEM INTEGRITY (FMVSS 213, S5.1.1)

Date of Test

Test No.

Item Code

Test	Compliance Requirement	Test Result	PASS/ FAIL
Structural Integrity	No complete separation		
	No partial separation with exposed edge radius < 9.53 mm (1/4")		
	No partial separation with protrusions > 6.35 mm (3/8")		
Adjustment Position	No change		
Back Surface / Seating Surface Angle	Not < 45 degrees	deg.	

REMARKS:

Technician: _____

INJURY CRITERIA (FMVSS 213, S5.1.2)

Date of Test

Test No.

Test No.

Test	Compliance Requirement	Test Result	PASS/ FAIL
Head Injury Criterion	≤ 1000		
Chest Injury Criterion	Cumulative duration over 60 g \leq 3 ms	Peak g = Duration exceeding 60 g =	

REMARKS:

Technician: _____

Date: _____

OCCUPANT EXCURSION (FMVSS 213, S5.1.3, S5.1.4, S5.2.1.1 (C))

Date of Test

Test No.

Item Code

FORWARD-FACING RESTRAINTS

Test	Compliance Requirement	Test Result	PASS/ FAIL
Torso Retention (FMVSS 213, S5.1.3.1)	Retain within system		
Knee Target Excursion (FMVSS 213, S5.1.3.1)	≤ 305 mm (12 in.)	mm (in.)	
Head - Torso Angle (FMVSS 213, S5.2.1.1 (c))	Rearward change ≤ 45 degrees	deg.	

REAR-FACING RESTRAINTS

Test	Compliance Requirement	Test Result	PASS/ FAIL
Torso Retention (FMVSS 213, S5.1.3.2)	Retain within system		
Head Target Excursion (FMVSS 213, S5.1.3.2)	Not beyond restraint's top and forward edge		
Back Support Angle (FMVSS 213, S5.1.4)	\leq 70 degrees	deg.	
Head - Torso Angle (FMVSS 213 S5.2.1.1 (c))	Rearward change ≤ 45 degrees	deg.	

REMARKS:

Technician: _____

APPENDIX A EQUIPMENT LIST AND CALIBRATION SCHEDULES

> APPENDIX B PHOTOGRAPHS OF EQUIPMENT