



ON THE STANDARD SEAT ASSEMBLY

FIGURE 15







NOTES:

(1) ANCHOR POINT ON REAR PACKAGE SHELF LOCATED 544 mm RIGHT OR LEFT OF THE CENTER SORLS AS SHOWN

IN FIGURE 15a.

(2) REAR LAP BELT BUCKL LOCATED 178 mm RIGHT OR LEFT OF THE CENTER SORL AS SHOWN IN FIGURE 15a.

3) HEAD EXCURSION LIMIT IS: (i) 720 mm WITH TETHER ATTACHED AND (ii) 813 mm WITH TETHER UNATTACHED.

(4) UNIVERSALE LOWER ANCHORAGE BARS LOCATED 102 mm FORWARD OF POINT Z AND 323 mm UPWARD FROM FLOOR.

LOCATION OF UNIVERSAL CHILD RESTRAINT ANCHORAGE SYSTEM

AND FORWARD EXCURSION LIMITS FOR THE STANDARD SEAT ASSEMBLY

D.1.2 INSTRUMENTATION

TRANSDUCERS (S213, S5.1.2, S6.1.1.1, S7.2)

The following transducers are required:

- (1) Accelerometer for monitoring impact sled deceleration. Accelerometer type and class as required to adequately measure an acceleration response as specified in Figures 17 and 18.
- (2) Two triaxial accelerometer packages for mounting one each in the head and the thorax of the three-year-old dummy. Six accelerometers are required for mounting, three each in the head and thorax of the six-year old unweighted dummy. Each axis of the accelerometers shall meet the following minimum performance requirements:

Mounting frequency response:	± 5%, 0 to 2000 Hz
Maximum damping:	0.005 of critical, nominal
Transverse sensitivity:	5% maximum
Linearity and hysteresis:	± 3% of reading, maximum
Dynamic range:	± 500 g, minimum
Type and Class:	See App. D (3 yr. old dummy) and Appendix B or C (6 yr. old dummy)

- (3) Seat belt webbing load cells to monitor belt preload during seat installation. This item is not required if an equivalent belt tension measurement device is utilized to determine the preload on the Type I and Type II seat belt assembly.
- (4) Velocity transducer or integration of the sled accelerometer to determine speed of Dynamic Impact Test.
- (5) Force transducer to monitor the load applied to the dummy sling during the Buckle Release Tests described in this procedure.
- (6) Force transducer to measure buckle release force.

PLAYBACK AND RECORDING EQUIPMENT

Equipment shall be provided that has the following capabilities:

(1) Have a minimum capability of 8 data channels for measuring the following during the Dynamic Impact Test:

- 6 Dummy accelerations
- 1 Sled acceleration
- 1 Sled velocity
- (2) Provide a permanent record of all data channels during dynamic impact.
- (3) Provide a permanent record of seat belt preload.
- (4) Provide a permanent record of force applied to the dummy sling during the Buckle Release Tests described in this procedure.
- (5) Provide a permanent record of buckle release force.

HIGH SPEED CAMERAS

At least three (3), on board 16-mm high-speed movie camera or video capable of 1,000 frames per second (fps) is required to record the dynamic performance of the child restraint system. The movie film/video will be analyzed to determine occupant excursions as outlined in this procedure.

In order to obtain a complete view of the restraint system behavior during the entire test, a large field of view is required. An onboard camera system is suggested for maximum resolution of head and knee-target excursions of the three-year old and six-year old dummy. For a typical sled configuration, a single onboard camera mounted 182.9 cm (6 feet) from and perpendicular to the SORL, with its optical axis approximately 635 mm (25 inches) above the base plane of the standard seat assembly and 864 mm (34 inches) forward of the seat back pivot axis, will provide a suitable arrangement for accurately assessing the excursions near the 813 mm (32-inch) head limit and the 914 mm (36-inch) knee pivot-point limit. If a single camera is used, a 13-mm lens mounted as suggested above will have a field of view approximately 1499 mm (59 inches) wide and 1067 mm (42 inches) high. When placed at the 864 mm (34-inch) location, the camera will cover the initial installation configuration of the test as well as the maximum forward motions of the restraint system and dummy.

For built-in child restraint systems using the specific vehicle for the dynamic Test it is suggested that a minimum of two 16 mm high-speed movie camera or video capable of 1000 frames per second (fps) be utilized on board the vehicle. The location of the camera must be perpendicular to the SORL and placed on the outdoor skin of the vehicle at a known distance forward of the child restraint system. Because of the vehicle construction and obstructions (B pillar, front seats, etc.), the camera cannot be placed 864 mm (34 inches) forward of the seat back pivot as suggested above, therefore, the camera must be located at an accurately measured distance forward of the restraint system so the forward excursions can be measured with a minimum of error.

For a test of a forward-facing restraint in which the target point on either side of the dummy's head is above the top of the standard seat assembly, a second camera is required for observing the rebound phase of the test. This camera should be mounted at the same height and distance from the SORL as the first camera but directly above the seat back pivot axis. Ensure that the field of view of the camera includes a vertical reference.

The limiting resolution of typical onboard camera/film systems is approximately 40 line-pairs per millimeter (mm). With a 1499 mm (59-inch) by 1067 mm (42-inch) field of view, the corresponding lower limit on position-resolution capability is 3.8 mm (0.15 inch). Any angle determinations made from reading the positions of two targets will also be affected by the resolution limit. This uncertainty can be minimized by placing targets as far apart as possible.

Place a rigidly fixed reference grid on the far side of the standard seat assembly, with field calibration targets and head and knee pivot-point limit lines displayed vertically on it. The vertical limit lines should be positioned to account for parallax such that, when the head leading-edge or knee pivot-point reach those lines in the camera field of view, they have exceeded their excursion limits beyond any question of experimental error. This will allow a simple PASS or FAIL determination to be made before the excursions are actually measured. Even though the knee pivot-points are on either side of the SORL, the placement of the camera at 864 mm (34 inches) will result in such a small parallax error that a single line can be used for determining the excursion of either knee pivot-point. The vertical grid lines will also serve as reference for the measurement of the back support angle of rear-facing restraints.

For built-in child restraint systems using the specific vehicle, a rigidly fixed reference grid should be placed in the vehicle in line with the onboard camera. This reference must be a known distance from the seat back pivot point.

If an alternate method of comparable accuracy is available for observing and measuring occupant excursions, this method may be used instead of a high-speed movie system with the concurrence of the COTR.

D.2 SYSTEMS CHECK

Before beginning a series of child restraint system compliance tests, conduct one trial test to determine that all systems are functioning properly. In particular:

(1) Ensure the test velocities and severity conditions given in this procedure are met.

- (2) When applicable, conduct the trial test with an instrumented dummy to assure correct operation of transducers, signal conditioning, and record/playback equipment.
- (3) Review high-speed movie coverage of the test setup and timing of the camera operation.
- (4) Ensure accurate calibrations of the high-speed movie field of view are available in the plane of motion of the child restraint system.
- D.3 TEST CONDITIONS
- D.3.1 ENVIRONMENTAL CONDITIONS (S213, S6.1.1(d))

The Dynamic Impact Test shall be performed under the following environmental conditions:

Temperature	19°C (66°F) to 26°C (78°F)
-------------	----------------------------

Relative Humidity 10% to 70%

D.3.2 IMPACT SPEED (S213, S6.1.1)

Configuration I tests shall be conducted at a velocity change of 48 km/h, + 0, - 3.2 km/h (30 mph, + 0, - 2 mph), or for the specific vehicle test with the deceleration produced in a 48 km/h frontal barrier crash.

Configuration II tests shall be conducted at a velocity change of 32 km/h, +0, - 3.2 km/h (20 mph, + 0, - 2 mph), or for the specific vehicle test with the deceleration produced in a 32 km/h frontal barrier crash.

The test facility must establish a target impact speed, which, with all equipment and instrumentation accuracies considered, ensures that the actual speed is within the tolerance band. The target speed should be the maximum possible and still meet the required criteria. The target speed must be reported to the COTR prior to starting the testing program.

D.3.3 IMPACT SEVERITY (S213, S6.1.1)


The impact sled acceleration function envelopes shown in Figures 17 and 18 are defined by the coordinates in Tables 1 and 2.

TABLE 1 TEST CONFIGURATION I ACCELERATION FUNCTION ENVELOPE

UPP	UPPER LIMIT LOWER LIMIT		RLIMIT
TIME (msec)	ACCELERATION (G's)	TIME (msec)	ACCELERATION (G's)
0	3	4	0
10	25	13	19
52	25	46	19
90	0	75	0

TABLE 2 TEST CONFIGURATION II ACCELERATION FUNCTION ENVELOPE

TIME (msec)	UPPER LIMIT ACCEL.(G's)	LOWER LIMIT ACCEL.(G's)
0	0.0	-2.0
9.5	14.0	9.4
14	17.0	13.5
20	17.7	14.0
32	16.5	12.5
40	14.8	11.0
44	15.3	11.5
50	15.0	11.5
60	12.0	9.0
66	9.0	6.0
72	5.0	2.0
76	0.0	-2.0



CONFIGURATION I ACCELERATION FUNCTION CURVE ACCELERATION FUNCTION FOR $\Delta V = 48 \text{ km/h} (30 \text{ mph})$

FIGURE 17






FIGURE 18

D.4 DUMMY PREPARATION

D.4.1 DUMMY SELECTION (S213, S6.1.2.3, S7.2)

Determine whether to use the newborn, twelve-month-old dummy, three-yearold dummy, six-year-old dummy, or weighted six-year-old dummy based on the manufacturer's label information for occupant weight class.

A child restraint that is recommended for children having a specific mass range or height range shall use the tested child restraint according to the following table.

MASS	HEIGHT	DUMMY
≤ 5 kg	650 mm	Newborn Part 572 (K)
> 5 kg ≤ 10 kg	> 650 mm, <u><</u> 850 mm	Newborn Part 572 (K) Twelve-Month-Old Part 572 (R)
> 10 kg, <u><</u> 18 kg	> 850 mm <u><</u> 1100 mm	Twelve-Month-Old Part 572 (R)* Three-Year-Old Part 572 (P)
> 18 kg	> 1100 mm	Six-Year-Old Part 572(I)(Hybrid II) or Six-Year-Old Part 572(N)(Hybrid III)**
> 22.7 kg	> 1100 mm	Six-Year-Old Part 572 (S) weighted to 28.2 Kg

TABLE 3 DUMMY SELECTION BY MASS AND HEIGHT

*The twelve-month-old dummy is not tested in a booster seat.

**Child restraint manufacturer's option to use six-year-old HII for child restraints manufactured on or after August 1, 2005, and before August 1, 2008.

D.4.2 PRETEST CONDITIONING

NEWBORN INFANT DUMMY (S213, S9)

Prior to testing, condition the newborn infant dummy at any ambient temperature from 19°C to 25.5°C and at any relative humidity from 10 percent to 70 percent, for at least 4 hours.

TWELVE-MONTH-OLD DUMMY (S213, S9)

Calibrate the twelve-month-old dummy according to the requirements of 49 CFR Part 572, Subpart R as described in Appendix E of this procedure. Calibrations are performed prior to the start of the compliance test program, after an apparent noncompliance (as described by the COTR), after 30 tests, or

if the dummy has been in storage for thirty days or more during the testing program.

Prior to testing, condition the twelve-month-old dummy at any ambient temperature from 20.6°C to 22.2°C and at any relative humidity from 10 percent to 70 percent, for at least 4 hours.

THREE-YEAR-OLD DUMMY (S213, S9)

Calibrate the three-year-old dummy according to the requirements of 49 CFR Part 572, Subpart P as described in Appendix D of this procedure. Calibrations are performed prior to the start of the compliance test program, after an apparent noncompliance (as described by the COTR), after 30 tests, or if the dummy has been in storage for thirty days or more during the testing program.

Prior to testing, condition the three-year-old dummy at any ambient temperature from 20.6°C to 22.2°C and at any relative humidity from 10 percent to 70 percent, for at least 4 hours.

SIX-YEAR-OLD DUMMY (UNWEIGHTED AND WEIGHTED) (S213, S9)

Calibrate the six-year-old dummy according to the requirements of 49 CFR Part 572, Subpart I (Hybrid II) as described in Appendix B or 49 CFR Part 572, Subpart N (Hybrid III) as described in Appendix C of this procedure. Calibrate the six-year-old weighted dummy according to the requirements of 49 CFR Part 572, Subpart S as described in Appendix G of this procedure. Calibrations are performed prior to the start of the compliance test program, after an apparent noncompliance (as described by the COTR), after 30 tests, or if the dummy has been in storage for thirty days or more during the testing program.

Prior to testing, condition the six-year-old dummy (unweighted and weighted) at any ambient temperature from 20.6°C to 22.2°C and at any relative humidity from 10 percent to 70 percent, for at least 4 hours.

D.4.3 DUMMY INSTRUMENTATION

NEWBORN INFANT DUMMY

No instrumentation is installed in the newborn infant dummy.

TWEVLE-MONTH-OLD DUMMY

Three uniaxial accelerometers in the dummy's head and three uniaxial accelerometers in the dummy's thorax are used to instrument the twelve-monthold dummy per the requirements of 49 CFR Part 572, Subpart R.

THREE-YEAR-OLD DUMMY

Three uniaxial accelerometers in the dummy's head and three uniaxial accelerometers in the dummy's thorax are used to instrument the three-year-old dummy per the requirements of 49 CFR Part 572, Subpart P.

SIX-YEAR-OLD DUMMY (UNWEIGHTED)

Three uniaxial accelerometers in the dummy's head and three uniaxial accelerometers in the dummy's thorax are used to instrument the six-year-old dummy per the requirements of 49 CFR Part 572, Subpart I (Hybrid II) or 49 CFR Part 572, Subpart N (Hybrid III).

D.4.4 DUMMY CLOTHING (S213, S9)

NEWBORN INFANT DUMMY (S213, S9.1(a))

The newborn infant dummy is tested unclothed.

TWELVE-MONTH-OLD DUMMY (S213, S9.1(c))

The dummy is clothed in a cotton-polyester based tight fitting sweat shirt with long sleeves and ankle long pants whose combined weight is not more than 0.25 kg (0.55 lb).

THREE-YEAR-OLD AND SIX-YEAR-OLD DUMMY (WEIGHTED AND UNWEIGHTED) (S213, S9.1(e) and (f))

The three-year-old dummy is clothed in thermal knit waffle-weave polyester and cotton underwear, a size 4 long-sleeved shirt (three-year-old dummy) or a size 5 long-sleeved shirt (six-year-old dummy) having a mass of 0.090 kg (0.2 lb), a size 4 pair of long pants having a mass of 0.090 kg (0.2 lb) and cut off just far enough above the knee to allow the knee target to be visible, and size 8 canvas oxford style sneakers weighing not more than 0.26 kg (0.57 lb) each (three-year-old dummy) or size 13M canvas oxford style sneakers weighing not more than 0.43 kg (0.95 lb) each (six-year-old dummy). Machine-wash the clothing, other than the shoes, in 71°C (160°F) to 82°C (180°F) water, and machine-dry at 43°C (110°F) to 54°C (130°F) approximately 30 minutes. Shirt sleeve may be cut off at the elbows to improve the visibility of the dummy head during maximum excursion.

D.4.5 DUMMY TARGETING

TWELVE-MONTH-OLD DUMMY

Photographic targets are required to identify the head center of gravity of the twelve-month-old dummy, which is located on either side of the dummy head at the head accelerometer mounting block bolt. Adhesive backed paper or fabric targets with a pattern that facilitates identifying and tracking the head center of gravity in the high speed movies are recommended.

THREE-YEAR-OLD AND SIX-YEAR-OLD DUMMY (WEIGHTED AND UNWEIGHTED)

Photographic targets are required to identify the head center of gravity and the pivot points of the knees of the three-year-old and six-year-old dummy. Adhesive backed paper or fabric targets having a pattern that facilitates identifying and tracking of the head and knee reference points in the high speed movies are recommended. The head center of gravity is identified by the head center of gravity reference pin, which protrudes from each side of the head. Note that the head center of gravity target is not used for maximum forward excursion measurements. It may be used, however, along with a second target placed on the head to facilitate determination of maximum head/torso angle. The knee pivot-points are defined by the centers of the knee pivot bolts and are used for maximum forward excursion measurements.