THOR-LX / HYBRID III RETROFIT VERSION 3.2 **Drawing Package Specifications**

DRAWING FILE NAMING SYSTEM:

AABBCNNN

AA - The first set of letters are used as the name given to the project and will remain consistent through-out the entire package of drawing.

T1 = THOR 50th percentile male dummy.

- **BB** The second set of letters refers to the body area of the dummy. The two letter descriptor tags can be found in the chart labeled Two Letter Descriptor Tags For Body Areas.
- **C** A single letter noting the type of drawing.

M	Mechanical Drawing	S	Skins
E	Electrical Drawing	T	Assembly Tools
W	Welding Drawing	C	Connector Wire
P	Purchased Dummy Part	A	Drawing Arrangement
I	Instrument Wire	X	Drawing Index
F	Fabric Pattern	В	Bill of Materials

NNN - The last three digits is a numbering scheme for the different levels of drawings such as an assembly drawing, subassembly drawing, and part or detail drawing. In general, the examples given below applies to the majority of the drawings but due to the complexity of some of the parts in the dummy these may vary slightly.

000 100, 200, 900	Denotes an assembly drawing. Denotes a subassembly drawing.
010, 011, 099 110, 111, 199 210, 211, 299	Denotes a part drawing.
910, 911, 999	

09/20/01 T1TDA000 - 1 Revision - H

2 LETTER DESCRIPTOR TAGS FOR BODY AREAS

AREA 2 LETTER TAG

ANKLE	AK
CALIBRATION EQUIPMENT	CE
FOOT	FT
KNEE	KN
THOR-LX	LX
LOWER LEG	LL

REVISIONS:

The denotation of revisions to drawings are indicated within the title block located in the lower left-hand corner of a drawing. The latest revision number will be indicated in the designated area labeled revision . If there is no revision number or the abbreviation N/C (No Change) is shown, it means that no modification has been done to the drawing.

A description of modifications made to a drawing will be listed under the revisions section located in the top right hand corner of a drawing. The category under revisions labeled zone identifies the location of the major modification done to a drawing. The zone will be identified by a letter corresponding to one of the letters listed along the sides of the border of a drawing and a number corresponding to one of the numbers listed along the top or bottom of the border of a drawing. For example, a change made to a drawing at a zone of D3", the letter D would be read from the side of the border and the number 3" would be read from top/bottom of the border. The imaginary intersection that the letter/number combination makes is the location of the modification made to a drawing.

VENDOR ABBREVIATIONS:

For convenience, the names of vendors were abbreviated. The abbreviation of the vendor is followed by the part number.

BD BEARINGS AND DRIVES
35 WEST BROAD STREET
WEST HAZELTON, PA 18201
PHONE # (717) 459-0333, FAX # (717) 459-1977

CON CONTELEC (NOVOTECHNIK U.S. INC.)

237 CEDAR HILL STREET MARLBORO, MA 01752

PHONE # (508) 485-2244 ; FAX # (508)485-2430

DNA 10317 US HWY. 250 N.

MILAN, OH 44846-9570

PHONE # (419) 625-5200; FAX # (419) 625-5335

DN DENTON

2967 WATERVIEW DRIVE ROCHESTER HILLS, MI 48309

PHONE # (248) 852-5100; FAX # (248) 852-6060

END ENDEVCO

30700 RANCHO VIEJO ROAD

SAN JUAN CAPISTRANO, CALIFORNIA 92675 PHONE # (949) 493-8181; FAX # (949) 661-7231

EN ENTRAN

10 WASHINGTON AVE. FAIRFIELD, NJ 07004-3877

PHONE # (201) 227-1002 ; FAX # (201)227-6865

FX FOAMEX

1641 BORDER AVE.

TORRANCE, CA 905901-2810 PHONE # (310) 328-1332

GN GEON, INC. (FORMERLY BF GOODRICH)

6100-T OAKTREE BLVD. INDEPENDENCE, OHIO 44131

PHONE # (216) 447-6000

MCM MCMASTER CARR

473 RIDGE ROAD

DAYTON, NEW JERSEY 08810-0317

PHONE # (908)329-3200; FAX # (908) 329-3772

MWE MID-WEST EXPRESS

8 GREENWOOD AVE.

ROMEOVILLE, IL 60441-1399

PHONE # (815) 886-7812; FAX # (815) 886-1510

PB PACIFIC BEARING

P.O. BOX 6980

ROCKFORD, IL 61125-6980

PHONE # (800) 962-8979; FAX # (815) 962-3818

SAV SAVA INDUSTRIES, INC.

4 NORTH CORPORATE DRV.

P.O. BOX 30

RIVERDALE, NJ 07457-0030

PHONE # (201) 835-0882, FAX # (210) 835-0877

SI STERLING INSTRUMENTS

2101 JERICHO TURNPIKE

BOX 5416

NEW HYDEPARK, NY 11042-5416

PHONE # (516) 328-3300 ; FAX # (516)326-8827

TT TRANSDUCER TECHNIQUES

43178 BUSINESS PARK DR. TEMECULA, CA 92590

PHONE # (909) 676-3965; FAX # (909) 676-1200

YKK YKK U.S.A., INC.

SOUTHEAST MANUFACTURING B

1306 COBB INDUSTRIAL DRV.

P.O. BOX 6729

MARIETTA, GA 30062

SCREW ABBREVIATIONS:

F.H.S.C.S. FLAT HEAD SOCKET CAP SCREW

B.H.S.C.S. BUTTON HEAD SOCKET CAP SCREW

S.H.C.S. SOCKET HEAD CAP SCREW

S.S.S SOCKET SET SCREW

MATERIAL ABBREVIATIONS:

CRS COLD ROLLED STEEL SS STAINLESS STEEL

AL ALUMINUM

BILL OF MATERIALS - PART TYPE ABBREVIATIONS:

<u> </u>	THE PROPERTY OF THE PROPERTY O
A	ASSEMBLY
C	CUT FOAM OR PLASTIC
Q	CAST METAL PART
F	FABRIC OR SEWN PATTERN
I	PURCHASED INSTRUMENT
M	MACHINED PART
O	MOLDED PART
P	PURCHASED
S	SKIN
W	WELDED ASSEMBLY

ADDITIONAL ABBREVIATIONS:

N/C NO CHANGE B.C. Bolt Circle

COATING SPECIFICATIONS:

- " CLEAR ANNODIZE A CLEAR ANNODIZED COATING WITH THICKNESS UP TO 0.0005"
- " BLACK ANNODIZE A BLACK ANNODIZED COATING WITH THICKNESS UP TO 0.0005"
- " TEFLON COATING ACHESON GP 1904 SPRAY APPLICATION OF PTFE AND GRAPHITE IN A THERMOPLASTIC BINDER. THICKNESS RANGE UP TO 0.001"

BORDER SIZES:

The border sizes are as follows:

Border A = 10.5" x 8" Border B = 16.5" x 10.5"

Border C = 21.5" x 16.5"

Border D = 33.5" x 21.5"

Border E = 43.5" x 33.5"