

Electronically Controlled Braking Systems Field Operational Test (ECBS FOT)

May 12, 2004

Jonathan Mueller

National Highway Traffic Safety Administration Office of Applied Vehicle Safety Research Driver-Vehicle Interaction & Heavy Truck Research Division



Agenda



- FOT Introduction
- Test Approach & Templates
- The Technologies
- Vehicle Fleet
- Data Collection & Project Schedule



Introduction DOT Initiatives




- Accelerate deployment of new safety technologies to reduce accidents & fatalities
- Demonstrate benefits, measure reliability and advance state of the art of heavy truck ECBS & ABS technology
 - Laboratory and track testing (SAE/RAI)
 - Field testing in real-life commercial operations
- August 2002: RFA for ECBS Field Operational Tests
 - Template 1: Severe Duty Truck
 - Template 2: "Mixed" Tractor-Trailer
 - Template 3: "Optimized" Tractor-Trailer

 May 1, 2003: Award made to the Freightliner Team for a combination of Templates 2 and 3



FOT Team Structure





Goals and Objectives



Overall Goal

Evaluate the safety, performance, reliability, maintainability and durability of ECBS, ABS and enabled safety technologies

Template 2 Objective: "Mixed" Tractor-Trailers Evaluate the compatibility and performance of unmatched combinations of tractors and trailers equipped with ABS or ECBS from multiple suppliers

Template 3 Objective: "Matched" Tractor-Trailers Evaluate ECBS and ECBS-enabled safety technologies on matched tractor-trailers with brake control systems from the same suppliers

Agenda



- FOT Introduction
- Test Approach & Templates
- The Technologies
- Vehicle Fleet
- Data Collection & Project Schedule



Test Approach



- Install ECBS and ABS with enabled safety technologies on Freightliner tractors and Great Dane trailers purchased by WAL*MART
- Operate vehicles in WAL*MART real-life commercial operations for 12 months
 - Collect vehicle onboard system data, maintenance data, fleet operator and driver experience, and safety-related data
- Provide information to DOT and the Independent Evaluator for analysis and evaluation throughout the FOT



Template 2: Quantity of Tractor & Trailers



"Mixed" Tractor-Trailer

Group	Tractors		Trailers	
Group				
T2-	10	Meritor Wabco ABS	— 15	Meritor Wabco ABS
Config.1		w/ Arvin Meritor drum		w/ Arvin Meritor drum
<i>T2-</i>	10	Meritor Wabco ABS	15	Meritor Wabco ABS
Config.2		w/ Bendix Knorr disc		w/ Bendix Knorr disc
<i>T2-</i>	10	Meritor Wabco ECBS	15	Meritor Wabco ECBS
Config.3		w/ Bendix Knorr disc		w/ Bendix Knorr disc
<i>T2-</i>	10	Bendix ABS6	→ 15	Bendix EBS
Config.4		w/ Bendix Knorr disc		w/ Bendix Knorr disc
	Total 40		Total 60	
F				

Template 2 Experimental Plan



- Phase 1:
 - 6 Months Duration
 - Enabled Technologies "OFF"
 - Data recorded, but does not affect operations
- Phase 2:
 - 6 Months Duration
 - Enabled Technologies "ON"
 - Data recorded and fully functional interactive systems



Template 3 Number of Tractor & Trailers



"Optimized" Tractor-Trailer

Croup	Tractors	Trailers	
Group	8 Meritor Wabco ECBS	40 Meritor Wabco ECBS	
ТЗ	w/ Bendix Knorr disc	w/ Bendix Knorr disc	
	Total 8	Total 40	



Template 3 Experimental Plan



- Phase 0:
 - Profile drivers in ABS tractors prior to operation of ECBS tractors
- Phase 1:
 - 6 Months Duration
 - ECBS with Enabled Technologies "OFF"
 - Data recorded, but does not affect operations
- Phase 2:
 - 6 Months Duration
 - ECBS with Enabled Technologies "ON"
 - Data recorded and fully functional interactive systems



Agenda



- FOT Introduction
- Test Approach & Templates
- The Technologies
- Vehicle Fleet
- Data Collection & Project Schedule




Meritor WABCO Technologies



- Electronically Controlled Braking System (ECBS)
 - Pneumatic control lines and logic replaced with electronics
 - Platform for future advanced technologies
 - Full pneumatic redundancy in the event of a major electrical malfunction
- Electronic Stability Control (ESC)
 - Attempts to correct instabilities caused by roll and yaw inducing maneuvers
 - Assists driver to follow intended course
- Adaptive Cruise Control (ACC)
 - Extension of Cruise Control
 - Automatic control of engine, engine brake & foundation brakes to maintain a safe following distance
 - Collision warning capability









Meritor WABCO Technologies



Tractor:

- Baseline ABS Systems
- ABS with Brake Performance Monitoring
 - Detects degraded brake performance
- ABS with Roll Stability Control
 - Attempts to correct instabilities caused by roll inducing maneuvers



Meritor WABCO Technologies



Trailer:

- Standard ABS
- Electronically Controlled Braking System (ECBS)
 - Pneumatic control lines and logic replaced with electronics
 - Electronically controlled by ECBS tractor or pneumatically controlled by ABS tractor
 - Platform for future advanced technologies
 - Full pneumatic redundancy in the event of a major electrical failure
- Roll Stability Support (RSS)
 - Attempts to correct instabilities caused by roll inducing maneuvers



Bendix Technologies



Tractor:

- Premium ABS6 Features
 - Anti-lock braking
 - Automatic traction control
 - Brake system monitoring and diagnostics
- Air Disc Brakes
 - Increased braking torque
 - Resistance to brake fade
 - Reduced hysteresis & improved side-to-side brake balance
 - Improved brake diagnostics
 - Lining wear sensing
 - Reduced maintenance downtime & parts count



Bendix Technologies



Trailer:

- ECBS (TEBS4) Features
 - Closed-loop service brake pressure control
 - Lining wear monitoring for air disc brakes
 - Brake system monitoring and diagnostics
- ECBS Enabled Technologies
 - Trailer roll stability program (TRSP)
- Air Disc Brakes
 - Increased braking torque
 - Resistance to brake fade
 - Reduced hysteresis & improved side-to-side brake balance
 - Improved brake diagnostics
 - Lining wear sensing
 - Reduced maintenance downtime & parts count



Agenda



- FOT Introduction
- Test Approach & Templates
- The Technologies
- Vehicle Fleet
- Data Collection & Project Schedule



WAL*MART Freightliner Columbia Tractors







WAL*MART Fleet Operations




- Distribution of perishables and dry goods
- 24 / 7 Operations
- Hub-and-Spoke operations
 - Deliveries from hubs to distribution centers (DC), and from DC to WAL*MART stores, SuperCenters or Sam's club stores
- National operations
 - 38 Distribution Centers (Terminals)
 - > 4,700 stores, SuperCenters and Sam's club stores



Distribution Center - Loveland, CO







WAL*MART

People Saving People www.nhtsa.dot.gov

Loveland Fleet Statistics

- Operations
 - Approx. 217 Tractors & 1000 Trailers
 - Freightliner 58" Columbia RR Sleeper Cab
 - Single Trailers
 - Average of 125,000 miles / year / tractor
 - Average trip: ~ 250 miles (one way), one or more deliveries
 - Variety of routes and weather (highways, urban and/or country roads, mountains, plains)
- Drivers
 - Assigned to their own tractor
 - ~ 14 years experience with WAL*MART
 - < 1% driver turn-over rate</p>



Agenda



- FOT Introduction
- Test Approach & Technologies
- Vehicle Fleet
- The Templates
- Data Collection & Project Schedule



Data Sources




- Onboard Driving & Equipment Data
- Fleet Operations and Maintenance Data
- Surveys and Interviews
- Safety Benefits Data
- Relevant Fleet Historical Information



Data Transfer On-Board Vehicle Data








Program Schedule & Work Plan Highlights







Thank you!

Jonathan Mueller *NHTSA* (202)366-0098 jmueller@nhtsa.dot.gov

