

Urine Albumin-to-Creatinine Ratio (UACR)

In Evaluating Patients with Diabetes for Kidney Disease

The two key markers for chronic kidney disease (CKD) are urine albumin and estimated glomerular filtration rate (eGFR).

Assess urine albumin excretion yearly to diagnose *and* monitor kidney damage in patients with type 1 diabetes for five years or more or with type 2 diabetes.


- More frequent monitoring may be indicated in patients with changing clinical status or after therapeutic interventions.
- Use a spot urine albumin-to-creatinine ratio (UACR). UACR estimates 24-hour urine albumin excretion. Twenty-four-hour collection and timed specimens are not necessary.


$$\frac{\text{Urine albumin (mg/dL)}}{\text{Urine creatinine (g/dL)}} = \frac{\text{UACR in mg/g}}{\text{UACR in mg/g}} \approx \frac{\text{Albumin excretion in mg/day}}{\text{Uniform of the properties of the propert$$


UACR is a ratio between two measured substances. Unlike a dipstick test for albumin, UACR is unaffected by variation in urine concentration.

Albuminuria¹ is present when UACR is greater than 30 mg/g and is a marker for CKD.

Albuminuria is used to diagnose and monitor kidney disease. Change in albuminuria may reflect response to therapy and risk for progression. A decrease in urine albumin may be associated with improved renal and cardiovascular outcomes.







A randomized trial of diabetes patients with CKD found that the greater the reduction of UACR in response to treatment (with ARBs), the lower the risk of progression to kidney failure. (De Zeeuw D, et al. *Kidney International*, 2004:65:2309-2320)

¹Albuminuria is a term that describes all levels of urine albumin. *Microalbuminuria* is a term used to describe urine albumin levels not detected by a dipstick test, i.e., 30 mg/g—300 mg/g. *Macroalbuminuria* is sometimes used to describe albumin levels more than 300mg/g.



Estimated Glomerular Filtration Rate (eGFR)

In Evaluating Patients with Diabetes for Kidney Disease

The two key markers for chronic kidney disease (CKD) are estimated glomerular filtration rate (eGFR) and urine albumin.

Calculate eGFR from stable serum creatinine levels at least once a year in all patients with diabetes.

- eGFR is more accurate than serum creatinine alone. Serum creatinine is affected by muscle mass, and related factors of age, sex, and race.
- eGFR is not reliable for patients with rapidly changing creatinine levels, extremes in muscle mass and body size, or altered diet patterns.

See if your lab reports eGFR routinely. If it does not, ask your lab to do so. You can also calculate an eGFR yourself by using GFR calculators available on NKDEP's website at www.nkdep.nih.gov/professionals/gfr_calculators.

NKDEP recommends reporting values greater than or equal to 60 as ">60," rather than numeric values. Exact values above 60 are not reliable. CKD may be present if UACR > 30mg/g CKD may be present if UACR > 30mg/g CKD (eGFR < 60 ml/min/1.73 m²) Kidney Failure

If CKD is detected, it should be addressed as part of a comprehensive approach to the treatment of diabetes.

For more information on UACR, eGFR, and kidney disease, go to www.nkdep.nih.gov.

The National Kidney Disease Education Program (NKDEP) of the National Institutes of Health aims to improve early detection of kidney disease, help identify patients at risk for progression to kidney failure, and promote interventions to slow progression of kidney disease.

